



# Iowa Department of Transportation

## LOCAL LETTING INFORMATION

-----  
Franklin County -- LFM-11-222(20)--RI-35 AND LFM-12-291(23)--RI-35

Proposal Guarantee \$ 12,500.00

Courthouse, Hampton, IA, May 12, 2011, 2:00 PM

Bridge Abutment Repair, Install new H-piling at abutment locations to supplement existing decayed wood timber piling.

Contact # 641-456-4671 FAX # 641-456-3219

20.000	EACH	BEARING PAD ASSEMBLY
140.000	SY	ENGINEER FABRIC
800.000	LF	PILE, STEEL, HP 12X63
298.000	LB	REINFORCE STEEL
70.000	TON	REVTMENT, CLASS E
8.000	EACH	SAFETY CLOSURE
0.900	CY	STRUCT CONC (BRIDGE)
10838.000	LB	STRUCTURAL STEEL

-----  
Lucas County Secondary Road Department County -- FM-C059(50)--55-59

Proposal Guarantee \$ 5000

May 12, 2011 Chariton - Lucas County Supervisor's Office, IA 10:00 am CDST

Bid Turn-in Location: Lucas County Auditor's Office

Farm-To-Market Granular Surfacing

Sites: 119.8 miles of various FM Roads

Contact # 641-774-4013 FAX # 641-774 2993

30,150.00 ton Granular Surfacing - On Road

-----  
Delaware County Secondary Road Department County -- L-C-12(01)--73-28

Proposal Guarantee \$ 6,250.00

May 16, 2011 Manchester, Iowa - Delaware County Supervisors Office, IA 1:15 P.M.

Bid Turn-in Location: Delaware County Auditors Office

R.C.B. Culvert Replacement-Single Box

Contact # 563-927-3505 FAX # 563-927-3102

120	ton	Granular Surfacing, On Road, class a Stone
756	cy	Excavation, Class 23
81.8	cy	Structural Concrete (RCB Culvert)
13,860	lb	Steel Reinforcing
170	sy	Engineering Fabric
170	ton	Revetment, Class E Rip-Rap

-----  
Delaware County Secondary Road Department County -- LOST-12(01)--73-28

Proposal Guarantee \$ 37,500.00

May 16, 2011 Manchester, Iowa - Delaware County Supervisors Office, IA 1:15 P.M.

Bid Turn-in Location: Delaware County Auditors Office

H.M.A. resurfacing with Cold in Place Recycling

Contact # 563-927-3505 FAX # 563-927-3102

2564	ton	Granular Shoulders, Type B
2633	ton	HMA (300,000 ESAL) Base course
2633	ton	HMA (300,000 ESAL) I-S course
327	ton	Asphalt Binder (PG58-28)
500	ton	Surfacing, Driveway Class A Stone
27500	sy	Cold In Place Recycled Asphalt Pavi
112	ton	Asphalt Stabilizing Agent (Foamed
600	sy	Removal of Pavement
318.48	sta.	Painted Pvmt Markings Water/Solv.



# Iowa Department of Transportation

## LOCAL LETTING INFORMATION

Dallas County -- M-74

Proposal Guarantee \$ 10,000.00

County Engineer's Office, Adel , IA, May 19, 2011, 1:00 PM

Slide Repair, Build a 500' tiled key trench of

Contact # 515-993-4289 FAX # 515-993-3965

0.460	ACRE	CLEAR+GRUBB
3930.000	CY	EXCAVATION, CL 10, RDWY+BORROW
815.000	CY	EXCAVATION, CL 12, RDWY+BORROW
1.000	LS	MOBILIZATION
400.000	TON	POROUS BACKFILL
6500.000	TON	REVTMENT, SPECIAL
2.000	EACH	SAFETY CLOSURE
2.000	EACH	SUBDRAIN OUTLET (RF-19F)
150.000	LF	SUBDRAIN, PVC, STD, NON-PERFORATED, 6"
500.000	LF	SUBDRAIN, PVC, STD, PERFORATED, 6"
1.000	LS	TRAFFIC CONTROL

Franklin County Secondary Road Department County -- L-20-195(7)--RI-35

Proposal Guarantee \$ 37,500

May 19, 2011 - Hampton - Courthouse, IA - 2:00 P.M.

Bid Turn-in Location: Auditor's Office

Pavement removal and replacement

Contact # 641-456-4671 FAX # 641-456-3219

3500	cy	Excavation - Class 10
7185	sy	PCC Pavement
120	sta	Shoulder - Construction
	sta	Shoulder - Finish
7280	SY	Pavement removal and crushing

Union County -- LFM-611--7X-88

Proposal Guarantee \$ 25,000.00

County boardroom, Creston , IA, May 23, 2011, 11:00 AM

320-Bridges, Bridge replacement on Redwood Avenue over Squaw Creek.

Contact # 641-782-7417 FAX # 641-782-6492

204.000	LF	CONC ENCASE STEEL H PILE, HP 10X42(P10L)
162.000	LF	CONC OPEN RAIL, TL-4
1.000	LS	CONSTRUCTION SURVEY
1050.000	SY	ENGINEER FABRIC
450.000	CY	EXCAVATION, CL 10, CHANNEL
1295.000	CY	EXCAVATION, CL 10, RDWY+BORROW
70.000	CY	EXCAVATION, CL 20
144.000	TON	GRANULAR SURF ON RD, CL A CR STONE
1.200	ACRE	MULCH
1380.000	LF	PILE, STEEL, HP 10X42
33898.000	LB	REINFORCE STEEL
680.000	TON	REVTMENT, CLASS E
1.000	LS	RMVL OF EXISTING BRIDGE
1.200	ACRE	SEED+FERTILIZE (RURAL)
4.000	EACH	STEEL BEAM G'RAIL BARRIER TRANS SECTION
4.000	EACH	STEEL BEAM G'RAIL END ANCHOR, BOLTED
4.000	EACH	STEEL BEAM G'RAIL END TERMINAL
125.900	CY	STRUCT CONC (BRIDGE)



# Iowa Department of Transportation

## LOCAL LETTING INFORMATION

Winnebago County -- LFM-(A14)--7X-95

Proposal Guarantee \$ 25,000.00

Courthouse, Forest City , IA, May 24, 2011, 11:00 AM

366-HMA Paving, HMA Resurfacing

Contact # 641-585-2905 FAX # 641-585-2891

414.000	TON	ASPH BINDER, PG 58-28
2.058	MILE	CLEAN+PREPARATION OF BASE
1.000	LS	CONSTRUCTION SURVEY
25.000	EACH	FLAGGER
3100.000	TON	GRANULAR SHLD, TYPE B
341.000	STA	GROOVE CUT - PAV'T MARK
2100.000	TON	HMA (3M ESAL) BASE, 1/2"
2400.000	TON	HMA (3M ESAL) INTERMEDIATE, 1/2"
2400.000	TON	HMA (3M ESAL) SURF, 1/2", NO FRIC
1.000	LS	HMA PAV'T SAMPLE
1.000	LS	MOBILIZATION
341.000	STA	PAINTED PAV'T MARK, WATERBORNE/SOLVENT
4.000	EACH	RUMBLE STRIP PANEL (HMA SURF)
1.000	LS	TRAFFIC CONTROL

Winnebago County -- LFM-(R50)--7X-95

Proposal Guarantee \$ 100,000.00

Courthouse, Forest City , IA, May 24, 2011, 11:00 AM

366-HMA Paving, 4

Contact # 641-585-2905 FAX # 641-585-2891

1260.000	TON	ASPH BINDER, PG 58-28
79900.000	GAL	ASPH STABILIZING AGENT(STD ASPH EMULSION
6.374	MILE	CLEAN+PREPARATION OF BASE
82410.000	SY	COLD IN-PLACE RECYCLED ASPH PAV'T
1.000	LS	CONSTRUCTION SURVEY
45.000	EACH	FLAGGER
9600.000	TON	GRANULAR SHLD, TYPE B
1093.000	STA	GROOVE CUT - PAV'T MARK
6400.000	TON	HMA (3M ESAL) BASE, 1/2"
7300.000	TON	HMA (3M ESAL) INTERMEDIATE, 1/2"
7300.000	TON	HMA (3M ESAL) SURF, 1/2", NO FRIC
1.000	LS	HMA PAV'T SAMPLE
1.000	LS	MOBILIZATION
465.000	CY	MODIFIED SUBBASE
1474.000	STA	PAINTED PAV'T MARK, WATERBORNE/SOLVENT
978.000	SY	PAV'T, SCARIFICATION
1955.000	SY	RMVL OF PAV'T
8.000	EACH	RUMBLE STRIP PANEL (HMA SURF)
1.000	LS	SIGNING
1955.000	SY	STD/S-F PCC PAV'T, CL C CL 3, 8"
1.000	LS	TRAFFIC CONTROL



# Iowa Department of Transportation

## LOCAL LETTING INFORMATION

-----

Winnebago County -- LFM-(R34)--7X-95  
 Proposal Guarantee \$ 12,500.00  
 Courthouse, Forest City , IA, May 24, 2011, 11:00 AM  
 359-Miscellaneous, Asphalt Microsurfacing  
 Contact # 641-585-2905 FAX # 641-585-2891

923.520	TON	AGG - MICROSURFACING
27705.000	GAL	EMULSIFIED ASPH - MICROSURFACING
12.000	EACH	FLAGGER
1.000	LS	MOBILIZATION
1012.000	STA	PAINTED PAV'T MARK, WATERBORNE/SOLVENT
7.124	MILE	PREPARATION OF SURF - MICROSURFACING
6.000	EACH	RUMBLE STRIP PANEL (HMA SURF)
1.000	LS	TRAFFIC CONTROL

-----

Mills County Secondary Road Department County -- L-B244615--73-65  
 Proposal Guarantee \$ 5000.00  
 May 24, 2011 Glenwood, Iowa - Board of Supervisors Mills County Court House 418 Sharp Street Glen, Iowa 51534, IA 9:00 AM  
 Bid Turn-in Location: Mills County Engineers Office 403 Railroad Ave. Glenwood, Iowa 51534  
 10.0'x 8.0' Twin RCB Culvert, 15° Skew  
 Contact # 712-527-4873 FAX # 712-527-5124

1	ls	Clearing And Grubbing
197.0	cy	Excavation, Class 10 Roadway and Borrow
80.0	cy	Excavation, Class 10, Channel
150.0	ton	Granular surfacing on road, Class D Roadstone
1.0	ls	Removal of Existing Bridge
43.5	cy	Granular Backfill
800.0	cy	Excavation - Class 20
182.4	cy	Structural Concrete (RCB Culvert)
25,564.0	lb	Reinforcing Steel
1.0	ea	Apron, Conc. 36
30.0	lf	Culv. Conc. Entrance Pipe, 36
356.7	sy	Engineering Fabric
118.8	ton	Revetment, Class E
2.0	ea	Safety Closure
1.0	ls	Construction Survey
1.0	ls	Traffic Control
1.0	ls	Mobilization
1.0	ls	Removal and Reinstall Fence
1.0	ls	Temporary fence
1.0	ls	Temporary Stream Crossing
0.9	Acres	Mulch
0.9	Acres	Seeding and Fertilizing (Rural)



# Iowa Department of Transportation

## LOCAL LETTING INFORMATION

Mills County Secondary Road Department County -- L-221S--73-65

Proposal Guarantee \$ 5000.00

May 24, 2011 Glenwood, Iowa - Board of Supervisors, Mills County Court House 418 Sharp Street Glenwood, Iowa 51534, IA 9:30 AM

Bid Turn-in Location: Mills County Engineers Office 403 Railroad Ave. Glenwood, Iowa

Culvert Replacement - RCB

Contact # 712-527-4873 FAX # 712-527-5124

0.3	acre	Clearing And Grubbing
1,576.2	cy	Excavation, Class 10 Channel
1.0	ls	Removal of Existing Structures
313.3	ton	Granular Backfill
115.1	cy	Structural Concrete (RCB)
19,345.0	lb	Reinforcing Steel
1.0	ea	Aprons, Concrete, 24
41.5	lf	Culvert, Concrete entrance Pipe, 24
1.0	ea	Aprons, Metal 24
60.0	lf	Culvert, Corrugated Metal Entrance pipe, 24
94.4	cy	Flowable Mortar
266.7	sy	Engineering Fabric
109.0	lf	Removal and reinstall of fence, Barbed Wire
1.0	ls	Construction Survey
1.0	ls	Traffic Control
2.0	ea	Flaggers
1.0	ls	Mobilization
0.3	Acre	Mulching
0.3	Acre	Seeding and Fertilizing (Rural)

Cherokee County Secondary Road Department County -- L-58-B-11

Proposal Guarantee \$ 1500.00

May 31, 2011 Cherokee - Cherokee County Board of Supervisor's Room, IA 0930 A.M.

Bid Turn-in Location: Cherokee County Auditor's office, 520 W. Main, Cherokee, IA

Replace bridge on J Ave. approximately 1/2 mile north of C-44. Replacement Bridge will be an Oden bridge.

Sites: Between 560 & 570'th streets on J Ave.

Contact # 712-225-6712 FAX # 712-225-6715

713	CY	EMBANKMENT-IN-PLACE
1	LS	REMOVAL OF EXISTING BRIDGE
320	CY	EXCAVATION, CLASS 20
136	SY	ENGINEERING FABRIC
120	TON	REVTMENT, CLASS E
2	EACH	SAFETY CLOSURE
1	LS	TRAFFIC CONTROL
1	LS	MOBILIZATION
44.7	TON	GRANULAR SURFACE ON RD. CL A STONE
72.5	CY	GRANULAR SUBBASE
72.5	CY	GRANULAR SUBBASE, PLACE ONLY
1.76	CY	STRUCTURE CONCRETE (BRIDGE-PAVING BLOCKS)
1	LS	FURNISH ODEN ENTERPRISES BRIDGE
1	LS	INSTALL ODEN ENTERPRISES BRIDGE



# Iowa Department of Transportation

## LOCAL LETTING INFORMATION

---

Wright County -- L-B061856--73-99

Proposal Guarantee \$ 12,500.00

Courthouse, Clarion , IA, June 02, 2011, 10:00 AM

320-Bridges, Bridge Replacement

Contact # 515-532-3597 FAX # 515-532-6063

1.000 LS Furnish 34' x 28' 6" Oden Bridge As Per Plan

1.000 LS Install 34' x 28' 6" Oden Bridge As Per Plan



# Iowa Department of Transportation

## BULLETIN REPORTING FORM

County: Winnebago Project No.: L-(E8WB)  
 Proposal Guarantee: \$12,500 DBE or TSB Goal: \_\_\_\_\_ %  
 Date of Letting: May 24, 2011 Time of Letting: 11:15 A.M.  
 Bid Turn-In Location: County Engineer Type of Project: 332- Box Culvert  
 Contact Phone #: 6415852905 Contact Fax #: 6415852891

Specific Description of Project: Replace existing timber bridge with a twin 10'x10'x58' cast in place box culvert with end sections and flared wingwalls.

QUANTITY	UNIT	DESCRIPTION
1800	CY	EXCAVATION, CL. 10, RDWY & BRW
1	LS	QUALITY MANAGEMENT-CONCRETE
150	TON	GRAN. SURF. ON ROAD, CL. A.
1	LS	REMOVAL OF EXISTING BRIDGE
200	TON	GRANULAR BACKFILL
400	CY	EXCAVATION, CL. 20
255	CY	STRUC. CONC. (RCB CULVERT)
35100	LB	REINFORCING STEEL
150	TON	REVTMENT, CL. E
2	EACH	SAFETY CLOSURE
1	LS	CONSTRUCTION SURVEY
1	LS	TRAFFIC CONTROL
1	LS	MOBILIZATION
2	EACH	TILE RELOCATION
0.8	ACRE	MULCHING
0.8	ACRE	FERTILIZE & SEED (RURAL)
80	LF	SILT FENCE

Date: 4/29/2011 Local Agency Official: Jim Witt

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts at DOT.Contracts@DOT.iowa.gov