## Illinois State Water Survey Division

ΑT


WATER QUALITY SECTION PEORIA, ILLINOIS



SWS Contract Report 466

THE EFFECTS OF HYDROPOWER DEVELOPMENT AT THE BRANDON ROAD DAM ON DOWNSTREAM DISSOLVED OXYGEN RESOURCES


> by Thomas A. Butts, Harvey R. Adkins, and Donald H. Schnepper



CROSS SECTION OF TAINTER GATE

Prepared for the Village of Rockdale in cooperation with Beling Consultants, Joliet, Illinois

August 1989



## THE EFFECTS OF

#### HYDROPOWER DEVELOPMENT AT THE BRANDON ROAD DAM

## ON DOWNSTREAM DISSOLVED OXYGEN RESOURCES

by Thomas A. Butts, Harvey R. Adkins, and Donald H. Schnepper

Illinois Department of Energy and Natural Resources
State Water Survey Division
Water Quality Section
P.O. Box 697
Peoria, Illinois 61652

Prepared for the Village of Rockdale in cooperation with Beling Consultants, Joliet, Illinois

August 1989

## CONTENTS

P	age
Introduction	1
Cause of the problem	2
General effects of dams	
Purpose of study	
Illinois Waterway background information	
Acknowledgments	5
Dam aeration theory.	5
Methods and procedures.	9
Field studies.	
SWS BOD-DO model.	
Biochemical oxygen demand (BOD)	
Sediment oxygen demand (SOD).	
Natural stream aeration and tributary inputs	
Dissolved oxygen saturation	
Dam aeration	
Hydraulic and hydrologic model	
Water temperature considerations	
<del>-</del>	
Parameters and parametric coefficient modeling	
Modeling procedure	
Stepwise regression analyses	Τ./
Results	17
Dam calibration	
Weir box data and results	
River-run data and results	
Model support data	
Hydraulic and hydrologic information	
Water quality information	
BOD-DO model products	
Stepwise regression analyses	.21
Discussion	.22
Conclusions.	.26
Tables	.29
Figures.	47
References.	.55
Appendices	
Appendix A. Flow duration curves for main stem gaging stations and tributaries	.59
Appendix B. Main stem flows for various flow duration percents .	69
Appendix C. Tributary flows for various flow duration percents .	71
Appendix D. Estimated pool elevations for various flow duration percents	.73
Appendix E. Time of travel from Lockport dam to point source	./ 3
waste load inputs for various flow duration percents	77

Appendix F.	Ultimate carbonaceous and nitrogenous inputs at
	Lockport on the main stem and eight tributaries 83
Appendix G.	Tributary DO concentrations used in conjunction
	with the various flow duration percents. 87
Appendix H.	Carbonaceous and nitrogenous BOD usage rates used
	with various flow duration percents. 89
Appendix I.	Examples of BOD-DO model runs for 99.8 percent
	flow duration at 12°C and 28°C and for 8 percent
	flow duration at 12°C and 28°C 93
Appendix J.	The BOD-DO model program written in BASIC
Appendix K.	Data used to develop stepwise regression
	relationships 105

# THE EFFECTS OF HYDROPOWER DEVELOPMENT AT THE BRANDON ROAD DAM ON DOWNSTREAM DISSOLVED OXYGEN RESOURCES

by Thomas A. Butts, Harvey R. Adkins, and Donald H. Schnepper

#### INTRODUCTION

The Illinois Pollution Control Board (IPCB) dissolved oxygen (DO) standards, as administered by the Illinois Environmental Protection Agency (IEPA), are not being consistently met along several major reaches of the Illinois Waterway. Undesirably low DO levels still occur routinely, particularly during low summer flows, in spite of the fact that hundreds of millions of dollars have been expended over the last 20 years to reduce point source waste loads.

Secondary contact and indigenous aquatic life standards are applicable to the Des Plaines River down to the I-55 highway bridge, which is 8.25 miles below the Brandon Road dam. Section 302.405 of Subpart B of the IPCB Rules and Regulations (1986) states:

Dissolved oxygen (STORET number 00300) shall not be less than 3.0 mg/l during at least 16 hours in any 24-hour period, nor less than 2.0 mg/l at any time, and after December 31, 1977 shall not be less than 4.0 mg/l at any time.

General use water quality standards are applicable to the Illinois Waterway below the I-55 bridge. Section 302.206 of Subpart B of the IPCB Rules and Regulations (1986) states:

Dissolved oxygen (STORET number 00300) shall not be less than  $6.0 \, \text{mg/l}$  during at least 16 hours of any 24 hour period, nor less than  $5.0 \, \text{mg/l}$  at any time.

Dissolved oxygen surveys conducted in the Peoria pool by the Water Quality Section (WQS) of the State Water Survey (SWS) during the summers of 1982, 1983, and 1986 show that DO concentrations often drop below 5.0 mg/l even during relatively high summer flows. In the LaGrange pool below Peoria, concentrations as low as 3.5 mg/l were observed during 1983 summer low flow conditions. Computer biochemical oxygen demand (BOD) - DO model simulations have clearly demonstrated that significant improvements in DO levels cannot be achieved by requiring additional organic waste load (BOD) reductions at the point sources. Most treatment plants along the waterway are presently achieving 90 to 95 percent BOD reductions. In addition, since 1971 ammonia input to the waterway (another cause of oxygen depletion) has been reduced over 50 percent. Additional treatment would not produce a commensurate improvement in DO levels. The only plant along the waterway amenable to a large-scale upgrading is the Metropolitan Sanitary District of Greater Chicago Calumet plant. Butts et al. (1983) have shown that upgrading the effluent of this plant to 7 mg/l BOD and 2 mg/l ammonia would improve the DO level in the critical reach of the Peoria pool by only 0.6 mg/l during low flow conditions.

#### Cause of the Problem

The reason the improvement in DO has not been commensurate with the reduction of waste inputs is that the waste assimilative capacity of the waterway has been drastically reduced due to the physical alterations of the natural stream channel over the last 50 years. Dam construction, dredging, and channelization have slowed flows and increased water depths, thereby reducing the natural reaeration capacity, i.e., the ability of the water to replenish oxygen from the air that has been lost to biological oxidation. Also, the pools and deepened channels have created sediment traps. These trapped sediments often exert a significant sediment oxygen demand (SOD) (Butts, 1974). In some pools, the reaeration capacity is barely adequate to supply the oxygen needed to stabilize the SOD.

#### General Effects of Dams

Dams are built across streams for reasons such as aesthetics (as exemplified by small channel dams in parks), flow and navigation control, and hydroelectric power generation. Regardless of the purpose of the dam, all affect water quality to some degree. The manifestations can be both positive and negative, and some effects may be subtle and indirect while others may be obvious and direct.

One of the most obvious and direct effects dams have on water quality is the creation of abrupt changes in dissolved oxygen concentrations. When DO problems are likely to appear at a new dam, consideration should be given in the design for maximizing aeration efficiency, and at established sites, operating procedures should be geared (when feasible) to maximizing reaeration in a practical manner.

To fully appreciate the need for an efficient aeration design or operating procedure at a dam site, an understanding is needed of the basic ecological and environmental consequences dams have on aquatic systems. Weirs and dams create pools which have DO levels inherently above or below those normally expected in a free-flowing stream of similar water quality. If the water is nutrient-rich but not grossly polluted, excessive algal growths can be expected to occur in the pools, resulting in wide fluctuations of diurnal DO levels. During the day, supersaturation may occur because of algal cell photosynthesis, whereas during the night almost total depletion may occur because of the respiratory needs of the algae. Essentially the pools act as biological incubators for plankton. of sustained photosynthetic in the absence oxygen production, concentrations may often fall below desired levels since the waste assimilative capacities of the pools are often much lower than those of free-flowing reaches of the same stream. Several factors account for this.

One is that the physical reaeration capability of a pool is much lower than that of a free-flowing reach of similar length. Reaeration is directly related to stream velocity and inversely related to depth. Consequently, since pooling decreases velocity and increases depth, natural physical aeration in a pool proceeds at a much slower rate. Butts et al. (1973) showed that for the Rock River in Illinois the average reaeration constant for an 11-mile pool was only 11 percent of the average of the one calculated for the preceding 11-mile upstream free-flowing reach.

The problem of low aeration rates in pools is compounded by the fact that more oxygen is used in the pool than in a free-flowing reach since the detention time is increased as a result of lower velocities. This enables microorganisms suspended in the water and micro- and macroorganisms indigenous to the bottom sediments in the pools to use more of the DO resources in a given area to satisfy respiratory needs. The detention time in the afore-mentioned Rock River pool was 2.23 days compared with the free-flowing reach time of travel of only 0.68 days.

Also, dams promote the accumulation of sediments upstream. If these sediments are polluted or laden with organic material, additional strain is put on the DO resources since the quantity of oxygen needed to satisfy sediment oxygen demand is directly related to the detention time and inversely related to depth, as shown by Butts et al. (1974). Depths behind navigation dams at intermediate to low flow fluctuations change at a lower rate than do corresponding detention times because flat pool elevations need to be maintained for navigational interests. Essentially, a fixed volume of water is preserved, allowing more time for benthic organisms to deoxygenize the water as flow rates decrease.

The reduction in oxygen levels behind the dams can be partially compensated for by aeration at the dam site. This localized aeration cannot make up for the overall damage rendered in the pools, but it can establish or control conditions in the next succeeding downstream reach. Unfortunately, dam aeration theory dictates that head loss structures deaerate water with supersaturated levels of DO at the same rate at which they would aerate water at equivalent subsaturated levels.

For example, water with a DO level 2 mg/l above saturation is deoxygenated at the same rate that it would be reaerated at 2 mg/l below saturation with all other physical conditions remaining unchanged.

Butts and Evans (1978) found that for highly productive streams such as the Fox River in Illinois, any DO above 200 percent saturation is lost instantaneously to the air as the flow makes contact with a weir or spillway crest. Dams in essence "blow out" supersaturated oxygen which may be needed as a reserve for algal respiration at some future time downstream.

## Purpose of Study

The purpose of this study was to evaluate the possible effects of hydroelectric power development at the Brandon Road lock and dam on the Des Plaines River (figure 1) on downstream dissolved oxygen resources. Water passing through penstocks and turbines receives very little aeration, whereas flow released through Tainter gates, such as those at Brandon Road which are perched on top of a high spillway, can be highly aerated depending upon gate manipulation and management.

Comprehensive evaluations were made by using Illinois River hydraulic and water quality models developed and verified by the WQS of the SWS over the last 15 years. Data inputs to the models and model coefficients were derived and developed from the results of recent water quality sampling conducted along the whole of the waterway and at the Brandon Road dam by the SWS as part of this study, and from the most current U.S. Army Corps of

Engineers river cross-sectional soundings. Statistical procedures were used to reduce the raw river data to meaningful form for use in the models.

Specific questions addressed and answered in this study are:

- 1. Will hydropower development at Brandon Road have negative effects on the already strained DO resources downstream of the dam?
- 2. If negative effects appear (as reflected by the results of the model study), what is their frequency of occurrence?
- 3. Can predicted negative effects be reduced or eliminated by managing and controlling water released through the potential power plant and/or dam flow release gates?
- 4. If flow release control is not a viable alternative, is artifical reaeration practical?

## Illinois Waterway Background Information

The Illinois Waterway (figure 1) is special among the many streams and rivers within Illinois: it drains 43 percent of the state and small portions of Wisconsin and Indiana. During dry weather, its headwaters consist principally of treated Chicago area wastewaters diluted with flow diverted from Lake Michigan. The waterway is not a free-flowing stream; it consists of eight navigational pools extending over 327 miles between the Mississippi River and Lake Michigan (figure 2). Locks and dams are located at Lockport (mile 291.1), Brandon Road (286.0), Dresden Island (271.5), Marseilles (247.0), Starved Rock (231.0), Peoria (157.7), and LaGrange (80.2). Tainter gates are used for flow control at the Brandon Road, Dresden Island, Marseilles, and Starved Rock dams. The Peoria and LaGrange dams are unique in that bottom hinged rectangular plates, known as Chanoine wickets, are lowered to lie flat on the river bottom during high flows for river traffic to pass. During low flows, desired upstream head is achieved by raising the wickets and inserting timbers called needles between each wicket, thereby creating a sharp-crested, low-head channel dam or spillway. All the flow at Lockport is passed through penstocks for power.

Although the dams are principally responsible for the reduction in the ability of the waterway to assimilate wastes, some of the natural aeration capacity lost through pooling can be partially made up at the dam. As water is passed either under or over flow release control structures at the dams, it is instantaneously reaerated due to the great turbulence and head loss factors associated with these releases. Historically, these flow release structures have been operated only to meet flow needs. No consideration has been given to optimizing and coordinating flow control adjustments with downstream water quality needs. If slightly more than one part per million of DO could be added by reaeration at the Starved Rock dam by better management relative to reaeration, the DO standards could probably be achieved in the Peoria pool when or if improvements are made to the Calumet treatment plant. The purpose of this study was to define the aeration characteristics of the Brandon Road flow release control structures so that a practical operating scheme could be developed and employed to enhance the dissolved oxygen resources in the Dresden Island pool below the dam.

## Acknowledgments

This study was funded by a research grant from the Village of Rockdale. The research was conducted as part of the work of the Water Quality Section of the Illinois State Water Survey (Richard G. Semonin, Chief). Robert Rogina of Beling Consultants in Joliet, Illinois, provided considerable valuable assistance and guidance. Field crews consisting at various times of Dave Beuscher, Jud Williams, Dave Green, Jim Kelton, Pete Berg, John Mathis, and Eric Von Hoven made this study possible by spending long days and nights in the field collecting data. Dave Hullinger and Dana Shackleford ran the laboratory analyses. Special recognition is given to Harvey Adkins, who supervised the field crews and was responsible for designing the computer programs needed to handle the massive amounts of data generated by this study. Harvey died unexpectedly at the age of 31 before the completion of this report, and this report is therefore dedicated in memory of him and his truly great concern for the environment.

#### DAM AERATION THEORY

As previously noted, water flowing over weirs and spillways or through head-loss control structures such as Tainter and sluice gates can be aerated or deaerated depending upon the ambient upstream DO concentration. This relatively instantaneous DO change at a dam site may be dramatic and may have a more lasting effect on water quality and overall aquatic biology than any other single physical factor. This is especially true where deep pools are created behind navigation dams which limit the natural physical reaeration capacity of a stream. The effects of these structures on water quality cannot be ignored; any water quality model dealing with DO as a parameter must take into consideration the influence of all types of dams, and this must be done with accuracy and confidence.

Unfortunately, however, little work has been done to develop universally applicable techniques for predicting DO changes at dams. The lack of information and methodologies applicable to navigation dams where flow releases are usually gate-controlled is especially noticeable when searching for information. Most of the limited work on developing a dam reaeration model has been done by studying channel dams, weirs, and head loss structures on small streams and rivers. Usually when dam aeration is incorporated into a water quality model, it is handled with a simplistic "black box" approach whereby the change in DO concentration is correlated to a single factor, the water fall height.

Typical examples of this approach are the simple models developed by Crevensten and Stoddard (1974) and by Foree (1976). From field observations, Crevensten and Stoddard derived an empirical expression in which dam aeration is expressed as a direct function of the water fall and a variable numerical coefficient. Force derived an empirical expression from field data, in which dam aeration is a direct function of the natural logarithm base (e) raised to the power of 0.16 times the water fall. The

specificity of these equations limits their usage to the conditions for which they were developed.

Only two references were found related to evaluating the aeration capacity of flow-controlling works at navigation dams. One was the work reported by Susag et al. (1967) for the Hastings Dam on the Mississippi River below Minneapolis, Minnesota, and the other was the work reported by Preul and Holler (1969) for two dams in the vicinity of Cincinnati on the Ohio River. Of particular note is the fact that both published papers were void of references to previous works on the subject, indicating an historical lack of interest in the subject. In addition to studying the two Ohio River Dams in situ, Preul and Holler evaluated a laboratory-scale model of a Tainter gate of one of the dams.

Both the Mississippi and Ohio River dam studies were interesting and informative, and management techniques were developed to increase aeration efficiencies in a manner compatible with navigation interests. However, these management techniques were basically site-specific and not directly transferable to other locations, although an attempt was made by Preul and Holler (1969) to develop a more universally applicable mathematical model using dimensional analysis. Aeration efficiencies were equated to the Froude number. A good relationship was found to occur within the range of conditions encountered during sampling of the two Ohio River dams. However, this relationship, along with the operational procedures proposed, is dependent upon an intimate knowledge of hydraulic parameters relative to energy dissipation and to the discharge characteristics of the gates and attendant receiving basins. Essentially, the application of this approach requires discharge rating information on flow releases through gates.

The Hastings Dam study was designed to evaluate the aeration efficiencies of navigational dam flow releases for three conditions: 1) Tainter gates unsubmerged in the downstream direction (tailwater area), 2) Tainter gates submerged by tailwater, and 3) replacement of Tainter gates with bulkheads (fixed walls), which create sharp-crested weir overflows. Unsubmerged Tainter gate discharges were found to be three times more efficient than submerged discharges relative to reaeration when the upstream DO was 0 mg/l. Under similar DO and head conditions, the bulkhead overflow-weirs exhibited aeration efficiencies 2.5 times as great as the submerged Tainter gate discharges.

Preul and Holler also explored the possibility of increasing the aeration by overflow rather than underflow. Instead of using bulkheads in the gate openings, the gates were fully closed, letting water spill over the top. This operational procedure was found to be the least efficient method; both submerged and unsubmerged tailwater releases exhibited higher efficiencies.

In addition to differential water levels around which simplistic statistical formulations have been developed, other factors such as water film thickness, water quality, structural design and/or configuration, and flow rate all influence aeration to some degree.

Gameson (1957) has shown experimentally that the largest percentage of DO changes occurs at the foot or on the aprons of spillways or flow release structures; consequently, the physical design of a structure is important.

Water spilling onto a concrete apron or a rocky scarp and water forming a hydraulic jump at the base of a dam have reaeration potentials different from those of water falling into a deep, quiet pool. Preul and Holler (1969) showed that the size of the hydraulic jump created in Tainter gate stilling basins was the most important factor regulating reaeration at the two Ohio River dams studied. Their conclusion was that submerged hydraulic jumps are inefficient aerators. For optimum oxygen absorption, the supercritical flow under a gate must break the surface for gates that discharge into stilling basins.

Velz (1947) and many others have shown experimentally that aeration is a direct function of water temperature, i.e., warm water reaerates at a faster rate than cold water. This fact should be accounted for in the development of a dam aeration model.

Another criterion which should be directly accounted for in an aeration formulation is water quality. After conducting a literature review on the effects of contaminants on reaeration rates, Kothandaraman (1971) reported that most contaminants retard oxygen uptake although a few appear to enhance it. Aeration rates have been reduced up to 60 percent by adding large portions of sewage to tap water, whereas suspended sediments, depending on the type, either increase or decrease the aeration rate to a slight degree.

Preul and Holler (1969) recognized the existence of this phenomenon in their work, but they made no attempt to ascertain its effect on their DO observations which were made year-round. In the laboratory scale model study of a Tainter gate, they assume that alpha, the oxygen transfer ratio of polluted to unpolluted water, is unity. While this assumption may be correct, it is open to question because the chemical contaminants sodium sulfite and cobalt chloride had to be added to deoxygenate the experimental water. Susag et al. (1967) used alpha values ranging from 0.9 to 1.0.

Gameson (1957), in some original dam aeration work, proposed the use of an equation involving both theoretical and rational concepts which relate water fall height, water temperature, structure geometry, and water quality to a factor defined as the deficit ratio, r. The definition of r is:

$$r - (C_S - C_h)/(C_S - C_R)$$
 (1)

where  $C_S$  is the DO saturation concentration at a given temperature and  $C_A$  and  $C_B$  are, respectively, the DO concentrations above and below the dam or flow release structure.

Although equation 1 is simple, it serves to illustrate two principles important to dam aeration concepts. First, it demonstrates that the upstream DO concentration dictates the rate of oxygen exchange at any dam. Second, for a given set of water and temperature conditions, higher ratios reflect higher aeration efficiencies. Relative to the first concept, Gameson (1957) and Gameson et al. (1958) found in laboratory experiments that the ratio is independent of above-dam DO concentrations of  $C_{\rm S}$  ± 10 mg/l. However, data collected by Barrett et al. (1960) indicate that this independence may be reduced to  $C_{\rm S}$  ± 4 mg/l for full-sized field structures.

The original dam aeration formula (Gameson, 1957; Gameson et al., 1958) relating temperature, water quality, dam cross-sectional design, and differential water levels to the deficit ratio has been modified and refined and appears in the following form (Water Research Centre, 1973):

$$r = 1 + 0.38 \text{ abh } (1 - 0.11h)(1 + 0.046T)$$
 (2)

where a is the water quality factor; b is the weir, spillway, or gate aeration coefficient; h is the static head loss at the dam (i.e., upstream and downstream water surface elevation difference) in meters; and T is the water temperature in °C.

This equation can be used to model the relative and absolute efficiencies of a spillway or flow release structure by determining specific values of "b". Every spillway or gate has a specific coefficient, but generalized categories can be developed in reference to a standard. The standard weir (b = 1.0) by definition is a sharp-crested weir with the flow free-falling into a receiving pool having a depth equal to or greater than 0.16 h. An idealized step weir (a series of sharp-crested weirs) has a b-value of 1.9 (Water Research Centre, 1973); however, actual field-measured values are usually lower.

Equation 2 was developed by British researchers from data collected at many relatively low head channel dams and weirs transecting small streams. Good reproducibility can be achieved when h does not exceed 3 to 4 meters, the maximum height of the dams at which data collections were made during development of the equation. In addition, close examination of the equation reveals that the factor (h)" (1 - 0.11 h) mathematically restrains the use of the equation to heights of 4.55 meters or less.

The water quality factor (a) has to be evaluated experimentally in the field or estimated from published criteria. Refinements of Gameson's (1957) early categorization of a-values are: grossly polluted water, a = 0.65; moderately polluted, a -1.0; slightly polluted, a = 1.6; and clean water, a = 1.8. These values are based on a minimal amount of field and laboratory data and are refinements of those originally published by Gameson (1957). The direct applications of these values are subjective, and since considerable latitude exists numerically between values, significant errors can result.

This study and the management strategies which will be developed as a result of it are based upon the dam aeration theory as expressed by equations 1 and 2. Equation 2 has some minor deficiencies, but the SWS has collected extensive information relative to its use for a wide variety of weir and dam structures throughout Illinois, including all the dams along the Illinois Waterway (Butts and Evans, 1978, 1980; Butts and Adkins, 1987). The last reference is very important to this study because it involved an in-depth study of the aeration characteristics of the Starved Rock dam Tainter gate flow release structures during the summer of 1985. The methods developed made possible an accurate assessment of the effects hydropower development at Starved Rock would have on downstream DO resources (Butts et al., 1987). The Starved Rock hydropower study, been used as a "model" for evaluating the characteristics of the Brandon Road dam.

#### METHODS AND PROCEDURES

This study consisted of two distinct phases. First, extensive field work had to be done to generate data for use in evaluating the aeration characteristics of the Brandon Road dam flow release gates. The methods and procedures used were similar to those developed and applied by Butts and Adkins (1987) for gathering data for use in evaluating the aeration characteristics of the Starved Rock dam Tainter gate flow release controls. The second part of the study involved applying a BOD-DO model to the Illinois Waterway to assess the variability in DO levels under a wide range of flow and temperature conditions between river mile 291.04 (Lockport dam) and river mile 219.80 in the Peoria pool. After this information was derived, it was used to evaluate the potential effects the establishment of a hydropower plant at the Brandon Road dam at river mile 286.0 would have on downstream DO resources under critical low-flow, high-temperature conditions. Above-dam DO concentrations ( $C_A$  in equation 1) were generated These values dictated the development of various for each model run. probability functions relative to the frequency of plant shutdowns needed to prevent unacceptable negative impacts on downstream DO levels.

## Field Studies

The purpose of conducting field studies was to obtain data for deriving b-values for the Brandon Road dam for use in equation 2. The procedure for doing this entailed two steps. First a weir-box system, with a known b-value, was set up to determine the a-value in equation 2. River water was pumped from a point upstream of the dam into an elevated box equipped with a 30° V-notch weir having a weir aeration coefficient (b) of 1.038 (Butts and Adkins, 1987). The water quality factor (a) can be calculated by measuring water temperature, DO changes, and water fall height. The calculated a-value, in turn, can be used in equation 2 to accurately determine Tainter gate b-values. After the weir box data were generated for a particular run, instream DO and temperature data were collected above and below the dam.

Upon arrival at the dam, the number and location of open gates and pool elevation information was obtained from the lockmaster or one of his assistants. Also, a bucket of well water was obtained for use in calibrating the DO meters. The weir box and appurtenances were then set up on a mooring pier above the upstream lock gates (figure 4).

A 4-liter sample of river water was obtained and poured back and forth between two 5-gallon buckets four or five times and then placed in an 8-liter plastic jug for further aeration (or deaeration in the case of supersaturated conditions). Jug aeration was accomplished by attaching a fine bubble aeration stone to a portable air compressor equipped with a cigarette lighter electrical attachment. At the end of the weir box run (1-1/2 to 2 hours) two samples were drawn off for DO and temperature measurements. If the DO differences exceeded 0.1 mg/l, a third sample was drawn and measured.

Four DO probes were calibrated in the field using the tap water which was obtained from the well located at the lock control house. River water does not suffice for calibrating because algal activity can cause river

water DOs to fluctuate widely over the 20 minutes needed for calibration. Well water is naturally low in DO, but once it becomes highly aerated, the DO concentration remains stable. Aeration was accomplished by pouring the water between two 5-gallon buckets at least 10 times.

The weir and receiving boxes were set up to attain a maximum water-fall height of 1.3 m, a maximum receiving depth of 0.5 m, and a maximum pumping rate of 1.77 l/sec. DO and temperature measurements were taken 30 minutes after the boxes filled. Water was pumped using a 1.5-inch portable gasoline-powered Honda WB15 centrifugal pump. A tarp was hung around the weir box setup when necessary to prevent wind from affecting the results.

The general layout of the dam is shown on figure 3; figures 4 and 5 show upstream and downstream photographic views of the dam. Flow is regulated by raising various numbers of the 21 Tainter gates (figures 3, 4, and 5) above the upstream water surface to maintain an upstream pool elevation of 538.5 feet above mean sea level (Mades, 1981). In a closed position the bottoms of the gates rest on top of an ogee spillway at an elevation of 536.3. In the past, some flow was released through 16 head gates located on the lock side of the dam (figures 3 and 5). These gates are now permanently sealed shut, but they were in operation during this study.

Above-dam DO and temperature measurements were taken at 4 to 7 vertical locations depending upon the number of gates open. The verticals were sampled at 2-foot intervals starting at the surface. Sampling was done by boat above the dam and from the Brandon Road bridge below the dam. Downstream sampling was confined to the left side of the river looking downstream, to avoid interference with head gate releases. Sampling below the dam was done at mid-depth at 5-minute intervals. Two-way radio contact was maintained with the above-dam sampling boat so that downstream sampling could be continued 5 to 10 minutes beyond the upstream termination time to allow for time of travel. On one occasion, DO and temperature readings were taken at the foot of the spillway from a boat and compared to those taken at the bridge. Essentially, both sets of data were found to be the same.

The upstream sampling depths were accurately and easily controlled by attaching the stirrer-probe to a heavily weighted fishing downrigger. Algae samples were collected both upstream and downstream. A 2-liter water quality sample was obtained downstream for analysis in the laboratory for suspended solids, chemical oxygen demand, and methylene blue active substances (MBAS) in terms of linear alkylate sulfonate (LAS). The latter chemical parameter is a measure of the surface active agent (detergent) content of the water. These parameters, along with algal enumeration, are easily measured variables considered (on an intuitive and subjective basis) to have a significant influence on reaeration.

Runs were made once or twice a week during July, August, and September and were alternated between day and night periods during the warm summer months. Night runs were run because significant diurnal fluctuations in the DO above the dam can occur due to algal activity. Nine day and nine night runs (10:00 p.m. to 2:00 a.m.) were completed. Although photosynthetic oxygen production can be significant above the Brandon Road

dam, daytime DO levels never became supersaturated; in fact, they did not even approach saturation concentrations. However, at times, day values did exceed night values by almost 2 mg/l.

All DO and temperature measurements were made using YSI model 58 digital dissolved oxygen meters equipped with YSI model 5795A submersible stirrers and YSI model 5739 dissolved oxygen field probes.

## SWS BOD-DO Model

The basic model used by the SWS to evaluate BOD-DO relationships in a flowing stream is a simple one-dimensional model in which the basic components are computed separately and are then combined algebraically to obtain a net DO concentration. The basic formulation is:

$$DO_n = DO_a - DO_u + DO_r + DO_x$$
 (3)

where  $DO_n$  is the net DO at the end of a reach;  $DO_a$  is the initial DO at the beginning of a reach;  $DO_u$  is the DO used biologically;  $DO_r$  is the DO addition due to aeration and photosynthetic oxygen production (P); and  $DO_x$  is the DO addition due to dam aeration and/or tributary inputs.

Details of the methodologies that can be used to compute the various components of equation 3 have been outlined in detail in previous SWS publications and reports (Butts et al., 1970, 1974, 1975, 1981).

Biochemical Oxygen Demand (BOD)

 $\rm DO_u$  may include dissolved oxygen usage resulting from carbonaceous BOD (CBOD), nitrogenous BOD (NBOD), sediment oxygen demand (SOD), and algal respiration (R). Algal activity can supplement stream DO through photosynthetic oxygen production (P), it can suppress stream DOs when R exceeds P, or it may have no effect when P equals R. For this study, P is assumed to equal R. Both CBOD and NBOD are programmed to follow first-order biochemical oxidation reactions as expressed by the general equation:

$$BOD_t = L_a \qquad (1-e-K_1(t-t_0)) \qquad (4)$$

where BOD<sub>t</sub> is the BOD exerted over a time period t in days;  $L_a$  is the ultimate BOD;  $K_1$  is the rate coefficient to the base of the natural logarithm, e; and  $t_0$  is the lag time in days to the onset of usage. For this study,  $t_0$  was set equal to zero for carbonaceous demand. However, tests have shown that oxidation of the large ammonia-N load discharged from the Chicago area does not commence until about three days travel time below the Lockport dam (Butts et al., 1975; Butts et al., 1987).

Sediment Oxygen Demand (SOD)

The SOD portion of DO usage is computed by using the expression:

$$G' = \underbrace{3.28Gt}_{H} \tag{5}$$

where G' is the oxygen usage per reach in mg/l, G is the SOD rate in g/m²/day; t is the detention time per reach in days; and H is the average reach water depth in feet. No allowance is made for reducing the SOD rates when the overlying water DO falls below 2 mg/l, as is done in some models. On the basis of several hundred in situ SOD measurements made by the Water Survey over the last few years, the conclusion has been reached that when the SOD is due primarily to bacterial respiration, the DO uptake rate remains relatively constant even at DO concentrations below 2 (Butts et al., 1974, 1981, 1982; Lee et al., 1975; Butts and Evans, 1978, 1979; Roseboom et al., 1979; Mathis and Butts, 1981). The benthic biomass in the whole length of the waterway, except in a few short reaches, is sparse, and most SOD is bacteria-related.

#### Natural Stream Aeration and Tributary Inputs

The aeration factor  ${\rm DO_r}$  is computed by using the theoretical concepts advocated by Velz (1947, 1970). Reference should be made to the Velz publications or to the report by Butts et al. (1973) for a detailed discussion of this somewhat complicated and lengthy computational procedure.

Dissolved oxygen, ammonia, and BOD inputs from tributaries are adjusted on a mass balance basis.

## Dissolved Oxygen Saturation

Dissolved oxygen saturation concentrations used in equation 1 and in the BOD-DO model, as schematically represented by equation 3, were computed by means of the ASCE formula (American Society of Civil Engineers, 1960):

$$DO_S = 14.652 - 0.41022T + 0.007991T2 - 0.00007777T^3$$
 (6)

where  $\mathrm{DO_S}$  = DO saturation at T°C. Equation 6 is referenced to mean sea level (MSL). Consequently, DO saturation computations for locations other than at MSL need to be corrected for changes in elevation. A correction factor of 0.981 needs to be applied when equation 6 is used to calculate DOg at Brandon Road. Also, equation 6 was developed experimentally using distilled water. Natural waters may be capable of sustaining saturation levels higher or lower than those predicted by equation 6 since natural waters contain various kinds and amounts of impurities. The ratio of the ambient saturation concentration to equation 6 values corrected for elevation is referred to as beta ( $\mathcal{B}$ ).

#### Dam Aeration

Aeration at the dams was accounted for by incorporating equation 2 in the computer model. As part of this overall study, field data and information were gathered for use in determining the aeration characteristics of the Brandon Road and Dresden Island flow control gates. The dam aeration coefficients for the Marseilles dam were obtained from Butts and Evans (1980) and those for the Starved Rock dam from Butts and Adkins (1987). Reference should be made to Butts and Adkins (1987) for the

detailed procedures used in calibrating the Brandon Road and Dresden Island dam gates.

## Hydraulic and Hydrologic Model

Stream water quality modeling requires hydraulic and hydrologic information as part of its input. Hydraulic and hydrologic parameters for the waterway between Lockport and Grafton were computed with the use of a flow and time-of-travel simulation program based on volume displacement, i.e., time equals the volume of water divided by the flow rate. concept, although basically very simple, can be used to generate reliable information for steady-state flows, the conditions under which most DO Critical to the accuracy and reliability investigations are made. information generated are quality and the quantity of stream cross-sectional data available and used.

The Corps of Engineers is required to maintain minimal channel depths in navigable streams such as the Illinois Waterway. As a part of the process of maintaining a navigation channel in the Illinois Waterway, the Corps has established permanent bench marks along the river which define cross sections. Soundings of the river bed are routinely made, and these data are plotted on maps at scales of 1" = 200'. Using the most current maps, the SWS has generated a computer data base of more than 1650 cross sections spaced at an average interval of 930 feet between the Lockport dam and the Mississippi River at Grafton.

The output from the hydraulic-hydrologic program includes cross section number, mile point, flow at the end of a reach, average flow within a reach, average cross-sectional area and average depth within a reach, time of travel within a reach, accumulated time of travel, and reach lengths and volumes. Inputs required are staff gage elevations and main stem and tributary discharges. Tributary and main stem discharges were developed and used in this study in terms of flow duration, i.e., the percent of time a given flow is equaled or exceeded in value. The daily average flows over all the years of record for all existing main stem and tributary gaging stations were entered into a computer file and sorted according to increasing rank. Percentage values were then computed, and the flows for given percentages were plotted on extreme log probability paper according to the procedure outlined by Mitchell (1957). Thirty flow conditions were used, ranging from an extremely low flow value of 99.8 percent duration (only 0.2 percent of the historically observed daily average flows were less) to a moderately high flow value of 8 percent (92 percent of the daily average flows have been less).

Duration curves were established for three main stem gaging stations and five tributaries. The main stem stations are Lockport (Corps MP 291.04), Marseilles (246.98), and Henry (196.12); the tributaries and their confluence MPs are the Des Plaines River (290.00), DuPage River (276.82), Kankakee River (272.86), Fox River (239.77), and Vermilion River (226.34).

The Corps of Engineers maintains staff gages at frequent intervals along the whole course of the waterway, which are read daily. The flows derived from the duration curves were matched with similar recorded flows

for which staff gage readings (pool elevations or stage) were available. The matchup stages were used in the hydraulic-hydrologic model runs.

The Illinois Waterway mile points (MP) used by the SWS are slightly different from those appearing on official navigation charts and maps published by the Corps of Engineers. The SWS, in compiling their computer file of cross sections, also electronically traced the longitudinal distances along the navigation channel and found the distances to be somewhat different from the Corps' in some locations. Besides differences attributable to accuracy errors, which obviously can be a factor, the Corps distances deviate from those measured by the Water Survey for two major reasons: 1) the Corps retains original mileage designations even when channel shortening and straightening have occurred, and 2) the Corps measures mileage along direct navigation approaches to the locks, whereas the actual water flow is usually over a more circuitous route via spillway and riffle areas. The effect of the former practice is to exaggerate the length, whereas the effect of the latter is to reduce it. The two, however, appear to balance each other in the end as the net difference at Lockport (Corps MP 291.0) is only 0.04 of a mile.

#### Water Temperature Considerations

Water temperature is probably the single most important factor governing dissolved oxygen concentrations in surface waters. Two reasons account for this. One is that as water temperatures become lower, the capacity of the water to retain DO becomes greater. For instance, the DO saturation of pure water at 30°C is 7.44 mg/l, whereas at 0°C it is 14.65 mg/l. The second reason is that as water temperatures become lower, bacterial and biological activity is reduced, resulting in less oxygen usage in the biochemical processes, which stabilizes dissolved organic matter and organic-laden bottom sediments. For example, the bacterial oxidation rate of dissolved ammonia is three times as great at 22°C as at 10°C.

Availability of daily water temperatures covering a recent 3- or 4-year period, and access to them, were needed to make this study meaningful and to achieve its goals and objectives. Surprisingly and unfortunately, such information has not been routinely generated along the Illinois Waterway. For the study performed at Starved Rock for the City of Peru (Butts et al., in press), a sophisticated computer model was used to generate theoretical Illinois River water temperatures on the basis of recorded average daily air temperatures as supplied by the U.S. Weather Service. This approach was not practical for the waterway in the vicinity of the Brandon Road and Dresden Island dams, since a poor correlation exists between air and river water temperatures in this area. This poor correlation is attributable to the unnatural temperature variability introduced upstream by discharges from very large wastewater treatment plants, to cooling water discharges from large coal-fired electric generating plants, and to the periodic diversion of Lake Michigan water for flushing purposes.

An extensive search was conducted to find a source of recorded information. A "last minute" source was found, but in the end, it proved to be inadequate for use in the modeling effort. However, it was

informative. The Commonwealth Edison steam generating plant at Joliet provided data from June 11, 1984 - October 17, 1984; May 10, 1985 - November 3, 1985; and May 16, 1986 - August 31, 1986. The critical temperature for the middle reaches of the Illinois River, as determined by the Starved Rock study (Butts et al., in press), fell somewhere between 18°C and 20°C. Previous data indicates that river water temperatures between 18°C and 20°C usually occur between June 1 and September 30 in the middle and lower reaches of the waterway during a typical year. As a consequence, the duration curves referred to in the previous subsection, "Hydraulic and Hydrologic Model", were developed for this period. The Commonwealth Edison data indicated, however, that water temperatures in the 18°C to 20°C range commonly occur between early May and early November. This discovery was made after the majority of the BOD-DO model simulations had been completed on the basis of duration curves developed for the 122-day period between June 1 and September 30.

The study had progressed to a point that did not permit redoing the duration curves, but a "last ditch" effort did turn up a new source of continuously recorded daily water temperatures. During the 1970's, the U.S. Geological Survey (USGS) maintained a temperature recording station at the Dresden Island dam. Examination of these data (United States Geological Survey, 1976, 1977, 1978, 1979) revealed that the most realistic period for 18-20°C temperatures falls between April 1 and November 30 for a typical year. Consequently, temperature frequencies were developed for this 244-day period. Included in the frequency distribution were the years 1975, 1976, and 1977. The authors of this report feel that the flow duration curves adequately represent the expanded period of analysis. Future revisions can be made if the preliminary results warrant them.

## Parameters and Parametric Coefficient Modeling

Computer modeling results are no better than the quality of the input data. In this case, high-quality water quality data were available from a study of the upper waterway conducted by the WQS of the SWS during June through September of 1982. This information was needed and helped make this study possible.

Basic regression curve fitting techniques were used to equate certain required parameters to flow so that estimates could be made as to what these values would be for the 30 specified flow-duration flows. In other words, reliable boundary conditions had to be established for a wide range of flow conditions. The parameters equated to flow are the initial carbonaceous and nitrogenous BOD input loads at Lockport on the main stem, the tributary carbonaceous and nitrogenous BOD load inputs, the initial starting DO at Lockport (assumed to be 0.5 mg/l on the basis of extensive historical data), the tributary DO concentrations at their mouths, the instream carbonaceous BOD usage factor ( $\rm K_{\rm c}$ ), and the instream nitrogenous BOD usage factor ( $\rm K_{\rm c}$ ).

The last two parameters vary from reach to reach along the main stem. Consequently, separate regression equations were developed to fit the needs of certain reaches. Flow and water quality data were not available for three small tributaries: the Mazon River, Bureau Creek, and the Illinois and Mississippi Canal. Inputs were estimated for these sources by using

some water quality information gathered prior to 1982 and by estimating flows by using the Vermilion River duration curve.

Fair to good positive correlations were found to exist between BOD loads and flows by using the simple linear model:

$$Y = AQ + B \tag{7}$$

where Y is either  $L_{ac}$  (ultimate carbonaceous BOD) or  $L_{an}$  (ultimate nitrogenous BOD) in lbs/day or DO in mg/l

 $Q = Lockport(Q_L)$  or tributary flows: Des Plaines,  $Q_{DS}$ ; DuPage,  $Q_D$ ; Kankakee,  $Q_K$ ; Fox,  $Q_F$ ; or Vermilion,  $Q_V$ , in cfs

A and B = regression coefficients

The logarithms of the BOD-usage rates, main stem  $K_c$  and  $K_n$ , were more highly correlated to the logs of the three main stem gaging station flows (table 4) than their untransformed values. Consequently, the usage rates fit the nonlinear multiple regression model:

$$\log K - A \log Q_{T} + B \log Q_{M} + C \log Q_{H} + D$$
 (8)

where  $K = either K_c$  or  $K_n$  in 1/days

 $Q_L$ ,  $Q_M$ ,  $Q_H$  = flows at Lockport, Marseilles, and Henry, respectively, in cfs

A,B,C,D = regression coefficients

Waste loads originating from point sources between the Lockport and Peoria dams were lifted from table 18 of SWS Contract Report 324 (Butts et al., 1983). The summer month values listed in the table were used in this analysis.

## Modeling Procedure

DO usage was initiated at Lockport, i.e., the model runs had to start there because the bulk of the carbonaceous and nitrogenous wastes originate from the Chicago area. Consequently, Chicago area wastes, particularly ammonia-N, dictate to a great degree what the downstream DO concentrations will be in the absence of photosynthetic oxygen production. The residual Chicago area wastes were routed downstream and reinforced with point and tributary sources. When flows were less than 8600 cfs at Marseilles, all the flow arriving at the Marseilles dam was routed through the hydroelectric power plant. Only flows in excess of 8600 cfs were routed through the dam flow release gates and allowed to reaerate. This, in effect, produced a continuous DO sag curve across the dam boundary at low flows and resulted in significantly lower DO levels immediately above the Starved Rock dam. This phenomenon is supported by historical data generated along this reach of the river as shown by figure 6 (Butts et al., 1975).

Dissolved oxygen sag curves were generated at 2°C intervals starting at 12°C and ending at 28°C. Curves were extrapolated for 10, 11, 29, and 30°C and for the odd degrees between 12°C and 28°C. Each combination of flow and temperature produced a minimum DO value downstream. These values were used as a basis for determining what minimum DO concentrations were

needed immediately below the Brandon Road dam to maintain a minimum 5.0 mg/l at the low point on the sag curve.

## Stepwise Regression Analyses

A mathematical statistical computational procedure, known as stepwise regression analysis, was used to evaluate interrelationships between certain variables or parameters measured or examined during this study. A certain parameter is designated as a dependent variable while others are specified as independent variables. A computer program correlates the dependent variable to each of the independent variables and ranks each independent variable in the order of importance relative to its predictive reliability. Also, regression coefficients are computed for use in developing or formulating prediction equations.

#### RESULTS

The results of this study are presented in three parts. First the information and data collected from the field calibration work are presented along with ensuing results. Next, all the information collected for preparing and formulating input to the BOD-DO model is presented in a reduced manner. This is followed by presentation of the results of 270 model runs resulting from a combination of 30 flow durations and 9 temperatures. These results form the basis for an extended, more detailed discussion.

## Dam Calibration

Eighteen field calibration runs were made from July 9, 1986 through September 24, 1986. Nine runs were made during daylight, and 9 runs were made during the night. Table 1 summarizes the hydraulic conditions which occurred over the course of the field study period. A good range of conditions existed: flows ranged from a low of 3250 cfs, with only 4 gates open, to a high of 13,230 cfs, with 18 gates open. This makes the results meaningful over a wide range of expected warm weather flows. The lowest flow is exceeded about 75 percent of the time, and the highest flow is exceeded only about 0.3 percent of the time during warm weather conditions (Appendix A).

## Weir Box Data and Results

The results of the weir box field experiments conducted to determine the water quality factor "a" in equation 2 are presented in table 2. A good range of conditions occurred during the sampling period. Above-the-weir (inlet) DOs, the most important criterion governing the results, ranged from 2.61 mg/l or 31.7 percent of book-value (clean-water) saturation to 6.73 mg/l or 82.3 percent of book-value saturation. Note that actual saturation values deviated somewhat from clean-water published values. Most of the time the saturation values were within ± 2 to 3 percent, but occasionally the deviation was much greater. For example,

during daylight sampling on September 24 it was +12.5 percent. The actual experiment saturation concentrations were used in the evaluation of the weir box data and the river-run data collected for evaluating the dam aeration coefficient "b". The water quality factor remained fairly constant for all runs, ranging from a low of 0.93 to a high of 1.24 with the average being 1.10. An a-value equal to 1.10 is indicative of moderately polluted water. This is not surprising since during warm weather the Des Plaines River at Brandon Road consists primarily of treated sewage effluent diluted with water diverted from Lake Michigan. Illinois River at the Dresden Island dam displayed an average a-value of 1.56 during the same period in which this study was conducted. Inflow of clean water from the Kankakee River, tributary to the Illinois River immediately above Dresden Island, greatly influences water quality in this area of the waterway. The average Brandon Road and Dresden Island a-values were used for all BOD-DO model runs.

#### River-Run Data and Results

The data collected instream to "calibrate" the aeration efficiency of the Tainter gates are presented in table 3. The above-dam DOs were always well below saturation, with the average saturation percentage being equal to 40.9, while those below the dam became nearly saturated, with the average saturation percentage being equal to 90.3 percent. This alone shows that, on the average, the Brandon Road dam flow release controls are excellent aerators and provide nearly saturated reserves for downstream demands.

The average and median values for the dam aeration coefficient were 1.81 and 1.87, respectively. The median value of 1.87 was used in all BOD-DO model runs. The b-value of 1.87 is essentially equal to the maximum value of 1.82 which can be achieved at the Starved Rock dam with 4-foot gate openings (Butts and Adkins, 1987), but considerably greater than the value of 1.03 which would result from 2.25-foot gate openings at Starved Rock.

#### Model Support Data

#### Hydraulic and Hydrologic Information

The flow duration curves developed for the three main stem flow gaging stations and the five tributaries are presented in Appendix A. The 30 duration percentages and the corresponding flows for the three main stem gaging stations located within the study area are presented in Appendix B. The listing for the Kingston Mines gage is an empirical downstream extension of the Henry gage results and was incorporated into the system to carry the hydraulic and hydrologic computer model computations through to the Peoria lock and dam. Note that the mile listings are SWS designations. The tributary flows are presented in Appendix C. The Mazon, I & M Canal, and Bureau Creek flows were derived by taking percentages of Vermilion River duration curve values. In reality, these four relatively small streams exhibited little effect on main stem conditions over the entire range of flows. The pool elevations selected to match up with the flows

presented in Appendix B are given in Appendix D. The times of travel to the various point source waste load inputs are given in Appendix E.

Note in Appendix E the extreme length of time required for water to travel between the Lockport dam (290.99) and the Peoria dam (158.06) during very low flow periods compared to that required during the higher flows. This has a significant influence on the waste assimilative capacity of the waterway. It essentially dictates the reach or reaches in the waterway where critical low DO values will occur. High flows often produce lower DOs in the lower pools than do very low flows. Several factors account for this. Most significant is the fact that high flows usually have a higher BOD concentration, and this unproportionally higher load is flushed downstream where it is oxidized. At high flows, the detention times in the short upper pools are insufficient to allow bio-oxidation to commence to a great degree, and what little oxygen depletion is incurred is instantly made up via reaeration at the dam flow release control structures. Another factor which is not considered in the modeling results presented in this report is photosynthetic oxygen production. The DO resources along the waterway are supplemented very little by primary productivity during high flows. The higher the flow, the more turbid the water; also, the high velocities tend to "wash out" algal cells. During low to very low flows, photosynthetic oxygen production is a valuable supplement to Illinois Waterway DO resources, from the lake-area above the Starved Rock dam down to the Peoria lock and dam.

#### Water Quality Information

The regression coefficients associated with the simple regression (equation 7) and multiple regression (equation 8) formulations developed for generating realistic water quality parameters and waste load inputs for the 30 flow conditions (Appendices B and C) are presented in table 4a. Five sets of long-term 1982 BOD data were available for the main stem and tributaries for generating carbonaceous and nitrogenous waste loads in terms of pounds per day, and their attendant instream usage rate factors (K-values) in terms of l/days. Seventeen DO measurements were available for use in estimating daily average DO concentrations at each tributary mouth. Inputs from the Mazon River, I & M Canal, and Bureau Creek were arrived at by using the Vermilion River equations.

Overall, good predictive relationships were produced for the waste load inputs. Correlation coefficients between waste loads in lbs/day and flow in cfs ranged from a low of 0.60 for the Kankakee River to a high of 0.99 for the Vermilion and DuPage Rivers for carbonaceous BOD (CBOD), and from a 1 ow of 0.39 for the Kankakee to a high of 0.99 for the Des Plaines for nitrogenous BOD (NBOD). The respective CBOD-flow and NBOD-flow correlation coefficients at Lockport were 0.88 and 0.67. An inverse relationship occurred between DO and flow for all the tributaries as evidenced by the negative A-values listed under DO in table Correlation coefficients, relating DO in mg/l to flow in cfs, ranged from a low of -0.27 for the Kankakee to a high of -0.77 for the Des Plaines. negative relationship results from the influence of photosynthetic oxygen production on low-flow DOs as briefly discussed in the preceding subsection. Flows in small tributaries usually decrease significantly during warm summer months, thereby creating slow moving water and pools.

This promotes primary productivity and attendant increases in peak daily DO levels. Larger streams, such as the relatively nutrient-free Kankakee, are not nearly so vulnerable to photosynthetic oxygen production influences and fluctuations.

The ultimate  $L_{ac}$  and  $L_{an}$  values for the Sanitary and Ship Canal at Lockport and for the tributaries, computed by using the coefficients in table 4a in conjunction with equation 7 for conditions involving the 30 duration flows, are presented in Appendix F. The tributary input-DOs for the 30 flow conditions are presented in Appendix G.

The carbonaceous BOD usage rate ( $K_c$ ) and the nitrogenous usage rate ( $K_n$ ) are variable throughout the study reach. Table 4b lists the regression coefficients associated with equation 8 for various reaches down to the Peoria Lock and Dam (river mile 157.0). Multiple correlation coefficients ranged from 0.780 to 0.995 for CBOD rates and from 0.675 to 0.998 for NBOD rates.

The  $K_c$  and  $K_n$  values, computed by using equation 8 in conjunction with the coefficient and intercept values listed in table 4b, are presented in Appendix H for the 30 flow durations. For the extremely low flow conditions of 99.8 and 99 percent durations, equation 8 produced  $K_c$  rates slightly too high to be realistically used in the BOD-DO model. To rectify this, values computed for the 98 percent duration were extended for use at the two lower flows. Also, note from table 4b and Appendix H that equation 8 produced nonsensical  $K_c$  results for the data available for the reach between Corps miles 179.0 and 222.6. To rectify this, the averages of the values for the reaches upstream and downstream of this reach were substituted here.

Note that, at Lockport, as the flows increase the waste loads increase in terms of total pounds per day (Appendix F), but the rate of usage, as measured by the K-values contained in Appendix H, decreases with increasing flow rates. This situation has been documented by other waterway studies conducted by Butts et al. (1970), Butts et al. (1975), and Butts et al. (1981). This fact, along with the occurrence of decreasing time of travel with increasing flows, helps transfer a tremendous amount of Chicago area wastes into critical reaches of the Starved Rock and Peoria pools. Recognition of this phenomenon helps in understanding why low DOs have been routinely documented in the Peoria pool even during relatively high flows during warm summer months. Any water quality management scheme developed in conjunction with hydropower development along the waterway, especially at Starved Rock and to a lesser degree at Dresden Island, has to consider this fact.

A water temperature duration curve, developed by using the USGS data at Dresden Island for April 1 through November 30 for the years 1975, 1976, and 1977, is presented as figure 7. The frequency distribution is plotted on arithmetical, normal probability paper.

## BOD-DO Model Products

Examples of results of BOD-DO model runs for two flow conditions, 99.8 and 8 percent flow duration, at two temperatures, 12 and 28°C, are

presented in Appendix I. The computer program used to derive these results, written in BASIC, is presented in Appendix J. The DO concentrations predicted to occur immediately downstream of the Brandon Road dam and the minimum DO concentrations predicted to occur within the Dresden Island pool for the 270 simulations run at various flows and temperatures are given in tables 5 and 6, respectively.

These results represent predicted ambient conditions, i.e., river-run situations without hydropower at the Brandon Road dam. Clearly evident is the fact that even without hydropower the minimum DO standard of 5.0 mg/l is violated in the Dresden Island pool. The 5.0 mg/l standard below the I-55 bridge (river mile 277.9) is critical. Aeration at the Brandon Road dam is sufficient to insure that the minimum DO standard of 4.0 mg/l, as specified for the reach between the dam and the I-55 bridge, will seldom be violated (figure 6). In fact, if a 5.0 mg/l minimum standard were to be prescribed for this reach, persistent violations still would not occur. However, the DO drops rapidly below the I-55 bridge while the minimum standard increases from 4.0 mg/l to 5.0 mg/l. Consequently, the naturally rapid drop in DO coupled with the more stringent standard makes the reach of the waterway between the bridge and the Dresden Island dam extremely vulnerable to violations. Therefore, the management of the proposed hydropower plant, relative to downstream water quality, will have to be tailored to meet the standards below the I-55 bridge and not those above the bridge.

## Stepwise Regression Analyses

Stepwise regression techniques were used to equate 12 independent variables, (1) number of gates open; (2) total head loss; (3) total discharge; (4) head-gate discharge; (5) water quality factor (a); (6) COD; (7) MBAS; (8) suspended solids (SS); (9) above-dam algae counts; (10) below-dam algae counts; (11) water temperature; and (12) above-dam DO, to either of three independent variables, (1) the deficit ratio (r); (2) dam aeration coefficient (b); or (3) the below-dam DO ( $P_0$ ). The results of the analyses, arranged in the order of the significance of the inclusion of each independent variable into the regression equation, are presented in table 7. The parametric data used to generate these results are given in Appendix K. The 3 dependent variables represent optional ways of presenting dam aeration efficiencies.

The aeration efficiencies of the Brandon Road dam, irrespective of how they are measured, appear to be influenced by many factors as evidenced by the results summarized in table 7. The 12 dependent variables explain only 64 percent of the variability observed for  $P_0$ , whereas they explain 84.4 percent of the variability observed for the deficit ratio (r). Negative regression equation coefficient values indicate that inverse relationships exist between the dependent and independent variables, i.e., increases in independent variable values cause decreases in dependent variable values. Significant is the fact that the regression equation coefficients for head-gate flow are negative in all three cases. This means that downstream DO concentrations are reduced with increased flow through the headgates. However, since the head gates are now permanently sealed, some slight improvement in reaeration should be evident at this time. Also of significance is the fact that general water quality conditions, as

represented by the a-value, are related to reaeration in a positive manner, as evidenced by the positive values of the regression equation coefficients in all three cases. The potential is considerable for improvement in water quality since the average a-value observed during this study was 1.10 compared to a theoretical high of 1.80. Consequently, improved water quality could induce improved reaeration at the Brandon Road dam site, albeit any such improvement would probably be small.

Stepwise regression techniques were also used to equate 9 independent variables, (1)- total discharge; (2) water quality factor (a); (3) COD; (4) MBAS; (5) suspended solids (SS); (6) above-dam algae counts; (7) below-dam algae counts; (8) water temperature; and (9) above-dam DO, to the B-values given in Appendix K. The results of the analyses, arranged in the order of the significance of the independent variable inclusion, are presented in Note that only 4 of the 8 independent variables contribute significantly toward providing a good estimate of B since the standard error of estimate begins to increase after the a-variable is included. This means that prediction equations which successively include the independent variable represented by steps 5 through 9 will produce successively poorer estimates of B. The regression equation coefficient associated with the water quality factor (a) is positive which indicates that increases in & should be realized with improvements in water quality The water quality factor averaged 1.10 for this study at Brandon Road. (table 2). A change from this value to a maximum clean water value of 1.8, while assuming the average of the other parametric values in Appendix K remained unchanged, would result in an 8.6 percent increase in B. This would produce approximately an 0.3 mg/l increase in the downstream DO when the DO upstream of the dam was 4.0 mg/l at 25°C.

#### DISCUSSION

Information is presented and discussed in this section which will allow decisions to be made by proper authorities concerning the feasibility of developing hydropower facilities at Brandon Road without directly causing additional downstream DO standard violations. The minimum simulated DOs presented in table 6 are used as the nucleus for making this evaluation. Probability factors are developed.

The problem can be attacked simply by assigning a minimum acceptable 5.0~mg/l DO level throughout the affected pool. The precise  $C_B$  required in each specific instance can be ascertained only by a trial-and-error process. Various values need to be assigned to Cg and used in the BOD-DO model to make simulations between the Brandon Road and Dresden Island dams. Adjustments need to be made in Cg for each successive trial until the critical 5.0~mg/l value is achieved.

To perform such an evaluation for the nine temperatures and 30 flow conditions presented in table 5 would be costly and would greatly delay the dissemination of the results. Consequently, a simple, alternative, indirect method was used to achieve the same results without significantly sacrificing the accuracy and integrity of the final product.

An assumption was made that the Cg-values needed to maintain a minimum downstream DO  $(C_m)$  of 5.0 mg/l would be equal to the differences between the appropriate Cg and  $C_m$  values listed in tables 5 and 6 (with some adjustment for natural stream reaeration) added to 5.0 mg/1.adjustments for natural stream aeration can be either negative or positive depending upon whether the adjusted Cg-values are greater or less than the corresponding values in table 5. If greater, the natural stream aeration addition is positive; if less, the addition is negative. For example, the simulation run for a flow duration of 45 percent at 12°C yielded a  $C_{B}$  = 8.18 mg/l and a  $C_m$  = 7.33 mg/l (tables 5 and 6), resulting in a new Cg, unadjusted for stream aeration, of 5.0 + 8.18 - 7.33 or 5.85 mg/l. This value is considerably less than the simulated Cg; consequently, the 5.85 has to be reduced somewhat to account for the potential increase in the natural stream reaeration rate at this lower concentration. Table 9 lists these adjusted values. For the above example, the final Cg rate is equal to 5.74 mg/l with an allowance of 0.11 mg/l for additional natural stream reaeration. Conversely, for 28°C at a flow duration of 75 percent, the Cq was readjusted upward from 7.57 mg/l to 7.60 mg/l because of potentially reduced reaeration since 7.57 mg/l (5.0 + 6.28 - 3.71) is greater than the original simulated Cq-value of 6.28 mg/l.

The adjusted Cg-values listed in table 9 have to be related to the frequency of occurrence of existing or observed above-dam DOs  $(C_A)$  to be meaningful. Table 10 shows a tabulation of 48 above-dam DOs which are relatively current and reliable for the months of June through October. Included are the 18 values collected during this study. The last two columns of table 10 present the low-to-high rankings of all 48 values in the table and of the current 18 (1986) values, for use in developing frequency distribution plots on normal probability paper as shown in figure 8.

The feasibility or the practicality of building a hydropower plant essentially hinges on simple probability analysis. In general, if  $E_1,\ E_2,\ E_3,\ \dots$ ,  $E_n$  are "n" independent events having respective probabilities of  $P_1,\ P_2,\ P_3,\ \dots$ ,  $P_n,$  then the probability of the occurrence of  $E_1$  and  $E_2$  and  $E_3$  and . . .  $E_n$  is  $(P_1)(P_2)(P_3)$  . . .  $(P_n)$ . For this study, by letting  $P_1$  equal the probability of occurrence of a given flow rate,  $P_2$  equal the probability of occurrence of a given temperature, and  $P_3$  equal the probability of occurrence of a given DO concentration, the number of seasonal days during which power generation would be restricted would be  $(P_1)(P_2)(P_3)(244)$ .

The flows at Brandon Road for the 30 specified duration percents were computed by using the ISWS Illinois Waterway hydraulic-hydrologic model in conjunction with the flow duration information presented in Appendix A. The Brandon Road flows and corresponding duration percents are given in table 11. The temperature probabilities were obtained from the temperature duration curve (figure 7).. The DO probabilities were obtained from the DO duration curve (figure 8).

The probability factors and the corresponding number of days during which the downstream DOs are expected to fall below 5.0 mg/l are summarized in table 11 for P3 referenced to the 48-value frequency distribution curve (figure 8) and in table 12 for P3 referenced to the 1986 18-value curve (figure 8) for the condition whereby all the upstream flow is used for

power generation. This obviously exemplifies the worst possible scenario, but it provides considerable insight into the practical feasibility of the project. The end results indicate that approximately 206 24-hour periods of shutdown will be required between April 1 and November 30 during a typical year irrespective of whether the 48-value or current 18-value frequency distribution curve is used to evaluate P3.

The  $P_3$ 's derived from the 1986 data curve actually produce a very small fractional increase in the number of required shutdown days (0.095 days, tables 11 and 12) since the 1986 data curve falls below the overall-data curve between DO values of 3.55 and 5.75 mg/l (figure 8). The minimum required above-dam DO values would have to be less than 3.55 mg/l to produce a reduction in the number of days. Such a reduction cannot occur since, theoretically, the minimum acceptable above-dam DO values must equal at least 4.0 mg/l, the immediate downstream DO standard.

The total of 206 days of shutdown could possibly be reduced somewhat by artificially introducing dissolved oxygen into the water and/or by using only a fraction of the stream flow for power generation and routing the remainder over the dam spillway. Because of the fixed nature of the gate openings at Brandon Road, increased aeration cannot be achieved via gate manipulation.

One alternative for artificial reaeration is turbine venting, includes diffusing oxygen in the turbine flow, aspirating air into the downstream draft tube, and directly injecting compressed air. A 2 to 4 mg/l DO increase could possibly be achieved by using these procedures. The actual amount would depend on prevailing conditions such as saturation deficit, water temperature, and water quality. If a 4 mg/l addition could routinely be achieved by one of these methods, present downstream conditions probably could be maintained. The field study results given in table 3 show that the average DO pickup over the dam was 4.01 mg/l including a low of 2.42 mg/l and a high of 5.06 mg/l. Because of reduced turbine efficiency and direct operating power costs, turbine venting methods should be considered only if a minimum DO increase of 4.0 mg/l can be achieved routinely. Anything less would probably not be acceptable to regulatory agencies since downstream standard violations routinely persist even with the 3.0 to 5.0 mg/l increases being achieved with the flow passing over the dam spillway.

Another alternative often considered for use in increasing the DO at low-head power installations on small streams is the supplementation of DO by either instream aeration or direct injection of Neither of these appears feasible immediately above the pure oxygen. Brandon Road dam. Both need a deep pool to allow diffusion of oxygen into the water as bubbles rise from the bottom. Depths above the dam are much too shallow to provide for the needed residence time. During field sampling for this study, the maximum depth encountered above the dam was 8 feet, with the overall cross-sectional average ranging between 6 and 7 feet. This is in contrast to a spillway height above the upstream bottom of approximately 36 feet as shown by the difference between the top elevation of the Tainter gate spillway of 536.75 and an approximate upstream bottom elevation of 501.0 (figure 3). The pooled area above the dam has filled in with sediments to depths up to 30 feet. This not only reduces residence time for oxygen diffusion, but it also creates a

tremendous source of sediment oxygen demand when disturbed. Any diffused air or pure oxygen probably could not even supply enough oxygen to satisfy the SOD it would create. Also, disturbance of the light-weight, flocculent sediments would increase turbidity greatly for a considerable period of time.

Another alternative that could be considered and evaluated is the concept of side channel aeration that has been devised and developed by the Metropolitan Sanitary District of Greater Chicago (MSD). Macaitis et al. (1984) and Butts (1988) have evaluated such a system, which is referred to as "sidestream elevated pool aeration stations" (SEPA). The concept involves diverting a portion of the instream flow to an off-channel location where it is lifted by energy-efficient, low-head screw pumps to a reservoir. From here, it is allowed to spill back into the main stream channel after being aerated over weirs. The preliminary data being derived from a prototype weir system experiment, in which the Water Quality Section of the State Water Survey is participating, indicate that DO saturation levels of over 90 percent can be achieved by using a three-step weir system with a total water drop of 15 feet. In terms of absolutes, DO concentrations appear to be capable of being raised by as much as 5.4 mg/l during high deficit conditions.

The Brandon Road dam presently is a good aerator. This high efficiency results from the fact that structural design of the flow control spillway incorporates a high dam reaeration coefficient with a high water fall (table 1). Modification of the existing structure to increase aeration appears impractical, and an attempt to do so would probably go unrewarded.

The key element in developing, designing, and implementing management scheme for minimizing downstream deterioration of DO resources in the event of power development at Brandon Road is continuous knowledge of the upstream DO concentrations. The upstream DO concentrations need to be monitored at frequent intervals and the results instantly provided to the plant manager for operational decisions. A "one-shot" data base needs to be developed relative to daily fluctuations in the downstream DO profile within the Dresden Island pool. These data should be collected for at least one season from April 1 through November 30. A statistical relationship could then be developed relating the minimum DO in the pool to that observed upstream of the dam. Other factors such as flow, water weather conditions would be quality, and incorporated into relationship if they were found to have significant influence on DO levels in this reach of the waterway. Once the relationship or model was developed, periodic DO monitoring in the Dresden Island pool should be done to verify the model and to routinely update and make adjustments in it to insure that water quality degradation does not occur.

Although the purpose and scope of this study did not include an evaluation of the feasibility of operating a power plant at Brandon Road by manipulating flows and supplementing or adding DO to the power flow, some limited computations were done with this in mind. Tables 13 and 14 list predicted minimum downstream DOs based on using 90 and 70 percent of Des Plaines River flows of 2545 cfs (95 percent duration) and 3948 cfs (50 percent duration) for power generation. Included in the analyses were 2.0 mg/l and 4.0 mg/l DO additions to the power flow. These examples are

included only to put the overall feasibility of operating a power plant at Brandon Road into better perspective. In reality, an infinite number of combinations exists. A limited extension of these computations could possibly be used to develop probability values analogous to those presented in tables 11 and 12, which were derived for total flow diversion for power generation.

Note, from table 13a, that 90 percent use of the available flow and a 2.0 mg/l DO addition has little possibility of meeting a minimum 5.0 mg/l standard for the 2545 cfs (95 percent flow duration) flow; for the 3948 cfs (50 percent flow duration) condition, prospects improve only slightly. The fact must be kept in mind that only about a 13 to 15 percent chance (figure 8) exists that the above-dam DO ( $C_{\rm A}$ ) will be equal to or greater than 4.0 mg/l.

If the amount of river flow diverted for power use is limited to 70 percent as shown in table 14, prospects improve considerably, especially if a 4.0 mg/l addition to the power flow can be maintained. The flow which was not used for power was routed over the spillway and was reaerated by using the rate-factor determined during this study.

Instead of prescribing a percentage of flow for power use, the above computations could be done on the basis of maintaining a fixed flow over the spillway, such as 500 cfs, and routing the rest through the proposed power plant.

#### CONCLUSIONS

- The Brandon Road dam flow release structure, as presently operated, is 1. an efficient aerator. The Tainter gates, perched on top of a 35.75-foot-high ogee spillway, were found to have an average weir reaeration coefficient of 1.87, a relatively high value when compared to a simple sharp-crested, to the standard of 1.0 assigned free-falling weir or spillway. Aeration at the dam site is further enhanced by the great difference in upstream and downstream water levels; during flat pool conditions the differential is 34 feet. During this study, the average above-dam DO saturation percentage was 40.1, and the average below-dam percentage was 88.7. On one occasion, the DO in the water was increased from 2.54 mg/l to 7.60 mg/l after passing over the spillway.
- 2. The minimum DO standard of 5.0 mg/l for the lower Dresden Island pool is occasionally being violated during warm weather, although Brandon Road dam aeration produces nearly saturated DO levels at the head of the pool. BOD-DO computer model simulations run during this study indicate that a stream flow of approximately 3000 cfs at 20°C would be needed to maintain water quality standards; however, at 28°C a flow of over 4000 cfs would be needed.

- 3. Establishment of hydropower facilities at Brandon Road will create additional stress on downstream DO resources without artificial supplementation of DO at the plant site. Computer model simulations indicate that substandard DOs will occur on about 206 days a year if a hydropower plant is operated without supplementing DO. The spillway Tainter gate design does not provide flexibility in improving DO uptake at the spillway, and even if it did, the present efficiency is so great any increase in DO would be minimal.
- 4. Establishment of a hydropower plant at Brandon Road would possibly be feasible if means were provided for artificially supplementing DO in the water used for power generation. Various alternatives are available for doing this such as turbine venting, instream aeration by mechanical means, and sidestream elevated pool aeration. Cursory computer model simulations indicate that at least a 4.0 mg/l addition of DO will be needed at low flows to prevent additional downstream degradation. Further study is required to evaluate the feasibility of doing this.
- 5. Improvements in Pes Plaines River water quality above the Brandon Road dam would probably have a positive impact on dam aeration efficiency. A small positive correlation was found to exist between dam aeration efficiency and general water quality. This indicates that the cleaner the water the greater the dam aeration rate. Also, a positive correlation was found to exist between water quality and the dissolved oxygen saturation limit. Consequently, if the present moderately polluted water could be upgraded to clean water, dam aeration efficiencies would improve. However, only slight improvements would be realized since the present efficiencies already exceed 90 percent most of time.

TABLES

Table 1. Hydraulic Conditions Existing during Brandon Road Dam Calibration Sampling Runs

	-	]	Pool eleva	ations		Estimated flow
19 86	Number of	Above	Below	Difference	Flow	through head
Date	gates open	(MSL)	(MSL)	(ft.)	cfs	pates (%)
7/09  p.m.	9	538.85	504.73	34.12	7 <del>,</del> 976	10
7/16 a.m.	4	538.37	504.65	33.72	3,250	10
7/16 p.m.	8	538.83	504.61	34.22	7,118	20
7/23 a.m.	9	538.53	504.49	34.04	6,826	10
7/23 p.m.	8	538.68	504.56	34.12	6,625	10
7/29 p.m.	8	538.57	504.54	34.03	6,273	10
8/07 a.m.	6	538.55	504.58	33.97	4,869	10
8/07 p.m.	7	538.55	504.53	34.02	5,553	10
8/14 a.m.	6	538.65	504.59	34.06	5,121	10
8/14 p.m.	7	538.62	504.50	34.12	5,734	10
8/20 a.m.	6	538.53	504.57	33.96	4,822	10
8/27 a.m.	8	538.57	504.60	33.97	6,288	10
9/05 a.m.	5	538.63	504.56	34.07	4,369	10
9/11 p.m.	7	538.59	504.56	34.03	5,650	10
9/17 a.m.	6	538.35	504.65	33.70	4,416	30
9/17 p.m.	5	538.41	504.52	33.89	3,937	10
9/24 a.m.	13	538.45	504.51	33.94	9,051	40
9/24 p.m.	18	538.59	504.52	34.07	13,230	30

Table 2. Water Quality Factor Results Obtained by Using the Calibrated Weir Box (b = 1.038) at Brandon Road

	Exp	erimenta	al DO								Water
	satu	ration :	results		Weir-b	ox DO		Temp.	(°C)	Deficit	quality
1986	Temp	DO	% of book	Above	weir	Below	weir	Above	Below	ratio	factor
Date	(°C)	mg/1	value	(mg/1)	% sat	(mg/l)	% sat	weir	weir	r	a
7/09 p.m.	28.8	7.47	100.1	3.87	49.1	6.08	77.1	25.9	25.9	2.20	1.03
7/16 a.m.	26.1	7.89	100.5	3.43	43.5	6.05	76.6	25.9	25.8	2.38	1.18
7/16  p.m.	29.6	8.17	111.1	2.61	32.6	6.14	77.0	25.1	25.3	2.31	1.15
7/23 a.m.	27.9	7.80	102.8	2.33	29.8	5.72	65.4	26.3	26.3	2.46	0.98
7/23  p.m.	25.7	8.15	103.0	3.69	47.3	6.26	80.2	26.4	26.4	2.44	1.02
7/29  p.m.	25.2	8.04	100.6	3.41	44.3	5.92	76.5	27.2	26.9	2.32	1.09
8/07 a.m.	23.7	8.68	105.5	2.74	33.9	6.18	76.5	24.6	24.6	2.46	1.02
8/07  p.m.	24.1	8.51	104.3	2.94	37.1	6.12	76.7	25.6	25.3	2.43	1.15
8/14 a.m.	24.9	8.17	101.7	6.73	84.9	7.43	93.7	25.6	25.6	2.11	1.15
8/14  p.m.	24.5	8.24	101.8	4.97	62.4	6.81	85.2	25.4	25.2	2.37	0.93
8/20 a.m.	26.2	7.59	96.8	4.14	52.8	6.14	78.5	26.2	26.3	2.40	1.18
8/27 a.m.	22.3	8.50	100.6	3.30	40.9	5.94	73.6	24.7	24.7	2.22	1.24
9/05 a.m.	25.2	8.00	100.1	3.54	45.0	6.01	76.5	26.0	26.1	2.34	1.06
9/11 p.m.	20.3	9.23	104.9	4.21	50.4	6.71	80.2	22.9	22.8	2.20	1.16
9/17 a.m.	18.2	10.14	110.4	3.90	45.3	6.87	79.7	21.4	21.3	2.12	1.19
9/17 p.m.	19.5	8.35	93.4	3.15	36.5	5.94	68.6	21.3	21.1	2.29	1.09
9/24 a.m.	21.5	9.91	116.4	3.60	42.7	7.13	84.7	22.4	22.5	2.37	1.14
9/24 p.m.	21.7	9.36	109.4	4.04	48.0	6.87	81.4	22.5	22.4	2.19	1.00
									A	verage	1.10

Note: Runs were made at water drop heights of approximately 1.3 meters, receiving water depths of approximately 0.5 meters, and flow rates of approximately 1.77 liters per sec. The %-of-book values are computed by using equation 6 DO saturation values which have been corrected for altitude by multiplying by 0.981.

Table 3. Brandon Road Dam Calibration Results

	Depth averaged dissolved oxygen			Depth	Dam			
	Concentrat	ion $(mg/l)$	) % book	sat.	tempera	ture (°C)	Deficit	aeration
1986	Above	Below	Above	Below	Above	Below	ratio	factor
Date	dam	dam	dam	dam	dam	dam	r	b
7/09 p.m.	$\overline{3.64}$	$\overline{7.25}$	$4\overline{5.4}$	99.0	25.0	<del>24.</del> 8	5.43	2.39
7/16 a.m.	4.41	6.83	55.1	85.5	25.1	25.2	3.04	0.96
7/16  p.m.	2.54	7.60	31.7	95.1	25.1	25.2	4.97	1.96
7/23 a.m.	2.48	7.34	31.3	92.6	25.6	25.6	4.79	1.70
7/23  p.m.	3.08	7.15	39.3	91.0	26.2	26.1	5.32	1.97
7/29 p.m.	3.15	6.87	41.0	89.3	27.3	27.2	5.26	2.06
8/07 a.m.	2.39	7.08	29.5	89.0	24.5	25.4	4.66	1.59
8/07 p.m.	2.58	7.12	32.5	88.1	25.5	24.6	4.36	1.53
8/14 a.m.	3.38	7.05	42.5	88.4	25.4	25.3	4.46	2.00
8/14 p.m.	3.58	7.11	44.8	85.0	25.2	25.2	4.46	1.62
8/20 a.m.	3.25	7.01	41.0	88.2	25.6	25.5	4.83	1.78
8/27 a.m.	3.14	7.32	38.9	90.7	24.6	24.7	4.76	2.00
9/05 a.m.	3.42	6.99	43.1	86.9	25.6	25.6	4.31	1.62
9/11 p.m.	3.57	7.74	42.4	91.6	22.5	22.3	4.67	2.05
9/17 a.m.	3.83	8.64	44.4	100.0	21.3	21.4	4.91	2.32
9/17 p.m.	2.76	6.89	31.8	79.4	20.9	21.0	4.43	1.76
9/24 a.m.	5.28	8.43	62.2	99.5	22.1	22.2	3.36	1.14
9/24 p.m.	3.38	8.05	39.7	94.9	21.9	22.1	4.81	2.13
						1	Average	1.81
						]	Median	1.87

Note: The %-of-book values are computed by using equation 6 DO saturation values which have been corrected for altitude by multiplying by 0.981.

Table 4. Regression Coefficients Associated with Equations 7 and 8

a. DO and  $L_{\text{a}}$  Values for Equation 7

	<u>DO</u> ( <u>mg</u>	$\begin{array}{ccc} & & \text{Ultimate CBOD} \\ \underline{\text{DO}} & & \underline{\text{Mg/l}} & & \underline{\text{L}_{\text{ac}}} & \text{(lbs} \underline{\text{/day}}) \end{array}$			Ultimate NBOD $L_{an}$ (lbs/day)		
Location	A (10-4)	В	A	В	А	В	
Lockport	_	_	25.57	5818	86.97	74617	
Des Plaines	-6.8	11.72	16.01	6272	34.82	1249	
DuPage	-45.5	8.64	30.17	605	37.03	148	
Kankakee	-1.5	8.80	10.22	25384	6.75	26198	
Fox	-7.5	11.39	25.92	22228	43.03	2431	
Vermilion	-6.7	9.31	18.65	567	12.59	1450	

b. Main Stem values for Equation 8

		$K_c$ (1	/day)			$K_n$ (	l/day	
Inclusive							•	
MP	A	В	С	D	A	В	С	D
$2\overline{91.0}$								
	-2.899	0.665	0.128	6.331	-3.443	1.436	0	5.422
288.7								
0.70	-6.503	1.988	0.158	13.754	-2.352	1.425	-0.158	2.357
278.0	F 000	1 000	0 104	11 505	2 520	1 260	0 010	c 1c2
270 6	-5.823	1.978	0.124	11.507	-3.538	1.360	0.013	6.163
270.6	-4.291	1.145	0.150	9.158	-6.054	2.527	0	10.657
231.0	- <b>4.</b> 291	1.113	0.130	9.130	-0.034	2.527	U	10.037
231.0	-4.351	1.179	0.108	9.403	-6.054	2.527	0	10.657
222.6	1,001	_,_,	0.120	7.100	0.001	_,_,	· ·	201007
	*	*	*	*	-4.287	2.548	-0.155	4.934
179.0								
	-5.744	1.545	0.117	12.914	-1.631	1.289	-0.115	0.218
167.0								
	-5.744	1.545	0.117	12.914	-1.352	-0.631	0.060	0.983
157.0								

<sup>\*</sup> The regression coefficients were nonsensical for this reach

Table 5. Summary of DO Concentrations for a Point Immediately below the Brandon Road Dam for BOD-DO Model Simulations Run at Various Temperatures and Flow Durations

Below dam DO concentrations (mg/l),  $C_{\rm B}$ , at Flow Corps of Engineers river mile 286.17 for river water temperatures (°C) of duration 14 26 28 12 16 18 20 22 24 응 7.897.647.417.196.98 6.776.58 6.38 6.20 99.8 99 7.89 7.64 7.41 7.19 6.98 6.77 6.58 6.38 6.20 6.58 6.38 6.20 98 7.89 7.64 7.41 7.19 6.98 6.77 97 7.92 7.65 7.41 7.19 6.98 6.77 6.58 6.38 6.20 6.58 6.20 96 7.94 7.67 7.42 7.19 6.98 6.77 6.38 95 7.97 7.71 7.45 7.20 6.98 6.77 6.58 6.38 6.20 90 8.03 7.77 7.52 7.28 7.04 6.82 6.60 6.40 6.20 85 8.07 7.80 7.55 7.31 7.08 6.86 6.64 6.44 6.23 7.10 6.46 80 8.08 7.82 7.57 7.33 6.88 6.67 6.26 75 7.84 7.59 6.90 6.68 6.48 6.28 8.10 7.35 7.12 70 8.11 7.85 7.60 7.36 7.13 6.91 6.70 6.50 6.30 65 8.13 7.86 7.61 7.37 7.14 6.92 6.71 6.51 6.31 60 8.14 7.88 7.63 7.39 7.16 6.94 6.73 6.52 6.32 55 7.89 7.64 7.40 6.95 6.74 6.53 6.33 8.15 7.17 50 6.75 8.16 7.90 7.65 7.41 7.18 6.96 6.55 6.34 45 8.18 7.92 7.67 7.43 7.20 6.97 6.76 6.56 6.36 40 7.68 7.44 7.21 6.77 6.57 8.19 7.93 6.99 6.37 35 8.21 7.95 7.69 7.45 7.22 7.00 6.79 6.58 6.38 30 8.22 7.96 7.71 7.47 7.24 7.02 6.80 6.60 6.40 25 8.24 7.98 7.73 7.49 7.25 7.03 6.82 6.61 6.41 20 8.26 7.99 7.74 7.50 7.27 7.04 6.83 6.63 6.42 17 7.74 7.50 7.27 7.05 6.84 6.63 6.43 8.26 8.00 15 8.26 8.00 7.74 7.50 7.27 7.05 6.84 6.63 6.43 14 8.26 8.00 7.74 7.50 7.27 7.05 6.84 6.63 6.43 13 8.25 7.99 7.74 7.50 7.27 7.05 6.84 6.63 6.43 12 8.25 6.83 6.63 6.43 7.99 7.73 7.49 7.26 7.04 11 8.24 7.98 7.73 7.49 7.26 7.04 6.83 6.42 6.62 10 8.23 7.97 7.72 7.48 7.25 7.03 6.82 6.62 6.42 9 8.22 7.96 7.71 7.47 7.24 7.02 6.81 6.61 6.41 8 8.20 7.94 7.69 7.45 7.23 7.01 6.80 6.60 6.40

Table 6. Summary of Minimum DO Concentrations in the Dresden Island Pool Derived for BOD-DO Model Simulations Run at Various Temperatures and Flow Durations

Minimum DO concentrations (mg/l),  $C_m$ , in the Dresden Island pool for

Flow			th			l pool fo			
duration					eratures	_			
(%)	12	14		18	20	22	24	26	28
99.8	$\frac{12}{4.57}$	3.85	3.10	$\frac{10}{2.31}$	$\frac{20}{1.69}$	$\frac{22}{1.53}$	0.75	0	0
99	5.06	4.43	3.77	3.07	2.33	1.74	1.35	0.60	0
98	5.78	5.28	4.76	4.23	3.68	3.11	2.75	1.90	1.53
97	5.95	5.45	5.06	4.43	3.91	3.36	2.78	2.18	1.82
96	5.96	5.47	4.98	4.48	3.97	3.44	2.89	2.31	1.94
95	6.19	5.70	5.21	4.71	4.20	3.68	3.14	2.57	1.96
90	6.62	6.17	6.02	5.24	4.79	4.34	3.95	3.50	2.99
85	6.81	6.37	5.94	5.50	5.12	4.65	4.21	3.78	3.34
80	6.93	6.50	6.08	5.70	5.24	4.83	4.41	3.98	3.55
75	7.01	6.60	6.18	5.77	5.37	4.96	4.55	4.13	3.71
70	7.11	6.71	6.30	5.90	5.51	5.11	4.71	4.31	3.90
65	7.13	6.73	6.33	5.94	5.55	5.16	4.77	4.37	3.97
60	7.23	6.83	6.44	6.06	5.67	5.29	4.90	4.51	4.12
55	7.28	6.89	6.50	6.12	5.74	5.37	4.99	4.60	4.22
50	7.31	6.92	6.54	6.16	5.78	5.41	5.03	4.65	4.26
45	7.33	6.95	6.57	6.19	5.82	5.44	5.07	4.69	4.31
40	7.36	6.98	6.61	6.23	5.86	5.49	5.12	4.75	4.37
35	7.41	7.04	6.67	6.30	5.93	5.57	5.21	4.84	4.47
30	7.47	7.10	6.74	6.38	6.02	5.67	5.31	4.95	4.59
25	7.52	7.16	6.80	6.45	6.10	5.75	5.40	5.05	4.70
20	7.59	7.24	6.90	6.56	6.22	5.88	5.55	5.21	4.87
17	7.61	7.26	6.92	6.59	6.25	5.92	5.59	5.26	4.93
15	7.62	7.28	6.95	6.62	6.29	5.97	5.64	5.32	4.99
14	7.63	7.29	6.96	6.63	6.31	5.99	5.67	5.34	5.02
13	7.65	7.32	6.99	6.67	6.35	6.03	5.72	5.40	5.08
12	7.67	7.34	7.01	6.69	6.38	6.07	5.76	5.45	5.13
11	7.68	7.35	7.04	6.72	6.42	6.11	5.81	5.50	5.19
10	7.68	7.36	7.04	6.73	6.43	6.13	5.83	5.53	5.22
9	7.68	7.37	7.06	6.75	6.45	6.16	5.86	5.57	5.27
8	7.66	7.37	7.07	6.77	6.47	6.18	5.90	5.61	5.32

Table 7. Summary of Results of Stepwise Regression Analyses Relating the Deficit Ratio (r), the British Dam Aeration Coefficient (b), and the Below-dam DO Percent Saturation ( $P_0$ ) to Appendix K data.

			Regression	Standard	Multiple	Explained
Dependent	Step		equation	error of	correlation	
variable	No.	Independent variable added			coefficient. R	
r	1	Above-dam DO (% sat.)	-0.0176	0.512	0.573	0.327
	2	Total head (ft.)	-1.8631	0.485	0.658	0.433
	3	Total discharge (cfs)	0.0030	0.495	0.670	0.449
	4	Head gate discharge (cfs)	0.0015	0.461	0.746	0.557
	5	Number of gates open	-2.2541.	0.459	0.771	0.594
	6	Suspended solids (mg/l)	-0.0520	0.426	0.824	0.679
	7	Above-dam algae (No./ml)	0.0019	0.422	0.845	0.714
	8	MBAS (mg/l)	29.6048	0.411	0.870	0.756
	9	Water quality factor, a	2.8481	0.404	0.889	0.790
	10	Water temperature (°C)	-0.1360	0.382	0.914	0.836
	11	COD (mg/l)	0.0175	0.406	0.917	0.841
	12	Below-dam algae (No./ml)	-0.0001	0.440	0.919	0.844
b	1	Above-dam DO (% sat.)	-0.0080	0.357	0.352	0.124
	2	Total discharge (cfs)	0.0023	0.349	0.465	0.216
	3	Number of gates open	-1.6826	0.332	0.582	0.338
	4	Water temperature (°C)	-0.1673	0.320	0.654	0.427
	5	Suspended solids (mg/l)	-0.0314	0.304	0.724	0.524
	6	Total head (ft.)	-1.6757	0.300	0.756	0.575
	7	Above-dam algae (No./ml)	0.0012	0.306	0.772	0.596
	8	Water quality factor, a	2.7140	0.306	0.798	0.637
	9	MBAS (mg/l)	20.8017	0.308	0.821	0.674
	10	Head gate discharge (cfs)	0.0001	0.286	0.868	0.753
	11	COD (mg/1)	0.0320	0.276	0.897	0.804
	12	Below-dam algae (No./ml)	-0.0003	0.283	0.910	0.827
$P_{O}$	1	Head gate discharge (cfs)	-0.0149	3.769	0.658	0.432
	2	Below-dam algae (No./ml)	-0.0029	3.717	0.695	0.483
	3	Suspended solids (mg/l)	-0.3308	3.756	0.712	0.507
	4	Water quality factor, a	18.4839	3.792	0.730	0.533
	5	Water temperature (°C)	0.2460	3.839	0.747	0.558
	6	MBAS (mg/l)	98.5456	3.975	0.752	0.566
	7	Above-dam algae (No./ml)	0.0035	4.156	0.754	0.569
	8	COD (mg/l)	0.2653	4.373	0.755	0.570
	9	Number of gates open	-10.2226	4.628	0.756	0.572
	10	Total discharge (cfs)	0.0121	4.677	0.786	0.618
	11	Total head (ft.)	-11.8386	4.916	0.799	0.638
	12	Above-dam DO (% sat.)	-0.0392	5.373	0.800	0.640

Note: The "Regression equation coefficient" value presented in the table for each parameter is the coefficient value for that parameter at the point when the parameter first enters into the stepwise regression equation. Each new successive parameter entry will result in slight modifications of the absolute values presented here, but the sign will not change.

Table 8. Summary of Results of Stepwise Regression Analyses Relating the  $\mathcal B$ -factor to Selected Independent Variable Data Listed in Appendix K

		Regression	Standard	Multiple	Explained
Step		equation	error of	correlation	variation
No.	Independent variable added	coefficient	estimate	coefficient. R	R <sup>2</sup>
1	Suspended solids (mg/l)	0.00162	0.044	0.615	0.378
2	Below-dam algae (No./ml)	-0.00008"	0.042	0.712	0.508
3	Total discharge (cfs)	0.00001	0.041	0.729	0.531
4	Water quality factor, a	0.11422	0.041	0.751	0.564
5	Water temperature (°C)	-0.00273	0.042	0.757	0.573
6	Above-dam DO (% sat.)	-0.00067	0.044	0.759	0.576
7	Above-dam algae (No./ml)	-0.00002	0.046	0.760	0.578
8	COD (mg/l)	0.00025	0.048	0.760	0.578
9	MBAS (mg/l)	0.02958	0.051	0.760	0.578

Note: The "Regression equation coefficient" value presented in the table for each parameter is the coefficient value for that parameter at the point when the parameter first enters into the stepwise regression equation. Each new successive parameter entry will result in slight modifications of the absolute values presented here, but the sign will not change.

Table 9. Minimum DOs Required below the Brandon Road Dam to Maintain a Minimum 5.0 mg/l Concentration in the Dresden Island Pool (Concluded on next page)

Minimum DO concentrations (mg/l) required immediately Flow below the Brandon Road dam to maintain a 5.0 mq/1minimum standard downstream for water temperatures (°C) of duration 18 10 14 19 20 응 11 12 13 15 16 17 8.57 8.82 9.109.38 9.70 10.02 10.27 10.51 99.8 7.86 8.09 8.32 99 7.49 7.66 7.83 8.03 8.22 8.45 8.67 8.93 9.19 9.49 9.79 6.98 7.10 7.23 7.36 7.51 7.65 7.81 7.97 8.15 8.33 98 6.86 6.95 7.08 7.20 7.28 7.35 7.56 7.77 7.93 8.09 97 6.70 6.83 7.58 7.08 7.20 7.44 7.72 7.88 8.03 96 6.70 6.83 6.96 7.32 95 6.88 7.00 7.12 7.24 7.37 7.49 7.64 7.79 6.50 6.63 6.75 7.26 7.04 7.15 7.25 90 6.16 6.26 6.36 6.47 6.57 7.03 7.48 85 6.00 6.10 6.19 6.29 6.39 6.49 6.59 6.70 6.81 6.89 6.96 5.90 5.99 6.08 6.18 6.28 6.38 6.55 6.62 6.74 6.86 80 6.47 75 5.83 5.92 6.01 6.10 6.19 6.29 6.38 6.48 6.57 6.66 6.75 70 5.83 6.27 6.36 6.53 5.74 5.91 6.00 6.08 6.18 6.44 6.61 65 5.82 5.99 6.16 6.24 6.33 6.41 6.50 6.58 5.73 5.91 6.07 60 5.65 5.73 5.81 5.90 5.98 6.07 6.15 6.23 6.31 6.40 6.48 55 5.62 5.70 5.77 5.85 5.93 6.02 6.10 6.18 6.25 6.34 6.42 5.99 50 5.57 5.66 5.74 5.83 5.91 6.06 6.14 6.22 6.31 6.39 45 5.66 5.74 5.82 5.89 5.97 6.05 6.13 6.29 6.37 5.57 6.21 40 5.56 5.64 5.72 5.80 5.87 5.95 6.02 6.10 6.18 6.26 6.34 5.61 5.76 5.90 5.96 6.04 6.20 6.27 35 5.54 5.68 5.83 6.12 30 5.50 5.57 5.63 5.70 5.77 5.84 5.91 5.98 6.05 6.13 6.20 25 5.46 5.53 5.59 5.66 5.73 5.80 5.87 5.94 6.00 6.07 6.13 20 5.43 5.49 5.54 5.60 5.65 5.71 5.77 5.83 5.89 5.96 6.02 17 5.70 5.39 5.45 5.51 5.58 5.64 5.75 5.81 5.86 5.93 5.99 15 5.39 5.45 5.50 5.56 5.62 5.67 5.71 5.77 5.83 5.89 5.95 14 5.37 5.43 5.49 5.55 5.61 5.66 5.70 5.76 5.82 5.88 5.93 13 5.36 5.41 5.46 5.51 5.56 5.62 5.67 5.72 5.77 5.83 5.88 5.79 12 5.34 5.39 5.44 5.49 5.54 5.59 5.64 5.69 5.74 5.84 5.32 5.37 5.57 5.71 5.76 11 5.42 5.47 5.52 5.61 5.66 5.80 10 5.37 5.41 5.46 5.50 5.55 5.60 5.65 5.69 5.74 5.32 5.78 9 5.36 5.31 5.40 5.44 5.48 5.53 5.57 5.62 5.66 5.71 5.75 8 5.53 5.31 5.36 5.40 5.43 5.46 5.50 5.58 5.62 5.67 5.72

Table 9. (Concluded)

Minimum DO concentrations (mg/l) required immediately Flow below the Brandon Road dam to maintain a 5.0 mg/l minimum standard downstream for water temperatures (°C) duration of 21 30 왕 22 23 24 25 26 27 28 29 11.7010.50 10.58 10.84 $11.\overline{1}9$ 11.54 11.88 11.7911.52 99.8 11.61 10.02 99 10.24 10.50 11.44 11.70 10.37 10.84 11.17 11.97 12.23 8.93 9.79 10.03 98 8.53 8.73 8.83 9.30 9.67 9.91 10.15 97 8.28 8.46 8.68 8.90 9.13 9.36 9.47 9.58 9.69 9.80 96 8.21 8.38 8.58 8.78 9.00 9.21 9.33 9.45 9.57 9.69 95 7.96 8.12 8.32 8.51 8.72 8.93 9.18 9.42 9.67 9.91 7.49 7.58 7.67 8.46 90 7.37 7.81 7.95 8.12 8.29 8.63 85 7.09 7.21 7.33 7.44 7.57 7.82 7.95 8.08 7.69 8.21 80 6.95 7.05 7.16 7.27 7.39 7.50 7.63 7.75 7.88 8.00 75 6.94 7.13 7.25 7.49 7.72 6.85 7.04 7.37 7.60 7.83 70 6.71 6.80 6.90 6.99 7.10 7.20 7.31 7.42 7.53 7.64 65 6.67 6.76 6.85 6.94 7.05 7.15 7.26 7.36 7.47 7.57 60 6.57 6.65 6.74 6.83 6.92 7.01 7.12 7.22 7.33 7.43 7.22 55 6.50 6.58 6.75 7.03 7.12 7.31 6.67 6.84 6.93 50 6.55 6.72 7.00 7.19 6.47 6.64 6.81 6.90 7.09 7.28 45 6.45 6.53 6.61 6.69 6.78 6.87 6.97 7.06 7.16 7.25 6.50 6.92 40 6.42 6.58 6.65 6.74 6.82 7.01 7.11 7.20 35 6.35 6.42 6.50 6.58 6.66 6.74 6.83 6.92 7.01 7.10 30 6.27 6.34 6.42 6.49 6.57 6.65 6.73 6.81 6.89 6.97 25 6.20 6.27 6.35 6.42 6.49 6.64 6.79 6.56 6.71 6.86 6.08 20 6.14 6.21 6.27 6.35 6.42 6.49 6.55 6.62 6.68 17 6.05 6.11 6.18 6.24 6.44 6.31 6.37 6.50 6.57 6.63 15 6.01 6.06 6.13 6.19 6.25 6.31 6.38 6.44 6.51 6.57 14 5.99 6.04 6.10 6.16 6.23 6.29 6.35 6.41 6.47 6.53 13 5.94 6.00 6.06 6.11 6.29 6.17 6.23 6.35 6.41 6.47 12 5.90 5.95 6.01 6.06 6.12 6.18 6.24 6.30 6.36 6.42 11 5.86 5.91 5.96 6.01 6.07 6.18 6.12 6.23 6.29 6.34 10 5.83 5.87 5.93 5.98 6.03 6.08 6.14 6.20 6.26 6.32 9 5.79 5.83 5.89 5.94 5.99 6.09 6.03 6.14 6.20 6.25 8 5.76 5.80 5.84 5.88 5.93 6.03 6.08 6.13 5.98 6.18

Table 10. Dissolved Oxygen Data Recorded Immediately above the Brandon Road Dam Which Were Used to Generate the Probability Function, P2

					DO-values m high to	
		Temp	DO		All	1986
Date	Reference	_(°C)_	(mq/1)	Rank	values	values
8/23/77	Polls et al. (1985)	-	4.60	1	0.40	2.39
9/02/77	11	-	3.80	2	0.60	2.48
9/12/77	11	-	1.40	3	0.90	2.54
9/22/77	11	-	3.50	4	1.30	2.58
10/03/77	***	-	1.90	5	1.40	2.76
10/14/77	11	-	3.20	6	1.46	3.08
9/12/78	Butts and Evans (1980)	27.4	3.18	7	1.50	3.14
10/12/78		19.6	3.40	8	1.60	3.15
8/15/79		24.8	0.60	9	1.90	3.25
8/29/79		25.6	1.60	10	1.90	3.38
9/11/79		26.0	1.46	11	2.00	3.38
6/03/82	Butts et al. (1987)	19.5	2.00	12	2.00	3.42
6/08/82		23.0	2.90	13	2.39	3.57
6/15/82		24.0	1.30	14	2.48	3.58
6/22/82		20.5	1.90	15	2.54	3.64
6/30/82		22.0	1.50	16	2.58	3.83
7/08/82		26.5	2.80	17	2.76	4.41
7/14/82		25.5	0.90	18	2.80	5.28
7/20/82		27.0	0.40	19	2.90	
7/27/82		26.0	3.60	20	3.08	
8/03/82		28.0	3.10	21	3.10	
8/10/82		24.0	2.00	22	3.10	
8/17/82		26.0	3.10	23	3.14	
8/30/82	•	24.0	3.20	24	3.15	
9/10/82		25.5	3.60	25	3.18	
9/24/82		18.9	5.75	26	3.20	
10/01/82		21.4	5.50	27	3.20	
9/19/83	Polls et al. (1985)		4.40	28	3.25	
9/29/83		-	3.70	29	3.38	
10/03/83		-	4.20	30	3.38	
7/09/86	This study	27.3	3.15	31	3.40	
7/16/86		26.2	3.08	32	3.42	
7/17/86		25.6	2.48	33	3.50	
7/23/86		25.1	2.54	34	3.57	
7/24/86	11	25.1	4.41	35	3.58	
7/29/86		25.0	3.64	36	3.60	
8/07/86		25.4	2.39	37	3.60	
8/08/86	11	25.5	2.58	38	3.64	
8/14/86	11	25.4	3.38	39	3.70	
8/15/86		25.2	3.58	40	3.80	
8/20/86		25.6	3.25	41	3.83	
8/27/86		24.6	3.14	42	4.20	
9/05/86		25.6	3.42	43	4.40	
9/11/86		22.5	3.57	44	4.41	
9/17/86		21.3	3.83	45	4.60	
9/18/86		20.9	2.76	46	5.28	
9/24/86		22.1	5.28	47	5.50	
9/25/86		21.9	3.38	48	5.75	

Table 11. Probability of the Occurrence of Specified Flows, Temperatures, and 1977 through 1986 Above-Dam DOs  $(C_A)$  and Their Combined Effects on Days of Operation (Concluded on next page)

Probability of occurrence of above-dam DOs (P3) which are equal to or less than those reauired to maintain a 5.0 mg/l minimum standard (tab]e 9) for temperatures (°C) of Brandon Road flow 10-11 11-12 12-13 13-14 14-15 15-16 16-17 17-18 18-19 19-20 20-21 21-22 22-23 Rate Duration Probability 9-10 .0239 P2 = .0116.0280 .0225 .0478 .0171 .0239 .0437 .0506 .0772 .0328 .0273 .0396 .0458 (cfs) (왕) Ρ1  $.0\overline{02}$ 1.000  $1.000 \ 1.000 \ 1.000 \ 1.000 \ 1.000 \ 1.000 \ 1.000 \ 1.000$ 99.8 1.000 1.000 1.000 1854 1.000 1.0001.000 1.000 1.000 1.000 1.000 1.000 1.000 2094 .01 1.000 1.000 1.000 1.000 1.000 1.000 99 1.000 1.000 1.000 1.000 1.000 1.000 1.000 1.000 1.000 1.000 2252 1.000 1.000 1.000 98 .01 1.000 1.000 1.000 1.000 1.000 1.000 1.000 2369 97 .01 1.000 1.000 1.000 1.000 1.000 1.000 1.000 1.000 1.000 1.000 1.000 1.000 1.000 2449 96 .01 1.000 1.000 1.000 1.000 1.000 1.000 1.000 1.000 1.000 1.000 1.000 1.000 1.000 2545 95 .05 1.000 1.000 1.000 1.000 1.000 1.000 1.000 1.000 1.000 1.000 1.000 1.000 1.000 2838 90 .05 1.000 1.000 1.000 1.000 1.000 1.000 3050 1.000 1.000 1.000 1.000 1.000 1.000 1.000 1.000 1.000 1.000 85 .05 .998 1.000 1.000 .995 1.000 1.000 1.000 1.000 1.000 1.000 1.000 .998 .999 1.000 1.000 1.000 3244 80 .05 1.000 1.000 1.000 1.000 1.000 1.000 1.000 3355 .992 .996 .999 1.000 75 .05 1.000 1.000 3521 .992 .999 .999 1.000 1.000 1.000 1.000 1.000 1.000 1.000 .983 .996 1.000 70 .05 .982 .991 .996 .998 1.000 1.000 1.000 1.000 1.000 1.000 1.000 3620 65 .05 .999 1.000 .978 .984 3764 60 .05 .991 .995 .998 .999 1.000 1.000 1.000 1.000 1.000 1.000 1.000 3881 55 .05 .975 .982 .988 .993 .996 .999 1.000 1.000 1.000 1.000 1.000 1.000 1.000 .970 .978 3948 50 .05 .986 .992 .996 .998 .999 1.000 1.000 1.000 1.000 1.000 1.000 .970 .978 4044 45 .05 .986 .991 .995 .998 .999 1.000 1.000 1.000 1.000 1.000 1.000 .999 1.000 1.000 1.000 1.000 1.000 1.000 4151 .976 .984 40 .05 .969 .990 .994 .997 4316 .968 .975 .987 .992 .995 35 .05 .980 .999 1.000 1.000 1.000 1.000 1.000 1.000 .997 4522 .971 .977 30 .05 .964 .983 .988 .993 .996 .998 1.000 1.000 1.000 1.000 1.000.1.000 .973 .997 .999 1.000 1.000 1.000 1.000 4744 25 .05 .959 .967 .978 .985 .990 .994 .998 5114 .957 .964 .968 .974 .978 .984 20. .05 .992 .995 .998 .999 .999 1.000 1.000 .988 5309 .954 .972 .977 17 .03 .960 .965 .983 .986 .991 .993 .997 .998 .999 1.000 1.000 5458 15 .954 .960 .964 .969 .975 .980 .984 .988 .995 .999 .02 .992 .997 .999 1.000 5551 14 .953 .958 .963 .968 .974 .978 .986 .991 .994 .01 .980 .996 .998 .999 1.000 5734 13 .01 .952 .956 .959 .965 .969 .976 .978 .984 .987 .992 .994 .997 .999 .998 5931 12 .01 .950 .954 .958 .963 .968 .972 .977 .981 .986 .989 .999 .992 .995 .997 6167 11 .01 .949 .952 .957 .960 .966 .970 .975 .979 .984 .987 .990 .993 .996 .997 6395 .952 .956 .977 .986 10 .01 .949 .960 .964 .969 .973 .981 .989 .992 .994 .996 6715 9 .01 .948 .951 .955 .959 .970 .963 .968 .975 .978 .982 .987 .990 .993 .995 7072 8 .01 .948 .951 .955 .958 .960 .964 .968 .971 .976 .980 .985 .991 .993 .987

4

#### Table 11. (Concluded)

Probability of occurrence of above-dam DOs (P3) which are equal to or less than those required to maintain a 5.0 mg/l

			are equar								NO. OI
	Brandon Road			um standa:						Combined	shut-
Rate	Duration	Probability	23-24	24-25	25-26	26-27	27-28	28-29	>29	probability	down
(cfs)	(%)	P1	P2= .0553	.0455	.0485	.0669	.0485	.0711	.0908	(P1)(P2)(P3)	days*
1854	99.8	.002	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.001837	0.448
2094	99	.01	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.009184	2.241
2252	98	.01	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.009184	2.241
2369	97	.01	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.009184	2.241
2449	96	.01	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.009184	2.241
2545	95	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.009184	2.241
2338	90	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045920	11.204
3050	85	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045920	11.204
3244	80	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045913	11.203
3355	75	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045909	11.202
3521	70	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045892	11.198
3620	65	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045890	11.197
3764	60	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045867	11.192
3881	55	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045855	11.189
3948	50	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045840	11.185
4044	45	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045838	11.184
4151	40	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045829	11.182
4316	35	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045808	11.177
4522	30	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045779	11.170
4744	25	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045729	11.157
5114	20	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045672	11.144
5309	17	.03	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.027384	6.682
5458	15	.02	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.018242	4.451
5551	14	.01	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.009115	2.224
5734	13	.01	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.009104	2.221
5931	12	.01	.999	1.000	1.000	1.000	1.000	1.000	1.000	.009094	2.219
6167	11	.01	.998	.999	1.000	1.000	1.000	1.000	1.000	.009084	2.216
6395	10	.01	.998	.999	.999	1.000	1.000	1.000	1.000	.009077	2.215
6715	9	.01	.997	.998	.999	.999	1.000	1.000	1.000	.009065	2.212
7072	8	.01	.994	.996	.998	.999	.999	1.000	1.000	.009051	2.208

Total Days 206.089

No. of

<sup>\*</sup> Number of days of shutdown required in the 244 day period between April 1 and November 30 of any given year to maintain a downstream DO of 5 mg/l.

Table 12. Probability of the Occurrence of Specified Flows, Temperatures, and 1986 Above-Dam DOs  $(C_A)$  and Their Combined Effects on Days of Operation (Concluded on next page)

					Probabi	lity of	occurr	ence of	above-	dam DOs	<i>i</i> (P3)	which	are ed	qual to	or le	ess	
_	Bran	don Road f	Elow	than those	require	d to ma	intain	a 5.0 m	g/l min	imum st	andard	(tabl	e 9) f	or ten	nperatu	ıres (°	C) of
	Rate	Duration.	Probabil	ity 9-10	10-11	11-12	12-13	13-14	14-15	15-16	16-17	17-18	18-19	19-20	20-21	21-22	22-23
_	(cfs)	(왕)	<u>P1</u>	P2=.0116	.0280	.0225	.0171	.0239	.0239	.0437	.0506	.0478	.0772	.0328	.0273	.0396	.0458
	1854	99.8	.002	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000
	2094	99	.01	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000		1.000	1.000	1.000	1.000
	2252	98	.01	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000
	2369	97	.01	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000
	2449	96	.01	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000
	2545	95	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000
	2838	90	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000
	3050	85	.05	.998	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000
	3244	80	.05	.995	.998	.999	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000
	3355	75	.05	.992	.996	.999	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000
	3521	70	.05	.983	.992	.996	.999	.999	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000
	3620	65	.05	.982	.991	.996	.998	.999	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000
	3764	60	.05	.978	.984	.991	.995	.998	.999	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000
4	3881	55	.05	.979	.982	.988	.993	.996	.999	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000
w	3948	50	.05	.974	.978	.986	.992	.996	.998	.999	1.000	1.000	1.000	1.000	1.000	1.000	1.000
	4044	45	.05	.974	.978	.986	.991	.995	.998	.999	1.000	1.000	1.000	1.000	1.000	1.000	1.000
	4151	40	.05	.973	.976	.984	.990	.994	.997	.999	1.000	1.000			1.000	1.000	1.000
	4316	35	.05	.973	.977	.980	.987	.992	.995	.997		1.000		1.000		1.000	1.000
	4522	30	.05	.972	.974	.979	.983	.988	.993	.996	.998	1.000	1.000	1.000	1.000	1.000	1.000
	4744	25	.05	.971	.973	.977	.978	.985	.990	.994	.997	.998	.999	1.000	1.000	1.000	1.000
	5114	20	.05	.970	.972	.974	.977	.978	.984	.988	.992	.995	.998	.999		1.000	1.000
	5309	17	.03	.969	.971	.973	.975	.978	.983	.986	.991	.993	.997	.998	.999	1.000	1.000
	5458	15	.02	.969	.971	.972	.974	.977	.980	.984	.988	.992	.995	.997	.999	.999	1.000
	5551	14	.01	.968	.970	.971	.973	.977	.979	.980	.986	.991	.994	.996	.998	.999	1.000
	5734	13	.01	.968	.969	.971	.973	.974	.978	.978	.984	.987	.992	.994	.997	.998	.999
	5931	12	.01	.967	.968	.970	.972	.973	.977	.977	.981	.986	.989	.992	.995	.997	.999
	6167	11	.01	.966	.967	.970	.971	.972	.976	.976	.979	.984	.987	.990	.993	.996	.997
	6395	10	.01	.966	.967	.969	.971	.972	.975	.975	.979	.981	.986	.989	.992	.994	.996
	6715	9	.01	.965	.966	.969	.970	.971	.974	.975	.977	.978	.982	.987	.990	.993	.995
	7072	8	.01	.965	.966	.969	.9.70	.971	.973	.974	.975	.977	.980	.985	.987	.991	.993

Table 12. (Concluded)

Probability of occurrence of above-dam DOs (P3) which are equal to or less than those required to maintain a 5.0 mg/l

	Brandon Road	flow	minir	num stand	dard (tabl	.e 9) for	temperat	tures (°0	c) of	Combined	shut-
Rate	Duration	Probability	23-24	24-25	25-26	26-27	27-28	28-29	>29	probability	down
(cfs)	(%)	P1	P2= .0553	.0455	.0485	.0669	.0485	.0711	.0908	(P1)(P2)(P3)	days*
1854	99.8	.002	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.001837	0.448
2094	99	.01	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.009184	2.241
2252	98	.01	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.009184	2.241
2369	97	.01	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.009184	2.241
2449	96	.01	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.009184	2.241
2545	95	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.009184	2.241
2338	90	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045920	11.204
3050	85	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045920	11.204
3244	80	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045913	11.203
3355	75	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045909	11.202
3521	70	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045892	11.198
3620	65	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045890	11.197
3764	60	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045867	11.192
3881	55	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045855	11.228
3948	50	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045840	11.185
4044	45	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045838	11.185
4151	40	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045829	11.183
4316	35	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045808	11.177
4522	30	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045779	11.173
4744	25	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045729	11.166
5114	20	.05	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.045672	11.151
5309	17	.03	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.027384	6.687
5458	15	.02	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.018242	4.455
5551	14	.01	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.009115	2.226
5734	13	.01	1.000	1.000	1.000	1.000	1.000	1.000	1.000	.009104	2.224
5931	12	.01	.999	1.000	1.000	1.000	1.000	1.000	1.000	.009094	2.222
6167	11	.01	.998	.999	1.000	1.000	1.000	1.000	1.000	.009084	2.220
6395	10	.01	.998	.999	.999	1.000	1.000	1.000	1.000	.009077	2.219
6715	9	.01	.997	.998	.999	.999	1.000	1.000	1.000	.009065	2.216
7072	8	.01	.994	.996	.998	.999	.999	1.000	1.000	.009051	2.214

Total Days 206.184

No. of

<sup>\*</sup> Number of days of shutdown required in the 244 day period between April 1 and November 30 of any given year to maintain a downstream DO of  $5\,\mathrm{mg/l}$ .

Table 13. Predicted DOs Based on Using 90 Percent of Des Plaines River Flows at 95 and 50 Percent Flow Durations for Power Generation with 2 mg/l and 4 mg/l DO Additions to Power Flow

Temperature °C		95% f	low du	s (mg/ ration C <sub>A</sub> ) in 4	with		5	0% fl	ow du	ratio	/1) fon with in mg/	ı
a. <u>2.0 mg/l Addition</u>												
12 14 16 18 20 22 24 26 28	1.94 1.68 1.43 1.15 0.84 0.51 0.14 0.00	2.81 2.46 2.30 2.03 1.71 1.38 1.01 0.62 0.17	3.69 3.43 3.18 2.90 2.59 2.25 1.88 1.49 1.04	4.57 4.31 4.15 3.77 3.46 3.13 2.75 2.36 1.91	5.44 5.18 4.92 4.65 4.33 4.00 3.62 3.23 2.78	6.32 6.26 5.80 5.37 <u>5.08</u> 4.77 4.42 4.04 3.20		3.59 3.43 3.27 3.09 2.92 2.71 2.51	4.46 4.31 4.14 3.97 3.79 3.66	5.50 5.34 5.18 <u>5.01</u> 4.84 4.67 4.45 4.25 4.05	6.37 6.21 6.05 5.89 5.71 5.54 5.32 5.12 4.92	7.30 7.14 6.93 6.61 6.46 6.41 6.13 5.54 5.25
			þ	). <u>4.0</u>	mg/l	Additi	on					
12 14 16 18 20 22 24 26 28	3.64 3.38 3.13 2.85 2.54 2.21 1.84 1.45 1.00	4.51 4.26 4.00 3.73 3.41 3.08 2.71 2.32 1.87	5.39 5.13 4.88 4.60 4.29 3.95 3.58 3.19 2.74	6.27 6.01 5.75 5.47 5.16 4.83 4.45 4.06 3.16	7.04 6.88 6.62 6.35 5.94 5.25 4.69 3.94 3.13	8.02 7.76 7.14 6.41 5.91 5.22 4.65 3.91 3.25	4.57 4.41 4.26 4.09 3.92 3.75 3.56 3.36 3.16	5.44 5.29 5.13 4.97 4.79 4.62 4.43 4.23 4.03	6.32 6.16 6.01 5.84 5.67 5.49 5.30 5.10 4.90	7.20 7.04 6.88 6.71 6.54 6.37 6.17 5.97 5.32	7.97 7.91 7.75 7.59 7.32 6.79 6.41 5.85 5.29	8.95 8.79 8.27 7.65 7:29 6.76 6.38 5.82 5.26

Note: From table 9, 95% flow duration = 2545 cfs and 50% flow duration = 3948 cfs; underlined values denote values which fall within the 5.0 mg/l minimum standard

Table 14. Predicted DOs Based on Using 70 Percent of Des Plaines River Flows for 95 and 50 Percent Flow Durations for Power Generation with 2 mg/l and 4 mg/l DO Additions to Power Flow

Temperature		Predic 95% f lbove-d <u>2</u>	low du	ration	with		5	0% fl	ed DOs ow du: n <u>DO(</u>	ration	n with	ı
a. 2.0 mg/l Addition												
12	2.92	3.65	4.38	5.11	6.54	6.57		4.53		5.99		7.45
14	2.61	3.34	4.06	4.79	5.52	6.24	3.59	4.32	$\frac{5.04}{4.04}$	5.77	6.50	7.22
16	2.31	3.03	3.76	4.48	$\frac{5.20}{4.07}$	5.92	3.39	4.11		5.56	6.28	7.00
18 20	1.99 1.63	2.71 2.35	3.43	4.15 3.78	4.87	5.59 5.22	3.18	3.90	4.62	5.34 5.11	6.06	6.78
22	1.26	$\frac{2.35}{1.97}$	3.07 2.69	3.76 3.41	4.50 4.12	$\frac{5.22}{4.84}$	2.96 2.65	3.68 3.46	4.40 4.18	$\frac{5.11}{4.90}$	5.83 5.61	6.55 6.33
24	0.84	1.56	2.27	2.99	3.70	4.41	2.51	3.23	3.94	4.66	5.37	6.08
26	0.42	1.13	1.84	2.55	3.70	3.97	2.28	2.99	3.70	4.41	5.12	5.83
28	0.00	0.64	1.35	2.06	2.76	3.12		2.75		4.17	$\frac{3.12}{4.87}$	
20	0.00	0.04	1.55	2.00	2.70	3.12	2.01	2.75	3.40	1.1/	1.07	5.25
			b	. <u>4.0</u>	mg/l	Additi	<u>on</u>					
12	4.27	5.00	5.73	6.46	7.19	7.92	5.20	5.93	6.66	7.39	8.12	8.85
14	3.96	4.69	5.41	6.14	6.87	7.59	4.99	5.73	6.44	7.17	7.90	8.62
16	3.66	4.38	5.11	5.83	6.55	6.99	4.79	5.51	6.24	6.96	7.68	8.12
18	3.34	4.06	4.78	5.50	6.22	6.31	4.58	5.30	6.02	6.74	7.46	7.55
20	2.98	3.70	4.42	<u>5.13</u>	5.78	5.80	4.36	5.08	5.80	6.51	7.16	7.18
22	2.61	3.32	4.04	4.76	5.12	5.14	4.15	4.86	5.58	6.30	6.66	6.68
24	2.19	2.91	3.62	4.34	4.56	4.57	3.91	4.63	5.34	6.06	6.28	6.29
26	1.77	2.48	3.19	3.90	3.84	3.85	3.68	4.39	5.10	5.81	5.75	5.76
28	1.28	1.99	2.70	3.06	3.06	3.07	3.38	4.09	4.80	5.08	5.09	<u>5.10</u>

Note: From table 9, 95% flow duration = 2545 cfs and 50% flow duration = 3948 cfs; underlined values denote values which fall within the 5.0 mg/l minimum standard

FIGURES




Figure 1. Illinois Waterway




Figure 2. Illinois Waterway profile




Figure 3. Plan and section view of Brandon Road dam




Figure 4. Above dam, showing weir in operation





Figure 5. Below dam at Brandon Road bridge






Figure 6. Upper Illinois Waterway DO profile




Figure 7. April 1 - November 30 frequency distribution of water temperatures at Dresden Island




Figure 8. Frequency distribution of DO above the Brandon Road dam

#### REFERENCES

- American Society of Civil Engineers, Committee on Sanitary Engineering Research. 1960. Solubility of atmospheric oxygen in water. ASCE Journal of the Sanitary Engineering Division, SE7(86):41.
- Barrett, M.J., A.L.H. Gameson, and C.G. Ogden. 1960. <u>Aeration studies at four weir systems</u>. Water and Water Engineering v. 775(64):507, September.
- Butts, T.A. 1988. <u>Development of design criteria for sidestream elevated</u> <u>pool aeration stations</u>. Illinois State Water Survey Contract Report 452, 84 p.
- Butts, T.A. 1974. Measurements of sediment oxygen demand characteristics in the upper Illinois Waterway. Illinois State Water Survey Report of Investigation 76, 32 p.
- Butts, T.A., H.R. Adkins, and D.H. Schnepper. (in press). The effects of hydropower development at the Starved Rock dam on downstream dissolved oxygen resources. Illinois State Water Survey contract report prepared for the City of Peru in cooperation with Beling Consultants of Moline, Illinois.
- Butts, T.A. and H.R. Adkins. 1987. <u>Aeration characteristics of Starved Rock Dam Tainter gate flow controls</u>. Illinois State Water Survey Contract Report 423, 120 p.
- Butts, T.A. and R.L. Evans. 1978. <u>Sediment oxygen demand studies of selected northeastern Illinois streams</u>. Illinois State Water Survey Circular 129, 129 p.
- Butts, T.A. and R.L. Evans. 1979. <u>Sediment oxygen demand in a shallow oxbow lake</u>. Illinois State Water Survey Circular 136, 28 p.
- Butts, T.A. and R.L. Evans. 1980. <u>Aeration characteristics of flow release controls on Illinois Waterway dams</u>. Illinois State Water Survey Circular 145, 69 p.
- Butts, T.A., R.L. Evans, and S. Lin. 1975. <u>Water quality features of the upper Illinois Waterway</u>. Illinois State Water Survey Report of Investigation 79, 60 p.
- Butts, T.A., R.L. Evans, and R.E. Sparks. 1982. <u>Sediment oxygen demand fingernail clam relationship in the Mississippi River Keokuk pool.</u>
  Transactions of the Illinois State Academy of Science, v. 75:29-39.
- Butts, T.A., R.L. Evans, and J.B. Stall. 1974. A waste allocation study of selected streams in Illinois. Illinois State Water Survey Contract Report prepared for Illinois EPA.
- Butts, T.A., V. Kothandaraman, and R.L. Evans. 1973. <u>Practical considerations for assessing the waste assimilative capacity of Illinois streams</u>. Illinois State Water Survey Circular 110, 49 p.

- Butts, T.A., D. Roseboom, T. Hill, S. Lin, D. Beuscher, R. Twait, and R.L. Evans. 1981. Water quality assessment and waste assimilative analysis of the LaGrange pool. Illinois River. Illinois State Water Survey Contract Report 260, 116 p.
- Butts, T.A., D.H. Schnepper, and R.L. Evans. 1970. <u>Dissolved oxygen resources</u> and waste assimilative capacity of the LaGrange pool. Illinois River. Illinois State Water Survey Report of Investigation 64, 28 p.
- Butts, T.A., D.H. Schnepper, and K.P. Singh. 1983. <u>The effects of Lake Michigan discretionary diversion strategies on Illinois Waterway dissolved oxygen resources</u>. Illinois State Water Survey Contract Report 324.
- Butts, T.A., D.B. Shackleford, and T.E. Hill. 1987. <u>Upper Illinois Water-way water quality a 1982 study related to increased Lake Michigan diversion</u>. Draft report prepared by the WQS of the SWS for DWR-IDOT and the U.S. Army Corps of Engineers, 129 p.
- Crawford, Murphy & Tilly, Inc. Consulting Engineers. 1982. Results of water quality testing on the Illinois River from Brandon Road to Starved Rock lock and dam. Prepared for the Rock Island District Corps of Engineers (Contract No. DACW 23-79-D-0040, work order Nos. 5,6,7, and 8), Springfield, IL.
- Crevensten, D. and A. Stoddard. 1974. <u>Water quality model of the lower Fox River. Wisconsin</u>. Proceedings, Seventeenth Conference on Greater Lakes Research, International Association for Great Lakes Research, Hamilton, Ontario, Canada.
- Foree, E.G. 1976. Reaeration and velocity prediction for small streams.

  ASCE Journal of the Environmental Engineering Division v.

  102(EE5):937.
- Gameson, A.L.H. 1957. Weirs and the aeration of rivers. Journal of the Institution of Water Engineers (British) v. 6(11):477.
- Gameson, A.L.H, K.G. Vandyke, and C.G. Ogden. 1958. The effect of temperature on aeration at weirs. Water and Water Engineering (British) v. 753(62):489.
- Kothandaraman, V. 1971. <u>Effects of contaminants on reaeration rates in river water</u>. Journal Water Pollution Control Federation, v. 43(5):806-817.
- Lee, M.T., J.B. Stall, and T.A. Butts. 1975. The 1975 Sediment Survey of Lake Meredosia. Illinois State Water Survey Special Report.
- Macaitis, B., J. Variakojis, B. Kuhl. 1984. <u>A planning feasibility report on sidestream elevated pool aeration stations</u>. The Metropolitan Sanitary District of Greater Chicago, Chicago, IL, 36 p.
- Mades, D.M. 1981. <u>Stage-discharge relationships at dams on the Illinois and Pes Plaines Rivers in Illinois</u>. U.S. Geological Survey Open File Report 81-1009, Champaign, IL, 56 p.


- Mathis, B.J. and T.A. Butts. 1981. <u>Sediment oxygen demand and effect on dissolved oxygen in a cutoff meander of the Kaskaskia River</u>. University of Illinois Water Resources Center Research Report 162.
- Mitchell, W.D. 1957. <u>Flow duration of Illinois streams</u>. USGS Report Issued by the Division of Waterways, Illinois Department of Transportation, 189 p.
- Polls, I., S.J. Sedita, D.R. Zenz, and C. Lue-Hing. 1985. <u>Illinois Water-way water quality survey from Lockport lock and dam to the Peoria lock and dam 1977 and 1983</u>. The Metropolitan Sanitary District of Greater Chicago Report No. 85-14, 220 p.
- Preul, C.H. and A.G. Holler. 1969. <u>Reaeration through low dams in the Ohio River</u>. Proceedings of the 24th Industrial Waste Conference Part Two, Purdue University, Lafayette, Indiana.
- Roseboom, D.P., R.L. Evans, W. Wang, T.A. Butts, and R.M. Twait. 1979.

  <u>Effect of bottom conditions on eutrophy of impoundments</u>. Illinois

  State Water Survey Circular 139, 139 p.
- Susag, R.H., M.L. Robins, and G.J. Schroepfer. 1967. <u>Improving river</u> aeration at an underflow dam. ASCE Journal of the Sanitary Engineering Division, v. 93(SA6):133.
- United States Geological Survey. 1976, 1977, 1978, 1979. Water resources data for Illinois water year 1975. (water year 1976) (water year 1977) (water year 1978). USGS, Champaign, IL.
- Velz, C.J. 1947. <u>Factors influencing self-purification and their relation</u> to pollution abatement. Sewage Works Journal, v. 19(7):629-644.
- Velz, C.J. 1970. Applied stream sanitation. John Wiley & Sons, Inc., New York, p. 168.
- Water Research Centre. 1973. <u>Aeration at weirs</u>. In Notes on Water Pollution, Elder Way, Stevenage, Herts, England, June, No. 61.


#### Appendix A

Flow Duration Curves for Main Stem Gaging Stations at Lockport, Marseilles, and Henry, and for the Tributaries: Des Plaines, DuPage, Kankakee, Fox, and Vermilion Rivers




PERCENT OF TIME DISCHARGE IS GREATER

SANITARY AND SHIP CANAL AT LOCKPORT




PERCENT OF TIME DISCHARGE IS GREATER

ILLINOIS RIVER AT MARSEILLES




PERCENT OF TIME DISCHARGE IS GREATER



PERCENT OF TIME DISCHARGE IS GREATER


# DES PLAINES RIVER AT RIVERSIDE






### PERCENT OF TIME DISCHARGE IS GREATER

# DU PAGE RIVER AT SHOREWOOD




PERCENT OF TIME DISCHARGE IS GREATER

# KANKAKEE RIVER AT WILMINGTON



PERCENT OF TIME DISCHARGE IS GREATER
FOX RIVER AT DAYTON





PERCENT OF TIME DISCHARGE IS GREATER

**VERMILION RIVER AT LOWELL - LEONORE** 

#### Appendix B

Main Stem Flows for Various Flow Duration Percents

# Main Stem Flows for Various Flow Duration Percents

Gage Name	Lockport	Marseilles	Henry	Kingston Mines
SWS Mile Flow Duration	291.00	246.39	196.66	145.76
%	1061	2000	4001	C C 4.1
99.8	1761	3000	4891	6641
99	1988	3400	5367	7135
98	2140	3650	5664	7437
97	2250	3 820	5867	7656
96 05	2320	4000	6081	7 890
95	2410	4140	6247	8067
90	26 90	4550	6735	8576
85 80	2900	4800	7033	8867
	3080	5100	7390	922 8
75 70	3189	5300	7628	9442
65	3340	5500	7 866	9646
60	3420 3550	57 50 6000	8163	9910 10164
55			8461	
55 50	3650 3690	6250 6550	8758	103 86 10672
			9115	11063
45 40	3750	6 950	9591	11401
	3830	7350	10067	
35 30	3950	7900	10722	11859 1246 9
25	4100 4210	8550 9400	11495 12507	13201
20	4430	10600		14366
20 17	4430 45 80		13935	15012
15	45 80 46 80	11400 12100	14887 15720	15580
14	4720			15886
13	4720 4850	12500 13000	161%	
13	5000	13500	16791 17396	16365 16816
11	5200		17386	17225
10	5400 5400	14000 14500	17 981 18576	17540
9	5700	15200	19409	18120
8	6000	15200	20242	18677
O	0000	1000	404 <b>4</b> 4	10077

# Appendix C

Tributary Flows for Various Flow Duration Percents

Tributary Flows forVarious Flow Duration Percents

Gage Name	Des Plaines	DuPage	Kanka- kee	Maz on	Fox	Vermil- ion	1 & M Canal	Bureau Creek
SWS Mile Flow Duration	289.94	276.96	272.90	263.52	239.17	226.50	211.19	209.36
%								
99.8	8	29	400	4	170	11	1	2
99	16	34	515	5	228	12	1	2
98	20	37	580	5	26 9	13	1	2
97	25	40	620	5	286	13	1	2
%	28	41	655	6	300	14	1	2
95	31	43	675	6	312	15	2	3
90	43	51	770	7	366	18	2	3
85	56	59	890	10	414	24	2	4
80	69	67	980	13	458	31	3	5
75	85	76	1100	16	508	40	4	7
70	103	84	1220	21	56 5	51	5	9
65	120	92	1340	27	625	66	7	11
60	141	103	1490	35	690	86	9	15
55	165	113	1650	48	770	188	12	20
50	192	126	1860	60	860	147	15	25
45	224	140	2100	77	96 5	190	19	32
40	260	155	2430	102	1100	250	25	42
35	305	177	2750	143	1270	350	35	59
30	365	203	3170	175	1450	430	43	73
25	450	235	3500	217	1760	530	53	89
20	560	280	3900	269	2080	660	66	111
17	635	320	4650	331	2340	810	81	137
15	700	355	5250	380	2580	930	93	157
14	740	370	5400	413	2720	1010	101	171
13	7 85	3 88	5600	441	2840	1080	108	182
12	830	410	5 850	465	3000	1140	114	192
11	885	435	6200	507	3150	1240	124	209
10	950	460	6700	564	3340	1380	138	233
9	1000	485	7 250	625	3530	1530	153	258
8	1080	525	7700	674	3780	1650	165	27 9

### Appendix D

Estimated Pool Elevations for Various Flow Duration Percents

# Pool Elevations (feet above MSL) for Various Flow Duration Percents

Gage Name	Lockport Lo		Brandon Road Lo			Marseil- les Up		Starved Rock Up
SWS Mile	291.00	286.25	286.24	271.52	271.51	246.78	246.77	231.02
Duration	ı							
%								
99.8	53 8.6	53 8.6	504.8	504.8	483.3	483.3	459.0	459.0
99	53 8.6	53 8.6	504.8	504.8	483.3	483.3	459.0	459.0
98	53 8.9	53 8.9	505.0	505.0	484.3	484.4	459.0	459.1
97	53 8.9	53 8.9	505.1	505.2	484.3	483.5	459.1	459.2
96	539.0	539.0	505.3	505.3	484.4	483.6	459.1	459.3
95	539.0	539.0	505.5	505.5	484.4	483.7	459.1	459.3
90	539.1	539.0	505.5	505.3	484.4	483.7	459.3	459.3
85	539.2	539.0	505.4	505.1	484.4	483.7	459.5	459.4
80	539.2	53 9.0	505.5	505.1	484.5	483.7	459.4	
75	539.3	539.2	505.6	505.1	484.6	483.7	459.4	
70	539.3	53 9.2	505.6	505.1	484.6	483.7	459.4	459.3
65	539.3	539.1	505.6	505.1	484.7	483.7	459.5	459.3
60	539.3	53 9.0	505.6	505.1	484.8	483.7	459.5	459.4
55	539.3	53 8.9	505.6	505.1	484.9	483.7	459.5	459.4
50	539.3	53 8.9	505.6	505.2	485.6	483.7	459.6	459.4
45	539.3	53 9.0	505.6	505.2	485.6	483.7	459.6	459.4
40	539.4	53 9.1	505.6	505.2	485.6	483.7	459.7	459.4
35	53 9.2	53 9.0	505.6	505.2	485.8	483.7	459.8	459.4
30	539.0	53 8.9	505.6	505.2	486.0	483.7	459.9	459.4
25	539.0	53 8.9	505.6	505.2	486.2	483.7	460.0	459.4
20	53 9.0	53 8.9	505.6	505.2	486.4	483.7	460.2	459.4
17	539.0	53 8.9	505.6	505.2	486.4	483.7	460.2	459.4
15	53 9.0	53 8.8	505.5	504.8	486.6	483.5	460.2	459.3
14	539.0	53 8.8	505.5	504.8	486.9	483.4	460.2	459.2
13	539.0	53 8.7	505.5	504.8	487.2	483.3	460.2	459.1
12	539.1	53 8.7	505.5	504.8	487.5	483.3	460.3	459.0
11	539.2	53 8.6	505.5	504.8	487.9	483.3	460.4	45 8.9
10	53 9.3 539.4	53 8.6 53 8.6	505.7 505.9	504.8 504.8	488.0 488.2	483.2 483.2	460.5 460.6	458.7 458.9
9 8	539.4	53 8.6	505.9	504.8	488.2	483.2 483.1	460.6	458.9 458.9
0	0.666	0.0	300.1	504.0	400.5	403.1	400.7	400.9

Pool Elevations (feet above MSL) for Various Flow Duration Percents (cont)

Gage Name	Starved Rock Lo	LaSalle	Spring Valley	Henry	Peoria Boat Yd	Peoria Upper	Peoria Lower
SWS Mile	231.01	223.05	218.69	196.66	164.61	158.06	158.05
Flow							
Duration %							
% 99.8	440.6	440.6	440.6	440.6	440.0	440 0	420.0
99.0	440.6	440.6	440.6	440.6	440.0 440.0	440.0	430.9
98	440.6	440.6	440.6	440.6	440.0	440.0 440.0	430.9 431.3
97	440.7	440.7	440.6	440.6	440.0	440.0	431.3
96	440.7	440.7	440.6	440.6	440.1	440.0	431.0
95	440.8	440.8	440.6	440.5	440.1	440.0	431.9
90	440.8	440.8	440.7	440.5	440.1	440.0	432.3
85	440.8	440.8	440.7	440.5	440.0	440.0	432.3
80	441.2	441.0	440.8	440.4	439.9	43 9.8	433.8
75	441.3	441.1	440.9	440.4	43 9.8	43 9.7	434.0
70	441.6	441.3	441.0	440.4	43 9.8	43 9.6	434.0
65	441.9	441.5	441.1	440.4	439.7	439.5	434.0
60	442.0	441.6	441.3	440.6	440.0	439.8	434.4
55	442.1	441.8	441.5	440.9	440.3	440.1	434.8
50	442.2	442.0	441.7	441.1	440.6	440.4	435.2
45	442.3	442.2	441.9	441.3	440.9	440.7	435.6
40	442.3	442.2	442.0	441.3	440.7	440.4	436.0
35	442.4	442.3	442.1	441.4	440.5	440.1	436.5
30	442.4	442.3	442.2	441.4	440.3	43 9.8	437.0
25	442.6	442.5	442.4	441.5	440.5	440.1	437.3
20	444.0	443.8	443.4	442.6	440.7	440.3	43 8.0
17	446.0	445.5	445.1	443.3	440.9	440.4	43 9.0
15	448.0	447.2	446.6	443.8	441.1	440.5	440.5
14	448.1	447.4	446.8	444.0	441.5	440.8	440.8
13	448.2	447.6	447.0	444.2	441.8	441.2	441.2
12	448.4	447.7	447.1	444.5	442.5	441.6	441.6
11	448.9	448.2	447.4	444.7	442.7	441.9	441.9
10	449.3	448.7	447.7	445.0	443.0	442.2	442.2
9	449.9	449.3	448.3	445.6	443.6	442.8	442.8
8	450.5	449.9	448.9	446.2	444.2	443.4	443.4

### Appendix E

Time of Travel from Lockport Dam to Point Source Waste Load Inputs for Various Flow Duration Percents

Time of Travel (days) from Lockport Dam to Point Source Waste Load Location

Flow		Poi	nt Source	River Mile	5	
Duration %	290.99	289.94	286.25	283.72	276.96	272.90
99.8	.00075	.14188	.34683	1.30374	2.82286	3.79622
99	.00066	.12572	.83789	1.15423	2.50425	3.37115
98	.00063	.11923	.79591	1.09879	2.38296	3.20807
97	.00060	.11342	.75660	1.04933	2.29047	3.09100
96	.00058	.11072	.73775	1.02869	2.24674	3.02774
95	.00056	.10659	.70996	.99826	2.19561	2.96278
90	.00050	.09610	.63774	.89586	1.96540	2.64800
85	.00047	.08974	.59396	.83084	1.81907	2.45107
80	.00044	.08451	.55841	.78423	1.72114	2.31833
75	.00043	.08249	.54609	.76753	1.68187	2.26285
70	.00041	.07 858	.51969	.73099	1.60699	2.16558
65	.00040	.07668	.50368	.70911	1.56119	2.10379
60	.00039	.07384	.48208	.67992	1.50228	2.02652
55	.00038	.07178	.46538	.65734	1.45678	1.96670
50	.00037	.07101	.45794	.64691	1.43635	1.94044
45	.00037	.06 992	.44970	.63416	1.40433	1.89463
40	.00036	.06 893	.44140	.62126	1.37402	1.85332
35	.00035	.06602	.42078	.59378	1.31818	1.77811
30	.00033	.06282	.39805	.56324	1.25594	1.69488
25	.00032	.06114	.38126	.53 849	1.19480	1.60688
20	.00030	.05804	.35569	.50126	1.10539	1.48064
17	.00029	.05619	.34236	.482 84	1.06925	1.43392
15	.00029	.05497	.33165	.46595	1.02592	1.37047
14	.00029	.05449	.32673	.45870	1.00789	1.34466
13	.00028	.05298	.31525	.44296	.97398	1.29904
12	.00027	.05170	.30588	.42939	.94311	1.25730
11	.00026	.04999	.29347	.41237	.90855	1.21266
10	.00025	.04846	.28338	.40132	.88956	1.18794
9	.00024	.04621	.27013	.3 8563	.85931	1.14790
8	.00023	.04443	.25784	.37054	.82788	1.10486

Time of Travel (days) from Lockport Dam to Point Source Waste Load Location (cont.)

Flow		Poi	int Source	River Mile	2	
Duration						
%	271.52	263.52	252.42	246.78	23 9.17	231.02
99.8	4.26001	5.22895	6.75885	7.75489	8.3 8545	9.62905
99	3.77541	4.62218	5.96533	6.84304	7.40240	8.50616
98	3.58738	4.45501	5.76690	6.59890	7.12329	8.15657
97	3.45652	4.28370	5.54147	6.34239	6.85193	7.85092
96	3.38107	4.18328	5.39861	6.17072	6.65963	7.62274
95	3.30834	4.08393	5.26384	6.01563	6.48851	7.42097
90	2.95469	3.65377	4.72207	5.40524	5.84695	6.70130
85	2.73197	3.38281	4.38750	5.03359	5.46444	6.28303
80	2.58128	3.19792	4.14421	4.75249	5.15267	5.91697
75	2.51357	3.10817	4.01888	4.60413	4.98981	5.72404
70	2.40347	2.96947	3.84104	4.40399	4.77623	5.48212
65	2.33122	2.87761	3.71432	4.25323	4.61406	5.28993
60	2.24243	2.76716	3.56884	4.08518	4.43273	5.08384
55	2.17265	2.67870	3.44885	3.94456	4.27866	4.90235
50	2.13799	2.65269	3.40872	3.88482	4.20816	4.80296
45	2.08119	2.56722	3.27971	3.72841	4.03381	4.59355
40	2.02845	2.48555	3.15631	3.58009	3.87299	4.40169
35	1.94128	2.37515	3.00363	3.39853	3.67508	4.16699
30	1.84512	2.25227	2.83631	3.20165	3.46080	3.91555
25	1.74572	2.12772	2.66633	2.99977	3.23904	3.65065
20	1.60607	1.95623	2.44110	2.73791	2.95563	3.32183
17	1.54871	1.87033	2.31740	2.59276	2.79572	3.13555
15	1.47495	1.78053	2.19908	2.45471	2.64568	2.96294
14	1.44646	1.75130	2.16026	2.40664	2.59111	2.89580
13	1.39723	1.69831	2.09476	2.33057	2.50749	2.79870
12	1.35179	1.64902	2.03530	2.26301	2.43494	2.71373
11	1.30312	1.59777	1.97488	2.19510	2.36244	2.63004
10	1.27421	1.55775	1.91908	2.12988	2.29253	2.54767
9	1.22944	1.50227	1.84794	2.04914	2.20892	2.43907
8	1.18229	1.44761	1.77920	1.97042	2.12351	2.36022

Time of Travel (days) from Lockport Dam to Point Source Waste Load Location (cont.)

Flow Duration		Ро	int Source	River Mil	е	
%	226.50	222.21	218.24	211.19	209.36	190.51
99.8	10.03861	10.55652	10.96233	11.75824	11.96269	14.21006
99	80867 90	9.33091	9.69499	10.41204	10.59679	12.64081
98	8.50202	8.93 934	9.28243	9.95746	10.13169	12.06636
97	8.18244	8.60263	8.93262	9.58270	9.75064	11.61976
96	7.94453	8.35079	8.66 875	9.29363	9.45517	11.25591
95	7.73290	8.126 95	8.43 557	9.04259	9.19959	10.95176
90	6.98675	7.34808	7.63352	8.19612	8.34129	9.95493
85	6.55408	6.89737	7.16 895	7.70515	7.84367	9.38709
80	6.183 88	6.51418	6.77453	7.28579	7.41746	8.87590
75	5.983 99	6.30439	6.55780	7.05519	7.18309	8.596 88
70	5.74070	6.05453	6.30218	6.78644	6.91077	8.28307
65	5.54538	5.85074	6.09113	6.55955	6.67962	8.00268
60	5.33157	5.62638	5.86078	6.31966	6.43720	7.737 94
55	5.14355	5.42994	5.65928	6.10978	6.22533	7.51516
50	5.03634	5.31307	5.53621	5.97526	6.087 85	7.35015
45	4.816 86	5.08107	5.29561	5.71852	5.826 98	7.04856
40	4.61280	4.86180	5.06567	5.46912	5.57249	6.73581
35	4.36590	4.59841	4.7 8959	5.16910	5.26644	6.36597
30	4.09958	4.31412	4.49199	4.84640	4.93724	5.96238
25	3.82120	4.01838	4.182 87	4.51108	4.59516	5.54632
20	3.49674	3.6 8991	3.85164	4.17238	4.25459	5.19278
17	3.33105	3.53470	3.70880	4.04904	4.13488	5.08002
15	3.18035	3.39666	3.58283	3.93 990	4.02894	4.97474
14	3.10847	3.32007	3.50294	3.85409	3.94178	4.87548
13	3.00563	3.21167	3.3 9043	3.73391	3.81979	4.73562
12	2.91574	3.11557	3.28903	3.62353	3.70755	4.61274
11	2.83298	3.03192	3.203 88	3.53367	3.61653	4.50706
10	2.75037	2.947 94	3.11829	3.443 83	3.52580	4.40 853
9	2.62973	2.81585	2.97 864	3.29315	3.37329	4.25282
8	2.56298	2.75698	2.92651	3.25133	3.333 80	4.22414

Time of Travel (days) from Lockport Dam to Point Source Waste Load Location (cont.)

99.8       15.68171       16.92263       19.37045       20.52188       20.8         99       13.98961       15.13155       17.3 9019       18.45536       18.7         98       13.34869       14.43686       16.59267       17.61088       17.8         97       12.86466       13.93719       16.06408       17.06423       17.3         96       12.457 93       13.49480       15.55280       16.52135       16.7         95       12.12330       13.13477       15.14362       16.08958       16.3         90       11.03922       11.97305       13.84367       14.72969       14.9         85       10.42481       11.30738       13.07736       13.92099       14.1	
99.8       15.68171       16.92263       19.37045       20.52188       20.8         99       13.98961       15.13155       17.3 9019       18.45536       18.7         98       13.34869       14.43686       16.59267       17.61088       17.8         97       12.86466       13.93719       16.06408       17.06423       17.3         96       12.457 93       13.49480       15.55280       16.52135       16.3         95       12.12330       13.13477       15.14362       16.08958       16.3         90       11.03922       11.97305       13.84367       14.72969       14.9         85       10.42481       11.30738       13.07736       13.92099       14.1	
99       13.98961       15.13155       17.3 9019       18.45536       18.7         98       13.34869       14.43686       16.59267       17.61088       17.8         97       12.86466       13.93719       16.06408       17.06423       17.3         96       12.457 93       13.49480       15.55280       16.52135       16.5         95       12.12330       13.13477       15.14362       16.08958       16.3         90       11.03922       11.97305       13.84367       14.72969       14.9         85       10.42481       11.30738       13.07736       13.92099       14.1	58.06
99       13.98961       15.13155       17.3 9019       18.45536       18.7         98       13.34869       14.43686       16.59267       17.61088       17.8         97       12.86466       13.93719       16.06408       17.06423       17.3         96       12.457 93       13.49480       15.55280       16.52135       16.5         95       12.12330       13.13477       15.14362       16.08958       16.3         90       11.03922       11.97305       13.84367       14.72969       14.9         85       10.42481       11.30738       13.07736       13.92099       14.1	00044
98 13.34869 14.43686 16.59267 17.61088 17.8 97 12.86466 13.93719 16.06408 17.06423 17.3 96 12.457 93 13.49480 15.55280 16.52135 16.3 95 12.12330 13.13477 15.14362 16.08958 16.3 90 11.03922 11.97305 13.84367 14.72969 14.9 85 10.42481 11.30738 13.07736 13.92099 14.3	
97       12.86466       13.93719       16.06408       17.06423       17.3         96       12.457 93       13.49480       15.55280       16.52135       16.3         95       12.12330       13.13477       15.14362       16.08958       16.3         90       11.03922       11.97305       13.84367       14.72969       14.3         85       10.42481       11.30738       13.07736       13.92099       14.1	
96	
95     12.12330     13.13477     15.14362     16.08958     16.3       90     11.03922     11.97305     13.84367     14.72969     14.9       85     10.42481     11.30738     13.07736     13.92099     14.1	
90 11.03922 11.97305 13.84367 14.72969 14.9 85 10.42481 11.30738 13.07736 13.92099 14.1	
85 10.42481 11.30738 13.07736 13.92099 14.1	
	94270
QN Q Q Q Q Q Q Q Q Q Q Q Q Q Q Q Q Q Q	L2631
	32247
	36472
	13 919
	7215
	79079
	57508
50 8.21139 9.03736 10.65309 11.3 9547 11.5	67 97
45 7.88759 8.72935 10.36543 11.106 85 11.2	27587
40 7.53366 8.31839 9.84418 10.53990 10.7	70030
35 7.11892 7.847 80 9.25842 9.90362 10.0	5421
30 6.66345 7.32801 8.61460 9.20681 9.3	34679
25 6.20266 6.84555 8.09038 8.66099 8.7	9470
20 5.82761 6.48883 7.70547 8.24011 8.3	36381
17 5.70516 6.3 8363 7.60092 8.12152 8.2	24012
15 5.58960 6.27 836 7.496 43 8.00729 8.1	L2190
	L0387
	83 83
12 5.21836 5.98659 7.35711 7.90773 8.0	2117
	0620
	34976
	31595
	06 96

## Appendix F

Ultimate Carbonaceous and Nitrogenous Inputs At Lockport On The Main Stem and Eight Tributaries

Ultimate BOD Loads at Lockport  $L_{an}$  = 25.572  $Q_L$  - 5818  $L_{an}$  = 86-970  $Q_L$  - 74618

Flow Duration	Ultimate Carbonaceous BOD, L <sub>ac</sub>	Ultimate Nitrogeneous BOD, $L_{an}$
%	(lbs/day)	(lbs/day)
99.8 99 98 97 96 95 90 85 80 75 70 65 60 55 40 35 30 25 20 17 15 14	3 9215 45020 48907 51720 53510 55811 62972 6 8342 72945 75502 7 9594 81639 84964 87521 88544 9007 8 92124 95193 99029 101842 107467 111303 113861 114883	7 8537 982 80 111498 121065 127153 134980 159332 177596 493250 201948 215862 222820 234126 242823 246302 251520 25847 8 268914 281960 291527 310660 323706 332403 335882
13 12	118208 122044	347188 360234
11 10 9	127158 132273 139944	377628 395021 421112
8	147616	447204

Note:  $Q_{L}$  is the flow at Lockport for a given flow duration percent (see Appendix C )  $\,$ 

Ultimate Tributary Carbonaceous (L ) BOD Load (lbs/day)  $\text{L}_{\text{ac}} = \text{A} + \text{BQ}_{\text{T}}$ 

	Des Plaines	Du Page	Kanka- kee	Mazon	Fox	Vermil- ion	I & M Canal	Bureau Creek
Coef								
А	6272.1	604.8	253 84.1	566.8	22228.2	566.8	566.8	566.8
В	16.010	30.177	10.218	18.648	25.923	18.648	18.648	18.648
Flow								
Duration								
%								
99.8	6400	1480	29471	641	32598	772	585	604
99	6528	1631	30646	660	3557 9	7 91	585	604
98	6 592	1721	31310	660	37264	809	5 85	604
97	6672	1812	31719	660	3 8301	809	5 85	604
96	6720	1842	32077	679	3 9208	82 8	5 85	604
95	6768	1902	32281	679	39727	847	604	623
90	6961	2144	33252	6 97	42189	902	604	623
85	7169	23 85	3447 8	753	45300	1014	604	641
80	7377	2627	353 98	809	47633	1145	623	660
75	7633	2 898	36624	865	50744	1313	641	6 97
70	7 921	3140	37 850	958	53 855	1518	660	735
65	8193	3381	39076	1070	56 966	1798	6 97	772
60	8530	3713	40609	1219	60854	2171	735	847
55	8914	4015	42244	1462	65002	2767	7 91	940
50	9346	4407	443 89	1686	70446	3308	847	1033
45	9858	4830	46 842	2003	76667	4110	921	1164
40	10435	5282	50214	2469	85222	5229	1033	1350
35	11155	5946	53483	3233	93518	7094	1219	1667
30	12116	6731	57775	3830	104405	8586	1369	1928
25	13477	7696	61147	4613	112960	10450	1555	2226
20	1523 8	9054	65234	5583	123330	12875	1798	2637
17	1643 9	10262	72897	6739	142772	15672	2077	3122
15	1747 9	11318	79028	7653	158326	17 910	2301	3495
14	18120	11770	80561	826 9	162215	19401	2450	3756
13	18840	12314	82604	87 91	167399	20707	2581	3961
12	19561	12977	85159	923 8	173880	21826	26 93	4147
11	20441	13732	88735	10021	182 953	236 91	2879	4464
10	21482	14486	93 844	11084	195915	26301	3140	4912
9	22283	15241	99464	12222	210173	29099	3420	5229
8	23563	16448	104062	13136	22183 9	31336	3644	5770

Note:  $Q_T$  is the tributary flow for a given flow duration percent (see Appendix C ); A and B are statistically derived regression coefficient

Ultimate Tributary Nitrogeneous ( $L_{an}$ ) BOD Load (lbs/day)  $L_{an} \ = \ A \ + \ BQ_T$ 

	Des Plaines	Du Page	Kanka- kee	Mazon	Fox	Vermil- ion	1 & M Canal	Bureau Creek
Coef								
A	1249.3		26198.0	1450.2	2430.6	1450.2	1450.2	1450.2
В	34.820	37.031	6.7 45	12.586	43.030	12.586	12.586	12.586
Flow								
Duration								
%								
99.8	1528	1222	28896	1501	19643	1589	1463	1475
99	1806	1407	29672	1513	24591	1601	1463	147 5
98	1946	1518	30110	1512	273 88	1614	1463	1475
97	2120	1629	30380	1513	29109	1614	1463	1475
96	2224	1666	30616	1526	30615	1626	1463	1475
95	2329	1740	307 51	1526	31476	1639	1475	1488
90	2747	2036	31391	153 8	35564	1677	1475	1488
85	3199	2333	32201	1576	40727	1752	1475	1501
80	3652	2629	32808	1614	44600	1840	1488	1513
75	4209	2962	33617	1652	49764	1964	1501	153 8
70	4836	3258	34427	1715	54927	2092	1513	1563
65	5428	3555	35236	1790	60091	2281	1538	1589
60	6159	3962	36248	1891	66545	2533	1563	1639
55	6995	4332	37327	2054	73430	2935	1601	1702
50	7935	4814	38743	2205	82466	3300	1639	1765
45	9049	5332	40362	2419	927 94	3 842	16 89	1853
40	10303	5888	42588	2734	106 993	4597	1765	197 9
35	11869	6702	44746	3250	120763	5855	1891	2193
30	13959	7665	47 57 9	3653	138836	6862	1991	236 9
25	16918	8850	79805	4181	153035	8121	2117	2570
20	20749	10516	52503	4836	170247	9757	2281	2 847
17	23360	11998	57 561	5616	202520	11645	2470	3175
15	25623	13294	61608	6233	228338	13156	2621	3426
14	27016	13849	62620	6648	2347 92	14163	2721	3602
13	28583	14516	63969	7001	243398	15044	2810	3741
12	30150	15330	656 55	7303	254156	157 99	2 885	3867
11	32065	16256	68016	7832	26 9216	17057	3011	40 81
10	34328	17182	71388	8549	290731	18820	3187	43 83
9	36069	18108	75098	9317	314398	20707	3376	4597
8	3 8855	19589	78133	9933	333761	22218	3527	4962

Note:  $Q_T$  is the tributary flow for a given flow duration percent (see Appendix C ); A and B are statistically derived regression coefficient

## Appendix G

Tributary DO Concentrations
Used in Conjunction with the Various Flow Duration Percents

Tributary DO Concentrations (mg/l)  ${\rm DO_T} = {\rm A} \ + {\rm BQ_T}$ 

	Des Plaines	Du Page	Kanka- kee	Mazon	Fox	Vermil- ion	I & M Canal	Bureau Creek
Coef	11 704	0 (40	0 7 07	0 211	11 205	0 211	0 211	0 211
A B	11.724	8.642	8.7 97		11.395	9.311 0.00067	9.311	9.311
Flow	0.00679	0.00455	0.00015	0.00067	0.00075	0.00067	0.00067	0.00067
Duration								
buracion %								
99.8	11.67	8.51	8.74	11.27	9.30	9.31	9.31	9.31
99	11.62	8.49	8.72	11.22	9.30	9.31	9.31	9.31
98	11.59	8.47	8.71	11.19	9.30	9.31	9.31	9.31
97	11.55	8.46	8.70	11.18	9.30	9.31	9.31	9.31
96	11.53	8.46	8.70	11.17	9.30	9.31	9.31	9.31
95	11.51	8.45	8.70	11.16	9.30	9.31	9.31	9.31
90	11.43	8.41	8.68	11.12	9.30	9.31	9.31	9.31
85	11.34	8.37	8.66	11.08	9.30	9.30	9.31	9.31
80	11.26	8.34	8.65	11.05	9.29	9.30	9.31	9.31
75	11.15	8.30	8.63	11.01	9.28	9.30	9.31	9.31
70	11.02	8.26	8.61	10.97	9.28	9.30	9.31	9.31
65	10.91	8.22	8.60	10.93	9.27	9.29	9.31	9.30
60	10.77	8.17	8.57	10.88	9.25	9.29	9.31	9.30
55	10.60	8.13	8.55	10.82	9.23	9.28	9.30	9.30
50	10.42	8.07	8.52	10.75	9.21	9.27	9.30	9.29
45	10.20	8.00	8.48	10.67	9.18	9.26	9.30	9.29
40	9.96	7.94	8.43	10.57	9.14	9.24	9.29	9.28
35	9.65	7.84	8.38	10.44	9.08	9.22	9.29	9.27
30	9.25	7.72	8.32	10.31	9.02	9.19	9.28	9.26
25	8.67	7.57	8.27	10.11	8.96	9.17	9.28	9.25
20	7.92	7.37	8.21	9.83	8.87	9.13	9.27	9.24
17	7.41	7.19	8.10	9.64	8.77	9.09	9.26	9.22
15	6.97	7.03	8.01	9.46	8.69	9.06	9.25	9.21
14	6.70	9.96	7.99	9.35	8.63	9.03	9.24	9.20
13	6.39	6.88	7.96	9.26	8.59	9.02	9.24	9.19
12	6.09	6.78	7.92	9.14	8.55	9.00	9.23	9.18
11	5.72	6.66	7.87	9.03	8.48	8.97	9.23	9.17
10	5.27	6.55	7.79	8.89	8.39	8.93	9.22	9.16
9	4.93	6.44	7.70	8.75	8.29	8.89	9.21	9.14
8	4.39	6.25	7.64	8.56	8.21	8.86	9.20	9.12

Note:  $Q_T$  is the tributary flow for a given flow duration percent (see Appendix C ); A and B are statistically derived regression coefficients

### Appendix H

Carbonaceous and Nitrogenous BOD Usage Rates Used with Various Flow Duration Percents

# Carbonaceous BOD Usage Rates( $K_c$ , 1/days) for Various Flow Duration Percents log $K_c$ = AlogQ<sub>L</sub> + BlogQ<sub>M</sub> + ClogQ<sub>H</sub> + D

288.7-27 8.0-270.6-231.0-222.6-179.0-167.0-27 8.0 231.0 222.6 179.0 167.0 157.0 288.7 270.6 Coef \*\* -5.7437 -5.7437 -2.8988 -6.5026 -5.8225 -4.2911 -4.3514 Α 1.1791 1.9881 1.9784 1.5449 1.5449 В 0.6646 1.1448 C 0.1279 0.1578 0.1239 0.1495 0.1078 0.1169 0.1169 D 6.3309 13.7544 11.5074 9.1577 9.4027 \*\* 12.9137 12.9137 Flow Duration 왕 .3 500 .6070 .4400 .3350 .3430 .4455 .5480 .5480 99.8 99 .3500 .3430 .5480 .5480 .6070 .4400 .3350 .4455 .3345 98 .5919 .4253 .3203 .327 9 .4305 .5330 .5330 .3001 .2736 .27 93 .4306 .4306 97 .4703 .3491 .3 550 96 .2839 .4247 .3213 .2542 .2590 .3241 .3 893 .3 893 95 .2610 .3566 .2765 .2255 .2293 .20 82 .3310 .3310 90 .2040 .1774 .1585 .1601 .2055 .2055 .2130 .1828 .1710 .1463 .1280 .1230 .1235 .1346 .1457 .1457 85 80 .1504 .1125 .1022 .1025 .1027 .1083 .1139 .1139 .0920 75 .1412 .0991 .0938 .0938 .0974 .1009 .1009 .0746 70 .0779 .07% .07 94 .0802 .0809 .0809 .1261 .0713 .0760 .1218 .0734 .0761 .0758 .0759 .0760 65 .0648 .0627 .06 80 .0658 .0658 60 .1130 .06 85 .0669 .0552 .0600 55 .1076 .0574 .0640 .0635 .0618 .0600 50 .1081 .0590 .0601 .0648 .0643 .0626 .0608 .0608 .1080 .0603 .0619 .0652 .0646 .0629 .0611 .0611 45 40 .1061 .0592 .0615 .0640 .0633 .0614 .0594 .0594 .0598 .0606 .0583 .0560 .0560 35 .1026 .0565 .0615 30 .0979 .0524 .0568 .0579 .0570 .0543 .0515 .0515 .0593 .0517 25 .0976 .0540 .0584 .0574 .0546 .0517 20 .0925 .0501 .0567 .0547 .0536 .0504 .0471 .0471 .0438 17 .0889 .0471 .0543 .0521 .0509 .0474 .0438 .0875 .0465 .0543 .0512 .0500 .0464 .0427 .0427 15 14 .0876 .0471 .0553 .0515 .0502 .0466 .0429 .0429 13 .0834 .0429 .0512 .0482 .0469 .0431 .0392 .03 92 12 .07 87 .03 82 .0464 .0444 .0431 .0390 .0350 .0350 .0297 11 .0723 .0320 .0399 .03 81 .0339 .0297 .0393 10 .0666 .0270 .0345 .0350 .0338 .0296 .0253 .0253 9 .0591 .0201 .0278 .0294 .0284 .0243 .0201 .0201 .0527 .0165 .0226 .0250 .0240 .0161 .0161 .0201

Note:  $Q_L$ ,  $Q_M$ , and  $Q_H$  are flows at the Lockport, Marseilles, and Henry gaging stations (see Appendix B )

<sup>\*\*</sup> Regression analysis produced nonsensical results for the carbonaceous coefficients in this reach. The listed K-values are the averages of the up and downstream reach values

# Nitrogeneous BOD Usage Rates( $K_n$ , 1/days) for Various Flow Duration Percents log $K_n$ = AlogQ<sub>L</sub> + BlogQ<sub>M</sub> + ClogQ<sub>H</sub> + D

	291.0- 288.7	288.7- 27 8.0	27 8.0- 270.6	270.6- 231.0	231.0- 222.6	222.6- 179.0	179.0- 167.0	167.0- 157.0
Coef								
A							-1.6308	
В	1.4361	1.4252	1.3600	2.5272	2.5272	2.5476	1.2887	0.6307
С		-0.1558	0.0127	0.0000		-0.1553		0.0602
D	5.4217	2.3569	6.1634	10.6574	10.6574	4.9337	0.2182	0.9829
Flow								
Duration								
%		1001			4440	0016	0.056	1000
99.8	.1877	.1271	.2857	.4110	.4110	.2016	.0 956	.1022
99	.1482	.1126	.2209	.4110	.4110	.1625	.0912	.0944
98	.1274	.1038	.1875	.3149	.3149	.1409	.0881	.0 897
97	.1145	.0979	.1671	.2609	.2609	.1269	.0858	.0864
96	.1101	.0968	.1597	.2434	.2434	.1224	.0862	.0 855
95	.1015	.0925	.1463	.2109	.2109	.1149	.0 845	.0832
90	.07 97	.0808	.1129	.1376	.1376	.0902	.07 91	.0764
85	.0665	.0726	.0931	.1000	.1000	.0744	.0745	.0716
80 75	.0590	.06 82 .0665	.0818	.0809	.0809	.0666	.0727 .0722	.06 88 .0676
	.0559	.0621	.0814	.0735	.0599	.0637	.0722	.0649
70 65	.0498	.0621	.06 81	.0599	.0599	.0568	.0692	.0645
60	.0489	.0622	.0618	.0573	.0573	.0536	.0702	.0634
55	.0458	.0595	.0592	.0520	.0320	.0526	.0700	.0627
55 50	.0441	.0595	.0592	.0510	.0510	.0526	.0702	.0627
45	.0455	.0640	.0623	.0510	.0510	.0605	.0729	.0659
40	.0403	.0655	.0623	.0544	.0544	.0632	.0782	.0651
35	.0472	.066 8	.0618	.0544	.0542	.0659	.0815	.0662
30	.0471	.067 8	.0603	.0528	.0528	.06 80	.0843	.0665
25	.0486	.0720	.0626	.0572	.0572	.0763	.0903	.06 84
20	.0485	.0745	.0616	.056 9	.0569	.0819	.0958	.06 93
17	.0480	.07 56	.0605	.0559	.0559	.0846	.0989	.06 97
15	.0485	.0776	.0608	.0570	.0570	.0 889	.1025	.0705
14	.0494	.07 93	.0617	.0588	.0588	.0928	.1050	.0712
13	.0476	.07 82	.0592	.0551	.0551	.0 906	.1053	.0706
12	.0453	.0764	.0559	.0504	.0504	.0872	.1047	.06 95
11	.0417	.0730	.0512	.0436	.0436	.0804	.1026	.0676
10	.03 85	.06 99	.0470	.0379	.0379	.0744	.1005	.0658
9	.0342	.0654	.0414	.0308	.0308	.0661	.0973	.0632
8	.0306	.0614	.0367	.0253	.0253	.0591	.0944	.0608

Note:  $Q_L$ ,  $Q_M$ , and  $Q_H$  are, respectively, the flows at the Lockport, Marseilles, and Henry gaging stations (see Appendix B ); the regression equations produced unrealistically high values for flows for the 99.8 and 99 percent durations

### Appendix I

Examples of BOD-DO Model Runs for 99.8 Percent Flow Duration at 12°C and 28°C and for 8 Percent Flow Duration at 12°C and 28°C

(River mile points represent SWS designations)

FILE = A	:998PCEN.DAT	Γ		FILE = A	1:998PCEN.	DAT	
MP	DO			MP	DO		
291.00	0.50	248.65	6.16	201 00	0 50		
290.99	0.50	247.08	6.07	291.00 290.99	0.50	248.65	0.42
290.68	0.49	246.78	6.05	290.68	0.50	247.08	0.58
289.94	0.47			289.94	0.46 0.33	246.78	0.62
		246.75	6.07	200.01	0.33		
289.94	0.52	245.90	6.25	289.94	0.39	246.75	0.68
		243.73	6.51	203.51	0.35	245.90	1.26
288.66	0.29	243.42	6.51	288.66	0.00	243.73	2.06
287.23	0.02	242.68	6.49	287.23	0.00	243.42	1.94
286.25	0.00	239.45	6.45	286.25	0.00	242.68	2.13
006.05		239.17	6.44			239.45	1.76
286.25	7.89	020 17		286.25	6.20	239.17	2.36
286.21	7 00	239.17	6.68			239.17	2.81
	7.88	220 62	C C1	286.21	6.18	237.17	2.01
285.82 285.33	7.91 7.85	238.63 236.97	6.61	285.82	6.18	238.63	2.58
284.39	7.61	236.29	6.47	285.33	6.03	236.97	2.15
284.01	7.50	234.30	6.38 6.22	284.39	5.49	236.29	1.92
283.72	7.43	231.06	6.06	284.01	5.27	234.30	2.57
200172	13	231.02	6.05	283.72	5.12	231.06	1.28
281.09	6.76		0.03	281.09	2 72	231.02	2.70
280.47	6.65	231.02	8.71	280.47	3.73 3.54		
278.30	6.43	229.63	8.71	278.30	3.20	231.02	6.00
278.12	6.40	228.85	8.65	278.12	3.16	229.63	4.60
277.82	6.36	226.50	8.49	277.82	3.10	228.85	4.51
276.96	6.21			276.96	2.89	226.50	4.28
076 06		226.50	8.49			226 50	4 20
276.96	6.24	004 00		276.96	2.97	226.50	4.30
276.22	F 00	224.89	8.40			224.89	4.07
273.56	5.92 4.99	223.35 222.60	8.30	276.22	1.85	223.35	3.83
272.90	4.85	222.21	8.27	273.56	2.31	222.60	3.77
2,2,50	4.03	222.21	8.26	272.90	0.00	222.21	3.74
272.90	5.47	220.10	8.19	272.90	0 20		
				272.90	0.20	220.10	3.63
272.41	5.19			272.41	0.00		
272.19	5.07			272.19	0.00		
271.67	4.69			271.67	0.00		
271.52	4.57			271.52	0.00		
271.52	9.27			271.52	6.37		
270.64	9.15			000 51			
270.23	9.08			270.64	5.91		
267.09	8.43			270.23	5.66		
265.00	7.99			267.09 265.00	3.75		
263.67	7.72			263.67	2.74 2.23		
263.52	7.70			263.52	2.18		
				203.32	2.10		
263.52	7.70			263.52	2.20		
262.75	7.57			262.75	1.80		
261.58 257.97	7.40			261.58	2.18		
257.97	6.98 6.76			257.97	0.39		
254.35	6.60			256.00	2.43		
252.97	6.45			254.35	0.00		
252.42	6.40			252.97	2.82		
				252.42	0.00		
250.01	6.24			250.01	0.24		

FILE = A: Ts = 12	8PCEN.DAT			FILE = A:: Ts = 28	8PCEN.DAT		
MP	DO			MP	DO		
291.00	0.50	248.65	9.78	291.00	0.50	248.65	7.06
290.99	0.50	247.08	9.77	290.99	0.50	247.08	7.02
290.68	0.51	246.78	9.76	290.68	0.50	246.78	7.01
289.94	0.53			289.94	0.52		
200.01	0.55	246.78	10:20			246.78	7.40
289.94	1.12			289.94	1.11		
		246.75	10.20			246.75	7.40
288.66	1.13	245.90	10.20	288.66	1.09	245.90	7.39
287.23	1.15	243.73	10.19	287.23	1.06	243.73	7.38
286.25	1.18	243.42	10.19	286.25	1.03	243.42	7.38
		242.68	10.18			242.68	7.36
286.25	8.20	239.45	10.15	286.25	6.40	239.45	7.29
		239.17	10.15			239.17	7.28
286.21	8.20			286.21	6.40		
285.82	8.20	239.17	9.84	285.82	6.40	239.17	7.53
285.33	8.20			285.33	6.38		
284.39	8.17	238.63	9.84	284.39	6.30	238.63	7.52
284.01	8.15	236.97	9.83	284.01	6.25 6.22	236.97	7.49
283.72	8.14	236.29	9.83	283.72	0.22	236.29	7.48
201 00	0 04	234.30	9.83 9.83	281.09	5.94	234.30 231.06	7.44 7.41
281.09	8.04	231.06 231.02	9.83	280.47	5.88	231.00	7.41
280.47	8.02	231.02	9.03	278.30	5.78	231.02	/ • 11
278.30	7.98 7.97	231.02	10.42	278.12	5.76	231.02	7.64
278.12 277.82	7.96	229.60	10.42	277.82	5.74	229.60	7.63
276.96	7.92	228.85	10.41	276.96	5.63	228.85	7.60
270.50	7.52	226.50	10.39			226.50	7.52
276.96	7.81			276.96	5.67		
		226.50	10.21			226.50	7.58
276.22	7.77			276.22	5.58		
273.56	7.69	224.89	10.20	273.56	5.34	224.89	7.53
272.90	7.68	223.35	10.18	272.90	5.32	223.35	7.48
		222.66	10.17	070 00	C 10	222.66	7.46
272.90	7.66	222.21	10.17	272.90	6.49	222.21	7.45
0.00 41	7 66	000 10	10 10	272.41	6.47	220.10	7.30
272.41	7.66	220.10	10.12	272.11	6.46	220.10	7.30
272.09 271.67	7.66 7.67			271.67	6.43		
271.57	7.67			271.52	6.42		
2/1.52	7.07				***		
271.52	10.02			271.52	7.50		
270.64	10.02			270.64	7.49		
270.23	10.02			270.23	7.48		
267.09	9.98			267.09	7.40		
265.00	9.96			265.00	7.35		
263.67	9.95			263.67	7.31		
263.52	9.95			263.52	7.31		
263.52	9.90			263.52	7.38		
262.75	9.90			262.75	7.36		
261.58	9.89			261.58	7.33		
257.97	9.86			257.97	7.26		
256.00	9.85			256.00	7.22		
254.35	9.83			254.35	7.19		
252.97	9.82			252.97	7.16		
252.42	9.82			252.42	7.15		
250.01	9.80			250.01	7.09		

### Appendix J

The BOD-DO Model Program Written in BASIC

#### DOBOD MODEL PROGRAM

The  $\underline{\text{DOBOD}}$  program is a direct translation from the original program to the  $\underline{\text{BASIC}}$  program language. The original was written by T. A. BUTTS for the Wang 720C. The translated program differs from the original in that:

- 1. the input data is read from sequential files stored on disks
- 2. The check of the height of dam has been changed to 4.55(step 1110)
- 3. The various data manipulations required in the Wang program to prevent loss of data and computations have been eliminated.
- 4. The check value in the series expansion has been set at 0.0008805 (step 650).
- 5. The results are sent to the printer instead of the terminal.

There are two versions of the <u>DOBOD</u> program--i) uncompiled and 2) compiled. Both versions reside in the subdirectory <u>PROGRAM</u> as <u>DOBOD.BAS</u> (uncompiled) and <u>DOBQD.EXE</u> (compiled). The compiled version runs several times faster than the uncompiled. However, the user must be familiar with IBM PC operation to run either program. The hardware system used in the development of the program was an <u>IBM XT</u> and an <u>EPSON LX-80</u> printer. The program should work on any equipment compatible to the IBM and EPSON.

To run the compiled program do:

- 1) Boot-up the IBM in the usual manner.
- 2) Turn on printer.
- 3) Change to the subdirectory PROGRAM by CD\PRoGRAM (enter)
- 4) Insert data disk into floppy slot.
- 5) Type <u>DOBOD</u> (enter).
- 6) Enter the data asked for at the prompts.

7) Repeat steps 4 (when necessary), 5 and 6 for all sets of data.

Following is a copy of the DOBOD program:

10 REM	DOBOD MODEL	
20 REM The following is a list	of the parameters used	and their definitions.
30 REM Initial Input	Sub-section Input	Re-initialization
40 REM		
50 REM MP=river mile @ start	MP=river mile @ end	
60 REM tl=TOT @ start (days)	t2=TOT @ end (days)	
70 REM DOac=DO @ start (mg/l)	H=Avg. depth (feet)	
80 REM Q1=Flow @ start (cfs)	Qa=Avg. flow (cfs)	
90 REM Lac = ult.carb. (lbs/day)	G20 = SOD rate (gm/sqm/d)	Lac
100 REM Lan=ult nitro(lbs/day)	PR=Algae +/- (gm/sqm/d)	Lan
110 REM Kc = carb rate $(/day)$	y) Q2=Flow 8 end (cfs)	Kc
120 REM t0=Nit lag time (days)	Qt=Trib flow (cfs)	
130 REM Kn=Nitro rate (/day)		Kn
140 REM Tr=Ref temp (deg Cel)	A=W0 factor @ dam	
150 REM	B=Dam aeration factor	
160 REM	HD=Height of dam (feet	)
170 REM	CODE= 1 input more data	a; 2 re-initialize
180 REM	DEFINE THE FUNCTIONS U	SED
190 DEF FNKC20 (T) =	L.047^(T-20) 'c	onvert carbonaceous rate

```
200 DEF FNKN20(T) = 1.097^(T-20) 'convert nitrogenous rate 10-22 deg Celsius
210 DEF FNKN22(T) = 1.203*(.877^ (T-22)) 'convert nitro rate 22-30 deg Celsius
220 DEF FNKA20(T) = 1.024^{\circ} (T-20)
                                                           'convert reaeration rate
230 DEF FNL20(T) = .02*T+.6
                                                                   'convert ultimate
240 DEF FNDOSAT(T) = 14.652-.41022*T+.007991*T^2-7.7774E-05*T^3 'compute DOsat
250 DEF FNMGE3(H) =
                             13.94*(LOB(H))-7.45
                                                          'compute M for H>=3 feet
260. DEF FNMLT3(H) = .721*H+2.279
                                                            'compute M for H<3 feet
270 DEF FNK(H,M,T) = (6.2918E-05/H^2)*M*(1.1^(T-20)) 'compute K for series \Leftrightarrow:p
280 REM_____DATA INPUT FROM DISK____
290 ON ERROR GOTO 1270
300 INPUT "Enter A: (filename. ext) of datafile used"; NAM*
310 INPUT "Enter Simulation Temperature-Ts"; TS
320 LPRINT "FILE = "; NAM$
330 LPRINT "Ts = ";TS:LPRINT
340 LPRINT "MILEPOINT", "DO":LPRINT
350 OPEN "I", #1,
                                                                    'open data file
                                         NAMŚ
360 INPUT#i, MP, Tl, DOAC, Ql, LAC, LAN, KC, TO, KN, TR
                                                                          'Initialize
370 LPRINT USING "####.##"; MP, DOAC
380 \text{ AAA} = \text{Tl}
                                                     'Set variable for SOD & ALGAE
           INPUT#1,MP,T2,H,QA,G20,PR,02,QT,DOTC,A,B,HD,CODE 'data input
400 REM____
            ____COMPUTATIONS___
410 KC20=KC/FNKC20(TR)
                                      'Convert KC (reference temperature) to KC20
420 KCS = KC20*FNKC20(TS) 'Convert KC20 to KCS (simulation temperature)
430 REM -____Convert KN (reference temperature) to KN20_____
440 IF TR> = 22 THEN KN20 = KN/FNKN22 (TR) ELSE KN20 = KN/'FNKN20 (TR)
450 REM_____Convert KN20 to KNS (simulation temperature)___
460 IF TR>=22 THEN KNS = KN20*FNKN22 (TS) ELSE KNS = KN20*FNKN20(TS)
470 LACS = LAC*FNL20(TS) 'convert ultimate @ 20 to ultimate @ simulation-
480 REM_____check for nitrogenous demand and adjust variables if needed____
490 IF KNS <=0 THEN 500 ELSE IF (DOA-2)>0 THEN 500 ELSE T0=T2
500 KCT = KCS*(T2-T1) 'compute carbonaceous exponent 
510 LCUSED = LAC*(1-E)(P(-KCT)) 'carbonaceous use between Tl and T2 
520 KNT = KNS*(T2-T1-T0) 'compute nitrogenous exponent
520 \text{ KNT} = \text{KNS*}(T2-T1-T0)
530 IF KNT <0 THEN KNT = 0
                                                  'nitrogenous lag time > (T2-T1)
540 \text{ LNUSED} = \text{LAN*}(1-\text{EXP}(-\text{KNT}))
                                               'nitrogenous use between Tl and T2
550 DOU = LCUSED + LNUSED
                                                       'biological use in sub-reach
560 REM_____calculate mix time time (M) for depth (H)____
570 IF H >= 3 THEN M = 13.94*LOG(H)-7.45 ELSE M = .721*H+2.279
580 \text{ MIXES} = 1440*(T2-T1)/M
                                                'number of mixes between Tl and T2
590 REM_____compute K for (H) in feet and (M) in minutes_____
600 \text{ K} = (6.2918E-05/(H*H))*(1.1^(TS-20))*M
610 REM___
              ____series expansion of e^ (-K(2N-1)^2)/(2N-1)^2____
620 \text{ SUM} = 0
630 FOR I = 1 TO 1000
640 AA = (2*I-1)^2:BB = EXP(-K*AA) : CC = BB/AA:SUM = SUM + CC
650 IF CC <.0000005 GOTO 670
660 NEXT I
670 SATDO = FNDOSAT(TS) 'saturation DO @ simulation temperature 'mg/r
680 R0 = 100-81.06*SUM '% DO absorbed/mix @ zero initial DO
690 R = R0/100
                                                   'DO absorbed/mix @ zeroinitial DO
690 R = RU/IUU

700 E = 5.39136*QA*SATDO 'avg.saturation DO III ICCO.'
710 F = E*MIXES*R 'partial computation of Gannon's equation 'convert DOA (mg/l) to (lbs/day)
730 REM___
                               SOD USE
740 \text{ GS} = G20*FNKC20(TS)
                                                'SOD rate § simulation temperature
750 GPRIME = 3.2B*GS*(T2-AAA)/H
                                                                       'SOD in reach
                            GPRIME*QA*5.39136
                                                              'SOD in reach-lbs/day
760 SODUSED =
770 DOU = DOU + SODUSED
                                                              'use in reach -lbs/day
```

```
____ALGAE USE__
780 REM_
790 PRS = PR*FNKC20(TS)
                                         'Algae rate § simulation temperature
800 PRPRIME = PRS*(T2-AAA)/H
                                                            'Algae use in reach
810 PRUSED = 5.39136*QA*PRPRIME
                                                   'Algae use in reach--lbs/day
             _____Add algae use if respiring; subtract if producing
830 IF PR <0 THEN DOU=DOU+PRUSED ELSE DOU=DOU-PRUSED
850 D = DOA-DOU/2 'DO remaining § end of reach--no reaeration--lbs/day
860 X = 0
870 DEFICIT = (1-D/E)
                                                                'Oxygen deficit
                       'amt of oxygen absorbed in reach--Gannon equation
880 DOR = DELLO-

890 DON = DOA+DOR-DOU

DON/(5.39136*01)
880 DOR = DEFICIT*F
                      DOA+DOR-DOU 'net DO @ end of reach~lbs/day DON/(5.39136*01) 'net DO @ end of reach-mg/l
910 IF DONC <0 THEN DONC=0
920 X = X+1
930 IF X >1 GOTO 970
940 D = \langle DOA + DON \rangle / 2
                               'replace (DOA-DOU/2) with (DOA+DON)/2--lbs/day
                      'replace (DOA-DOU/2) with (DOA+DON)/2--108/day
'replace initial DO in reach with DOnet--lbs/day
950 DOAC = DONC
960 GOTO 870
970 IF ABS(DONC-DOAC)>.05 GOTO 940 'compute DOnc until difference <0.05
980 Y = 5.39136*(Q2-Q1)\#DONC+DON 'dissolved oxygen-lbs/day
990 DOAC = DONC
1000 LPRINT USING "####.##"; MP, DOAC
1020 IF QT = 0 GOTO 1090
1030 DOTL = 5.39136*OT*DOTC
                                        'convert tributary DO to lbs/day
1040 IF Y < 0 THEN DON=0
1050 DOXC = (DOTL+Y)/(5.39136*(Q2+QT)) 'DO concentration after trib-mg/l
1060 IF DOXC =< 0 THEN DOAC = DOAC ELSE DOAC = DOXC
1070 LPRINT; LPRINT USING "####.##"; MP, DOAC
1080 REM___
                           ____INFLUENCE OF DAM__
1090 IF HD = 0 GOTO 1160
1100 \text{ HD} = \text{HD}/3.28083
                                    'convert dam height from feet to meters
1110 IF HD >4.55 THEN HD=4.55
1120 DR = 1+.38\#A*B*HD*<1-.11*HD)*(1+.046*TS)
                                                                 'Deficit ratio
1130 DOXD = SATDO-((SATDO-DONC/DR) 'DO concentration downstream of dam--mg/l
1140 IF HD =0 THEN DOAC=DOAC ELSE DOAC=DOXD
1150 LPRINT: LPRINT USING "###.##"; MP, DOAC
1160 \text{ AAA} = T2
1170 IF CODE=2 THEN GOTO 1190 ELSE GOTO 390
                         ____RE-INITIALIZE___
1180 REM____
1190 INPUT#1, LAC, LAN, KC, KN
1200 T1=T2
1210 AAA=T1
1220 Q1=Q2
1230 T0=T2
1240 LPRINT
1250 GOTO 390
                       _____CLOSE DATA FILE; TERMINATE_____
1270 IF ERR = 62 THEN CLOSE #1:LPRINT CHR$(27)CHR$(12)
1280 END
```

### CREATION OF SEQUENTIAL DATA FILES

There are two common methods of storing information on a diskette. The packed binary format is used to store (code) information for random access files. These are the type of files used in spreadsheets and relational data base management programs. ASCII (American Standard

 $\underline{\mathtt{C}}\mathtt{ode}$  for Information Interchange) format is used to store (code) information for sequential files.

The  $\underline{\text{DOBOD}}$  program was written to read data stored (coded) on a diskette as a  $\underline{\text{sequential}}$  file. This requires that the data files be generated by a program that stores data in the ASCII format.  $\underline{\text{Word}}$  Processing programs are programs whose output is in the ASCII format.

PC-WRITE is such a word processing program and is located in the subdirectory  $P\underline{CW}$ . It can be accessed from the root directory with the command  $\underline{CD}\underline{PCW}$  <enter>. The  $\underline{Tutorial}$  and  $\underline{Quick}$   $\underline{Guide}$  for the PC-WRITE program are available within the Water Quality Section. No discussion of how to use this program will be presented here. It is assumed the user will be skilled in PC-WRITE.

Data for the  $\underline{\text{DOBOD}}$  program is of three catagories; 1)  $\underline{\text{Initialization}}$  (one record), 2)  $\underline{\text{Input}}$  (one or more records) and 3)  $\underline{\text{Re-initialization}}$  (one record). Individual inputs of each record  $\underline{\text{must be}}$  separated by a comma and no blank spaces are allowed.

For the  $\underline{\text{Initialization data record}}$  the following individual inputsare:

Data Types	Symbol
River Mile @ start of sub-section Time-of-travel (days) Dissolved Oxygen (mg/L) Discharge of river (cfs) Ultimate Carbonaceous (lbs/day). Ultimate Nitrogenous (lbs/day) Carbonaceous rate (/day) Nitrogenous Lag Time (days) Nitrogenous rate (/day)	$\begin{array}{c} \text{MP} \\ \textbf{t}_1 \\ \text{DO}_{ac} \\ \textbf{Q}_1 \\ \textbf{L}_{ac} \\ \textbf{L}_{ac} \\ \textbf{k}_c \\ \textbf{t}_0 \\ \textbf{k}_n \end{array}$
Reference temperature °Cel	$T_r$

For the Input record(s) the following individual inputs are:

<u>Data Types</u>	Symbol
River Mile @ end of sub-section	MP
Time-of-travel @ end	$t_2$
Avg. depth of river (feet)	H
Avg. discharge in sub-sect. (cfs)	Q <sub>?</sub>
SOD rate (gm/m²/day)	$G_{20}$
Algae $+/- (gm.m^2/day)$	PR
"Discharge of river @ end (cfs)	$Q_2$
Tributary discharge (cfs)	Qt.
Tributary DO (mg/L)	DO <sub>tc</sub>
Water Quality Factor @ dam	A
Dam aeration factor	В
Height Df dam (feet)	$H\!D$
Program control (1 = input more	CODE
<pre>data; 2 = re-initialization)</pre>	

For the  $\underline{\text{Re-initialization record}}$  the following individual inputs are:

```
Data Types
                Ultimate Carbonaceous (lbs/day)
                                                    L_{ac}
                Ultimate Nitrogenous (lbs/day)
                                                    Lan
                Carbonaceous rate (/day)
                                                    k.
                Nitrogenous rate (/day)
     Following is a copy of the file 70PCEN.DAT showing the format of the
data entry:
291.00,0,.5,3340,79594,215862,.126,0,0,20
290.99,.00041,15.10,3340,1.0,0,3340,0,0,0,0,0,1
290.68,.01929,14.95,3343,1,0,3345,0,0,0,0,0,1
289.94,.07858,15.17,3352,1,0,3357,103,11.02,0,0,0,2
123478,222033,.078,0
288.66,.18758,11.59,3472,3.5,0,3481,0,0,0,0,0,1
287.23,.31938,16.72,3494,3.5,0,3508,0,0,0,0,0,1
286.25,.51969,12.43,3515,3.5,0,3521,0,0,1.1,1.87,33.6,2
128895,231859,.078,0
286.21,.52217,2.52,3522,3.5,0,3522,0,0,0,0,0,1
285.82,.53338,3.42,3527,.5,0,3528,0,0,0,0,0,1
285.33,.56359,6.72,3534,2.0,0,3536,0,0,0,0,0,1
284.39,.65924,10.11,3544,3.5,0,3551,0,0,0,0,0,1
284.01,.70106,6.91,3555,3.5,0,3558,0,0,0,0,0,1
283.72,.73099,9.77,3561,3.5,0,3562,0,0,0,0,0,2
126949,231882,.078,0
281.09,1.11859,9.00,3583,3.0,0,3606,0,0,0,0,0,1
280.47,1.20051,10.65,3611,3.0,0,3616,0,0,0,0,0,1
278.30,1.41943,11.42,3635,2.5,0,3651,0,0,0,0,0,1
278.12,1.44391,13.04,3654,3.0,0,3654,0,0,0,0,0,1
277.82,1.48455,11.39,3658,3.0,0,3659,0,0,0,0,0,1
276.96,1.60699,8.02,3668,3.5,0,3673,84,8.26,0,0,0,2
127775,237371,.075,0
276.22,1.71756,7.64,3765,3.5,0,3770,0,0,0,0,0,1
273.56,2.08307,11.37,3793,3.5,0,3813,0,0,0,0,0,1
272.90,2.16558,11.64,3819,2.0,0,3824,1220,8.61,0,0,0,2
161597,271826,.075,0
272.41,2.23423,13.57,5048,3.0,0,5052,0,0,0,0,0,1
272.19, 2.26605, 15.64, 5056, 3.0, 0, 5056, 0, 0, 0, 0, 1
271.67, 2.36944, 15.07, 5060, 3.0, 0, 5064, 0, 0, 0, 0, 1
271.52,2.40347,14.44,5066,3.0,0,5067,0,0,1.56,1.52,20.4,2
150894,271826,.08,0
270.64, 2.45239, 5.64, 5074, .5, 0, 5081, 0, 0, 0, 0, 1
270.23,2.47695,11.09,5088,.5,0,5088,0,0,0,0,0,
267.09, 2.69170, 8.82, 5113, 1.5, 0, 5139, 0, 0, 0, 0, 0, 1
265.00,2.85194,10.20,5158,1.5,0,5174,0,0,0,0,0,1
263.67,2.95816,10.30,5184,1.5,0,5195,0,0,0,0,0,1
263.52,2.96947,10.81,5198,1.5,0,5198,21,9.3,0,0,0,2
145702,273779,.08,.06
262.75,3.03117,11.07,5226,1.5,0,5232,0,0,0,0,0,1
261.58,3.12116,10.05,5241,1.5,0,5251,0,0,0,0,0,1
257.97,3.37550,10.10,5279,1-5,0,5310,0,0,0,0,0,1
256.00,3.53408,10.22,5325,1.5,0,5342,0,0,0,0,0,1
254.35,3.66370,9.78,5355,1.5,0,5369,0,0,0,0,0,1
252.97,3.79320,11.19,5381,1.5,0,5392,0,0,0,0,0,1
252.42,3.84104,11.66,5397,1.5,0,5401,0,0,0,0,0,2
 136548,259361,.08,.06
250.01,4.06617,11.22,5422,1.5,0,5441,0,0,0,0,0,1
```

Symbol

248.65,4.19867,10.57,5453,1.5,0,5463,0,0,0,0,0,1

```
247.08, 4.36399, 11.96, 5476, 1.5, 0, 5489, 0, 0, 0, 0, 0, 1
246.78, 4.40399, 12.61, 5494, 1.5, 0, 5494, 0, 0, 0, 0, 0, 2
130686,252685,.08,.06
246.75, 4.40465, .86, 5494, .5, 0, 5494, 0, 0, 0, 0, 0, 1
245.90,4.41578,1.32,5502,.5,0,5508,0,0,0,0,0,1
243.73,4.45748,2.96,5553,.5,0,5593,0,0,0,0,0,1.
243.42,4.47560,8.76,5599,1.5,0,5604,0,0,0,0,0,1
242.68, 4.52874, 9.26, 5614, 1.5, 0, 5630, 0, 0, 0, 0, 0, 1
239.45,4.75018,10.03,5684,1.5,0,5742,0,0,0,0,1
239.17,4.77623,10.76,5752,1.5,0,5752,565,10.97,0,0,0,2
182050,302260,.08,.06
238.63,4.82620,12.49,6328,1.5,0,6336,0,0,0,0,0,1
236.97,4.94727,10.73,6367,1.5,0,6394,0,0,0,0.0,1
236.29,5.02208,12.42,6408,1.5,0,6418,0,0,0,0,0,1
234.30,5.19454,10.33,6454,1.5,0,6487,0,0,0,0,0,1
231.06,5.47399,11.27,6549,1.0,0,6600,0,0,0,0,0,1
231.02,5.48212,15.99,6602,1.0,0,6602,0,0,1.25,.914,17.7,1
229.63,5.55401,5.98,6624,.5,0,6650,0,0,0,0,0,1
228.85,5.60122,10.81,6665,2.0,0,6677,0,0,0,0,0,1
226.50,5.74070,10.09,6718,2.0,0,6759,51,9.28,0,0,0,2
171829,287357,.079,.06
224.89,5.85693,11.61,6839,1.5,0,6867,0,0,0,0,0,1
223.35,5.98877,14.77,6869,1.5,0,6920,0,0,0,0,0,1
222.66,6.03242,14.02,6935,1.5,0,6944,0,0,0,0,0,1
222.21,6.05453,11.38,6953,1.5,0,6960,0,0,0,0,0,2
166259,282198,.08,.056
220.10,6.17843,10.12,7000,1.5,0,7034,0,0,0,0,0,1
```

After the sequential data file has been generated by the word processing program the file is copied to the diskette using the command:

#### COPY (filename.ext)/V A:

Naming the file (filename.ext) uses the conventions listed in the  $\underline{DOS}$  manual. It is suggested that the (ext) be  $\underline{.DAT}$  signifing that the file is a data file. The /V portion of the copy command is an instruction that causes the  $\underline{IBM}$  XT to verify that the file is copied correctly to the diskette.

This program description and instructions were written using PC WRITE and is stored in the PCW subdirectory as the file DOBOD.TXT.

--D . H. SCHNEPPER

## Appendix K

Data Used to Develop Stepwise Regression Relationships

106

Data Collected at Brandon Road Which Was Used to Develop Stepwise Regression Equations Relating Either the DO
Percent Saturation Below the Dam, the Deficit Ratio (r), the Dam Aeration
Coefficient (b), or the Beta-factor (3) to Various Physical and Water Quality Parameters

1986	No. gates	Total head	Disch	arge (cfs)	a	COD	MBAS	SS	Algae (	no/ml)	Temp	DO (%	sat)	r	b	
Date	open	loss (ft.)	Total	Head gates	(eg 2)	mg/1	mg/1	mg/1	Above	Below	°C	Above	Below	(eg. 1)	(eg. 2)	ß
7/09 p.m.	9	34.12	7,976	800	1.03	24.8	0.05	29	210	380	24.8	45.4	90.0	5.43	2.39	1.001
7/16 a.m.		33.72	3,250	330	1.18	17.8	0.07	26	267	302	25.2	55.1	85.5	3.04	0.96	1.005
7/16  p.m.	8	34.22	7,118	1450	1.15	16.2	0.03	48	403	437	25.2	31.7	95.1	4.97	1.96	1.111
7/23 a.m.		34.04	6,826	690	0.98	33.1	0.11	16	363	876	25.6	31.3	92.6	4.79	1.70	1.028
7/23 p.m.	8	34.12	6,625	670	1.02	16.1	0.09	10	149	105	26.1	39.3	91.0	5.32	1.97	1.030
7/29 p.m.	8	34.03	6,273	630	1.09	24.3	0.09	19	649	92	27.2	41.0	89.3	5.26	2.06	1.006
8/07 a.m.		33.97	4,869	490	1.02	17.6	0.07	8	662	204	25.4	29.5	89.0	4.66	1.59	1.055
8/07 a.m.	7	34.02	5,553	560	1.15	17.6	0.07	7	53	267	24.6	32.5	88.1	4.36	1.53	1.043
8/14 a.m.	6	34.06	5,121	520	1.15	26.6	0.07	14	128	166	25.3	42.5	88.4	4.46	2.00	1.017
8/14 p.m.	7	34.12	5,734	580	0.93	20.2	0.10	16	281	281	25.2	44.8	89.0	4.46	1.62	1.018
8/20 a.m.	6	33.96	4,822	490	1.18	20.0	0.09	12	229	1117	25.5	41.0	88.2	4.83	1.78	0.968
8/27 a.m.	8	33.97	6,288	630	1.24	20.9	0.09	17	286	626	24.7	38.9	90.7	4.76	2.00	1.006
9/05 a.m.	5	34.07	4,369	440	1.06	23.5	0.06	24	502	586	25.6	43.1	86.9	4.31	1.62	1.001
9/11 p.m.	7.	34.03	5,650	570	1.16	20.9	0.06	12	265	428	22.3	42.4	91.6	4.67	2.05	1.049
9/17 a.m.	6	33.70	4,416	1300	1.19	15.4	0.07	22	170	164	21.4	44.4	100.0	4.91	2.32	1.104
9/17 p.m.	5	33.89	3,937	400	1.09	16.9	0.08	18	372	571	21.0	31.8	79.4	4.43	1.76	0.934
9/24 a.m.	13	33.94	9,051	3600	1.14	27.8	0.07	60	208	445	22.2	62.2	99.5	3.36	1.14	1.154
9/24 p.m.	18	34.07	13,230	4000	1.00	29.5	0.07	71	347	1056	22.1	39.7	94.9	4.81	2.13	1.094

Note: "Above" and "Below" refer to above and below the dam; DO (% sat.) DO saturation concentrations corrected for for elevation by multiplying equation 6 values by 0.981.