


Accepted Manuscript

Potential benefits of digital fabrication for complex structures: Environmental assessment of a robotically fabricated concrete wall

Isolda Agustí-Juan, Florian Müller, Norman Hack, Timothy Wangler, Guillaume Habert



PII: S0959-6526(17)30698-4

DOI: [10.1016/j.jclepro.2017.04.002](https://doi.org/10.1016/j.jclepro.2017.04.002)

Reference: JCLP 9353

To appear in: *Journal of Cleaner Production*

Received Date: 13 December 2016

Revised Date: 29 March 2017

Accepted Date: 1 April 2017

Please cite this article as: Agustí-Juan I, Müller F, Hack N, Wangler T, Habert G, Potential benefits of digital fabrication for complex structures: Environmental assessment of a robotically fabricated concrete wall, *Journal of Cleaner Production* (2017), doi: 10.1016/j.jclepro.2017.04.002.

This is a PDF file of an unedited manuscript that has been accepted for publication. As a service to our customers we are providing this early version of the manuscript. The manuscript will undergo copyediting, typesetting, and review of the resulting proof before it is published in its final form. Please note that during the production process errors may be discovered which could affect the content, and all legal disclaimers that apply to the journal pertain.

1 **Potential benefits of digital fabrication for complex structures:** 2 **Environmental assessment of a robotically fabricated concrete wall**

3
4 Isolda Agustí-Juan ^{a*}, Florian Müller ^a, Norman Hack ^b, Timothy Wangler ^c, Guillaume Habert ^a

5 ^a Chair of Sustainable Construction, IBI, ETH Zürich, Stefano-Franscini-Platz 5, 8093 Zürich, Switzerland.

6 ^b Chair of Architecture and Digital Fabrication, ITA, ETH Zürich, Stefano-Franscini-Platz 5, 8093 Zürich, Switzerland.

7 ^c Physical Chemistry of Building Materials group, IfB, ETH Zürich, Schafmattstrasse 6, 8093 Zürich, Switzerland.

8 * Corresponding author. E-mail address: agusti@ibi.baug.ethz.ch (Isolda Agustí-Juan).

9

10 **Abstract**

11 Digital fabrication represents innovative, computer-controlled processes and technologies with the
12 potential to expand the boundaries of conventional construction. Their use in construction is currently
13 restricted to complex and iconic structures, but the growth potential is large. This paper aims to
14 investigate the environmental opportunities of digital fabrication methods, particularly when applied to
15 complex concrete geometries. A case study of a novel robotic additive process that is applied to a wall
16 structure is evaluated with the Life Cycle Assessment (LCA) method. The results of the assessment
17 demonstrate that digital fabrication provides environmental benefits when applied to complex
18 structures. The results also confirm that additional complexity is achieved through digital fabrication
19 without additional environmental costs. This study provides a quantitative argument to position digital
20 fabrication at the beginning of a new era, which is often called the Digital Age in many other
21 disciplines.

22 **Keywords**

23 Digital fabrication, LCA, complexity, concrete, robotic construction, sustainability.

24

25 **1 Introduction**

26 The construction sector is responsible for significant environmental impacts, such as 40% of the
27 energy consumption and greenhouse gas emissions worldwide (UNEP, 2012). But these extremely
28 large impacts represent also opportunities for improvement, and buildings are seen by the main
29 international agencies (UNEP, IPCC) as a key player for carbon mitigation actions (IPCC, 2014). This
30 potential is foreseen as occurring through the implementation of new technologies, such as digital
31 technologies (McKinsey&Company, 2016). Digital technologies are broadly used in the manufacturing
32 industry and the direct production of elements from design information (e.g., 3D printing) has become
33 an essential component of modern product development (Chen et al., 2015). However, digital
34 fabrication in construction is still in its early stage, probably because the construction industry is a
35 highly fragmented, risk-averse sector (Arora et al., 2014). Most construction firms are small, so few of
36 them have the ability to exploit new technologies, which rely on specific knowledge. Learning is done
37 on a project-to-project basis with professionals to develop perceptions and skills from their individual

38 experiences (Gieseckam et al., 2016). This unsystematic process of building up knowledge leads to a
39 reluctance to use unfamiliar technologies and materials (Pinkse and Dommissie, 2009).

40 Finally, the benefits that digital technologies can provide are not clear. Recent publications have
41 highlighted the potential sustainability benefits of additive manufacturing (Ford and Despeisse, 2016;
42 Kohtala, 2015). However, most of these studies focused on small-scale processes. For instance,
43 Kreiger and Pearce (2013) showed that distributed manufacturing through 3D printing has potentially
44 fewer environmental impacts and lower energy demand than conventional manufacturing. Similar
45 results were gathered by Faludi et al. (2015), who highlighted a reduction in waste and energy savings
46 from a smaller machining effort with 3D printing compared to traditional CNC milling. Finally, Gebler et
47 al. (2014) provided a general perspective on 3D printing technologies from an environmental,
48 economic and social perspective. However, very few of these studies were quantitative, and Ford and
49 Despeisse (2016) are pushing for more applied research on the environmental implications of digital
50 fabrication. In particular, its implementation in the construction sector requires quantitative
51 assessments that consider aspects such as the design freedom that is facilitated by additive
52 techniques.

53 The objective of this study is to quantify the environmental benefits that digital fabrication can provide
54 to the construction sector and define for which processes these construction techniques have a clear
55 interest. Digital design and robotic fabrication developments which increase complexity in architecture
56 yet should provide a cost effective method to deal with this structural complexity. Consequently, this
57 study focuses on the environmental assessment of a building element that can be produced with
58 different levels of complexity and a comparison between an additive robotic fabrication technique and
59 traditional building construction techniques. This approach enables us to evaluate the potential
60 environmental benefits of digital fabrication for each level of complexity. Specifically, we perform a
61 comparative assessment of two construction processes (digital fabrication and conventional
62 construction) for different types of concrete walls, from the simplest to the most complex.

63

64 **2 From 3D printing to digital fabrication in architecture**

65 The first three dimensional printing (3DP) technologies arrived during the 1980s to more efficiently
66 fabricate prototypes in the product manufacturing industry. 3DP employs additive manufacturing (AM)
67 processes to create three-dimensional objects by adding consecutive layers of material. These
68 systems can now manufacture end products with the development of new materials and improvements
69 in speed and accuracy based on superior hardware and computer technology (Lipson and Kurman,
70 2013). Nowadays, AM is used across various industries (medicine, aerospace, art, etc.), mainly for
71 prototypes but increasingly for final products (implants, lightweight structures, jewellery, etc.).
72 Computer-controlled manufacturing methods are fundamentally transforming many design and
73 production disciplines, similar to the mechanisation of the textile industry or the introduction of the
74 assembly line. The high flexibility and reduced production costs of digital technologies introduced a
75 new era towards the mass customisation of products (Berman, 2012).

76 3DP has experienced rapid development in recent years, and more materials can now be used in
77 these processes. The size of these technologies has also rapidly increased, showing the potential to
78 build large and complex-shaped structures by printing. As interest in additive manufacturing has
79 grown, research into large-scale processes has begun to reveal potential applications in construction
80 (Feng et al., 2015). The development of digital fabrication in architecture starts from specific projects,
81 in which design aspirations and technological innovations lead to the development of fabrication
82 processes beyond conventional boundaries (Dunn, 2012). Digital fabrication processes at the
83 architectural scale are based on computational design methods and robotic construction processes,
84 which are typically categorised as subtractive or additive fabrication. Specifically, architecture is
85 typically built through material aggregation (assembly, lamination, extrusion, and other forms of 3D
86 printing) in additive fabrication processes, frequently with an industrial robot, which enables the
87 implementation of the additive principle at a large scale (Gramazio and Kohler, 2008).

88 Recent developments in digital technologies and the introduction of computer-controlled additive
89 fabrication in architecture demonstrate strong potential to construct customised complex structures
90 (Gramazio et al., 2014). In particular, the optimisation of concrete structures through digital fabrication
91 is currently being broadly investigated because of the large use of concrete in building construction
92 and the labour costs from formwork preparation (Wangler et al., 2016). For example, the research
93 project “Contour Crafting” at the University of Southern California showed the possible application of
94 layered extrusion technologies for large-scale concrete construction (Khoshnevis et al., 2006).
95 Similarly, Loughborough University applied 3D concrete printing to non-standard geometries to reduce
96 the amount of material, time, waste and need for formwork (Lim et al., 2012). However, some of these
97 technologies have limitations regarding the incorporation of reinforcement during the production
98 process. The project Smart Dynamic Casting (SDC) at ETH Zürich overcame this problem with a novel
99 digital fabrication process for complex concrete structures that enables the implementation of
100 reinforcement during production. SDC uses dynamic slip-forming techniques to fabricate customised,
101 vertically oriented shapes, which would conventionally require custom-made formworks (Lloret et al.,
102 2014).

103

104 **3 Methodology**

105 The selected method for the evaluation of the case study is the Life Cycle Assessment (LCA)
106 framework present in the ISO 14040-44: 2006 standards (ISO, 2006a, b). LCA has been commonly
107 used in many industrial sectors to evaluate the environmental load of processes and products during
108 their life cycle. This method presents a comprehensive, systemic approach for the environmental
109 evaluation, comparison and optimisation of processes (Cabeza et al., 2014). LCA has become a
110 widely used methodology over the past 20 years to evaluate the impacts of materials, construction
111 elements and buildings (Hoxha et al., 2017).

112 European regulations for the promotion of a sustainable built environment highly stress the reduction
113 of energy during the use phase. However, the proportional percentage of embodied energy is
114 increasing as the operational energy demand is further optimised. Recent studies such as Passer et


115 al. (2012) agree that the operational energy is reaching the limit of reduction measures. Further
116 optimisation of the life-cycle impacts of buildings may only occur by lowering the embodied energy of
117 materials (Pacheco-Torgal, 2014). Consequently, we performed a cradle-to-gate analysis, including
118 data from raw material extraction and transport, building materials and digital technologies production,
119 and robotic fabrication (EN 15978 modules: A1-A3, A5). The operation and end-of-life stages were
120 excluded from this case study evaluation.

121 The LCA method was applied in this paper to compare the differences in the environmental impacts
122 between digital fabrication and conventional construction and to understand for which type of projects
123 digital fabrication produces environmental benefits. This case study compared two functional units of
124 reinforced concrete wall with equal functionality and structural performance, including 1 m² of wall that
125 was constructed with digital fabrication techniques and 1 m² of a conventional reinforced concrete
126 wall. Specifically, the LCA comparison was applied to different types of walls, including straight, single-
127 curved and double-curved, to illustrate the possible levels of complexity. Finally, we tested the
128 variability regarding the volume of concrete and steel in the structure in a sensitivity analysis to
129 evaluate the additional benefits of digital fabrication if the process is optimised. The LCA method was
130 implemented in the software SimaPro 8. Because of the Swiss context of this project, Ecoinvent v3.1
131 was used as a database (Weidema B. P., 2013). The Recipe Midpoint (H) v1.12 impact method
132 (Goedkoop et al., 2009) was used. The selected impact categories were climate change (kg CO₂ eq.),
133 ozone depletion (kg CFC-11 eq.), human toxicity (kg 1.4-DB eq.), terrestrial acidification (kg SO₂ eq.),
134 freshwater eutrophication (kg P eq.), terrestrial ecotoxicity (kg 1.4-DB eq.), freshwater ecotoxicity (kg
135 1.4-DB eq.), water depletion (m³), metal depletion (kg Fe eq.) and fossil depletion (kg oil eq.).

136

137 **4 Description of the Mesh Mould construction technique**

138 Contemporary architecture has evolved towards a new culture based on the integration of design,
139 structure and materiality to create complex non-standard surfaces (Rippmann et al., 2012). However,
140 non-standard architecture requires the planning and fabrication of complex and labour-intensive rebar
141 geometries and formworks that are not easy to fabricate with current construction techniques. The
142 research project Mesh Mould from Gramazio Kohler Research at ETH Zürich is a novel construction
143 system that is based on the combination of formwork and reinforcement into one single element that is
144 fabricated on-site. This element is a three-dimensional mesh that is robotically fabricated through
145 bending, cutting and welding steel wires. The mesh acts as the formwork during concrete pouring and
146 as structural reinforcement after the concrete is cured (Hack et al., 2015). The structure is no longer
147 restricted to planarity or single curvature and can be geometrically complex and individually adapted to
148 the forces that act on the mesh (Hack et al., 2013). Figure 1 shows one of the recent prototypes of the
149 Mesh Mould project.



150

151 **Figure 1.** Prototypes of the Mesh Mould structure (Gramazio Kohler Research, ETH Zurich).

152

153 5 Case study

154 The Mesh Mould construction technique was selected as a case study for the following LCA evaluation
 155 because of its formal and functional flexibility, which is adaptable from conventional to highly complex
 156 architectural forms. The Life Cycle Inventory (LCI) of a wall that is fabricated with the Mesh Mould
 157 technique and the LCI of different conventionally constructed reinforced concrete walls are
 158 summarised in this section. We considered a section of 1 m² with a thickness of 20 cm for both types
 159 of walls.

160 5.1 Digitally fabricated wall

161 5.1.1 Concrete


162 The concrete in the Mesh Mould wall is more demanding than that from the conventional technique.
 163 The properties of the concrete influence the protrusion rate through the mesh and the roughness of
 164 the surface. In response to the requirements of the Mesh Mould technique, the Institute of Building
 165 Materials (IFB, ETH Zürich) developed a special concrete mixture that could be optimised for the filling
 166 and trowelling processes (Hack et al., 2015). This mix is described and compared with an ordinary
 167 C25/30 concrete in **Table 1**. The ETHZ IFB concrete was modelled in the LCI using Ecoinvent
 168 processes. The silica fume was considered a by-product from the production of ferrosilicon alloy, and
 169 the allocation of environmental impacts was performed according to an economic distribution (Chen et
 170 al., 2010). Hypothesis on costs and production scheme were taken from Grist et al. (2015). For
 171 modelling the superplasticiser, we used data from different concrete production processes in
 172 Ecoinvent database. An average from different superplasticisers was included due to the unavailability
 173 of LCA data from the superplasticiser developed for the ETHZ IFB concrete (for details, see
 174 supplementary information). The volume of concrete contained in 1 m² of wall was $V_{c,MM} = 0.2 \text{ m}^3$.

175

| Flow | ETHZ IFB | C 25/30 |
|--|-------------------------|-------------------------|
| Ordinary Portland cement | 500 kg/m ³ | 300 kg/m ³ |
| Undensified silica fume | 43.5 kg/m ³ | - |
| Water | 169 kg/m ³ | 190 kg/m ³ |
| Aggregates of grain size 0-4 mm | 705 kg/m ³ | 790 kg/m ³ |
| Aggregates of grain size 4-8 mm | 1,008 kg/m ³ | 1,100 kg/m ³ |
| Polycarboxylate ether superplasticiser | 4.32 kg/m ³ | - |


176 **Table 1.** ETHZ IFB concrete and C25/30 concrete mix composition.

177 The difference in environmental impacts between an ordinary C25/30 concrete and the ETHZ IFB
 178 high-performance concrete mix was investigated in the LCA comparison, which is shown in **Figure 2**.
 179 The graph shows that the difference between the contribution to climate change of 1 cubic meter (m³)
 180 of the two concrete mixtures is significant. The customised mixture contributes approximately 40%
 181 more CO₂ emissions than the conventional concrete. The increased amount of Portland cement (500
 182 kg/m³) is the main cause of this discrepancy, which nearly duplicates the amount within 1 cubic meter
 183 (m³) of C25/30 concrete. In contrast, the analysis through the cement efficiency concept developed by
 184 Damineli et al. (2010), where the environmental impact is expressed in kg CO₂.m⁻³.MPa⁻¹, indicates a
 185 higher CO₂ intensity in the ordinary concrete (**Figure 3**). The ETHZ IFB mix presents a compressive
 186 strength of 60 MPa, which duplicates the strength of the C25/30 concrete. Consequently, less ETHZ
 187 IFB concrete is needed to reach the same structural performance as an ordinary concrete, producing
 188 20% less CO₂ emissions.



189

190 **Figure 2.** Comparison of the climate change impact of 1 cubic meter of C25/30 and ETHZ IFB
 191 concrete.



192

193 **Figure 3.** Comparison of the cement efficiency of 1 cubic meter of C25/30 and ETHZ IFB concrete
 194 (expressed in kg CO₂/m³/MPa).

195 The background data source for performing the LCAs can be found in the supplementary information.

196 5.1.2 Steel mesh

197 Metal wires with a diameter of 3 mm formed the 3D mesh of the digitally fabricated prototypes. The
 198 steel was B500A, which indicates the same tension yield strength $f_{yk} = 500 \text{ N/mm}^2$ as the
 199 reinforcements in a conventional wall but less ductile material. Conventionally, reinforced concrete
 200 walls have a minimum nominal reinforcement $r_{min} = 0.3 - 0.7\%$ of the concrete volume, depending on
 201 the structural normative (CEN, 2004). Because of constraints such as the additional formwork function,
 202 the mesh volume fraction for the digitally fabricated wall was assumed to be $r_{MM} = 0.7\%$. Considering
 203 these data, the total steel mass of 1 m² of wall was calculated as follows:

$$m_{s,MM} = V_{MM} \cdot r_{MM} \cdot \rho_s = 0.2 \cdot 0.007 \cdot 7850 \approx 11 \text{ kg} \quad (1)$$

204 where V_{MM} is the total volume of the wall, r_{MM} is the percentage of contained reinforcement and ρ_s is
 205 the standard density of the steel.

206 5.1.3 Energy

207 The energy demand of the robotic construction process was calculated based on the construction time
 208 of a wall prototype and the power supply of the construction robot. The tool head had a theoretical
 209 building speed of 10 h per 1 m² (volume of 1 m x 1 m x 0.2 m). The robot "In-Situ Fabricator", which
 210 has been developed by the NCCR Digital Fabrication, is electrically powered by lithium-ion batteries
 211 with a total capacity of 5.1 kWh, which enable the robot to operate for 3–4 h without being plugged in
 212 (Dörfler et al., 2016). As a result, the energy consumption during the construction with the Mesh Mould
 213 technique (E_{MM}) was calculated:

$$E_{MM} = P_R \cdot T_{MM} = \frac{5.1}{3} \cdot 10 \approx 17 \text{ kWh} \quad (2)$$

214 where P_R is the power consumption of the robot and T_{MM} is the construction time of the functional unit
 215 of the wall.

216 5.1.4 Digital technologies

217 The embodied energy of the digital technologies was included in the LCI of the Mesh Mould wall,
 218 including the production of the "In-Situ Fabricator" construction robot and an attached tool for welding,
 219 bending and cutting, which are a property of the NCCR Digital Fabrication. The environmental impact
 220 of the robot production was calculated based on its material composition, which is listed in Agustí-Juan
 221 and Habert (2017). In addition, the tool head had an approximate mass of 10 kg and mainly consisted
 222 of aluminium. Because of the uncertainty in the service life of both customised digital technologies, we
 223 assumed a running time of 90,000 hours (Motion Controls Robotics, 2017). Based on the service life

224 and the construction time, we calculated the units of the robot and the tool that were used during the
225 construction of the project:

$$u_R = u_{tool} = \frac{T_{MM}}{T_{DT}} = \frac{10}{90,000} = 1.11 \cdot 10^{-4} \quad (3)$$

226 where u_R and u_{tool} represent the units of the robot and the bending, welding and cutting tool, T_{MM} is
227 the construction time and T_{DT} the lifetime of the digital technologies.


228 5.2 Conventional wall

229 5.2.1 Concrete and reinforcing steel

230 A reinforced concrete wall with a thickness of 0.2 m, as described in the Elementaten-Katalog EAK
231 (CRB, 2011), was taken as a reference. The conventional wall contained the same volume of concrete
232 and steel as the digitally fabricated wall. The concrete was C25/30, which is characterised by a
233 compression strength $f_{ck} = 25 \text{ N/mm}^2$. The reinforcing steel was an ordinary, highly ductile B500B,
234 with a tension yield strength $f_{yk} = 500 \text{ N/mm}^2$.

235 5.2.2 Formwork

236 Four walls with increasing complexity were evaluated: straight, curved, double-curved and complex
237 double-curved. The formwork for the construction of the conventional wall varied according to the
238 degree of complexity of the wall. The initial scenario compared two straight concrete walls, one that
239 was digitally fabricated with the Mesh Mould technique and one that was conventionally constructed.
240 The formwork for the conventional wall consisted of three-layered laminated boards of spruce veneers
241 (PERI, 2015). The formwork consisted of two panels with a nominal thickness of 21 mm, and we
242 considered 10 times reuse (Malpricht, 2010). In scenario 1, we increased the complexity of the
243 structure for a curved wall, so no formwork reuse was assumed. Additional softwood boards were
244 used to support the facing of the three-layered panels and control the deformation of the concrete
245 surface. In scenario 2, the complexity of the wall was increased compared to the previous scenario,
246 this time considering a double-curved wall. In this case, the varying loads from the different physical
247 states of the concrete were difficult to control and led to a higher use of softwood to stabilise the facing
248 of the formwork. Double-curved wooden moulds can be fabricated (Weilandt et al., 2009), but these
249 designs are labour intensive and have some formal limitations. Finally, the scenario with the highest
250 complexity was a complex double-curved wall with a free-form polystyrene formwork, similar to the
251 structure in **Figure 4**.



252

253 **Figure 4.** Sketch of a double-curved wall with a conventional foam formwork (Hack et al., 2014).

254 This system consisted of polystyrene blocks that were cut according to the desired form and covered
 255 by a 5-mm layer of epoxy resin. The data inventory of the formwork production included the material
 256 and the energy demand for wire cutting the blocks. Additionally, we included 30% of waste
 257 polystyrene, produced during cutting of EPS blocks into complex formwork shapes (Kaftan and
 258 Stavric, 2013). The energy demand of the formwork production was calculated based on the speed
 259 (1,500 mm/min) and power (600 W) of a 2-axis wire-cutting machine. Finally, we considered the landfill
 260 deposition of the polystyrene after use. The LCI of the formwork in each scenario is summarized in

261 **Table 2.**

| Scenario | Structure | Formwork reuse (times) | 3-layer laminated board [m ³] | Softwood board [m ³] | EPS foam slab [m ³] | Epoxy resin [m ³] | Energy [kWh] |
|----------|----------------------------|------------------------|---|----------------------------------|---------------------------------|-------------------------------|--------------|
| 0 | Straight wall | 10 | 0.0042 | 0 | 0 | 0 | |
| 1 | Curved wall | 0 | 0.042 | 0.105 | 0 | 0 | |
| 2 | Double-curved wall | 0 | 0.042 | 0.320 | 0 | 0 | |
| 3 | Complex double-curved wall | 0 | 0 | 0 | 0.52 | 0.01 | 0.013 |

262 **Table 2.** Life Cycle Inventory of the formwork for the conventional wall in the different scenarios.

263 5.2.3 Manual labour

264 The construction of a conventional wall system involves manual labour. However, energy
 265 requirements and emissions that are related to human life are usually not included in environmental
 266 analysis. Some studies have included it and conclude that the environmental impact is anyhow
 267 negligible compared to the impact of construction work (Alcott, 2012).

268


269 6 Results

270 The results of the Life Cycle Assessment are presented below. The digitally fabricated wall is analysed
 271 in detail and compared to a conventional structure with the same functional unit.

272 6.1 Assessment of the digitally fabricated wall

273 The environmental assessment of the wall that was constructed with the Mesh Mould technique is
 274 illustrated in **Figure 5**. The concrete production process has a relative impact of more than 75% for
 275 Climate change because of the energy-intensive transformation process of the clinker for the cement

276 production and simultaneous release of CO₂ during calcination. Moreover, the concrete has a
 277 contribution of approximately 60% to the environmental impact in indicators such as terrestrial
 278 acidification, fossil depletion and water depletion. Specifically, the impact of the concrete in the first
 279 indicators is caused by the burning process of fossil fuels during clinker production and the water is
 280 depleted during gravel production. On the other hand, the reinforcement has a dominant impact for
 281 freshwater eutrophication (63%), human toxicity (57%), freshwater ecotoxicity (61%) and metal
 282 depletion (89%). The pollution in the steel production for these impact categories is primarily related to
 283 the release of heavy metals to the atmosphere during steel recycling (Gomes et al., 2013). In contrast,
 284 the embodied energy of the digital technologies has a negligible relative impact, with a contribution of
 285 approximately 2% to freshwater eutrophication, human toxicity, freshwater ecotoxicity and metal
 286 depletion. Finally, the influence of the electricity production to fulfil the energy demand during
 287 construction is small in most of the midpoint categories, with a maximum contribution of 20% in ozone
 288 depletion. The results of the LCA indicate that the environmental performance of the Mesh Mould wall
 289 primarily depends on the use of materials. Therefore, an additional analysis to determine the
 290 environmental potential of an optimised design is conducted in the sensitivity analysis.




291
 292 **Figure 5.** Relative contribution of the individual processes to the environmental impact of a wall that is
 293 constructed with the Mesh Mould process.

294 6.2 Comparison of conventional and digital fabrication techniques

295 The LCA comparison of the digital fabrication and conventional construction processes for four types
 296 of walls is graphically depicted in **Figure 6**. This figure includes an analysis of the climate change and
 297 human toxicity indicators with an increase in the walls' complexity, which is represented by the four
 298 scenarios in Table 3. The results present variability that depends on the midpoint category and
 299 considered scenario. For a straight wall, the environmental impacts of the conventional wall are lower
 300 than the Mesh Mould wall. For a single-curved wall, the contribution to climate change of a
 301 conventional wall is lower than the digitally fabricated one, while the human toxicity is similar for both
 302 (6% difference). For the double-curved wall, the CO₂ emissions from the Mesh Mould wall are still 8%
 303 higher than the conventional wall constructed with plywood formwork. In contrast, the human toxicity
 304 indicator in the same scenario is 19% higher in a double-curved conventional wall than in the Mesh


305 Mould wall. The results prove that the environmental performance of the conventional wall decreases
 306 with increasing structural complexity. The difference in environmental impacts between a single-
 307 curved and a double-curved wall is mainly attributed to the increase in softwood boards to contain the
 308 additional forces from the increased structural complexity of the structure. Finally, for a complex
 309 double-curved wall, which implies the use of polystyrene formwork in the conventional technique, the
 310 Mesh Mould construction process allows savings of 38% for climate change and 31% for human
 311 toxicity factors.



312

313 **Figure 6.** LCA comparison of a Mesh Mould wall (no formwork required) and a wall that is constructed
 314 with conventional techniques (formwork). The scenarios represent the increasing complexity of the
 315 walls.

316 The relative contributions from the production processes of a complex double-curved wall with
 317 polystyrene formwork to the different impact categories are depicted in **Figure 7**. We can observe the
 318 high impact of the epoxy resin for the formwork covering, which is responsible for 45% of the climate
 319 change emissions, 64% of terrestrial acidification, 60% of water depletion and 69% of fossil depletion.
 320 Moreover, the production of the polystyrene mostly influences the ozone depletion indicator (17%).
 321 Finally, the landfilling of the formwork after one reuse highly contributes to ecotoxicity. On the contrary,
 322 the environmental impacts of the Mesh Mould construction process do not change with rising demands
 323 of the form, so the environmental potential is growing with the required effort in the conventional
 324 technique. Therefore, the digital fabrication method becomes more interesting the more unique and
 325 complex the architectural forms are.



326

327 **Figure 7.** Relative contribution of the individual processes to the environmental impact of a complex
 328 double-curved wall that is constructed with conventional techniques.

329


330 7 Sensitivity analysis

331 The results show that the digital fabrication process induces greater environmental impacts than the
 332 conventional technique for walls with low degrees of complexity (scenarios 0 and 1). The Mesh Mould
 333 construction process is a research project that is still in its optimisation phase. As a result, the LCI of
 334 the digitally fabricated wall contains some assumptions, mainly at the material level, during the
 335 comparison with conventional construction. In this section, the uncertainty on the concrete and steel
 336 volume in the Mesh Mould wall is graphically depicted to further analyse when digital fabrication
 337 produces environmental benefits compared to conventional construction.

338 7.1 Concrete

339 In the initial comparison, the Mesh Mould wall was conservatively considered to have the same
 340 dimensions as a conventional wall built with C25/30 concrete. However, the compression strength of
 341 the ETHZ IFB concrete is higher based on the greater amount of cement, which could be used to
 342 reduce the thickness of the structural element. In published case studies, the use of high performance
 343 concrete has already been efficiently used to reduce thickness of structural elements such as bridges
 344 and provide an environmental benefit (Habert et al., 2012). Moreover, the difficulty of positioning the
 345 rebars and the formwork before pouring the concrete inside a tight building element is here potentially
 346 overcome with digital fabrication techniques. Consequently, this section quantifies the minimum wall
 347 thickness that is compliant with structural requirements to improve the environmental performance of a
 348 straight wall that is constructed with the Mesh Mould process. In the following analysis, the break-
 349 even-point is approached by continuously reducing the thickness of the Mesh Mould wall. The
 350 maximum thickness of the digitally fabricated wall can be distinguished when the contribution from
 351 both construction elements to the impact categories is equal. The calculation approach for the Mesh
 352 Mould wall is based on adjusting the concrete volume to the variable thickness of the wall without

353 modifying the other parameters. **Figure 8** compares the CO₂ emissions for wall thicknesses between
 354 10 and 20 cm to those of a 20-cm-thick conventional concrete wall.



355

356 **Figure 8.** Comparison of the contribution to the climate change category of two straight walls: a
 357 conventionally built wall with constant thickness and a digitally fabricated wall with variable thickness.

358 The graph demonstrates that the CO₂ emissions of the digitally fabricated wall are 12% lower than the
 359 conventional wall when the thickness is reduced to 10 cm. The graph shows a break-even point for the
 360 climate change category at a thickness of 12 cm, which means that digital fabrication technology
 361 would be effectively performant from an environmental perspective when producing thinner straight
 362 walls than those from conventional methods. The feasibility of a Mesh Mould wall with this thickness is
 363 evaluated by calculating the slenderness criteria according to Eurocode 2: Design of concrete
 364 structures (CEN, 2004), which leads to the ratios in formulas 4 and 5:

$$\frac{l_0}{t_{wall,MM}} \leq 25 \quad (4)$$

365 where $t_{wall,MM}$ is the minimum thickness of a Mesh Mould concrete wall and l_0 is the effective length of
 366 the wall, which is calculated by

$$l_0 = \beta \cdot l_w = 2.4 \quad (5)$$


367 where l_w is the clear height of the wall (2.4 m), and β is a coefficient that represents the support
 368 conditions, which was conservatively taken as 1.0 for this evaluation. The calculation shows that a
 369 minimal wall thickness of $t_{wall,min} \geq 0.1$ m is required in the Mesh Mould wall. Therefore, the thickness at
 370 the break-even point of CO₂ emissions ($t_{MM,BEP} = 0.12$ m) would be sufficient. Finally, a second
 371 calculation regarding the compression strength of the ETHZ IFB concrete mix is performed. A direct
 372 proportionality between the strength of the concrete and the bearing capacity of the wall is assumed,
 373 and no failure modes or load situations except compression are considered to simplify the calculation.
 374 The conventional wall has a thickness of 0.2 m and its concrete has a compression strength of $f_{ck} = 25$
 375 N/mm². Formula 6 shows the minimum required compression strength ($f_{ck,MM,min}$) of the ETHZ IFB
 376 mix for a wall of 12 cm:

$$f_{ck,MM,min} = \frac{t_{wall,con}}{t_{MM,BEP}} \cdot f_{ck} = \frac{0.2}{0.12} \cdot 25 = 41.7 \text{ N/mm}^2 \quad (6)$$

377 where $t_{\text{wall,con}}$ is the thickness of the conventional wall, $t_{\text{MM,BEP}}$ is the thickness of the Mesh Mould wall
 378 at the break-even point and f_{ck} is the compression strength of the standard concrete mix. Typically,
 379 high-performance concrete has a fine fraction of a supplementary cementitious material and $w/c < 0.4$,
 380 which enables the material to reach a compressive strength over 80 or even 100 N/mm². The ETH IFB
 381 mix is a high-performance concrete, which contains silica fume as supplementary cementitious
 382 material and has a water-cement ratio (w/c) of 0.34. This concrete mixture presents a minimum
 383 compressive strength between 60-70 MPa, which exceeds the required $f_{ck,MM,min} = 41.7$ N/mm². In
 384 conclusion, the conducted structural analysis shows that the break-even point in CO₂ emissions for the
 385 digitally fabricated wall compared to a conventional wall is theoretically reachable and that the wall
 386 thickness can be reduced to 0.1 m.

387 7.2 Reinforcing steel

388 During the initial analysis, the volume fraction value that was assumed for the reinforcement of the
 389 Mesh Mould wall was $r_{\text{MM}} = 0.7\%$. In this sensitivity analysis, we establish a range around the previous
 390 value with a minimum and maximum reinforcement content. On the one hand, distributing steel only
 391 where it is structurally necessary could potentially reduce the steel volume fraction of $r_{\text{MM,min}} = 0.5\%$.
 392 On the other hand, the structural performance of the wires in a bearing wall could increase the
 393 reinforcement content, with a steel volume fraction of $r_{\text{MM,max}} = 1.5\%$. **Figure 9** graphically depicts the
 394 sensitivity analysis of the digitally fabricated wall when considering the previous range of
 395 reinforcement volume fractions.



396

397 **Figure 9.** LCA comparison of two straight walls: a conventionally built wall with 0.7% steel volume
 398 fraction and a digitally fabricated wall with variable volume fraction of reinforcement.

399 The graph reveals the great impact of the variability in the amount of reinforcement steel on the global
 400 environmental impact of digitally fabricated wall. In particular, the uncertainty between $r_{\text{MM,min}} = 0.5\%$
 401 and $r_{\text{MM,max}} = 1.5\%$ results in a difference of approximately 125% in freshwater eutrophication and
 402 freshwater ecotoxicity, 113% in human toxicity and 140% in metal depletion emissions. The
 403 importance of efficient steel usage is shown in the previous results. However, the optimisation of
 404 reinforcing steel reduces the environmental impacts compared to a conventional reinforced concrete

405 wall only in some categories such as metal depletion (23%). In categories such as climate change, the
406 reduction in steel do not enable the Mesh Mould wall to achieve lower emissions compared to a
407 conventionally constructed straight concrete wall. Consequently, the structural performance of walls
408 that are fabricated with the Mesh Mould technique should be modelled and tested to minimise the
409 volume fraction of steel but combined with the optimisation of other parameters, such as the concrete
410 volume.

411

412 **8 Synthesis**

413 The results of the sensitivity analysis are summarised in this section. The extreme values of the
414 individual materials represent a range of possible outcomes for the Mesh Mould case study.


415 Scenarios for the digitally fabricated wall:

- 416 • **Best scenario:** The optimal performance of the Mesh Mould wall is characterised by a minimal
417 reinforcement steel volume fraction of $r_{MM,min} = 0.5\%$ and a lower wall thickness of $t_{MM,min} = 0.1$ m,
418 which is the limit from the slenderness criteria.
- 419 • **Reference scenario:** The initially considered Mesh Mould wall has a reinforcement of $r_{MM} = 0.7\%$
420 and a wall thickness of $t_{wall} = 0.2$ m.
- 421 • **Worst scenario:** Buckling failure might require a wall thickness of $t_{MM} = 0.2$ m, and additional
422 complications with the mesh could lead to a reinforcement steel content of $r_{MM,max} = 1.5\%$.

423 Scenarios for conventional construction:

- 424 • **Standard scenario:** The smallest environmental impact for the conventional method is reached in
425 a straight wall, where the formwork was reused 10 times. The dimensions are set to $t_{wall} = 0.2$ m,
426 using $r_{wall} = 0.7\%$ of steel and ordinary C25/30 concrete.
- 427 • **Complex scenario:** Conventionally, a complex double-curved wall that is constructed with
428 polystyrene formwork and is not reusable showed the worst environmental performance. The
429 dimensions are set to $t_{wall} = 0.2$ m, with $r_{wall} = 0.7\%$ of steel and ordinary C25/30 concrete.

430 The range of environmental impacts from the best- and worst-case scenarios and as well as the initial
431 digitally fabricated wall compared to the complexity-dependent impacts of the conventional wall are
432 illustrated in **Figure 10**.



433

434 **Figure 10.** LCA comparison of a digitally fabricated wall with a straight and a complex double-curved
 435 wall that are constructed with conventional techniques. The error bars represent the best and worst
 436 scenarios of the wall.

437 The large variability in the environmental emissions of the best and worst cases of the Mesh Mould
 438 wall highlights the importance of material optimisation. The best scenario of the digitally fabricated wall
 439 reduces material usage and decreases the CO₂ emissions by 33% compared to the reference
 440 scenario. Simultaneously, the worst scenario exhibits substantially higher emissions than the
 441 reference scenario, with an increase of 52% in metal depletion. The results indicate that the best
 442 scenario of the Mesh Mould wall produces potential environmental benefits compared to a
 443 conventionally constructed straight concrete wall. Specifically, the best scenario of the Mesh Mould
 444 wall reduces the emissions by 3-13% depending on the indicator. However, the outcome of this
 445 comparison greatly depends on the material optimisation of the system. A less optimised Mesh Mould
 446 wall (worst scenario) has lower environmental performance than a conventional straight wall.

447 Finally, the results prove that the reference Mesh Mould system can currently environmentally
 448 compete with a conventionally constructed double-curved wall. The reference scenario of the Mesh
 449 Mould wall shows greater impacts compared to the complex conventional scenario only in three
 450 midpoint categories, but the difference is minimal (1-9%). Moreover, the worst scenario of the digitally
 451 fabricated wall can environmentally compete with a complex conventional wall in categories such as
 452 climate change, terrestrial ecotoxicity or fossil depletion. In conclusion, the complexity is an important
 453 factor to consider during comparisons with conventional construction. Contrary to conventional
 454 techniques, the impacts of the Mesh Mould process do not increase with the uniqueness and
 455 complexity of the architectural forms.

456

457 9 Discussion

458 In this paper, we evaluated the environmental potential of an innovative digital fabrication process for
 459 the construction of complex concrete structures. The conducted research confirmed the environmental

460 potential of additive fabrication, as anticipated in previous studies such as Kohtala and Hyysalo
461 (2015). Moreover, the analysis showed that digital fabrication in complex geometries (double-curved
462 walls) provides an environmental benefit compared to conventional construction. Digital fabrication
463 techniques facilitate the construction of complex and slender structures without the use of
464 conventional formworks, with associated material savings. However, does this additional complexity in
465 the structure provide an environmental benefit? This question seems reasonable and can be
466 addressed by examining which additional functions can support double-curved walls that are built with
467 digital fabrication. This specific question leads to the use of complex forms in architecture. Complexity
468 is an architecture characteristic, whose costs and value creation have often been discussed in the
469 literature (Venturi, 1977), and we would like to raise three different possibilities to discuss the
470 appropriate use of complexity for sustainability.

471 First, complexity can be seen as a consequence of a highly integrated construction process. The
472 conventional organisation of a construction is conceived as a successive and layered process where
473 each element and function is addressed by a different element and built at different moments by
474 different skilled workers. This combination of functions through the help of digital technologies can
475 save time and building materials, frequently associated with money and grey energy reductions
476 (Agustí-Juan and Habert, 2017). This integrated design increases the complexity, which can be
477 handled with no additional costs through digital fabrication. When digital fabrication is used to build
478 elements that permit an integrated design, the complexity of these elements is likely justified from an
479 environmental perspective because integrated functions can save materials and because the
480 production of these complex elements is more efficient when digital fabrication is used. However, the
481 choice of functions is crucial. For instance, the complex building element in this study can be
482 understood as the fusion of structure and final layering. From a classic sustainable design perspective,
483 these two elements are considered to have completely different service lives. The structure has a
484 service life of 60 years, while interior finishing is thought to be changed every 15 years (Hoxha et al.,
485 2014). If the structure must be changed every 15 years, the environmental impact drastically
486 increases. On the contrary, avoiding the replacement of interior finishing because of its long-lasting
487 design can save energy.

488 This observation leads to a second question regarding complexity in architecture as an enlightenment
489 of the structure and more generally as an ornament. The function of ornaments has long been
490 discussed. Rosenbauer (1947) stated that "Engineering, when it uses materials up to their functional
491 limits approaches the economy of nature and thereby creates forms as beautiful as the forms of
492 nature. [...] Engineering occasionally produces art but we cannot assume that all art will come from
493 engineering. We must have poets and we must have designers and their business is to embellish and
494 adorn our lives and our culture. [...] Ornament cannot be abolished as the desire for embellishment is
495 essentially human, and humans will gratify it wherever they can". This author also wrote that "the
496 machine will then produce ornament willed by the designer as naturally as did the handtools of the
497 artist craftsman. Then there will be proper and excellent ornament, differing from traditional ornament
498 as our culture differs from those of the past. The public will buy it as the good things of the past were

499 bought by that public, and greater numbers will be economically able to do so. This is the real manner
500 in which the machine may raise our standard of living.”

501 Considering this perspective and the results of this study, in which the machine produced ornaments
502 with lower environmental impact than the same element from a conventional technique, we can
503 consider digital fabrication as an effective construction technique to produce complex ornaments.
504 Moreover, the function of ornaments and the inherent complexity that is related to its production is
505 justified by the social need of ornamentation. In a recent perspective on ornamentation in architecture,
506 Moussavi and Kubo (2006) established that “Architecture needs mechanisms that allow it to become
507 connected to culture”. The aesthetic composition of buildings is effectively related to the culture by
508 creating affects and sensations. Even if modern design does not require ornaments, society continues
509 demanding these additional elements to connect with the contemporary culture. In their book, the
510 authors also showed through examples how ornaments in contemporary architecture can integrate
511 functions (structure, visibility, etc.) behind an apparently purely aesthetic performance.

512 Finally, complexity can be seen as a consequence of a problem-solving attitude. Societies often solve
513 problems by developing more complex environments and technologies (Tainter and Taylor, 2014).
514 This can be seen as positive, for instance, studies on environmental psychology-oriented design
515 suggest that high levels of spatial and visual complexity in the workspace foster creativity. Factors
516 such as the creativity or productivity of employees are influenced by their aesthetic judgements of the
517 built environment (Gifford, 2014). However, complexity both solves problems and generates them.
518 Innovative technologies, which are intended to save energy through complex designs and controls,
519 may consume more. The complexity of designs produces unintended interactions among components,
520 producing further problems, and the current sustainability concerns regarding buildings are creating
521 more complex building designs. Complexity in control systems, for example, leads to unanticipated
522 growth in facility management. Interior environmental systems are so complex that many users cannot
523 fine-tune the controls, so a large amount of energy is wasted (Bordass and Leaman, 1997).

524 Digital fabrication can facilitate the production of elements with higher complexity without increasing
525 the environmental costs, as is usually observed in conventional construction, which could contradict
526 the traditional observation pattern that increasing complexity, while initially effective, accumulates and
527 induces diminishing returns, undermining the ability to solve future problems. In that sense, this study
528 matches the common understanding of the digital revolution as the third moment in humanity when an
529 increase in system complexity allowed positive feedback (Gershenfeld, 2012). These occasions have
530 been so rare that they are designated with terms that signify a new era, namely, the Agricultural
531 Revolution and the Industrial Revolution. These events were followed by great expansions in the
532 number of humans, wealth and complexity of societies.

533

534 **10 Conclusions**

535 In this study, the environmental impact of an innovative digital fabrication construction was compared
536 to a similar structure that was built with conventional construction techniques. The results showed that
537 digital fabrication produces high environmental benefits compared to conventional construction when

538 complex structures are built. In this study, we confirmed that the environmental impact of the Mesh
539 Mould process does not grow with the uniqueness and complexity of the architectural form. Additional
540 complexity was achieved without additional environmental costs, so the potential benefit of digital
541 fabrication increased proportionally to the level of complexity of the structure. This result is a
542 quantitative argument to position digital fabrication at the beginning of a new era, which is often called
543 the Digital Age in many other disciplines. This analysis also showed that the current Mesh Mould
544 system can environmentally compete with conventional structures, which have a high degree of both
545 formal and structural complexity. However, the results highlighted the need for improvement to
546 compete at a lower degree of complexity. In this case, high thickness reduction must be achieved
547 without compromising the structural performance. Finally, this study also raised the attention of the
548 need to justify complexity from an environmental point of view to avoid the risk of complexifying a
549 socio-technical system for no real mean.

550

551 **Acknowledgements**

552 The authors thank the Institute of Structural Engineering (IBK) from ETH Zürich for their invaluable
553 input. This research was supported by the National Competence Centre for Research, NCCR Digital
554 Fabrication, which was funded by the Swiss National Science Foundation (project number
555 51NF40_141853).

556

557 **Appendix. Supplementary information**

558 Supplementary information regarding background data and results from the LCAs can be found in
559 appendix.

560

561 **References**

562 Agustí-Juan, I., Habert, G., 2017. Environmental design guidelines for digital fabrication. *Journal of*
563 *Cleaner Production* 142, 2780-2791.

564 Alcott, B., 2012. Mill's scissors: structural change and the natural-resource inputs to labour. *Journal of*
565 *Cleaner Production* 21, 83-92.

566 Arora, S.K., Foley, R.W., Youtie, J., Shapira, P., Wiek, A., 2014. Drivers of technology adoption — the
567 case of nanomaterials in building construction. *Technological Forecasting and Social Change* 87, 232-
568 244.

569 Berman, B., 2012. 3-D printing: The new industrial revolution. *Business horizons* 55, 155-162.

570 Bordass, W., Leaman, A., 1997. Design for manageability. *Building Research & Information* 25, 148-
571 157.

572 Cabeza, L.F., Rincón, L., Vilariño, V., Pérez, G., Castell, A., 2014. Life cycle assessment (LCA) and
573 life cycle energy analysis (LCEA) of buildings and the building sector: A review. *Renewable and*

- 574 Sustainable Energy Reviews 29, 394-416.
- 575 CEN, 2004. Eurocode 2: Design of Concrete Structures-Part 1-1: General Rules and Rules for
576 Building.
- 577 Chen, C., Habert, G., Bouzidi, Y., Jullien, A., Ventura, A., 2010. LCA allocation procedure used as an
578 incitative method for waste recycling: an application to mineral additions in concrete. Resources,
579 Conservation and Recycling 54, 1231-1240.
- 580 Chen, D., Heyer, S., Ibbotson, S., Salonitis, K., Steingrímsson, J.G., Thiede, S., 2015. Direct digital
581 manufacturing: definition, evolution, and sustainability implications. Journal of Cleaner Production 107,
582 615-625.
- 583 CRB, 2011. Catalog of elements: Energy characteristics EAK, Zurich, Switzerland (in German).
- 584 Damineli, B.L., Kemeid, F.M., Aguiar, P.S., John, V.M., 2010. Measuring the eco-efficiency of cement
585 use. Cement and Concrete Composites 32, 555-562.
- 586 Dörfler, K., Sandy, T., Gifftthaler, M., Gramazio, F., Kohler, M., Buchli, J., 2016. Mobile Robotic
587 Brickwork, in: Reinhardt, D., Saunders, R., Burry, J. (Eds.), Robotic Fabrication in Architecture, Art and
588 Design 2016. Springer International Publishing, Cham, Switzerland, pp. 204-217.
- 589 Dunn, N., 2012. Digital fabrication in architecture. Laurence King Publishing Ltd, London, United
590 Kingdom.
- 591 Faludi, J., Bayley, C., Bhogal, S., Iribarne, M., 2015. Comparing environmental impacts of additive
592 manufacturing vs traditional machining via life-cycle assessment. Rapid Prototyping Journal 21, 14-33.
- 593 Feng, P., Meng, X., Chen, J.-F., Ye, L., 2015. Mechanical properties of structures 3D printed with
594 cementitious powders. Construction and Building Materials 93, 486-497.
- 595 Ford, S., Despeisse, M., 2016. Additive manufacturing and sustainability: an exploratory study of the
596 advantages and challenges. Journal of Cleaner Production 137, 1573-1587.
- 597 Gebler, M., Uiterkamp, A.J.S., Visser, C., 2014. A global sustainability perspective on 3D printing
598 technologies. Energy Policy 74, 158-167.
- 599 Gershenfeld, N., 2012. How to make almost anything: The digital fabrication revolution. Foreign Affairs
600 91, 43-57.
- 601 Giesekam, J., Barrett, J.R., Taylor, P., 2016. Construction sector views on low carbon building
602 materials. Building Research & Information 44, 423-444.
- 603 Gifford, R., 2014. Environmental psychology matters. Annual review of psychology 65, 541-579.
- 604 Goedkoop, M., Heijungs, R., Huijbregts, M., De Schryver, A., Struijs, J., van Zelm, R., 2009. ReCiPe
605 2008: A life cycle impact assessment method which comprises harmonised category indicators at the
606 midpoint and the endpoint level. Ministry of Housing, Spatial Planning and Environment (VROM), Den
607 Haag, Netherlands.
- 608 Gomes, F., Brière, R., Feraille, A., Habert, G., Lasvaux, S., Tessier, C., 2013. Adaptation of
609 environmental data to national and sectorial context: application for reinforcing steel sold on the

- 610 French market. *The International Journal of Life Cycle Assessment* 18, 926-938.
- 611 Gramazio, F., Kohler, M., 2008. *Digital materiality in architecture*. Lars Müller Publishers, Baden,
612 Switzerland.
- 613 Gramazio, F., Kohler, M., Langenberg, S., 2014. *FABRICATE: Negotiating Design & Making*. gta
614 Verlag, Zurich, Switzerland.
- 615 Grist, E.R., Paine, K.A., Heath, A., Norman, J., Pinder, H., 2015. The environmental credentials of
616 hydraulic lime-pozzolan concretes. *Journal of Cleaner Production* 93, 26-37.
- 617 Habert, G., Arribe, D., Dehove, T., Espinasse, L., Le Roy, R., 2012. Reducing environmental impact by
618 increasing the strength of concrete: quantification of the improvement to concrete bridges. *Journal of*
619 *Cleaner Production* 35, 250-262.
- 620 Hack, N., Lauer, W., Gramazio, F., Kohler, M., 2015. Mesh Mould: robotically fabricated metal meshes
621 as concrete formwork and reinforcement. *Ferro* 11, 347-359.
- 622 Hack, N., Lauer, W., Langenberg, S., Gramazio, F., Kohler, M., 2013. Overcoming Repetition: Robotic
623 fabrication processes at a large scale. *International Journal of Architectural Computing* 11, 285-300.
- 624 Hack, N., Lauer, W.V., Gramazio, F., Kohler, M., 2014. Mesh Mould: Differentiation for Enhanced
625 Performance, 19th International Conference on Computer-Aided Architectural Design Research in
626 Asia (CAADRIA 2014) Kyoto, pp. 139–148.
- 627 Hoxha, E., Habert, G., Chevalier, J., Bazzana, M., Le Roy, R., 2014. Method to analyse the
628 contribution of material's sensitivity in buildings' environmental impact. *Journal of Cleaner Production*
629 66, 54-64.
- 630 Hoxha, E., Habert, G., Lasvaux, S., Chevalier, J., Le Roy, R., 2017. Influence of construction material
631 uncertainties on residential building LCA reliability. *Journal of Cleaner Production* 144, 33-47.
- 632 IPCC, 2014. *Climate Change 2014: Synthesis Report*. Contribution of Working Groups I, II and III to
633 the Fifth Assessment Report of the Intergovernmental Panel on Climate Change. IPCC, Geneva,
634 Switzerland.
- 635 ISO, 2006a. 14040: Environmental management—life cycle assessment—principles and framework.
- 636 ISO, 2006b. 14044: Environmental management—life cycle assessment—requirements and
637 guidelines.
- 638 Kaftan, M., Stavic, M., 2013. ROBOTIC FABRICATION OF MODULAR FORMWORK, in: Stouffs, R.,
639 Janssen, P., Roudavski, S., Tunçer, B. (Eds.), *Conference on Computer-Aided Architectural Design*
640 *Research in Asia (CAADRIA 2013)*, pp. 75-84.
- 641 Khoshnevis, B., Hwang, D., Yao, K.-T., Yeh, Z., 2006. Mega-scale fabrication by contour crafting.
642 *International Journal of Industrial and Systems Engineering* 1, 301-320.
- 643 Kohtala, C., 2015. Addressing sustainability in research on distributed production: an integrated
644 literature review. *Journal of Cleaner Production* 106, 654-668.
- 645 Kohtala, C., Hyysalo, S., 2015. Anticipated environmental sustainability of personal fabrication. *Journal*

- 646 of Cleaner Production 99, 333-344.
- 647 Kreiger, M., Pearce, J.M., 2013. Environmental life cycle analysis of distributed three-dimensional
648 printing and conventional manufacturing of polymer products. *ACS Sustainable Chemistry &*
649 *Engineering* 1, 1511-1519.
- 650 Lim, S., Buswell, R.A., Le, T.T., Austin, S.A., Gibb, A.G., Thorpe, T., 2012. Developments in
651 construction-scale additive manufacturing processes. *Automation in construction* 21, 262-268.
- 652 Lipson, H., Kurman, M., 2013. *Fabricated: The new world of 3D printing*. John Wiley & Sons,
653 Indianapolis, United States of America.
- 654 Lloret, E., Shahab, A.R., Linus, M., Flatt, R.J., Gramazio, F., Kohler, M., Langenberg, S., 2014.
655 Complex concrete structures: Merging existing casting techniques with digital fabrication. *Computer-*
656 *Aided Design* 60, 40-49.
- 657 Malpricht, W., 2010. *Formwork planning: a teaching and exercise book*. With 49 tables, 36 examples
658 and 13 tasks. Carl Hanser Verlag, Munich, Germany (in German).
- 659 McKinsey&Company, 2016. *Imagining construction's digital future*.
660 [www.mckinsey.com/industries/capital-projects-and-infrastructure/our-insights/imagining-constructions-](http://www.mckinsey.com/industries/capital-projects-and-infrastructure/our-insights/imagining-constructions-digital-future)
661 [digital-future](http://www.mckinsey.com/industries/capital-projects-and-infrastructure/our-insights/imagining-constructions-digital-future) (accessed 15/10/2016).
- 662 Motion Controls Robotics, 2017. *Robot Life Cycle -FAQs*. [www.motioncontrolsrobotics.com/robot-life-](http://www.motioncontrolsrobotics.com/robot-life-cycle-faqs/)
663 [cycle-faqs/](http://www.motioncontrolsrobotics.com/robot-life-cycle-faqs/) (accessed 14/02/2017).
- 664 Moussavi, F., Kubo, M., 2006. *The Function of Ornament*. Actar, Barcelona, Spain.
- 665 Pacheco-Torgal, F., 2014. Eco-efficient construction and building materials research under the EU
666 Framework Programme Horizon 2020. *Construction and Building Materials* 51, 151-162.
- 667 Passer, A., Kreiner, H., Maydl, P., 2012. Assessment of the environmental performance of buildings: A
668 critical evaluation of the influence of technical building equipment on residential buildings. *The*
669 *International Journal of Life Cycle Assessment* 17, 1116-1130.
- 670 PERI, 2015. *Formwork Scaffolding Engineering*. [www.peri.com/en/products/formwork/wall-](http://www.peri.com/en/products/formwork/wall-formwork.html)
671 [formwork.html](http://www.peri.com/en/products/formwork/wall-formwork.html) (accessed 16/11/2015).
- 672 Pinkse, J., Dommissie, M., 2009. Overcoming barriers to sustainability: an explanation of residential
673 builders' reluctance to adopt clean technologies. *Business Strategy and the Environment* 18, 515-527.
- 674 Rippmann, M., Lachauer, L., Block, P., 2012. Interactive vault design. *International Journal of Space*
675 *Structures* 27, 219-230.
- 676 Rosenbauer, W., 1947. *The Function of Ornament*. *College Art Journal* 6, 222-225.
- 677 Tainter, J.A., Taylor, T.G., 2014. Complexity, problem-solving, sustainability and resilience. *Building*
678 *Research & Information* 42, 168-181.
- 679 UNEP, 2012. *Building Design and Construction: Forging Resource Efficiency and Sustainable*
680 *Development*, Geneva, Switzerland.

- 681 Venturi, R., 1977. Complexity and contradiction in architecture. The Museum of Modern Art, New York,
682 United States of America.
- 683 Wangler, T., Lloret, E., Reiter, L., Hack, N., Gramazio, F., Kohler, M., Bernhard, M., Dillenburger, B.,
684 Buchli, J., Roussel, N., 2016. Digital Concrete: Opportunities and Challenges. RILEM Technical
685 Letters 1, 67-75.
- 686 Weidema B. P., B.C., Hischier R., Mutel C., Nemecek T., Reinhard J., Vadenbo C. O., Wernet G.,
687 2013. Overview and methodology. Data quality guideline for the ecoinvent database version 3,
688 Ecoinvent Report 1(v3). Swiss Centre for Life Cycle Inventories, St. Gallen, Switzerland.
- 689 Weilandt, A., Grohmann, M., Bollinger, K., Wagner, M., 2009. Rolex Learning Center in Lausanne:
690 From conceptual design to execution. Proceedings of the International Association for Shell and
691 Spatial Structures, Valencia, Spain, 640-653.
- 692

Potential benefits of digital fabrication for complex structures: Environmental assessment of a robotically fabricated concrete wall

Highlights

- LCA comparison between robotic fabrication and conventional construction.
- Mesh Mould construction process analysed from an environmental point of view.
- Environmental benefits of digital fabrication when applied to complex structures.
- Justification of complexity from a sustainable perspective.