

On spatial conditional extremes for ocean storm severity

R. Shooter^{a*}, E. Ross^b, J. Tawn^c and P. Jonathan^{c,d}

Summary: We describe a model for the conditional dependence of a spatial process measured at one or more remote locations given extreme values of the process at a conditioning location, motivated by the conditional extremes methodology of Heffernan and Tawn. Compared to alternative descriptions in terms of max-stable spatial processes, the model is advantageous since it is conceptually straightforward, and admits different forms of extremal dependence (including asymptotic dependence and asymptotic independence). We use the model within a Bayesian framework to estimate the extremal dependence of ocean storm severity (quantified using significant wave height, H_S) for locations on spatial transects with approximate east-west (E-W) and north-south (N-S) orientations in the northern North Sea (NNS) and central North Sea (CNS). For H_S on standard Laplace marginal scale, the conditional extremes “linear slope” parameter α decays approximately exponentially with distance for all transects. Further, the decay of mean dependence with distance is found to be faster in CNS than NNS. The persistence of mean dependence is greatest for the E-W transect in NNS, potentially since this transect is approximately aligned with the direction of propagation of the most severe storms in the region.

Keywords: conditional extremes, spatial dependence, non-stationary, significant wave height

^a*STOR-i Centre for Doctoral Training, Department of Mathematics and Statistics, Lancaster University LA1 4YR, United Kingdom.*

^b*Shell Global Solutions International BV, Amsterdam, The Netherlands.*

^c*Department of Mathematics and Statistics, Lancaster University LA1 4YW, United Kingdom.*

^d*Shell Research Ltd., London SE1 7NA, United Kingdom.*

* *Correspondence to: r.shooter@lancaster.ac.uk*

1. INTRODUCTION

Quantifying extreme ocean environments is important for safe and reliable construction and operation of offshore and coastal infrastructure. Extreme value analysis provides a framework within which the marginal and dependence characteristics of extreme ocean environments can be estimated, and joint inferences corresponding to very long periods of observation made in the presence of non-stationarity with respect to covariates.

The spatial structure of ocean surface roughness within a storm is of particular concern when inferences are based on observations from multiple locations in a neighbourhood. For a given ocean basin, when the distance between two locations is small relative to the spatial extent of a storm low pressure field, it is reasonable to expect that large values of ocean surface roughness (for a period of time of the order of an hour, quantified in terms of significant wave height H_S) at the two locations will be dependent. Moreover, the extent of this spatial dependence will potentially itself be non-stationary with respect to covariates, such as storm direction and season. A reasonable statistical description of H_S on a neighbourhood of locations should therefore admit appropriately flexible descriptions of extremal spatial dependence. Incorrect specification or estimation of the dependence structure can lead to misleading joint predictions of H_S on the neighbourhood. We note a number recent articles on spatial extremes with at least some synoptic content, including Davison et al. (2012), Reich and Shaby (2012), Ribatet (2013), Huser and Wadsworth (2018) and Tawn et al. (2018).

A number of recent studies explore the extremal spatial dependence of H_S . For example, Kereszturi et al. (2016) assesses the extremal dependence of North Sea storm severity using the summary statistics χ and $\bar{\chi}$ (or equivalently η , Coles et al., 1999), outlined in Section 3. Estimates for these summary statistics were used to categorise observed extremal dependence as either asymptotic dependence (AD, suggesting that extreme events tend to

occur simultaneously) or asymptotic independence (AI, suggesting that extreme events are unlikely to occur together); further discussion of these concepts is given in Section 3.1. In Kereszturi et al. (2016), it was found that, in most cases considered, asymptotic independence seemed to be the more appropriate assumption, compared to the assumption of asymptotic dependence. Kereszturi (2016) and Ross et al. (2017a) extend this assessment to include the estimation of a number of max-stable process (MSP) and inverted MSP models (Wadsworth and Tawn, 2012), including the so-called Smith (Smith, 1990), Schlather (Schlather, 2002) and Brown-Resnick (Brown and Resnick, 1977) models, and corresponding models for the inverted processes. For all models considered, there is evidence that the extremal dependence of H_S at two locations varies with the distance between the locations, and their relative orientation.

By construction, MSP models considered in Kereszturi (2016) and Ross et al. (2017a) exhibit AD exclusively, whereas inverted MSP models only exhibit AI. In general, we do not know a priori which form of extremal dependence is more appropriate: a decision concerning the form of extremal dependence present in the sample must therefore be made before parameter estimation; this is less than ideal, although estimation of χ and $\bar{\chi}$ can aid this choice. We note alternative AD models including those of Reich and Shaby (2012), Ferreira and de Haan (2014), Rootzen et al. (2018), Kiriliouk et al. (2018). A number of more sophisticated hybrid models have been proposed (e.g. Wadsworth and Tawn 2012, Wadsworth et al. 2017, Huser and Wadsworth 2018) spanning dependence classes, but these tend to be rather computationally challenging to estimate in practice.

The conditional extremes model of Heffernan and Tawn (2004) provides an alternative approach to characterising extremal spatial dependence admitting both AI and AD. The conditional extremes model also allows the incorporation of covariate effects (e.g. Jonathan et al., 2014). In the current work, we propose an extension of the conditional extremes method to a spatial setting, known as the spatial conditional extremes (SCE) model. SCE provides a

framework to quantify the extreme marginal and dependence structure of H_S for locations in a neighbourhood, including the behaviour of extremal dependence of H_S at different locations as a function of the relative displacements of locations. Model estimation can be achieved using a relatively straightforward Markov chain Monte Carlo (MCMC) scheme, and unlike for MSP models, does not require composite likelihood techniques for parameter estimation and hence does not incur parameter bias, as detailed in Tawn et al. (2018) and Wadsworth and Tawn (2018).

The layout of the article is as follows. In Section 2, we present motivating applications involving samples of H_S on spatial neighbourhoods in the northern and central North Sea. Section 3 outlines the spatial conditional extremes model. Parameter estimation is performed using Bayesian inference as described in Section 4; details of parameter constraints from Keef et al. (2013a), and the Metropolis-within-Gibbs sampling scheme, are given in the Appendix. Results of the application of the SCE model to the north-south transect of the northern North Sea sample are given in Section 5, with corresponding results for the east-west transect (for the northern North Sea), and north-south and east-west transects for the central North Sea reported in Section 6. Section 7 provides discussion and conclusions.

2. MOTIVATING APPLICATION

We consider hindcast data for storm peak significant wave height (henceforth H_S for brevity) from two neighbourhoods, one in the northern North Sea (NNS) and one in the central North Sea (CNS), as illustrated in Figure 1. In each neighbourhood, values for H_S are available on north-south (N-S) and east-west (E-W) transects intersecting at a central location.

[Figure 1 about here.]

The NNS sample corresponds to winter storms (occurring in winter months October-March) from the NEXTRA hindcast (Oceanweather 2002) for 20 locations on the two transects.

Storm intervals for a total of 1680 storms during the period 1 Oct 1964 to 31 Mar 1995 were isolated from up- and down-crossings of a sea state significant wave height threshold for the central location, using the procedure outlined in Ewans and Jonathan (2008). Storm peak significant wave height for each storm interval at each location provided a sample of 1680×20 observations for further analysis. For each storm-location combination, the direction (from which waves emanate, measured clockwise from North) at the time of the storm peak, referred to as the storm direction, was also retained. The spatial extremal characteristics of this sample have been examined previously in Ross et al. (2017a); further discussion and illustrations of the data are available there.

The CNS sample corresponds to hindcast storm peak events (occurring at any time of year) for a period of 37 years from 10 January 1979 to 30 December 2015 for 21 locations on the two transects. The hindcast uses CFSR wind fields (Saha et al. 2014) and a MIKE21 spectral wave simulator model (Sorensen et al. 2005) to generate storm time-series at each location. Storm periods were again identified as exceedances of a threshold non-stationary with respect to season and direction, using the procedure of Ewans and Jonathan (2008) for the central location. In this way, a total of 3104 storm events were isolated per location for further analysis.

As will be explained further in Section 3, the SCE model is most conveniently considered for data with marginal standard Laplace distributions. For simplicity, we therefore choose to transform the NNS and CNS samples to standard Laplace scale prior to spatial conditional extremes analysis, as suggested by Keef et al. (2013b), for example. This is achieved by estimating non-stationary marginal models (directional for NNS and directional-seasonal for CNS), following the approach of Ross et al. (2017a) and Ross et al. (2017b), independently per location. Transformed data then follow a standard Laplace distribution for each location.

Figure 1 illustrates that the inter-location spacing for the NNS hindcast is considerably larger than for the CNS hindcast. For this reason, it is important we compare the variation

of extremal spatial dependence between locations explicitly as a function of physical distance (here in kilometres, km). Scatter plots of Laplace-scale storm peak H_S for pairs of locations separated by distances of 43.0, 171.8 and 300.7 km along the NNS north-south (NNS:N-S) transect, coloured red in Figure 1, are shown by the black points in Figure 4 (see Section 5.1).

3. SPATIAL CONDITIONAL EXTREMES

3.1. Characterising extremal dependence

Key concepts in assessing extremal dependence are the notions of asymptotic dependence (AD) and asymptotic independence (AI). Typically, these are assessed through calculating two quantities, χ and $\bar{\chi}$, introduced by Coles et al. (1999). For bivariate data (X, Y) with common margins, the quantity χ is calculated as

$$\chi = \lim_{u \rightarrow u_F} \mathbb{P}(Y > u | X > u),$$

where u_F is the upper endpoint of the common marginal distribution F of the random variables. Then $\bar{\chi}$ is defined by Coles et al. (1999) as $\bar{\chi} = 2\eta - 1$. Here, η , known as the coefficient of tail dependence, is defined by Ledford and Tawn (1996) from the asymptotic approximation, as $z \rightarrow u_F$,

$$\mathbb{P}(X > z, Y > z) \sim L\left(\frac{1}{\mathbb{P}(X > z)}\right) [\mathbb{P}(X > z)^{1/\eta}],$$

where $L(w)$ is a slowly varying function, so that $L(tw)/L(w) \rightarrow 1$ as $w \rightarrow \infty$ for $t > 0$. Coles et al. (1999) provide details on how to calculate estimates for χ and $\bar{\chi}$. Then $\chi > 0$ defines the extent of AD present, whereas $\chi = 0$ suggests the variables exhibit AI. In the latter case, $\bar{\chi}$ measures the extent of AI present. Tawn et al. (2018) present a spatial equivalent for these measures. Crucially, the spatial characteristics under these two limiting extremal behaviour types are very different; under AD, two (or more) extreme events may occur at

separate sites simultaneously, whilst under AI this is not the case. Realistically, a spatial field is likely to exhibit a mixture of these behaviours: at short inter-location distance, asymptotic dependence may prevail; for sites a large distance apart, asymptotic independence is more likely, leading to independence at very large distances. The SCE model accommodates both these possibilities.

3.2. The conditional extremes model of Heffernan and Tawn (2004)

In its simplest form, for a sample from a pair (X, Y) of random variables with Laplace marginal distributions, for x larger than some suitable threshold u , the model proposed by Heffernan and Tawn (2004) is

$$Y|\{X = x\} = a(x) + b(x)Z, \quad (1)$$

where Z is a residual process with typically unknown distribution function G . A particular form that may be utilised when working with Laplace margins is to set $a(x) = \alpha x$ and $b(x) = x^\beta$, for $-1 \leq \alpha \leq 1$ and $0 \leq \beta \leq 1$. This form of the conditional extremes model is used as the basis for the rest of this paper. We also assume that the unknown residual distribution G is Gaussian.

This model may be extended to a general multivariate case. Let Z be a multivariate Gaussian distribution with marginal distributions $N(\mu_j, \sigma_j^2)$ ($j = 0, \dots, n$) for a set of spatial random variables (X_0, \dots, X_n) with standard Laplace margins. Then we have a multivariate model given by

$$(X_1, \dots, X_n)|\{X_0 = x\} \sim \text{MVN}(\boldsymbol{\alpha}x + \boldsymbol{\mu}x^\beta, \mathbf{B}\boldsymbol{\Sigma}\mathbf{B}^T), \quad (2)$$

where $x > u$, $\boldsymbol{\alpha} = (\alpha_1, \dots, \alpha_n)^T$, $\boldsymbol{\beta} = (\beta_1, \dots, \beta_n)^T$, $\boldsymbol{\mu} = (\mu_1, \dots, \mu_n)^T$, and $\mathbf{B} = \text{diag}(x^{\beta_1}, x^{\beta_2}, \dots, x^{\beta_n})$, and $\boldsymbol{\Sigma}$ is the variance-covariance matrix of the residuals Z . In

expression (2), vector operations are carried out component-wise.

We then have marginal models for $j = 1, \dots, n$ given by

$$X_j | \{X_0 = x\} \sim N(\alpha_j x + \mu_j x^{\beta_j}, \sigma_j^2 x^{2\beta_j}).$$

Equation (2) corresponds to the multivariate extension of Equation (1), in which information about parameters $\theta = \{\alpha_i, \beta_i, \mu_i, \sigma_i\}_{i=1}^n$ can be shared between random variables. The increased number of parameters, as compared to Equation (1), means that this model is more computationally-challenging to estimate.

3.3. The spatial conditional extremes (SCE) model

The SCE model is a spatial extension of the conditional extremes model, following the work of Tawn et al. (2018) and Wadsworth and Tawn (2018). First suppose that $X(\cdot)$, the process of interest, is stationary and isotropic and has Laplace marginal distributions. Also suppose that we have sampling locations $s, s_0 \in \mathcal{S}$, where \mathcal{S} is some spatial domain. Then for $h = |s - s_0|$, the distance or lag between two sites, we have

$$X(s) | \{X(s_0) > u\} = \alpha(h)X(s_0) + X(s_0)^{\beta(h)}Z(s - s_0). \tag{3}$$

For a set of fixed spatial locations, Equations (2) and (3) are equivalent if we assume that Z is a residual Gaussian process with mean function $\mu(h)$ and covariance incorporating $\sigma(h)$, as described in Equations (4) and (6). Of key importance is that different combinations of parameter values correspond to different types of spatial dependence. We have AD at all distances h when $\alpha(h) = 1$ and $\beta(h) = 0$ for all $h \geq 0$, while a mixture of limiting dependence classes is observed if $(\alpha(h), \beta(h)) = (1, 0)$ for $h \leq h_{AD}$ but also $\alpha(h) < 1$ for $h > h_{AD}$, for some distance h_{AD} . The process exhibits AD up to distance h_{AD} and AI thereafter. Hence, the proposed framework is able to estimate extremal dependence flexibly.

The model set out in expression (3) gives the behaviour of the process conditional on the process being extreme at s_0 . We need this model to hold for all $s_0 \in \mathcal{S}$, and for all of these conditional distributions to be self-consistent with one another. Although the original multivariate conditional extremes models of Heffernan and Tawn (2004) do not impose additional assumptions about pairwise exchangeability, our choice of a stationary isotropic model imposes the required structure on the different conditional models to yield the required self-consistency.

Although not key to developments in this paper, a natural question is whether the conditional models stem from a valid stochastic process. This is clarified by Wadsworth and Tawn (2018). They show that extreme events arising from a valid stochastic process can be generated over space, in such a way that events can be extreme at any spatial location. Therefore, although the SCE model is not explicitly specified as a stochastic process over space, it is specified implicitly for a process that has an extreme event somewhere in \mathcal{S} . In this paper, we focus only on questions relating to the behaviour of the process given that there is an extreme event somewhere in \mathcal{S} . Wadsworth and Tawn (2018) discuss an extension for which this condition is removed.

3.4. Constraints

For a given h , we constrain the possible values of pairs of parameters $(\alpha(h), \beta(h))$ as suggested by Keef et al. (2013a), and outlined in the Appendix. The motivation for this constraint is to impose an ordering of conditional distributions associated with asymptotic independence ($\alpha(h) < 1$) and asymptotic positive dependence ($\alpha(h) = 1, \beta(h) = 0$). In practice, this means that certain combinations of $(\alpha(h), \beta(h))$ are inadmissible. We also impose gradient-based constraints on $(\alpha(h), \beta(h))$ following Lugrin (2018), in order to improve the identifiability of the parameter combinations. The motivation for these constraints is ensuring that the derivative, with respect to x , of $\mathbb{E}(X(h)|X(0) = x) = \alpha(h)x + \mu(h)x^{\beta(h)}$ is positive, for $x \geq u$,

with u some suitable threshold; we then have the constraints $\alpha(h) + \mu(h)\beta(h)x^{\beta(h)-1} \geq 0$ and $\alpha(h) \geq 0$ for all h .

4. INFERENCE

We consider two variants of the SCE model, differing by the manner in which “linear slope” parameters $\{\alpha_k\}$ are estimated. In the more general form, outlined in Section 4.1, these parameters are estimated freely given the sample data, likelihood function and constraints from Section 3.4. In the restricted parametric form, outlined in Section 4.2, the decay of α with distance h follows a prescribed physically-plausible exponential form described by only two parameters. We first consider the more general “free” model.

4.1. Likelihood for the “free” model

Consider $p + 1$ equally-spaced points on a transect. Suppose we condition on the value of H_S at a point on the line, marked in black in the two examples of Figure 2. Our goal is to fit a joint distribution for the values of H_S at all remaining points, conditioned on an extreme value observed at the conditioning point.

As the set of remaining random variables depends on the conditioning point chosen, we require two indices to define locations: an index $c \in \{0, 1, 2, \dots, p\}$ to indicate the “conditioning” point, and an index $j \in \{1, 2, \dots, p\}$ for the remaining points on the line, which we henceforth call “remote” points. The conditioning point will therefore always have an index of the form $(c, 0)$, as illustrated in Figure 2, where $c = 0$ in the upper image, and $c = 2$ in the lower.

We indicate the location of the conditioning point as s_{c0} , and the location of remote points using $\{s_{cj}\}$. The distances of remote points to the conditioning point are then denoted by $\{h_{c0j}\}$, with $h_{c0j} = |s_{cj} - s_{c0}|$. Similarly, distances between remote points (c, j) and (c, j') are denoted $\{h_{cjj'}\}$ with $h_{cjj'} = |s_{cj'} - s_{cj}|$; example values of (c, j) and h_{c0j} are indicated in

Figure 2. In the case of the lower image in Figure 2, note that there are locations that sit a common distance from the conditioning point (with the same value of h_{c0j} , shown as discs of the same colour).

[Figure 2 about here.]

We assume that conditional dependence is isotropic on a transect, so that the parameters of the SCE model are at most a function of inter-location distances only. Specifically, the parameters α , β , μ and σ are functions of distance from conditioning location, and the residual dependence between remote locations will in addition be a function of distances between remote locations. We seek a model for the joint dependence structure for any number of locations conditional on an extreme value at the conditioning location. For definiteness, consider first the case of two remote locations (c, j) and (c, j') (with $j' \neq j$) and conditioning location $(c, 0)$, and corresponding random variables $(X_{cj}, X_{cj'}, X_{c0})$. We can then write the SCE model as

$$(X_{cj}, X_{cj'}) | \{X_{c0} = x_{c0}\} \sim \text{MVN}_2(\mathcal{M}_{cjj'}, \mathcal{C}_{cjj'}), \quad x_{c0} > q_\tau \quad (4)$$

where q_τ is the quantile of a standard Laplace distribution with non-exceedance probability τ ,

$$\mathcal{M}_{cjj'} = [\alpha(h_{c0j}), \alpha(h_{c0j'})]x_{c0} + [\mu(h_{c0j}), \mu(h_{c0j'})]x_{c0}^{[\beta(h_{c0j}), \beta(h_{c0j'})]}$$

and

$$\begin{aligned} \mathcal{C}_{cjj'} &= \begin{bmatrix} x_{c0}^{\beta(h_{c0j})} & 0 \\ 0 & x_{c0}^{\beta(h_{c0j'})} \end{bmatrix} \begin{bmatrix} \sigma(h_{c0j}) & 0 \\ 0 & \sigma(h_{c0j'}) \end{bmatrix} \begin{bmatrix} 1 & \rho^{h_{cjj'}} \\ \rho^{h_{cjj'}} & 1 \end{bmatrix} \\ &\times \begin{bmatrix} \sigma(h_{c0j}) & 0 \\ 0 & \sigma(h_{c0j'}) \end{bmatrix}^T \begin{bmatrix} x_{c0}^{\beta(h_{c0j})} & 0 \\ 0 & x_{c0}^{\beta(h_{c0j'})} \end{bmatrix}^T \end{aligned} \quad (5)$$

and ρ is the between-neighbour residual correlation parameter. We can extend the model to three or more remote locations, or reduce it for one remote location in the obvious way. Hence we can construct a sample Gaussian likelihood L under the model for all observations, with conditioning variate exceeding q_τ , of all possible combinations of two or more locations on the line. We note that in Equation (5), any correlation function $K(\cdot)$ could be used in the third matrix; for this work, we specifically use an exponential correlation function, so that $K(h_{c_j j'}) = \rho^{h_{c_j j'}}$.

The likelihood L is a function of $\{\alpha(h_{c0j}), \beta(h_{c0j}), \mu(h_{c0j}), \sigma(h_{c0j})\}$, and ρ (for different distances $\{h_{c_j j'}\}$ between remote locations). Since the locations are equally-spaced, the values of α , β , μ and σ can only be estimated for given distances $h = k\Delta$, for lag index $k = 1, 2, \dots, p$, where Δ is the location spacing for the application (expressed in kilometres). For ease of discussion below, we can therefore write $L \triangleq L(\theta)$ for the full parameter set as

$$\theta = \{\{\alpha_k, \beta_k, \mu_k, \sigma_k\}_{k=1}^p, \rho\}, \tag{6}$$

where parameters are indexed by lag k not distance h , so that $\alpha_k = \alpha(k\Delta)$, etc.

In practice, we also pool all available observations corresponding to unique combinations of distances (i.e., from different choices of conditioning location $(c, 0)$) in the SCE likelihood; we thereby exploit the sample well, in a computationally-favourable manner. Hence, we no longer have the true likelihood under our model but instead a pseudo-likelihood, since the same observation (of each location on a transect) may enter more than one conditioning likelihood contribution (corresponding to conditioning on extreme values at a particular location). Using a pseudo-likelihood as if it is a likelihood is widely known to give point estimates that are asymptotically consistent, but that measures of uncertainty are underestimated. In our Bayesian inference, we expect to underestimate posterior credibility intervals using these pooled data.

Various approaches are available to adjust estimated uncertainty, either by inflating variances or modifying the pseudo-likelihood. In Bayesian inference, the methods of Ribatet et al. (2012) provide an appropriate approach to valid inference for any selected model. In this paper, however, we use the raw pseudo-likelihood for presentation of results, which we justify as follows. The paper focuses on model selection between the free model introduced in this section and a nested parametric model, introduced in Section 4.3, with the actual uncertainties of the parameters being of secondary importance relative to the selection of the better model. When using the pseudo-likelihood in place of the full likelihood, inference for the free model will give parameter estimates with credible intervals which are too narrow. Thus, if our subsequent parametric model estimates fall inside these intervals, it suggests that the parametric model provides a better fit than the free model. We emphasise that credible intervals referred to in this work correspond to pseudo-likelihood credible intervals.

4.2. MCMC for the free model

We use Bayesian inference to estimate the joint posterior distribution of parameters θ from Equation (6). In our experience, Bayesian inference with reasonable prior specification and MCMC scheme, provides a more reliable approach to parameter estimation, than maximum likelihood techniques. An outline of the procedure, discussion of the priors used and an algorithm, are given in the Appendix. In brief, we proceed as follows.

First, we use random search to find a reasonable starting value for θ . Then, to improve on the starting solution, we use a Metropolis-within-Gibbs algorithm iteratively to sample each of the elements of θ in turn. Then we use a *grouped adaptive* random walk Metropolis-within-Gibbs algorithm iteratively to convergence, judged to have occurred when trace plots for parameters and their dependence stabilise. Within the grouped adaptive algorithm, we jointly update the parameters $(\alpha_k, \beta_k, \mu_k, \sigma_k)$ for each k , following the adaptive approach of Roberts and Rosenthal (2009) to make correlated proposals. We also adjust proposal standard deviation such that the acceptance rate is optimised for all parameters.

4.3. Inference for the “parametric- α ” model

Though the constraints of Section 3.4 go some way to improving identifiability of suitable parameter combinations, it is still difficult to obtain plausible results in some cases for the free SCE model. Therefore, we shall consider a parametric form for α based on physical considerations, whereby $\alpha(h)$ should in general decrease with increasing h , but also to reduce the dimension of the parameter space, helping parameter identifiability. Specifically, we explore the performance of a SCE model where α is parameterised as a function of distance, writing

$$\alpha_k = \exp \left\{ - \left(\frac{k}{\kappa_1} \right)^{\kappa_2} \right\}, \quad k = 1, 2, \dots, p \tag{7}$$

with parameters $\kappa_1, \kappa_2 > 0$. The resulting likelihood is $L \triangleq L(\theta^*)$ with adjusted parameter set

$$\theta^* = \{ \kappa_1, \kappa_2, \{ \beta_k, \mu_k, \sigma_k \}_{k=1}^p, \rho \}. \tag{8}$$

The MCMC procedure for the parametric- α model is similar to that for the free model, except that κ_1, κ_2 are separated from the grouped parameters $(\beta_k, \mu_k, \sigma_k)$ for each k .

4.4. Comparison of free and parametric- α models

To compare results from free and parametric- α models, we use the Deviance Information Criterion (DIC), as proposed by Spiegelhalter et al. (2002), a Bayesian analogue of the Akaike Information Criterion (Akaike 1974). Defining $D(\theta) = -2 \log L(\theta)$, where L is our pseudo-likelihood, we measure model complexity using

$$p_D = \overline{D(\theta)} - D(\bar{\theta}),$$

where $\overline{D(\theta)}$ is the average of the deviances (calculated after burn-in) and quantifies lack-of-fit. Further, $\bar{\theta}$ is the average of posterior estimates of θ , and note that this is an estimate for the posterior mean. Explicitly, from the final m iterations of the MCMC chain, we calculate

$$\bar{\theta} = \frac{1}{m} \sum_{i=1}^m \theta^{(i)} \quad \text{and} \quad \overline{D(\theta)} = \frac{1}{m} \sum_{i=1}^m D(\theta^{(i)}),$$

where component-wise averages are taken in the first equation. The DIC is then calculated as

$$DIC = p_D + \overline{D(\theta)} = 2\overline{D(\theta)} - D(\bar{\theta}),$$

with lower values preferred.

5. APPLICATION TO NORTHERN NORTH SEA NORTH-SOUTH TRANSECT (NNS:N-S)

We now apply the free model and parametric- α model to data for the NNS:N-S transect. We start by considering the free model in some detail (in Section 5.1), demonstrating that the fitted model explains the data well. Next, in Section 5.2, we consider the corresponding parametric- α model, and show that this also fits well, as well as using the DIC, as defined in Section 4.4, to show that the fit of free and parametric- α models is similar. The analysis is extended to other transects and locations in Section 6. Throughout this section, we adopt a conditioning threshold with non-exceedance probability $\tau = 0.9$ for the SCE model, after testing the stability of inferences to other choices of threshold. Threshold choice of course involves a bias-variance trade-off: increasing sample size for tail modelling versus inclusion of points from outside the tail region. We note that parameter estimates were relatively stable for choices of extreme value threshold above $\tau = 0.8$ and below either $\tau = 0.9$ (for NNS data)

or $\tau = 0.95$ (for CNS data).

5.1. Free model

The inference scheme introduced in Section 4 is used to estimate parameters θ (see Equation (6)) for the NNS:N-S transect. Posterior mean and pseudo-likelihood credible intervals for estimates of each of $\alpha(h)$, $\beta(h)$, $\mu(h)$ and $\sigma(h)$ from the final 1000 iterations (out of a total of 20000 iterations) of the MCMC algorithm described in Section 4.2 are shown in Figure 3. Trace plots showing convergence of MCMC chains are given in the Supplementary Material accompanying this article. We note that the parameter ρ has a posterior mode of approximately 0.73 and a 95% pseudo-likelihood credible interval with width of approximately 0.09.

[Figure 3 about here.]

We see from Figure 3 that α decays exponentially with h ; this motivates the adoption of the parametric- α model in Section 5.2. In particular, we see that $\alpha(h) \neq 1$ for any h , so this suggests asymptotic independence is present for all distances h . We see that $\mu(h)$ mirrors the behaviour of $\alpha(h)$ to some extent, in that for $h < 200$ km, μ increases fairly quickly, before stabilising and possibly decreasing again; this illustrates the anticipated dependence between estimates for α and μ in the conditional extremes model. The parameter β is relatively constant with h , taking values between 0.3 and 0.4, whereas σ increases in general with h . The behaviour of $\alpha(h)$ and $\sigma(h)$ appears reasonable given physical intuition and evidence from the data (the black points) in Figure 4: extremal dependence reduces as distance between conditioning and remote sites increases, yet the overall variability at each location is constant given that H_S at each location has been transformed to standard Laplace scale.

Figures 4 and 5 display diagnostics for the fitted model. Figure 4 shows the original data on Laplace scale (in black), at three different separations h of remote and conditioning points.

Data simulated under the fitted model are overlaid in red; there is good general agreement. Figure 5 shows observed sequences of H_S values along transects with conditioning value (of H_S at either end-point of the transect) between 3.5 and 4.5 on Laplace scale in blue, as well as two simulated spatial processes from the fitted model, shown in red. The figure also shows the corresponding 95% pseudo-likelihood credible interval under the fitted SCE model with conditioning values between 3.5 and 4.5; again there is general agreement between observation and simulation under fitted model; in particular the simulated processes appear to have similar smoothness to the observed processes.

[Figure 4 about here.]

[Figure 5 about here.]

5.2. “Parametric- α ” fit

Figure 3 suggests an exponential decay of parameter α with distance h in the free model. Here, we examine the performance of the SCE model with the functional form for $\alpha(h)$ given in Equation (7) and with parameters θ^* to estimate (as defined in (8)).

[Figure 6 about here.]

Comparing Figures 3 and 6 shows that pseudo-likelihood credible intervals for $\alpha(h)$ are considerably narrower in the parametric- α model. This is not surprising, since the parametric- α model has a smaller number of parameters. Moreover, the parametric decay of α in the parametric- α model restricts its possible values for any h . Further, they show that posterior mean estimates for $\alpha(h)$, $\beta(h)$, $\mu(h)$ and $\sigma(h)$ are similar under the two models.

The informal discussion above suggests that the quality of fit of free and parametric- α models is similar. To compare these models more formally, we use the DIC introduced in Section

4.4. Values for parameter estimates and likelihood from the last $m=1000$ MCMC iterations are used to estimate the DIC for the two models; the DIC for the free model was calculated to be 27514.22, and for the parametric- α model 27501.68. Since the DIC for the parametric- α model is smaller than for the free model, we infer in this case that the parametric- α model is to be preferred, and that the difference between free and parametric- α fits is small. However, the parametric- α model has the additional advantage that the computational time is decreased due to the smaller number of parameters to estimate in this version of the SCE model.

6. APPLICATION TO OTHER NORTH SEA TRANSECTS

The wave environment in the NNS and CNS is known not to be isotropic (e.g. Feld et al. 2015); we might therefore suspect that the extremal spatial dependence in these neighbourhoods might also be sensitive to transect orientation. Inspection of Figure 1 shows that fetches in the NNS are in general longer than in the CNS; further, water depths in the NNS are greater than those in the CNS. It is not unreasonable therefore to anticipate that extremal spatial dependence may be different in different regions of the North Sea. Moreover, for the data considered here, the CNS data are available on a finer grid than for the NNS data, so we may be able to pick out finer-scale features of the dependence structure. Furthermore, the lengths of transects and their spatial resolutions vary, offering the possibility of detecting finer-scale effects (in the CNS) and longer-range effects (for transects with largest distances h). This motivates estimating SCE models for the NNS:E-W transect, and the CNS:N-S and CNS:E-W transects.

Below, we start by comparing DIC values for free and parametric- α models. Since it was found that the performance and characteristics of the models were similar for all transects, subsequent discussion of parameter behaviour with h is restricted to the parametric- α model. As in Section 5, all MCMC chains are of length 20000, and we utilise the final 1000 iterations

for inference.

6.1. Comparison of Model Fits for all Transects

We compare DIC values for free and parametric- α model parameterisations to assess in particular whether the parametric- α model is a reasonable general representation for all transects, relative to the free model. Table 1 gives values for the DIC for each of the transects considered in this work.

[Table 1 about here.]

From the table, we see that the DIC is lower for the parametric- α model for NNS transects; for the CNS transects, the free model produces lower values for the DIC. However, comparing the differences between DIC values per transect with the variability of the corresponding negative log-likelihoods from the MCMC, we see that differences in the DIC are small in each case. We conclude that there is little material difference between free and parametric- α fits for any of the transects.

6.2. NNS east-west transect

We first apply the parametric- α model to NNS:E-W, coloured magenta in Figure 1, using a non-exceedance probability of $\tau = 0.9$ when applying the SCE model, as in Section 5. Posterior estimates for model parameters are shown in Figure 7. This transect has fewer sites available for analysis than NNS:N-S in Section 5, and hence fewer data may be pooled together for estimation. Therefore, we would naturally expect model parameter uncertainties to be larger. From the figure it is clear that the pseudo-likelihood credible intervals are wider than for NNS:N-S, at similar h .

[Figure 7 about here.]

The behaviour of parameter estimates for μ and σ with h are similar to those observed for NNS:N-S. However, in NNS:E-W, β increases with distance. The figure also illustrates that estimates for $\alpha(h)$ on NNS:E-W are larger; in particular, $\alpha(h \approx 50 \text{ km}) \approx 0.9$, suggesting that dependence is much higher at short range for NNS:E-W than for NNS:N-S, for which $\alpha(h \approx 50 \text{ km}) \approx 0.6$. Further, the rate of decay of α with h is smaller for NNS:E-W than for NNS:N-S. These findings are plausible given physical intuition: the largest events in the NNS are Atlantic storms travelling approximately E-W. It is reasonable then to expect that spatial dependence along E-W transects may be higher than for transects with other orientations.

6.3. CNS transects

For the central North Sea north-south transects (CNS:N-S, coloured dark blue in Figure 1; and CNS:E-W coloured cyan), the separation Δ of locations is smaller than for NNS transects. Furthermore, as more data are available at each site for this ocean basin, we set $\tau = 0.95$ for the SCE model. Parameter estimates from the parametric- α model are shown in Figure 8 for CNS:N-S.

[Figure 8 about here.]

Compared to NNS transects, α decreases quickly with h . At $h \approx 100 \text{ km}$ the value of α is approximately 0.5, close to that estimated for the NNS:N-S transect at $h \approx 150 \text{ km}$, but at $h \approx 250 \text{ km}$ for NNS:E-W. The behaviour of μ and σ with h is similar to earlier cases, and β is approximately constant at approximately 0.3, and σ at 0.52. Pseudo-likelihood credible intervals for estimates increase with h .

For the CNS:E-W transect, posterior estimates for the SCE parameters are shown in Figure 9; this transect is slightly longer than the CNS:N-S transect.

[Figure 9 about here.]

The parameter μ increases with h , and β is approximately constant at approximately 0.33. There is some evidence that $\sigma(h)$ decreases for $h > 50$ km. The general behaviour of α with h is similar to that for the CNS:N-S transect, with a somewhat slower decay.

7. DISCUSSION AND CONCLUSIONS

In this work, we use a spatial conditional extremes model to investigate the extremal dependence of significant wave height H_S along straight line transects of different lengths with different spatial orientations and resolutions in the northern and central North Sea. The analyses described in Sections 5 and 6 suggest that the general nature of extremal dependence is similar for all transects. It appears that the linear dependence parameter α in the SCE model decays with separation h of locations, and that this decay is approximately exponential (recalling that H_S is expressed on standard Laplace scale). The parameter μ increases with h , potentially to a finite asymptote, while the parameter β appears to remain approximately constant as a function of h . There is some evidence that σ increases initially with h , but no consistent subsequent behaviour is observed.

Features of the extremal dependence vary by region and transect orientation. For instance, we note that the estimate of ρ , the residual dependence parameter, for the NNS:N-S transect (with a posterior mode of approximately 0.73 and a 95% pseudo-likelihood credible interval width of approximately 0.06) is different from its value for the other three transects (for which ρ is estimated to have a mode of approximately 0.5 in each case, and 95% pseudo-likelihood credible intervals of width of approximately 0.06). Figure 10(a) illustrates the behaviour of the conditional mean $\alpha(h)x + \mu(h)x^{\beta(h)}$ from the SCE model for a (Laplace-scale) conditioning value $x = 5$, approximately corresponding to the 0.997 quantile. Figure 10(b) shows the corresponding evolution of the conditional standard deviation $\sigma(h)x^{\beta(h)}$.

[Figure 10 about here.]

From Figure 10 it is clear that extremal dependence of H_S in the NNS is more persistent than in the CNS, and that extremal dependence on the NNS:E-W transect is more persistent than on the NNS:N-S transect (see also Section 6.2). That is, longer-range extremal dependence is observed for the E-W transect in the NNS; the same conclusion was drawn by Ross et al. (2017a) in their analysis of related data for the same region, using one- and two-dimensional max-stable process models. It will be interesting to extend the current SCE model to two-dimensional neighbourhoods of locations, particularly to investigate whether directional differences, related to differences due to transect orientation reported here, are observed.

From an intuitive perspective, we expect the value of SCE parameter α to decay to zero for large h , since for large h the value at the conditioning location should not affect the value at the remote location. For the same reason, we expect $\beta(h)$ and $\mu(h)$ to decay to zero, and $\sigma(h)$ to asymptote to a finite value; see Wadsworth and Tawn (2018) for discussion of the modelling of spatial independence at long range. We plan to examine this by exploring the characteristics of storm peak H_S on long transects extending over at least 1000 km.

Inspection of Equations (2) or (5) readily shows that identification of SCE model parameters is problematic in general, although considerations such as those of Keef et al. (2013a) help restrict the admissible set of parameter values. Imposing an exponential form on the decay of $\alpha(h)$ with h was found at least not to be detrimental in the current work. Inspection of the resulting behaviour of parameter estimates in the figures above suggests that further parameterisation of $\mu(h)$ in particular may be useful.

Understanding the extremal spatial dependence of ocean storms is important for the reliable characterisation of extreme storms and their impact on marine and coastal facilities and habitats. From a statistical perspective, the ocean environment provides a useful test bed for models for spatial extremal dependence over a range of distances. From an offshore engineering perspective, the findings of studies such as the present work can lead to

more informed procedures to accommodate the effects of spatial dependence in engineering design guidelines. The spatial conditional extremes model would seem to offer a relatively straightforward method to help achieve this.

8. ACKNOWLEDGEMENTS

The authors would like to acknowledge discussions with David Randell and Matthew Jones at Shell and Jenny Wadsworth at Lancaster University. R. Shooter acknowledges financial support from EP/L015692/1 (STOR-i Centre for Doctoral Training) and Shell Research Ltd. We thank referees for their very helpful comments.

DATA AVAILABILITY STATEMENT

The data are confidential and cannot be shared generally. It may be possible to obtain permission to access the original data from the data owners; the authors can assist with this process. Interested parties should contact the corresponding author for further information.

APPENDIX

This appendix summarises the constraints on the conditional extremes model introduced by Keef et al. (2013a), and the MCMC procedure used for parameter estimation.

The constraints of Keef et al. (2013)

We also constrain the possible parameter values of $\alpha(h)$ and $\beta(h)$, for $h > 0$, as suggested by Keef et al. (2013a). The constraint of interest, for $\alpha(h)$, $\beta(h)$ and some given h , in this work is Case 1 of Theorem 1 as given by Keef et al. (2013a); namely that we require either

$$\alpha(h) \leq \min\{1, 1 - \beta(h)z_h(q)v^{\beta(h)-1}, 1 - v^{\beta(h)-1}z_h(q) + v^{-1}z_h^+(q)\}$$

or

$$1 - \beta(h)z_h(q)v^{\beta(h)-1} < \alpha(h) \leq 1, \text{ and}$$

$$(1 - \beta(h)^{-1})\{\beta(h)z_h(q)\}^{1/(1-\beta(h))}(1 - \alpha(h))^{-\beta(h)/(1-\beta(h))} + z_h^+(q) > 0.$$

Here, $z_h(q)$ is the q th quantile of the distribution of standardised residuals from the conditional extremes model at distance h with non-exceedance probability q . Similarly, $z_h^+(q)$ is the q th quantile of the distribution of standardised residuals from the conditional extremes model assuming asymptotic positive dependence (i.e., forcing $\alpha(h) = 1, \beta(h) = 0$) at distance h with non-exceedance probability q . In practice, as suggested by Keef et al. (2013a), it is sufficient to satisfy the constraints above for $q = 1$ and ν equal to the maximum observed value of the conditioning variate.

MCMC procedure

The MCMC method implemented in Section 4.2 is adapted from the method of Roberts and Rosenthal (2009). Suppose the parameters of interest are $\boldsymbol{\theta} = \{\alpha_k, \beta_k, \mu_k, \sigma_k\}_{k=1}^p \cup \{\rho\}$, where p is the number of sampling locations. The total number of parameters is therefore $n_P = 4p + 1$. We impose uniform prior distributions for each of these parameters; explicitly, $\pi(\alpha_k) \sim \text{Unif}(0, 1)$, $\pi(\beta_k) \sim \text{Unif}(0, 1)$, $\pi(\mu_k) \sim \text{Unif}(-2, 2)$ and $\pi(\sigma_k) \sim \text{Unif}(0, 3)$ for all $k = 1, \dots, p$, and $\pi(\rho) \sim \text{Unif}(0, 1)$. A total of n updates of $\boldsymbol{\theta}$ will be performed.

First we obtain a random starting solution $\boldsymbol{\theta}^{(0)}$ by sampling the elements of $\boldsymbol{\theta}$ from their prior distributions, verifying that the starting solution has a valid likelihood (defined in Section 4.1).

Writing $\theta_k^{(i)}$ as the value of the k th parameter of $\boldsymbol{\theta}$ at the i th iteration, we then use an adaptive random walk Metropolis-within-Gibbs scheme for n_S iterations. That is, for $i = 2, \dots, n_S$, where $n_S < n$, we update each $\theta_k^{(i)}$ in turn. If $i \leq 2n_P$, we propose a candidate value $\theta_k^{(i)c}$

from distribution

$$Q_1 = N(\theta_k^{(i-1)}, 0.1^2).$$

For $i > 2n_P$ (and $i \leq n_S$) we propose $\theta_k^{(i)c}$ from distribution Q_2 defined by

$$Q_2 = (1 - \beta)N(\theta_k^{(i-1)}, 2.38^2\Sigma_i) + \beta N(\theta_k^{(i-1)}, 0.1^2),$$

where $\beta = 0.05$, as proposed by Roberts and Rosenthal (2009), and Σ_i is the empirical covariance of the parameter θ_k from the previous i iterations.

For $i > n_S$, we use a grouped adaptive random walk Metropolis-within-Gibbs scheme, updating quartets $\boldsymbol{\theta}_{G_k}^{(i)} = (\alpha_k^{(i)}, \beta_k^{(i)}, \mu_k^{(i)}, \sigma_k^{(i)})$ jointly, before updating ρ independently as before. If $i \leq n_S + 2n_P$, and the quartet state is $\boldsymbol{\theta}_{G_k}^{(i)}$, we propose candidates $\boldsymbol{\theta}_{G_k}^{(i)c}$ from distribution

$$Q_3 = MVN(\boldsymbol{\theta}_{G_k}^{(i-1)}, (0.1^2)/4).$$

If $i > n_S + 2n_P$, we propose $\boldsymbol{\theta}_{G_k}^{(i)c}$ from distribution

$$Q_4 = (1 - \beta)MVN(\boldsymbol{\theta}_{G_k}^{(i-1)}, 2.38^2\Sigma_i) + \beta MVN(\boldsymbol{\theta}_{G_k}^{(i-1)}, 0.1^2/4),$$

where again $\beta = 0.05$ and Σ_i is the empirical variance-covariance matrix of the parameters $\boldsymbol{\theta}_{G_k}^{(i)}$ from the previous i iterations. Finally we update ρ .

Throughout, a candidate state is accepted using the standard Metropolis-Hastings acceptance criterion. Since prior distributions for parameters are uniform, and proposals symmetric, this is effectively just a likelihood ratio. That is, we accept the candidate state with probability $\min(1, L^c/L)$, where L and L^c are the likelihoods evaluated at the current and candidate states respectively, with candidates lying outside their prior domains rejected.

The MCMC procedure is summarised in the following Algorithm 1.

```

Sample  $\boldsymbol{\theta}^{(0)}$  from prior distributions;
for  $i = 1, 2, \dots, n$  do
  if  $i \leq n_S$  then
    (Adaptive Random Walk Metropolis-within-Gibbs);
    if  $i \leq 2n_P$  then
      for  $k = 1, 2, \dots, n_P$  do
        | Propose  $\boldsymbol{\theta}_k^{(i)c}$  from  $Q_1$  then accept or reject;
      end
    end
  else
    for  $k = 1, 2, \dots, n_P$  do
      | Propose  $\boldsymbol{\theta}_k^{(i)c}$  from  $Q_2$  then accept or reject;
    end
  end
end
if  $i > n_S$  then
  (Grouped Adaptive Random Walk Metropolis-within-Gibbs);
  if  $i \leq n_S + 2n_P$  then
    for  $k = 1, 2, \dots, p - 1$  do
      | Propose  $\boldsymbol{\theta}_{G_k}^{(i)}$  from  $Q_3$  then accept or reject;
    end
    Propose candidate from  $Q_1$  for  $\rho$  then accept or reject;
  end
  else
    for  $k = 1, 2, \dots, p - 1$  do
      | Propose  $\boldsymbol{\theta}_{G_k}^{(i)c}$  from  $Q_4$  then accept or reject;
    end
    Propose candidate from  $Q_2$  for  $\rho$  then accept or reject;
  end
end
end

```

Algorithm 1: Adaptive random walk Metropolis-within-Gibbs algorithm.

REFERENCES

- Akaike, H., 1974. A new look at the statistical model identification. *IEEE Trans. Autom. Control* 19, 716–723.
- Brown, B.M., Resnick, S.I., 1977. Extreme values of independent stochastic processes. *Journal of Applied Probability* 14, 732–739.
- Coles, S., Heffernan, J., Tawn, J., 1999. Dependence measures for extreme value analyses. *Extremes* 2, 339–365.
- Davison, A.C., Padoan, S.A., Ribatet, M., 2012. Statistical modelling of spatial extremes. *Statist. Sci.* 27, 161–186.
- Ewans, K.C., Jonathan, P., 2008. The effect of directionality on northern North Sea extreme wave design criteria. *J. Offshore. Arct. Eng.* 130, 041604:1–041604:8.
- Feld, G., Randell, D., Wu, Y., Ewans, K., Jonathan, P., 2015. Estimation of storm peak and intra-storm directional-seasonal design conditions in the North Sea. *J. Offshore. Arct. Eng.* 137, 021102:1–021102:15.
- Ferreira, A., de Haan, L., 2014. The generalized pareto process; with a view towards application and simulation. *Bernoulli* 20, 1717–1737.
- Heffernan, J.E., Tawn, J.A., 2004. A conditional approach for multivariate extreme values. *J. R. Statist. Soc. B* 66, 497–546.
- Huser, R.G., Wadsworth, J.L., 2018. Modeling spatial processes with unknown extremal dependence class. *J. Am. Statist. Soc.* doi:10.1080/01621459.2017.1411813.
- Jonathan, P., Ewans, K.C., Randell, D., 2014. Non-stationary conditional extremes of northern North Sea storm characteristics. *Environmetrics* 25, 172–188.
- Keef, C., Papastathopoulos, I., Tawn, J.A., 2013a. Estimation of the conditional distribution of a vector variable given that one of its components is large: additional constraints for the Heffernan and Tawn model. *J. Mult. Anal.* 115, 396–404.
- Keef, C., Tawn, J.A., Lamb, R., 2013b. Estimating the probability of widespread flood events. *Environmetrics* 24, 13–21.
- Kereszturi, M., 2016. Assessing and modelling extremal dependence in spatial extremes. PhD thesis, Lancaster University, U.K.
- Kereszturi, M., Tawn, J., Jonathan, P., 2016. Assessing extremal dependence of North Sea storm severity. *Ocean Eng.* 118, 242–259.

- Kiriliouk, A., Rootzen, H., Segers, J., Wadsworth, J.L., 2018. Peaks over thresholds modelling with multivariate generalized pareto distributions. *Technometrics* doi:10.1080/00401706.2018.1462738.
- Ledford, A.W., Tawn, J.A., 1996. Statistics for near independence in multivariate extreme values. *Biometrika* 83, 169–187.
- Lugrin, T., 2018. Semi-parametric Bayesian risk estimation for complex extremes. PhD thesis, EPFL, Lausanne, Switzerland.
- Oceanweather, 2002. North European Storm Study User Group Extension and Reanalysis Archive. Oceanweather Inc.
- Reich, B.J., Shaby, B.A., 2012. A hierarchical max-stable spatial model for extreme precipitation. *Ann. Appl. Stat.* 6, 1430–1451.
- Ribatet, M., 2013. Spatial extremes: max-stable processes at work. *Journal de la Societe Francaise de Statistique* 154, 156–177.
- Ribatet, M., Cooley, D., Davison, A., 2012. Bayesian inference from composite likelihoods, with an application to spatial extremes. *Statistica Sinica* 22, 813–845.
- Roberts, G.O., Rosenthal, J.S., 2009. Examples of adaptive MCMC. *J. Comp. Graph. Stat.* 18, 349–367.
- Rootzen, H., Segers, J.L., Wadsworth, J., 2018. Multivariate peaks over thresholds models. *Extremes* 21, 115–145.
- Ross, E., Kereszturi, M., van Nee, M., Randell, D., Jonathan, P., 2017a. On the spatial dependence of extreme ocean storm seas. *Ocean Eng.* 145, 1–14.
- Ross, E., Randell, D., Ewans, K., Feld, G., Jonathan, P., 2017b. Efficient estimation of return value distributions from non-stationary marginal extreme value models using Bayesian inference. *Ocean Eng.* 142, 315–328.
- Saha, S., Moorthi, S., Wu, X., Wang, J., Nadiga, S., Tripp, P., Behringer, D., Hou, Y.T., ya Chuang, H., Iredell, M., Ek, M., Meng, J., Yang, R., Mendez, M.P., van den Dool, H., Zhang, Q., Wang, W., Chen, M., Becker, E., 2014. The NCEP Climate Forecast System Version 2. *Journal of Climate* 27, 2185–2208.
- Schlather, M., 2002. Models for stationary max-stable random fields. *Extremes* 5, 33–44.
- Smith, R.L., 1990. Max-stable processes and spatial extremes. Unpublished article, available electronically from www.stat.unc.edu/postscript/rs/spatex.pdf.
- Sorensen, O.R., Kofoed-Hansen, H., Rugbjerg, M., Sorensen, L.S., 2005. A third-generation spectral wave model using an unstructured finite volume technique. *Proceedings of the 29th International Conference on Coastal Engineering*.

- Spiegelhalter, D., Best, N., Carlin, B., van der Linde, A., 2002. Bayesian measures of model complexity and fit (with discussion). *Journal of the Royal Statistical Society, Series B* 64, 1–34.
- Tawn, J., Shooter, R., Towe, R., Lamb, R., 2018. Modelling spatial extreme events with environmental applications. *Spatial Statistics* 28, 39 – 58.
- Wadsworth, J., Tawn, J., 2012. Dependence modelling for spatial extremes. *Biometrika* 99, 253–272.
- Wadsworth, J.L., Tawn, J.A., 2018. Spatial conditional extremes. In submission .
- Wadsworth, J.L., Tawn, J.A., Davison, A.C., Elton, D.M., 2017. Modelling across extremal dependence classes. *J. Roy. Statist. Soc. C* 79, 149–175.

FIGURES




Figure 1. NNS and CNS locations considered.




Figure 2. Illustration of notation used to describe the disposition of points on the line, enabling pooling of data from pairs of locations by distance. The (c, j) notation is shown below the line, and distance h_{c0j} given above each point. Points with the same value of h_{c0j} are shown in the same colour; Δ is the inter-location spacing.




Figure 3. NNS:N-S transect, free model: parameter estimates for (a) α , (b) β , (c) μ and (d) σ with distance h_i , summarised using posterior means (disk) and 95% pseudo-likelihood credible intervals (with end-points shown as solid triangles).




Figure 4. Scatter plots illustrating dependence between values of Laplace-scale storm peak H_S at different relative distances for NNS:N-S transects, from (a) original sample and (b) simulation under the fitted free model. Black points are the original data on Laplace scale; red points are data simulated under the fitted model.




Figure 5. Observed spatial processes from the NNS:N-S transect with Laplace-scale values at the left-hand location in the interval $[3.5, 4.5]$, together with posterior predictive estimates from simulation under the fitted free model, represented using the median (black) and upper and lower limits of a 95% pseudo-likelihood credible interval. Red lines are simulated spatial processes from the fitted model.




Figure 6. NNS:N-S transect, parametric- α model: parameter estimates for (a) α , (b) β , (c) μ and (d) σ with distance h , summarised using posterior means (disk) and 95% pseudo-likelihood credible intervals (with end-points shown as solid triangles).




Figure 7. NNS:E-W transect, parametric $\alpha(h)$ model: estimates for (a) $\alpha(h)$, (b) $\beta(h)$, (c) $\mu(h)$ and (d) $\sigma(h)$ with distance h , summarised using posterior means (disk) and 95% pseudo-likelihood credible intervals (with end-points shown as solid triangles).




Figure 8. CNS:N-S transect, parametric- α model: parameter estimates for (a) α , (b) β , (c) μ and (d) σ with distance h , summarised using posterior means (disk) and 95% pseudo-likelihood credible intervals (with end-points shown as solid triangles).




Figure 9. CNS:E-W transect, parametric- α model: parameter estimates for (a) α , (b) β , (c) μ and (d) σ with distance h , summarised using posterior means (disk) and 95% pseudo-likelihood credible intervals (with end-points shown as solid triangles).




Figure 10. Pseudo-likelihood credible intervals for (a) the conditional mean and (b) the conditional standard deviation of the fitted dependence model as a function of distance in kilometres, for conditioning Laplace-scale value of 5, and different transects: NNS:N-W (red), NNS:E-W (magenta), CNS:N-S (blue), CNS:E-W (cyan).

TABLES

Model	DIC	
	Free	Parametric- α
NNS:N-S	27514.22	27501.68
NNS:E-W	7360.93	7356.75
CNS:N-S	23471.67	23476.13
CNS:E-W	23809.94	23827.10

Table 1. Table of DIC values for the free fit model and parametric- α model for all of the transect analyses.