

TIME RISK ASSESSMENT FRAMEWORK FOR HIGHWAY PROJECTS IN
NIGERIA

RASHEED ADEWALE SALAWU

A thesis submitted in fulfilment of the
requirements for the award of the degree of
Doctor of Philosophy (Quantity Surveying)

Faculty of Built Environment
Universiti Teknologi Malaysia

MARCH 2016

DEDICATION

To The Almighty ALLAH who has made it possible for me to attain this academic level in my chosen profession

To my parents, who Almighty ALLAH have used to provide the necessary support and motivation towards the attainment of this academic level

To my wife Risikat Ayobami and son, Abdullahi Adeolu who have been great sources of inspiration and shown their understanding throughout the duration of the study

ACKNOWLEDGEMENT

All praises and glory be to Almighty ALLAH, the glorious and the merciful for keeping me among the living and giving me inspirations to start and successfully completed this research.

My profound gratitude goes to my supervisor, Assoc. Prof. Dr. Fadhlin Abdullah who has always been there to attend to my inquiries and led me towards the exploration of the frontiers of knowledge in my research area. Through her guidance, suggestions and motivations, she made me have good understanding of the PhD research process. My appreciation also goes to the academia in the Department of Quantity Surveying for their contributions and suggestions during progress report presentations.

I also appreciate the Management of Yaba College of Technology for the approval of my study leave, the understanding of my colleagues in the quantity surveying department and the financial support given to me by TETFUND (Nigeria) to undertake this research.

The association, motivation and love of my Nigerian friends in UTM: Femi Akinyode, Ajayi Arowosegbe and Hafeez Sanni are also appreciated

Finally, I thank the authority of Universiti Teknologi Malaysia (UTM) for providing me with conducive environment and enabling facilities to complete this research.

ABSTRACT

Time overrun on construction projects continue to linger and is substantial in both developed and developing countries. Numerous risk management standards and risk assessment models have been developed to identify and minimise risks in improving time performance of construction projects. However, such attempts do not seem parallel with the improvements required. Hence, this study aims to develop a two dimensional risk assessment framework for highway rehabilitation projects by integrating probability and severity measures of significant risk factors with organisational risk management capability measures to derive risk magnitude index for highway rehabilitation projects. To accomplish this aim, quantitative survey research design was employed. Two sets of questionnaires were developed and administered to construction professionals and organisations that are directly involved in the execution of the sampled design, bid and build highway rehabilitation projects in Nigeria. List and classification of risk factors were validated by Delphi survey and data collected from the questionnaire survey were analysed by the application of Fuzzy set theory, analysis of variance and spearman rank correlation. Results of the data analysis reveal that the overall risk indices on rehabilitation projects executed by different construction organisations are significantly different but have strong inverse relationship with the risk management maturity indices of the construction organisations. Based on this relationship, a decision matrix was developed as a tool to combine overall risk indices with risk management maturity indices to derive risk magnitude indices for all risk factors and project level risk. The inputs, concepts, techniques and tools leading to this result formed the basis for the development of the proposed risk assessment framework. The framework was validated through structured interview with a team of experts. The validation team strongly agreed with the logical soundness and completeness of the proposed two dimensional risk assessment framework, affirming the framework to be practicable and acceptable for assessing time risks on highway rehabilitation projects in Nigeria. The framework can thus be adopted to ensure a complete and comprehensive assessment of risk on highway rehabilitation projects.

ABSTRAK

Masalah penyiapan projek-projek pembinaan diluar masa yang telah ditetapkan masih berterusan dan wujud di kedua-dua negara maju serta negara membangun. Pelbagai standard pengurusan risiko dan model penilaian risiko telah dibangunkan untuk mengenal pasti dan mengurangkan risiko bagi meningkatkan prestasi masa projek-projek pembinaan. Namun begitu, usaha-usaha tersebut seolah-olah tidak selari dengan penambahbaikan yang diperlukan. Oleh itu, kajian ini bertujuan untuk membangunkan satu kerangka kerja penilaian risiko dua dimensi dengan mengintegrasikan ukuran kebarangkalian dan ketenatan faktor risiko yang signifikan dengan ukuran keupayaan pengurusan risiko organisasi untuk mendapatkan indeks magnitud risiko bagi projek pemulihan lebuah raya. Reka bentuk penyelidikan kajian kuantitatif telah digunakan dalam kajian ini. Dua set soal selidik telah dibangunkan dan ditadbir untuk para profesional pembinaan dan organisasi yang terlibat secara langsung dalam pelaksanaan projek pemulihan lebuah raya persekutuan di Nigeria yang dibangunkan secara reka, bida dan bina yang telah digunakan sebagai sampel dalam kajian ini. Senarai dan klasifikasi faktor-faktor risiko telah disahkan dengan kajian Delphi manakala data yang dikumpul daripada borang soal selidik kajian dianalisis menggunakan teori set Fuzzy, analisis varians dan korelasi peringkat Spearman. Hasil analisis data menunjukkan bahawa indeks risiko keseluruhan projek pemulihan lebuah raya yang dilaksanakan oleh organisasi pembinaan yang berbeza adalah secara signifikan berbeza tetapi mempunyai hubungan songsang yang kukuh dengan indeks kematangan pengurusan risiko organisasi pembinaan. Berdasarkan hubungan tersebut matriks keputusan telah dibangunkan sebagai alat untuk menggabungkan indeks risiko keseluruhan dengan indeks kematangan pengurusan risiko untuk mendapatkan indeks magnitud risiko untuk semua faktor risiko dan risiko peringkat projek. Input, konsep, teknik dan peralatan daripada keputusan ini membentuk asas bagi pembangunan kerangka kerja penilaian risiko yang dicadangkan. Kerangka kerja ini telah disahkan melalui temu bual berstruktur dengan kumpulan pakar. Pasukan pengesahan sangat bersetuju dengan kemantapan logik dan kesempurnaan kerangka kerja penilaian risiko dua dimensi yang dicadangkan dan mengesahkan kerangka kerja tersebut adalah praktikal dan boleh diterima untuk menilai risiko masa bagi projek-projek pemulihan lebuah raya di Nigeria. Kerangka kerja tersebut boleh diterima pakai bagi memastikan penilaian risiko yang lengkap dan komprehensif untuk projek-projek pemulihan lebuah raya.

TABLE OF CONTENTS

CHAPTER	TITLE	PAGE
	DECLARATION	ii
	DEDICATION	iii
	ACKNOWLEDGMENT	iv
	ABSTRACT	v
	ABSTRAK	vi
	TABLE OF CONTENTS	vii
	LIST OF TABLES	xvii
	LIST OF FIGURES	xx
	LIST OF ABBREVIATIONS	xxii
	LIST OF APPENDICES	xxiii
1	INTRODUCTION	1
	1.1 Background to the Research	1
	1.2 Problem Statement	4
	1.3 Research Questions	10
	1.4 Aim and Objectives of the Research	11
	1.5 Scope of the Research	12
	1.6 Justification and Significance of this Research	13
	1.7 Research methodology	15
	1.8 Organisation of Chapters	18

2	LITERATURE REVIEW : DEVELOPMENT OF HIGHWAY PROJECTS	21
2.1	Introduction	21
2.2	Definition of Transport Infrastructure	22
2.3	Transport Infrastructure Investments and Economic Development	23
2.4	Conditions of Highways in Developed and Developing Countries	26
2.5	Issues on the Development of Highway Projects in Developed and Developing Countries	31
2.5.1	Time Overrun on Highway Projects in Developed and Developing Countries	31
2.5.2	Sources of Time Overrun on Highway Projects in Developed and Developing Countries	34
2.6	Perceptions and Nature of Risks	40
2.7	Nature of Highway Rehabilitation Projects	43
2.8	Development of Highway Rehabilitation Projects in Nigeria	45
2.8.1	Geographical and Socio- Economic Characteristics of Nigeria	46
2.8.2	National Development Plans and Highway Development in Nigeria	48
2.8.3	Road Classifications and Extent of Distress on Federal Highways in Nigeria	52
2.8.4	Investments on Federal Highway Projects in Nigeria	54
2.8.5	Procurement Regulations and Rules for Highway Projects	55
2.8.6	Project Management Model for Highway Rehabilitation Projects	58
2.9	Uncertain Events and Conditions on Highway rehabilitation Projects in Nigeria	61
2.9.1	Client Related Sources of Uncertainties on Highway Rehabilitation Projects in Nigeria	61
2.9.2	Contractors Related Sources of Uncertainties on Highway Projects	65
2.9.3	Consultant Related Uncertainties on Highway Rehabilitation Projects in Nigeria	66

	2.9.4	Uncontrollable Sources of Uncertainties on Highway Rehabilitation Projects in Nigeria	67
	2.10	Risk Factors on Highway Rehabilitation Projects in Nigeria	71
	2.11	Summary of this Chapter	72
3		LITERATURE REVIEW : RISK MANAGEMENT AND MATURITY MODELS FOR HIGHWAY PROJECTS	74
	3.1	Introduction	74
	3.2	Theories for Managing Risks and Uncertainties on Highway Projects	75
	3.2.1	Multi-Attributes Decision Making Technique	75
	3.2.2	Basic Structure, Principles and Operations of Fuzzy System for Highway Project Risk Assessment	77
	3.2.2.1	Basic Structure of Fuzzy System	78
	3.2.2.2	Operations in Fuzzy Systems	79
	3.2.2.3	Fuzzification, Fuzzy Sets and Membership Functions	82
	3.2.2.4	Fuzzy Propositions, Relations and Rule Base	84
	3.2.2.5	Fuzzy Implication, Aggregation and Defuzzification	88
	3.3	Risk Management of Highway Construction Projects	89
	3.3.1	Formal Risk Management Approaches and Process	90
	3.3.2	Risk Management Context	93
	3.3.3	Risk Identification and Classification	94
	3.3.4	Risk Analysis and Evaluations on Highway Projects	97
	3.3.4.1	Essential Requirements of Effective Risk Assessment Technique	98
	3.3.4.2	Risk Analysis Process	99
	3.3.4.3	Risk Assessment Procedures and Models	100

	3.3.4.4	One Dimensional Risk Assessment Models	101
	3.3.4.5	Two Dimensional Risk Assessment Models.	106
3.4		Risk Management Capability of Construction Organisations	109
	3.4.1	Risk Management Maturity Models for Highway Projects	110
	3.4.1.1	Organisation Risk Management Culture and Awareness	112
	3.4.1.2	Organisation Risk Management Practice and Applications	113
	3.4.1.3	Organisation Risk Management Resources	114
	3.4.1.4	Organisation Risk Management Process	114
	3.4.1.5	Maturity Levels of the Attributes of the Risk Management Capability	115
	3.4.2	Overall Risk Management Maturity of Organisations	116
	3.4.3	Essential Requirements of Holistic Risk Management Practice	120
	3.4.4	Risk Management Practices on Construction Projects	121
3.5		Summary of this Chapter	123
4		RESEARCH METHODOLOGY	125
	4.1	Introduction	125
	4.1.1	Research Designs and Perspectives	125
	4.1.2	Quantitative Research Perspective	126
	4.1.3	Qualitative Research Perspective	128
	4.1.4	Mixed Mode Research Perspective	129
	4.2	Research Procedure for this Study	131
	4.3	Research Design and Justification	132
	4.4	Research Design.	134
	4.4.1	1.1.1 Research Population, Sampling Frame and Sample.	135

4.4.2	Development of Hierarchical Structures for Risk Factors and Risk Management Capability	136
4.4.3	Research Instrument	139
4.4.3.1	Design and Contents of the Questionnaire	139
4.4.3.2	Validation of the Questionnaire	143
4.4.3.3	Questionnaire Administration	144
4.4.4	Methods of Data Analysis	146
4.4.4.1	Validity and Reliability Tests	147
4.4.4.2	Objective one: Determination of Time Performance and the Significant Risk Factors in Highway Rehabilitation Projects	147
4.4.4.2A	Time Performance in Federal Highway Rehabilitation Projects in Nigeria	148
4.4.4.2B	Determination of the Significant Risk Factors Leading to the Observed Time overrun in Federal Highway Rehabilitation Projects	148
4.4.6.3	Objective two: Assessment of Probability-Severity Indices of the Significant Risk Factors on Highway Rehabilitation Projects	149
4.4.4.3A	Assessing the Probability-Severity Indices of Significant Risk Factors for all Highway Rehabilitation Projects	150
4.4.4.3B	Assessment of the Differences in the Probability-Severity Indices of Different Contractors	162
4.4.4.4	Objective three: Assessing Risk Management Capability of Construction Organisations Undertaken Highway Rehabilitation Projects.	162
4.4.4.5	Objective Four: Determination of Risk Magnitude Indices on Highway Rehabilitation Projects	168

	4.4.4.5A	Determine the Relationship between the Probability-Severity Indices of Significant Risk Factors and Risk Management Maturity Indices of Contractors	168
	4.4.4.5B	Combination of the Probability-Severity Indices of Significant Risk Factors with Risk Management Maturity Indices of Highway Contractors	169
	4.4.4.6	Objective five: Formulation of a Two Dimensional Risk Assessment Framework for Highway Rehabilitation Projects	170
	4.5	Chapter Summary	171
5		DATA PRESENTATION, ANALYSIS, DISCUSSIONS AND FINDINGS	173
	5.1	Introduction	173
	5.2	Background Analysis of the Respondents	173
	5.2.1	Academic and Professional Qualifications of Respondents	174
	5.2.2	Working Experiences of the Respondents on Highway Projects	176
	5.2.3	Profile of Contractors that Executed the Highway Rehabilitation Projects	177
	5.2.4	Reliability and Validity Tests of the Respondents Ratings	178
	5.3	Analysis, Findings, Interpretation and Discussions	179
	5.3.1	Determination of Time Performance of and the Significant Risk Factors on Highway Rehabilitation Projects	179
	5.3.1.1	Determination of Time Overrun in Federal Highway Rehabilitation Projects in Nigeria	180
	5.3.1.2	Determination of the Significant Risk Factors leading to Time Overrun in Federal Highway Rehabilitation Projects	182
	5.3.1.3	Summary of Findings and Discussions of Time	

	Performances on Highway Rehabilitation Projects	185
5.3.1.4	Summary of Findings and Discussions of the Significant Risk Factors on Highway Rehabilitation Projects	186
5.3.2	Assessment of the Probability- Severity Indices of Significant Risk Factors	188
5.3.2.1	Probability-Severity Indices of the Significant Risk Factors for all Highway Rehabilitation Projects	190
5.3.2.2	Probability-Severity Indices of all the Significant Risk Factors based on Different Construction Organisations	192
5.3.2.2A	Probability-Severity indices on Highway Rehabilitation Projects Executed by “BG Contractor”	192
5.3.2.2B	Probability-Severity indices on Highway Rehabilitation Projects Executed by “BP” Contractor	194
5.3.2.2C	Probability-Severity indices on Highway Rehabilitation Projects Executed by “HZ” Contractor	196
5.3.2.2D	Probability-Severity indices on Highway Rehabilitation Projects Executed by “KK” Contractor	199
5.3.2.2E	Probability-Severity Indices on Highway Rehabilitation Projects Executed by “RC” Contractor	201
5.3.2.3	Assessment of the Differences in the Probability-Severity Indices of Significant Risk Factors among Different Contractors	203
5.3.2.4	Probability-Severity Indices of the Significant Risk Factors on Highway Rehabilitation Projects Executed in different States of Nigeria	205
5.3.2.4A	Probability-Severity Indices on Highway Rehabilitation Projects Executed in Oyo State.	205

5.3.2.4B	Probability-Severity Indices of Significant Risk Factors on Highway Rehabilitation Projects Executed in Lagos State.	206
5.3.2.4C	Probability-Severity Indices of Significant Risk Factors on Highway Rehabilitation Projects Executed in Ogun State	208
5.3.2.4D	Probability-Severity Indices of Significant Risk Factors on Highway Rehabilitation Projects Executed in Ondo State	209
5.3.2.4E	Probability-Severity Indices of Significant Risk Factors on Highway Rehabilitation Projects Executed in Osun State	211
5.3.2.5	Assessment of the Differences in the Probability-Severity Indices of Significant Risk Factors in different States of Nigeria	212
5.3.2.6	Summary of Findings and Discussions of the Probability-Severity Indices of Significant Risk Factors	213
5.3.2.6A	Probability-Severity Indices of the Significant risk Factors in all Highway Rehabilitation projects	214
5.3.2.6B	Probability-Severity Indices of Significant Risk Factors on Highway Rehabilitation Projects Executed by different Contractors	217
5.3.2.6C	Assessment of the differences in Probability-Severity Indices of the Significant Risk Factors among Different Contractors	221
5.3.2.6D	Assessment of the Differences in Probability-Severity Indices of the Significant Risk Factors in different States of Nigeria	222
5.3.3	Risk Management Capability of Construction Organisations Undertaken the Highway Rehabilitation Projects	222

	5.3.3.1	Risk Management Capability of different Construction Organisations	223
	5.3.3.1A	Risk Management Capability of “BG” Contractor	223
	5.3.3.1B	Risk Management Capability of “BP” Contractor	224
	5.3.3.1C	Risk Management Capability of “HZ” Contractor	225
	5.3.3.1D	Risk Management Maturity of “KK” Contractor	226
	5.3.3.1E	Risk Management Maturity of “RC” Contractor	227
	5.3.3.2	Overall Risk Management Maturity of all the Construction Organisations	229
	5.3.3.3	Summary of Findings and Discussions of the Risk Management Capability of Construction Organisations	230
	5.3.4	Assessing Risk Magnitude Indices on Highway Rehabilitation Projects	234
	5.3.4.1	Correlation of the probability-Severity Indices and RMMI of the Highway Rehabilitation Contractors	234
	5.3.4.2	Combination of the Probability-Severity Indices with Risk Management Maturity Indices of Highway Contractors	235
	5.3.4.3	Determination of the Risk Magnitude Indices for the Highway Contractors	238
	5.3.4.4	Summary of Findings and Discussions of the Assessment of Risk Magnitude Indices on Highway Rehabilitation Projects	239
	5.4	Chapter Summary	240
6		FRAMEWORK DEVELOPMENT AND VALIDATION	243
	6.1	Introduction	243
	6.2	Definition of Framework	243

6.3	Development Process of the Proposed Risk Assessment Framework	244
6.3.1	Framework Conceptualization	245
6.3.2	The Proposed Risk Assessment Framework	247
6.3.2.1	The Risk Management Context phase	248
6.3.2.2	Risk Identification and Structuring Phase	249
6.3.2.3	Project Risk Analysis Phase	251
6.3.2.4	Project Risk Evaluation Phase	251
6.3.2.5	Organisational Risk Management Capability Evaluation Phase	253
6.3.2.6	Project Risk Magnitude Assessment Phase	254
6.4	Validation of the Proposed Framework	256
6.4.1	Structured Interview	257
6.4.2	Background Information of the Experts for the Framework Validation	258
6.4.3	Data Analysis of Experts Ratings	260
6.5	Summary of this chapter	262
7	CONCLUSIONS AND RECOMMENDATIONS	264
7.1	Introduction	264
7.2	Achievement of Research Objectives	264
7.2.1	Objective 1: Determine Time Performance of, and the Significant Risk Factors on DBB Highway Rehabilitation Projects in Nigeria.	265
7.2.2	Objective 2: Assessing Probability-Severity Indices of the Significant Risk Factors on Highway Rehabilitation Projects in Nigeria	266
7.2.3	Objective 3: Assessing Risk Management Capability of Construction Organisations Undertaking Highway Rehabilitation Projects in Nigeria.	268
7.2.4	Objective 4: Determine the Risk Magnitude Indices on Highway Rehabilitation Projects in Nigeria	269

7.2.5	Objective 5: Formulating and Validating a Two Dimensional Risk Assessment Framework for Highway Rehabilitation Projects.	270
7.3	Recommendations	272
7.4	Research Limitations	273
7.5	Suggestions for Further Research	274
	REFERENCES	275
	Appendices A – D	303

LIST OF TABLES

TABLE NO.	TITLE	PAGE
1.1	The Corresponding Research Questions in the Objectives of this Research	12
1.2	Definitions of Terms as Related to this Research	17
2..1	Condition of Highway Infrastructure in Major African Countries between 2010 and 2014	26
2.2	Condition of Highway Infrastructure in Major Asian Countries between 2010 and 2014	27
2.3	Condition of Highway Infrastructure in Major European/America Countries between 2010 and 2014	27
2.4	Percentage time overrun on highway Construction projects in developed and developing countries	33
2.5	Controllable Potential Risk Factors on Highway Construction Projects	37
2.6	Uncontrollable Potential Risk Factors on Highway Construction Projects	39
2.7	Rehabilitation Treatments for Different Highway Pavements	44
2.8	Highway Rehabilitation Techniques and Treatments	44
2.9	Total road length, Paved and Unpaved Surface in Nigeria between 1904 & 2010	51
2.10	Allocation Trends on Federal Highway Projects from 1962 to 2013	54
2.11	Criteria and ratings for the pre-qualification of contractors for highway projects in Nigeria	57
2.12	Budget Allocation and Utilisation on Highway Construction and Rehabilitation Projects in Nigeria between 2009 and 2013	64
3.1	Fuzzy set operators	80
3.2	Fuzzy relations	86
3.3	Limitations of one dimensional risk assessment models	104

3.4	Attributes of risk management capability adopted by different authors	111
3.5	Risk Management Maturity levels adopted by different Authors	115
3.6	Characteristics of optimised risk management maturity level	117
3.7	Characteristics of managed risk management maturity level	118
3.8	Characteristics of novice risk management maturity level	119
3.9	Characteristics of naive risk management maturity level	119
4.1	Questionnaire distribution in this research	145
4.2	Linguistic Values and Triangular Fuzzy Sets for Probability of risk	152
4.3	Linguistic Values and Triangular Fuzzy Sets for Severity of Risk.	152
4.4	Linguistic values, Descriptions and Trapezoidal Fuzzy Sets of Probability-Severity indices	153
4.5	Fuzzy rule base table	155
4.6	Centre of fuzzy sets and decision criteria for defuzzified crisp values of probability-severity indices (PSI).	162
4.7	Maturity levels and rating scale of the attributes and dimensions of risk management capability.	166
4.8	Table 4.8 Range of risk magnitude indices and colour codes for different linguistic values of risk magnitude.	170
5.1	Profile of the contractors that executed the highway rehabilitation projects	177
5.2	Cronbach's alpha coefficient of risk factors on highway rehabilitation projects	178
5.3	Percentage time overrun on Federal highway rehabilitation projects in five States, Nigeria	181
5.4	Normalised values of the impact of risk factors on highway rehabilitation projects.	183
5.5	Significant risk factors on highway rehabilitation projects in Nigeria	187
5.6	Codes and groups of the significant risk factors	189
5.7	Probability-Severity indices of the significant risk factors, risk groups and overall project level risk for all Rehabilitation projects	191

5.8	Probability-Severity indices on highway rehabilitation projects executed by “BG” Contractors	194
5.9	Probability-Severity indices on highway rehabilitation projects executed by “BP” Contractor.	196
5.10	Probability-Severity indices on highway rehabilitation projects executed by “HZ” Contractor	198
5.11	Probability-Severity indices on highway rehabilitation projects executed by “KK” Contractor.	200
5.12	Probability-Severity indices of significant risk factors on highway rehabilitation projects executed by “RC” Contractor.	202
5.13	Probability-severity indices of significant factors for different risk groups and Contractors	203
5.14	ANOVA of the differences in the probability-severity indices of significant risk factors among different Contractors.	204
5.15	Probability-Severity indices of the significant risk factors on highway rehabilitation projects executed in Oyo State.	206
5.16	Probability-Severity indices of significant risk factors on highway rehabilitation projects executed in Lagos State, Nigeria.	207
5.17	Probability-Severity indices of significant risk factors on highway rehabilitation projects executed in Ogun State.	209
5.18	Probability-Severity indices of significant risk factors on highway rehabilitation projects executed in Ondo State.	210
5.19	Probability-Severity indices of significant risk factors on highway rehabilitation projects executed in Osun State, Nigeria	212
5.20	ANOVA of the probability-severity indices of significant risk factors in different States in South-West of Nigeria.	213
5.21	Attributes indices and risk management maturity index of “BG” construction organization.	224
5.22	Attributes Indices and Risk Management Maturity Index of “BP” Construction Organisation.	225
5.23	Attributes Indices and Risk Management Maturity Index of “HZ” Construction Organisation.	226
5.24	Attributes Indices and Risk Management Maturity Index of “KK” Construction Organisation.	227
5.25	Attributes Indices and Risk Management Maturity Index of “RC” Contractor.	228

5.26	Overall risk management maturity index of all the contractors undertaking highway rehabilitation projects in the South-West of Nigeria.	229
5.27	Summary of the maturity levels of contractors in different attributes of risk management capability.	230
5.28	Risk management maturity levels of contractors in different attributes of risk management capability.	233
5.29	Correlation of the PSI and the RMMI of the highway rehabilitation contractors.	235
5.30	Decision matrix of risk management maturity indices, probability-severity indices and risk magnitude indices.	236
5.31	Colour codes, range of risk magnitude indices and Interpretations.	237
5.32	Risk Magnitude indices for different construction organisations.	239
6.1	Background information of the Validation team members	259
6.2	Overall framework assessment	261
7.1	Significant Risk Factors on Highway Rehabilitation Projects in Nigeria	266

LIST OF FIGURES

FIGURE NO.	TITLE	PAGE
1.1	Scope and limitations of the existing one and two dimensional risk assessment models	10
1.2	Research methodology	16
2.1	Flowchart of the various groups of infrastructure	23
2.2	Average total, paved and unpaved road density in major African, Asian and Europe/American countries	28
2.3	Map of Nigeria	48
2.4	Pillars of the vision 20:2020	50
2.5	Apapa –Oshodi road before rehabilitation	53
2.6	Construction Project Management Model	59
2.7	Project management model for DBB highway projects in Nigeria.	60
2.8	Contractor related uncertainties on highway rehabilitation projects	66
2.9	Interest rate trends in Nigeria (1986 – 2015)	69
2.10	Nigeria Naira/US\$ exchange rate trends (1986 – 2015)	70
3.1	Basic structure of fuzzy system	79
3.2	Triangular membership function for probability	84
3.3	Phases of risk management process in Australia and New Zealand risk management standards.	91
3.4	Phases of risk management process in Project management body of knowledge (PMBOK), chapter 11.	91
3.5	Phases of risk management process in Project Risk Analysis and Management Guide (PRAM, guide).	92
3.6	Risk assessment phases for different risk management standards	97
4.1	Research Approaches and Elements interaction	130
4.2	Research Procedure adopted this research	132

4.3	Hierarchical risk breakdown structure as the basis for the survey and validation of the proposed framework development	138
4.4	Hierarchical structure of organisational risk management capability	139
4.5	Data analysis process	146
4.6	Development and validation process for the proposed two dimensional risk assessment framework	171
5.1	Academic and professional qualifications of all respondents	174
5.2	Academic and professional qualifications of respondents from construction organisations only	175
5.3	Respondent's working experiences on highway construction and rehabilitation projects	176
5.4	Probability-severity indices (Overall project risk level) for different contractors	204
5.5	Average annual funding requirement, budgetary allocations and Funding Gap for highway projects the year 2009-2012	215
5.6	Risk groups' probability-severity indices according to different construction companies	221
5.7	Risk management maturity levels of the construction organisations	232
6.1	Development process for the proposed framework	245
6.2	Proposed Risk Assessment Framework for highway Rehabilitation	255
6.3	Tools and techniques for different phases of the risk assessment	256
6.4	Overall assessment of the framework	261

LIST OF ABBREVIATIONS

ORI	-	Overall risk index
RGI	-	Risk group index
RFI	-	Risk factor index
RP	-	Risk probability
RS	-	Risk severity
PSI	-	Probability-severity index
SRF	-	Significant risk factor
FAM	-	Fuzzy associative memory
TMF	-	Trapezoidal membership function
TFN	-	Triangular fuzzy number
ATFN	-	Aggregated triangular fuzzy number
TOPSIS	-	Technique for order preference by similarity to ideal solution
COPRAS	-	Complex proportional assessment
AHP	-	Analytical hierarchical process
RM3	-	Risk management maturity models
RMMI	-	Risk management maturity index
RMC	-	Risk management capability
PMBOK	-	Project Management Body of Knowledge
RAMP	-	Risk analysis and management of projects
AZ/NZS	-	Australia/New Zealand
PRAM	-	Project risk analysis and management
RMP		Risk management plan
DBB		Design, bid and build
BMPIU		Budget Monitoring and Price Intelligent Unit
SSA		Sub-Saharan Africa
WBS		Work Breakdown Structure

LIST OF APPENDICES

APPENDIX	TITLE	PAGE
A	Questionnaire survey for the development of time risk assessment framework for highway rehabilitation projects in Nigeria	303
A-1A	Questionnaire for the assessment of probability-severity parameters of risks on DBB procured highway rehabilitation projects in Nigeria (August, 2013)	304
A-1B	Questionnaire for the assessment of organisations risk management capability on highway projects in Nigeria	312
A-2	Invitation to two round Delphi survey	325
B	Fuzzy inference analysis computations	333
C	Fuzzy synthetic evaluation computations	343
D	Guideline of the structured interview for the validation of the proposed risk assessment framework	346

CHAPTER 1

INTRODUCTION

1.1 Background to the Research

Effective and adequate basic infrastructure enhances speedy growth of nation's gross national income (Ibrahim, 2011). This is because effective basic infrastructures improves productivity, changes economic output, creates direct employment, changes population pattern and increase suburbanisation. Basic infrastructural facilities desirable for sustaining economic development of a nation include good transportation network, water supply, power (electricity and alternative energy), fuel and housing provision (Ogunsemi, 2005). On the other hand, poor state of the basic infrastructure has been identified as the major challenges to the economic growth and development in developed and developing countries (Shatz, et.al. 2011). This assertion is particularly relevant to Nigeria that has a total road ways of 196,200km serving over 175 million people of Nigeria and the entire territory covering 910,768 square kilometres of land.

The poor state of the infrastructural facilities has consequential adverse effect on the economic growth and development in Nigeria. Hence, a long term development plan termed ``The Nigeria Vision 20:2020``become operational in 2007. The economic plan has the goal of propelling the country into the league of the top 20 economies in the world by the year 2020, with a minimum GDP of 900 billion US dollar and a per capita income of no less than 4000 US Dollar per annum (Usman,

2010). Among the strategies for achieving this goal is the plan to rehabilitate, upgrade, modernise and expand 7,000km of the existing highways before 2013. Many highway rehabilitation projects were embarked upon to improve the pavement condition of the highway network in Nigeria.

Consequent upon the extent of distress, damage to the highway pavement, obsolete geometrics, needs for capacity improvement and re-alignment of the existing highways in Nigeria, highway rehabilitation projects were embarked upon to increase structural capacity, functionality and serviceability of the existing highway. Thus the highway rehabilitation projects in Nigeria involves the removal and replacement of subbase and base layers of a very large portion of the existing highway pavement as well as asphalt and concrete layers. It is often done in combination with subgrade and drainage remediations, and possible geometric changes. All the highway rehabilitation projects were contracted by Design, Bid and Build procurement (DBB) approach.

To achieve the full benefits of design, bid and build procurement (DBB) approach on highway rehabilitation and construction contracts in Nigeria, the procurement act 2007 was enacted. The act provided the necessary regulations and standards required to arrive at best procurement decision. It also establishes the bureau for public procurement that is presently known as Budget Monitoring and Price Intelligent Unit (BMPIU) to enforce the provisions of the act. The BMPIU also developed due process rules of contracting games to ensure effective delivery of design, bid and build highway rehabilitation and construction projects. Despite all the provisions in the procurement act 2007 and the due process rules of contracting games, new highway constructions and highway rehabilitation projects in Nigeria are experiencing challenges of time and cost overrun (Okonjo-Iwealla, 2010). However, the challenges of time and cost overrun on highway construction projects are global phenomena but their magnitude is more in developing countries (Fybjerg, *et al.*, 2003).

Studies on performance of highway projects in Bangladesh, India, Thailand and China revealed an average time overrun of 33.37% and the time overrun ranges between 13.63% and 55.69% (Ahsan and Gunawan, 2010). In the United Kingdom,

time overrun on highway projects ranges from 1.5% to 38.2% (Olawale and Sun, 2010). Assaf and Al-Hejji (2006) also observed that time overrun on highway projects in Saudi Arabia ranges from 0 to 30% and in Nigeria, Ameh, *et al* (2010) observed that delay on infrastructure projects is on the average of 188%. These studies reflect that the magnitude of time overrun vary from one country to another and are substantial both in the developed and developing countries. Hence, causes of the time overrun experienced on highway projects both in the developed and developing countries have also been examined.

Studies on international highway construction projects in Bangladesh, India, Thailand, China and Indiana revealed that financial process, scope changes, adverse weather condition, contract bid amount, project types and riot and commotions constitute the major causes of delay on the projects (Ahsan and Gunawan, 2010; Anastasopoulos *et al*, 2012). Causes of delay on highway construction projects in Malaysia include improper planning and poor site management, inadequate contractor's experience, problem with sub-contractor, inadequate client finance and delayed payment for completed work (Sambasivan and Soon, 2007; Alaghbari, *et al*, 2007). In Saudi Arabia and United Arab Emirate, studies on highway construction projects affirmed that major causes of time overrun include change order, low bid, inefficient planning, delay in approval, delay in expropriation, delays in payment, design change, lack of project funds, lack of specialized technical staff, poor performance of labor and subcontractor, contractor's lack of experience on the job, contractor's cash flow problems and delay in mobilisation, poor productivity, and unexpected ground utility (Assaf and Al-Hejji, 2006; Al- Kharashi and Skitmore, 2009; Sameh *et al*., 2015; El- Sayegh, 2008; Perera,*et al*, 2014).

In Egypt, partial and delay payment, financial difficulties arising from client and contractors, low productivity level, ineffective planning and schedule, change of work scope, adverse effect of lowest bid, and non-utilisation of professionals and unexpected ground conditions are the major causes of delay on civil engineering projects (Abd El- Razek, *et al*,2008; Mohamed, et al, 2012). In Nigeria very little studies are reported on causes of delay on highway projects but significant causes of

delay on construction projects in general are reported to include financial issues, poor contract management and contractors site management problems (Aibinu and Odeyinka, 2006) improper planning and ineffective communication (Kasimu and Usman, 2013).

The Project Management Institute (2004) described uncertain events or conditions as risk, if their occurrence has positive or negative effect on any of the project performance objectives such as cost, time and quality. Thus, all the causes of delay on highway projects that are extensively described are infact uncertainties that lead to delay, cost overrun and underrun and poor quality on highway projects and so they are risk factors. It is therefore very important to properly and effectively manage the potential risk factors on highway projects if improvement on the project performance is to be achieved. In facilitating effective management of potential risk factors on highway projects, numerous systematic and formal risk assessment models have been developed. Within the context of this research, these models are broadly classified into one dimensional and two dimensional risk assessment models.

1.2 Problem Statement

Highway rehabilitation projects constituted about 90% of all highway construction projects in Nigeria. The highway rehabilitation projects are complex, unique in nature and they were executed under uncertain project environment. Hence, highway rehabilitation projects in Nigeria are subjected to numerous and variety of uncertain events and conditions. Uncertain events and conditions on highway construction projects are greater than other types of construction projects (Sameh *et al.*, 2015). These uncertainties relate to risks leading to time and cost overrun (PMI, 2004). Occurrence of time and cost overrun often lead to additional cost of construction, loss of profits, arbitration, litigation and total abandonment (Kikwasi, 2012; Enshassi *et al.* 2009; Sambasivan and Soon, 2007), numerous contractual claims and increased project cost (Lo, *et al.* 2006), financial waste and poor quality work

(Ramanathan *et al.*, 2012). Iyer and Jha (2006) asserted that major part of cost overrun on construction projects could be contained if risk factors causing time overrun are consciously and properly managed. This means that if risk factors causing time overrun are properly managed; additional cost, loss of profits to construction organisations and total project abandonment would be drastically minimized on highway rehabilitation projects in Nigeria.

Research efforts towards effective management of time related risk factors on highway construction projects led to the development of numerous risk assessment techniques and models which are in the context of this research broadly classified into one dimensional risk assessment models and two dimensional risk assessment models. Despite the number of the existing risk assessment techniques and models, time overrun on highway construction projects could not be curtailed, it continue to linger and its extent is substantial in both developed and developing countries. Hence, the existing risk assessment models are unsuitable for effective management of risks on highway construction projects. This constitutes a cause for concern in this research.

To achieve an effective management of time related risks on highway rehabilitation and construction projects, the time related risk factors have to be effectively identified and assessed. In lieu of the complex and unique nature of highway rehabilitation and construction projects, seven essential requirements are identified for effective assessment of risks on highway projects. These essential requirements are to estimate the probability of occurrence of risks and severity of the risks, and then combine the estimates to derive consequences of the risks on highway projects' performance objectives (Thomas *et al.* 2006; Jannadi and Almishari, 2003), application of quantitative techniques that is capable of handling the vagueness and ambiguity in subjective risk data on highway projects (Hwang *et al.*, 2014; Guyonnet *et al.*, 2003; Dikmen and Birgonul, 2006), appropriate structuring of risks on the highway projects and adopting quantitative technique that is capable of estimating the magnitude of individual risk factors and overall project level risk (Taroun *et al.*, 2011), integration of organization dimension of risk management practice with probability-severity parameters to derive the risk magnitude (Zhang, 2007; Mafakheri *et al.*,

2012), complete and comprehensive assessment of organisational risk management capability, and adopting systematic technique to assess the organisations risk management maturity level.

The existing one dimensional and two dimensional risk assessment models are deficient in meeting up with all the essential requirements for effective assessment of risks on highway rehabilitation and construction projects. One dimensional risk assessment models assessed risks by considering the probability and severity parameters of risks on highway projects. They adopted different quantitative techniques that are within the context of this research grouped into classical, modified classical and multi-criteria risk assessment models. The classical risk assessment models were developed with quantitative techniques such as Monte Carlo methodology (Molenaar, 2005; Oztas and Okmen, 2004); multiple regression analysis (MRA) and relative important index (Creedy *et al.*, 2010; Mahamid and Bruland, 2012); Decision Tree Analysis (Dey, 2010). These models provide range of estimated time and cost of highway projects but could not provide the magnitude of risk factors on projects and are incapable of handling subjective risk data which are inevitable on highway projects. The models also did not structure the potential risk factors on highway projects and this could affect the accuracy of the estimated time and cost of projects. Hence modified classical models were developed to handle the inevitable subjective risk data on highway projects.

Modified classical risk assessment models were developed by applying Monte Carlo simulation under fuzzy logic principles. Guyonnet, *et al.*, (2003) developed Monte Carlo simulation model with possibility and probability transformation, and Baudrit *et al.*, (2005) developed hybrid Monte Carlo simulations model. These models also provide range of estimated time and cost of highway projects but could not provide the magnitude of risk factors on projects. The models also did not structure the potential risk factors on highway projects and this could affect the accuracy of the estimated time and cost of projects. Hence, multi-criteria one dimensional risk assessment models were developed with quantitative techniques that are based on the application of Analytic Hierarchy Process (Zhang, *et al.*, 2007; Zayed, *et al.* 2008;

Subramanian, *et al.*, 2012); Technique for Order Performance by Similarity to Idea Solution (TOPSIS), Fuzzy synthetic evaluation process (Xu *et al.*, 2010) and Fuzzy inference technique (Carr and Tah ,2001). The multi-criteria one dimensional risk assessment models provide ratings of alternative highway projects based on the developed structure of the potential risk factors on highway projects. However the models could not provide the magnitude of risk factors on projects and the ratings are provided without considering the effect of organisational risk management capability on the consequences of the potential risk factors on highway projects.

The three groups of one dimensional risk assessment models described above are unable to meet up with four of the essential requirements for effective assessment of risks on highway rehabilitation and construction projects. The common limitations of these models are their inability to estimate the magnitude of individual risk factors and overall project level risk, this will make it difficult to plan and respond to the potential risk factors on highway projects and also defeated the purpose of formal risk management practice. The models also failed to integrate organization dimension of risk management practice or any supporting factors with probability-severity parameters to derive the magnitude of risks on projects. Hence, none of the attributes of organisational risk management capability was considered and no systematic technique was adopted to assess risk management maturity level of organisations.

Research efforts toward overcoming the common limitations of one dimensional risk assessment models led to the development of two dimensional risk assessment models. The current two dimensional risk assessment models integrated probability-severity parameters with different supporting factors, applied fuzzy inference and fuzzy synthetic evaluation techniques. Jannadi and Almishari (2003) proposed risk assessment model that integrated personnel/ property 'exposure' to all hazards of a work activity with probability-severity parameters. Zeng *et al.*, (2007) introduce factor index in its fuzzy AHP risk assessment model and Ebrahimnejad *et al.*, (2010) integrated quickness of reaction, event measure quantity and event capability criterion in the proposed Fuzzy TOPSIS risk analysis procedure. In addition, Dikmen *et al* (2007) proposed a two dimensional risk assessment models that

integrated company experience and favourability of contract clauses with probability-severity parameters of risk factors. Organisational risk management capability parameter was introduced in Mafakheri, *et al.*, (2012) to develop a Fuzzy AHP based two –dimensional risk assessment approach.

The two dimensional risk assessment models make very little improvement on the risk assessment modelling approaches but also fall short of meeting up with all the essential requirements for effective assessment of risks on highway construction projects. The supporting factors introduced in these models are not comprehensive for accurate and effective assessment of organisational risk management capability and the techniques adopted for assessing the supporting factors are unstructured and unsystematic. Attributes of organisational risk management capability such as risk management process, culture/awareness, resources and risk management practice/application (Ren and Yeo, 2004; Zou, *et al.*, 2010; Mu, *et al.*, (2014) are neither estimated nor integrated with the probability-severity parameters of risks on highway construction projects in the existing two dimensional risk assessment models.

In addition to the limitations of the existing risk assessment techniques and models, “due process rules of contracting games” that governs the procurement of design, bid and build (DBB) highway contracts in Nigeria do not provide formal risk management guidelines and procedures for highway rehabilitation and construction projects. This implies that initial contract period for federal highway rehabilitation and new highway construction projects in Nigeria are estimated by the application of informal risk management approach. Hence, the poor time performance experienced on highway rehabilitation and construction projects in Nigeria (Okonjo-Iwealla, 2013) could be associated with the absence of formal risk management guidelines and procedures in the Nigeria “due process rules of contracting games”.

Based on the essential requirements for effective assessment of risks on highway construction projects and the limitations of the one and two dimensional risk assessment models, the existing risk assessment models are incomplete and not suitable for effective assessment of risks on highway construction projects. Hence, the

existing risk assessment models could not curtail the occurrence of time overrun on highway construction projects. Further research effort is very essential to improve upon the existing risk assessment modelling approaches. Consequently, this research focus on developing a two dimensional risk assessment framework for design, bid and build highway rehabilitation projects in Nigeria. The proposed framework integrates all the essential requirements for effective assessment of risks on highway projects in order to overcome the limitations of the existing risk assessment models.

The proposed framework integrated three input parameters namely probability, severity and risk management capability to derive risk magnitude indices of the significant risk factors. Probability was considered as the frequency of occurrence of risk factors on highway rehabilitation projects and severity is the impact of the risk factors on the projects' time performance. Probability and severity estimates of the significant risk factors are combined to obtain the probability-severity indices. However, to overcome the limitations of the existing risk assessment models, risk management capability of the contractors were examined in terms of their risk management culture, risk management process, available resources and risk management practice. The impact of the contractors' risk management capability on the probability-severity indices of risk factors were examined in terms of risk magnitude indices. The risk magnitude indices were derived by combining the probability-severity indices with the risk management capability indices. It is hoped that the proposed framework will serve as good basis for developing formal risk management guidelines and procedures to be included in the Nigeria "due process rules of contracting games". The essential requirements for effective assessment of risk factors leading to time overrun on highway construction projects, the scope and limitation of the existing one and two dimensional risk assessment models for highway construction projects are summarised and shown Figure 1.1.




Figure 1.1 Scope and Limitations of the existing one and two dimensional risk assessment models.

1.3 Research Questions

This research attempts to answer the following questions:

1. What is the extent of time overrun on design, bid and build (DBB) Federal highway rehabilitation projects in Nigeria?
2. Which of the potential risk factors on highway projects are significantly preventing the achievement of time performance on the Federal highway rehabilitation projects in Nigeria?
3. What are the probability-severity indices of the significant risk factors, risk groups and project risk level on Federal highway rehabilitation projects in Nigeria?

4. Are there any significant difference in the probability-severity indices of significant risk factors on Federal highway rehabilitation projects executed by different construction organisations?
5. What is the impact of the different locations of the highway rehabilitation projects on probability severity indices of significant risk factors?
6. What is the risk management maturity level of the construction organisations executing the Federal highway rehabilitation projects in Nigeria?
7. What is the nature of relationship between probability-severity indices of the significant risk factors on highway rehabilitation projects executed by different construction organisations and their current risk management capability?
8. What is the magnitude of significant risk factors on highway rehabilitation projects?
9. What process should be adopted to develop an effective and acceptable risk assessment framework for highway rehabilitation projects?

1.4 Aim and Objectives of the Research

The aim of this research is to develop a two dimensional risk assessment framework for design, bid and build (DBB) procured highway rehabilitation projects in Nigeria. Accordingly, the objectives of the research are as follows:

- i. To determine time performance of and the significant risk factors on DBB procured highway rehabilitation projects in Nigeria;
- ii. To assess probability severity indices of the significant risk factors on highway rehabilitation projects in Nigeria;
- iii. To assess risk management capability of construction organisations undertaking highway rehabilitation projects in Nigeria;
- iv. To determine the risk magnitude indices on highway rehabilitation projects in Nigeria

- v. To formulate and validate a two dimensional time risk assessment framework for highway rehabilitation projects.

Answers to the research questions stated in section 1.3 are obtained in the corresponding research objectives as described in Table 1.1

Table 1.1 The corresponding research questions in the objectives of this research

Research Questions	Research Objectives
1 and 2	Objective 1:To determine time performance of and the significant risk factors on DBB procured highway rehabilitation projects in Nigeria
3, 4 and 5	Objective 2:To assess probability severity indices of the significant risk factors on highway rehabilitation projects in Nigeria
6	Objective 3:To assess risk management capability of construction organisations undertaking highway rehabilitation projects in Nigeria;
7 and 8	Objective 4:To determine the risk magnitude indices on highway rehabilitation projects in Nigeria
9	Objective 5:To formulate and validate a two dimensional risk assessment framework for highway rehabilitation projects

1.5 Scope of the Research

This research focused on Federal highway rehabilitation projects that are procured by design, bid and built (DBB). The focus on the Federal highway rehabilitation projects is limited to the projects located in Lagos, Ogun, Oyo, Ondo and Osun states in the South West zone of Nigeria. The focus on the DBB highway rehabilitation projects are also limited to the projects awarded and executed between 2001 and 2013. The research also focused on highway rehabilitation projects with completion stage ranging from 60% -100% as at December 2013. This is to ensure that sufficient risk data are obtained on every highway rehabilitation projects understudy in this research. However, highway rehabilitation projects that are 100% completed and their period of practical completion has expired as at 2013 were excluded from this research because risk data on them were not readily available. In addition, this

research is project specific and so it focuses on only the client, construction organisations and consulting firms that are undertaking the studied highway rehabilitation projects

1.6 Justification and Significance of this Research

Risks on highway projects are greater than other types of construction projects (Sameh *et al.*, 2015) and so effective management of the risks on them is critical to their successful performance. The existing risk assessment studies and models placed emphasis on highway construction, buildings and other civil engineering projects (Kaliba *et al.*,2009; Ahsan and Gunawan ,2010; Kikwasi (2012), Mahamid, *et al.* ,2012; Marzouk and El-Rasas ,2014;and Sameh *et al.*,2015). Very little of the studies and models are done to assess risks on highway rehabilitation projects. In Nigeria, majority of the risk assessment researches on construction projects were on building projects and on construction projects in general (Aibinu and Odeyinka, 2006; Kasimu and Usman, 2013). Most of them are not project specific and very little emphasis was placed on the assessment of risks on highway rehabilitation projects. However, most of the highway projects embarked upon in Nigeria between 2001 and 2014 are rehabilitation projects and these projects are facing issue of time overrun. Hence, this research focused on the effective assessment of risk factors to enhance time performance on highway rehabilitation projects. The outcome of the research established the extent of time overrun on highway rehabilitation projects and provided a checklist of probability and severity estimates of significant risk factors.

The attributes and techniques for assessing organisational risk management capability in the existing two dimensional risk assessment models are incomprehensive and unsystematic for effective assessment of risk management practice of organisations (Ren and Yeo, 2004; Zou, *et al.*, 2010; Mu, *et al.*, 2014). Hence, this research explored the risk management maturity models (RM3) and derived a systematic technique for a comprehensive estimation of the risk management

maturity of construction organisations. The systematic technique was applied on the contractors that are undertaking the studied highway rehabilitation projects and the outcome of the application established the risk management maturity levels of Federal highway rehabilitation contractors in Nigeria. The maturity levels described strength and weakness of highway contractors in risk management practice.

In addition, the existing risk assessment models estimates range of time and costs of projects and provided relative ratings of risk factors but they are not capable of estimating the magnitude of risk factors on projects (Taroun *et al.*, 2011). This means that the existing risk assessment models are inadequate for the project managers to make decision on risk response planning. Thus the purpose of formal risk management process is defeated. Hence, this research proposed a risk assessment framework that combined probability and severity measures of risks on highway rehabilitation projects with risk management maturity estimates of construction organisations to derive magnitude of risk factors and project risk level on highway rehabilitation projects. The risk assessment framework is comprehensive and systematic. In addition, quantitative technique adopted for assessing the probability-severity indices of risks on highway rehabilitation projects and the risk management maturity levels of the construction organisations in the framework was found suitable for handling subjective and objective risk data and for comprehensive assessment of organisational risk management capability.

Therefore, the outcomes of this research highlights the need to integrate risk management capability measures of construction organisations with the probability and severity measures of risks in highway rehabilitation projects. The research also highlighted the need to have good understanding of the risk management capability of construction of construction organisations prior to the award of rehabilitation contract. The outcome of this research also provided the indigenous construction organisations in Nigeria the database of probability and severity estimates of significant risk factors in Federal highway rehabilitation projects. This could serve as a checklist for the identification of potential risk factors in the future highway rehabilitation projects. Similarly, with the growing prospect of infrastructure development business in

Nigeria, the database of probability and severity measures of significant risk factors are useful information for SWOT analysis of Federal highway rehabilitation projects by foreign construction firms that are anticipating to explore highway construction business in Nigeria. The proposed framework would serve as a guide to the client and construction organisations towards effective assessment of risk factors on highway rehabilitation projects and boost the efficiency of the risk response plan.

1.7 Research methodology

This research commenced with the review of literatures to identify research problem, scope and limitations of the existing risk assessment models and approaches. The review was also used to determine the possible means of improving upon the risk assessment modelling and to determine the appropriate research approach and design for the identified aim and objectives of the research.

In lieu of the quantitative nature of the research objectives, survey research design was adopted. Consequently, two sets of questionnaire was developed, the first set was used to collect risk data for assessing probability and severity parameters of risk factors on highway rehabilitation projects and the second set was used to collect data for assessing the risk management capability of construction organisations. The developed questionnaire was validated in two round Delphi survey of experts and the validated questionnaire was administered to professionals who are directly involved in the execution of the sampled highway rehabilitation projects. The collected data were initially analysed by normalisation analysis process to identify the significant risk factors on highway rehabilitation projects. Collected data on significant risk factors were further analysed with Fuzzy inference technique to compute probability-severity indices of the significant risk factors, risk groups and project risk level on Federal highway rehabilitation projects. Similarly, collected data from the second set of the questionnaire were analysed with Fuzzy synthetic evaluation method to compute risk management maturity indices of the construction organisations.

Probability-severity indices of the significant risk factors and risk management maturity indices of the construction organisations were correlated by computing spearman rank correlation coefficient to establish the extent of relationship between them. Result of the computed correlation coefficient form the basis for the development of decision matrix. In addition, the developed decision matrix was used to combine probability-severity indices (PSI) and risk management maturity indices (RMMI) of construction organisations to derive risk magnitude indices. Therefore the concepts, process, tools and techniques adopted in this survey research and the developed decision matrix were used to develop an improved two dimensional risk assessment framework which was validated by structured interview. The flowchart of this methodology is shown in Figure1.2 and terms used in this research are defined in Table 1.2.




Figure 1.2 Research Methodology

Table 1.2 Definitions of Terms as Related to this Research

Terms	Definition
Risk	The uncertain events or conditions that their occurrence led to time overrun on highway rehabilitation projects
Risk management practice	This is the culture, practice, processes, resources put in place towards effective management of potential opportunities and threats to project
Risk management process	The systematic application of management policies, procedures and practice for the purpose of identifying, assessing, treating, monitoring, documenting and communicating project risk
Risk identification	The process of determining what are likely to occur at all stages of construction process, how and why
Risk analysis	The first part of risk assessment activities that systematically employ available information to determine the significant risk factors on highway rehabilitation projects.
Risk evaluation	The process of determining the tolerability of risk events and priorities of significant risk factors
Risk assessment	A phase in risk management process that involves risk analysis and evaluation
Risk probability	The frequency of occurrence of risk potential risk factors on highway rehabilitation projects. It is measured on the scale 1 to10
Risk severity	This is the degree of the consequences of potential risk factors on the time performance in highway rehabilitation projects
Probability-severity index	The measure of the product of probability and severity parameters of a significant risk factor
Risk group index	The measure of the product of probability and severity parameters on a group of significant risk factors
Risk management maturity index	The measure of the overall risk management capability of construction organisations
Attribute index	Measure of the individual attributes of the risk management capability in an organisation
Risk magnitude index	Measure of the combination of probability-severity index and risk management maturity indices of construction organisations.
Highway rehabilitation	Highway rehabilitation is the structural or functional enhancement of a pavement which produces a substantial extension in service life by substantially improving pavement condition and ride quality. It involves the removal and replacement of subbase and base layers of highway pavement as well as asphalt and concrete layers. It is often done in combination with subgrade, drainage remediations, and possible geometric improvement.

1.8 Organisation of Chapters

This thesis is made up of seven chapters. Chapter one is the Introduction to the research and consists of the background of the study, statement of the problem, research questions, aim and objectives, scope of the study, justification and significance of this research, brief research methodology, definition of terms, and outline of the thesis

Chapter two is the first part of the review of related literatures undertaken in this research. The chapter is organised in the following order: definition of transport infrastructure; transport infrastructure investments and economic development; conditions of highways in developed and developing countries; issues on the development of highway projects: time overrun on highway projects, sources of time overrun on highway projects in developed and developing countries; perception and nature of risks nature of risks; background information of Nigeria and highway rehabilitation projects' delivery: geographical and socio-economic characteristics of Nigeria, National development plans and highway development in Nigeria, road classifications and extent of distress on Federal highways in Nigeria, investment on Federal highway projects in Nigeria, procurement approach and regulations governing delivery of highway rehabilitation projects, project management models for highway rehabilitation projects in Nigeria.

The chapter also contain uncertain events and condition on highway rehabilitation projects in Nigeria: client related uncertainties on highway rehabilitation projects in Nigeria, contractor related uncertainties on highway rehabilitation projects in Nigeria, consultant related uncertainties on highway rehabilitation projects in Nigeria, uncontrollable uncertain events; risk factors on highway rehabilitation projects in Nigeria and then chapter summary.

Chapter three is the second part of the review of literature; the chapter contains the review of the techniques and theories for managing risks and uncertainties on

highway projects: multi-attributes decision making technique; basic structure of fuzzy systems, basic principles and operations of fuzzy logic for risks assessment. The chapter also covers the review of the existing risk management standards for highway construction projects and formal risk management process: risk planning, risk identifications, risk analysis and evaluations on highway projects, the essential requirements of effective risk assessment technique, risk analysis process and risk assessment models such as: one dimensional risk assessment models and two dimensional risk assessment models. The chapter is concluded with the review of the organisational risk management capability; risk management maturity models for projects; techniques for assessing overall risk management maturity of organisations; essential requirements of holistic risk management practice; risk management practices on construction projects and summary of this chapter.

Chapter Four briefly describes the various research designs and perspectives. It focuses on the adopted research procedure and design, describe the justification for the choice of the research design, study population, sampling frame and sample and the different phases of the research. The adopted hierarchical structures for risk factors and risk management capability were also presented. The chapter describes the design and contents of the developed questionnaire, method of validating and administration of the developed questionnaire. The chapter also describe methods of data analysis adopted in this research: fuzzy inference, fuzzy expert system algorithm and fuzzy synthetic evaluation methods. The chapter concludes with the description of the development and validation process of the proposed two dimensional risk assessment framework.

Chapter five presents the background information of the respondents engaged for this research namely: the academic and professional qualifications, the working experience, profile of the contractors and results of the reliability test. The chapter also included the results of data analysis techniques namely: fuzzy inference, fuzzy synthetic evaluation, analysis of variance, spearman rank correlation that were applied in this study were also presented. The results of the data analysis and findings were

organised and presented in the order of the research objectives of this study. The chapter ended with the summary of findings and discussions.

Chapter six contains the development and validation process adopted in this research to formulate a two dimensional risk assessment framework for highway rehabilitation projects. It provides the definition of framework and the three phase of the development process adopted for the proposed risk assessment framework: framework conceptualisation, drafting the proposed risk assessment framework and validation of the proposed framework. The chapter concludes with the summary of the chapter.

Chapter seven highlights the achievement of the research objectives, recommendations, and limitations of this research and suggestions for further research.

REFERENCES

- Abd El-Razek, M.E., Bassioni, H. A., Mobarak, A.M. (2008). Causes of Delay in Building Construction Projects in Egypt. *Journal of Construction Engineering and Management*. ASCE/ November, 833-841
- Abdullah, F. (2004). *Construction Industry and Economic Development: The Malaysian scene*. Skudai, Malaysia: Skudai Penerbit, Universiti Teknologi
- Abdul-Rahman, H., Yahya, I., Berawi, A., Wah, L.W. (2008). “Conceptual Delay Mitigation Model using a Project Learning Approach in Practice. *Construction Management and Economics*. 26, 15-27.
- Adams, F.K. (2006). Expert Elicitation and Bayesian Analysis of Construction Contract Risks: An Investigation. *Construction Management and Economics*. 24(1)81-96.
- Adams, F. K. (2008a). Construction Contract Risk Management: A Study of Practices in the United Kingdom. *Cost Engineering*. 50(1). 22–33.
- Adams, F.K. (2008b). “Risk Perception and Bayesian Analysis of International Construction Contract Risks: the Case of Payment Delays in a Developing Economy”. *International Journal of Project Management*. 26 (2), 138-148
- Adeniran, J.O., Yusuf, S.A., Adeyemi, O. A. (2014). The Impact of Exchange Rate Fluctuation on the Nigerian Economic Growth: An Empirical Investigation. *International Journal of Academic Research in Business and Social Sciences*. 4(8), 224-233
- Aganga, O. O. (2010). Fourth Quarter and Consolidated Budget Implementation Report, Budget Office of the Federation, Federal Ministry of Finance, Abuja
- Ahmed, A., Kayis, B., Amornsawadwatana, S. (2007). A Review of Techniques for Risk Management in Projects. *Benchmark: An International Journal*. 14 (1), 22-36

- Ahsan, K., Gunawan, T. (2010). Analysis of Cost and Schedule Performance of International Development Projects. *International Journal of Project Management*. 28 (2010), 68-78
- Aibinu, A.A., Odeyinka, H. A. (2006). Construction Delays and their Causative Factors in Nigeria. *Journal of Construction Engineering and Management*. ASCE / July, 831- 841
- Ahmed A., Kayis, B., Amornsawadwatana, S. (2007). "A Review of Techniques for Risk Management in Projects". *Benchmarking: An International Journal*. 14 (1), 22 – 36
- Ahmed, M. (2011). Financing Major Infrastructure in Nigeria to Achieve Intermodal Transportation Regime in Roads and Railways. Paper presented at the 1st National Building and Construction Economic Roundtable (BCERT) of the Quantity Surveyors Registration Board of Nigeria. 14 -15 June. Shehu Musa Yar'Adua Center, Abuja.
- Aje, O.I., Odusami, K.T., Ogunsemi, D.R. (2009). "The Impact of Contractors Management Capability on Cost and Time Performance of Construction Projects in Nigeria". *Journal of Financial Management of Property and Construction*. 14 (1), 171-187.
- Akintoye, A., Fitzgerald, E. (2000). A Survey of Current Cost Estimating Practices. *Construction Management and Economics*. 18(2), 161-172
- Akkirajul, R., Nayak, N., Torok, R., Kaenell, J. (2010). A Practitioner's Tool for Enterprise Risk Management Capability Assessment. Service Operations and Logistics and informatics (SOLI). *IEEE International Conference*. 369-375.
- Alaghbari, W., Kadir, M.R.A., Salim, A., Ernawati, O. (2007). "The Significant Factors causing Delay of Building Construction Projects in Malaysia". *Engineering, Construction and Architectural Management*. 14 (2), 192-206.
- Ali, A.S., Rahmat, I. (2010). The performance Measurement of Construction projects Managed by ISO Certified Contractors in Malaysia. *Journal of Retail & Leisure Property*. 9, 25-35.
- Al-Kharashi, A., Skitmore, M. (2009). Causes of Delays in Saudi Arabia Public Sector Construction Projects. *Construction Management and Economics*. 27 (1), 3-23.

- Al-Moumani, H.A. (2000). Construction Delay: a Quantitative Analysis. *International Journal of Project Management*. 18 (1), 51-59.
- Ameh, O. J., Soyigbe, A. A., Odusami, K. T. (2010). Significant Factors causing Cost Overruns in Telecommunication Projects in Nigeria. *Journal of Construction in Developing Countries*. 15(2), 49-67.
- Anastasopoulos, P. C., Samuel, A.M. I., Labi, A.M., Bhargava, A., Mannering, F. L. (2012). Empirical assessment of the Likelihood and Duration of Highway Project Time Delays. *Journal of Construction Engineering Management*. 138, 390-398.
- Anyawu, J.C., Oyefusi, A., Oaikhenan, H., Dimowo, F.A. (1997). *The Structure of the Nigerian Economy (1960 -1997)*. Onitsha: Joanee Educational Publishers Limited.
- Arize, A. C., Osang, T. Slottje, D.T. (2000). Exchange-Rate Volatility and Foreign Trade: Evidence from Thirteen LDCs.” *Journal of Business and Economic Statistics*. 18 (1), 10–17.
- Ashley, D., Bonner, J. (1987). Political Risks in International Construction. *Journal of Construction Engineering and Management*. 113 (3), 447–467.
- Assaf, S. A., Al-Hejji, S. (2006). “Causes of Delay in Large Construction Projects.” *International Journal of Project Management*. 24(4), 349-357.
- Assibey-Mensah, G.O. (2009). “Ghana’s Construction Industry and Global Competition”. *Journal of Black Studies*. 39 (6), 974-989.
- Attalla, M., Hegazy, T. (2003). “Predicting Cost Deviation in Reconstruction Projects: Artificial neural networks versus regression.” *Journal of Construction Engineering and Management*. 129(4), 405-411.
- Aureli, S., Salvatori, F. (2012). An Investigation on Possible Links between Risk Management, Performance Measurement and Reward Schemes”. *Journal of Accounting and Management Information Systems*. 11, 3: 306-334
- Australian and New Zealand Risk Management Standard (2004). AS/NZS4360, Home bush, NSW, Australia
- Awodele, O. A. (2012). Framework for Managing Risk in Privately Financed Market Project in Nigeria. Ph.D Thesis, Herrot –Watt University, United Kingdom.
- Baloi, D. (2002). A Framework for Managing Global Risk Factors Affecting Construction Cost Performance. PhD Thesis, Loughbrough University.

- Baloi, D., Price, A.D.F. (2003). Modelling Global Risk Factors Affecting Construction Cost Performance. *International Journal of Project Management*. 21, 261–269.
- Bannerman, P. L. (2008). Risk and Risk Management in Software Projects: A Reassessment. *Journal of Systems and Software*. 81(12), 2118-2133.
- Banaitiene, N., Banaitis, A., Norkus, A. (2011). Risk Management in Projects: Peculiarities of Lithuanian Construction Companies. *International Journal of Strategic Property Management*. 5(1), 60–73.
- Banister, D., Thurstain-Goodwin, M. (2011). Quantification of the Non-transport Benefits Resulting from Rail Investment. *Journal of Transport Geography*. 19, 212–223.
- Baudrit, C., Guyonnet, D., Dubois, D. (2005). Post Processing the Hybrid Method of addressing Uncertainty in Risk Assessments. *Journal of Environmental Engineering*. 131(12), 1750-1754.
- Baum, W.C., Tolbert, S.M (1995). *Investing in Development: Lessons of World Bank Experience*. Oxford: Oxford University Press.
- Benson, U.O., Victor, E.O. (2012). Real Exchange Rate and Macroeconomic Performance: Testing for the Balassa-Samuelson Hypothesis in Nigeria. *International Journal of Economics and Finance*. 4 (2), 127-134.
- Berechman, J., Ozmen, D., Ozbay, K. (2006). Empirical Analysis of Transportation Investment and Economic Development at State, County and Municipality levels. *Transportation*. 33, 537–551.
- Bhargava, A., Anastasopoulos, P. Ch., Labi, S., Sinha, K. C., Mannering, F. L. (2010) Three - Stage Least Analysis of Time and Cost Overruns in Construction Contracts. *Journal of Construction Engineering and Management*. ASCE/ November, 34-48
- Blaikie, N. (2009). *Approaches to Social Enquiry*. (2nd Ed) Cambridge, UK.
- Blaxter, L., Huges, C., Tight, M. (2001). *How to Research*. (2nd Ed) London: Open University Press, Polity Press.
- Branson, B.C. (2010). The Role of the Board of Directors and Senior Management in Enterprise Risk Management. In Fraser, J and Simkins, B. J. (Eds). *Enterprise Risk Management*.(pp 234-245).

- Bride, D., Volm, J. (2009). Perceptions of Owners in Germany Construction Projects: Congruence with Project Risk Theory. *Construction Management and Economics*. 27(11), 1059-1071.
- Budget Monitoring and Price Intelligent Unit (2005) The ABC of the Contract Due Process Policy. A Manual on Public Procurement Reform Programme in Nigeria. (1st Ed) Abuja: Government Press.
- Bureau for Public Procurement (2007) Public Procurement Act of Nigeria
- Cantos, P., Gumbau-Albert, M., Maudos, J. (2005). Transport Infrastructures, Spillover Effects and Growth: Evidence of the Spanish Case. *Transport Reviews*. 25(1), 25–50.
- Carr, V., Tah, J. H. M. (2001). A Fuzzy Approach to Construction Project Risk Assessment and Analysis: Construction Project Risk Management System. *Advances in Engineering Software*. 32 (2001), 847-857.
- Cartlidge, D. (2010). *Quantity Surveyor's Pocket Book*. Oxford: Butterworth-Heinemann, Elsevier.
- Central Bank of Nigeria (2003) Highway Maintenance in Nigeria: Lessons from Other Countries, *Occasional Paper No. 27 of the Research Department, Central Bank of Nigeria*.
- Chan, A. P. C., Yung, E. H. K., Lam, P. T. I., Tam, C. M., Cheung, S. O. (2001) Application of Delphi method in the Selection of Procurement Systems for Construction Projects. *Construction Management and Economics*. 19(7) 699-718.
- Chan, A. (2004), "Factors Affecting the Success of a Construction Project". *Journal of Construction Engineering Management*. 130(1), 153-5.
- Chan, E. H. W., Au, M. C. Y. (2007). Building Contractors' Behavioural Pattern in Weather Risks. *International Journal of Project Management*. 25(6), 615-626.
- Chan, J. H. L., Chan, D. W. M., Chan, A. P. C., Lam, P. T. I., Yeung, J. F. Y. (2011). Developing a Fuzzy Risk Assessment Model for Guaranteed Maximum Price and Target Cost Contracts in Construction. *Journal of Facility Management*. 9 (1), 34-51.
- Chapman, R. J. (1998). The Effectiveness of Working Group Risk Identification and Assessment Techniques. *International Journal of Project Management*. 16(6), 333-343.

- Chapman, C., Ward, S. (2000). "Estimation and Evaluation of Uncertainty: A Minimalist First Pass Approach". *International Journal of Project Management*. 18, 369-383.
- Chapman, C.; Ward, S. (2003). *Project Risk management: Processes Techniques and Insights*. Hoboken, NJ, USA: Wiley.
- Chapman, C. (2006). Key Points of Contention in Framing Assumptions for Risk and Uncertainty Management. *International Journal of Project Management*. 24, 303-313.
- Chatman, D. G., Noland, R. B. (2011). Do Public Transport Improvements Increase Agglomeration Economies? A review of Literature and an Agenda for Research. *Transport Reviews*. 31(6), 725–742.
- Cheng, S., Chan, C.W., Huang, G.H. (2002). Using Multiple Criteria Decision Analysis for Supporting Decision of Solid Waste Management. *Journal of Environmental Science and Health, Part A*. 37(6), 975-990.
- Cheung, S.O., Wong, P.S.P., Fung, A.S.Y., Coffey, W.V. (2006), "Predicting Project Performance through Neural Networks". *International Journal of Project Management*. 24,204-15.
- Chia, S.E., (2006). Risk Assessment Framework for Project Management. *Institute of Electrical Electronic Engineering*. 78,376-379.
- Chiara, N., Garvin, M.J. (2008). Variance Models for Project Financial Risk Analysis with Applications to Greenfield Bot Highway Projects. *Construction Management and Economic*. 26(9), 925-939.
- Chileshe, N., Kikwasi, G. J. (2014). Risk Assessment and Management Practices (RAMP) within the Tanzania Construction Industry: Implementation Barriers and Advocated Solutions. *International Journal of Construction Management*. 14, 239-254.
- Ching, H. Y., Colombo, M. T. (2014). Enterprise Risk Management Good Practices and Proposal of Conceptual Framework. Proceedings of the 2014 Industrial and Systems Engineering Research Conference, Brazil. (Eds) Guan, Y and H. Liao, H.
- Chou, J.S., Yang, I.T., Chong, W.K. (2009). Probabilistic Simulation for Developing Likelihood Distribution of Engineering Project Cost. *Automation in Construction*. 18, 570-577.

- Chou, J. S. (2011). Cost Simulation in an Item-based Project Involving Construction Engineering and Management. *International Journal of Project Management*, 29(6). 706–717. <http://doi.org/10.1016/j.ijproman.2010.07.010>.
- Connolly, J. P. (2006). Discussion of Modeling a Contractor's Markup Estimation. *Journal of Construction Engineering and Management*. 132(6), 657-658.
- Cooper, D., Grey, S., Raymond, G., Walker, P. (2005). *Project Risk Management Guidelines-Managing Risk in Large projects and complex procurements*. England: John Wiley & Sons, Ltd.
- Creedy, G. (2005). Risk Factors Leading to Cost Overrun in Highway Projects. Proceedings of the Queensland University of Technology research week international conference. 23-27 July. Brisbane, Australia.
- Creedy, G. D.; Skitmore, M.; Wong, J. K. W. (2010). Evaluation Of Risk Factors Leading to Cost Overrun in Delivery of Highway Construction Projects. *Journal of Construction Engineering and Management*. ASCE/May, 528-537.
- Creswell, J.W. (2003). *Research Design: Qualitative, Quantitative, and Mixed Methods Approaches*. (2nd Ed.) London: Sage Publications, Thousand Oaks.
- Creswell, J.W. (2009) *Research Design: Qualitative, Quantitative, and Mixed Methods Approaches*. (3rd Ed.) London: Sage Publications, Thousand Oaks.
- Creswell, J.W., Clark, V. L.P. (2011). *Designing and Conducting Mixed Methods Research*. (2nd Ed.) California: Thousand Oaks Sage Publications, Inc.
- Creswell, J.W. (2012). *Education Research: Planning, Conducting and Evaluating Quantitative and Qualitative Research*. (4th Ed.). New York: PEARSONS.
- Crouhy, M., Galai, D., Mark, R. (2006). *The Essentials of Risk Management*. New York: McGraw-Hill.
- Dada, J. O., Jagboro, G. O. (2007). An Evaluation of the Impact of Risk on Project Cost Overrun in the Nigerian construction industry. *Journal of Financial Management of Property and Construction*. 12(1), 37–44. <http://doi.org/10.1108/13664380780001092>.
- De, P., Tabucanon, M.T., Ogunlana, S.O. (1994). Planning for Project Control through Risk Analysis: A Petroleum Pipeline-Laying Project. *International Journal of Project Management*. 12 (1), 23-33.

- Deng, T. (2013). Impacts of Transport Infrastructure on Productivity and Economic Growth: Recent Advances and Research Challenges. *Transport Reviews*. 33(6) 686-689, DOI:10.1080/0144647.2013.851745.
- de la Cruz, M.P., del Cano, A., de la Cruz, E. (2006). Downside Risks in Construction Projects Developed by the Civil Service: The Case of Spain. *Journal of Construction Engineering and Management*. 132, 844-852.
- del Caño, A., de la Cruz, M. P. (2002). "An Integrated Methodology for Project Risk Management." *Journal of Construction Engineering and Management*. 128(6), 473-485.
- Demir, C., Kocabas, I. (2010). Project Management Maturity Models (PMMM) in Educational Organisations. *Procedia-Social and Behavioral Sciences*. 9, 1641-1645.
- Deublein, M., Schubert, M., Adey, B. (2014). "Prediction of Road Accidents: Comparison of Two Bayesian methods." *Structure and Infrastructure Engineering: Maintenance, Management, Life-Cycle Design and Performance*, 10:11, 1394-1416, DOI: 10.1080/15732479.2013.821139.
- Dey, P. K. (2001). Decision Support System for Risk Management: a case study. *Management Decision*. 39(8) 634-649.
- Dey, P. K. (2010). Managing Risk using Combined Analytic Hierarchy Process and Risk Map. *Applied Soft Computing*. 10 (2010) 990-1000.
- Dickmen, I. Birgonul, M.T. (2006). An Analytical Hierarchical Process Based Model for Risk and Opportunity Assessment of International Construction Projects. *Journal of Civil Engineering*. 33(1), 58-68.
- Dikmen, I., Birgonul, M. T., Han, S. (2007). Using Fuzzy Risk Assessment to Rate Cost Overrun Risk in International Construction Projects. *International Journal of Project Management*. 25,494-505.
- Dikmen, I., Birgonul, M.T., Anac, C., Tah, J.H.M., Aouad, G. (2008). Learning from Risks: A Tool for Post- Project Risk Assessment. *Automation in Construction*. 18, 42-50.
- Dissanayaka, S.M., Kumaraswamy, M.M. (1999). Evaluation of Factors Affecting Time and Cost Performance in Hong Kong Building Projects. *Engineering Construction and Architectural Management*. 6 (3), 287-298.

- Dlakwa, M., Culpin, M.F. (1990). "Reasons for Overrun in Public Sector Construction Projects in Nigeria". *International Journal of Project Management*. 8 (4), 237-241.
- Doloi, H., Sawhney, A., Iyer, K.C.B., Rentala, S. (2012). "Analysing Factors Affecting Delays in Indian Construction Projects", *International Journal of Project Management*. 30, 479-489.
- Dong, W.M., Wong, F.S. (1987). Fuzzy Weighted Average and Implementation of the Extension Principles. *Fuzzy Sets and System*. 21, 183-199.
- Dulaimi, M.F., Shan, H.G. (2002). The Factors Influencing Bid Mark-up Decisions of Large- and Medium-size Contractors in Singapore. *Construction Management and Economics*. 20(7), 601–610.
- Dwivedula, R., Bredillet, C.N. (2010). Profiling Work Motivation of Project Workers. *International Journal of Project Management*. 28, 158-165.
- Ebrahimnejad, S., Mousavi, S. M., Seyrafiapour, H. (2010). Risk Identification and Assessment for Built- Operate- Transfer Projects: A Fuzzy Multi Attribute Decision Making Model. *Expert System with Applications*. 37 (2010), 575-586.
- El- Seyegh, S. M. (2008). Risk Assessment and Allocation in the UAE Construction Industry. *International Journal of Project Management*. 26, 431-438.
- Enshassi, A., Al-Najjar, J., Kumaraswamy, M. (2009). "Delays and Cost Overruns in the Construction Projects in the Gaza strip". *Journal of Financial Management of Property and Construction*. 14 (2), 126-151.
- Erling, S.A., Svein Arne, J. (2000). "Project Evaluation Scheme: A Tool for Evaluating Project Status and Predicting Project Results". *Project Management Journal*. 6 (1), 61-69.
- Faridi, A.S., El-Sayegh, S.M. (2006). "Significant Factors Causing Delay in UAE Construction Industry". *Construction Management and Economics*. 24, 1167-1176
- Fellows, R. R., Liu, A. (2008). *Research Methods for Construction*. (3rd Ed.) London: Wiley Blackwell Science.
- Feng, G. (2010). *Analysis and Synthetic of Fuzzy Control System: A model- Based Approach*. London: CRC Press Taylor & Francis Group, LLC.
- Flanagan, R., Norman, G. (1993). *Risk Management and Construction*. Oxford: Blackwell.

- Flyvbjerg, B., Holm, M., Buhl, S. L. (2003). "How Common and How Large are Cost Overrun in Transport Infrastructure Projects?" *Transport Revenue*. 23(1), 71-88.
- Fong, L. C. (2012). Jurisprudence behind the CIPAA. Proceeding and Presentations of the Quantity Surveying International Conference and Malam Anugerah LJBM. 25-26 September. Renaissance Hotel, Kuala Lumpur, Malaysia.
- Forbes, D., Smith, S., Horner, M. (2008). "Tools for Selecting Appropriate Risk Management Techniques in the Built Environment. *Construction Management and Economics*. Oct -December 2008, (26), 1241-1250.
- Frimpong, Y., Oluwoye, J., Crawford, L. (2003). Causes of Delay and Cost Overruns in Construction of Groundwater Projects in a Developing Countries: Ghana as a Case Study. *International Journal of project Management*. 21 (5), 321-326.
- Ghosh, S., Jiintanapakanont, J. (2004). Identifying and Assessing the Critical Risk Factors in An underground Rail Project in Thailand: A Factor Analysis Approach. *International Journal of Project management*. 22, 633-643.
- Glover, J. (1993). Achieving the Organisational Change Necessary for Successful TQM. *International Journal of Quality and Reliability Management*. 10, 47-64.
- Goh, C. S., Abdul -Rahman, H. (2012). Applying Risk Management Workshop for a Public Construction Projects: A case study. *Journal of Construction Engineering and Management*. 14(3), 185–186
- Gordon, L.A., Loeb, M.P., Tseng, C. (2009). "Enterprise Risk Management and Firm Performance: A Contingency Perspective". *Journal of Accounting and Public Policy*. 28(4), 301–327.
- Grant, K.P., Cashman, W.M., Christensen, D.S. (2006). Delivering Projects on Time. *Research & Technology Management*. (November–December), 52–58.
- Guangshe, J., Li, C., Jianguo, C., Shuisen, Z., Jin, W. (2008). Application of Organizational Project Management Maturity Model (OPM3) to Construction in China: An empirical study. Proceeding of 2008 International Conference on Information Management, Innovation Management and Industrial Engineering DOI 10 1109/ICII.
- Gupta, M.M., Qi, J. (1991). Theory of T- Norms and Fuzzy Inference Methods. *Fuzzy Sets and System*. 40, 431-450.

- Guu, Sy-M. ((2002). Fuzzy Weighted Averages Revisited. *Fuzzy Sets and Systems*. 126 (2002), 411–414.
- Guyonnet, D., Bourgigne, B., Dubois, D., Fargier, H., Come, B., Chiles, J. (2003). Hybrid Approach for Addressing Uncertainty in Risk Assessments. *Journal of Environmental Engineering*. 129(1)68-79.
- Hallowell, M.R., Gambatese, J.A. (2010). Qualitative Research: Application of Delphi Method to CEM Research. *Journal of Construction Engineering and Management*. 136, 99-107.
- Han, S.H., Kim, D. Y., Kim, H., Jang, W. (2008). A Web-based Integrated System for *International Project Risk Management*. *Automation in Construction*. 17, 342-356.
- Hassanein, AMR A.G., Afify- Halaa, M.F. (2007). “Risk Management Practices of Contractors: A Case Study of Power Station Projects in Egypt”. *Journal of Financial Management of Property and Construction*. 12 (3), 164-179.
- Hashemi, H., Mousavi, S., Tavakkoli, R., Gholipour, Y. (2013). “Compromise Ranking Approach with Bootstrap Confidence Intervals for Risk Assessment in Port Management Projects. *Journal of Management Engineering*. 10, 334–344.
- Hastak, M., Shaked, A. (2000). ICRAM-I: Model for International Construction Assessment. *Journal of Management and Engineering*. ASCE 16(1), 59-69.
- Henschel, T. (2006). Risk Management Practices in Germany SMEs: an Empirical Investigation. *International Journal of Entrepreneurship and Small Business*. 3(5), 554-571.
- Hillson, D.A., (1997).Towards a Risk Maturity Model. *International Journal of project and Business Risk Management*. 1(1), 35-45.
- Hillson, D. A. (2004). *Effective Opportunity Management for Projects: Exploiting positive risk*. New York: Marcel Dekker.
- Hillson, D., Simeon, P. (2007). *Practical Project Risk Management-The Atom Methodology*. Vienna, Virginia: Management Concepts.
- Hong, J. J., Chu, Z. F., Wang, Q. (2011). Transport Infrastructure and Regional Economic Growth: Evidence from China. *Transportation*. 38(5), 737–752.
- Hopkinson, M., Lovelock, G. (2004). “The project Risk Maturity Model –Assessment of the UK MoD stop 30 acquisition

projects.”<http://www.businessrisksolutions.com/web%20site%20papers.Risk%20Maturity%20Model%20Assessment%20UK%20Mod%20DPA%20Major%20Projects.pdf>. Accessed on 24th May, 2015.

- Hopkinson, M.M. (2011). *The Project Risk Maturity Model: Measuring and Improving Risk Management Capability*. England: Gower Publishing Ltd.
- Howitt, D., Cramer D. (2008). *Introduction to SPSS in Psychology for Version 16 and Earlier*. (Fourth Ed.) England: PEARSON Prentice Hall.
- Hull, J. K. (1990). Application of Risk analysis Techniques in Proposal Assessment. *International Journal of Project Management*. 8,152-157.
- Hussin, M., Adnan, H., Rahmat, I. (2014). Developing a Facility Management Framework using Mixed Methods. Proceedings of the 13th European Conference on Research Methodology for Business and Management Studies ECRM 2014. 16-17 June. Cass Business School, City University London, UK ON. (Eds) Brown, A. and Rich, M. <http://books> in google.com.my books? Accessed on 8th October, 2015.
- Hwang B-G., Zhao X., Toh L.P. ((2014). Risk Management in Small Construction Projects in Singapore: Status, Barriers and Impact. *International Journal of Project Management*. 32(1), 116-124.
- Ibrahim, Y. (2011). Impetus for National Development: Nigeria Construction Industry. Paper presented at the 1st National Building and Construction Economic Round Table (BCERT) of the Quantity Surveyors Registration Board of Nigeria. 14-15, June. Shehu Musa Yar'Adua centre, Abuja.
- Ibrahim, A. D. (2011) Developing a Vibrant Construction Sector in Nigeria: Issues, strategies and challenges. Paper presented at the 1st National Building and Construction Economic Round Table (BCERT) of the Quantity Surveyors Registration Board of Nigeria. 14-15, June. Shehu Musa Yar'Adua centre, Abuja.
- Ighodaro, C.A.U. (2008). Road Infrastructure and Economic Growth in Nigeria. Paper Submitted at the First International Conference on Transport Infrastructure (ICTI.2008). 24-26 April. Beijing, China.
- International Association of Contract and Commercial Management (IACCM). (2003). 'Organisational Maturity in Business Risk Management. The IACCM

- Business risk management maturity model (BRM3)' <http://www.risk-doctor.com/pdf-files/brm1202.pdf>. Accessed on 8th October, 2014.
- Iyer, K. C., Jha, K. N. (2006). Critical Factors Affecting Schedule Performance: Evidence from Indian Construction Projects. *Journal of construction Engineering and Management*. 132(8), 871-880.
- Jabareen, Y. (2009). Building a Conceptual Framework: Philosophy, Definitions and Procedure. *International Journal of Qualitative Methods*. 8(4), 49-55.
- Jannadi, O. S., Almishari, S. (2003). Risk Assessment in Construction. *Journal of Construction Engineering and Management*. 129,492-500.
- Jerome, A.T. (2009). Private Sector Participation in Infrastructure in Africa (1970 to 2007), <http://ssrn.com/abstract=1526659>. Accessed on 15th June, 2015.
- Jiang, J. J., Edward, C., Gary K. (2002). The Importance of Building a Foundation for User: Involvement in Information System Projects. *Project Management Journal*. 22, (1), 20-26.
- Jiwattanakulpaisarn, P., Noland, R. B., Graham, D. J. (2012). Marginal Productivity of Expanding Highway Capacity. *Journal of Transport Economics and Policy*. 46(3), 333–347.
- Jones,(2006). Infrastructure to Support Inclusive Growth and Poverty Reduction- In Infrastructure for Supporting Inclusive Growth and Poverty Reduction in Asia, Asian Development Bank, © 2012 Asian Development Bank.
- Kaliba, C., Muya, M., Mumba, K. (2009). Cost Escalation and Schedule Delay in Road Construction project in Zambia. *International Journal of Project Management*. 27,522- 531.
- Kangari, R., Riggs, L.S (1989). Construction Risk Assessment by Linguistics. *IEEE Transactions on Engineering Management*. 36(2), 126-131.
- KarimiAzari, A., Mousavi, N., Mousavi, S. F., Hosseini, S. (2011). Risk Assessment Model Selection in Construction Industry. *Expert Systems with Application*. 38, 9105-9111.
- Kasabov, N. K. (1998). *Foundations of Neural Networks, Fuzzy Systems, and Knowledge Engineering*. London, England: The MIT Press.
- Kasimu, A.M., Usman, M.D. (2013). Delay in Nigeria Construction Industry. *Journal of Environmental Sciences and Resources Management*. 5 (2) 120-129.

- Kathleen T. H., Carlos E. C., Samuel H. C., Robert P. E (2001). Rehabilitation strategies for Highway Pavements. *NCHRP Web Document 35 (Project CI-38) Contractor's Final Report*
- Kerzner, H., (2003). *Project Management: A Systems Approach to Planning, Scheduling and Controlling*. (8th Ed.) New Jersey: John Wiley & Sons, Inc.
- Kerzner, H. (2009). *Project Management. A Systems Approach to Planning, Scheduling and Controlling*. (10th Ed.) New Jersey, Hoboken: John Wiley & Sons, Inc.
- Kikwasi, G. J. (2012). Causes and Effect of Delays and Disruptions in Construction Projects in Tanzania. *Australasian Journal of Construction Economics and Building conference series*. 1(92), 52-59.
- Koushki, P.A., Al-Rashid, K., Kartam, N. (2005). Delays and Cost Increases in the Construction of Private Residential Projects in Kuwait. *Construction Management and Economics (March 2005)*. 23, 285–294.
- Kovacic, Z., Bogdan, S. (2006). *Fuzzy Controller Design. Theory and Applications*. London: Taylor & Francis Group, LLC.
- Kululanga, G., Kuotcha, W. (2010). “Measuring Project Risk Management Process for Construction Contractors with Statement Indicators linked to numerical scores”. *Engineering Construction and Architectural Management*. 17(4), 336-351.
- Laryea, S., Hughes, W. (2008). How Contractors Price Risk in Bids: Theory and Practice. *Construction Management and Economics*. 26 (9), 591-608.
- Laryea, S., Hughes, W. (2011). Risk and Price in the Bidding Process of Contractors. *Journal of Construction Management and Engineering*. 137 (4), 248-258. ISSN.
- Lee, Y., Kozar, K.A. (2006). Investigating the Effect of Website Quality on e-business Success: An Analytic Hierarchy Process (AHP) Approach. *Decision Support System*. 42(3), 1383-1401.
- Li, Z. (2011). Estimating the Social Return to Transport Infrastructure: A Price-difference Approach Applied to a Quasi-Experiment. Paper presented at the Conference on Infrastructure for Inclusive Growth and Poverty Reduction. 14-15 April. Asian Development Bank, Manila.

- Liberatore, M.J., Nydick, R.L. (2008). The Analytic Hierarchy Process in Medical and Health Care Decision Making: A Literature Review. *European Journal of Operation Research*. 189 (1), 194-207.
- Limão, N., A. J. Venables. (2001). Infrastructure, Geographical Disadvantage, Transport Costs, and Trade. *The World Bank Economic Review*. 15 (3). 451–479.
- Liu, M., Ling, Y.Y. (2005). Modelling a Contractor's Mark-up Estimation. *Journal of Construction Engineering and Management ASCE*. 131(4) 391-399.
- Liu, J., Li, B., Lin, B.; Nguyen, V. (2007). “Key Issues and Challenges of Risk Management and Insurance in China's Construction Industry, an Empirical Study”. *Industrial Management & Data Systems*. 107(3), 328-396.
- Low, S. P., Liu, J., He. S. (2009). External Risk Management Practices of Chinese Construction Firms in Singapore. *KSCE Journal of Civil Engineering*. 13, 85-95.
- Loosemore, M., Raftery, J., Reilly, C., Higgon, D. (2006). *Risk Management in Projects*. (2nd Ed.) New York: Taylor and Francis.
- Love, P.E.D., Sing, C., Wang, X., Irani, Z., Thwala, D.W. (2014). Overruns in Transportation Infrastructure Project. *Structure and Infrastructure Engineering: Maintenance, Management, Life-Cycle Design and Performance*. 1-19.
- Luu, V.T., Kim, S-Y., Tuan, N.V., Ogunlana, S. O. (2009). Quantifying Schedule Risk in Construction Projects using Bayesian Belief Network. *International Journal of Project Management*. 27, 39-50.
- Lyons, T., Skitmore, M. (2004). Project Risk Management in the Queensland Engineering Construction Industry: A Survey. *International Journal of Project Management*. 22(1), 51- 61.
- Mafakheri, F., Breton, M., Chauhan, S. (2012). Project-to- Organization Matching: An Integrated Risk Assessment Approach. *International Journal of Information Technology Project Management*. 3(3), 45-59.
- Mahamid, I. (2011). “Risk Matrix for Factors Affecting Time Delay in Road Construction Projects: Owners' Perspective.” *Engineering Construction and Architectural Management*. 18(6), 609 – 617.

- Mahamid, I., Bruland, A. (2012). Cost Deviation in Road Construction Projects: The Case of Palestine. *Australia Journal of Construction Economics and Building*. 12 (1), 58-71.
- Mahamid, I., Bruland, A., Dmaid, N. (2012). Causes of Delay in Road Construction Projects. *Journal of Management in Engineering*. 28(3), 300–310. [http://doi.org/10.1061/\(ASCE\)ME.1943-5479.0000096](http://doi.org/10.1061/(ASCE)ME.1943-5479.0000096).
- Mahamid, I. (2013). Common Risks Affecting Time Overrun in Road Construction Projects in Palestine: Contractors' Perspective. *Australasian Journal of Construction Economics and Building*. 13(2), 45–53.
- Manoliadis, O., Tsolas, O., Nakou, A. (2006). Sustainable Construction and Drivers of Change in Greece: Delphi study. *Construction Management and Economics*. 24(2), 113- 120.
- Mansfield, N.R., Ugwu, O.O., Doran, T. (1994). Causes of Delay and Cost Overruns in Nigeria construction projects. *International Journal of Project Management*. 2(4), 254-260.
- Marcelino-Sádaba, S., Pérez-Ezcurdia, A., Angel M. Echeverría Lazcano, A. M.E., Pedro Villanueva, P.(2014). Project Risk Management Methodology for Small Firms. *International Journal of Project Management*. 32, 327–340.
- Martis, M. S. (2006). Validation of Simulation Based Models: A Theoretical Outlook. *The Electronic Journal of Business Research Methods*. 4(1), 39-46.
- Marzouk, M.M., El-Rasas, T.I. (2014). “Analyzing Delay Causes in Egyptian Construction Projects”. *Journal of Advanced Research*. 5 (1), 49-55.
- McCabe, B., Simaan M., AbouRizk, S.M., Randy Goebee, R. (1998). Belief Networks for Construction Performance Diagnostics. *Journal of Computing in Civil Engineering*, ASCE. 12(2), 93-100.
- Mckim, R.A. (1992). Risk Management: Back to Basic. *Cost Engineering*. 34(12), 7-16.
- Medawar, P.B. (1969). *Induction and Intuition in Scientific Thought*. London: Methuen.
- Memon, A.H., Ismail, A.R., Ade Asmi, A., Nor Hazana, A. (2013). “Using Structural Equation Modelling to Assess Effects of Construction Resource Related Factors on Cost Overrun”. *World Applied Sciences Journal*. 21, 6-15.

- Mikes, A. (2010). *Becoming the Lamp Bearer*. In Fraser, J. and Simkins, B.J. (Eds) *Enterprise Risk Management. Today's leading research and best practices for tomorrow's executives*. Hoboken: Wiley.
- Miles, M. B., and Huberman, A.M. (1994) *Qualitative Data Analysis: An Expanded Sourcebook*. (2nd Ed.) California: Sage Publication.
- Mochatar, K., Arditi, D (2001). Pricing Strategy in the US Construction Industry. *Construction Management and Economics*. 19, 405-415.
- Mohammed, K. A. (2014). Knowledge Management in the Civil Engineering Construction Sectors in Nigeria. PhD Thesis (Quantity Surveying). Universiti Teknologi Malaysia, Skudai.
- Molenaar, K. R. (2005). Programmatic Cost Risk Analysis for Highway Megaprojects. *Journal of Construction Engineering Management*. 131,343-353.
- Monetti, E., Rosa, S.A., Rocha, R. M., (2006). The Practice of Project Risk Management in Government Projects: A Case Study in Sao Paulo City. *Construction in Developing Economics: New Issues and Challenges*. Santiago, Chile. 18-20 January.
- Morse, J.M. (1991). Approaches to Qualitative-Quantitative Methodological Triangulation. *Nursing Research*. 40, 120-123.
- Moura, H. P., Teixeira, J. C., Pires, B. (2007). Dealing with Cost and Time Overrun in the Portuguese Construction Industry. *CIB World building congress 2007*.
- Mousavi, S., Tavakkoli-Moghaddam, R., Azaron, A., Mojtahedi, S., Hashemi, H. (2011). Risk Assessment for Highway Projects using Jackknife Technique. *Expert System with Applications*. 38, 5514-5524.
- Mu, S., Chen, H.(2013). Modelling Contractors Risk Management Capability in Metro Projects. Proceeding of the International Conference on Construction and Real Estate Management 702-711, ascelibrary.org/doi,101061/9780784413135.066.
- Mu, S., Chen, H.; Chohr, M., Peng W. (2014). Assessing Risk Management Capability of Contractors in Subway Projects in Mainland China. *International Journal of Project Management*. 32(2), 452-460.
- Muhtar, M. (2009). 2nd Quarter Budget Implementation Report Budget Office of the Federation, Federal Ministry of Finance, Abuja.

- Mustafa, M. A., Al- Bahar, J. F. (1991). Project Assessment using the Analytic Hierarchy Process. *IEEE Transactions on Engineering Management*. 38(1), 46-52.
- National Research Council (2005). The owner's Role in Project Risk Management. A Report of the Committee for Oversight and Assessment of U.S Department of Energy Project Management Board on Infrastructure and the Construction Environment. Lockbox, Washington National Academic press.
- Ngai, S.C., Drew, D.S., Lo, H.P., Skitmore, M. (2002). "A Theoretical Framework for Determining the Minimum Number of Bidders in Construction Bidding Competitions". *Construction Management and Economics*. 20 (6), 473-482.
- Neuman, W. (2006). *Social Research Methods: Qualitative and Quantitative Approaches*. (6th Ed.) Boston, USA: Pearson.
- Nieto-Morote, A., Ruz-Vila, F. (2011). A Fuzzy Approach to Construction Projects Risk Assessment. *International Journal of Project Management*. 29, 220-231.
- Nunnally, J. C., Bernstein, I. H. (1994). *Psychometric Theory*. (3rd Ed.) New York: McGraw-Hill.
- Odeyinka, H. A., Iyagba, R. I. (2000). Risk Management in Construction to Avoid Cost Overrun. *The Quantity Surveyor*. 31(2), April/June 14-21.
- Odeyinka, H.A., Lowe, J., Kaka, A. (2008). "An Evaluation of Risk Factors Impacting Construction Cash Flow Forecast". *Journal of Financial Management of Property and Construction*. 13 (1), 5-17.
- Ogunjuiba, K.K., Ehigiamusoe, K. (2014). Capital Budget Implementation in Nigeria: Evidence from the 2102 Capital Budget. *Contemporary Economics*. 8(3), 299-334.
- Ogunlana, S.O., Promkuntong, K., Jearkjirm, V. (1996). "Construction Delays in Fast-Growing Economy: Comparing Thailand with Other Economies". *International Journal of Project Management*. 14 (1), 37-45.
- Ogunsemi, D.R. (2005). Meeting the Challenges of National Development-A Case for Review of Quantity Surveying Curriculum. Paper Presented at the 21st biennial conference of the Nigeria Institute of Quantity Surveyors. 24-27 November. Premier Hotel, Ibadan, Nigeria.
- Ogunsemi, D. R., Awodele, O. A. (2005). Assessment of Factors Affecting Time Performance on Building Projects in South-Western Nigeria. Paper presented

- at International Conference on Science and Technology. 14-19 August. FUT, Akure, Nigeria.
- Ogunsemi, D. R. (2011). Critique of Public Procurement Act 2007. Paper Presented at the Seminar of the NIQS, Osun State Chapter on Public Procurement Act. 27-28th January. Royal Spring Hotel Inn, Oshogbo.
- Ogunsemi, D., Jagboro, G. O. (2006). Time-Cost Model for Building Projects in Nigeria. *Construction Management & Economics*. 24, 353-358.
- Okmen, O., Oztas, A. (2008). Construction Project Network Evaluation with Correlated Schedule Risk Analysis Model. *Journal of Engineering Management*. 134(1), 49-63.
- Okoli, C., Pawlowski, S. D. (2004). The Delphi Method as a Research Tool: An Example, Design Considerations and Applications. *Information and Management*. 42, 15-29.
- Okonjo- Iweala, C. (2010). Fourth Quarter Budget Implementation Report (2011). A Report Submitted to the Joint Finance Committee of the Nigeria National Assembly and Fiscal Responsibility Commission. October, 2011.
- Okonjo- Iweala, C. (2012). Fourth Quarter Budget Implementation Report (2012). A Report Submitted to the Joint Finance Committee of the Nigeria National Assembly and Fiscal Responsibility Commission. December, 2012.
- Okonjo- Iweala, C. (2013). Fourth Quarter Budget Implementation Report (2013): A Report Submitted to the Joint Finance Committee of the Nigeria National Assembly and Fiscal Responsibility Commission in November, 2013.
- Olawale, Y. A., Sun, M. (2010). Cost and Time Control of Construction Projects: Inhibiting Factors and Mitigating Measures in Practice. *Construction Management and Economics*. May (2010) 28, 509-526.
- Oluba, M. (2008). Who Should Provide Public Infrastructure in Nigeria?. *Economic Reflections*. 8(4). 23-35.
- Olurankinse, F. (2012). Analysis of the Effectiveness of Capital Expenditure Budgeting in the Local Government System of Ondo State, Nigeria. *Journal of Accounting and Taxation*. 4 (1), 1-6.
- Onolememen, M. O. (2013). Federal Ministry of Works-Transforming Nigeria roads: achievement and challenges in 2012: Report Presented to the Federal Executive council. April, 2013.

- www.slideshare.net/TransformingNG/ministry -of-works- progress. Accessed on November 9, 2014.
- Onolememen, M. O. (2014). Third Year Ministerial Press Briefing on the Achievement of President Goodluck Jonathan GCFR Administration in the Transformation of Road Sector in Nigeria.
- Onyeiwu, E. (2011). Challenges of Construction and Infrastructure Development in Nigeria. Paper presented at the 1st National Building and Construction Economic Roundtable (BCERT) of the Quantity Surveyors Registration Board of Nigeria. 14 -15 June. Shehu Musa Yar'Adua Center, Abuja.
- Oribuyaku, T. (2011). Developing Indigenous Capacity in Nigeria Construction Industry. Paper presented at the 1st National Building and Construction Economic Roundtable (BCERT) of the Quantity Surveyors Registration Board of Nigeria. 14 -15 June. Shehu Musa Yar'Adua Center, Abuja.
- Othman, A.A., Torrance, J.V., Hamid, M.A. (2006). "Factors Influencing the Construction Time of Civil Engineering Projects in Malaysia". *Engineering, Construction and Architectural Management*. 13(5), 481-501.
- Othman, A. (2008). Incorporating Value and Risk Management Concepts in Developing Low Cost Housing Projects. *Emirates Journal of Engineering Research*. 13, 45-52.
- Oztas, A., Okmen, O. (2004). Risk Analysis in Fixed- Price Design-Build Construction Projects. *Building and Environment*. 39, 229-237.
- Paek, J.H., Lee, Y.W., Ock, J.H. (1993). Pricing Construction Risk: Fuzzy Set Application. *Journal of Construction Engineering and Management*, ASCE. 109(4), 743-56.
- Papadaki, P., Gale, A. W., Rimmer, J.R., Kirtham, R.J., Taylor, A., Brown, M. (2014). Essential Factors that Increase the Effectiveness of Projects/ Programme Risk Management. *Procedia- Social and Behavioral Sciences*. 119(2014), 921-930.
- Pedrycz, k., Gomide, F. (2007). *Fuzzy System Engineering, Towards Human- Centric Computing*. New York: John Wiley and Sons.
- Perera, B. A. K., Dhannasinghe, I., Rameezdeen, R. (2009). Risk Management in Road Construction: The Case of Sri Lanka. *International Journal of Strategic Property Management*. 13 (2), 87-102.

- Perera, B.A.K.S., Rameezdeen, R., Chilshe, N., Hosseini, R. (2014). Enhancing the Effectiveness of Risk Management Practices in Sri Lanka Road Construction Projects: A Delphi Approach. *International Journal of Construction Management*. 14:1, 1-19, DOI:10.1080/15623599.2013.87271.
- Poh, Y. H., Tah, J. H. M. (2006). Integrated Duration- Cost Influence Network for Modelling Risk Impacts on Construction Tasks. *Construction Management and Economics*. 24(8), 861-868.
- Pradana, M., Bandula, J. (2012). Risk Management Practices in Small and Medium Enterprises: Evidence from Sri Lanka”. *International Journal of Multidisciplinary Research*. 2(7), 226-234.
- Project Management Institute (2004). *A guide to Project Management Body of Knowledge: (PMBOK)*. (3rd Ed.) Newton Square, PA: Project Management Institute.
- Project Management Institute “PMI” (2008). *A guide to the Project Management Body of Knowledge*. (4th Ed.) Newton Square, PA: Project Management Institute.
- Ramanathan, C., Potty, N.S., Arazi, B. (2012). “Analysis of Time and Cost Overrun in Malaysian Construction”. *Advanced Materials Research*. 452/453, 1002-1008, available at: www.scientific.net Accessed on 10th of July, 2015.
- Raihan, S. (2011). Infrastructure, Growth and Poverty in Bangladesh. Paper presented at the Conference on Infrastructure for Inclusive Growth and Poverty Reduction. 14–15 April. Asian Development Bank. Manila.
- Ren, Y.T., Yeo, K.T. (2004). Risk Management Capability Maturity Model for Complex Product Systems (CoPS) Projects. Proceedings of *International Engineering Management Conference*. (pp 807-811).
- Ren, Y.T., Yeo, K.T. (2009). Risk Management Capability Maturity Model for Complex Product Systems (CoPS) projects. *System Engineering*. 12(4), 275-294.
- Rezaire, K., Amalnik, M.S., Gereie, A., Ostadi, B., Shakhseeniaee, M. (2007). Using Extended Monte Carlo Simulation Method for the Improvement of Risk Management: Consideration of Relationships between Uncertainties. *Applied Mathematics and Computation*. 190, 1492-1501.

- Risk Management Research and Development Program Collaboration (RMRDPC). (2002). 'Risk management maturity level development' .<http://www.pmi-switzerland.ch/fall05/riskmm.pdf>, Accessed in October 08, 2014.
- Rowe, G., Wright, G. (1999). The Delphi Technique as a Forecasting Tool: Issues and Analysis. *International Journal of Forecasting*. 15(4), 353-375.
- Ruddock, L., Lopes, J. (2006). The Construction Sector and Economic Development: The 'Bon' curve. *Construction Management and Economics*. 24, 717-723.
- Rusteika, S., Boomer, J. (1992). Budgeting for Changes in Construction. *American Association of Cost Engineers Trans.* 1, 21- 27.
- Ruthankoom, R., Ogunlana, S.O. (2003). Testing Herzberg's Two Factor Theory in the Thai Construction Industry. *Engineering Construction and Architectural Management*. 10,333-341.
- Saaty, T.L. (2008). Decision Making with the Analytic Hierarchical Process. *International Journal of Service Science*. 1, 83-98.
- Sadeghi, N., Fayek, A. R., Pedrycz, W. (2010). Fuzzy Monte Carlo Simulation and Risk Assessment in Construction. *Computer-Aided Civil and Infrastructure Engineering*. 25, 238-252.
- Sambasivan, M., Soon, Y. W. (2007). Causes and Effects of Delay in Malaysia Construction Industry. *International Journal of Project Management*. 25 (2007), 517-526.
- Sameh M., El- Sayegh, S., Mahmoud H., Mansour, M. (2015). Risk Assessment and Allocation on Highway Construction Project in the UAE. *Journal of Management in Engineering* [10.1061/\(ASCE\)ME.1943-5479.0000365](https://doi.org/10.1061/(ASCE)ME.1943-5479.0000365) , 04015004. Accessed on 15th June, 2015.
- Schieg, M. (2006). Risk Management in Construction Project Management. *Journal of Business Economics and Management*. VII (2), 77-83.
- Serpella, A. F., Ferrada, X., Howard, R., Rubio, L. (2014). Risk Management in Construction Projects: A Knowledge-based Approach. *Procedia - Social and Behavioral Sciences*. 119, 653–662. <http://doi.org/10.1016/j.sbspro.2014.03.073>. Accessed on 15th June, 2015.
- Shatz, H. J., Kitchens, K. E., Rosenbloom, S., Wachs, M. (2011). Highway Infrastructure and the Economy: Implications for Federal Policy. RAND Corporation monograph series, RAND Corporation, Santa Monica.

- Shen, L., Platten, A., Deng, X. P. (2006). Roles of Public Private Partnerships to Manage risks in Public Sector Projects in Hong Kong. *International Journal of Project Management*. 24, 587-594.
- Shen, L.Y. (1999) Risk Management, In Rick, Best and G.D. Valence (Eds), *Building in values, Pre-Design Issues* (pp. 248-265). London: Arnold.
- Shehu, Z., Endut, I.R., Akintoye, A. (2014). "Factors Contributing to Project Time and hence Cost Overrun in the Malaysian construction industry". *Journal of Financial Management of Property and Construction*. 19(1), 55 – 75.
- Shih, H-S., Shyur, H-J., Lee, E. S. (2007). An Extension of TOPSIS for Group Decision making. *Mathematical and Computer Modelling*. 45, 801-813.
- Simister, S.J. (1994). Usage and Benefits of Project Risk Analysis and Management. *International Journal of Project Management*. 12(1), 5-8.
- Smith, R. J. (1992). Risk Management for Underground Projects: Cost Saving Techniques and Practices for Owners. *Tunnelling and Underground Space Technology*. 7(2), 109-177.
- Smith, N. (1999). *Managing Risk in Construction Projects*. Oxford: Blackwell Science.
- Smith, N. (2002). Risk Management in J. Kelly, R. Morledge and S. Wilkinson (Ed.), *Best value in Construction*. Osney Mead, Oxford: Blackwell Science Ltd.
- Smith, N. (2006). *Managing Risk in Construction Projects*. (2nd Ed) Malden: Wiley-Blackwell.
- Smit, Y., Watkins, J.A. (2012). A Literature Review of Small and Medium Enterprises (SME) Risk Management Practices in South Africa". *African Journal of Business Management*. 6(21) 6324-6330.
- Stoy, C. Dreier, F. Schalcher, H-R. (2007). Construction Duration of Residential Building Projects in Germany. *Engineering Construction and Architectural Management*. 14 (1), 52-64.
- Subramanyan, H., Sawani, P. H., Bhatt, V. (2012). Construction Project Risk Assessment: Development of Model Based on Investigation of Opinion of Construction Project Experts from India. *Journal of Construction Engineering and Management*. ASCE March, 138, 409-421.

- Sun, L., Srivastava, R. P., Mock, T.J. (2006). An Information Systems Security Risk Assessment Model under Dempster- Shafer Theory of Belief Function. *Journal of Management Information Systems*. 22(4), 109-142.
- Subramanyan, H., Sawani, P. H., Bhatt, V. (2012). Construction Project Risk Assessment: Development of Model Based on Investigation of Opinion of Construction Project Experts from India. *Journal of Construction Engineering and Management*. ASCE March, 138, 409-421
- Tadayon M., Jaafar M., Nasrie. (2012). An Assessment of Risk Identification in Large Construction Projects in Iran. *Journal of Construction in Developing Countries*. 17, 57-69.
- Tah, J.H.M., Thorpe, A., McCaffer, R. (1993). Contractor Project Risks Contingency Allocation using Linguistic Approximation. *Journal of Computing Systems in Engineering*. 4(2), 281-293.
- Tah, J., Carr, V. (2000). A Proposal for Construction Project Risk Assessment Using Fuzzy Logic. *Construction Management and Economics*. 18, 491-500.
- Tamosaitiene, J., Zavadskas, E.K., Turskis, Z. (2013). Multi-Criteria Risk Assessment of a Construction Project. *Procedia Computer Science*. 17 (2013), 129 – 133.
- Taroun, A., Yang, J.B., Lowe, D. (2011). Construction Risk Modelling and Assessment: Insights from Literature Review. *The Built & Human Environment Review*. 4(1), 87-97.
- Thomas, A.V., Kalidindi, S.N., Ganesh, L.S. (2006). Modelling and Assessment of Critical Risks in BOT Road Projects. *Construction Management and Economics*. 24(4), 407-424.
- Thuyet, N.V., Ogunlana, S.O., Dey, P.K. (2007). “Risk Management in Oil and Gas Construction Projects in Vietnam”, *International Journal of Energy Sector Management*. 1 (2), 75-194.
- Touran, A., Wisser, E. P. (1992). Monte Carlo Technique with correlated Random Variables. *Journal of Construction Engineering Management*. 118, 258-272.
- Touran, A. (2003). Probabilistic Model for Cost Contingency. *Journal of Construction Engineering Management*. 129,280-284.
- Tummala, R., Schoenherr, T. (2011). Assessing and Managing Risks Using the Supply Chain Risk Management Process (SCRMP). *Supply Chain Management International Journal*. 16 474-483.

- Umoren, V., Sule, R. O., Eni, D. D. (2011). Assessment of some Road Infrastructural Variables in Akwa Ibom State, Nigeria. *Ethiopian Journal of Environmental Studies and Management*. 4(2), 83-87.
- U.S. International Trade Commission USITC (2009). Sub-Sahara Africa: Effect of Infrastructure Condition on Export Competitiveness, Third annual report, USITC Publication.
- Usman, S. (2010). The First Implementation Plan (2010-2013). Validation Workshop of the First Four Year Implementation Plan for the Nigeria Vision 20:2020. Eko Hotel and Suite, Lagos.
- Vaziri, K., Carr, P. G., Nozicck, L. K. (2007). Project Planning for Construction under Uncertainty with Limited Resources. *Journal of Construction Engineering and Management*. 133(4), 268-275.
- Wang, M., Chou, H. (2003). Risk Allocation and Risk Handling of Highway Projects in Taiwan. *Journal of Management and Engineering*. 19(2), 60-68.
- Wang, S.Q., Dulaimi, M.F., Aguirra, M.Y. (2004). Risk Management Framework for Construction Projects in Developing Countries. *Construction Management and Economics*. 22, 237-252.
- Wang, Y-M., Lee, H-S. (2007). Generalizing TOPSIS for Multiple- Criteria Group Decision –Making. *Computers and Mathematics with Applications*. 53, 1762-1772.
- Wang, J., Yuan, H (2011). Factors Affecting Contractors' Risk Attitudes in Construction Projects: Case study from China. *International Journal of Project Management*. 29(2), 209–219.
- Wang, Y. M., Chin K. S. (2011).Fuzzy Analytic Hierarchy Process: A Logarithmic Fuzzy Preference Programming Methodology. *International Journal of Approximate Reasoning*. 52, 541–553.
- Wiguna, P. I., Scott, S. (2006). Relating Risk to Project Performance in Indonesian Building Contracts. *Construction Management and Economics*. 24(11), 1125-1135.
- Williams, T. M. (1996). “The Two-dimensionality of Project Risk.”. *International Journal of Project Management*. 14(3), 185–186.

- Windapo, A.O., Martins, O.O. (2006). Relationship between Risk Management Practices and Project Performance in Nigeria Property Development Companies. *The Professional Builder*. 34-39.
- Wong, C.H., Holt, G.D. (2003). "Developing a Contractor Classification Model using a Multivariate Discriminate Analysis Approach". *RICS Foundation Research Paper Series*. 4 (20), 1-23.
- Wong, J. T. Y., Hui, E. C. M. (2006). Construction Project Risks: Further Considerations for Constructors" Pricing in Hong Kong. *Construction Management and Engineering*. 24, 425-438.
- World Bank Report (2011). World Development Indicators database, available at: http://ddpext.worldbank.org/ext/ddpreports/ViewSharedReport?&CF=&REPORT_ID=9147&REQUEST_TYPE=VIEWADVANCED&HF=N/CP.Pr ofile.asp&WSP=N. Accessed on 15th December, 2014
- Wyk, R. V., Bowen, P., Akintoye, A. (2008). Project Risk Management Practice: The Case of a South African utility company. *International Journal of Project Management*. 26(2), 149-163.
- Xia, B., Chan, A.P.C. (2012). Measuring Complexity for Building Projects: Adelphi Study. *Engineering Construction and Architectural Management*, 19(1), 7-24.
- Xiano, H.; Proverbs, D. (2005), "Factors Influencing Contractors Performance: an International Investigation". *Engineering, Construction and Architectural Management*. 10 (5), 322-32.
- Xu, Y., Chan, A.P.C., Yeung, J. F. Y. (2010). Developing a Fuzzy Allocation Model for PPP Projects in China. *Journal of Construction Engineering and Management*. 136, 894-903.
- Xu, Y., Yeung, J. F. Y., Chan, A. P. C., Chan, D. W., Wang S. Q., Ke, Y. (2010). Developing a Risk Assessment Model for PPP Projects in China - A fuzzy Synthetic Evaluation Approach. *Automation in Construction*. 929- 943.
- Yahaya, M.I, (2008). Developing a Model for Vision-Based Progress Measurement and Visualisation of As-Built Construction Operations. Ph.D Thesis, Heriot-Watt University.
- Yang, I.T. (2008). Distribution-free Monte Carlo simulation: Premise and Refinement. *Journal of Construction Engineering Management*. 134, 352-360.

- Ye, S., Tiong, R. L. K. (2000). NPV-AT- Risk method in Infrastructure Project Investment Evaluation. ASCE. *Journal of Construction Engineering and Management*. 126 (3), 227–236.
- Yin, R.K. (2009). *Case Study Research Design and Methods. Applied Social Research Methods Series volume 5*. (4th Ed.). London: Thousand Oaks, Sage Publications.
- Yirenkyi-Fianko, A. B., Chileshe, N. (2015). An Analysis of Risk Management in Practice: the Case of Ghana's Construction Industry. *Journal of Engineering, Design and Technology*. 13(2), 240-259.
- Yong, Y.C., Mustafa, N. E., (2012). "Analysis of Factors Critical to Construction Project Success in Malaysia". *Engineering, Construction and Architectural Management*. 19 (5), 543-556 [http:// dx.doi.org/10.1108/09699981211259612](http://dx.doi.org/10.1108/09699981211259612)
- Yusof, S., Aspinwall, E. (2000). Total Quality Management Implementation Frameworks: Comparison and Review. *Total Quality Management*. 11(3), 281-294.
- Zadeh, L. A (1975). The Concept of a Linguistic Variable and its Application to Approximate Reasoning. *Information Science*. 8, 199-249.
- Zayed, T., Amer, M., Pan, J. (2008). Assessing Risk and Uncertainty Inherent in Chinese Highway Projects using AHP. *International Journal of Project Management*. 26, 408-419.
- Zayed, T., Liu, Y. (2014)."Cash Flow Modeling for Construction Projects", *Engineering, Construction and Architectural Management*. 21 (2), 170-189.
- Zanakis, S.H., Solomon, A., Wishart, N., Dublisch, S. (1998). Multi-attribute Decision Making: A Simulation Comparison of Selection Methods. *European Journal of Operational Research*. 107, 507-529.
- Zeng, J., An, M., Smith, N. J. (2007). Application of a Fuzzy Based Decision Making Methodology to Construction Project Risk Assessment. *International Journal of Project Management*. 25,589-600.
- Zhang, H (2007). A redefinition of the Project Risk Process: Using Vulnerability to open up the Event Consequence Link. *International Journal of Project Management*. 25, 694-701.

- Zhang, G., Zou, P. X. W. (2007). Fuzzy Analytical Hierarchy Process Risk Assessment Approach for Joint Venture Construction Projects in China. *Journal of Construction Engineering and Management*, ASCE/October, 771-779.
- Zou, P. X., Chen, Y., Chan, T. (2010). Understanding and Improving your Risk Management Capability: Assessment Model for Construction Organisations. *Journal of Construction Engineering and Management*. ASCE/August, 854-863.