



3-16-2010

Use of Parthenolide Derivatives as Antileukemic and Cytotoxic Agents

Peter A. Crooks

University of Kentucky, pcrooks@uky.edu

Craig T. Jordan

University of Kentucky, jordan.craig@uky.edu

Xiaochen Wei

University of Kentucky, twei@uky.edu

Right click to open a feedback form in a new tab to let us know how this document benefits you.

Follow this and additional works at: https://uknowledge.uky.edu/ps_patents



Part of the [Pharmacy and Pharmaceutical Sciences Commons](#)

Recommended Citation

Crooks, Peter A.; Jordan, Craig T.; and Wei, Xiaochen, "Use of Parthenolide Derivatives as Antileukemic and Cytotoxic Agents" (2010). *Pharmaceutical Sciences Faculty Patents*. 43.

https://uknowledge.uky.edu/ps_patents/43

This Patent is brought to you for free and open access by the Pharmaceutical Sciences at UKnowledge. It has been accepted for inclusion in Pharmaceutical Sciences Faculty Patents by an authorized administrator of UKnowledge. For more information, please contact UKnowledge@lsv.uky.edu.



US007678904B2

(12) **United States Patent**
Crooks et al.

(10) **Patent No.:** **US 7,678,904 B2**
(45) **Date of Patent:** ***Mar. 16, 2010**

(54) **USE OF PARTHENOLIDE DERIVATIVES AS ANTILEUKEMIC AND CYTOTOXIC AGENTS**

(75) Inventors: **Peter A. Crooks**, Nicholasville, KY (US); **Craig T. Jordan**, Rochester, NY (US); **Xiaochen Wei**, Lexington, KY (US)

(73) Assignee: **University of Kentucky**, Lexington, KY (US)

(*) Notice: Subject to any disclaimer, the term of this patent is extended or adjusted under 35 U.S.C. 154(b) by 730 days.

This patent is subject to a terminal disclaimer.

(21) Appl. No.: **11/031,315**

(22) Filed: **Jan. 7, 2005**

(65) **Prior Publication Data**

US 2005/0272716 A1 Dec. 8, 2005

(51) **Int. Cl.**

C07D 413/00 (2006.01)
C07D 411/00 (2006.01)
C07D 205/00 (2006.01)
C07D 405/00 (2006.01)
C07D 307/00 (2006.01)

(52) **U.S. Cl.** **544/153**; 544/378; 548/950; 548/526; 549/299

(58) **Field of Classification Search** 544/153, 544/378; 548/950, 526; 549/299

See application file for complete search history.

(56) **References Cited**

U.S. PATENT DOCUMENTS

2003/0125373 A1 7/2003 Nakshatri et al. 514/449
2004/0229936 A1* 11/2004 Hsieh et al. 514/450

FOREIGN PATENT DOCUMENTS

WO WO 01/45699 6/2001
WO WO 02/40017 5/2002

OTHER PUBLICATIONS

Ruangrungsi et al. STN Accession No. 1989:151284, Abstract of Journal of Natural Products, 1988, 51(6), 1220-5.*

Hwang et al. STN Accession No. 1996:592356, Abstract of Biochemical and Biophysical Research Communications, 1996, 226(3), 810-818.*

Wu et al. STN Accession No. 2001:506624 Abstract of Journal of Asian Natural Products Research, 2001, 3(2), 95-102.*

Ruangrungsi et al. STN Accession No. 1988:19252 Abstract of Journal of Natural Products, 1987, 50(5), 891-6.*

Ruangrungsi et al. Journal of Natural Products (1987), 50(5), 891-6.*

Hejchman et al. J. Med. Chem. 1995, 38, 3407-3410.*

U.S. Appl. No. 10/817,490, filed Nov. 18, 2004, Hsieh et al.
Hwang et al., "Synthesis and anti-viral activity of a series of sesquiterpene lactones and analogues in the subgenomic HCV replicon system" *Bioorganic and Medicinal Chemistry* 14: 83-91 (2006).

Cory and Cory, "Lactacystin, a proteasome inhibitor, potentiates the apoptotic effect of parthenolide, an inhibitor of NFkappaB activation, on drug-resistant mouse leukemia L1210 cells" *Anticancer Research* 2002, 22, 3805-9.

Cory and Cory, "Augmentation of apoptosis responses in p53-deficient L1210 cells by compounds directed at blocking NFkappaB activation" *Anticancer Research*, 2001, 21, 3807-11.

Gelfanov et al., "Transformation of interleukin-3-dependent cells without participation of Stat5/bcl-xL: cooperation of akt with aft/erk leads to p65 nuclear factor kappaB-mediated antiapoptosis involving c-IAP2" *Blood*, 2000, 98, 2508-17.

Kang et al., "Enhancement of 1alpha,25-dihydroxyvitamin D3-induced differentiation of human leukaemia HL-60 cells into monocytes by parthenolide via inhibition of NF-kappaB activity" *Brit. J. Pharmacol.* 2002, 135, 1235-44.

(Continued)


Primary Examiner—D. Margaret Seaman

Assistant Examiner—Nizal S Chandrakumar

(74) *Attorney, Agent, or Firm*—Merchant & Gould

(57) **ABSTRACT**

The present invention provides compounds of the formula (I)



(I)

wherein:

X₁, X₂ and X₃ are heteroatoms;

R₄, R₅, R₆, R₇, R₈, R₉ and R₁₀ are independently selected from H, halo, —OH, —NO₂, —CN and optionally substituted aliphatic, cycloalkyl, heterocycloalkyl, aryl or heteroaryl; and

Z is optionally substituted C₁₋₈ straight-chained or branched aliphatic, optionally containing 1 or more double or triple bonds, wherein one or more carbons are optionally replaced by R* wherein R* is optionally substituted cycloalkyl, heterocycloalkyl, aryl or heteroaryl; an amino acid residue, H, —CN, —C(O)—, —C(O)C(O)—, —C(O)NR¹—, —C(O)NR¹NR²—, —C(O)O—, —OC(O)—, —NR¹CO₂—, —O—, —NR¹C(O)NR²—, —OC(O)NR¹—, —NR¹NR²—, —NR¹C(O)—, —S—, —SO—, —SO₂—, —NR¹—, —SO₂NR¹—, —NR¹R², or —NR¹SO₂—, wherein R¹ and R² are independently selected from H and optionally substituted aliphatic, cycloalkyl, heterocycloalkyl, aryl or heteroaryl; or where R* is NR¹R², R¹ and R² optionally together with the nitrogen atom form an optionally substituted 5-12 membered ring, said ring optionally comprising 1 or more heteroatoms or a group selected from —CO—, —SO—, —SO₂— and —PO—; or

a pharmaceutically acceptable salt, ester or prodrug thereof.

OTHER PUBLICATIONS

Song et al., "A new sesquiterpene lactone from *Tsoongiodendron odoratum* chun" *J. Asian. Nat. Prod. Res.* 2001, 3, 285-91.
Wen et al., "Oxidative stress-mediated apoptosis" *J. Biol. Chem.* 2002, 277, 38954-38964.
Calvet et al., 2002, *Arkivoc* 2002(v) 189-195, "Diastereoselective thiol conjugate addition on δ -alkylated- γ -silylated- α , β -unsaturated- δ -lactones".
Martinelli et al., 2002, *Tetrahedron Letters*, 43:3365-3367, "Reaction of cryptophycin 52 with thiols".
Jha and Joshi, 2002 *Arkivoc* 2002(vii) 167-196, "Catalytic, enantioselective Michael addition reactions".
Allen et al. (1964) "The Thermal Reversibility of the Michael Reaction" *Can. J. Chem.*, 42 2616-2620.

European Supplementary Search Report dated Dec. 29, 2008 in related European Patent Application 04777849.3.

Ruangrungsi et al. (1988) "Constituents of *Michelia rajaniana*. Two new germacranolide amides" *J. of Natural Products* 51:(6):1220-1225.

Ruangrungsi et al. (1987) "Constituents of *Paramichelia baillonii*: a New Antitumor Germacranolide Alkaloid" *J. of Natural Products* 50:(5):891-896.

U.S. Appl. No. 60/459,769, filed Apr. 2, 2003, Hsieh et al.

Neelakantan, et al. (2009) *Bioorganic & Medicinal Chemistry Letters* "Aminoparthenolides as novel anti-leukemic agents: discovery of the NF- κ B inhibitor, DMAPT (LC-1)" preprint of approved article to be published in 2009.

* cited by examiner




FIGURE I




FIGURE 2




FIGURE 3




FIGURE 4




FIGURE 5





FIGURE 6



μM
FIGURE 7




FIGURE 8




FIGURE 9




FIGURE 10




FIGURE 1)




FIGURE 12

1

USE OF PARTHENOLIDE DERIVATIVES AS ANTI-LEUKEMIC AND CYTOTOXIC AGENTS

This application claims priority to U.S. application Ser. No. 10/888,274 which was filed, Jul. 9, 2004, and Provisional Application 60/486,171 filed Jul. 11, 2003.


FIELD OF THE INVENTION

The present invention relates to methods for the structural modification of the sesquiterpene lactone, parthenolide, and the use of these parthenolide derivatives in the treatment of carcinoma. More specifically, the invention relates to the methods to prepare structural analogs of the parent compound, parthenolide, in order to obtain new, pharmacologically active chemical entities with improved water solubility characteristics, and to use them in the treatment of leukemias and other parental and multi-drug resistant cancers.

BACKGROUND OF THE INVENTION

Sesquiterpene lactones are a group of secondary plant metabolites consisting of a 15-carbon structure containing an α -methylene- γ -butyrolactone moiety and other additional functional groups. Over the last two to three decades, these terpenoids have received considerable attention due to the broad spectrum of their biological activities, to the plants which produce them, and most importantly, because of their pharmacological effects in humans. About 4,000 of these terpenoids have been isolated and identified, most of them in Asteraceae (Compositae, sunflower family) (Schmidt, *Curr. Org. Chem.* 1999, 3, 577-608). Some of these plants have been used for centuries in indigenous medical practices in various cultures worldwide.

Parthenolide (1) is a Germacrane sesquiterpene lactone with a unique structure. It has been isolated from several different species in Asteraceae (Compositae) family, feverfew (*Tanacetum parthenium*) being one of them.



Feverfew has been used to reduce fever and pain and in the treatment of migraine and rheumatoid arthritis (Heptinstall et al., ACS Symposium Series (1998), 691 (Phytochemicals of Europe), 158-175.). The active component is parthenolide (1). Recently, it has been revealed that parthenolide (1) can induce tumor apoptosis by the inhibition of NF- κ B activities (Cory et al., *Anticancer Research* 2002, 22, 3805-9; Cory et al., *Anticancer Research* 2001, 21, 3807-11; Gelfanov et al., *Blood*, 2000, 98, 2508-17; Kang et al., *Brit. J. Pharmacol.* 2002, 135, 1235-44; Song et al., *J. Asian. Nat. Prod. Res.* 2001, 3, 285-91).


Parthenolide (1) is a lipophilic, neutral lactone with low polarity, and has a low water-solubility, limiting its develop-

2

ment as a therapeutic agent. Thus, a need exists for the development of soluble parthenolide derivatives that retain their anti-cancer activity.

SUMMARY OF THE INVENTION

In accordance with the present invention, a novel class of compounds with antileukemic activity is presented. Accordingly, the present invention provides compounds of formula (I):



wherein:

X₁, X₂ and X₃ are heteroatoms;

R₄, R₅, R₆, R₇, R₈, R₉ and R₁₀ are independently selected from H, halo, —OH, —NO₂, —CN and optionally substituted aliphatic, cycloalkyl, heterocycloalkyl, aryl or heteroaryl; and

Z is optionally substituted C₁₋₈ straight-chained or branched aliphatic, optionally containing 1 or more double or triple bonds, wherein one or more carbons are optionally replaced by R* wherein R* is optionally substituted cycloalkyl, heterocycloalkyl, aryl or heteroaryl; an amino acid residue, H, —CN, —C(O)—, —C(O)C(O)—, —C(O)NR¹—, —C(O)NR¹NR²—, —C(O)O—, —OC(O)—, —NR¹CO₂—, —O—, —NR¹C(O)NR²—, —OC(O)NR¹—, —NR¹NR²—, —NR¹C(O)—, —S—, —SO—, —SO₂—, —NR¹—, —SO₂NR¹—, —NR¹R², or —NR¹SO₂—, wherein R¹ and R² are independently selected from H and optionally substituted aliphatic, cycloalkyl, heterocycloalkyl, aryl or heteroaryl; or where R* is NR¹R², R¹ and R² optionally together with the nitrogen atom form an optionally substituted 5-12 membered ring, said ring optionally comprising 1 or more heteroatoms and/or a group selected from —CO—, —SO—, —SO₂— and —PO—; or

a pharmaceutically acceptable salt, ester or prodrug thereof.

The invention also provides a pharmaceutical composition comprising an effective amount of a compound of formula (I), or a pharmaceutically acceptable salt, ester or prodrug thereof, in combination with a pharmaceutically acceptable diluent or carrier.

The invention also provides a method of inhibiting cancer cell growth and metastasis of cancer cells, comprising administering to a mammal afflicted with cancer, an amount of a compound of formula (I), effective to inhibit the growth of said cancer cells.

The invention also provides a method comprising inhibiting cancer cell growth by contacting said cancer cell in vitro or in vivo with an amount of a compound of formula (I), effective to inhibit the growth of said cancer cell.

The invention also provides a compound of formula (I) for use in medical therapy (preferably for use in treating cancer, e.g. solid tumors), as well as the use of such compound for the manufacture of a medicament useful for the treatment of cancer and other diseases/disorders described herein.

The invention further provides methods of treating inflammatory diseases and disorders, including, for example, rheumatoid arthritis, osteoarthritis, allergies (such as asthma), and other inflammatory conditions, such as pain (such as migraine), swelling, fever, psoriasis, inflammatory bowel disease, gastrointestinal ulcers, cardiovascular conditions, including ischemic heart disease and atherosclerosis, partial brain damage caused by stroke, skin conditions (eczema, sunburn, acne), leukotriene-mediated inflammatory diseases of lungs, kidneys, gastrointestinal tract, skin, prostatitis and paradontosis.

The invention further provides methods of treating immune response disorders, whereby the immune response is inappropriate, excessive or lacking. Such disorders include allergic responses, transplant rejection, blood transfusion reaction, and autoimmune disorders such as systemic lupus erythematosus and rheumatoid arthritis.

BRIEF DESCRIPTION OF THE DRAWINGS

FIG. 1 shows the effectiveness of parthenolide and derivatives of the present invention against prostate cancer cell line CWR22 in a clonogenic assay.

FIG. 2 shows the effectiveness of parthenolide and derivatives of the present invention against lung cancer cell line A-549 in a cellular proliferation MTS-PMS assay.

FIG. 3 shows the effectiveness of parthenolide and derivatives of the present invention against lung cancer cell line H-522 in a cellular proliferation MTS-PMS assay.

FIG. 4 shows the effectiveness of parthenolide and derivatives of the present invention against lung cancer cell line H-23 in a cellular proliferation MTS-PMS assay.

FIG. 5 shows the effectiveness of parthenolide and derivatives of the present invention against lung cancer cell line H-460 in a cellular proliferation MTS-PMS assay.

FIG. 6 shows the effectiveness of parthenolide and derivatives of the present invention against breast cancer cell line HBL-100 in a clonogenic assay.

FIG. 7 shows the effectiveness of parthenolide and derivatives of the present invention against breast cancer cell line MD-231 in a clonogenic assay.

FIG. 8 shows the effectiveness of parthenolide and derivatives of the present invention against breast cancer cell line MD-436 in a clonogenic assay.

FIG. 9 shows parthenolide and DMAPT plasma concentrations at one hour following oral gavage in mice.

FIG. 10 shows DMAPT dose-dependent inhibition of NF- κ B DNA binding in two transitional cell carcinoma cell lines HT-1376 and UMUC-3 in electrophoretic mobility gel shift assay (EMSA).

FIG. 11 shows FSCScan analysis of TRAIL induced apoptosis assay using MDA-MB-231 breast cancer cells treated first with DMAPT, then TRAIL-RII-activating antibodies.

FIG. 12 shows FSCScan analysis of TRAIL induced apoptosis assay using MDA-MB-231 breast cancer cells treated first with DMAPT, then TRAIL.

DETAILED DESCRIPTION OF THE INVENTION

As used herein, the following definitions shall apply unless otherwise indicated.

The phrase "optionally substituted" is used interchangeably with the phrase "substituted or unsubstituted." Unless otherwise indicated, an optionally substituted group may have a substituent at each substitutable position of the group, and each substitution is independent of any other. Also, combinations of substituents or variables are permissible only if

such combinations result in stable compounds. In addition, unless otherwise indicated, functional group radicals are independently selected. Where "optionally substituted" modifies a series of groups separated by commas (e.g., "optionally substituted A, B or C"; or "A, B or C optionally substituted with"), it is intended that each of the groups (e.g., A, B and C) is optionally substituted.

The term "aliphatic" or "aliphatic group" as used herein means a straight-chain or branched C₁₋₁₂ hydrocarbon chain that is completely saturated or that contains one or more units of unsaturation, or a monocyclic C₃₋₈ hydrocarbon or bicyclic C₈₋₁₂ hydrocarbon that is completely saturated or that contains one or more units of unsaturation, but which is not aromatic (also referred to herein as "carbocycle" or "cycloalkyl"), that has a single point of attachment to the rest of the molecule wherein any individual ring in said bicyclic ring system has 3-7 members. For example, suitable aliphatic groups include, but are not limited to, linear or branched or alkyl, alkenyl, alkynyl groups and hybrids thereof such as (cycloalkyl)alkyl, (cycloalkenyl)alkyl or (cycloalkyl)alk-enyl.

The terms "alkyl," "alkoxy," "hydroxyalkyl," "alkoxy-alkyl" and "alkoxycarbonyl," used alone or as part of a larger moiety include both straight and branched chains containing one to twelve carbon atoms. The terms "alkenyl" and "alkynyl" used alone or as part of a larger moiety shall include both straight and branched chains containing two to twelve carbon atoms.

The terms "haloalkyl," "haloalkenyl" and "haloalkoxy" means alkyl, alkenyl or alkoxy, as the case may be, substituted with one or more halogen atoms. The term "halogen" or "halo" means F, Cl, Br or I.

The term "heteroatom" means nitrogen, oxygen, or sulfur and includes any oxidized form of nitrogen and sulfur, and the quaternized form of any basic nitrogen. Heteroatom further includes Se, Si and P.

The term "aryl" used alone or in combination with other terms, refers to monocyclic, bicyclic or tricyclic carbocyclic ring systems having a total of five to fourteen ring members, wherein at least one ring in the system is aromatic and wherein each ring in the system contains 3 to 8 ring members. The term "aryl" may be used interchangeably with the term "aryl ring". The term "aralkyl" refers to an alkyl group substituted by an aryl. The term "aralkoxy" refers to an alkoxy group substituted by an aryl.

The term "heterocycloalkyl," "heterocycle," "heterocyclyl" or "heterocyclic" as used herein means monocyclic, bicyclic or tricyclic ring systems having five to fourteen ring members in which one or more ring members is a heteroatom, wherein each ring in the system contains 3 to 7 ring members and is non-aromatic.

The term "heteroaryl," used alone or in combination with other terms, refers to monocyclic, bicyclic and tricyclic ring systems having a total of five to fourteen ring members, and wherein: 1) at least one ring in the system is aromatic; 2) at least one ring in the system contains one or more heteroatoms; and 3) each ring in the system contains 3 to 7 ring members. The term "heteroaryl" may be used interchangeably with the term "heteroaryl ring" or the term "heteroaromatic". Examples of heteroaryl rings include 2-furanyl, 3-furanyl, N-imidazolyl, 2-imidazolyl, 4-imidazolyl, 5-imidazolyl, 3-isoxazolyl, 4-isoxazolyl, 5-isoxazolyl, 2-oxadiazolyl, 5-oxadiazolyl, 2-oxazolyl, 4-oxazolyl, 5-oxazolyl, 1-pyrrolyl, 2-pyrrolyl, 3-pyrrolyl, 1-pyrazolyl, 3-pyrazolyl, 4-pyrazolyl, 2-pyridyl, 3-pyridyl, 4-pyridyl, 2-pyrimidyl, 4-pyrimidyl, 5-pyrimidyl, 3-pyridazinyl, 2-thiazolyl, 4-thiazolyl, 5-thiazolyl, 5-tetrazolyl, 2-triazolyl, 5-triazolyl, 2-thienyl,

5

3-thienyl, carbazolyl, benzimidazolyl, benzothienyl, benzofuranyl, indolyl, quinolinyl, benzotriazolyl, benzothiazolyl, benzooxazolyl, benzimidazolyl, isoquinolinyl, indazolyl, isindolyl, acridinyl, and benzisoxazolyl. The term "heteroaralkyl" refers to an alkyl group substituted by a heteroaryl. The term "heteroarylalkoxy" refers to an alkoxy group substituted by a heteroaryl.

An aryl (including aralkyl, aralkoxy, aryloxyalkyl and the like) or heteroaryl (including heteroaralkyl, heteroarylalkoxy and the like) group may contain one or more substituents. Suitable substituents on an unsaturated carbon atom of an aryl, heteroaryl, aralkyl or heteroaralkyl group are selected from halogen; haloalkyl; $-\text{CF}_3$; $-\text{R}$; $-\text{OR}$; $-\text{SR}$; 1,2-methylenedioxy; 1,2-ethylenedioxy; protected OH (such as acyloxy); phenyl (Ph); Ph substituted with R; $-\text{O}(\text{Ph})$; $-\text{O}(\text{Ph})$ substituted with R; $-\text{CH}_2(\text{Ph})$; $-\text{CH}_2(\text{Ph})$ substituted with R; $-\text{CH}_2\text{CH}_2(\text{Ph})$; $-\text{CH}_2\text{CH}_2(\text{Ph})$ substituted with R; $-\text{NO}_2$; $-\text{CN}$; $-\text{N}(\text{R})_2$; $-\text{NRC}(\text{O})\text{R}$; $-\text{NRC}(\text{O})\text{N}(\text{R})_2$; $-\text{NRCO}_2\text{R}$; $-\text{NRNRC}(\text{O})\text{R}$; $-\text{NR}-\text{NRC}(\text{O})\text{N}(\text{R})_2$; $-\text{NRNRCO}_2\text{R}$; $-\text{C}(\text{O})\text{C}(\text{O})\text{R}$; $-\text{C}(\text{O})\text{CH}_2\text{C}(\text{O})\text{R}$; $-\text{CO}_2\text{R}$; $-\text{C}(\text{O})\text{R}$; $-\text{C}(\text{O})\text{N}(\text{R})_2$; $-\text{OC}(\text{O})\text{N}(\text{R})_2$; $-\text{S}(\text{O})_2\text{R}$; $-\text{SO}_2\text{N}(\text{R})_2$; $-\text{S}(\text{O})\text{R}$; $-\text{NRSO}_2\text{N}(\text{R})_2$; $-\text{NRSO}_2\text{R}$; $-\text{C}(\text{=S})\text{N}(\text{R})_2$; $-\text{C}(\text{=NH})-\text{N}(\text{R})_2$; $-(\text{CH}_2)_y\text{NHC}(\text{O})\text{R}$; $-(\text{CH}_2)_z\text{R}$; $-(\text{CH}_2)_y\text{NHC}(\text{O})\text{NHR}$; $-(\text{CH}_2)_y\text{NHC}(\text{O})\text{OR}$; $-(\text{CH}_2)_y\text{NHS}(\text{O})\text{R}$; $-(\text{CH}_2)_y\text{NH}\text{SO}_2\text{R}$; or $-(\text{CH}_2)_y\text{NHC}(\text{O})\text{CH}(\text{V})_z-\text{R}(\text{R})$ wherein each R is independently selected from hydrogen, optionally substituted C_{1-6} aliphatic, an unsubstituted 5-6 membered heteroaryl or heterocyclic ring, phenyl (Ph), $-\text{O}(\text{Ph})$, or $-\text{CH}_2(\text{Ph})-\text{CH}_2(\text{Ph})$, wherein y is 0-6; z is 0-1; and V is a linker group. When R is C_{1-6} aliphatic, it may be substituted with one or more substituents selected from $-\text{NH}_2$, $-\text{NH}(\text{C}_{1-4}$ aliphatic), $-\text{N}(\text{C}_{1-4}$ aliphatic) $_2$, $-\text{S}(\text{O})(\text{C}_{1-4}$ aliphatic), $-\text{SO}_2(\text{C}_{1-4}$ aliphatic), halogen, $(\text{C}_{1-4}$ aliphatic), $-\text{OH}$, $-\text{O}(\text{C}_{1-4}$ aliphatic), $-\text{NO}_2$, $-\text{CN}$, $-\text{CO}_2\text{H}$, $-\text{CO}_2(\text{C}_{1-4}$ aliphatic), $-\text{O}(\text{halo } \text{C}_{1-4}$ aliphatic), or $-\text{halo}(\text{C}_{1-4}$ aliphatic); wherein each C_{1-4} aliphatic is optionally.

An aliphatic group or a non-aromatic heterocyclic ring may contain one or more substituents. Suitable substituents on a saturated carbon of an aliphatic group or of a non-aromatic heterocyclic ring are selected from those listed above for the unsaturated carbon of an aryl or heteroaryl group and the following: $=\text{O}$, $=\text{S}$, $=\text{NNHR}$, $=\text{NN}(\text{R})_2$, $=\text{N}-$, $=\text{NNHC}(\text{O})\text{R}$, $=\text{NNHCO}_2(\text{alkyl})$, $=\text{NNHSO}_2(\text{alkyl})$, or $=\text{NR}$, where each R is independently selected from hydrogen or an optionally substituted C_{1-6} aliphatic. When R is C_{1-6} aliphatic, it may be substituted with one or more substituents selected from $-\text{NH}_2$, $-\text{NH}(\text{C}_{1-4}$ aliphatic), $-\text{N}(\text{C}_{1-4}$ aliphatic) $_2$, halogen, $-\text{OH}$, $-\text{O}(\text{C}_{1-4}$ aliphatic), $-\text{NO}_2$, $-\text{CN}$, $-\text{CO}_2\text{H}$, $-\text{CO}_2(\text{C}_{1-4}$ aliphatic), $-\text{O}(\text{halo } \text{C}_{1-4}$ aliphatic), or $-\text{halo}(\text{C}_{1-4}$ aliphatic); wherein each C_{1-4} aliphatic is optionally substituted.

Substituents on a nitrogen of a non-aromatic heterocyclic ring are selected from $-\text{R}$, $-\text{N}(\text{R})_2$, $-\text{C}(\text{O})\text{R}$, $-\text{C}(\text{O})\text{OR}$, $-\text{C}(\text{O})\text{C}(\text{O})\text{R}$, $-\text{C}(\text{O})\text{CH}_2\text{C}(\text{O})\text{R}$, $-\text{SO}_2\text{R}$, $-\text{SO}_2\text{N}(\text{R})_2$, $-\text{C}(\text{=S})\text{N}(\text{R})_2$, $-\text{C}(\text{=NH})-\text{N}(\text{R})_2$ or $-\text{NRSO}_2\text{R}$; wherein each R is independently selected from hydrogen, an optionally substituted C_{1-6} aliphatic, optionally substituted phenyl (Ph), optionally substituted $-\text{O}(\text{Ph})$, optionally substituted $-\text{CH}_2(\text{Ph})$, optionally substituted $-\text{CH}_2\text{CH}_2(\text{Ph})$, or an unsubstituted 5-6 membered heteroaryl or heterocyclic ring. When R is a C_{1-6} aliphatic group or a phenyl ring, it may be substituted with one or more substituents selected from $-\text{NH}_2$, $-\text{NH}(\text{C}_{1-4}$ aliphatic), $-\text{N}(\text{C}_{1-4}$ aliphatic) $_2$, halogen, $-\text{O}(\text{C}_{1-4}$ aliphatic), $-\text{OH}$, $-\text{O}(\text{C}_{1-4}$ aliphatic), $-\text{NO}_2$, $-\text{CN}$, $-\text{CO}_2\text{H}$, $-\text{CO}_2(\text{C}_{1-4}$ aliphatic), $-\text{O}(\text{halo } \text{C}_{1-4}$ aliphatic) or $-\text{halo}(\text{C}_{1-4}$ aliphatic); wherein each C_{1-4} aliphatic is optionally substituted.

The term "linker group" or "linker" means an organic moiety that connects two parts of a compound. Linkers

6

include alkylidene chain that is a saturated or unsaturated, straight or branched, C_{1-8} carbon chain which is optionally substituted, and wherein up to two non-adjacent saturated carbons of the chain are optionally replaced by R^* wherein R^* is $-\text{C}(\text{O})-$, $-\text{C}(\text{O})\text{C}(\text{O})-$, $-\text{C}(\text{O})\text{NR}-$, $-\text{C}(\text{O})\text{NRNR}-$, $-\text{C}(\text{O})\text{O}-$, $-\text{OC}(\text{O})-$, $-\text{NRCO}_2-$, $-\text{O}-$, $-\text{NRC}(\text{O})\text{NR}-$, $-\text{OC}(\text{O})\text{NR}-$, $-\text{NRNR}-$, $-\text{NRC}(\text{O})-$, $-\text{S}-$, $-\text{SO}-$, $-\text{SO}_2-$, $-\text{NR}-$, $-\text{SO}_2\text{NR}-$, or $-\text{NRSO}_2-$; wherein R is selected from hydrogen or optionally substituted aliphatic, cycloalkyl, heterocycloalkyl, aryl or heteroaryl, and preferably H or optionally substituted C_{1-4} aliphatic. Optional substituents on the alkylidene chain are as described above for an aliphatic group. Alternatively, the linker group is R^* .

The term "treatment" refers to any treatment of a pathologic condition in a mammal, particularly a human, and includes: (i) preventing the pathologic condition from occurring in a subject which may be predisposed to the condition but has not yet been diagnosed with the condition and, accordingly, the treatment constitutes prophylactic treatment for the disease condition; (ii) inhibiting the pathologic condition, i.e., arresting its development; (iii) relieving the pathologic condition, i.e., causing regression of the pathologic condition; or (iv) relieving the conditions mediated by the pathologic condition.

The term "therapeutically effective amount" refers to that amount of a compound of the invention that is sufficient to effect treatment, as defined above, when administered to a mammal in need of such treatment. The therapeutically effective amount will vary depending upon the subject and disease condition being treated, the weight and age of the subject, the severity of the disease condition, the manner of administration and the like, which can readily be determined by one of ordinary skill in the art.

The term "pharmaceutically acceptable salts" includes, but is not limited to, salts well known to those skilled in the art, for example, mono-salts (e.g. alkali metal and ammonium salts) and poly salts (e.g. di- or tri-salts,) of the compounds of the invention. Pharmaceutically acceptable salts of compounds of formulas (I), (II), (III), or (IV) are where, for example, an exchangeable group, such as hydrogen in $-\text{OH}$, $-\text{NH}-$, or $-\text{P}(\text{=O})(\text{OH})-$, is replaced with a pharmaceutically acceptable cation (e.g. a sodium, potassium, or ammonium ion) and can be conveniently be prepared from a corresponding compound of formula (I) by, for example, reaction with a suitable base. In cases where compounds are sufficiently basic or acidic to form stable nontoxic acid or base salts, administration of the compounds as salts may be appropriate. Examples of pharmaceutically acceptable salts are organic acid addition salts formed with acids that form a physiological acceptable anion, for example, tosylate, methanesulfonate, acetate, citrate, malonate, tartarate, succinate, benzoate, ascorbate, α -ketoglutarate, and α -glycerophosphate. Suitable inorganic salts may also be formed, including hydrochloride, sulfate, nitrate, bicarbonate, and carbonate salts.

Pharmaceutically acceptable salts include quaternary ammonium salts formed with $\text{R}'\text{Y}$; where Y is selected from halogen, tosylate, methanesulfonate, benzenesulfonate, trifluoromethanesulfonate and the like; and R' is selected from an optionally substituted cycloalkyl, heterocycloalkyl, aryl or heteroaryl.

Suitable acids include hydrofluoric acid, hydrochloric acid, hydrobromic acid, hydriodic acid, sulfuric acid, nitric acid, phosphoric acid, carbonic acid, boric acid, selenious acid, hydrogen sulfide, phosphomolybdic acid, phosphorous acid, sulfurous acid, citric acid, maleic acid, D-malic acid, L-lactic acid, D-lactic acid, DL-lactic acid, oxalic acid, methanesulfonic acid, valeric acid, oleic acid, lauric acid, paratoluenesulfonic acid, 1-naphthalenesulfonic acid, 2-naphthalenesulfonic acid, phthalic acid, tartaric acid, L-malic acid,

7

DL-malic acid, malonic acid, succinic acid, fumaric acid, glycolic acid, thioglycolic acid, glycine, sarcosine, sulfonic acid, nicotinic acid, picolinic acid, isonicotinic acid, benzoic acid and substituted benzoic acid where benzene ring bears one or more substituents.

Pharmaceutically acceptable salts may be obtained using standard procedures well known in the art, for example, by reacting a sufficiently basic compound such as an amine with a suitable acid affording a physiologically acceptable anion. Alkali metal (for example, sodium, potassium or lithium) or alkaline earth metal (for example, calcium) salts of carboxylic acids can also be made.


The term "prodrug" or "prodrugs" is used in its ordinary meaning in the art and means a compound of the invention that has its charged moieties masked or protected by another moiety that is designed to be cleaved under particular physiological conditions, leaving the deprotected or unmasked compound of the invention. The use of masking agents is common and well-known in the art and, in particular, masking phosphate or phosphonate groups. All such masking agents are suitable and can be used with the compounds of the invention. Various agents such as acyloxy alkyl esters are described by Srivasta et al., (1984 *Bioorganic Chemistry* 12, 118-12), and by Freeman et al. (1997 *Progress in Medicinal Chemistry* 34:112-147) which are each incorporated in their entirety herein by reference; and 3-phthalidyl phosphonate esters are described by Dang Q., et al., (1999 *Bioorganic & Med. Chem Letters*, 9:1505-1510), which is incorporated in its entirety herein by reference. For example, and not by way of limitation, Srivasta et al. also describe acetoxymethyl, isobutyloxymethyl, and pivaloxymethyl as masking agents. Other suitable masking groups comprising pivaloxyalkyl, e.g., pivaloxymethyl, or a pivaloxyloxy group as described by Farquhar D. et al., (1995 *J. Med. Chem.*, 38:488-495) which is incorporated in its entirety herein by reference. Still other masking or protecting agents are described in U.S. Pat. Nos. 4,816,570 and 4,968,788 both of which are incorporated in their entirety herein by reference. Lipid prodrugs are also suitable for use with the compounds of the invention. By non-limiting example, certain lipid prodrugs are described in Hostetler et al., (1997 *Biochem. Pharm.* 53:1815-1822), and Hostetler et al., 1996 *Antiviral Research* 31:59-67), both of which are incorporated in their entirety herein by reference. Additional examples of suitable prodrug technology is described in WO 90/00555; WO 96/39831; WO 03/095665A2; U.S. Pat. Nos. 5,411,947; 5,463,092; 6,312,662; 6,716,825; and U.S. Pat. Published Patent Application Nos. 2003/0229225 and 2003/0225277 each of which is incorporated in their entirety herein by reference. Such prodrugs may also possess the ability to target the drug compound to a particular tissue within the patient, e.g., liver, as described by Erion et al., (2004 *J. Am. Chem. Soc.* 126:5154-5163; Erion et al., *Am. Soc. Pharm. & Exper. Ther. DOI:10.1124/jcpt.104.75903* (2004); WO 01/18013 A1; U.S. Pat. No. 6,752,981), each of which is incorporated in their entirety herein by reference. By way of non-limiting example, other prodrugs suitable for use with the compounds of the invention are described in WO 03/090690; and by Harris et al., (2002 *Antiviral Chem & Chemo.* 12: 293-300; Knaggs et al., 2000 *Bioorganic & Med. Chem Letters* 10: 2075-2078) each of which is incorporated in their entirety herein by reference.

The invention relates to the ability of the α -methylene- γ -butyrolactone moiety in sesquiterpene lactones to be structurally modified by, for example, Michael addition with amines or thiols. Modification of the parthenolide (1) molecule by this methodology using primary and/or secondary amines to form water-soluble amino derivatives, affords amine adducts that can easily be obtained as different inorganic or organic salts to further increase water solubility. Thus, a novel class of more water-soluble parthenolide ana-

8

logs is described. When compounds in this class were evaluated for antileukemic activity, it was found that these compounds were either equipotent as, or more potent than the parent compound, parthenolide. More importantly, these novel analogs showed greater cytotoxicity towards leukemia cells than towards normal cells. Thus, the present invention provides a new class of parthenolide derivatives with potent and selective anticancer activities.

In accordance with the present invention, there are provided compounds of formula (I):



wherein:

X₁, X₂ and X₃ are heteroatoms;

R₄, R₅, R₆, R₇, R₈, R₉ and R₁₀ are independently selected from H, halo, —OH, —NO₂, —CN and optionally substituted aliphatic, cycloalkyl, heterocycloalkyl, aryl or heteroaryl; and

Z is optionally substituted C₁₋₈ straight-chained or branched aliphatic, optionally containing 1 or more double or triple bonds, wherein one or more carbons are optionally replaced by R* wherein R* is optionally substituted cycloalkyl, heterocycloalkyl, aryl or heteroaryl; an amino acid residue, H, —CN, —C(O)—, —C(O)C(O)—, —C(O)NR¹—, —C(O)NR¹NR²—, —C(O)O—, —OC(O)—, —NR¹CO₂—, —O—, —NR¹C(O)NR²—, —OC(O)NR¹—, —NR¹NR²—, —NR¹C(O)—, —S—, —SO—, —SO₂—, —NR¹—, —SO₂NR¹—, —NR¹R², or —NR¹SO₂—, wherein R¹ and R² are independently selected from H and optionally substituted aliphatic, cycloalkyl, heterocycloalkyl, aryl or heteroaryl; or where R* is NR¹R², R¹ and R² optionally together with the nitrogen atom form an optionally substituted 5-12 membered ring, said ring optionally comprising 1 or more heteroatoms and/or a group selected from —CO—, —SO—, —SO₂— and —PO—; or

a pharmaceutically acceptable salt, ester or prodrug thereof.

Presently preferred compounds include compounds of formula (I) wherein R₅, R₆, R₇, R₉ and R₁₀ are independently selected from H, halo, —OH, —NO₂, —CN, —CH₃, —CF₃, —CH₂CH₃, —CH₂CF₃, —CH₂Cl, —CH₂OH, —CH₂CH₂OH and —CH₂NH₂. Further preferred embodiments include compounds where R₅, R₆, R₇, R₉ and R₁₀ are each H.

Other preferred embodiments of the present invention include compounds where R₄ and R₈ are independently selected from optionally substituted C₁₋₄ alkyl. In one preferred embodiment, R₄ is —CH₃, and in another, R₄ and R₈ are each —CH₃.

In one embodiment X₁, X₂ and X₃ are heteroatoms independently selected from O, N and S, and in one particular embodiment, X₁, X₂ and X₃ are each O.

According to one embodiment, it is preferred that where R₅, R₆, R₇, R₉ and R₁₀ are H, R₄ and R₈ are each —CH₃, and X₁, X₂ and X₃ are each O; Z is not —CH₂.

According to a further embodiment of the invention, Z is —(CH₂)_m—NR¹R² where m is an integer from 0 to 4, where preferably, R₅, R₆, R₇, R₉, and R₁₀ are H; and R₄ and R₈ are each —CH₃. In one particular embodiment, m is 1. In other embodiments, R¹ and R² are independently selected from

hydrogen, —CN or optionally substituted C₁-C₄ alkyl. In particular embodiments, R¹ and R² are independently selected from —NO₂, —CN, —CH₃, —CF₃, —CH₂CH₃, —CH₂CF₃, —CH₂Cl, —CH₂OH, —CH₂CH₂OH and —CH₂NH₂.

In yet a further embodiment, R¹ and R² together with N form an optionally substituted ring. The ring is a monocyclic, bicyclic or tricyclic aliphatic or aryl ring system, where the ring system is optionally substituted and optionally comprises one or more heteroatoms or a group selected from —CO—, —SO—, —SO₂— and —PO—. In one particular embodiment, R¹ and R² are —CH₂(CH₂)_nCH₂Y—, where Y is a heteroatom or a group selected from —CO—, —SO—, —SO₂— and —PO—; n is an integer 0 to 5; and together with N form an optionally substituted ring, which may be additionally fused to a cycloalkyl or aryl group to form a bicyclic or tricyclic ring system, where the system is optionally substituted and optionally comprises one or more heteroatoms. Alternatively, R₁ and R₂ are —(CH₂)_a—Y—(CH₂)_b—, where Y is a heteroatom or a group selected from —CO—, —SO—, —SO₂— and —PO—; a is an integer 0 to 5; b is an integer 0 to 5; where the sum of a and b is 0 to 5; and together with N form an optionally substituted ring, the ring being optionally fused to a cycloalkyl or aryl group to form a bicyclic or tricyclic ring system, where the system is optionally substituted and optionally comprises one or more heteroatoms.

Examples of ring systems include an optionally substituted uracil ring or a derivative thereof. Other examples include optionally substituted pyrrole, imidazole, purine and pyrazole and derivative thereof. Examples of fused ring systems include optionally substituted aziridin-1-yl, azetidin-1-yl, pyrrolidin-1-yl, piperidin-1-yl, homopiperidin-1-yl and heptamethyleneimin-1-yl.

According to a further embodiment of the invention, Z is —(CH₂)_m—S(O)_n—R¹ where m is an integer from 0 to 4, n is an integer from 0 to 2, where preferably, R₅, R₆, R₇, R₉, and R₁₀ are H; and R₄ and R₈ are each —CH₃. In one particular embodiment, m is 1. In another embodiment n is 0. In other embodiments, R¹ is independently selected from hydrogen, —CN, optionally substituted C₁-C₄ alkyl or aryl. In particular embodiments, R¹ is selected from —C₆H₅, —CH₂CH(CO₂H)(NH₂), and —CH₂CO₂H.

Exemplary compounds of the present invention include:

11S,11,13-Dihydro,13-dimethylaminoparthenolide (DMAPT);
 11S,11,13-Dihydro,13-diethylaminoparthenolide;
 11S,11,13-Dihydro,13-(tert-butylamino)parthenolide;
 11S,11,13-Dihydro,13-(pyrrolidin-1-yl)parthenolide;
 11S,11,13-Dihydro,13-(piperidin-1-yl)parthenolide (PIPT);
 11S,11,13-Dihydro,13-(morpholin-1-yl)parthenolide;
 11S,11,13-Dihydro,13-(4-methylpiperidin-1-yl)parthenolide (4MEPT);
 11S,11,13-Dihydro,13-(4-methylpiperazin-1-yl)parthenolide;
 11S,11,13-Dihydro,13-(homopiperidin-1-yl)parthenolide;
 11S,11,13-Dihydro,13-(heptamethyleneimin-1-yl)parthenolide;
 11S,11,13-Dihydro,13-(azetidin-1-yl)parthenolide;
 11S,11,13-Dihydro,13-methylbutyl aminoparthenolide;
 11S,11,13-Dihydro,13-methyl pentyl aminoparthenolide;
 11S,11,13-Dihydro,13-ethylaminoparthenolide;
 11S,11,13-Dihydro,13-methylaminoparthenolide;
 11S,11,13-Dihydro,13-cyclopropylaminoparthenolide;
 11S,11,13-Dihydro,13-propargylaminoparthenolide;
 11S,11,13-Dihydro,13-(N-benzyl-N-ethylamine)parthenolide;
 11S,11,13-Dihydro,13-(N-prolyl)parthenolide;
 11S,11,13-Dihydro,13-(S-thiophenol)parthenolide;
 11S,11,13-Dihydro,13-(N,N-diethanolamine)parthenolide

11S,11,13-Dihydro,13-(thiomorpholin-4-yl)parthenolide;
 11S,11,13-Dihydro,13-(4-hydroxypiperidin-1-yl)parthenolide;

11S,11,13-Dihydro,13-(1-methylhomopiperizin-4-yl)parthenolide;

11S,11,13-Dihydro,13-(S-mercaptoacetyl)parthenolide;

11S,11,13-Dihydro,13-(4-(2'-hydroxyethyl)piperidin-1-yl)parthenolide;

11S,11,13-Dihydro,13-(piperazin-1-yl-4-carboxaldehyde)parthenolide;

11S,11,13-Dihydro,13-(4-benzylpiperidin-1-yl)parthenolide;

11S,11,13-Dihydro,13-(piperidin-1-yl-4-carboxylic acid)parthenolide;

11S,11,13-Dihydro,13-(azetidin-1-yl-3-carboxylic acid)parthenolide;

11S,11,13-Dihydro,13-(S-cysteinyl)parthenolide;

11S,11,13-Dihydro,13-(4-(piperidin-1'-yl)piperidin-1-yl)parthenolide; and

11S,11,13-Dihydro,13-diallylaminoparthenolide.


Those of skill in the art will recognize that the invention comprises compounds that may contain one or more chiral centers on, for example, the parthenolide C-11 and thus can exist as racemic mixtures as pure diastereomers, or as pure enantiomers. For many applications, it is preferred to carry out stereoselective synthesis and/or to subject the reaction product to appropriate purification steps so as to produce substantially stereochemically pure or optically pure materials. Suitable stereoselective synthetic procedures for producing stereochemically pure or optically pure materials are well known in the art, as are procedures for resolving racemic mixtures into their optically pure enantiomers.

The present invention further provides for compounds having formula (I), or a pharmaceutically acceptable salt thereof, wherein Z is a group that is converted to —CH₂ under physiological conditions during or after administration to a mammalian patient, thereby yielding a methylene group. In particular embodiments X₁, X₂ and X₃ are O; R₅, R₆, R₇, R₉, and R₁₀ are H; R₄ and R₈ are —CH₃; and Z is optionally substituted C₁₋₈ straight-chained or branched aliphatic, optionally containing 1 or more double or triple bonds, wherein one or more carbons are optionally replaced by R* wherein R* is optionally substituted cycloalkyl, heterocycloalkyl, aryl or heteroaryl; an amino acid residue, H, —CN, —C(O)—, —C(O)C(O)—, —C(O)NR¹—, —C(O)NR¹NR²—, —C(O)O—, —OC(O)—, —NR¹CO₂—, —O—, —NR¹C(O)NR²—, —OC(O)NR¹—, —NR¹NR²—, —NR¹C(O)—, —S—, —SO—, —SO₂—, —NR¹—, —SO₂NR¹—, —NR¹R², or —NR¹SO₂—, wherein R¹ and R² are independently selected from H and optionally substituted aliphatic, cycloalkyl, heterocycloalkyl, aryl or heteroaryl. In preferred embodiments Z is —CH₂N(CH₃)₂, —CH₂N(H)(C(CH₃)₃), —CH₂N(CH₂CH₃)₂, —CH₂N(CH₂CH=CH₂)₂, —CH₂-azetidine, —CH₂-pyrrolidine, —CH₂-piperidine, —CH₂-homopiperidine, —CH₂-heptamethyleneimine, —CH₂-4-methylpiperidine, —CH₂-morpholine, —CH₂-pyrrolidine, —CH₂-proline, —CH₂-thiophenol, —CH₂-diethanolamine, —CH₂-hydroxypiperidine, —CH₂-methylhomopiperazine, —CH₂-thiomorpholine, —CH₂-mercaptoacetic acid, —CH₂-benzylpiperidine, —CH₂-piperidine-4-carboxylic acid, —CH₂-azetidine-3-carboxylic acid, —CH₂-piperidinylpiperidine, or —CH₂-cysteine.


The present invention further provides for compounds having formula (I), or a pharmaceutically acceptable salt thereof, wherein Z is CH₂N(CH₃)₂ which under physiological conditions during or after administration to a mammalian patient, undergoes mono- or di-demethylation; conversion to —CH₂, or cysteine or protein conjugation. In particular embodiments, X₁, X₂ and X₃ are O; R₅, R₆, R₇, R₉, and R₁₀ are H; R₄ and R₈ are —CH₃;

11

The present invention further provides compounds wherein the parthenolide based derivatives of formula (I) form dimers or duplexes with another molecule of formula (I) or with basic nitrogen-containing synergistic anticancer drug molecules such as 5-fluorouracil, cytarabine, mytomycin C, Doxorubicin and Daunorubicin. Accordingly, the present invention provides compounds of the general formula (II):




where L is a linker, as defined above, and W is a molecule with anti-cancer growth activity. Where W is another parthenolide derivative of formula (I), the present invention provides compounds of formula (III):



where R'₄, R'₅, R'₆, R'₇, R'₈, R'₉, R'₁₀, X'₁, X'₂ and X'₃ are independently as defined above for their counterparts, R₆, R₇, R₈, R₉, R₁₀, X₁, X₂ and X₃; and L is a linker, as defined above. Preferred linkers include optionally substituted alkyl and amine groups. In one particular embodiment, L is —CH₂N(R)CH₂—, where R is as defined above. Included are pharmaceutically acceptable salts formed with inorganic and/or organic acids, as defined above for compounds of formula (I).


In accordance with another embodiment of the invention, the methods for the preparation of the amino analogs described in this invention are disclosed in Schemes I and II.

Scheme I



12


Scheme II



In the above scheme, the solvent is selected from a low alkyl alcohol, such as methanol, ethanol, propanol, isopropanol, n-butanol, tert-butanol, and chloroform, methylene chloride, benzene, toluene, tetrahydrofuran, dioxane, 1,2-dimethoxyethane, pyridine, carbon tetrachloride, diethyl ether, tert-butyl methyl ether and/or the mixture of two or more of the solvents listed above. The base is selected from a low trialkylamine, such as trimethylamine, triethylamine, tripropylamine, and tributylamine, and pyridine, 2-, 3-, and 4-picolines, 2-, 3-, and 4-dimethylaminopyridines. The temperature is selected from -20° C. to 130° C. The reaction time required to effect the desired coupling reaction can vary widely, typically falling in the range of 30 min to 24 hours. Purification can be achieved by a variety of techniques, such as, liquid chromatography through neutral or basic silica gel, bonded silica gel phases such as octadecylsilica, octylsilica and the like, cellulose or alumina with the solvent such as, for example, the mixture of chloroform and methanol or ethanol, the mixture of methylene chloride and methanol or ethanol, the mixture of hexane and acetone or acetonitrile or methanol or ethanol or isopropanol, the mixture of diethyl ether and acetone or acetonitrile or methanol or ethanol or isopropanol; and recrystallization using normal organic solvent or solvent mixture, such as methanol, ethanol, propanol, isopropanol, tert-butanol, acetonitrile, diethyl ether, chloroform, methylene chloride and the mixture of two or more solvents listed above. The purity of the invention compounds prepared is assessed by mass spectrometry, nuclear magnetic resonance spectrometry (NMR) and elemental combustion analysis.

Furthermore, in accordance with still another embodiment of the present invention, the methods for the preparation of the invention salts are disclosed in Schemes III and IV.


Scheme III




In these schemes, HX is selected from hydrochloride, hydrobromide, hydroiodide, perchlorate, sulfate, hemisulfate, mesylate, toluenesulfonate, benzenesulfonate, succinate, hemisuccinate, fumarate, tartarate, ascorbate, acetate, hemifumarate, maleate, citrate, oxalate, malonate, malic, propionate and benzoate; Y^\ominus is selected from halide (fluoride, chloride, bromide, iodide), methylsulfonate, toluenesulfonate, benzenesulfonate and sulfate; and the solvent is selected from a low alkyl alcohol, such as diethyl ether, methanol, ethanol, propanol, isopropanol, n-butanol, tert-bu-

anol, and chloroform, methylene chloride, benzene, toluene, tetrahydrofuran, dioxane, 1,2-dimethoxyethane, pyridine, carbon tetrachloride, tert-butyl methyl ether, acetone and/or the mixture of two or more of the solvents listed above. The temperature is selected from -20°C . to 50°C . Purification can be achieved by recrystallization using normal organic solvent or solvent mixture, such as methanol, ethanol, acetone, propanol, isopropanol, t-butanol, acetonitrile, diethyl ether, chloroform, methylene chloride and the mixture of two or more solvents listed above.

Scheme IV




-continued




8


The present invention further provides analogues of compounds of formula (I). Examples are described below and include costunolide, dehydrocostuslactone, alantolactone, isoalantolactone, amino-3-oxo-isoalantolactone, helenalin, 11,13-dihydrohelenalin, aminocyanaropicrin, aminodesacylcyanaropicrin, (+)-aminoreynosin, aminosantamarin, aminosoulangianolide and aminoisotelekin. In addition, the present invention provides compounds of the analogues below, amino-3-oxo-isoalantolactone, aminocyanaropicrin, aminodesacylcyanaropicrin, (+)-aminoreynosin, aminosantamarin, aminosoulangianolide and aminoisotelekin wherein ($-\text{CH}_2-\text{NR}_1\text{R}_2$) is replaced by Z, where Z is as defined herein.



Dehydrocostuslactone




Alantolactone




Helenalin


-continued




Isoalantolactone



Costunolide



11, 13-Dihydrohelenalin



Aminocyanaropicrin

20

25

30

35

40

45

50


55

60


65

17


-continued




Aminodesacylcynaropicrins




(+)-Aminoreynosins




Aminosantamarins



Aminosoulangianolides



Amino-3-oxo-isoalantolactones




Aminoisotelekins

The invention relates to the ability of the α -methylene- γ -butyrolactone moiety in all the above-mentioned sesquiterpene lactones to be structurally modified by, for example, Michael addition with the following chemical entities to form more water-soluble derivatives than the corresponding parent

18

sesquiterpene, and with improved properties conducive for drug development, such as, chemical stability, reduced toxicity and oral bioavailability.

The present invention further provides compounds of the parthenolide-analog dehydrocostuslactone based derivatives of formula (IV):



Presently preferred compounds include compounds of formula (IV) wherein R_3 , R_5 , R_6 , R_9 and R_{10} are independently selected from H, halo, $-\text{OH}$, $-\text{NO}_2$, $-\text{CN}$, $-\text{CH}_3$, $-\text{CF}_3$, $-\text{CH}_2\text{CH}_3$, $-\text{CH}_2\text{CF}_3$, $-\text{CH}_2\text{Cl}$, $-\text{CH}_2\text{OH}$, $-\text{CH}_2\text{CH}_2\text{OH}$ and $-\text{CH}_2\text{NH}_2$. Further preferred embodiments include compounds where R_3 , R_5 , R_6 , R_9 and R_{10} are each H.

Other preferred embodiments of the present invention include compounds where R_4 and R_8 are independently selected from optionally substituted C_1 - C_4 alkyl. In one preferred embodiment, R_4 and R_8 are each $-\text{CH}_2$.

In one embodiment X_1 and X_2 are heteroatoms independently selected from O, N and S, and in one particular embodiment, X_1 and X_2 are each O.

According to a further embodiment of the invention, Z is $-(\text{CH}_2)_m-\text{NR}^1\text{R}^2$ where m is an integer from 0 to 4, where preferably, R_5 , R_6 , R_7 , R_9 and R_{10} are H; and R_4 and R_8 are each $-\text{CH}_3$. In one particular embodiment, m is 1. In other embodiments, R^1 and R^2 are independently selected from hydrogen, $-\text{CN}$ or optionally substituted C_1 - C_4 alkyl. In particular embodiments, R^1 and R^2 are independently selected from $-\text{NO}_2$, $-\text{CN}$, $-\text{CH}_3$, $-\text{CF}_3$, $-\text{CH}_2\text{CH}_3$, $-\text{CH}_2\text{CF}_3$, $-\text{CH}_2\text{Cl}$, $-\text{CH}_2\text{OH}$, $-\text{CH}_2\text{CH}_2\text{OH}$ and $-\text{CH}_2\text{NH}_2$.

In yet a further embodiment, R^1 and R^2 together with N form an optionally substituted ring. The ring is a monocyclic, bicyclic or tricyclic aliphatic or aryl ring system, where the ring system is optionally substituted and optionally comprises one or more heteroatoms or a group selected from $-\text{CO}-$, $-\text{SO}-$, $-\text{SO}_2-$ and $-\text{PO}-$. In one particular embodiment, R^1 and R^2 are $-\text{CH}_2(\text{CH}_2)_n\text{CH}_2\text{Y}-$, where Y is a heteroatom or a group selected from $-\text{CO}-$, $-\text{SO}-$, $-\text{SO}_2-$ and $-\text{PO}-$; n is an integer 0 to 5; and together with N form an optionally substituted ring, which may be additionally fused to a cycloalkyl or aryl group to form a bicyclic or tricyclic ring system, where the system is optionally substituted and optionally comprises one or more heteroatoms. Alternatively, R_1 and R_2 are $-(\text{CH}_2)_a-\text{Y}-(\text{CH}_2)_b-$, where Y is a heteroatom or a group selected from $-\text{CO}-$, $-\text{SO}-$, $-\text{SO}_2-$ and $-\text{PO}-$; a is an integer 0 to 5; b is an integer 0 to 5; where the sum of a and b is 0 to 5; and together with N form an optionally substituted ring, the ring being optionally fused to a cycloalkyl or aryl group to form a bicyclic or tricyclic ring system, where the system is optionally substituted and optionally comprises one or more heteroatoms.

Examples of ring systems include an optionally substituted uracil ring or a derivative thereof. Other examples include optionally substituted pyrrole, imidazole, purine and pyrazole and derivative thereof. Examples of fused ring systems include optionally substituted aziridin-1-yl, azetidin-1-yl, pyrrolidin-1-yl, piperidin-1-yl, homopiperidyn-1-yl and heptamethyleneimin-1-yl.

With respect to formulas (I) and (IV), in other embodiments, Z is hydroxylamine, a hydroxyalkylamino compound, a thioalkylamino compound, a diaminoalkane. Examples include ethylenediamine, piperazine, triaminoalkanes, polyamines, polylysine, putrescine, spermine, spermidine, aminoguanidines and agmatine. In other embodiments, Z is an amino acid. For example glycine, serine, hydroxyproline, β -alanine, cysteine, homocysteine, arginine, lysine, glutamic acid, ornithine, aspartic acid, γ -aminobutyric acid, or taurine. In other embodiments, Z is an amino sugar; for example glucosamine. In other embodiments, Z is a polyoxyethylene glycol of various molecular weights, each of which terminate in an amino functionality that will form an adduct with the appropriate sesquiterpene.

Modification of the sesquiterpene molecules by these methodologies, affords adducts that can easily be obtained as different inorganic or organic salts to further increase water solubility.

The compounds described herein are useful for treating cancer. Cancers treatable by the present therapy include the solid and hematological tumors, such as prostate cancer, ovarian cancer, breast cancer, brain cancer and hepatic cancer, comprising administering to a mammal afflicted with said cancer an amount of parthenolide derivative effective to inhibit the viability of cancer cells of said mammal. The parthenolide derivative may be administered as primary therapy, or as adjunct therapy, either following local intervention (surgery, radiation, local chemotherapy) or in conjunction with at least one other chemotherapeutic agent discussed hereinabove, as well as the solid tumors disclosed in U.S. Pat. No. 5,514,555. Hematological cancers, such as the leukemias are disclosed in the Mayo Clinic Family Health Book, D. E. Larson, ed., William Morrow, N.Y. (1990) and include CLL, ALL, CML and the like. Compounds of the present invention may be used in bone marrow transplant procedure to treat bone marrow prior to reintroduction to the patient. In addition, the compounds of the present invention may be used as chemotherapy sensitizers or radiation therapy sensitizers. Accordingly, a patient, or cells, or tissues, derived from a cancer patient, are pre-treated with the compounds prior to standard chemotherapy or radiation therapy. The present invention contemplates that parthenolide may also be used in such methods.

Within another aspect of the present invention, methods are provided for inhibiting angiogenesis in patients with non-tumorigenic, angiogenesis-dependent diseases, comprising administering a therapeutically effective amount of a composition comprising parthenolide derivative to a patient with a non-tumorigenic angiogenesis-dependent disease, such that the formation of new blood vessels is inhibited. Within other aspects, methods are provided for inhibit reactive proliferation of endothelial cells or capillary formation in non-tumorigenic, angiogenesis-dependent diseases, such that the blood vessel is effectively occluded. Within one embodiment, the anti-angiogenic composition comprising parthenolide derivative is delivered to a blood vessel which is actively proliferating and nourishing a tumor.

In addition to tumors, numerous other non-tumorigenic angiogenesis-dependent diseases, which are characterized by the abnormal growth of blood vessels, may also be treated

with the anti-angiogenic parthenolide derivative compositions, or anti-angiogenic factors of the present invention. Anti-angiogenic parthenolide derivative compositions of the present invention can block the stimulatory effects of angiogenesis promoters, reducing endothelial cell division, decreasing endothelial cell migration, and impairing the activity of the proteolytic enzymes secreted by the endothelium. Representative examples of such non-tumorigenic angiogenesis-dependent diseases include corneal neovascularization, hypertrophic scars and keloids, proliferative diabetic retinopathy, arteriovenous malformations, atherosclerotic plaques, delayed wound healing, hemophilic joints, nonunion fractures, Osler-Weber syndrome, psoriasis, pyogenic granuloma, scleroderma, trachoma, menorrhagia, retrolental fibroplasia and vascular adhesions. The pathology and treatment of these conditions is disclosed in detail in published PCT application PCT/CA94/00373 (WO 95/03036), at pages 26-36. Topical or directed local administration of the present compositions is often the preferred mode of administration of therapeutically effective amounts of parthenolide derivative, i.e., in depot or other controlled release forms.

Anti-angiogenic compositions of the present invention may also be utilized in a variety of other manners. For example, they may be incorporated into surgical sutures in order to prevent stitch granulomas, implanted in the uterus (in the same manner as an IUD) for the treatment of menorrhagia or as a form of female birth control, administered as either a peritoneal lavage fluid or for peritoneal implantation in the treatment of endometriosis, attached to a monoclonal antibody directed against activated endothelial cells as a form of systemic chemotherapy, or utilized in diagnostic imaging when attached to a radioactively labelled monoclonal antibody which recognizes active endothelial cells. The magnitude of a prophylactic or therapeutic dose of parthenolide derivative, an analog thereof or a combination thereof, in the acute or chronic management of cancer, i.e., prostate or breast cancer, will vary with the stage of the cancer, such as the solid tumor to be treated, the chemotherapeutic agent(s) or other anti-cancer therapy used, and the route of administration. The dose, and perhaps the dose frequency, will also vary according to the age, body weight, and response of the individual patient. In general, the total daily dose range for parthenolide derivative and its analogs, for the conditions described herein, is from about 0.5 mg to about 2500 mg, in single or divided doses. Preferably, a daily dose range should be about 1 mg to about 100 mg, in single or divided doses, most preferably about 5-50 mg per day. In managing the patient, the therapy should be initiated at a lower dose and increased depending on the patient's global response. It is further recommended that infants, children, patients over 65 years, and those with impaired renal or hepatic function initially receive lower doses, and that they be titrated based on global response and blood level. It may be necessary to use dosages outside these ranges in some cases. Further, it is noted that the clinician or treating physician will know how and when to interrupt, adjust or terminate therapy in conjunction with individual patient response. The terms "an effective amount" or "an effective sensitizing amount" are encompassed by the above-described dosage amounts and dose frequency schedule.

Any suitable route of administration may be employed for providing the patient with an effective dosage of parthenolide derivative (e.g., oral, sublingual, rectal, intravenous, epidural, intrathecal, subcutaneous, transcutaneous, intramuscular, intraperitoneal, intracutaneous, inhalation, transdermal, nasal spray, nasal gel or drop, and the like). While it is possible that, for use in therapy, parthenolide derivative or its

analogs may be administered as the pure chemicals, as by inhalation of a fine powder via an insufflator, it is preferable to present the active ingredient as a pharmaceutical formulation. The invention thus further provides a pharmaceutical formulation comprising parthenolide derivative or an analog thereof, together with one or more pharmaceutically acceptable carriers therefor and, optionally, other therapeutic and/or prophylactic ingredients. The carrier(s) must be 'acceptable' in the sense of being compatible with the other ingredients of the formulation and not deleterious to the recipient thereof, such as a human patient or domestic animal.

Pharmaceutical formulations include those suitable for oral or parenteral (including intramuscular, subcutaneous and intravenous) administration. Forms suitable for parenteral administration also include forms suitable for administration by inhalation or insufflation or for nasal, or topical (including buccal, rectal, vaginal and sublingual) administration. The formulations may, where appropriate, be conveniently presented in discrete unit dosage forms and may be prepared by any of the methods well known in the art of pharmacy. Such methods include the step of bringing into association the active compound with liquid carriers, solid matrices, semi-solid carriers, finely divided solid carriers or combinations thereof, and then, if necessary, shaping the product into the desired delivery system.

Pharmaceutical formulations suitable for oral administration may be presented as discrete unit dosage forms such as hard or soft gelatin capsules, cachets or tablets each containing a predetermined amount of the active ingredient; as a powder or as granules; as a solution, a suspension or as an emulsion; or in a chewable base such as a synthetic resin or chicle for ingestion of the agent from a chewing gum. The active ingredient may also be presented as a bolus, electuary or paste. Tablets and capsules for oral administration may contain conventional excipients such as binding agents, fillers, lubricants, disintegrants, or wetting agents. The tablets may be coated according to methods well known in the art, i.e., with enteric coatings.

Oral liquid preparations may be in the form of, for example, aqueous or oily suspensions, solutions, emulsions, syrups or elixirs, or may be presented as a dry product for constitution with water or other suitable vehicle before use. Such liquid preparations may contain conventional additives such as suspending agents, emulsifying agents, non-aqueous vehicles (which may include edible oils), or preservatives.

The compounds according to the invention may also be formulated for parenteral administration (e.g., by injection, for example, bolus injection or continuous infusion) and may be presented in unit dose form in ampules, pre-filled syringes, small volume infusion containers or in multi-dose containers with an added preservative. The compositions may take such forms as suspensions, solutions, or emulsions in oily or aqueous vehicles, and may contain formulatory agents such as suspending, stabilizing and/or dispersing agents. Alternatively, the active ingredient may be in powder form, obtained by aseptic isolation of sterile solid or by lyophilization from solution, for constitution with a suitable vehicle, e.g., sterile, pyrogen-free water, before use.

For topical administration to the epidermis, the compounds may be formulated as ointments, creams or lotions, or as the active ingredient of a transdermal patch. Suitable transdermal delivery systems are disclosed, for example, in A. Fisher et al. (U.S. Pat. No. 4,788,603), or R. Bawa et al. (U.S. Pat. Nos. 4,931,279; 4,668,506 and 4,713,224). Ointments and creams may, for example, be formulated with an aqueous or oily base with the addition of suitable thickening and/or gelling agents. Lotions may be formulated with an aqueous or oily base and

will in general also contain one or more emulsifying agents, stabilizing agents, dispersing agents, suspending agents, thickening agents, or coloring agents.

Formulations suitable for topical administration in the mouth include unit dosage forms such as lozenges comprising active ingredient in a flavored base, usually sucrose and acacia or tragacanth; pastilles comprising the active ingredient in an inert base such as gelatin and glycerin or sucrose and acacia; mucoadherent gels, and mouthwashes comprising the active ingredient in a suitable liquid carrier.

When desired, the above-described formulations can be adapted to give sustained release of the active ingredient employed, e.g., by combination with certain hydrophilic polymer matrices, e.g., comprising natural gels, synthetic polymer gels or mixtures thereof. The polymer matrix can be coated onto, or used to form, a medical prosthesis, such as a stent, valve, shunt, graft, or the like.

Pharmaceutical formulations suitable for rectal administration wherein the carrier is a solid are most preferably presented as unit dose suppositories. Suitable carriers include cocoa butter and other materials commonly used in the art, and the suppositories may be conveniently formed by admixture of the active compound with the softened or melted carrier(s) followed by chilling and shaping in molds.

Formulations suitable for vaginal administration may be presented as pessaries, tampons, creams, gels, pastes, foams or sprays containing, in addition to the active ingredient, such carriers as are known in the art to be appropriate.

For administration by inhalation, the compounds according to the invention are conveniently delivered from an insufflator, nebulizer or a pressurized pack or other convenient means of delivering an aerosol spray. Pressurized packs may comprise a suitable propellant such as dichlorodifluoromethane, trichlorofluoromethane, dichlorotetrafluoroethane, carbon dioxide or other suitable gas. In the case of a pressurized aerosol, the dosage unit may be determined by providing a valve to deliver a metered amount.

Alternatively, for administration by inhalation or insufflation, the compounds according to the invention may take the form of a dry powder composition, for example, a powder mix of the compound and a suitable powder base such as lactose or starch. The powder composition may be presented in unit dosage form in, for example, capsules or cartridges or, e.g., gelatin or blister packs from which the powder may be administered with the aid of an inhalator or insufflator.

For intra-nasal administration, the compounds of the invention may be administered via a liquid spray, such as via a plastic bottle atomizer. Typical of these are the Mistometer® (Wintrop) and the Medihaler® (Riker).

For topical administration to the eye, the compounds can be administered as drops, gels (U.S. Pat. No. 4,255,415), gums (see U.S. Pat. No. 4,136,177) or via a prolonged-release ocular insert.

The invention will now be described in greater detail by reference to the following non-limiting examples.

EXAMPLES

Example 1

General Synthetic Procedure for the Preparation of 11S,11,13-Dihydro,13-Substituted Aminoparthenolides

A mixture of parthenolide (Sigma P 0667, 100 mg, 0.4 mmol), the appropriate primary amine or secondary amine (2 mmol), and triethylamine (1 to 2 mL) in 30 mL of anhydrous

23

ethanol was stirred at a specific temperature ranging from ambient temperature to the temperature of the refluxing solvent utilized, or was left to stand in the refrigerator (-20°C . to 4°C .) overnight for 24 hours. Ethanol, triethylamine and/or the appropriate volatile amine were then evaporated under vacuum in a rotary evaporator. The resulting residue was subjected to silica gel column chromatographic purification using chloroform-methanol or methylene chloride-methanol mixed solvent as the mobile phase. NMR (Varian, 300 MHz and 400 MHz) and GC/MS (Agilent, 6890GC and 5973MSD) analysis methodologies were utilized to assure the identity and purity of the synthetic compounds.

Example 2

11S,11,13-Dihydro,13-dimethylaminoparthenolide (DMAPT)

Parthenolide (100 mg, 0.4 mmol), dimethylamine (2M in methanol, 1 mL), triethylamine (2 mL), ethanol (30 mL) were refluxed overnight. After column purification, 109 mg of pale yellow 11S,11,13-dihydro,13-dimethylaminoparthenolide was obtained (Yield: 93%). Melting point: $143-144^{\circ}\text{C}$. $^1\text{H-NMR}$ (300 MHz, CDCl_3): δ 5.22 (1H, d), 3.85 (1H, t), 2.75 (2H, m), 2.65 (1H, dd), 2.5-2.3 (3H, m), 2.25 (6H, s), 2.5-2.0 (5H, m), 1.7 (3H, s), 1.3 (3H, s), 1.3-1.15 (1H, m). $^{13}\text{C-NMR}$ (300 MHz, CDCl_3): δ 176.1, 134.4, 124.8, 81.9, 66.4, 61.3, 57.6, 47.8, 46.4, 46.1, 41.0, 36.6, 29.9, 24.0, 17.2, 16.9. Mass Spec (GC-MS): 293 (M^+) Retention time: 12.56 minutes. Ultra-violet (Methanol): λ_{max} at 214 nm. Infra-Red (Nujol): 1757.9, 1460, 1377 cm^{-1} . X-ray crystallographic analysis using a Nonius KappaCCD diffractometer DMAPT (11S,11,13-dihydro,13-dimethylaminoparthenolide) has the S-configuration at C-11.

Example 3

11S,11,13-Dihydro,13-diethylaminoparthenolide

Parthenolide (100 mg, 0.4 mmol), diethylamine (200 mg, 2.7 mmol), triethylamine (2 mL), ethanol (30 mL) were refluxed overnight. After column purification, 114 mg of yellow 11S,11,13-dihydro,13-diethylaminoparthenolide was obtained (Yield: 88%).

Example 4

Preparation of Salts of
11S,11,13-Dihydro,13-aminoparthenolide
Derivatives

The aminoparthenolide derivative was dissolved in anhydrous ether and to this solution was added the corresponding acid in ether or ethanol. The mixture was kept in the refrigerator (4°C .) overnight. The crystals formed was filtered and dried under vacuum, or submitted to further recrystallization, if needed.

Example 5

Preparation of
11S,11,13-dihydro,13-(piperidin-1-yl)parthenolide
hydrochloride

11S,11,13-dihydro,13-(piperidin-1-yl)parthenolide (5 mg) was dissolved in 2 mL of dry ether. Hydrochloride in ether (1M, 0.015 mL) was added to the ether solution until the

24

solution became cloudy; then more ether was added and the mixture was heated to obtain a clear solution. The mixture was left in refrigerator (4°C .) for more than 24 hours. The white crystals that formed were filtered through filter paper, and dried under vacuum overnight (Yield: 18%).

Example 6

Preparation of
11S,11,13-dihydro,13-dimethylaminoparthenolide
maleate

To 11S,11,13-dihydro,13-dimethylaminoparthenolide (30 mg, 0.1 mmol) in anhydrous ethanol (5 mL) was added maleic acid (12 mg, 0.1 mmol) in 3 mL of anhydrous ethanol. The solution was shaken well and filtered through a regular filter paper. The clear solution was left in the refrigerator for a week. The white crystals formed were obtained by filtration, dried in a desiccator under vacuum with anhydrous CaCl_2 (Yield: 55%).

Example 7

Preparation of
11S,11,13-dihydro,13-Dimethylaminoparthenolide
methiodide

To 11S,11,13-dihydro,13-dimethylaminoparthenolide (30 mg, 0.1 mmol) in anhydrous methanol (5 mL) was added iodomethane (90 mg, 0.6 mmol) in methanol (1 mL). The clear solution was shaken and stored at room temperature. After three days, the methanol was evaporated, the pale yellow residue was dried in a desiccator under vacuum, over anhydrous CaCl_2 . Recrystallization from acetone-ether afforded pale yellow crystals (Yield: 86%).

Example 8

11S,11,13-dihydro,13-(4-Methylpiperidin-1-yl)parthenolide methiodide

To 11S,11,13-dihydro,13-(4-methylpiperidin-1-yl)parthenolide (35 mg, 0.1 mmol) in anhydrous methanol (5 mL) was added iodomethane (90 mg, 0.6 mmol) in methanol (1 mL). The clear solution was shaken and stored at room temperature. After three days, the methanol was evaporated, the pale yellow residue was dried in a desiccator under vacuum, over anhydrous CaCl_2 . Recrystallization from acetone-ether afforded pale yellow crystals (Yield: 79%).

Example 9

Assay for Antileukemic Activity

For apoptosis analysis, one million primary acute myelogenous leukemia (AML) cells were washed with cold PBS and resuspended in 200 microliters of Annexin binding buffer (10 mM HEPES/NaOH pH 7.4; 140 mM NaCl; 2.5 mM CaCl_2). Annexin V-FITC (Pharmingen) and 0.25 mg/mL 7-AAD (7-aminoactinomycin D, Molecular Probes, CA) were added and the tubes were incubated at room temperature in the dark for 15 minutes. Cells were then diluted with 200 microliters of Annexin binding buffer and analyzed immediately by flow cytometry. Viable cells were identified as failing to label with Annexin V or 7-AAD. Cells beginning to die label with Annexin V, and as membrane integrity is lost, will also label

with 7-AAD. For each parthenolide derivative, the percentage of viable cells was determined after 24 hours of culture at a 10 micromolar concentration. Data are normalized to untreated control specimens. The data are in Table 1 for aminoparthenolide derivatives and Table 2 for the salts of some aminoparthenolides.

Healthy human bone marrow cells were used in the above assay to test the cytotoxicity of parthenolide. Eighty-five percent of the normal cells survived 10 μ M of parthenolide. All the aminoparthenolides evaluated afforded results similar to parthenolide, i.e. the survival rate of healthy human bone marrow cells was over 85% at a concentration of 10 μ M.

TABLE 1

Aminoparthenolides and their antileukemic activity				
Compound	Reactants and Solvent	Reaction Conditions	Yield (%)	Antileukemic activity
Parthenolide	Sigma P0667	Not applicable (N.A.)	N.A.	10 μ M, 84%
11S, 11,13-Dihydro, 13-dimethylaminoparthenolide (DMAPT)	Parthenolide (100 mg), dimethylamine (2 M in methanol, 1 mL), triethylamine (2 mL), ethanol (30 mL)	Refluxing overnight	93	5 μ M, 31% 10 μ M, 90% 20 μ M, 95%
11S, 11,13-Dihydro, 13-diethylaminoparthenolide (DEAPT)	Parthenolide (100 mg), diethylamine (200 mg, 2.7 mmol), triethylamine (2 mL), ethanol (30 mL)	Refluxing overnight	88	10 μ M, 60%
11S, 11,13-Dihydro, 13-(tert-butylamino) parthenolide (tBAPT)	Parthenolide (20 mg), tert-butylamine (0.2 mL), triethylamine (0.4 mL), ethanol (5 mL)	Refluxing 10 hours	39	10 μ M, 20%
11S, 11,13-Dihydro, 13-(pyrrolidin-1-yl) parthenolide (PyrPT)	Parthenolide (30 mg), pyrrolidine (0.2 mL), triethylamine (0.2 mL), ethanol (5 mL)	Refluxing 12 hours	80	5 μ M, 23% 10 μ M, 85% 20 μ M, 95%
11S, 11,13-Dihydro, 13-(piperidin-1-yl)parthenolide (PipPT)	Parthenolide (250 mg), piperidine (1 mL), triethylamine (5 mL), ethanol (100 mL)	Refluxing overnight	86	2.5 μ M, 71% 5 μ M, 91%
11S, 11,13-Dihydro, 13-(morpholin-1-yl)parthenolide (MorPT)	Parthenolide (100 mg), morpholine (0.5 mL), triethylamine (2 mL), ethanol (30 mL)	Refluxing overnight	91	5 μ M, 5% 20 μ M, 20%
11S, 11,13-Dihydro, 13-(4-methylpiperazin-1-yl)parthenolide (4MePipPT)	Parthenolide (100 mg), 4-methylpiperidine (0.5 mL), triethylamine (2 mL), ethanol (30 mL)	Refluxing overnight	89	10 μ M, 83%
11S, 11,13-Dihydro, 13-(4-methylpiperazin-1-yl)parthenolide (4MePizPT)	Parthenolide (30 mg), 4-methylpiperazine (0.2 mL), triethylamine (1 mL), ethanol (20 mL)	Refluxing overnight	74	10 μ M, 7%
11S, 11,13-Dihydro, 13-(homopiperidin-1-yl)parthenolide (HomoPipPT)	Parthenolide (100 mg), homopiperidine (500 mg), triethylamine (2 ml), ethanol (30 ml)	Refluxing overnight	82	10 μ M, 40%
11S, 11,13-Dihydro, 13-(heptamethyleneimin-1-yl)parthenolide (HeptaMePipt)	Parthenolide (100 mg), heptamethyleneimin (500 mg), triethylamine (2 mL), ethanol (30 mL)	Refluxing overnight	74	10 μ M, 10%
11S, 11,13-Dihydro, 13-(azetidin-1-yl)parthenolide (AzePT)	Parthenolide (100 mg), azetidine (100 mg), triethylamine (2 mL), ethanol (20 mL)	Stirred at room temperature 2 days	93	
11S, 11,13-Dihydro, 13-diallylaminoparthenolide	Parthenolide (100 mg), diallylamine (200 mg), triethylamine (2 mL), ethanol (30 mL)	Refluxing overnight	57	

TABLE 1-continued

<u>Aminoparthenolides and their antileukemic activity</u>				
Compound	Reactants and Solvent	Reaction Conditions	Yield (%)	Antileukemic activity
11S, 11,13-Dihydro, 13-Methylbutyl amino-parthenolide	Parthenolide 25 mg Methylbutylamine 20 mg Methanol, 8 hrs	Room temperature with stirring	85%	10 μ M, 68%
11S, 11,13-Dihydro, 13-Methyl pentyl amino parthenolide	Parthenolide 25 mg Methylpentylamine 20 mg Methanol, 6 hrs	Room temperature with stirring	88%	10 μ M, 45%
11S, 11,13-Dihydro, 13-ethylamino parthenolide	Parthenolide 25 mg Ethylamine 90 mg Methanol, 5 hrs	Room temperature with stirring	90%	10 μ M, 2%
11S, 11,13-Dihydro, 13-methylamino parthenolide	Parthenolide 25 mg, 2 M Methylamine in methanol (1 ml), Methanol, 5 hrs	Room temperature with stirring	93%	10 μ M, 4%
11S, 11,13-Dihydro, 13-cyclopropylamino parthenolide	Parthenolide 25 mg Cyclopropylamine 20 mg Methanol, 6 hrs	Room temperature with stirring	90%	10 μ M, -6%
11S, 11,13-Dihydro, 13-propargylamino parthenolide	Parthenolide 25 mg Propargylamine 20 mg Methanol, 6 hrs	Room temperature with stirring	82%	10 μ M, 7%

TABLE 2

<u>Aminoparthenolide salts and their antileukemic activity</u>				
Compound	Reactants and Solvent	Reaction Conditions	Yield (%)	Antileukemic activity
11S, 11,13-Dihydro, 13-dimethylaminoparthenolide hydrochloride	11S, 11,13-Dihydro, 13-dimethylaminoparthenolide (10 mg), HCl in ether (1 M, 0.03 mL)	Refrigerator, 24 hours	72	
11S, 11,13-Dihydro, 13-(pyrrolidin-1-yl)parthenolide hydrochloride	11S, 11,13-Dihydro, 13-(pyrrolidin-1-yl)parthenolide (5 mg), HCl in ether (1 M, 0.015 mL)	Refrigerator, 24 hours	10	10 μ M, 85%
11S, 11,13-Dihydro, 13-(piperidin-1-yl)parthenolide hydrochloride	11S, 11,13-Dihydro, 13-(piperidin-1-yl)parthenolide (5 mg), HCl in ether (1 M, 0.015 mL)	Refrigerator, 24 hours	18	10 μ M, 88%
11S, 11,13-Dihydro, 13-(4-methylpiperidin-1-yl)parthenolide hydrochloride	11S, 11,13-Dihydro, 13-(4-methylpiperidin-1-yl)parthenolide (50 mg), HCl in ether (1 M, 0.15 mL)	Refrigerator, 4 days	38.3	10 μ M, 62%
11S, 11,13-Dihydro, 13-dimethylaminoparthenolide maleate	11S, 11,13-Dihydro, 13-dimethylaminoparthenolide (30 mg), maleic acid (12 mg), ethanol (8 mL)	Room temperature for 1 week	55	
11S, 11,13-Dihydro, 13-dimethylaminoparthenolide methiodide	11S, 11,13-Dihydro, 13-dimethylaminoparthenolide (30 mg), added iodomethane (90 mg), methanol (6 mL)	Room temperature for 3 days	86	
11S, 11,13-Dihydro, 13-(4-methylpiperidin-1-yl)parthenolide methiodide	11S, 11,13-Dihydro, 13-(4-methylpiperidin-1-yl)parthenolide (70 mg), iodomethane (200 mg), methanol (12 mL)	Room temperature for 3 days	79	
11H, 13-(N,N-Dimethylamino)-dehydrocostuslactone				10 μ M, 12%
11H, 13-(N-Piperidine)-dehydrocostuslactone				10 μ M, 14%
11H, 13-(N-Butyl-N-methylamino)-dehydrocostuslactone				10 μ M, 8%

TABLE 2-continued

<u>Aminoparthenolide salts and their antileukemic activity</u>			
Compound	Reactants and Solvent	Reaction Conditions	Yield Antileukemic (%) activity
11H, 13-(N-Propylamino)-dehydrocostuslactone			10 μ M, 24%
11H, 13-(N-Diallyl)-dehydrocostuslactone			10 μ M, 2%
11H, 13-(N-Morpholine)-dehydrocostuslactone			10 μ M, 10%
11H, 13-(N-Pyrrolidine)-dehydrocostuslactone			10 μ M, 20%
11H, 13-(N-Ethyl-N-benzyl)-dehydrocostuslactone			10 μ M, 13%
11H, 13-(N-Methyl-N-propylamino)-dehydrocostuslactone			10 μ M, 1%
11H, 13-(N,N-Diethylamino)-dehydrocostuslactone			10 μ M, 5%
11H, 13-(N-Methyl-N-pentylamino)-dehydrocostuslactone			10 μ M, 0%

Example 10

Analysis of parthenolide and dimethylaminoparthenolide (DMAPT) Using Human-Mouse Xenografts

To assess the effect of parthenolide on primary human stem cell populations, experiments were conducted using transplantation into immune deficient NOD/SCID mice. Successful engraftment of NOD/SCID bone marrow at 6-8 weeks post-transplant has been shown to be a measure of stem cell content for human hematopoietic cell populations (Lapidot et al., *J Mol Med.* 1997; 75: 664-673; Dick, *Curr Opin Hematol.* 1996; 3:405-409). For each experiment, cryopreserved mononuclear cell specimens from normal or AML donors were thawed, and treated in vitro with 7.5 micromolar parthenolide for 12-18 hours. Following culture, 5-10 million cells/animal were injected intravenously into sublethally irradiated (300 Rad) NOD/SCID mice. After 6-8 weeks, animals were sacrificed and bone marrow was analyzed for the presence of human cells using flow cytometry as previously described (Guzman et al., *Proc Natl Acad Sci USA* 2002; 99: 16220-16225). Human specific antibodies for CD45 were used to assess the level of total engraftment.

In three independent experiments, the level of engraftment for parthenolide-treated AML cells was dramatically reduced, which indicates a direct effect on the AML stem cell compartment. In contrast, no reduction in engraftment was detected for parthenolide-treated normal specimens, thus showing the parthenolide does not target normal hematopoietic stem cells. Similarly, treatment of AML cells with 7.5 micromolar DMAPT also yielded a strong reduction in NOD/SCID engraftment while treatment of normal cells showed no significant effects.

Example 11

MTS-PMS Assay

A 96-well U-bottomed plate (Becton Dickinson Labware, Franklin Lakes, N.J.) at a concentration of 5,000 cells per 50 microliters (mL) of media was incubated in 5% CO₂ at 37° C.

25

for 24 hours. Varying compound concentrations in 50 mL of media were added to the media 24 hours later. Colorimetric readings were obtained using the MTS/PMS system and an ELISA plate reader, after 48 hours of exposure to DMAPT.

30

The readings obtained for each concentration tested were from an average of eight wells. Each experiment was expressed as a percentage of the solvent control and completed at least three times with consistent results. The results presented are an average of three experiments. The hormone refractory prostate cancer cell line CWR22Rv1 was treated with increasing concentrations of parthenolide and DMAPT. for three hours Both parthenolide and DMAPT reduced cellular proliferation by 50% at 5 μ m in the CWR22 MTS-PMS assay. Cellular proliferation was also measured in the MTS-PMS assay using four lung cancer cell lines treated with parthenolide and derivatives PIPT ((11S,11,13-dihydro,13-(piperidin-1-yl)parthenolide), 4MEPT (11S,11,13-dihydro, 13-(4-methylpiperidin-1-yl)parthenolide) and MAPT (11S, 11,13-dihydro,13-dimethylaminoparthenolide).

35

40

45

Parthenolide and its derivatives inhibited cellular proliferation in a dose dependent manner between 2 and 10 μ M with 70% inhibition at 10 μ M in A549, 50% in H460, 40% in H-23 and 40% in H522 (FIGS. 2-5).

50

Example 12

Clonogenic Assay

55

60

65

Initially, 100 cells growing in log phase were plated per 3 ml of media in each well of a six well plate. After 24 hrs of plating of the cells the test compound was added at varying concentrations. At 24 and 96 hours after addition of drug, the media was changed. Hence, the cells were only exposed to the drug for 24 hrs. When cell colonies appeared at Day 15 they were stained by Sure Stain Dye and counted. The hormone refractory prostate cancer cell line CWR22Rv1 was treated with increasing concentrations of parthenolide derivatives DMAPT, PIPT and 4MEPT for three hours. Cellular proliferation was reduced by up to 80% at 2 μ m in the clonogenic assay (FIG. 1). The breast cancer cell line clonogenic assay with hbl-100, mdl-231 and 436 cells showed almost complete inhibition of proliferation with DMAPT at 2 μ m concentra-

tion in the clonogenic assay (FIGS. 6-8). Parthenolide also reduced proliferation with similar dosage ranges.

Example 13

cDNA Array Analysis

Total cellular RNA was extracted from the human monocyte cell line THP-1 under three conditions 2 hours after Time 0:

- 1) Control was added at Time 0
- 2) Lipopolysaccharide (10 nM) was added at Time plus one (1) hour
- 3) At Time 0, 10 micromoles of DMAPT was added and then at Time+1 LPS (10 nM) was added.

RNA was extracted using RNeasy Min Kit (Qiagen, USA) according to the manufacturer's instructions. The Human Drug Targets for Inflammation and Immunomodulation Q series GE array kit (HS-048-12) was obtained from SuperArray Bioscience Corporation (Frederick, Md.). The kit determines expression of 96 genes that are associated with inflammation. RNA from respective samples was used as a template to generate biotin labeled cDNA probes using GEArray Ampolabelling RT kit (SuperArray, Bioscience Corp., USA). The cDNA probes corresponding to the mRNA population were then denatured and hybridization was carried out in GEHyb solution to nylon membranes spotted with gene specific fragments. Membranes were then washed in 2xSSC, 1% SDS twice for 15 minutes each, followed by 0.1 SSC, 0.5% SDS twice for 15 minutes each. Chemiluminescence was used to visualize the expression levels of each transcript and the results were quantified with the GEArray Analyzer. The change in a given gene transcript was estimated by normalizing the signal intensities with the signal derived from PPIA and with minimum background subtraction.

As can be seen in Table 3, transcription of 25 genes was increased after pre-treatment with LPS. More importantly pretreatment with DMAPT prevented or blunted the increase in gene transcription induced by LPS. For example, the transcription of tumor necrosis factor (TNF), released in septic shock, is increased by 3 fold (298%) when treated with LPS. Pretreatment with DMAPT however prevents transcription of LPS and in fact decreases its production to 2% of control. Similarly, transcription of cyclo-oxygenase-2, the target of classical non-steroidal anti-inflammatory agents, was increased 1.5 fold (150%). In the presence of DMAPT, the gene expression not only prevented the increase by LPS but decreased it to 30% (0.7) of solvent control. DMAPT therefore may act to decrease inflammation by decreasing cytokines as evidenced by decreased genes in human monocytes

TABLE 3

cDNA Array Analysis		
Gene	LPS Treatment for 1 hour: % Change of Gene	DMAPT Pre-treatment for 2 hours then 1 hour Treatment of LPS % Change of Genes
CD28 antigen (Tp44)	23	0.814
CD3G antigen, gamma polypeptide (TIT3 complex)	14	0.6
Colony stimulating factor 2 (granulocyte-macrophage)	26	0.926
Intercellular Adhesion Molecule 1	257	58
Interleukin 13	93	0.64
Interleukin 1 receptor, type I	10	0.33

TABLE 3-continued

cDNA Array Analysis		
Gene	LPS Treatment for 1 hour: % Change of Gene	DMAPT Pre-treatment for 2 hours then 1 hour Treatment of LPS % Change of Genes
5 Interleukin 1 receptor, type II	326	0.74
10 Nitric oxide synthase 2A (inducible)	226	48
Phosphodiesterase 4A, cAMP-specific	14	0.46
Phosphodiesterase 4B, cAMP-specific	220	0.59
15 Phospholipase A2, group IB (pancreas)	114	0.57
Phospholipase A2, group IVC	350	0.89
Phospholipase A2, group VII	129	0.05
Phospholipase C, gamma 1	342	0.24
Peroxisome proliferative activated receptor, gamma	49	0.48
20 Platelet-activating factor receptor	32	0.002
Prostaglandin D2 receptor (DP)	35	0.17
Prostaglandin F receptor (FP)	879	1.46
Cyclooxygenase 1	176	0.731
Cyclooxygenase 2	152	0.7
25 Thromboxane A synthase 1	283	0.07
Tumor necrosis factor (TNF superfamily, member 2)	298	0.02
Tumor necrosis factor (ligand) superfamily, member 13b	217	0.89
Tumor necrosis factor (ligand) superfamily, member 5	692	23
30 Vascular cell adhesion molecule 1	154	0.02

Example 14

Oral Bioavailability in Mice

Preliminary in vivo work was conducted to determine the bioavailability and toxicity of this agent in mice. As shown in FIG. 4 it was demonstrated that whereas 40 mg/kg of oral parthenolide provided a plasma level one hour after oral gavage of only ~200 nM, the same dose of DMAPT provided a plasma level of ~2500 ng/mL (i.e. 8 μM—average of 5 mice in each group; measured by LC-MS). Given the concern from providing such a high plasma concentration we completed a preliminary toxicity study that showed the mice gained weight and survived three weeks of daily treatment with oral DMAPT at 40 mg/kg with no overt toxicities.

Example 15

Electrophoretic Mobility Gel Shift Assay

Each cancer cell line in exponential growth phase was treated with solvent control or various concentrations of parthenolide derivatives dissolved in 100% ethanol for 3 hours prior to harvesting. Cells were harvested and whole cell extracts were prepared as described previously (Nakshatri et al., *Mol Cell Biol*, 17: 3629-3639, 1997; Sweeney et al., *Clin Cancer Res*, 10: 5501-5507, 2004). Extracts were incubated with a radiolabelled NFκB probe for 30 minutes at room temperature. The oligonucleotide probe binds to the NFκB DNA binding site in the promoter region of the immunoglobulin gene. Electrophoresis and autoradiography were performed as described previously (Nakshatri et al., 1997) using NFκB and SP-1 probes (Promega, Madison, Wis.). The speci-

33

ficity of parthenolide and derivative inhibition of NF- κ B DNA binding was verified by the use of the SP-1 probe as a control. Identification of the NF- κ B subunits binding to DNA and inhibited by DMAPT were identified by gel supershift. Constitutive NF- κ B DNA binding activity was determined in the lung cancer cell lines A-549, H-23, H-522, and H-460. All four non-small lung cancer cells were treated with increasing concentrations of DMAPT for three hours, and NF- κ B DNA binding was measured by electrophoretic mobility shift assay (EMSA) as described. NF- κ B DNA binding activity was highest in A-549 cells, followed by H-23, H-522 and H-460 cells. DMAPT between 2 and 10 micromolar substantially decreased NF- κ B DNA binding activity in all lung cancer cell lines tested.

Cancer cell lines HT-1376 and UMUC-3 were treated with increasing concentrations of DMAPT for three hours. Whole cell extracts were prepared as described and DNA binding by NF- κ B was analyzed by EMSA with NF- κ B and OCT-1 (internal control) probes. DMAPT decreased NF- κ B DNA binding in a dose-dependent manner with HT-1376 and UMUC-3 cell lines (FIG. 10).

The hormone refractory prostate cancer cell line, CWR22Rv1 was treated with increasing concentrations of DMAPT for three hours. Whole cell extracts were prepared as described and DNA binding by NF- κ B was analyzed by EMSA with NF- κ B and SP-1 (internal control) probes. DMAPT decreased NF- κ B DNA binding in a dose dependent manner with substantial decreases of NF- κ B DNA binding at 10 μ M DMAPT.

EMSA results thus showed DMAPT decreased the constitutive NF- κ B DNA binding in several cancer cell lines.

Example 16

Pretreatment of Radiation Sensitive Cell Line A549

The radiation sensitive cell line A549 was pretreated with parthenolide concentrations ranging from 0 to 2.5 micromolar. The cells were then subjected to ionizing radiation doses ranging from 0-6 Gy and survival fraction of the cells determined. Results demonstrated that parthenolide induced radiation sensitivity to the cells in a dose-dependent manner with survival fraction at 2.5 micromolar ranging from 10% at 2 Gy to less than 1% at 6 Gy. Cells not receiving pre-treatment with parthenolide had greater than 50% survival fraction at the highest radiation dose of 6 Gy and over 90% survival at 2 Gy.

Example 17

TRAIL Induced Apoptosis Assay


MDA-MB-231 breast cancer cells (2x10⁵ cells in 60 mm plates) were treated first with 2 or 5 μ M of DMAPT (LC-1). After two hours, TRAIL (TNF related-apoptosis-inducing-ligand, 5 ng/ml) or TRAIL-RII-activating antibodies (10 ng/ml) were added. After 48 hours of TRAIL or TRAIL-RII antibody treatment, cells were harvested and apoptosis was measured using carboxyfluorescein-FLICA assay. Briefly, both attached and floating cells were collected by trypsinization, incubated with carboxyfluorescein-labeled pan-caspase inhibitor FAM-VAD-FMK for 2 h at 37° C. Labeled cells were rinsed twice in PBS and resuspended in 300 μ l of PBS containing 0.3 μ g of propidium iodide. Apoptotic cells were identified by FACScan analysis. Live cells do not stain (FIGS. 11 and 12) Lower left quadrant). FAM-VAD-FMK stains apoptotic cells (upper left). Apoptotic cells that have lost plasma membrane integrity are stained by both FAM-VAD-

34

FMK and propidium iodide (upper right). Necrotic cells are stained only by propidium iodide (lower right). MDA-MB-231 cells are relatively resistant to TRAIL. However, they became sensitive to TRAIL or TRAIL-RII activating antibody-induced apoptosis and atypical apoptosis upon pre-treatment with DMAPT.

We claim:

1. A compound of the formula (I):



wherein:

X₁, X₂ and X₃ are O;

R₅, R₆, R₇, R₉, and R₁₀ are H, and R₄ and R₈ are methyl; and

Z is —CH₂R* wherein R* is an amino acid residue bonded to the Z methylene via a nitrogen or a sulfur atom; or R* is —NR¹CO₂—R², —NR¹C(O)NR², —S—R¹, —NR¹R², or —N⁺R¹R²R¹¹Y⁻ wherein

R¹ and R² are independently selected from H, CN, and optionally substituted straight-chained or branched aliphatic optionally containing 1 or more double or triple bonds; wherein optional substituents are selected from one or more of —NH₂, —NH(C₁₋₄ aliphatic), —N(C₁₋₄ aliphatic)₂, halogen, —OH, —O—(C₁₋₄ aliphatic), —NO₂, —CN, —CO₂H, —CO₂(C₁₋₄ aliphatic), —O(halo C₁₋₄ aliphatic), or -halo(C₁₋₄ aliphatic); wherein each C₁₋₄ aliphatic is optionally substituted; or R¹ and R² are independently selected from cycloalkyl, heterocycloalkyl, aryl or heteroaryl; and provided that R¹ and R² are not simultaneously H; or where R* is NR¹R², R¹ and R² optionally together with the nitrogen atom form an optionally substituted 5-12 membered ring, said ring optionally comprising 1 or more heteroatoms or a group selected from —CO—, —SO—, and —SO₂—;

R¹¹ is selected from H or C₁₋₄ aliphatic; and

Y⁻ is selected from the group consisting of fluoride, chloride, bromide, iodide, sulfate, nitrate, bicarbonate, carbonate, acetate, citrate, malonate, tartarate, succinate, benzoate, ascorbate, alpha-ketoglutarate, alpha-glycero-phosphate, methylsulfonate, toluenesulfonate, and benzenesulfonate; or

a pharmaceutically acceptable salt thereof.

2. The compound of claim 1 wherein Z is —CH₂—NR¹R².

3. The compound of claim 2 wherein R¹ and R² are independently selected from hydrogen, —CN or optionally substituted C₁-C₄ alkyl.

4. The compound of claim 3 wherein R¹ and R² are independently selected from —NO₂, —CN, —CH₃, —CF₃, —CH₂CH₃, —CH₂CF₃, —CH₂Cl, —CH₂OH, —CH₂CH₂OH and —CH₂NH₂.

5. The compound of claim 2 wherein R¹ and R² together with N form an optionally substituted ring.

6. The compound of claim 5 wherein said ring is a monocyclic, bicyclic or tricyclic alkyl or aryl ring system, said ring

35

system optionally substituted and optionally comprising one or more heteroatoms or a group selected from —CO—, —SO—, and —SO₂.

7. The compound of claim 6 wherein R¹ and R² are —CH₂(CH₂)_nCH₂Y—; where Y is a heteroatom or a group selected from —CO—, —SO—, and —SO₂—; n is an integer 0 to 5; and together with N form an optionally substituted ring, said ring optionally fused to a cycloalkyl or aryl group to form a bicyclic or tricyclic ring system, said system optionally substituted and optionally comprising one or more heteroatoms.

8. The compound of claim 6 wherein R₁ and R₂ are —(CH₂)_a—Y—(CH₂)_b—; where Y is a heteroatom or a group selected from —CO—, —SO—, and —SO₂—; a is an integer 0 to 5; b is an integer 0 to 5; the sum of a and b being 0 to 5; and together with N form an optionally substituted ring, said ring optionally fused to a cycloalkyl or aryl group to form a bicyclic or tricyclic ring system, said system optionally substituted and optionally comprising one or more heteroatoms.

9. The compound of claim 5 wherein NR₁R₂ is selected from optionally substituted aziridin-1-yl, azetidin-1-yl, pyrrolidin-1-yl, piperidin-1-yl, homopiperidin-1-yl and heptamethyleneimin-1-yl.

10. A compound selected from:

- 11S,11,13-Dihydro,13-dimethylaminoparthenolide;
- 11S,11,13-Dihydro,13-diethylaminoparthenolide;
- 11S,11,13-Dihydro,13-(tert-butylamino)parthenolide;
- 11S,11,13-Dihydro,13-(pyrrolidin-1-yl)parthenolide;
- 11S,11,13-Dihydro,13-(piperidin-1-yl)parthenolide;
- 11S,11,13-Dihydro,13-(morpholin-1-yl)parthenolide;
- 11S,11,13-Dihydro,13-(4-methylpiperidin-1-yl)parthenolide;
- 11S,11,13-Dihydro,13-(4-methylpiperazin-1-yl)parthenolide;
- 11S,11,13-Dihydro,13-(homopiperidin-1-yl)parthenolide;
- 11S,11,13-Dihydro,13-(heptamethyleneimin-1-yl)parthenolide;
- 11S,11,13-Dihydro,13-(azetidin-1-yl)parthenolide;
- 11S,11,13-Dihydro,13-methylbutyl aminoparthenolide;
- 11S,11,13-Dihydro,13-methyl pentyl aminoparthenolide;
- 11S,11,13-Dihydro,13-ethylaminoparthenolide;
- 11S,11,13-Dihydro,13-methylaminoparthenolide;
- 11S,11,13-Dihydro,13-cyclopropylaminoparthenolide;
- 11S,11,13-Dihydro,13-propargylaminoparthenolide;
- 11S,11,13-Dihydro,13-(N-benzyl-N-ethylamine)parthenolide;
- 11S,11,13-Dihydro,13-(N-prolyl)parthenolide;
- 11S,11,13-Dihydro,13-(S-thiophenolyl)parthenolide;
- 11S,11,13-Dihydro,13-(N,N-diethanolamine)parthenolide;

36

11S,11,13-Dihydro,13-(thiomorpholin-4-yl)parthenolide;

11S,11,13-Dihydro,13-(4-hydroxypiperidin-1-yl)parthenolide;

11S,11,13-Dihydro,13-(1-methylhomopiperizin-4-yl)parthenolide;

11S,11,13-Dihydro,13-(S-mercaptoacetyl)parthenolide;

11S,11,13-Dihydro,13-(4-(2'-hydroxyethyl)piperidin-1-yl)parthenolide;

11S,11,13-Dihydro,13-(piperazin-1-yl-4-carboxaldehyde)parthenolide;

11S,11,13-Dihydro,13-(4-benzylpiperidin-1-yl)parthenolide;

11S,11,13-Dihydro,13-(piperidin-1-yl-4-carboxylic acid)parthenolide;

11S,11,13-Dihydro,13-(azetidin-1-yl-3-carboxylic acid)parthenolide;

11S,11,13-Dihydro,13-(S-cysteinyl)parthenolide;

11S,11,13-Dihydro,13-(4-(piperidin-1'-yl)piperidin-1-yl)parthenolide;

11S,11,13-Dihydro,13-diallylaminoparthenolide; or a pharmaceutically acceptable salt thereof.

11. The compound of claim 1:

11S,11,13-Dihydro,13-dimethylaminoparthenolide hydrochloride;

11S,11,13-Dihydro,13-(pyrrolidin-1-yl)parthenolide hydrochloride;

11S,11,13-Dihydro,13-(piperidin-1-yl)parthenolide hydrochloride;

11S,11,13-Dihydro,13-(4-methylpiperidin-1-yl)parthenolide hydrochloride;

11S,11,13-Dihydro,13-dimethylaminoparthenolide maleate;

11S,11,13-Dihydro,13-dimethylaminoparthenolide methiodide; or

11S,11,13-Dihydro,13-(4-methylpiperidin-1-yl)parthenolide methiodide.

12. A pharmaceutical composition comprising a compound of claim 1 or a pharmaceutically acceptable salt thereof; in combination with a pharmaceutically effective diluent or carrier.

13. The compound of claim 1 wherein Z is —CH₂S—R¹; wherein R¹ is selected from optionally substituted straight-chained or branched aliphatic wherein optional substituents are selected from one or more of —NH₂, —N(C₁₋₄ aliphatic)₂, halogen, —OH, —O—(C₁₋₄ aliphatic), —NO₂, —CN, —CO₂H, —CO₂(C₁₋₄ aliphatic), —O-(halo C₁₋₄ aliphatic), or -(halo C₁₋₄ aliphatic); wherein each C₁₋₄ aliphatic is optionally substituted; cycloalkyl, heterocycloalkyl, aryl or heteroaryl.

* * * * *

UNITED STATES PATENT AND TRADEMARK OFFICE
CERTIFICATE OF CORRECTION

PATENT NO. : 7,678,904 B2
APPLICATION NO. : 11/031315
DATED : March 16, 2010
INVENTOR(S) : Peter A. Crooks, Craig T. Jordan and Xiaochen Wei

Page 1 of 1

It is certified that error appears in the above-identified patent and that said Letters Patent is hereby corrected as shown below:


Please change the priority data (page 1, first paragraph) lines 5-7, as follows:

Related U.S. Application Data:

This application is a continuation-in-part of application No. 10/888,274, filed on 07/09/2004, now patent No. 7,312,242, issued on 12/25/2007; which claims priority to provisional application No. 60/486,171 filed 07/11/2003.

Signed and Sealed this

Eighth Day of June, 2010

A handwritten signature in black ink that reads "David J. Kappos". The signature is written in a cursive, flowing style.

David J. Kappos
Director of the United States Patent and Trademark Office