University of Tennessee, KnoxvilleMasthead LogoTrace: Tennessee Research and Creative Exchange

Chancellor's Honors Program Projects

Supervised Undergraduate Student Research and Creative Work

5-2019

Appalachian Electric Cooperative Zinc Substation Foundation Project

Leah Stephens lsteph24@vols.utk.edu

James Throckmorton jthrockm@vols.utk.edu

Grayson Layne glayne1@vols.utk.edu

Ben Morris rmorri34@vols.utk.edu

Follow this and additional works at: https://trace.tennessee.edu/utk_chanhonoproj Part of the <u>Civil Engineering Commons</u>, <u>Geotechnical Engineering Commons</u>, and the <u>Structural Engineering Commons</u>

Recommended Citation

Stephens, Leah; Throckmorton, James; Layne, Grayson; and Morris, Ben, "Appalachian Electric Cooperative Zinc Substation Foundation Project" (2019). *Chancellor's Honors Program Projects*. https://trace.tennessee.edu/utk_chanhonoproj/2262

This Dissertation/Thesis is brought to you for free and open access by the Supervised Undergraduate Student Research and Creative Work at Trace: Tennessee Research and Creative Exchange. It has been accepted for inclusion in Chancellor's Honors Program Projects by an authorized administrator of Trace: Tennessee Research and Creative Exchange. For more information, please contact trace@utk.edu.

Leah Stephens 2371 Cherokee Ridge Way Knoxville, TN 37920

April 30, 2019

Dr. Rebekah PageHoward Baker Center1640 Cumberland Ave. Knoxville, TN 37996

Dear Dr. Page,

Our senior design team was partnered with C2RL to perform engineering analysis and design for a substation foundation located in New Market, Tennessee. Based on the needs of the project, several areas of work within the civil engineering discipline had to be considered as a team. The foundation was designed to withstand the large loads of the electrical equipment while in the presence of subterranean voids from the abandoned zinc mine. Geo-structural analysis and design was necessary to address the loads and the soil stability for the foundation. The environmental regulations were enforced to ensure that the fluid containment infrastructure was considered in the case of failure to avoid contamination. The sub-station required the use of transformers of significant size, such that a failure causing a fluid leak would cause considerable environmental damage. A temporary traffic plan was developed for use during construction. This plan required an analysis of current traffic patterns to ensure that safe accommodations were met during the temporary conditions. This analysis was done through a transportation study completed at the site. Based on the study of the existing conditions and the requirements of the project, a plan to accommodate the temporary conditions was developed, including a temporary traffic plan

and construction entrances/exits. Finally, the construction schedule was created with consideration of equipment delivery and temporary roadways, and a cost analysis was produced in order to determine that the final design was reasonable in terms of the budget. My contribution to the project was the analysis and design of the substation from a structural perspective. I completed a series of hand calculations and utilized RISAFoundation software to arrive at an optimal solution. A 12 inch thick, 3000 psi concrete mat foundation with #5 bar reinforcement at the top and bottom of the slab, spaced at 18 inches, was selected as the final design. This design satisfied all structural and geotechnical requirements. My calculations for the project are available in Appendix A of the report, which is attached. The other students' work can be seen in the remaining appendices. A complete summary of my structural work can be seen in the "Structural Design" section of the report. I also worked with my team on each of their sections to help with technical writing and editing. In addition, I completed research on alternative foundation designs and compared each based on their benefits and costs.

Sincerely,

Leah Stephens Senior, Civil and Environmental Engineering Enclosed:

Appalachian Electric Cooperative Zinc Substation Foundation Project and Appendices

Appalachian Electric Cooperative Zinc Substation Foundation Project

Smoky Mountain Foundation Inc.



Authored by:

Grayson Layne, Ben Morris, Leah Stephens, James Throckmorton

The University of Tennessee, Knoxville Tickle College of Engineering Department of Civil and Environmental Engineering CE 400: Senior Design Project Course Graduating May 2019

Acknowledgements

Smoky Mountain Foundation Inc. would like to acknowledge those who had an impact on this project. The Appalachian Electric Cooperative Zinc Substation Foundation project would not have been possible without the support of many different professionals within the local community and the University of Tennessee, Knoxville. Special thanks to:

Chris Soro- Principal Engineer at C2RL

Brian Williamson- Geotechnical Department Manager at GEOServices

Timothy Siegel- Senior Principal Engineer at Dan Brown and Associates

Dr. Angel Palomino- Associate Professor at the University of Tennessee- Knoxville in CEE Department

Dr. Jennifer Retherford – Senior Lecturer at the University of Tennessee- Knoxville in CEE Department

Disclaimer

The investigation, results, and construction drawings compiled by Smoky Mountain Foundation Inc. for the Appalachian Electric Cooperative Zinc Substation Foundation project was for a senior design project for the University of Tennessee, Knoxville. The design solutions proposed within this report are to be used for academic purposes only and construction should not occur without complete review by a licensed engineer.

Table of Contents

List of Figures	3
List of Tables	3
Introduction	4
Project Introduction	6
Defined Scope of Work	7
Site Conditions	8
Analysis and Design	9
Geotechnical Design	9
Structural Design	11
Environmental Design	13
Water Systems and Drainage Design	14
Traffic Analysis	14
Construction Management	15
Cost Estimate	17
Conclusion	18
References	19
Appendix A: Structural Calculations	А
Appendix B: Geotechnical Data	В
Appendix C: Environmental Calculations	C
Appendix D: Water Resources Calculations	D
Appendix E: Transportation Study	E
Appendix F: Construction Scheduling	F
Appendix G: Item Cost Breakdown	G

List of Figures

Figure 1.1: Smoky Mountain Foundation Inc. Team Members	4
Figure 2.1: Location of Project	6
Figure 2.2: Current Condition of Site	7
Figure 3.1: Site Layout	8
Figure 4.1: RISAFoundation Model Plan View	12
Figure 4.2: RISAFoundation Model Soil Pressure	13
Figure 5.1: Item Cost Breakdown	18

List of Tables

Table 1.1: Student Contact Information	5
Table 1.2: Faculty and Mentor Contact Information	5
Table 4.1: Milestones with Number of Activities and Durations	16

Introduction

Smoky Mountain Foundation Inc. is a civil and environmental engineering student team dedicated to producing innovative and quality designs for engineering projects in order to best serve the needs of the clients, the community, and the environment. The team is made up of four senior civil and environmental engineering students from the University of Tennessee, Knoxville, as shown in Figure 1.1. The contact information for the student team is presented in Table 1.1.

This report contains the analyses and conclusions drawn by Smoky Mountain Foundation Inc. for the design solution for the Appalachian Electric Cooperative Substation Project working in partnership with C2RL. The scope of the project encompasses geotechnical site investigations, analyses of soil stability, structural design of the foundation, creation of a construction-ready drawing set, and an estimation of costs. Smoky Mountain Foundation Inc. worked collaboratively with multiple mentors, such as employees at CR2L and professors at the University of Tennessee, Knoxville, to accomplish this task. The contact information for the mentors on this project can be found in Table 1.2.



Figure 1.1: Smoky Mountain Foundation Inc. Team Members (Left to Right) Grayson Lane, Ben Morris, James Throckmorton, and Leah Stephens

Name	Primary Position	Secondary Position	Number	Email
Ben Morris	Environmental Designer	Construction Designer	615-278-8121	rmorri34@vols.utk.edu
Grayson Layne	Construction Designer	Transportation Designer	423-326-4425	glayne1@vols.utk.edu
James Throckmorton	Geotechnical Designer	CADD Lead	615-495-5092	jthrockm@vols.utk.edu
Leah Stephens	Structural Designer	Technical Writer	561-779-2031	lsteph24@vols.utk.edu

Table 1.1: Student Contact Information

Name	Affiliation	Email
Qiang He	University of Tennessee, Knoxville	qianghe@utk.edu
Shuai Li	University of Tennessee, Knoxville	sli48@utk.edu
John Ma	The University of Tennessee, Knoxville	zma2@utk.edu
Danny Oliver	The University of Tennessee, Knoxville	doliver2@utk.edu
Angel Palomino	The University of Tennessee, Knoxville	apalomin@utk.edu
Jenny Retherford	University of Tennessee, Knoxville	jretherf@utk.edu
Chris Soro	C2RL	csoro@c2rl.com
Ron Whittaker	C2RL	rwhittaker@c2rl.com

Table 1.2: Faculty and Mentor Contact Information

Project Introduction

The Appalachian Electric Cooperative Zinc Substation Foundation project is located in New Market, Tennessee. Figure 2.1 illustrates the location of the project, while an existing site photograph facing southwest is presented in Figure 2.2. Based on Figure 2.2, the substation will be located in the background of the photo and will only utilize approximately half of the entire site. There is an abandoned zinc mine in the construction area which may impact the possible designs for the foundation. Members of Smoky Mountain Foundation Inc. team were tasked with performing engineering design services to address the needs of the project with efficiency and ingenuity. The project requires site investigation to capture the subsurface conditions. It is specifically important to take note of the known abandoned zinc mine and the observed hachured area, both of which may indicate further subsurface instability. Ultimately, the project requires engineering services in order to inform the contractor of the necessary infrastructure to accommodate the transformers, high side breakers, low side reclosers, and the control house. Lastly, the project requires the use of special and heavy equipment that must be accommodated in the final infrastructure design.




Figure 2.1: Location of Project



Figure 2.2: Current Condition of Site

Defined Scope of Work

Based on the needs of the project, several areas of work within the civil engineering discipline must be considered. The foundation is designed to withstand the large loads of the electrical equipment while in the presence of subterranean voids from the abandoned zinc mine. Thus, geo-structural analysis and design is necessary to address the loads and the soil stability for the foundation. The environmental regulations are enforced to ensure that the fluid containment infrastructure is considered in the case of failure to avoid contamination. The sub-station requires the use of transformers of significant size, such that a failure causing a fluid leak would cause considerable environmental damage. A temporary traffic plan is developed for use during construction. This plan requires an analysis of current traffic patterns to ensure that safe accommodations are met during the temporary conditions. This analysis was done through a transportation study completed at the site. Based on the study of the existing conditions and the requirements of the project, a plan to accommodate the temporary conditions was developed, including a temporary traffic plan and construction entrances/exits. Finally, the construction schedule is created with consideration of equipment delivery and temporary roadways, and a cost analysis is produced in order to determine that the final design is reasonable in terms of the budget.

Site Conditions

One of the initial tasks was to analyze the current site conditions. The project is located at the site of an abandoned zinc mine at 1414 Flat Gap Road, New Market, Tennessee. This mining efforts resulted in a large subsurface void that is located approximately 300 feet below the topsoil. The land above the mine was used for agricultural purposes after the mining efforts were abandoned and the land has a layer of organic alluvial top soil. Several hundred feet beneath the initial topsoil, there is a bedrock layer that consists of Mascot Dolomite, as determined by referencing the USGS Geological Map of the area, which can be found in Appendix B. In addition, the site slopes gently downhill from the southwest corner of the plot to the northeast corner. A hachured contour area located on the southeast corner of the lot was discovered. This area is visible from the surface and was located during a site walk through. This hachured area indicates the future possibility of a sinkhole and must be considered in the design. The site runs parallel with Flat Gap Road, which is a two-lane rural road with a speed limit of 45 mph. A railroad bridge spans across the road on the north side of the site. The bridge has been hit by passing traffic due to the low clearance of 15 feet. All of these conditions were considered throughout the analysis and design process.



Figure 3.1: Site Layout

Analysis and Design

The project required a design of a substation foundation; therefore, an analysis of the current site conditions was performed to obtain relevant data. The project was subdivided into geo-structural design, environmental and water system design, and construction design. In addition, a traffic study and analysis were completed to better prepare for possible construction impacts to the area.

Geotechnical Design

Geotechnical design is required for this project to account for soil stability issues in the design of the foundation and to determine the area's susceptibility to Karst topography. The foundation design considered the high loads of the electrical equipment, the soil conditions, and the abandoned zinc mine, such that a preferred solution could be identified.

Although it is known that the mine was built through dolomite bedrock, which would primarily indicate stable soil conditions, the location of the abandoned zinc mine brings the stability of the soil into question. Jefferson County is a geological region that contains Karst topography, according to USGS geologic data. This abundance of karst could impact the stability of the site even if the mine is deemed stable currently. The region is susceptible to carbonate erosion. Dolomite is classified as a carbonate and has a similar reaction to water as limestone. This reaction dissolves the carbonate material and could cause the mine's ceiling to become thinner over time. Without this vertical strength, the mine may experience deformation and possibly collapse, creating a void that could damage the substation. These possible issues were the motivating factor to determine soil strength and stability.

A geotechnical consultant from GEOServices was hired to perform the site investigation for the property. The consultant identified 10 boring locations from various areas of interest on the site. These borings were drilled between 25 ft and 35 ft into the soil, with one boring drilled 120 ft below the surface to analyze the bedrock and mine ceiling. Standard Penetration Test (SPT) and split-spoon sampling tests were conducted on these borings as well.

After boring was completed, laboratory work was conducted on specimens from the field to determine soil properties. Atterberg Limits were calculated, and the soil on site was found to be a clay of high plasticity, with a Plasticity Index of 50 on average. Using this data, the unit weight of the soil was determined to be between 110 pcf and 141 pcf. Considering the site consists mainly of this clay, an undrained condition was determined and a friction angle of zero was assumed. Cohesion of the soil was determined graphically using the Skempton Method and was calculated as 1600 psf.

Due to the results found from drilling and soil properties of the site, there are several precautions that have been taken. These precautions include: proper drainage

control of the site to eliminate water seepage into the mine, grading of the site to allow water runoff to drain into the retention pond to reduce the possibility of erosion damage to the bedrock, and cement capping of the bedrock below the site to prevent water damage to the mine. This cap prevents contact between the draining water and the mine's ceiling, reducing carbonate erosion. However, based on geotechnical data collected, this team recommends that this site is at no greater risk for sinkhole development than any other site. Therefore, this plan was deemed unnecessary and not cost effective to implement.

From recommendations from geotechnical advisers, any unusable soil, which would include any remaining vegetation and topsoil, will be removed and replaced by suitable gravel. TDOT D Stone is this team's recommendation for a strong and drainage friendly gravel covering. This gravel layer will cover the entire site to fully allow for drainage across the entire site. This layer will also reduce settlement under the foundation area, due to the much higher compressive strength of gravel when compared to the removed alluvial soil.

Design of the foundation system was performed to confirm limit states of bearing capacity, differential settlement, and total settlement. For the shallow foundation design for this project, this team's recommended allowable soil bearing capacity is 3,271 psf for the soil layer beneath the site. The bearing pressure of the foundation was calculated to be equal to 564 psf, indicating that the soil will provide sufficient strength for the load. The foundation will be placed 18 inches below the surface to protect from frost because the soil does not heave under the frost layer. Thawing causes the soil to heave which in turn causes settlement. The settlement leads to displacement in cladding and the superstructure which can cause aesthetic damage. By placing the foundation 18 inches below the surface, these issues can be avoided. From the allowable soil bearing pressure of the soil, total settlement should not exceed 1 inch, with a differential settlement of ³/₄ of an inch.

After reviewing all known data, several foundation design plans were considered by Smoky Mountain Engineering. One of these plans was a shallow foundation design. Considering that this foundation would need to support multiple pieces of electrical equipment over more than 50% of the site area, a mat foundation was determined to be an ideal shallow foundation design. Using this mat foundation, steel reinforcement would be relatively simple to install, minimizing labor costs and build time. This team also considered modification of the soil under the foundation to increase the allowable strength of the soil.

Another design option considered by Smoky Mountain Engineering was a deep foundation design. The two deep foundation options discussed included drilled shafts and micropiles. Drilled shafts offer greater strength and stability versus many other shallow foundation designs. Micropiles were considered a better option when compared to drilled shafts, offering much of the strength and stability of drilled shafts with much lower overall costs. These piles are not drilled as deeply as drilled shafts, minimizing any disturbances to the mine below.

After careful consideration of all data collected and calculated for this site, this team decided to implement a mat foundation with no soil modification in the center of the site as seen in the drawings. This option was deemed to be the most cost and time effective course of action for the loads and soil strength determined. Besides the addition of gravel for drainage and soil grading, soil modification will not be considered for this foundation design. The location was chosen due to it having the least elevation change across the site, which allows for the least amount of excavation and fill to be at final grade. After reviewing data from Shelby Tube samples taken from the borings, much of the clay was found to be lean clay with a minimal expansive nature. Therefore, soil modification was deemed unnecessary to implement. Drilled shafts were deemed unnecessary because this type of foundation is very intrusive, time consuming, and expensive. The loads generated by the substation and its equipment do not warrant such methods. Drilled shafts could also disturb the zinc mine beneath the foundation site, creating unnecessary risks. Micropiles were also found to be unnecessary. The mine is over 120 ft below the surface, according to boring termination. With the mine being at such a depth and loads being relatively low, the use of micropiles or any deep foundation was determined to be too costly and too conservative for the parameters of the project. Also, based on a cost comparison of micropiles, deep foundations, and mat foundations with no soil modifications, the mat foundation was roughly 63% less expensive. Thus, a mat foundation will generate the strength necessary for all loads and will minimize settlement across the site, while also being the most financially reasonable.

This team has determined that from the all data obtained through drilling, laboratory testing, and calculations, a mat foundation will be the best design choice for this site. If all parameters of soil stability and design are taken into account, the team is confident in the functionality of this design.

Structural Design

Due to the large electrical equipment necessary for a substation, there are significant loading requirements applied to the foundation. The mat foundation was designed to support the point loads of the transformers, high side breakers, and low side reclosers, along with the distributed and area loads of the control room. Several limit states needed to be verified for the design of the mat foundation, specifically shear, flexure, 1-way shear, and punching shear.

As shown in Appendix A, the limit states were analyzed through a series of hand calculations and the use of RISA software. RISAFoundation was selected to perform structural analyses for this project by inputting site specific conditions to arrive at the optimal solution. Loading was based on values provided by C2RL from a previous project, Bean Substation, which had very similar project requirements. Loading information was gathered for the transformers, high side breakers, low side reclosers, and control house

based on the drawings found in Appendix A. In addition, the size of the entire project, a 40' by 50' footprint, was determined based on the dimensions of the equipment and control house and the available land space. Figure 4.1 shows an image of the model from RISAFoundation which was used to design the mat foundation. This image shows the layout of the site and equipment, with the estimated loads overlaid on top. The model was run and checked for each of the limit states, as described above, which it greatly exceeded. Figure 4.2 shows a visual of the soil pressure variation across the site. The soil pressure variation is fairly standard and illustrates that the loading is small compared to the strength of the design and soil integrity. In addition, outputs from this model can be seen in Appendix A.




Figure 4.1: RISAFoundation Model Plan View




Figure 4.2: RISAFoundation Model Soil Pressure

Based on analysis with the RISAFoundation software, the final strength requirements were met. The final design requires a single the mat foundation with reinforcement. The reinforcement used will be #5 bars at the top and bottom of the foundation at 18 inch spacing. The slab is 12 inches thick and utilizes 3000 psi concrete. This design also satisfies the geotechnical limit states, as outlined in the geotechnical section. Full details for construction are presented in the accompanying construction-ready drawings.

Environmental Design

The existing site conditions and safety protocols for the electrical substation calls for an environmental design that will avoid contamination of local watersheds. The analysis includes the findings and observations of the environmental conditions and required actions from Smoky Mountain Foundations Inc. The requirements include a spill containment pond that will keep oil pollution out of the local storm water drainage system in case of substation failure.

As per the EPA's oil spill protection program, the Spill Prevention, Control and Countermeasure (SPCC), the site requires a spill containment area capable of holding the amount of oil held in the transformers and voltage regulators. The spill containment area is located at the lowest elevation of the site, in the Northeast corner of the property. The total storage volume for the spill containment pond is 244.8 cubic feet. This ensures all oil will be captured from the equipment in case of failure. The containment area is lined

with a geomembrane liner to contain any oil from permeating into the ground, while still allowing water to flow through.

Water Systems and Drainage Design

The water systems design required a plan for storm water drainage to make sure the site has no water collection areas, and that the plan does not overload the local storm water drainage infrastructure. As per the Tennessee criteria for storm water design, a 25-year storm is used to measure peak runoff from the lot. In the event of a 25-year 24-hour storm, the maximum rainwater runoff discharge by 5.75 cfs, according to calculations in Appendix D.

In order to ensure storm water is drained from the site appropriately, the team designed an appropriate grading plan. Once the location was determined for the concrete slab, the grading plan was then designed around it. Since a drainage ditch was already featured along the East perimeter if the lot in the pre-existing site conditions, Smoky Mountain Foundations designed a 2 percent grade, directing storm water runoff to the East side of the lot. This slope will allow some water to be absorbed by the lot, while directing excess to the adjacent storm water ditch. The local storm water drainage system is capable of containing the peak discharge during a 25-year, 24-hour storm for the designed 2 percent grade.

The pre-existing site conditions feature a hachured contour area in which runoff is directed into a void underground. All grading must be directed away from the depression to avoid any additional runoff to be discharged into the underground void. The final grading design, including the hachured contour area are featured in the proposed layout drawing.

Traffic Analysis

A traffic study was performed to determine any traffic safety issues impacting the construction site and to ensure that the current infrastructure of the traffic system is sufficient for the transportation of equipment and materials to the site. The purpose of this study is to identify any traffic safety and infrastructure issues that may be prevented in efforts to eliminate any delays in construction. The study included a review of current traffic volumes and speed along with lane width configurations and height clearance as necessary to confirm that the current infrastructure could sustain the special traffic of delivering the equipment and materials.

Traffic Study

The traffic study was performed on 10/25/2018 in order to observe the current traffic conditions and transportation infrastructure on a portion of Flat Gap road with a speed limit of 45 mph. The study was conducted at 7:30 AM to 9:00 AM in order to observe when the traffic volume would be at its assumed AM peak during the construction work hours of the project. The AM peak of traffic volume was used to assume to be consistent

with the PM peak traffic volumes based of traffic patterns that are linked to 9AM to 5PM work cycles. In order to adequately calculate the average speed of northbound and southbound traffic, a recording of an average time through a traffic study zone was chosen versus using a radar gun in order to be more discreet so that drivers would not slow down when they noticed someone checking their speed. The study consisted of setting two markers 200 feet apart, as shown in the drawings, creating a traffic study zone that northbound and southbound traffic traveled through and recording the time that local traffic took to travel through the zone. During the traffic study, traffic had a consistent free flow without any stoppage. The number of vehicles with time recordings traveling northbound and southbound can be seen in Appendix E. The recorded times were used to find the average speed of northbound and southbound traffic study zone recorded a traffic volume of 123 vehicles per hour during peak AM times with an average speed of traffic traveling 38.77 mph.

Although the average speed was below the posted speed limit, Smoky Mountain Foundations Inc. is taking measures to slow the flow of traffic to increase the safety of the drivers and construction workers alike during delivery periods of equipment and material throughout the construction phase. During scheduled delivery periods, placing temporary construction speed limits of 25 mph for a 2 to 4 hour window along with construction warning signs to cause the drivers to drive more cautiously and at a slower speed for the time period. Reducing the vehicles speed from 45 mph to 25 mph will reduce the needed stopping sight distance from 360 feet to 115 feet, allowing the vehicles sufficient space to stop within the construction zone. Based off the MUTCD procedures, the construction warning signs will be placed 360 feet, per MUTCD Table 6C-2, away from the farthest north and south extents of the construction zone as shown on the Traffic Study drawing. The same warning signs will also be place at every 100 feet, per MUTCD Table 6C-1, approaching the construction site as shown on the Traffic Study drawing. Reducing the speed traffic and providing proper warning will ensure that the construction workers can safely enter and leave the site by allowing the normal traffic and construction works more time to react. This extra time is critical when construction vehicles are towing long trailers that take extended periods of time to maneuver in and out of the site.

Construction Management

Construction design is required for this project to accurately articulate the scheduling, sequencing, resources (labor, equipment, material) needed to construct the foundation within the allotted budget, and the completion date. The two major focuses on the construction design of this project was scheduling and quantity takeoffs. Scheduling the activities in the correct sequence was emphasized in order to prevent any delays. Correctly calculating the quantities of materials resulted in an accurate project value and duration.

Construction Scheduling

The critical path method (CPM), with an emphasis on using a linear path, was used to determine scheduling of each activity and duration of the project. The focus on using a linear path was chosen so that the floats of each activity could be minimized to reduce any lag periods or delays in the schedule. To determine the preliminary phases of the project and the activities of each phase, a work breakdown structure was constructed, which can be seen in Appendix F. The duration of each activity was calculated using the RS Means values of each activity. As appropriate, durations of some activities were determined based on quantity takeoffs from the design drawings and RSMeans values. The activities were scheduled in a sequencing order to establish the required work according to the necessary actions in the construction process which can be seen in Appendix F. Using CPM, the forward pass of the schedule was used to calculate the early start and finish of each activity, while the backward pass of the schedule was used to calculate the early Monday through Friday and 8 hours in length. Table 4.1 shows the three planned milestones along with the duration of each milestone.

Milestone	Number of Activities	Duration (days)
Temporary Construction Entrance	2	2
Site Development	8	27
Substation Foundation	7	23
Total	17	52

Table 4.1: Milestones with Number of Activities and Duration	ns
--	----

Site Development

The excavation for the foundation had a calculated borrow of 26 cubic yards which is negligible considering the site had a total cut and fill of 1953 cubic yards. The 26 cubic yards of fill will be borrowed from a portion of the site where the final grade is not important to reduce cost and time. A 212' long by 137' wide oval staging area surrounding the foundation will be placed to accommodate the storage of material, equipment and contractor parking. The staging area can be seen on the Proposed Layout drawing. A 220' long by 20' wide temporary road will be used to connect Flat Gap Road and the staging area, as seen in the drawings. The staging area and temporary road will be constructed of 4" bedding of TDOT D Stone to support the loads displaced by construction vehicles and equipment.

A temporary construction entrance will be used to accommodate the trucks delivering the various substation equipment and machinery onto the site, due to their formidable weights and dimensions. These trucks displace a distributed load of up to 60 kips dispersed along the length of the truck and trailer on the entrance and staging area. The existing soil conditions would not be able to support the truck's load due to the stability of the current topsoil. A construction entrance was designed as a temporary


bridge using a 24" diameter Class 3 Concrete Pipe with an 8" bedding of TDOT D Stone and up to 18' of TDOT D Stone on top of the pipe. This design will allow the bridge to support an ultimate load of 4000 lbs. per horizontal linear foot of the bridge according to the CPDM. While many construction entrance configurations are feasible, a pipe and stone design that allows drainage across the entrance and ease of access into the site was selected to accommodate the anticipated 60 kip truck loads. The temporary construction entrance will be placed along the edge of Flat Gap Road and the center of the eastern side of the site which can be seen in the Construction Entrance drawing. This location was chosen to allow for a stopping site distance that allows traffic to adequately react to vehicles entering and leaving the construction site.

Erosion Control Plan

Smoky Mountain Foundation Inc. followed procedures in accordance to the Clean Water Act (CWA), the local standards for the Tennessee Department of Environment and Conservation. The team designed an erosion control plan to avoid local storm water drainage system overflow and pollution into local watersheds. A 3-foot-tall silt fence along the East and North perimeter was sufficient for the site because it satisfies EPA standards of 100 feet of fencing per 1/4 acre, and the slope never exceeds a 3:1 slope gradient, as shown in Appendix D. The silt fence should be arranged as shown in the erosion control drawings.

Cost Estimate

Based on the design described previously, the cost was estimated. The costs associated with the project have been divided into three subcategories of labor, material, and equipment cost. A summary cost estimate with information such as unit, quantity, unit price, and total price has been provided in Appendix G. The largest contributors to the total cost is material with an estimated cost of \$138988.92. The total cost estimate for the project was determined to be \$196113.53. Figure 5.1 provides a visual illustration showing the cost breakdown per item. By breaking down the costs into three categories, labor, materials, equipment can be seen that materials provide the greatest portion of the total cost.



Division	Cost
Material	138988.92
Labor	31558.66
Equipment	25565.95
Total	196113.53

Figure	5.1:	ltem	Cost	Breakdown
--------	------	------	------	-----------

Conclusion

Smoky Mountain Foundations Inc. has proposed a mat foundation for the Appalachian Utility Board's substation project located in New Market, Tennessee. This foundation was the preferred solution from multiple options and satisfied the structural and geotechnical requirements. A spill containment pond was designed for the northwest corner of the lot to satisfy substation safety protocols. A uniform 2 percent grading plan towards the Northeast corner of the site, and away from the hachured area allowed for the most optimal drainage plan. The total duration of the project was calculated to be 52 working days. The costs for the project were also determined using the RSMeans and TDOT standard pricing index. Based on these values, the project will cost \$196113.53 in total to implement.


References

- 1. "Acid Mine Drainage." *Mineral Processing & Metallurgy*, 11 Feb. 2018, <u>www.911metallurgist.com/blog/acid-mine-drainage</u>.
- 2. Average Unit Prices. Tennessee Department of Transportation, 2017, www.tn.gov/content/dam/tn/tdot/construction/old_web_page/aup2017.pdf.
- 3. Bates, Bruce. "Rapid Interactive Structural Analysis." *RISAFoundation*, RISAFoundation, 2018, risa.com/p_risafoundation.html.
- 4. Building Code Requirements for Structural Concrete: (ACI 318-14) ; and Commentary (ACI 318R-14). American Concrete Institute, 2014.
- 5. Carlson, Erik. *Alternative Foundation System*. pp. 18–25, *Alternative Foundation System*.<u>https://www.engr.psu.edu/ae/thesis/portfolios/2009/ejc5000/Website%20</u> Files/Analysis%201.pdf
- 6. "Concrete Pipe Design Manual." *American Concrete Pipe Association,* 2011, <u>https://www.concretepipe.org/wp-content/uploads/2014/09/cp-manual.pdf</u>
- 7. "Limestone." *Minerals Education Coalition*, mineralseducationcoalition.org/minerals-database/limestone/.
- 8. "Limestone: The Calcium Carbonate Chemical Sedimentary Rock." *Geology*, geology.com/usgs/limestone/.
- 9. "National Menu for Best Management Practices." United States Environmental Protection Agency, July 2018, <u>www.epa.gov/npdes/national-menu-best-</u> <u>management-practices-bmps-stormwater#edu</u>
- 10. "Reference Guide to Work Zone Traffic Control." *Occupational Safety and Health Administration*, Jan. 2011, <u>www.osha.gov/dte/grant_materials/fy10/sh-21004-</u> <u>10/wztc_refguide.pdf</u>.
- 11. "Soil Survey of Cocke County Area, Tennessee." *Natural Resources Conservation Service*, 2001, <u>https://www.nrcs.usda.gov/Internet/FSE_MANUSCRIPTS/tennessee/TN606/0/Co</u> <u>cke_TN.pdf</u>
- 12. SPCC Guidance for Regional Inspectors. *Environmental Protection Agency*, 2014, <u>https://www.epa.gov/sites/production/files/2014-04/documents/b_40cfr112.pdf</u>
- Stormwater Hydrology. Structural BMPs, 2008, w.knoxcounty.org/stormwater/manual/Volume%202/knoxco_swmm_v2_chap3_ja n2008.pdf
- 14. Tennessee Erosion and Sediment Control Handbook. *Tennessee Department of Environment and Conservation, 2012.*


- 15. "Tennessee Geologic Map Data." *USGS*, 2014, <u>https://mrdata.usgs.gov/geology/state/state.php?state=TN</u>
- 16. "Manual on Uniform Traffic Control Devices for Streets and Highways", US. Department of Transportation, 2009. <u>https://www.govinfo.gov/content/pkg/FR-2009-12-16/pdf/E9-28322.pdf</u>
- 17. Building Construction Cost Data. R.S. Means Co., 2004.

Appendix A: Structural Calculations

$$\frac{100 \text{ k}}{100 \text{ k}} \frac{100 \text{ k}}{100 \text{ k}} \frac{10$$



	О SHT 1 ог 1 D	-10
4	ORDER No. 239346	
	MATERIAL ID: CCDT1-72.5FK-001	
	.T 12002 N 2 22216 N-m 196	
	10) HV TERMINAL STATIC VERTICAL FORCE = 750N (169 lbf)	
	HV TERMINAL STATIC HORIZONTAL FORCE	
	(0.29 USED FUR ANCHOR BULI CALCULATION) OPERATIONAL FORCES IN ANY DIRECTION = 1100N (247 lbf)	
	FOUNDATION TO BE	
Ċ		
ວ	FOUR	
	rg) IVIAL WEIGHT DIMENSIONS: INCHES	+ Kg)
		i kg)
	BREAKEF	5
	VOLTAGE: 72.5 KV	
	IMPULSE WITHSTAND: 350 kV	
	TYPE: DT1-72.5FK F1	
i	T EMERGENCY TRIP PUSHBUTTON	
\sim	S EXTERNAL GFI RECEPTACLE	
	M RATINGS NAMEPLATE (EXTERNAL) N BCT NAMEPLATE (INTERNAL)	
	K NEMA 2 GROUND PAD (DIAMETRICALLY OPPOSED)	
	G LIFTING LUGS	
	F CABLE ENTRANCE	
	E2	-
	E1	2.0
	D SF6 DENSITY MONITOR	
-	B NEMA 4-HOLE TE	Ы
<u>ــــــــــــــــــــــــــــــــــــ</u>	A2 MINIMUM DISTANCE FOR BUSHING REMOVAL (27 inches / 686 mm)	പ്ര
	A1 MINIMUM DISTANCE FOR INTERRUPTER REMOVAL (65 inches / 1650 mm)	
	LEGEND	
	D	



sale of apparatus	basis for the manufacture or					
known generally in h it is established t vese drawings and s	contained herein which is not known generally in except to any extent to which it is established Modular Connections, LLC. These drawings and s			ГССО-1477-Г	-	57
				WW#2E816	; -	56
	THE KVA, INC.		COMPRESSION FITTING, #2/0 TO #6 WIRE PANDUIT	CTAPF2/0-12-Q	-	55
	Bessemer, Al 35022		SWITCH, 600A 240VAC 3P MTS N1 SQ-D (CUSTOMER SUPPLIED MC INSTALLED)	DTU326	N	54
ONNECT			PANELBOARD, 225A LUG 125VDC FLINE 99" SQ.D	HCM50912N		53
	REV NO.		REINFORCEMENT ANGLE NARROW FRAME BRACKET PDQ FOR EXTERIOR DOORS	ANGLE #999011		52
L REVISIONS	R1 GENERAL		CONTACTOR, 240V 2P N.O. NEVA 1 GE	CH CR463L2UASA14AU		51
MIRROR I	"MAY BE BUILT		PUSH BUTTON, METAL 30MM 600V AC 10A UNIVERSAL SQ.D.	9001KR1U	· N	50
TION. TN	IN PLAN NUMB		LIGHTING CONTACTOR PHOTOCELL, 120V TWISTLOCK FISHER PIERCE	FP120		49
			240V AC 50A 2 POLE N.O. CONTACTOR, 208/ENCLOSURE	5B104		48
			CONTACTOR BLOCK, 30MM 600VAC 10A N.O. SQ.D.	9001KA3	-	47
FLOOF	- INDICATES RECEPTACLE GROUP.		CONTACTOR BLOCK, 30MM 600VAC 10A N.O. SQ.D.	9001KA2		46
INT. C			LIGHTING CONTRACTOR PHOTOCELL RECEPTACLE, 120V TWISTLOCK FISHER PERCE	FPNS476-71		45
INT. V			TY RAP MOUNTING BASE	ES12411	50	44
			SPILL CONTAINMENT, C&D	SP42092P	!	
	Ē		WIRE #6 STRANDED GREEN INSULATED	580011G	150FT	
	101LDING SHALL NOT EXCE		STEAD CEDILIND CONTRINCTOR SI IEROET 2" NALON EDE HALO MIRE DA NINI IT (STD)			4
			1-5/8" X 1-5/8" BY 18" LONG SLOTTE	ES1121	4	39
Γ	VENTILATION SHALL BE PROVIDED AT A RATE NOT LESS THAN T CUBIC FOOT PER MINUTE PER SQUARE FOOT OF FLOOR AREA OF ROOM.			ES1121	N	38
PUE	TO 1% OF THE TOTAL VOLUME OF THE ROOM; OR 2.) CONTINUOUS		STRUT, 1-5/8" X 1-5/8" X 30" LONG SLOTTED ZINC PLATED	ES1121	∞	37
ITEN	FOLLOWING ALTERNATIVES MOST ALSO BE INSTALLED: 1.7 AN EXTRAOST FAN WITH A HYDROGEN LIMIT SWITCH SO THAT TO LIMIT THE HYDROGEN		WIRE, #2/0 BARE STRANDED COPPER	580030	60FT	36
6. TP	GALLONS ARE TO BE INSTALLED WITHIN THIS BUILDING, ONE OF THE		GROUND CLAMP, #4-300MCM SINGLE WIRE TO FLAT BRONZE 2 PECE WITH SS HARDWARE ANDERSON HUBBELL (STD)	GC141A02	1	35
.5. 4 구 구 7	9)IF BATTERIES WITH AN ELECTROLYTE CAPACITY OF MORE THAN 50		CABLE TRAY, 24" HORZ. REDUCING TEE TO 12", 4" THK WITH 12" RADUIS FLG IN HUSKY	ALJA-24T12-12	2	34
2			CABLE TRAY, 24" HORIZ. REDUCING TEE TO 18", 4" THK WITH 12" RADUIS FLG IN HUSKY	ALJA-24T18-12		_
1(Sf	8) AFTER FABRICATION OF UNISTRUT AND ALL THREAD ROD SPRAY WITH		CABLE TRAY, 12"W X 4"THK X 12' LONG FLG IN ALUMINUM HUSKY	A9JA-12-144	1PC	
ĒŌ	7)USE 18 AWG THHN WIRE FOR ALL ALARM WIRES.		CABLE TRAY, 18"W X 4"THK X 12' LONG FLG IN ALUMINUM HUSKY	A9JA-18-144		
3. PE				A 9.1A-24-144		
2. P[CABLETEAV 24"WAY A"THE ON DEC VEET OF TSIDE ELEONA 13" BAINING ELEONAL INVERSES	VI IN 24VOOD 12	<u> </u>	200
			ANDERSON HUBBELL		5	22
NC			GROUND CLAMP; #4-300MCM DOUBLE WIRE TO FLAT BRONZE 2 PIECE WITH SS HARDWARE	00143000	÷ +	2 ⁷
	5)DOOR LOCKSET INSIDE LEVER HAS AN ANSI F13 FUNCTION THAT		GEOLIND BAD 1/4" X 4" X 14" (NO HOLES) CODEEDTINNED DI ATE	04JUZ	<u> </u>	36
			WINDOW 24"H X 36"W HORIZONTAL SLIDING W SCREEN		\ 	24
	INSTALLED TIEMS ARE SUBJECT TO LOCAL REVIEW, APPROVAL AND INSPECTION PROCESS.		RELAY PANEL (CUSTOMER PROVIDED MC INSTALLED)		<u> </u>	23
	IN THE APPROVAL PROCESS ARE TO BE SITE INSTALLED. ALL SITE	<u> </u>	FAN, 12" EXHAUST 2750 CFM SHUTTER MTD WITH SCREENED HOOD TPI CORP	CE 12-DS		22
	4)LOCAL BUILDING OFFICIALS: ALL THE ITEMS THAT ARE NOT COVERED		LOUVER, 12" X 12" MOTORIZED WITH DAY TON	WW #4C556		21
	3)ALL SERVICE ENTRANCE EQUIPMENT SHALL BE LISTED FOR IT'S USE.		SWITCH, 600VDC 3W NONFUSABLE (CUSTOMER SUPPLIED MC INSTALLED)			20
			EYEWASH STATION, SELF CONTAINED FEND-ALL	PUREFLOW 1000	<u>→</u> ;	19
	ALL WIRE IS RATED AT 90°C W/75°C RATED LUGS.		PROVIDED MC INSTALLED) BATTERIES, 100AH 125VDC (4 CELLS PER JAR) C&D (CUSTOMER PROVIDED MC INSTALLED)	4JC-100	5	18
	2)ALL MIRE AMPACITIES BASED ON TABLE 310–16 NEC, 310–15(b)(2)(a).		BATTERY CHARGER, 30A 130VDC OUTPUT 240VAC INPUT W/ ALARMS HINDLE (CUSTOMER	AT1013030E240SXSXAGLXP	<u> </u>	17
			SWITCH, 20A 120-277 TOGGLE SPST NORY HUBBELL	CS12211	1 ω	16
	1)MAIN DISCONNECT GROUND WIRE MUST BE ATTACHED		EMERGENCY LIGHT. (2)HEAD LED WITH BATTERY BACKUP LITHONIA (STD)	EML2LEDM12	- 0	15
	NULES:		LIGHT, 36W LED MEDIUM WALL FACK INST EMERGENCY/EXIT I GHT 120/277VAC (2)HEAD I ED WIRATT RACKIPI (THONIA (STD)	FCRI FDM6		14
		1	RECEPTACLE, 20A 120V DUPLEX NORY HUBBELL (STD)	CR53521	• ∞	12
			FLOORMOUNT HALF DOME CHROME	1426A41	1	11
	32-001050-0000	п	THERMOSTAT, FOR HEAT PUMP AUTO CHANGEOVER BARD (STD)	8403-058	<u> </u>	10
	CABLE TRAY, 24"W X 4"THK X 21' LONG ALUMINUM FLG IN HUS		HEAT PUMP, 2 TON 1PH 60A WITH 8KW HEAT BARD GRAY	W24H1-A08XP4XXE	<u> </u>	9
	C-1203636FSRH ENCLOSUR	0	PANELBOARD, 200A MB 120/240V AC 1PH 42 POSITION SQ.D	NQ42L2C	2	œ -
		נת	LOAD CENTER, 100A ML 120/240VAC 1PH 12 POSITION SQ.D	Q0112L125G	2	7
D	PACK IN SHELTER		LOCKSET, PANIC PDQ 3'2"-4'0" DOOR WILEVER TRIM & IC MORT HOUSING LESS CORE PDQ	4208RA689429LPEKFH-071C-LC	-	6
		64	DOOR STOP, WITH HOOK BURNS (STD)	531US26D	-	σ
		63	DOOR, LITE KIT 24"W X 30"H 1-3/4 THICK DOOR BRONZE W/ CLEAR WIRESHIELD GLASS & GLAZE TAPE AIR LOUVERS	VSL 2403 WS PAK	ω	4
	RUBUOU3-7.3EF2F	σ×	DOOR PULL, 12-1/8" LG X 1/2" DIA ALUMINUM, MOMASTER (STD)	1871A65	-	3
	AWN4-232-EU	s g	DOOR, 3' X 7' INSULATED STEEL 20GA PAINTED WHITE FOR INTERIOR (STD)	CECO	-	2
	MR136 PFEF		DOOR, 4080 18GA GALV UH BLANK 4-1/2" X 4-1/2" HINGE CLSR REINFORCED PRIME PAINTED			
		59	DESCRIPTION	MANUF. P/N	QTY	IT.#
		58	EQUIPMENT LIST			

TENNESSEE PROJECT DATA

DESIGN LOADS: FLOOR LIVE LOAD (THROUGHOUT) FLOOR DEAD LOAD MAX. (THROUGHOUT) ROOF LEVE LOAD ROOF LEVE LOAD GROUND SNOW LOAD FLAT ROOF SNOW LOAD FLAT ROOF SNOW LOAD SNOW LOAD IMPORTANCE FACTOR SNOW LOAD IMPORTANCE FACTOR THERMAL FACTOR ULTIMATE WIND SPEED (3-SEC GUST) SEISMIC IMPORTANCE FACTOR RISK CATEGORY WIND CLASSIFICATION WIND LOAD HORIZONTAL (MWFRS) WIND LOAD HORIZONTAL (C & C) DESIGN CODES: 2006 INTERNATIONAL BUILDING CODE 2006 INTERNATIONAL MECHANICAL CODE 2006 INTERNATIONAL PLUMBING CODE 2006 INTERNATIONAL FUEL GAS CODE 2006 INTERNATIONAL FIRE CODE 2008 NATIONAL ELECTRIC CODE 2008 NATIONAL ENERGY CONSERVATION CODE PER SECTION 501.2, USE 2006 INTERNATIONAL ENERGY CONSERVATION CODE PER SECTION 501.2, USE 2006 NATIONAL ENERGY CONSERVATION CODE PER SECTION 501.2, USE 2006 INTERNATIONAL ENERGY CONSERVATION CODE PER SECTION 501.2, USE 2006 NATIONAL ENERGY CONSERVATION CODE PER SECTION 501.2, USE 2006 INTERNATIONAL ENERGY CONSERVATION CODE PER SECTION 501.2, USE 2006 INTERNATIONAL ENERGY CONSERVATION CODE PER SECTION 501.2, USE 2006 INTERNATIONAL ENERGY CONSERVATION CODE PER SECTION 501.2, USE 2006 INTERNATIONAL ENERGY CONSERVATION CODE PER SECTION 501.2, USE 2006 INTERNATIONAL ENERGY CONSERVATION CODE PER SECTION 501.2, USE 2006 INTERNATIONAL ENERGY CONSERVATION CODE PER SECTION 501.2, USE 2006 INTERNATIONAL ENERGY CONSERVATION CODE PER SECTION 501.2, USE 2006 INTERNATIONAL ENERGY CONSERVATION CODE PER SECTION 501.2, USE 2006 INTERNATIONAL ENERGY CONSERVATION CODE PER SECTION 501.2, USE 2006 INTERNATIONAL ENERGY CONSERVATION CODE PER SECTION 501.2, USE 2006 INTERNATIONAL ENERGY CONSERVATION CODE PER SECTION 501.2, USE 2006 INTERNATIONAL ENERGY CONSERVATION CODE PER SECTION 501.2, USE 2006 INTERNATIONAL ENERGY CONSERVATION CODE PER SECTION 501.2, USE 2006 INTERNATIONAL ENERGY CONSERVATION CODE PER SECTION 501.2, USE 2006 INTERNATIONAL ENERGY CONSERVATION CODE PER SECTION 501.2, USE 2006 INTERNATIONAL ENERGY CONSERVATION CODE PER SECTION 501.2, USE 2006 INTERNATIONAL ENERGY CONSERVATION CODE PER SECTION 501.2, USE SEISMIC IMPORTANCE FACTOR SEISMIC USE GROUP SPECTRAL RESPONSE ACCELARATION S" SEISMIC DESION CATEGORY STE CLASS BASIC SEISMIC-FORCE RESISTING SYSTEM DESIGN BASE SHEAR ANALYSIS PROCEDURE OCCUPANCY USE GROUP CONSTRUCTION TYPE MINIMUM SETBACK WIND LOAD (UPLIFT) (C & C) WIND LOAD HORIZONTAL (WINDOW & DOOR) 1.25 D D BEARING WALL SYSTEM - SPECIAL 0.2W EQUIVALENT LATERAL-FORCE PROCEEDURE S2 UNSPRINKLED SEE NOTE 3 FOR COMMON OR ASSUMED PROPERTY LINE TO COMPLY WITH IBC TABLES 602 & 704.8 ±0.18 42.1 PSF 62.9 PSF (ZONE 4) 81.6 PSF (ZONE 5) 39.8 PSF (ZONE 5) 40.1 PSF (ZONE 5) 52.9 PSF (ZONE 5) 52.9 PSF (ZONE 2) 91.9 PSF (ZONE 3) 110 PSF (OPTIONAL 200 PSF) 36 PSF 50 PSF 52.2 PSF 50 PSF 50 PSF 1.2 1.2 1.2 1.0 1.0

IOTES:

- THE INTENDED OCCUPANCY OF THIS EQUIPMENT SHELTER IS FOR PERFORMING THE REQUIRED SERVICE/MAINTENANCE OF EQUIPMENT ONLY.
 PER IBC 2006 TABLE 720.1(2), 4" SAND-LIGHTWEIGHT CONCRETE WALLS HAVE FIRE RESISTANCE RATING OF 2 HOURS WITH UNPROTECTED OPENINGS.
 PER IBC 2006 TABLE 705.8, ANY WALL W/ 10% OR LESS OF UNPROTECTED OPENINGS MAY UTILIZE A SETBACK GREATER THAN 5'-O'. ANY WALL W/ 15% OR LESS OF UNPROTECTED OPENINGS MAY UTILIZE A SETBACK GREATER THAN 10'-O". ANY WALL W/ 25% OR LESS OF UNPROTECTED OPENINGS MAY UTILIZE A SETBACK GREATER THAN 15'-O". ANY WALL W/ 45% OR LESS OF UNPROTECTED OPENINGS MAY UTILIZE A SETBACK GREATER THAN 20'-O". ANY WALL W/ UNPROTECTED OPENINGS MAY UTILIZE A SETBACK GREATER THAN 5. THE USE OF THIS SHELTER WITHOUT RESTROOM FACILITIES IS SUBJECT TO LOCAL REVIEW AND APPROVAL.
 THES STRUCTURES ARE NOT DESIGNED FOR FLOOD HAZARD AREAS.
- ITEMS TO BE SITE INSTALLED & SUBJECT TO LOCAL CODE REVIEW & COMPLIANCE AND ARE NOT INSPECTED BY THE THIRD PARTY: FOUNDATION, CONNECTION TO PUBLIC UTILITIES, SITE WORK, ETC..


FINISH COLOR SCHEDULE

EXT. WALLS: EXPOSED AGGREGATE -EXT. TRIM: MINDFUL GRAY COARSE EXT. DOORS: MINDFUL GRAY INT. WALL & CEILING: STANDARD FINI INT. DOOR(S): SAME AS EXTERIOR CO FLOOR: URETHANE PAINTED GRAY W, WALLS: EXPOSED AGGREGATE - GREYSTONE GRAY

T. WALL & CEILING: STANDARD FINISH T. DOOR(S): SAME AS EXTERIOR COLOR OOR: URETHANE PAINTED GRAY W/ ANTISKID

ODEL #MCL801

SER: MODEL #MCL801 ATION, TN MIRROR IMAGE"				
AL REVISIONS			11-15-17	CRR
DESCRIPTION			DATE	DWN BY
565	DRAWN BY	DATE	JOB NO.	
Fax: 877–675–5851 Email: info@ModularConnections.com	모	9-26-17	9-26-17 MCP983-MC4334	4334
	SCALE		PROJ MGR	
LIST FOR 16' X 28' X 9'8" IH SHELTER	NA		СLР	
specifications are the property of Maduar Connections LLC. All information of lower generally in the field of Maduar Connections, LLC and its confidential by it is established to have been known previously from sources other than these drawings and specifications may not be reproduced, capied or used as the pr sale of opportaux without writtle permission.	DRAMING NO.	D16230 R1		SHEET 01



DESCRIPTION			DATE	DWN BY
ECTIONS. LLC Phone: 205-980-4565	DRAWN BY	DATE	JOB NO.	
Fax: 877-675-5851 Email: info@ModularConnections.com	모	9-26-17	9-26-17 MCP983-MC4334	334
	SCALE		PROJ MGR	
h shelter	NA		CLP	
and the property of Modular Connections, LLC. All information	DRAWING NO.			SHEET
Intentiny in the new or would connections, the situative connection abilished to have been known previously from sources other than ngs and specifications may not be reproduced, copied or used as the pparatus without written permission.	D162	D16230 R1		02

11-15-17

CRR


STANDARD CONDUIT FITTINGS ARE DIECAST SET-SCREW TYPE EMT FITTINGS UNLESS SPECIFIED OTHERWISE ON DRAWING

NOTES: 1)'LV' DESIGNATES LOW VOLTAGE CONDUIT. 2)'P' DESIGNATES PVC CONDUIT.


CONDUIT KEY

(R) G = 3" (LV) (R) H = 4" (LV)







Plan View of Model




Soil pressure






QX




ΜZ



MXZ

Strip:	DS1	Max Top bar Spac.:		Stress Block:	Rectangular
Material:	Conc3000NW	Min Top bar Spac.:		Rebar Orientation:	0
Strip Width: Total Cuts:	600.39 in 50	Max Bot bar Spac.: Min Bot bar Spac.:	18 in	Rebar Spacing Inc: Design Rule:	-



ACI 318-11 Code Check

Top Bending Check	0.173	Bot Bending Check	0.326	1 Way Shear Check	0.131
Gov Mu Top	78.692 k-ft	Gov Mu Bot	-148.513 k-ft	Gov Vu	65.691 k
phi*Mn Top	455.096 k-ft	phi*Mn Bot	455.096 k-ft	phi*Vn	502.522 k
Governing Cut	DS1-X23	Governing Cut	DS1-X44	Governing Cut	DS1-X43
Tension Bar Fy	60 ksi	Concrete Weight	.145 k/ft^3	Top Cover	1.5 in
Shear Bar Fy	60 ksi	λ	1	Bottom Cover	1.5 in
F'c	3 ksi	E_Concrete	3156 ksi	Side Cover	3 in
Flex. Rebar Set	ASTM A615	Prvd Bot Bar Spac.	#5@18in	Prvd Top Bar Spac.	#5@18in

Bending St	eel Reqd/Prvd,	Units: in^2)				
Cut Label	Top As Reqd	Top As Prvd	Bot As Reqd	Bot As Prvd	Rho Reqd(T/S)	Rho Prvd(Gross)
DS1-X23	1.722	10.124	NA	10.124	0.00180	0.00281
DS1-X44	NA	10.124	3.26	10.124	0.00180	0.00281
DS1-X43	NA	10.124	2.355	10.124	0.00180	0.00281

Structural Calculation

Load 1 (k) Load 2 (k) Load 3 (k) 4.	40
Soil Bearing Capacity (psi) Soil Bearing Capacity (psi) Compressive strength of concrete (f'c) (p: 3) Load 1 (k) Load 2 (k) Load 3 (k) 4.	40
Compressive strength of concrete (f'c) (p. 3) Load 1 (k) Load 2 (k) Load 3 (k)	50
Load 1 (k) Load 2 (k) Load 3 (k) 4.	7
Load 2 (k) Load 3 (k) 4.	000
Load 3 (k) 4.	110
	110
Load 4 (k) 4.	659
	659
Load 5 (k) 0	.74
Load 6 (k) 0	.74
Height (feet)	1
Weight of Reinforced Concrete (lbs/ft3)	150

100K 100K 300K Ih losi=w 15' 15' 15



Flexure

Punching Shear


1-Way Shear

Calculations


εs


Converting soil bearing capacity load (2016 300 Load of concrete (k) Area of steel (inches2) 0.2 Compressive strength of steel (psi) 60000 c (inches) 0.0092272203 Height (inches) 3.0153787 Unrealistically small, will assume larger height for constructability purposes 0.01


d (inches) 0.00025125 Does not yield φVn 530.798 Less than soil bearing capacity=good φMn 65.64705882 0.007843137255 a (inches)



Will compare to Vu and Mu and draw shear and moment diagrams when I receive loading information







Appendix B: Geotechnical Data

		E C				Substatio					LOG OF BORING B-1
	C. Geetechnic	al and Materials Eng				City, Tenr					SHEET 1 OF 2
GEWJERVICES, LLL	L-Beolechnic	ai anu iviateriais Eng	lineers	G	EOService	s Project # 2	1-190	57			DRILLER B. Snow
BORING NO.					B-1						ON-SITE REP
			0	0,105		4050.0			D	RTU	
DATE REFUSAL:		lanuary 31, 201 No D		FT.		1252.0	FT.				WATER LEVEL DATA (IF APPLICABLE) COMPLETION: DEPTH DRY FT.
SAMPLED		25.0 FT.	7.6				- F I.				ELEV. FT.
TOP OF ROC				FT.	ELEV.		FT.				AFTER 1 HRS: DEPTH TNP FT.
BEGAN COR	ING	C	EPTH	FT.							ELEVFT.
FOOTAGE C		-		FT.							AFTER 24 HRS. DEPTH TNP FT.
BOTTOM OF	HOLE D	DEPTH	25.0	FT.	ELEV.	1227.0	FT.				ELEVFT.
BORING AD	/ANCED	BY:		POWER A	UGERING	Х	•				PROPOSED FFE: FT.
STRATU		SAMPLE		SAMPLE		FIELD		LABOR			
DEPTH		FROM	TO	OR	SAMPLE	RESULTS	1		SULTS		STRATUM DESCRIPTION
FT.	ELEV.	FT.	FT.	RUN NO.	TYPE	N-Value	Qu	LL	PI	%M	
_											Topsoil (12 Inches)
_		4.0				4 - 3 - 3					_
—		1.0	2.5	1	SS	N = 6					F
2.5 -	1249.5										-
-											F
—		3.5	5.0	2	SS	4 - 7 - 8 N = 15					–
-	1017.0	5.5	5.0	2		N = 15					-
5.0 —	1247.0										
_											Lean CLAY (CL) - dark reddish brown - moist -
-		6.0	7.5	3	SS	5 - 8 - 13 N = 21					- firm to very stiff
7.5 -	1244.5	0.0		0							(RESIDUUM)
7.5 -	1244.5										Ľ
-						0 40 40					-
-		8.5	10.0	4	SS	6 - 10 - 10 N = 20					F
10.0 —	1242.0										-
-											-
-											–
_											-
12.5 -	1239.5										_
-											<u>-</u>
-						3 - 5 - 7					-
-		13.5	15.0	5	SS	N = 12					F
15.0 —	1237.0										–
-											- Fat CLAY (CH) - with trace chert gravel -
											 orangish brown - moist - stiff to firm (RESIDUUM)
_											
17.5 -	1234.5										-
				_		3 - 3 - 4					<u> </u>
- 1		18.5	20.0	6	SS	N = 7					-
20.0 —	1232.0										Continued
REN	ARKS:										

GE					Substation					LOG OF BORING B-1
GEOServices, LLC-Geotechnica	al and Materials Eng	ineers			City, Tenn					SHEET 2 OF 2
,			GI	=OService	s Project # 2	1-190	57			DRILLER B. Snow ON-SITE REP.
BORING NO. / LOCAT	ION			B-1				DF	RY ON	I COMPLETION ? Yes
DATE J	•	9	SURF		1252.0	FT				WATER LEVEL DATA (IF APPLICABLE)
		EPTH		-	.202.0					COMPLETION: DEPTH DRY FT.
	25.0 FT.	7.6	М	-						ELEV. FT.
TOP OF ROCK	D	EPTH	FT.							AFTER 1 HRS: DEPTH TNP FT.
BEGAN CORING		EPTH		ELEV.		FT.				ELEVFT.
FOOTAGE CORED (LF			FT.							AFTER 24 HRS. DEPTH TNP FT.
		25.0		-	1227.0	FT.				ELEVFT.
BORING ADVANCED				UGERING	X					PROPOSED FFE:FT.
STRATUM DEPTH	SAMPLE	то	SAMPLE	SAMPLE	FIELD RESULTS		LABOR	ATORY SULTS		
FT. ELEV.	FROM	FT.	RUN NO.	TYPE	N-Value	Qu	LL	PI	%М	STRATUM DESCRIPTION
					• uide					(continued)
_										-
-										-
—										Fat CLAY (CH) - with trace chert gravel -
22.5 – 1229.5										orangish brown - moist - stiff to firm
_										(RESIDUUM)
—	23.5	25.0	7	SS	3 - 3 - 4 N = 7					–
-	20.0	20.0	1	00	1 1 = 7					-
25.0 <u> </u>										Boring Terminated at 25.0 Feet
_										_
-										-
<u> </u>										–
27.5 = 1224.5										<u> </u>
-										-
—										–
- 30.0 - 1222.0										-
-										_
—										–
-										-
32.5 - 1219.5										-
—										–
-										-
										<u> </u>
35.0 <u> </u>										–
-										-
—										-
37.5 - 1214.5										-
										F
-										<u> -</u>
										-
40.0 — 1212.0										l
REMARKS:										

GE		2			Substation					LOG OF BORING B-2	
GEOServices, LLC-Geotech	nical and Materials En	uineers			City, Tenn					SHEET 1 OF 2	
,			G	EOService	es Project # 2	1-190	157			DRILLER B. Snow ON-SITE REP.	
BORING NO. / LOC/	ATION			B-2				DI	RY OI	N COMPLETION ? Yes	
	January 31, 20	19	SURF		1250.0	FT.		•		WATER LEVEL DATA (IF APPLICABLE)	
		DEPTH	•		120010					COMPLETION: DEPTH DRY FT.	
SAMPLED	25.0 FT.									ELEVFT.	
TOP OF ROCK										AFTER 1 HRS: DEPTH <u>TNP</u> FT.	
BEGAN CORING				ELEV.		FT.					
FOOTAGE CORED BOTTOM OF HOLE		25.0	FT.	FLEV	1225.0	FT				AFTER 24 HRS. DEPTH <u>TNP</u> FT. ELEV. FT.	
BORING ADVANCE			•							PROPOSED FFE: FT.	
STRATUM	SAMPL	E DEPTH	SAMPLE		FIELD		LABOR	ATORY			
DEPTH	FROM	то	OR	SAMPLE	RESULTS		RE	SULTS		STRATUM DESCRIPTION	STRATUM DESCR
FT. ELEV.	FT.	FT.	RUN NO.	TYPE	N-Value	Qu	LL	PI	%М	1	
-										- Topsoil (12 Inches)	- Topsoil (12 In
—					3 - 5 - 6						
_	1.0	2.5	1	SS	N = 11					-	-
2.5 - 1247.5	5									_	-
—										–	-
_					2 - 2 - 2					-	-
-	3.5	5.0	2	SS	N = 4					_	-
5.0 — 1245.0)									—	-
-										-	-
-					W.O.H - 2 - 2					-	–
—	6.0	7.5	3	SS	N = 4					—	–
7.5 – 1242.5	5									-	-
_										-	-
_	8.5	10.0	4	SS	3-3-5					—	—
-		10.0	4		N = 8					Lean CLAY (CL) - with trace root structures in	Lean CLAY (CL) - with trace
10.0 — 1240.0)									upper 5' - dark reddish brown and dark brown	
_										moist - stiff to firm (RESIDUUM)	
-											- (RESIDUU
										–	-
12.5 – 1237.5										-	–
-										_	-
—	13.5	15.0	5	SS	5 - 7 - 8 N = 15					–	-
- 15.0 — 1235.0										-	-
-	,									_	-
—										–	–
-										-	-
17.5 – 1232.5	5									-	–
										⊨	–
-					3 - 4 - 3					-	-
_	18.5	20.0	6	SS	N = 7						
20.0 — 1230.0)										
	I									Continued	Continued
REMARKS	8: <u>W.O.H We</u>	eight of Hamr	ner								

CE	E				Substatio					LC		B-2
GEOServices, LLC-Geotechnic					City, Tenn						SHEET 2 OF 2	
GEOSERVICES, LLG-GEOTECHNIC	ai anu iviateriais Enį	jineers	G	EOService	s Project # 2	1-190	57					
BORING NO. / LOCAT				B-2						ON-SITE REP.	Yes	
		10			1250.0	FT		Dr				
	January 31, 201 No D	DEPTH			1250.0						/EL DATA (IF APPLIC DEPTH DRY FT.	ADLE)
	25.0 FT.										ELEV. FT.	
TOP OF ROCK		EPTH	FT.	ELEV.		FT.				AFTER 1 HRS:	DEPTH TNP FT.	
BEGAN CORING		EPTH	FT.	ELEV.		FT.					ELEVFT.	
FOOTAGE CORED (L			FT.							AFTER 24 HRS.	DEPTH TNP FT.	
		25.0		-	1225.0	FT.				PROPOS	ELEVFT.	
BORING ADVANCED		. <u>.</u>		UGERING	X					PROPOSE	ED FFE:FT.	
STRATUM DEPTH	SAMPLE	DEPTH TO	SAMPLE	SAMPLE	FIELD RESULTS			ATORY SULTS		ett		
FT. ELEV.	FROM	FT.	RUN NO.	TYPE	N-Value	Qu	LL	PI	%М	Sir	RATUM DESCRIPTION	
									,0111	_	(continued)	
_												
-										-		
											 with trace root struct eddish brown and data 	
22.5 – 1227.5											loist - stiff to firm	ark brown -
-											(RESIDUUM)	
—	23.5	25.0	7	SS	3 - 4 - 4 N = 8					<u> </u>		
– 25.0 — 1225.0										-		
-										Boring T	erminated at 25.0 F	eet
—										<u> </u>		
-										-		
27.5 – 1222.5										_		
										<u> </u>		
-										-		
_										<u> </u>		
30.0 — 1220.0										- 		
-										-		
—										<u> </u>		
_										-		
32.5 - 1217.5										-		
—												
-										-		
-										_		
35.0 — 1215.0												
-										-		
_												
										 		
37.5 - 1212.5										-		
_												
										–		
-										–		
40.0 — 1210.0				1						l		
REMARKS:												

				AEC	Substatio	n				LOG OF BORING B-3
GE	シリこ				City, Tenr		e			SHEET 1 OF 6
GEOServices, LLC-Geotechnica	al and Materials Eng	jineers	G	EOService	s Project # 2	21-190)57			DRILLER B. Snow
										ON-SITE REP.
ORING NO. / LOCAT	ION			B-3				D	RY ON	I COMPLETION ? Yes
ATE J	anuary 31, 201	19	SURF	ACE ELEV.	1250.0	FT.				WATER LEVEL DATA (IF APPLICABLE)
EFUSAL:	Yes D	DEPTH 49.5	FT.	ELEV.	1200.5	FT.				COMPLETION: DEPTH DRY FT.
-	124.5 FT.	37.9	-							ELEVFT.
OP OF ROCK		DEPTH 49.5		ELEV.		FT.				AFTER 1 HRS: DEPTH TNP FT.
EGAN CORING OOTAGE CORED (LF		DEPTH 49.5	-	ELEV.	1200.5	FT.				ELEVFT. AFTER 24 HRS. DEPTH TNP FT.
OTTOM OF HOLE D		75.0 124.5		ELEV.	1125.5	FT				ELEV. FT.
		121.0		-						
ORING ADVANCED I	BY:		POWER	AUGERING	Х	-	r			PROPOSED FFE: FT.
STRATUM	SAMPLE		SAMPLE		FIELD		LABOR		,	
DEPTH	FROM	то	OR	SAMPLE	RESULTS	1		SULTS		STRATUM DESCRIPTION
FT. ELEV.	FT.	FT.	RUN NO.	TYPE	N-Value	Qu	LL	PI	%М	
-										- Topsoil (12 Inches)
_					1 - 3 - 3					_
	1.0	2.5	1	SS	N = 6					<u> </u>
2.5 – 1247.5										-
—										–
_					2 - 3 - 3					-
_	3.5	5.0	2	SS	N = 6					_
5.0 — 1245.0										<u> </u>
-										-
_					3 - 4 - 5					—
_	6.0	7.5	3	SS	N = 9					
7.5 – 1242.5										_
—										—
_					3 - 4 - 7					-
_	8.5	10.0	4	SS	N = 11					<u> </u>
10.0 — 1240.0										Lean CLAY (CL) - dark reddish brown and da
-										 brown - moist to wet - firm to very stiff
—										(RESIDUUM)
_										<u> </u>
12.5 – 1237.5										_
—										—
-					4 - 5 - 6					-
_	13.5	15.0	5	SS	N = 11					
15.0 — 1235.0										_
-										-
-						1				F
<u> </u>						1				
17.5 – 1232.5						1				_
— I						1				\vdash
-					4 - 4 - 7					-
_	18.5	20.0	6	SS	N = 11	1				<u> </u>
20.0 — 1230.0										
										Continued
1										

				AEC	Substatio	n				LOG OF BORING B-3
GE				Jefferson	City, Ten	nesse	e			SHEET 2 OF 6
GEOServices, LLC-Geotech	nical and Materials En	igineers			s Project # 2					DRILLER B. Snow
										ON-SITE REP.
BORING NO. / LOCA	ATION			B-3				D	RYO	N COMPLETION ? Yes
DATE	January 31, 20	19	SURF	ACE ELEV.	1250.0	FT.		-		WATER LEVEL DATA (IF APPLICABLE)
REFUSAL:	-	DEPTH 49.5	-	ELEV.		FT.				COMPLETION: DEPTH DRY FT.
SAMPLED	124.5 FT.	37.9	-	-		-				ELEV. FT.
TOP OF ROCK		DEPTH 49.5	FT.	ELEV.	1200.5	FT.				AFTER 1 HRS: DEPTH TNP FT.
BEGAN CORING	!	DEPTH 49.5	FT.	ELEV.	1200.5	FT.				ELEV. FT.
FOOTAGE CORED	(LF)	75.0	FT.							AFTER 24 HRS. DEPTH TNP FT.
BOTTOM OF HOLE	DEPTH	124.5	FT.	ELEV.	1125.5	FT.				ELEVFT.
BORING ADVANCE	D BY:		POWER	AUGERING	х					PROPOSED FFE: FT.
STRATUM	SAMPI	E DEPTH	SAMPLE		FIELD	_	LABOR	ATORY	/	
DEPTH	FROM	то	OR	SAMPLE	RESULTS	;		SULTS		STRATUM DESCRIPTION
FT. ELEV.	FT.	FT.	RUN NO.	TYPE	N-Value	Qu	LL	PI	%М	
	1						<u>_</u>			(continued)
_						1			1	
_										-
_						1			1	–
22.5 – 1227.5	5					1			1	-
—										F
-					2 - 3 - 4					<u>-</u>
_	23.5	25.0	7	SS	N = 7					_
25.0 — 1225.0)									L
-										-
—										F
-										-
27.5 - 1222.5	;									
	,									
-										-
—	28.5	30.0	8	SS	4 - 5 - 6 N = 11					–
- 4000		00.0	Ŭ	00						Lean CLAY (CL) - dark reddish brown and dark
30.0 — 1220.0)									brown - moist to wet - firm to very stiff
_										- (RESIDUUM)
_										-
—										–
32.5 - 1217.5	5									-
_										
_					2 - 3 - 3	1			1	L
_	33.5	35.0	9	SS	N = 6	1			1	-
35.0 — 1215.0)									F
-						1			1	-
						1			1	
_										L
37.5 - 1212.5	5					1			1	-
—						1			1	F
-					3 - 4 - 7					-
_	38.5	40.0	10	SS	N = 11	1			1	
- 40.0 — 1210.0)					1				
										Continued
DEMARKO	·.									
REMARKS										

	E C			AEC	Substatio	n				LOG OF BORING B-3
GEOServices, LLC-Geotechni					City, Tenn					SHEET 3 OF 6
GEOSERVICES, LLG-GEOLECIIII	cai an u iviateriais en	jineers	G	EOService	es Project # 2	1-190	57			DRILLER B. Snow ON-SITE REP.
BORING NO. / LOCA	TION			B-3				D	RY ON	I COMPLETION ? Yes
	January 31, 20 [°]	19	SURF	ACE ELEV.	1250.0	FT.		•		WATER LEVEL DATA (IF APPLICABLE)
REFUSAL:	-	DEPTH 49.5		ELEV.		FT.				COMPLETION: DEPTH DRY FT.
SAMPLED	124.5 FT.	37.9	м			-				ELEVFT.
TOP OF ROCK		DEPTH 49.5		ELEV.		FT.				AFTER 1 HRS: DEPTH TNP FT.
BEGAN CORING		DEPTH 49.5		ELEV.	1200.5	FT.				
FOOTAGE CORED (I BOTTOM OF HOLE	-	75.0 124.5		EL EV	1125.5	FT				AFTER 24 HRS. DEPTH <u>TNP</u> FT. ELEV. FT.
BORING ADVANCED		124.0				• • •				PROPOSED FFE: FT.
	1				1					
STRATUM DEPTH	FROM	Е DEPTH ТО	SAMPLE	SAMPLE	FIELD RESULTS			SULTS		STRATUM DESCRIPTION
FT. ELEV.	FT.	FT.	RUN NO.	TYPE	N-Value	Qu		PI	%М	
_										_ (continued)
_										_
-										-
42.5 - 1207.5										-
										_
-					6 - 7 - 17					 Lean CLAY (CL) - dark reddish brown and dark
_	43.5	45.0	11	SS	N = 24					 brown - moist to wet - firm to very stiff (RESIDUUM)
45.0 — 1205.0										<u> </u>
-										-
_										-
—										_
47.5 - 1202.5										Weathered ROCK (WR) - Dolomite - light gray -
_					7 - 9 - 50/1"					moist - very hard
—	48.5	49.6	12	SS	N = 59/7"					CRESIDUUM) Auger Refusal at 49.5 Feet
- 50.0 - 1200.0	RUN 1	From (ft.)	To (ft.)	REC	RQD					Began Coring at 49.5 Feet
- 1200.0		49.5	59.5	66%	65%					_ DOLOMITE - with healed calcite seams - light
—										gray - moderately fractured and slightly weathered - moderately hard - no discernable dip
_										angle - weak HCl reaction
52.5 - 1197.5										
_										
-										VOID (51.9 to 55.3 Feet)
-										
55.0 — 1195.0										
_										
_										-
										DOLOMITE - with healed calcite seams - light
57.5 – 1192.5										 gray - moderately fractured and slightly weathered - moderately hard - no discernable dip
_										– angle - weak HCl reaction
—										⊢
- 60.0 — 1190.0										
	I									Continued
REMARKS:	Black indicat	tes depth of v	oid encounte	red.						

CF					Substatio					LOG OF BORING B-3
GEOServices, LLC-Geotechni	cal and Materials En	lineers			City, Tenn					SHEET 4 OF 6
DLUJEI VILES, LLU-DEULELIIII	cal and materials Lii	1110013	GI	EOService	s Project # 2	1-190	57			DRILLER B. Snow ON-SITE REP.
BORING NO. / LOCA				B-3				וח		I COMPLETION ? Yes
		10			1250.0	FT		. 0		
	January 31, 20 ² Yes E	DEPTH 49.5		CE ELEV. ELEV.		FT. FT.				WATER LEVEL DATA (IF APPLICABLE) COMPLETION: DEPTH DRY FT.
SAMPLED	124.5 FT.	37.9			1200.0					ELEV. FT.
TOP OF ROCK		DEPTH 49.5		ELEV.	1200.5	FT.				AFTER 1 HRS: DEPTH TNP FT.
BEGAN CORING	0	DEPTH 49.5	FT.	ELEV.	1200.5	FT.				ELEV. FT.
FOOTAGE CORED (L	_F)	75.0	FT.	-						AFTER 24 HRS. DEPTH TNP FT.
BOTTOM OF HOLE I	DEPTH	124.5	FT.	ELEV.	1125.5	FT.				ELEVFT.
BORING ADVANCED	BY:		POWER A	UGERING	Х					PROPOSED FFE:FT.
STRATUM	SAMPLE	DEPTH	SAMPLE		FIELD		LABOR	ATORY		
DEPTH	FROM	то	OR	SAMPLE	RESULTS			SULTS		STRATUM DESCRIPTION
FT. ELEV.	FT.	FT.	RUN NO.	TYPE	N-Value	Qu	LL	PI	%М	(continued)
-	RUN 2	From (ft.) 59.5	To (ft.) 69.5	REC 100%	RQD 91%					_ (continued)
—		0010	0010		0170					-
_										_
62.5 - 1187.5										-
—										–
_										-
-										_ DOLOMITE - with healed calcite seams - ligh
65.0 — 1185.0										gray - slightly fractured and slightly weathered moderately hard - no discernable dip angle -
-										weak HCl reaction
_										–
_										–
67.5 - 1182.5										-
_										
_										_
-	RUN 3	From (ft.)	To (ft.)	REC	RQD					
70.0 — 1180.0		69.5	79.5	91%	81%					–
_										-
_										_
—										-
72.5 – 1177.5										-
_										–
_										DOLOMITE - with healed calcite seams - ligh
-										 gray - slightly to moderately fractured and slightly to moderately fractured and slightly to moderately fractured and slightly fractional slightly fracting slightly fractional slightly fractional slightly fraction
75.0 — 1175.0										weathered - moderately hard - no discernable c angle - weak HCI reaction
_										
-										-
										–
77.5 – 1172.5										-
_										-
—										F
- 80.0 - 1170.0										-
00.0 1170.0				_		_	_	_	_	Continued
REMARKS:										

GE					Substatio					LOG OF BORING B-3
GEOServices, LLC-Geotechn	ical and Materials En	lineers			City, Tenn					SHEET 5 OF 6
	incer ene interners ch	gineera	GI	EOService	s Project # 2	1-190	57			DRILLER B. Snow
BORING NO. / LOCA				B-3						I COMPLETION ? Yes
		10			1250.0	CT.		. 0		
	January 31, 20 Yes [DEPTH 49.5		CE ELEV. ELEV.		FT. FT.				WATER LEVEL DATA (IF APPLICABLE) COMPLETION: DEPTH DRY FT.
SAMPLED	124.5 FT.	37.9			1200.0	•				ELEV. FT.
TOP OF ROCK		DEPTH 49.5		ELEV.	1200.5	FT.				AFTER 1 HRS: DEPTH TNP FT.
BEGAN CORING	[DEPTH 49.5	FT.	ELEV.	1200.5	FT.				ELEVFT.
FOOTAGE CORED (-	75.0								AFTER 24 HRS. DEPTH TNP FT.
BOTTOM OF HOLE	DEPTH	124.5	FT.	ELEV.	1125.5	FT.				ELEVFT.
BORING ADVANCE	DBY:		POWER A	UGERING	Х					PROPOSED FFE:FT.
STRATUM	SAMPLI	E DEPTH	SAMPLE		FIELD		LABOR	ATORY		
DEPTH	FROM	то	OR	SAMPLE	RESULTS			SULTS		STRATUM DESCRIPTION
FT. ELEV.	FT.	FT.	RUN NO.	TYPE	N-Value	Qu	LL	PI	%М	(continued)
-	RUN 4	From (ft.) 79.5	To (ft.) 89.5	REC 100%	RQD 98%					_ (continued)
_					/-					— _
_										
82.5 - 1167.5										-
—										–
_										-
-										DOLOMITE - with healed calcite seams - light
85.0 — 1165.0										gray - slightly fractured and slightly weathered - moderately hard - no discernable dip angle -
-										weak HCl reaction
_										-
—										–
87.5 - 1162.5										-
_										–
—										–
- 4460.0	RUN 5	From (ft.)	To (ft.)	REC	RQD					
90.0 — 1160.0 —		89.5	99.5	98%	75%					-
—										_
-										-
<u> </u>										-
										_
-										-
—										 DOLOMITE - with healed calcite seams - light gray - slightly to moderately fractured and slightly
- 95.0 — 1155.0										 gray - signify to moderately fractured and significant significan
_										angle - weak HCl reaction
—										–
_										-
97.5 - 1152.5										_
—										–
-										-
-										_
100.0 — 1150.0										Continued
	1									
REMARKS	:									

					AEC	Substatio	n				LOG OF BORING B-3
					lefferson	City, Tenn	esse	e			SHEET 6 OF 6
GEUService	es, LLC-Geotec	nical and Materials En	gineers	G	EOService	s Project # 2	1-190	57			DRILLER B. Snow ON-SITE REP.
BORING	NO. / LOC	ATION			B-3				D	ry Oi	N COMPLETION ? Yes
DATE		January 31, 20	19	SURF	ACE ELEV.	1250.0	FT.		-		WATER LEVEL DATA (IF APPLICABLE)
REFUSA	L:	Yes [DEPTH 49.5		ELEV.		FT.				COMPLETION: DEPTH DRY FT.
SAMPLE	D	124.5 FT.	37.9	М			-				ELEVFT.
TOP OF	ROCK	[DEPTH 49.5	FT.	ELEV.	1200.5	FT.				AFTER 1 HRS: DEPTH <u>TNP</u> FT.
BEGAN (DEPTH 49.5		ELEV.	1200.5	FT.				ELEVFT.
	E CORED		75.0			4405 5					AFTER 24 HRS. DEPTH TNP FT.
	OF HOLE		124.5	•			FT.				ELEVFT.
BORING	ADVANCE	D BY:		POWER A	UGERING	Х					PROPOSED FFE: FT.
ST	RATUM	SAMPLI	E DEPTH	SAMPLE		FIELD		LABOR	ATORY	,	
	ЕРТН	FROM	то	OR	SAMPLE	RESULTS	1		SULTS		STRATUM DESCRIPTION
FT.	ELEV.	FT. RUN 6	FT. From (ft.)	RUN NO. To (ft.)	TYPE REC	N-Value RQD	Qu	LL	PI	%M	(continued)
	_	KUN 0	99.5	10 (it.) 109.5	90%	63%					- (continued)
-	_										 DOLOMITE - light gray - slightly to moderately
-											 fractured and slightly weathered - moderately
102.5	- 1147.	5									 hard - no discernable dip angle - weak HCI
-	_										reaction
	_										-
	_										VOID
105.0	- 1145.)									(104.0 to 105.0 Feet)
	_										-
-	_										 DOLOMITE - light gray - slightly to moderately
-	_										 fractured and slightly weathered - moderately
107.5	- 1142.	5									 hard - no discernable dip angle - weak HCl
-											reaction
	_										
	_		F ((1))	T (1)	550						
110.0	- 1140.	RUN 7	From (ft.) 109.5	To (ft.) 124.5	REC 90%	RQD 81%					–
	-		105.5	124.0	5070	0170					-
-	_										–
-											
112.5	- 1137.	5									-
-											–
_	_										 DOLOMITE - with trace healed calcite seams -
	_										 light gray - slightly fractured and slightly
115.0	- 1135.)									- weathered - moderately hard - no discernable di
	-										angle - weak HCl reaction
-	_										
.	_	1									–
117.5	- 1132.	5									-
-	_										H
	_	1									L
	_										_
120.0	— 1130.)									Coring Terminated at 124.5 Feet
		1									Comy reminated at 124.3 Feet
F	REMARK	S: Black indicat	tes depth of v	oid encounte	red.						

GF				AEC	Substatio	n				LOG OF BORING B-4
GE				Jefferson	City, Teni	nesse	e			SHEET 1 OF 4
GEOServices, LLC-Geotech	nical and Materials En	gineers	G	EOService	s Project # 2	21-190)57			DRILLER B. Snow
										ON-SITE REP.
BORING NO. / LOCA	ATION			B-4				D	RYON	I COMPLETION ? No
DATE	February 4, 20		-	ACE ELEV.		FT.				WATER LEVEL DATA (IF APPLICABLE)
REFUSAL:		DEPTH 68.0	-	ELEV.	1180.0	FT.				COMPLETION: DEPTH <u>59.0</u> FT.
AMPLED	78.3 FT.	23.9	-		1100.0					ELEV. <u>1189.0</u> FT.
BEGAN CORING		DEPTH <u>68.0</u> DEPTH 68.0	-	ELEV. ELEV.		FT.				AFTER 1 HRS: DEPTH <u>TNP</u> FT. ELEV. FT.
OOTAGE CORED		10.3	-							AFTER 24 HRS. DEPTH TNP FT.
BOTTOM OF HOLE	DEPTH	78.3	FT.	ELEV.	1169.7	FT.				ELEVFT.
ORING ADVANCE	D BY:		POWER	AUGERING	х					PROPOSED FFE: FT.
STRATUM	SAMPL	E DEPTH	SAMPLE	T I	FIELD	-	LABOR	ATORY	(
DEPTH	FROM	то	OR	SAMPLE	RESULTS			SULTS		STRATUM DESCRIPTION
FT. ELEV.	FT.	FT.	RUN NO.	TYPE	N-Value	Qu	LL	PI	%М	1
_										- Topsoil (10 Inches)
					2 - 3 - 2					
_	1.0	2.5	1	SS	N = 5					-
2.5 - 1245.5	5									-
										—
_					5 - 5 - 6					-
_	3.5	5.0	2	SS	N = 11					-
5.0 — 1243.0)									–
_										-
_					4 - 7 - 6					–
_	6.0	7.5	3	SS	N = 13					–
7.5 - 1240.5	5									-
_										-
_	0.5	10.0	4	66	5 - 9 - 12					–
	8.5	10.0	4	SS	N = 21					Fat CLAY (CH) - with trace root structures in t
10.0 — 1238.0)									upper 5' - reddish brown, dark reddish brown
										orangish brown - moist - very stiff to firm (RESIDUUM)
_										- ((KESIDOOM))
12.5 – 1235.5	:									— _
12.5 - 1235.5	,									_
_										-
—	13.5	15.0	5	SS	6 - 9 - 9 N = 18					–
- 15.0 — 1233.0)									-
_										-
										–
_										-
17.5 - 1230.5	5					1			1	-
—						1			1	F
_					6 - 6 - 8					
_	18.5	20.0	6	SS	N = 14	1			1	-
20.0 — 1228.0)					1			1	Continued
	1									Continued
	:									

	F A C			AEC	Substatio	n				LOG OF BORING B-4
GE	272			Jefferson	City, Tenr	nesse	e			SHEET 2 OF 4
GEOServices, LLC-Geotechnica	al and Materials En	gineers	G	EOService	s Project # 2	21-190)57			DRILLER B. Snow
										ON-SITE REP.
ORING NO. / LOCAT	ION			B-4				D	RY ON	COMPLETION ? No
ATE F	ebruary 4, 20	19	SURF	ACE ELEV.	1248.0	FT.				WATER LEVEL DATA (IF APPLICABLE)
EFUSAL:	Yes [DEPTH 68.0	FT.	ELEV.	1180.0	FT.				COMPLETION: DEPTH <u>59.0</u> FT.
AMPLED	78.3 FT.	23.9	М							ELEV. <u>1189.0</u> FT.
OP OF ROCK		DEPTH 68.0		ELEV.	1180.0	FT.				AFTER 1 HRS: DEPTH <u>TNP</u> FT.
		DEPTH 68.0		ELEV.	1180.0	FT.				ELEVFT.
DOTAGE CORED (LF		10.3			1100 7	FT				AFTER 24 HRS. DEPTH TNP FT.
		78.3		ELEV.		FT.				ELEVFT.
ORING ADVANCED I	BY:		POWER		Х	-	-			PROPOSED FFE: FT.
STRATUM	SAMPL	E DEPTH	SAMPLE		FIELD		LABOR	ATORY	,	
DEPTH	FROM	то	OR	SAMPLE	RESULTS	-	RES	SULTS	1	STRATUM DESCRIPTION
FT. ELEV.	FT.	FT.	RUN NO.	TYPE	N-Value	Qu	LL	PI	%М	
-										_ (continued)
- - 22.5 - 1225.5										 - -
	23.5	25.0	7	SS	2 - 3 - 3 N = 6					
5.0 — 1223.0 -										 Fat CLAY (CH) - with trace root structures in upper 5' - reddish brown, dark reddish brown orangish brown - moist - very stiff to firm (RESIDUUM)
- - 27.5 - 1220.5										- (REODOON)
-					3 - 4 - 3					
– 0.0 — 1218.0 –	28.5	30.0	8	SS	N = 7					-
- 10155										 -
2.5 – 1215.5 – –					2 - 3 - 2					- -
- 1213.0 -	33.5	35.0	9	SS	N = 5					 Lean CLAY (CL) - orangish brown and ligh brown - moist to wet - very soft to firm (RESIDUUM)
- 7.5 - 1210.5										- -
-	38.5	40.0	10	SS	3 - 2 - 3 N = 5					-
- 40.0 - 1208.0										

GF					Substation								B-4
GEOServices, LLC-Geotechni	cal and Materials Eng	jineers			City, Tenn s Project # 2							SHEET 3 OF 4 R B. Snow	
			0		3 T TOJECI # 2	1-130	57				ON-SITE REP		
BORING NO. / LOCA	TION			B-4				D	RY O		PLETION ?	No	
DATE	February 4, 201	19	SURF	ACE ELEV.	1248.0	FT.					WATER I	LEVEL DATA (IF APPLIC	ABLE)
REFUSAL:	Yes D	DEPTH 68.0	FT.	ELEV.	1180.0	FT.				cc	MPLETION:	DEPTH <u>59.0</u> FT.	
	78.3 FT.	23.9										ELEV. <u>1189.0</u> FT.	
TOP OF ROCK		DEPTH 68.0				FT.				AF	TER 1 HRS:	DEPTH TNP FT.	
BEGAN CORING FOOTAGE CORED (L		DEPTH 68.0 10.3		ELEV.	1180.0	FT.					TER 24 HRS.	ELEVFT. DEPTH TNP FT.	
BOTTOM OF HOLE		78.3		ELEV.	1169.7	FT.					121(2411(0)	ELEV. FT.	
BORING ADVANCED		. <u> </u>		UGERING							PROP	OSED FFE: FT.	
STRATUM	SAMPLE	E DEPTH	SAMPLE		FIELD		LABOR	ATORY	(
DEPTH	FROM	то	OR	SAMPLE	RESULTS	-	RE	SULTS	T			STRATUM DESCRIPTION	
FT. ELEV.	FT.	FT.	RUN NO.	TYPE	N-Value	Qu	LL	PI	%N	м			
-										-		(continued)	
_													
_										E			
42.5 - 1205.5										-			
-					W.O.H								
_					W.O.H 1								
-	43.5	45.0	11	SS	N = 1					-			
45.0 — 1203.0													
_										L			
-										-			
—										_			
47.5 – 1200.5										L			
_					W.O.H 2 -					-			
—	48.5	50.0	12	SS	3 N = 5								
					-							(CL) - orangish brown	
-										_		moist to wet - very soft t (RESIDUUM)	to firm
—										-		(ICESIDOOM)	
_										E			
52.5 - 1195.5										–			
—										_			
-					W.O.H W.O.H 1					-			
_	53.5	55.0	13	SS	N = 1					Γ			
55.0 — 1193.0													
-										-			
_													
-										\vdash			
57.5 - 1190.5										-			
-					W.O.H W.O.H								
_	E0 F	60.0	4 4	00	W.O.H.								
-	58.5	60.0	14	SS	N = 0					-			
60.0 — 1188.0										•		Continued	
REMARKS:	W.O.H We	eight of Hamn	ner										

CE				AEC	Substatio	n				LOG OF BORING B-4
GE	うして			Jefferson	City, Tenr	nesse	e			SHEET 4 OF 4
GEOServices, LLC-Geotechnic	al and Materials Eng	jineers	G	EOService	s Project # 2	21-190	57			DRILLER B. Snow
										ON-SITE REP.
BORING NO. / LOCAT	TON			B-4				D	RYON	N COMPLETION ? No
DATE	February 4, 201	9	SURF	ACE ELEV.	1248.0	FT.				WATER LEVEL DATA (IF APPLICABLE)
REFUSAL:	Yes D	DEPTH 68.0	FT.	ELEV.	1180.0	FT.				COMPLETION: DEPTH <u>59.0</u> FT.
SAMPLED	78.3 FT.	23.9								ELEV. <u>1189.0</u> FT.
TOP OF ROCK		DEPTH 68.0		ELEV.		FT.				AFTER 1 HRS: DEPTH TNP FT.
BEGAN CORING FOOTAGE CORED (L		DEPTH <u>68.0</u> 10.3		ELEV.	1180.0	FT.				ELEVFT. AFTER 24 HRS. DEPTH TNP FT.
		78.3		ELEV.	1169.7	FT.				ELEV. FT.
BORING ADVANCED				AUGERING	X	-				PROPOSED FFE: FT.
						-				
STRATUM		DEPTH	SAMPLE		FIELD		LABOR		,	
DEPTH	FROM	то	OR	SAMPLE	RESULTS	T		SULTS		STRATUM DESCRIPTION
FT. ELEV.	FT.	FT.	RUN NO.	TYPE	N-Value	Qu	LL	PI	%М	(continued)
-										-
_										
_										L
62.5 - 1185.5										-
—										
_					3 - 3 - 3					 Lean CLAY (CL) - orangish brown and lig brown - moist to wet - very soft to firm
-	63.5	65.0	15	SS	N = 6					– (RESIDUUM)
65.0 — 1183.0										–
-										-
_										
_										Ľ
67.5 - 1180.5										Auger Refusal at 68.0 Feet
—	RUN 1	From (ft.)	To (ft.)	REC	RQD					Began Coring at 68.0 Feet
-		68.0	78.3	100%	96%					
_										-
70.0 — 1178.0										–
-										-
—										F
_										Ľ
72.5 - 1175.5										
—										DOLOMITE - with healed calcite seams - I gray - slightly fractured and slightly weather
-										 moderately hard - no discernable dip angle
-										weak HCl reaction
75.0 — 1173.0										–
-										-
—										F
_										Ľ
77.5 - 1170.5										-
—										F
-										Coring Terminated at 78.3 Feet
_										
- 80.0 - 1168.0										
REMARKS:										

CE	E	2			Substation					LOG OF BORING B-5
GL		\supset			City, Tenn					SHEET 1 OF 2
GEOServices, LLC-Geotechnic	al and Materials Eng	jineers	GI	EOService	es Project # 2	1-190)57			DRILLER B. Snow
				2.5						
BORING NO. / LOCAT				B-5					RY Un	N COMPLETION ? Yes
	-	19 DEPTH	-	-	1248.0	-				
	25.0 FT.		-	ELEV.		FI. -				COMPLETION: DEPTH <u>DRY</u> FT. ELEV. FT.
TOP OF ROCK		DEPTH	-	ELEV.		FT.				AFTER 1 HRS: DEPTH TNP FT.
BEGAN CORING		DEPTH				-				ELEV. FT.
FOOTAGE CORED (L	-		FT.							AFTER 24 HRS. DEPTH TNP FT.
BOTTOM OF HOLE)EPTH	25.0	FT.	ELEV.	1223.0	FT.				ELEVFT.
BORING ADVANCED	BY:		POWER A		Х	-				PROPOSED FFE:FT.
STRATUM	SAMPLE	E DEPTH	SAMPLE		FIELD		LABOR	ATORY		
DEPTH	FROM	то	OR	SAMPLE	RESULTS	1		SULTS	· · · · · ·	STRATUM DESCRIPTION
FT. ELEV.	FT.	FT.	RUN NO.	TYPE	N-Value	Qu	LL	PI	%M	
-	1				ļ	'				- Topsoil / Gravel (12 Inches)
_					5 - 7 - 8	'				_
_	1.0	2.5	1	SS	N = 15	'				F
2.5 – 1245.5	1 1				ļ	'				-
	1 !				ļ	'				
_		_			3 - 5 - 6	'				Ľ
-	3.5	5.0	2	SS	N = 11	'				 Fat CLAY (CH) - with trace chert gravel -
5.0 — 1243.0	1 !				ļ	'				orangish brown and reddish brown - moist - stil
_					ļ	'				to very stiff
_					5-6-8	'				- (RESIDUUM)
—	6.0	7.5	3	SS	N = 14	'				 -
7.5 – 1240.5	1 !				ļ	'				-
_					ļ	'				F
—	8.5	10.0	4	SS	5 - 8 - 8 N = 16	'				F
- 1000	0.0	10.0	т Т		N - 10	'				-
10.0 — 1238.0 -	1 1				ļ	'				_
_					ļ	'				F
-					ļ	'				-
 12.5 – 1235.5	1 1				ļ	'				E
-					ļ	'				F
_					5 - 6 - 8	'				-
—	13.5	15.0	5	SS	5 - 6 - 8 N = 14	'				-
_ 15.0 — 1233.0					ļ	'				 Lean CLAY (CL) - with chert gravel at depth - orangish brown and reddish brown - moist - still
-	1 !				ļ	'				– (RESIDUUM)
—					ļ	'				F
-					ļ	'				L
17.5 - 1230.5					ļ	'				_
—	1 1				ļ	'				 -
-					3 - 4 - 6	'				-
_	18.5	20.0	6	SS	N = 10	'				–
20.0 — 1228.0			L			<u> </u>				Continued
	ł									Oblinition
REMARKS:										

CE					Substatio					LOG OF BORING B-5
GEOServices, LLC-Geotechnic					City, Tenn					SHEET 2 OF 2
deugervices, LLG-Deulechini	Cal and Materials Eng	JIIICEI'S	G	EOService	s Project # 2	1-190)57			DRILLER B. Snow
BORING NO. / LOCA				B-5				וח		ON-SITE REP
	January 31, 201	0	SURE		1248.0	ст				WATER LEVEL DATA (IF APPLICABLE)
			FT.	•		FT.				COMPLETION: DEPTH DRY FT.
	25.0 FT.	7.6	•							ELEV. FT.
TOP OF ROCK	C	DEPTH	FT.	ELEV.		FT.				AFTER 1 HRS: DEPTH TNP FT.
BEGAN CORING		DEPTH	-	ELEV.		FT.				ELEVFT.
FOOTAGE CORED (L			FT.		1000.0					AFTER 24 HRS. DEPTH TNP FT.
BOTTOM OF HOLE		25.0	•	UGERING	1223.0 X	FI.				ELEVFT
STRATUM	1	DEPTH	SAMPLE		FIELD		LABOR	ATOPY		
DEPTH	FROM	то	OR	SAMPLE	RESULTS			ULTS		STRATUM DESCRIPTION
FT. ELEV.	FT.	FT.	RUN NO.	TYPE	N-Value	Qu	LL	PI	%М	
_										_ (continued)
—										–
-										-
22.5 - 1225.5										Lean CLAY (CL) - with chert gravel at depth -
										orangish brown and reddish brown - moist - stif (RESIDUUM)
-					5 - 7 - 8					-
_	23.5	25.0	7	SS	N = 15					-
25.0 — 1223.0										Boring Terminated at 25.0 Feet
-										
_										-
_										–
27.5 – 1220.5										-
_										
_										_
-										-
30.0 — 1218.0										_
_										<u> </u>
-										-
<u> </u>										<u>⊢</u> _
52.5 <u> </u>										<u> </u>
-										-
—										–
- 35.0 — 1213.0										
-										-
—										–
<u> </u>										Ē
37.5 - 1210.5										-
-										F
										Ē
-										-
40.0 — 1208.0						<u> </u>				1
REMARKS:										

					Substatio					LOG OF BORING B-6
GEOServices, LLC-Geotechnic					City, Tenr					SHEET 1 OF 2
GEOSERVICES, LLG-GEOLECINIC	ai anu iviateriais Enį	jineers	GI	EOService	s Project # 2	1-190	57			DRILLER B. Snow
BORING NO. / LOCAT				B-6						ON-SITE REP.
					1248.0	FT		. 0	KT ON	
	January 31, 20 ² No E	DEPTH		•	1248.0	FT.				WATER LEVEL DATA (IF APPLICABLE) COMPLETION: DEPTH <u>DRY</u> FT.
	25.0 FT.					-				ELEV. FT.
TOP OF ROCK		DEPTH		ELEV.		FT.				AFTER 1 HRS: DEPTH TNP FT.
BEGAN CORING		DEPTH	FT.	ELEV.		FT.				ELEVFT.
FOOTAGE CORED (L	-		FT.							AFTER 24 HRS. DEPTH TNP FT.
		25.0	•	-	1223.0	FI.				ELEV. FT.
BORING ADVANCED				UGERING	X	•				PROPOSED FFE: FT.
STRATUM DEPTH	FROM	то То	SAMPLE	SAMPLE	FIELD RESULTS		LABOR	SULTS		STRATUM DESCRIPTION
FT. ELEV.	FT.	FT.	RUN NO.	TYPE	N-Value	Qu	LL	PI	%М	
_										– Topsoil (12 Inches)
—					1 - 1 - 2					
	1.0	2.5	1	SS	N = 3					-
2.5 - 1245.5										_
—										—
-					4 - 4 - 5					-
-	3.5	5.0	2	SS	N = 9					_
5.0 — 1243.0										—
-										-
-			_		4 - 5 - 5					_
—	6.0	7.5	3	SS	N = 10					—
7.5 – 1240.5										-
_										-
—	8.5	10.0	4	SS	7 - 9 - 10 N = 19					—
- 10.0 - 1238.0	0.0	1010	•							Fat CLAY (CH) - with chert gravel at depth - da
-										reddish brown, orangish brown and dark brown
—										moist - soft to very stiff (RESIDUUM)
-										-
12.5 – 1235.5										–
—										–
-					5 - 6 - 5					-
_	13.5	15.0	5	SS	N = 11					-
15.0 — 1233.0										–
-										-
_										-
—										–
17.5 - 1230.5										-
-										–
—	18.5	20.0	6	SS	2 - 4 - 4 N = 8					_
- 1000 0	10.0	20.0	U		14 = O					-
20.0 — 1228.0		-	-	·				-	-	Continued
REMARKS:										

		E				Substatio					LOG OF BORING B-6	
GELService	s. LLC-Gentechnic	al and Materials Eng	incers			City, Tenn					SHEET 2 OF 2	
	.a, 110-00000000000000000	an ana materialis chi	111001 3	GI	EOService	s Project # 2	1-190	57			DRILLER B. Snow ON-SITE REP.	
	NO. / LOCAT				B-6						COMPLETION ? Yes	
			0			1048.0			. 0		T	
DATE REFUSA		January 31, 201 No D	9 DEPTH			1248.0					WATER LEVEL DATA (IF APPLICABLE) COMPLETION: DEPTH DRY FT.	
SAMPLE		25.0 FT.									ELEV. FT.	
TOP OF			EPTH		ELEV.		FT.				AFTER 1 HRS: DEPTH TNP FT.	
BEGAN C	ORING	C	EPTH	FT.							ELEVFT.	
	E CORED (L	-		FT.							AFTER 24 HRS. DEPTH TNP FT.	
	OF HOLE D		25.0	•	-	1223.0	FT.				ELEVFT.	
	ADVANCED				UGERING	Х					PROPOSED FFE:FT.	
		SAMPLE		SAMPLE		FIELD		LABOR				
FT.	EPTH ELEV.	FROM FT.	TO FT.	OR RUN NO.	SAMPLE TYPE	RESULTS N-Value	Qu		SULTS PI	%M	STRATUM DESCRIPTION	
		F 1.	F1.	KON NO.	TIFE	N-Value	QU		F1	/0141	(continued)	
_	_										<u>-</u>	
	_										-	
	_										Fat CLAY (CH) - with chert gravel at depth - c	
22.5	1225.5										 reddish brown, orangish brown and dark brow moist - soft to very stiff 	wn -
	_										– (RESIDUUM)	
-	_	23.5	25.0	7	SS	2 - 3 - 3 N = 6					–	
05.0	- - 1223.0	20.0	20.0	1	00	11 = 0					-	
25.0 -	- 1223.0										Boring Terminated at 25.0 Feet	
	_										–	
	-										-	
27.5	- 1220.5											
27.5	- 1220.5										<u> </u>	
	_										-	
-											–	
30.0 -											-	
	_										-	
-	_										–	
l .	_										-	
32.5	- 1215.5										-	
											–	
	_										-	
	_										-	
35.0 -	- 1213.0										–	
	-										-	
-	_										–	
-											–	
37.5	- 1210.5										-	
-												
	_										F	
	-										-	
40.0 -	- 1208.0				<u> </u>						1	
F	REMARKS:											_

CE	E				Substatio					LOG OF BORING B-7
GEOServices, LLC-Geotechnic					City, Tenn					SHEET 1 OF 2
GEOSERVICES, LLG-GEOTECHNIC	ai an u iviateriais Enį	Jineers	GI	EOService	s Project # 2	1-190	57			DRILLER B. Snow
										ON-SITE REP.
BORING NO. / LOCAT				B-7				. Di	RYON	N COMPLETION ? Yes
				-	1248.0					
		DEPTH		ELEV.		FT.				COMPLETION: DEPTH DRY FT.
TOP OF ROCK	<u>35.0</u> FT.	DEPTH		EI EV		FT				ELEVFT. AFTER 1 HRS: DEPTH TNP FT.
BEGAN CORING		DEPTH								ELEV. FT.
FOOTAGE CORED (L				•						AFTER 24 HRS. DEPTH TNP FT.
BOTTOM OF HOLE	DEPTH	35.0	-	ELEV.	1213.0	FT.				ELEV. FT.
BORING ADVANCED	BY:		POWER A	UGERING	Х	•				PROPOSED FFE: FT.
STRATUM	SAMPLE	DEPTH	SAMPLE		FIELD		LABOR	ATORY		
DEPTH	FROM	то	OR	SAMPLE	RESULTS			SULTS	1	STRATUM DESCRIPTION
FT. ELEV.	FT.	FT.	RUN NO.	TYPE	N-Value	Qu	LL	PI	%M	
-										- Topsoil (12 Inches)
_					3 - 3 - 4					_
_	1.0	2.5	1	SS	N = 7					–
2.5 – 1245.5										-
—										F
_					5 - 7 - 8					-
-	3.5	5.0	2	SS	N = 15					-
5.0 — 1243.0										–
-										-
_					5 - 7 - 9					
_	6.0	7.5	3	SS	N = 16					L
7.5 – 1240.5										-
—										F
-					5 - 7 - 9					-
-	8.5	10.0	4	SS	N = 16					
10.0 — 1238.0										Fat CLAY (CH) - with trace chert gravel - orangish brown, brown and reddish brown - moi
-										- very stiff to soft
_										(RESIDUUM)
_										L
12.5 - 1235.5										-
—										F
_					2 - 2 - 5					-
-	13.5	15.0	5	SS	N = 7					-
15.0 — 1233.0										–
-										-
_										
 _										<u> </u>
17.5 - 1230.5										-
-										F
					2 - 2 - 3					Ľ
-	18.5	20.0	6	SS	N = 5					-
20.0 — 1228.0										Continued
'	I									
REMARKS:										

GE					Substatio		_			LOG OF BORING B-7
GEOServices, LLC-Geotechni	cal and Materials Eng	jineers			City, Tenr s Project # 2					SHEET 2 OF 2 DRILLER B. Snow
			0		3110j00(#2	.1-100	57			ON-SITE REP.
BORING NO. / LOCA	TION			B-7				D	RY ON	COMPLETION ? Yes
DATE	January 31, 201	19	SURF	ACE ELEV.	1248.0	FT.		-		WATER LEVEL DATA (IF APPLICABLE)
REFUSAL:	No D	DEPTH	FT.	ELEV.		FT.				COMPLETION: DEPTH DRY FT.
	<u>35.0</u> FT.	10.7								ELEVFT.
TOP OF ROCK BEGAN CORING			FT.							AFTER 1 HRS: DEPTH <u>TNP</u> FT. ELEV. FT.
FOOTAGE CORED (L		-	FT.			FI.				AFTER 24 HRS. DEPTH TNP FT.
BOTTOM OF HOLE		35.0	FT.	ELEV.	1213.0	FT.				ELEVFT.
BORING ADVANCED	BY:		POWER A		х	-				PROPOSED FFE: FT.
STRATUM	SAMPLE	DEPTH	SAMPLE		FIELD		LABOR	ATORY	1	
DEPTH	FROM	то	OR	SAMPLE	RESULTS	1		SULTS	1	STRATUM DESCRIPTION
FT. ELEV.	FT.	FT.	RUN NO.	TYPE	N-Value	Qu	LL	PI	%М	(continued)
-										_ (continued)
-										-
—										_
22.5 – 1225.5										
_										_
—	23.5	25.0	7	SS	1 - 2 - 2 N = 4					—
_ 25.0 — 1223.0										
-										-
—										—
-										 Fat CLAY (CH) - with trace chert gravel -
27.5 - 1220.5										 orangish brown, brown and reddish brown - moist
—										- very stiff to soft (RESIDUUM)
_					4 - 3 - 5					
-	28.5	30.0	8	SS	N = 8					-
30.0 — 1218.0										—
_										-
-										-
 32.5 – 1215.5										—
32.5 – 1215.5										_
-					3 - 3 - 3					-
_	33.5	35.0	9	SS	N = 6					_
35.0 — 1213.0										Boring Terminated at 35.0 Feet
-										- Bonng Terminated at 35.0 Feet
_										_
_										_
37.5 - 1210.5										-
-										-
—										–
- 40.0										-
40.0 — 1208.0										
REMARKS:										

CE					Substatio					LOG OF BORING B-8
					City, Tenr					SHEET 1 OF 2
GEOServices, LLC-Geotechnic	cai anu materiais Enį	jineers	G	EOService	s Project # 2	21-190	57			DRILLER B. Snow
				5.0						ON-SITE REP.
BORING NO. / LOCAT				B-8				- D	RYON	N COMPLETION ? Yes
				-	1244.0	-				
	<u>No</u> E 25.0 FT.	DEPTH 7.6		ELEV.		-				COMPLETION: DEPTH <u>DRY</u> FT. ELEV. FT.
TOP OF ROCK		DEPTH		ELEV.		FT.				AFTER 1 HRS: DEPTH TNP FT.
BEGAN CORING		DEPTH								ELEV. FT.
FOOTAGE CORED (L	.F)		FT.	-		-				AFTER 24 HRS. DEPTH TNP FT.
BOTTOM OF HOLE	DEPTH	25.0	FT.	ELEV.	1219.0	FT.				ELEVFT.
BORING ADVANCED	BY:	-	POWER A	UGERING	Х	-				PROPOSED FFE: FT.
STRATUM	SAMPLE	DEPTH	SAMPLE		FIELD		LABOR	ATORY		
DEPTH	FROM	то	OR	SAMPLE	RESULTS	1		SULTS	1	STRATUM DESCRIPTION
FT. ELEV.	FT.	FT.	RUN NO.	TYPE	N-Value	Qu	LL	PI	%М	
-										- Topsoil (12 Inches)
_					1 - 2 - 3					
_	1.0	2.5	1	SS	N = 5					L
2.5 – 1241.5										-
-										Lean CLAY (CL) - with trace organics - dark
_					1 - 2 - 2					 brown - moist - firm to soft (CULT?)
-	3.5	5.0	2	SS	N = 4					-
5.0 — 1239.0										<u>-</u>
-										-
_					1 - 2 - 3					_
—	6.0	7.5	3	SS	N = 5					–
7.5 – 1236.5										-
_										<u> </u>
_	0.5	40.0			5-8-9					–
-	8.5	10.0	4	SS	N = 17					-
10.0 — 1234.0										F
_										L
-										-
—										Fat CLAY (CH) - with trace root structures in the
12.5 – 1231.5										upper 2' - orangish brown and reddish brown -
-										 moist - very stiff to firm (RESIDUUM)
—	13.5	15.0	5	SS	3 - 5 - 6 N = 11					
- 1000.0	1010	1010	0							-
15.0 — 1229.0 —										-
_										–
-										-
17.5 – 1226.5										
										Ē.
-										-
-	18.5	20.0	6	SS	1 - 3 - 3 N = 6					F
_ 20.0 — 1224.0										-
	l									Continued
REMARKS:										

		E C				Substatio					LOG OF BORING B-8
GEO Samuia	S LLC Centeshnis	al and Materials Eng				City, Tenn					SHEET 2 OF 2
GEUSERVICE	s, LLL-Bevlechnic	ai anu iviateriais Eng	lineers	GI	EOService	s Project # 2	1-190)57			DRILLER B. Snow
					D.o.						
	NO. / LOCAT				B-8				. Di		I COMPLETION ? Yes
-		ebruary 1, 201	9 DEPTH			1244.0					
REFUSAI SAMPLEI		25.0 FT.			ELEV.		F1.				COMPLETION: DEPTH <u>DRY</u> FT. ELEV. FT.
TOP OF I			EPTH		ELEV.		FT.				AFTER 1 HRS: DEPTH TNP FT.
BEGAN C			EPTH								ELEVFT.
FOOTAG	E CORED (L	F)		FT.							AFTER 24 HRS. DEPTH TNP FT.
BOTTOM	OF HOLE	DEPTH	25.0	FT.	ELEV.	1219.0	FT.				ELEVFT.
BORING	ADVANCED	BY:		POWER A	UGERING	Х		ī			PROPOSED FFE: FT.
	RATUM	SAMPLE		SAMPLE		FIELD		LABOR			
l – – – – – – – – – – – – – – – – – – –	EPTH ELEV.	FROM	то	OR	SAMPLE	RESULTS	0			%M	STRATUM DESCRIPTION
FT.	ELEV.	FT.	FT.	RUN NO.	TYPE	N-Value	Qu	LL	PI	70IVI	(continued)
	_										
	_										-
-											 Fat CLAY (CH) - with trace root structures in the str
22.5	- 1221.5										 upper 2' - orangish brown and reddish brown moist - very stiff to firm
	_										– (RESIDUUM)
	_	23.5	25.0	7	SS	2 - 3 - 4 N = 7					<u> </u>
	_	23.5	25.0	1	55	N = 7					-
25.0 -	<u> </u>										Boring Terminated at 25.0 Feet
-											—
	-										-
27.5	 1216.5										— _
27.5	1210.5										_
	_										-
-											–
30.0 -	- - 1214.0										-
	_										-
-	_										–
	_										-
32.5	- 1211.5										-
-											-
	_										-
	_										-
35.0 -	- 1209.0										–
	-										-
	_										–
-	_										–
37.5	- 1206.5										-
	_										–
-											—
40.0	-										-
40.0 -	- 1204.0										
F	REMARKS:										

GF					Substation					LOG OF BORING B-9
GEOServices, LLC-Geotechni	cal and Materials Eng	jineers			City, Tenn					SHEET 1 OF 2
			G	EOService	s Project # 2	1-190	57			DRILLER B. Snow ON-SITE REP.
BORING NO. / LOCAT	TION			B-9				D	RYON	N COMPLETION ? No
	February 1, 201	19	SURF		1242.0	FT.		i		WATER LEVEL DATA (IF APPLICABLE)
		DEPTH		-	-	-				COMPLETION: DEPTH <u>27.0</u> FT.
	35.0 FT.			_						ELEV. <u>1215.0</u> FT.
TOP OF ROCK		DEPTH		-		-				AFTER 1 HRS: DEPTH <u>TNP</u> FT.
		DEPTH	-	ELEV.		FT.				ELEVFT. AFTER 24 HRS. DEPTH TNP FT.
FOOTAGE CORED (L BOTTOM OF HOLE		35.0	FT.	FLEV.	1207.0	FT				AFTER 24 HRS. DEPTH TNP FT. ELEV FT.
BORING ADVANCED			-			-				PROPOSED FFE: FT.
STRATUM	SAMPLE	E DEPTH	SAMPLE		FIELD	-	LABOR	ATORY		
DEPTH	FROM	то	OR	SAMPLE	RESULTS		RES	SULTS		STRATUM DESCRIPTION
FT. ELEV.	FT.	FT.	RUN NO.	TYPE	N-Value	Qu	LL	PI	%М	
-										- Topsoil (12 Inches)
<u> </u>					1 - 2 - 2					
_	1.0	2.5	1	SS	N = 4		1			Ē
2.5 – 1239.5							1			_
-							1			F
<u> </u>					4-5-4		1			-
_	3.5	5.0	2	SS	N = 9		1			–
5.0 — 1237.0										┣-
-							1			-
_					3 - 4 - 6		1			E
_	6.0	7.5	3	SS	N = 10		1			F
7.5 - 1234.5							1			-
							1			
—					6 - 8 - 9		1			F
-	8.5	10.0	4	SS	N = 17		1			- Fat CLAY (CH) - with trace root structures in the
10.0 — 1232.0							1			upper 5' and chert gravel from 8 - 10' - reddish
_							1			 brown and dark reddish brown - moist - soft to very stiff
_										_ (RESIDUUM)
—							1			F
12.5 – 1229.5							1			<u>-</u>
_							1			-
—	13.5	15.0	5	SS	3 - 4 - 4 N = 8		1			 -
– 15.0 — 1227.0	10.0	10.0	Ŭ		11- 0		1			-
15.0 — 1227.0							1			<u> </u>
_							1			F
-							1			-
 17.5 – 1224.5										
							1			F
-							1			-
—	18.5	20.0	6	SS	2 - 2 - 3 N = 5					F
_ 20.0 <u> </u>			<u> </u>							-
20.0 1222.0										Continued
REMARKS:										

GE					Substatio City, Tenn		0			LOG OF BORING B-9 SHEET 2 OF 2				
GEOServices, LLC-Geotechnic	cal and Materials Eng	ineers			s Project # 2					DRILLER B. Snow				
			_		- ,		-			ON-SITE REP.				
BORING NO. / LOCAT	ION			B-9				. D	RY ON	COMPLETION ? No				
	February 1, 201			-	1242.0	FT.				WATER LEVEL DATA (IF APPLICABLE)				
		EPTH		ELEV.		FT.				COMPLETION: DEPTH 27.0 FT.				
SAMPLED TOP OF ROCK	<u>35.0</u> FT.	10.7 EPTH		EL EV		FT				ELEV. <u>1215.0</u> FT. AFTER 1 HRS: DEPTH TNP FT.				
BEGAN CORING		EPTH				-				ELEV. FT.				
FOOTAGE CORED (L			FT.	-		-				AFTER 24 HRS. DEPTH TNP FT.				
BOTTOM OF HOLE D	DEPTH	35.0	FT.	ELEV.	1207.0	FT.				ELEVFT.				
BORING ADVANCED	BY:		POWER A		Х	-				PROPOSED FFE: FT.				
STRATUM	SAMPLE	DEPTH	SAMPLE		FIELD		LABOR	ATORY	,					
DEPTH	FROM	то	OR	SAMPLE	RESULTS	<u> </u>		SULTS	1	STRATUM DESCRIPTION				
FT. ELEV.	FT.	FT.	RUN NO.	TYPE	N-Value	Qu	LL	PI	%М	(continued)				
-														
-										-				
—										—				
22.5 – 1219.5										-				
-										_				
—	23.5	25.0	7	SS	2 - 3 - 2 N = 5									
_ 25.0 <u> </u>														
-														
—										—				
_														
27.5 - 1214.5										 Lean CLAY (CL) - orangish brown and dark reddish brown - moist - firm to very soft 				
_										(RESIDUUM)				
_	00.5	00.0	0		1 - 1 - 1					_				
-	28.5	30.0	8	SS	N = 2					-				
30.0 — 1212.0										-				
—										_				
-										-				
32.5 - 1209.5										-				
—										<u> </u>				
-					2 - 2 - 2					-				
-	33.5	35.0	9	SS	N = 4					_				
35.0 — 1207.0										Boring Terminated at 35.0 Feet				
-														
-										-				
—										—				
37.5 – 1204.5														
-										-				
—										⊢				
- 40.0 — 1202.0										-				
REMARKS:														

GE					Substatio City, Tenn		e.			LOG OF BORING B-10 SHEET 1 OF 2	
GEOServices, LLC-Geotechnic	cal and Materials Eng	gineers			s Project # 2					DRILLER B. Snow	
							- 			ON-SITE REP.	
BORING NO. / LOCAT	ΓΙΟΝ			B-10				DI	RY ON	COMPLETION ? Yes	
DATE	January 31, 201	19			1254.0	-				WATER LEVEL DATA (IF APPLICABLE)	
REFUSAL:		DEPTH		ELEV.		FT.				COMPLETION: DEPTH DRY FT.	
	25.0 FT.	7.6 DEPTH	M								
TOP OF ROCK BEGAN CORING		DEPTH DEPTH		-		-				AFTER 1 HRS: DEPTH <u>TNP</u> FT. ELEV. FT.	
FOOTAGE CORED (L		DEF III				•				AFTER 24 HRS. DEPTH TNP FT.	
		25.0	=	ELEV.	1229.0	FT.				ELEV. FT.	ļ
BORING ADVANCED	BY:		POWER /		x					PROPOSED FFE: FT.	-
STRATUM	SAMPLE	E DEPTH	SAMPLE		FIELD		LABOR	ATORY			-
DEPTH	FROM	то	OR	SAMPLE	RESULTS	-	RES	SULTS		STRATUM DESCRIPTION	ļ
FT. ELEV.	FT.	FT.	RUN NO.	TYPE	N-Value	Qu	LL	PI	%М		
_			1		I					Topsoil (4 Inches)	
			1		3 - 4 - 5					F	ļ
_	1.0	2.5	1	SS	N = 9					<u> </u>	ļ
2.5 - 1251.5			1		I					-	ļ
—			1		I					F	ļ
_			1		4 - 5 - 7					- 	ļ
-	3.5	5.0	2	SS	N = 12					_	ļ
5.0 — 1249.0			1		I					–	
-			1		I					-]
_				~~	5-8-9					-]
	6.0	7.5	3	SS	N = 17					–	
7.5 – 1246.5			1		I					-	
_			1		i					–	
_	8.5	10.0	4	SS	4 - 7 - 9 N = 16					–	
- 10.0 - 1244.0	0.0	10.0			11 - 10					 Fat CLAY (CH) - with trace chert gravel at dep roddich brown and grangish brown, moist, s 	
- 1244.0			1		i					reddish brown and orangish brown - moist - s to very stiff	tin
—			1		i					(RESIDUUM)	
-			1		I					-	
12.5 – 1241.5			1		I					<u>–</u>	
_			1		I					–	
-			1		3 - 5 - 7					-	
_	13.5	15.0	5	SS	N = 12						
15.0 — 1239.0			1		I					–	
-			1		I					-	
			1		I						
_			1		I					–	
17.5 – 1236.5			1		I					-	
			1		I						
_	40.5	00.0			4 - 5 - 6					E	
- 1001.0	18.5	20.0	6	SS	N = 11					-	
20.0 — 1234.0		<u> </u>		·					1	Continued	
REMARKS:											•

GF		2			Substation City, Tenn		0			LOG OF BORING B-10 SHEET 2 OF 2
GEOServices, LLC-Geotechni	cal and Materials Eng	ineers			s Project # 2					DRILLER B. Snow
			0		5110,000 // 2	1 100	01			ON-SITE REP.
BORING NO. / LOCA	TION			B-10				DI	RY ON	I COMPLETION ? Yes
DATE	January 31, 201	19	SURF	ACE ELEV.	1254.0	FT.				WATER LEVEL DATA (IF APPLICABLE)
		DEPTH		ELEV.		FT.				COMPLETION: DEPTH DRY FT.
	25.0 FT.									ELEVFT.
TOP OF ROCK										AFTER 1 HRS: DEPTH <u>TNP</u> FT. ELEV. FT.
BEGAN CORING FOOTAGE CORED (L		DEPTH	FT.	ELEV.		F1.				AFTER 24 HRS. DEPTH TNP FT.
BOTTOM OF HOLE		25.0		ELEV.	1229.0	FT.				ELEV. FT.
BORING ADVANCED	BY:			UGERING						PROPOSED FFE: FT.
STRATUM	SAMPLE	DEPTH	SAMPLE		FIELD		LABOR	ATORY		
DEPTH	FROM	то	OR	SAMPLE	RESULTS	D	RES	SULTS	D	STRATUM DESCRIPTION
FT. ELEV.	FT.	FT.	RUN NO.	TYPE	N-Value	Qu	LL	PI	%М	
-										_ (continued)
_										<u>–</u>
_										Fat CLAY (CH) - with trace chert gravel at depth
22.5 – 1231.5										 reddish brown and orangish brown - moist - stiff
—										to very stiff (RESIDUUM)
_					3 - 5 - 7					
-	23.5	25.0	7	SS	N = 12					_
25.0 — 1229.0										Boring Terminated at 25.0 Feet
_										
_										_
—										–
27.5 – 1226.5										-
-										-
—										–
- 1004.0										-
30.0 — 1224.0 —										-
_										—
-										-
32.5 - 1221.5										-
_										_
-										-
_										<u> </u>
35.0 — 1219.0										
-										-
—										–
<u> </u>										
37.5 - 1216.5										_
-										H
_										-
-										_
40.0 — 1214.0										
REMARKS:										

Appandix B Gestech Section Sample Calendartins · Bearing Carporty of Mart Familition Assumptions Undramed levelshim -> d'=0 Gimens PI = 50 -> From graphical correlation in Skengston's Method => 54/0%= 0.20 0'p= (110 13/43) (50 Pt) = 1600 13/42 5500 13/42 Su = 1600 13/ft = E abre to undramed caretition Vesse Method Sprendsheet FS= 3 -> Jefferen Centy Regulation Callumble = 3,271 15/8+2 Pallmonthe = 6,541 K

BEARING CAPACITY OF SHALLOW FOUNDATIONS Terzaghi and Vesic Methods

Date Identification	April 15, 2019					
Input Units of M	leasurement		Results	Те	zaghi	
	E	SI or E	В	Bearing Capaci q ult =	-	lb/ft^2
	n Information			qa=	n/a	lb/ft^2
Shape B =		E SQ, CI, CO, or RE) ft	٨	Ilowable Colur	nnlo	od
Б- L=) ft	P	P = #VA		
D =		5 ft				
Soil Inform	nation					
c =		D lb/ft^2				
phi =) <mark>deg</mark>) lb/ft^3				
gamma = Dw =) ft				
Factor of S F =		3				
F -		, 				
Copyright 2000 by	/ Donald P. Coduto					

	Unit conve	1000
	Gamma w phi (radian	62.4 0
Vesic 9,812 lb/ft^2 3,271 lb/ft^2 6,541 k	Terzaghi Con a theta = Nc = Nq = N gamma gamma' = coefficient coefficient sigma zD'	nputations 1 5.70 1.00 0.00 110 0 0 165
	Vesic Compu	tation
	Nc =	5.14
	sc =	1.16
	dc =	1.02
	Nq =	1.00
	sq = dq =	1.00 1.00
	N gamma	0.00
	s gamma =	0.68
	d gamma -	1.00
	B/L =	0.8
	k =	0.0375
	W sub f	0

SETTLEMENT ANALYSIS OF SHALLOW FOUNDATIONS

Sch ert ann Method

Date	April 15, 2019
Identification	E ample 7.6
Input	
Units	
Shape	
B =	
L =	
D =	
P =	
Dw =	
gamma =	
t =	

E E or SI RE SQ, CI, CO, or RE 40 ft 50 ft 2.5 ft 380 k 120 ft 141 lb/ft^3 50 yr

Results


q = delta =

565 lb/ft^2 0.94 in

$ \begin{array}{ c c c c c c c c c c c c c c c c c c c$	Depth to Soil L						
$\begin{array}{c c c c c c c c c c c c c c c c c c c $	Тор	Bottom	Es		l epsilon		delta
$\begin{array}{cccccccccccccccccccccccccccccccccccc$			(lb/ft^2)	(ft)		()	(in)
$\begin{array}{cccccccccccccccccccccccccccccccccccc$							
$\begin{array}{cccccccccccccccccccccccccccccccccccc$							
5.5 6.5 7.5 4902 3.5 0.176 0.1989 0.0239 6.5 7.5 8.5 7353 5.5 0.218 0.1642 0.0197 8.5 9.5 7353 6.5 0.239 0.1799 0.0216 9.5 10.5 7353 8.5 0.239 0.1799 0.0225 10.5 11.5 7353 8.5 0.281 0.2173 0.0273 11.5 12.5 7353 10.5 0.323 0.2430 0.0292 13.5 14.5 7353 10.5 0.323 0.2430 0.0292 13.5 14.5 7353 11.5 0.344 0.2746 0.0329 15.5 16.5 7353 12.5 0.364 0.2746 0.0329 15.5 16.5 7353 14.5 0.406 0.3061 0.0367 17.5 18.5 10049 15.5 0.427 0.2355 0.0283 18.5 19.5 10049 16.5 0.448 0.2471 0.0296 19.5 20.5 10049 18.5 0.400 0.2702 0.0324 21.5 22.5 10049 18.5 0.490 0.2702 0.0324 22.5 21.5 10049 18.5 0.490 0.2702 0.0324 22.5 22.5 10049 18.5 0.490 0.2702 0.0324 22.5 22.5 10667 21.5 0.518 0.1720 0.0206 <							
6.5 7.5 4902 4.5 0.197 0.2226 0.0267 7.5 8.5 7353 5.5 0.218 0.1642 0.0197 8.5 9.5 7353 6.5 0.239 0.1799 0.0216 9.5 10.5 7353 7.5 0.260 0.1957 0.0235 10.5 11.5 7353 9.5 0.302 0.2273 0.0273 12.5 13.5 7353 10.5 0.323 0.2430 0.0292 13.5 14.5 7353 11.5 0.344 0.2588 0.0311 14.5 15.5 16.5 7353 11.5 0.344 0.2588 0.0311 14.5 17.5 7353 14.5 0.365 0.2903 0.0348 16.5 17.5 7353 14.5 0.460 0.3061 0.0367 17.5 18.5 10049 15.5 0.427 0.2355 0.283 18.5 19.5 10049 15.5 0.427 0.2366 0.310 20.5 21.5 10049 18.5 0.490 0.2702 0.0324 21.5 22.5 21.5 10049 18.5 0.490 0.2702 0.0324 22.5 23.5 16667 22.5 0.511 0.2817 0.0206 23.5 24.5 10491 9.5 0.511 0.2170 0.0206 23.5 25.5 16667 22.5 0.501 0.1665 0.0201 </td <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>							
7.5 8.5 7353 5.5 0.218 0.1642 0.0197 8.5 9.5 7353 6.5 0.239 0.1799 0.0216 9.5 10.5 7353 7.5 0.260 0.1957 0.0235 10.5 11.5 7353 8.5 0.302 0.2273 0.0273 12.5 13.5 7353 10.5 0.323 0.2430 0.0292 13.5 14.5 7353 11.5 0.344 0.2588 0.0311 14.5 15.5 7353 12.5 0.364 0.2746 0.0329 15.5 16.5 7353 14.5 0.404 0.2355 0.0361 0.0361 15.5 16.5 7353 14.5 0.404 0.2476 0.0329 15.5 16.5 7353 14.5 0.404 0.2476 0.0361 0.0361 16.5 17.5 7353 14.5 0.409 0.2565 0.0286 0.0310 17.5 18.5 10049 16.5 0.427 0.2355 0.0284							
8.5 9.5 7353 6.5 0.239 0.1799 0.0216 9.5 10.5 7353 7.5 0.260 0.1957 0.0235 10.5 11.5 7353 8.5 0.281 0.2173 0.0273 11.5 12.5 13.5 7353 10.5 0.322 0.2273 0.0273 12.5 13.5 7353 10.5 0.323 0.2430 0.0292 13.5 14.5 7353 11.5 0.344 0.2588 0.0311 14.5 15.5 7353 14.5 0.406 0.3061 0.0367 17.5 18.5 10049 15.5 0.427 0.2355 0.0284 19.5 20.5 10049 17.5 0.469 0.2586 0.0310 19.5 20.5 10049 18.5 0.490 0.2586 0.0324 21.5 22.5 10049 18.5 0.511 0.2817 0.0388 22.5 23.5 1							0.0267
9.5 10.5 7353 7.5 0.260 0.1957 0.0235 10.5 11.5 7353 8.5 0.281 0.2173 0.0273 12.5 13.5 7353 9.5 0.302 0.2273 0.0273 12.5 13.5 14.5 7353 10.5 0.323 0.2430 0.0229 13.5 14.5 7353 11.5 0.344 0.2588 0.0311 14.5 15.5 7353 12.5 0.384 0.03061 0.0367 15.5 16.5 7353 14.5 0.406 0.3061 0.0367 17.5 18.5 10049 15.5 0.427 0.2355 0.0283 18.5 19.5 10049 16.5 0.448 0.2471 0.0206 20.5 21.5 10049 18.5 0.490 0.2702 0.0324 21.5 22.5 10049 19.5 0.511 0.2817 0.0338 22.5 23.5 <t< td=""><td></td><td></td><td>7353</td><td></td><td></td><td>0.1642</td><td>0.0197</td></t<>			7353			0.1642	0.0197
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$				6.5			0.0216
11.5 12.5 7353 9.5 0.302 0.2273 0.0273 12.5 13.5 7353 10.5 0.323 0.2430 0.0292 13.5 14.5 7353 11.5 0.344 0.2588 0.0311 14.5 15.5 7353 11.5 0.364 0.2746 0.0329 15.5 16.5 7353 13.5 0.385 0.2903 0.0348 16.5 17.5 7353 14.5 0.406 0.3061 0.0367 17.5 18.5 10049 15.5 0.448 0.2471 0.0226 19.5 20.5 10049 17.5 0.469 0.2586 0.0310 20.5 21.5 10049 18.5 0.490 0.2702 0.0324 21.5 22.5 10049 18.5 0.490 0.2702 0.0324 21.5 22.5 10049 18.5 0.490 0.2702 0.0324 21.5 22.5 10049 18.5 0.490 0.2702 0.0324 21.5 22.5 10667 21.5 0.518 0.1720 0.0206 23.5 24.5 16667 21.5 0.509 0.1693 0.0203 24.5 25.5 16667 22.5 0.448 0.1610 0.0193 27.5 28.5 22059 25.5 0.476 0.1196 0.0143 28.5 29.5 22059 25.5 0.443 0.1112 0.0138	9.5	10.5	7353	7.5	0.260	0.1957	0.0235
$\begin{array}{cccccccccccccccccccccccccccccccccccc$	10.5	11.5	7353	8.5	0.281	0.2115	0.0254
$\begin{array}{cccccccccccccccccccccccccccccccccccc$	11.5	12.5	7353	9.5	0.302	0.2273	0.0273
14.5 15.5 7353 12.5 0.364 0.2746 0.0329 15.5 16.5 7353 13.5 0.385 0.2903 0.0348 16.5 17.5 7353 14.5 0.406 0.3061 0.0367 17.5 18.5 19049 15.5 0.427 0.2355 0.0283 18.5 19.5 10049 15.5 0.448 0.2471 0.0296 19.5 20.5 10049 17.5 0.469 0.2586 0.0310 20.5 21.5 10049 18.5 0.490 0.2702 0.0324 21.5 22.5 10049 19.5 0.511 0.2817 0.0208 22.5 23.5 16667 20.5 0.518 0.1720 0.0206 23.5 24.5 16667 22.5 0.501 0.1665 0.0200 25.5 26.5 16667 22.5 0.501 0.1683 0.0193 24.5 26.5 27.5 16667 24.5 0.448 0.1610 0.0143 27.5 28.5 22059 25.5 0.468 0.1175 0.0141 29.5 30.5 22059 26.5 0.468 0.1175 0.0143 28.5 29.5 2059 29.5 0.443 0.1112 0.0133 32.5 33.5 14216 30.5 0.435 0.1694 0.0203 33.5 34.5 14216 31.5 0.435 0.1694 0.0	12.5	13.5	7353	10.5	0.323	0.2430	0.0292
15.5 16.5 7353 13.5 0.385 0.2903 0.0348 16.5 17.5 7353 14.5 0.406 0.3061 0.0367 17.5 18.5 10049 15.5 0.427 0.2355 0.0283 18.5 19.5 10049 16.5 0.448 0.2471 0.0296 19.5 20.5 10049 17.5 0.469 0.2586 0.0310 20.5 21.5 10049 18.5 0.490 0.2702 0.0324 21.5 22.5 10049 19.5 0.511 0.2817 0.0338 22.5 23.5 16667 20.5 0.518 0.1720 0.0206 23.5 24.5 16667 22.5 0.501 0.1693 0.203 24.5 25.5 16667 22.5 0.501 0.1688 0.0197 26.5 27.5 16667 23.5 0.493 0.1638 0.0197 26.5 27.5 16667 24.5 0.484 0.1610 0.0193 27.5 28.5 22059 25.5 0.476 0.1196 0.1143 28.5 29.5 22059 28.5 0.443 0.1112 0.0133 32.5 33.5 14216 30.5 0.443 0.1112 0.0133 32.5 33.5 14216 33.5 0.443 0.1629 0.0195 35.5 36.5 14216 33.5 0.441 0.1629 0.0195	13.5	14.5	7353	11.5	0.344	0.2588	0.0311
16.5 17.5 7353 14.5 0.406 0.3061 0.0367 17.5 18.5 10049 15.5 0.427 0.2355 0.0283 18.5 19.5 10049 16.5 0.448 0.2471 0.0296 19.5 20.5 21.5 10049 17.5 0.469 0.2586 0.0310 20.5 21.5 10049 18.5 0.490 0.2702 0.0324 21.5 22.5 23.5 10049 18.5 0.490 0.2702 0.0324 22.5 23.5 26.5 10667 20.5 0.511 0.2817 0.0388 22.5 23.5 24.5 16667 21.5 0.509 0.1693 0.0203 24.5 25.5 16667 22.5 0.501 0.1665 0.2000 25.5 26.5 16667 23.5 0.493 0.1638 0.0197 26.5 27.5 16667 24.5 0.484 0.1610 0.0193 27.5 28.5 29.5 0.476 0.1196 0.0143 28.5 29.5 20.55 0.468 0.1175 0.0141 29.5 30.5 31.5 22059 28.5 0.451 0.1133 30.5 31.5 22059 29.5 0.443 0.1112 0.0133 32.5 33.5 14216 31.5 0.426 0.1661 0.0199 35.5 36.5 14216 31.5 0.446 0.166	14.5	15.5	7353	12.5	0.364	0.2746	0.0329
16.5 17.5 7353 14.5 0.406 0.3061 0.0367 17.5 18.5 10049 15.5 0.427 0.2355 0.0283 18.5 19.5 10049 16.5 0.448 0.2471 0.0296 19.5 20.5 21.5 10049 17.5 0.469 0.2586 0.0310 20.5 21.5 10049 18.5 0.490 0.2702 0.0324 21.5 22.5 23.5 10049 18.5 0.490 0.2702 0.0324 22.5 23.5 26.5 10667 20.5 0.511 0.2817 0.0388 22.5 23.5 24.5 16667 21.5 0.509 0.1693 0.0203 24.5 25.5 16667 22.5 0.501 0.1665 0.2000 25.5 26.5 16667 23.5 0.493 0.1638 0.0197 26.5 27.5 16667 24.5 0.484 0.1610 0.0193 27.5 28.5 29.5 0.476 0.1196 0.0143 28.5 29.5 20.55 0.468 0.1175 0.0141 29.5 30.5 31.5 22059 28.5 0.451 0.1133 30.5 31.5 22059 29.5 0.443 0.1112 0.0133 32.5 33.5 14216 31.5 0.426 0.1661 0.0199 35.5 36.5 14216 31.5 0.446 0.166	15.5	16.5	7353	13.5	0.385	0.2903	0.0348
18.519.51004916.50.4480.24710.029619.520.51004917.50.4690.25860.031020.521.51004918.50.4900.27020.032421.522.51004919.50.5110.28170.033822.523.51666720.50.5180.17200.020623.524.51666721.50.5090.16930.020324.525.51666722.50.5010.16650.020025.526.51666723.50.4930.16380.019726.527.51666724.50.4840.16100.019327.528.52205926.50.4760.11960.014328.529.52205926.50.4680.11750.014129.530.52205927.50.4590.11540.013830.531.52205928.50.4430.11120.013332.533.51421630.50.4350.16940.020333.534.51421631.50.4260.16610.19934.535.51421633.50.4100.15970.019235.536.51421633.50.4100.15970.019236.537.51421634.50.4010.15640.018837.538.52647135.50.3850.08050.009739.540.5	16.5	17.5	7353		0.406	0.3061	0.0367
18.5 19.5 10049 16.5 0.448 0.2471 0.0296 19.5 20.5 21.5 10049 17.5 0.469 0.2586 0.0310 20.5 21.5 10049 18.5 0.490 0.2702 0.0324 21.5 22.5 23.5 10049 19.5 0.511 0.2817 0.0338 22.5 23.5 24.5 16667 20.5 0.518 0.1720 0.0206 23.5 24.5 16667 21.5 0.509 0.1693 0.0203 24.5 25.5 16667 22.5 0.501 0.1665 0.0200 25.5 26.5 16667 23.5 0.493 0.1638 0.0197 26.5 27.5 16667 24.5 0.484 0.1610 0.0193 27.5 28.5 22059 25.5 0.476 0.1196 0.0143 28.5 29.5 22059 27.5 0.468 0.1175 0.0141 29.5 30.5 31.5 22059 28.5 0.443 0.1112 0.0133 32.5 33.5 14216 30.5 0.435 0.1694 0.0203 33.5 34.5 14216 31.5 0.426 0.1661 0.199 34.5 35.5 14216 33.5 0.410 0.1597 0.0192 35.5 36.5 14216 33.5 0.410 0.1564 0.0188 37.5 38.5 26471 $35.$							
19.520.51004917.50.4690.25860.031020.521.51004918.50.4900.27020.032421.522.51004919.50.5110.28170.033822.523.51666720.50.5180.17200.020623.524.51666721.50.5090.16930.020324.525.51666722.50.5010.16650.020025.526.51666723.50.4930.16380.019726.527.51666724.50.4840.16100.019327.528.52205925.50.4760.11960.014328.529.52205926.50.4680.11750.014129.530.52205927.50.4590.11540.013830.531.52205928.50.4510.11330.013631.532.52205929.50.4430.11120.013332.533.51421630.50.4350.16940.020333.534.51421631.50.4260.16610.019934.535.51421633.50.4100.15640.018837.538.52647135.50.3930.08230.009938.539.52647135.50.3680.07710.09240.541.52647138.50.3680.07710.09241.542.5<	18.5	19.5	10049	16.5		0.2471	0.0296
20.521.51004918.50.4900.27020.032421.522.51004919.50.5110.28170.033822.523.51666720.50.5180.17200.020623.524.51666721.50.5090.16930.020324.525.51666722.50.5010.16650.020025.526.51666723.50.4930.16380.019726.527.51666724.50.4840.16100.019327.528.52205925.50.4760.11960.014328.529.52205926.50.4680.11750.014129.530.52205927.50.4590.11540.013830.531.52205928.50.4510.11330.013631.532.52205929.50.4430.11120.013332.533.51421631.50.4260.16610.019934.535.51421632.50.4180.16290.019535.536.51421633.50.4100.15970.019236.537.51421633.50.4010.15640.018837.538.52647135.50.3930.08230.009739.540.52647137.50.3770.07880.09540.541.52647138.50.3660.07710.092241.542.5	19.5		10049	17.5	0.469		
21.522.51004919.50.5110.28170.033822.523.51666720.50.5180.17200.020623.524.51666721.50.5090.16930.020324.525.51666722.50.5010.16650.020025.526.51666723.50.4930.16380.019726.527.51666724.50.4840.16100.019327.528.52205925.50.4760.11960.014328.529.52205926.50.4680.11750.014129.530.52205927.50.4590.11540.013830.531.52205928.50.4430.11120.013332.533.51421631.50.4260.16940.020333.534.51421631.50.4260.16610.019934.535.51421632.50.4180.16290.019535.536.51421633.50.4100.15970.019236.537.51421634.50.4010.15640.018837.538.52647135.50.3930.08230.009739.540.52647137.50.3770.07880.09540.541.52647138.50.3680.07710.092241.542.52647139.50.3600.07530.090	20.5		10049	18.5	0.490	0.2702	
22.523.51666720.50.5180.17200.020623.524.51666721.50.5090.16930.020324.525.51666722.50.5010.16650.020025.526.51666723.50.4930.16380.019726.527.51666724.50.4840.16100.019327.528.52205925.50.4760.11960.014328.529.52205926.50.4680.11750.014129.530.52205927.50.4590.11540.013830.531.52205928.50.4510.11330.013631.532.52205929.50.4430.11120.013332.533.51421631.50.4260.16610.019934.535.51421632.50.4180.16290.019535.536.51421632.50.4100.15970.019236.537.51421634.50.4010.15640.018837.538.52647135.50.3930.08230.009938.539.52647136.50.3850.08050.009739.540.52647137.50.3770.7880.09540.541.52647138.50.3660.07710.092241.542.52647139.50.3600.07530.090							
23.524.51666721.50.5090.16930.020324.525.51666722.50.5010.16650.020025.526.51666723.50.4930.16380.019726.527.51666724.50.4840.16100.019327.528.52205925.50.4760.11960.014328.529.52205926.50.4680.11750.014129.530.52205927.50.4590.11540.013830.531.52205928.50.4510.11330.013631.532.52205929.50.4430.11120.013332.533.51421630.50.4350.16940.020333.534.51421631.50.4260.16610.019934.535.51421632.50.4180.16290.019535.536.51421633.50.4100.15970.019236.537.51421634.50.4010.15640.018837.538.52647135.50.3930.08230.009739.540.52647137.50.3770.07880.009540.541.52647138.50.3660.07710.009241.542.52647139.50.3600.07530.0090		23.5					
$\begin{array}{cccccccccccccccccccccccccccccccccccc$	23.5		16667	21.5	0.509	0.1693	0.0203
$\begin{array}{cccccccccccccccccccccccccccccccccccc$			16667			0.1665	0.0200
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$							
27.528.52205925.50.4760.11960.014328.529.52205926.50.4680.11750.014129.530.52205927.50.4590.11540.013830.531.52205928.50.4510.11330.013631.532.52205929.50.4430.11120.013332.533.51421630.50.4350.16940.020333.534.51421631.50.4260.16610.019934.535.51421632.50.4180.16290.019535.536.51421633.50.4100.15970.019236.537.51421634.50.4010.15640.018837.538.52647135.50.3930.08230.009938.539.52647136.50.3850.08050.007739.540.52647137.50.3770.7880.009241.542.52647139.50.3600.07530.0090							
28.529.52205926.50.4680.11750.014129.530.52205927.50.4590.11540.013830.531.52205928.50.4510.11330.013631.532.52205929.50.4430.11120.013332.533.51421630.50.4350.16940.020333.534.51421631.50.4260.16610.019934.535.51421632.50.4180.16290.019535.536.51421633.50.4100.15970.019236.537.51421634.50.4010.15640.018837.538.52647135.50.3930.08230.009938.539.52647136.50.3850.08050.009739.540.52647137.50.3770.07880.009241.542.52647139.50.3600.07530.0090			22059				0.0143
29.530.52205927.50.4590.11540.013830.531.52205928.50.4510.11330.013631.532.52205929.50.4430.11120.013332.533.51421630.50.4350.16940.020333.534.51421631.50.4260.16610.019934.535.51421632.50.4180.16290.019535.536.51421633.50.4100.15970.019236.537.51421634.50.4010.15640.018837.538.52647135.50.3930.08230.009938.539.52647136.50.3850.08050.009739.540.52647137.50.3770.07880.009241.542.52647139.50.3600.07530.0090	28.5						0.0141
30.531.52205928.50.4510.11330.013631.532.52205929.50.4430.11120.013332.533.51421630.50.4350.16940.020333.534.51421631.50.4260.16610.019934.535.51421632.50.4180.16290.019535.536.51421633.50.4100.15970.019236.537.51421634.50.4010.15640.018837.538.52647135.50.3930.08230.009938.539.52647136.50.3850.08050.009739.540.52647137.50.3770.07880.009241.542.52647139.50.3600.07530.0090			22059	27.5			
$\begin{array}{cccccccccccccccccccccccccccccccccccc$	30.5						
32.533.51421630.50.4350.16940.020333.534.51421631.50.4260.16610.019934.535.51421632.50.4180.16290.019535.536.51421633.50.4100.15970.019236.537.51421634.50.4010.15970.019236.537.51421634.50.4010.15640.018837.538.52647135.50.3930.08230.009938.539.52647136.50.3850.08050.009739.540.52647137.50.3770.07880.009240.541.52647138.50.3680.07710.009241.542.52647139.50.3600.07530.0090	31.5		22059			0.1112	0.0133
33.534.51421631.50.4260.16610.019934.535.51421632.50.4180.16290.019535.536.51421633.50.4100.15970.019236.537.51421634.50.4010.15640.018837.538.52647135.50.3930.08230.009938.539.52647136.50.3850.08050.009739.540.52647137.50.3770.07880.009240.541.52647138.50.3680.07710.009241.542.52647139.50.3600.07530.0090	32.5		14216		0.435	0.1694	0.0203
34.535.51421632.50.4180.16290.019535.536.51421633.50.4100.15970.019236.537.51421634.50.4010.15640.018837.538.52647135.50.3930.08230.009938.539.52647136.50.3850.08050.009739.540.52647137.50.3770.07880.009540.541.52647138.50.3680.07710.009241.542.52647139.50.3600.07530.0090							
35.536.51421633.50.4100.15970.019236.537.51421634.50.4010.15640.018837.538.52647135.50.3930.08230.009938.539.52647136.50.3850.08050.009739.540.52647137.50.3770.07880.009540.541.52647138.50.3680.07710.009241.542.52647139.50.3600.07530.0090							
36.5 37.5 14216 34.5 0.401 0.1564 0.0188 37.5 38.5 26471 35.5 0.393 0.0823 0.0099 38.5 39.5 26471 36.5 0.385 0.0805 0.0097 39.5 40.5 26471 37.5 0.377 0.0788 0.0095 40.5 41.5 26471 38.5 0.368 0.0771 0.0092 41.5 42.5 26471 39.5 0.360 0.0753 0.0090						0.1597	
37.5 38.5 26471 35.5 0.393 0.0823 0.0099 38.5 39.5 26471 36.5 0.385 0.0805 0.0097 39.5 40.5 26471 37.5 0.377 0.0788 0.0095 40.5 41.5 26471 38.5 0.368 0.0771 0.0092 41.5 42.5 26471 39.5 0.360 0.0753 0.0090							
38.5 39.5 26471 36.5 0.385 0.0805 0.0097 39.5 40.5 26471 37.5 0.377 0.0788 0.0095 40.5 41.5 26471 38.5 0.368 0.071 0.0092 41.5 42.5 26471 39.5 0.360 0.0753 0.0090							
39.5 40.5 26471 37.5 0.377 0.0788 0.0095 40.5 41.5 26471 38.5 0.368 0.0771 0.0092 41.5 42.5 26471 39.5 0.360 0.0753 0.0090							
40.5 41.5 26471 38.5 0.368 0.0771 0.0092 41.5 42.5 26471 39.5 0.360 0.0753 0.0090							
41.5 42.5 26471 39.5 0.360 0.0753 0.0090							
	42.5	43.5	26471	40.5	0.351	0.0736	0.0088
43.5 44.5 26471 41.5 0.343 0.0717 0.0086							

44.5	45.5	26471	42.5	0.334	0.0699	0.0084	
45.5	46.5	26471	43.5	0.325	0.0681	0.0082	
46.5	47.5	26471	44.5	0.317	0.0663	0.0080	
47.5	48.5	26471	45.5	0.308	0.0645	0.0077	
48.5	49.5	26471	46.5	0.300	0.0627	0.0075	
49.5	50.5	26471	47.5	0.291	0.0609	0.0073	
50.5	51.5	26471	48.5	0.282	0.0591	0.0071	
51.5	52.5	26471	49.5	0.274	0.0573	0.0069	
52.5	53.5	386000	50.5	0.265	0.0038	0.0005	
53.5	54.5	386000	51.5	0.256	0.0037	0.0004	
54.5	55.5	386000	52.5	0.248	0.0036	0.0004	
55.5	56.5	386000	53.5	0.239	0.0034	0.0004	
56.5	57.5	386000	54.5	0.230	0.0033	0.0004	
57.5	58.5	386000	55.5	0.222	0.0032	0.0004	
58.5	59.5	386000	56.5	0.213	0.0031	0.0004	
59.5	60.5	386000	57.5	0.204	0.0029	0.0004	
60.5	61.5	386000	58.5	0.196	0.0028	0.0003	
61.5	62.5	386000	59.5	0.187	0.0027	0.0003	
62.5	63.5	386000	60.5	0.178	0.0026	0.0003	
63.5	64.5	386000	61.5	0.170	0.0024	0.0003	
64.5	65.5	386000	62.5	0.161	0.0023	0.0003	
65.5	66.5	386000	63.5	0.153	0.0022	0.0003	
66.5	67.5	386000	64.5	0.144	0.0021	0.0002	
67.5	68.5	386000	65.5	0.135	0.0019	0.0002	
68.5	69.5	386000	66.5	0.127	0.0018	0.0002	
69.5	70.5	386000	67.5	0.127	0.0017	0.0002	
70.5	71.5	386000	68.5	0.109	0.0016	0.0002	
71.5	72.5	386000	69.5	0.101	0.0014	0.0002	
72.5	73.5	386000	70.5	0.092	0.0013	0.0002	
73.5	74.5	386000	71.5	0.083	0.0012	0.0001	
74.5	75.5	386000	72.5	0.075	0.0011	0.0001	
75.5	76.5	386000	73.5	0.066	0.0009	0.0001	
76.5	77.5	386000	74.5	0.057	0.0008	0.0001	
77.5	78.5	386000	75.5	0.049	0.0007	0.0001	
78.5	79.5	386000	76.5	0.040	0.0006	0.0001	
79.5	80.5	386000	77.5	0.031	0.0005	0.0001	
80.5	81.5	386000	78.5	0.023	0.0003	0.0000	
81.5	82.5	386000	79.5	0.014	0.0002	0.0000	
82.5	83.5	386000	80.5	0.010	0.0001	0.0000	
83.5	84.5	386000	81.5	0.010	0.0001	0.0000	
84.5	85.5	386000	82.5	0.010	0.0001	0.0000	
85.5	86.5	386000	83.5	0.009	0.0001	0.0000	
86.5	87.5	386000	84.5	0.009	0.0001	0.0000	
87.5	88.5	386000	85.5	0.009	0.0001	0.0000	
88.5	89.5	386000	86.5	0.009	0.0001	0.0000	
89.5	90.5	386000	87.5	0.009	0.0001	0.0000	
90.5	91.5	386000	88.5	0.009	0.0001	0.0000	
91.5	92.5	386000	89.5	0.009	0.0001	0.0000	
92.5	93.5	386000	90.5	0.009	0.0001	0.0000	
93.5	94.5	386000	91.5	0.008	0.0001	0.0000	
94.5	95.5	386000	92.5	0.008	0.0001	0.0000	
95.5	96.5	386000	93.5	0.008	0.0001	0.0000	
96.5	97.5	386000	94.5	0.008	0.0001	0.0000	
97.5	98.5	386000	95.5	0.008	0.0001	0.0000	
98.5	99.5	386000	96.5	0.008	0.0001	0.0000	
99.5	100.5	386000	90.5 97.5	0.008	0.0001	0.0000	
100.5	101.5	386000	98.5	0.008	0.0001	0.0000	
101.5	102.5	386000	99.5	0.007	0.0001	0.0000	
102.5	103.5	386000	100.5	0.007	0.0001	0.0000	
103.5	104.5	386000	101.5	0.007	0.0001	0.0000	
104.5	105.5	386000	102.5	0.007	0.0001	0.0000	
105.5	106.5	386000	103.5	0.007	0.0001	0.0000	
106.5	107.5	386000	104.5	0.007	0.0001	0.0000	
107.5	108.5	386000	105.5	0.007	0.0001	0.0000	

Copyright 2000 by Donald P. Coduto



GE	590	5			an Station lle, Tenne					LOG OF BORING B-1 SHEET 1 OF 1
GEBServices, LLC-Sextechnics	and Materials Eng	ineers	0		s Project # 2		13.8			DRILLER Fred Reynolds
				200814108	o r rojeut # /	1-10				ON-SITE REP.
BORING NO. / LOCAT	ON			B-1				DF	RY ON	COMPLETION ? Yes
DATE	July 8, 2016		SURF	ACE ELEV.	1108.0	FT.				WATER LEVEL DATA (IF APPLICABLE)
REFUSAL:	the second s	EPTH 9.1	10.1		1098.9	-				COMPLETION: DEPTH Dry FT.
	9.1 FT.	2.8	M	1441069	,	-				ELEV. FT.
TOP OF ROCK	0	EPTH	FT.	ELEV.		FT.				AFTER 1 HRS: DEPTH TNP FT.
BEGAN CORING	D	ЕРТН	FT.	ELEV.		FT.				ELEV. FT.
FOOTAGE CORED (LF	}		FT.							AFTER 24 HRS. DEPTH TNP FT.
BOTTOM OF HOLE D	EPTH		FT.	ELEV.	1108.0	FT.				ELEVFT.
BORING ADVANCED B	BY:		POWER	AUGERING	x					PROPOSED FFE: FT.
STRATUM	SAMPLE	DEPTH	SAMPLE		FIELD		LABORA	TORY		
DEPTH	FROM	то	OR	SAMPLE	RESULTS		RES	ULTS		STRATUM DESCRIPTION
FT. ELEV.	FT.	FT.	RUN NO.	TYPE	N-Value	Qu	LL	PI	%M	
-									1 N	
-									8	Lean CLAY - with silt and trace root structure orangish brown and gray - moist - very stiff to
-	1.0	2.5	1	SS	28					- very hard
2.5 - 1105.5	P0.677		101						1	(RESIDUUM)
									- 3	
-	1									-
-	3.5	5.0	2	SS	74				- 8	
5.0 - 1103.0	82638		1. 435-01							<u>-</u>
=				1 1						-
-									- 8	 Weathered Shale - gray - dry - very hard
-	6.0	6.7	3	SS	50/2"					=
7.5 - 1100.5			1000							
	I							- 1		
-										-
-	8.5	8.6	4	SS	50/1"				1	Auger Refusal at 9.1 feet
10.0 - 1098.0										-
=										-
-										
-										
12.5 - 1095.5										
- 1095.5										<u> </u>
-										-
-										
16.0 - 1003.0										-
15.0 - 1093.0										
_										
-				L						
17.6 - 1000.6										
17.5 - 1090.5									1	-
-										-
-										
-										5
20.0 - 1088.0								_		
1										
REMARKS:										

GF	539	5			n Station le, Tennes	see			LOG OF BORING SHEET 1 OF 1	B-2
GL&Services, LLC-Gestech	ical and Materials Es	gisears	G		s Project # 21		3.8		DRILLER Fred Reynolds	
					s r tojeci w z	1-104	50		ON-SITE REP.	
BORING NO. / LOCA	TION			B-2				DRY O	N COMPLETION ? Yes	
DATE	July 8, 2016	i .	SURF	ACE ELEV.	1106.0	FT.			WATER LEVEL DATA (IF APPLICAE	BLE)
REFUSAL:		DEPTH 6.0		ELEV.					COMPLETION: DEPTH Dry FT.	
AMPLED	6.0 FT.	1.8	M	N 1943 3424					ELEV. FT.	
OP OF ROCK		DEPTH	FT.	ELEV.		FT.			AFTER 1 HRS: DEPTH Dry FT.	
IEGAN CORING		DEPTH	FT.	ELEV.		FT.			ELEV. FT.	
OOTAGE CORED (FT.						AFTER 24 HRS. DEPTH TNP FT.	
OTTOM OF HOLE	DEPTH	6.0	FT.	ELEV.	1100.0	FT,			ELEVFT.	
ORING ADVANCED	BY:		POWER.	AUGERING	x				PROPOSED FFE: FT.	
STRATUM	SAMPL	E DEPTH	SAMPLE		FIELD		LABORA	TORY		
DEPTH	FROM	то	OR	SAMPLE	RESULTS		RES	ULTS	STRATUM DESCRIPTION	
FT. ELEV.	FT.	FT.	RUN NO.	TYPE	N-Value	Qu	LL	PI %N		
-									-	
_									Lean CLAY (CL) - with shale fragmen shale like structure - orangish brown a	
<u>–</u>	1.0	2.5	1	SS	25				dry - very stiff to very hard	
2.5 - 1103.5									(RESIDUUM)	
-										
-									-	
-	3.5	4.7	2	SS	50/2"				- Weathered Shale - gray - dry	
5.0 - 1101.0				1 1						
-									-	
—									Auger Refusal at 6.0 Feet	
_				1 1					_	
7.5 - 1098.5										
-									F	
-									-	
-									_	
10.0 - 1096.0				1 1					-	
-									-	
-										
—									-	
12.5 - 1093.5				1 1					-	
-				1 1						
_									<u> </u>	
-									-	
15.0 - 1091.0									-	
_										
-				1 1					-	
—									-	
17.5 - 1088.5									-	
-									-	
									-	
									-	
20.0 - 1086.0						-				

GEE EllServices, LLC-Geetechni	S Cal and Materials Eng	S	G		an Station lle, Tenne s Project #	ssee	38			LOG OF BORING B-3 SHEET 1 OF 1 DRILLER Fred Reynolds ON-SITE REP.
ORING NO. / LOCAT	ION			B-3		_		DRY	ON C	COMPLETION ? Yes
DATE	July 8, 2016		SURF	ACE ELEV.	1107.0	FT.				WATER LEVEL DATA (IF APPLICABLE)
REFUSAL:	and the second se	EPTH 7.7	- N N N N N N N N.		1099.3	FT.				COMPLETION: DEPTH Dry FT.
SAMPLED	7.7 FT.	2.3	м	02250230		-				ELEV. FT.
OP OF ROCK	D	EPTH	FT.							AFTER 1 HRS: DEPTH Dry FT.
BEGAN CORING		EPTH	FT.	ELEV.	_	FT.				ELEVFT.
OOTAGE CORED (L	Comments		-FT.	10000	100000					AFTER 24 HRS. DEPTH TNP FT.
BOTTOM OF HOLE D		3 <u>-</u>	FT.	ELEV.	1107.0	FT.				ELEVFT.
BORING ADVANCED	BY;		POWER	AUGERING	х	-				PROPOSED FFE:FT.
STRATUM	SAMPLE	DEPTH	SAMPLE		FIELD		LABORATO	DRY	Т	
DEPTH	FROM	то	OR	SAMPLE	RESULTS	1	RESUL	-	_	STRATUM DESCRIPTION
FT. ELEV.	FT.	FT.	RUN NO.	TYPE	N-Value	Qu	LL F	PI %	м	Teneril (Clashes)
-									-	Topsoil (6 inches)
-									F	-
_	1.0	2.5	1	SS	21				Ľ	<u>-</u>
2.5 - 1104.5				1 1					-	-
									ŀ	
-									ŀ	 Lean CLAY (CL) - with shale fragments -
-	3,5	5.0	2	SS	38				T.	 orangish brown and gray - moist - very stiff (RESIDUUM)
5.0 - 1102.0				1 1					F	-
-									ŀ	
-									h	-
_	6.0	7.5	3	SS	33				Ľ	=.
7.5 - 1099.5				1 1					-	Auger Refusal at 7.7 feet
-									ł	- Auger Refusar at 7.7 feet
_				1 1					Ľ	
-									Γ.	-
10.0 - 1097.0				1					ł	-
-				1 1					ŀ	-
_									t	
_				1 1					F	
12.5 - 1094.5									-	
-				1 1					F	-
_									Ľ	-
-									-	-
15.0 - 1092.0									ŀ	
-									-	
-									L	
-									F	
17.5 - 1089.5									-	2
-									F	
									Ľ	
									[
-										

GE	599	5			an Station lle, Tennes					LOG OF BORING B-4
GERServices, LLC-Gentechnik	al and Materials Er	ginears	0		s Project # 2		138			DRILLER Fred Reynolds
										ON-SITE REP.
BORING NO. / LOCAT	ION			B-4		_		C	RY O	COMPLETION ? Yes
DATE	July B 2016		SURF	ACE FLEV	1106.0	FT		- 0 - 50		WATER LEVEL DATA (IF APPLICABLE)
REFUSAL:	the second s	DEPTH 20.0	74751.51		1086.0	-				COMPLETION: DEPTH Dry FT.
SAMPLED	20.0 FT.	6.1	• 0.00		1400.0	0.00				ELEVFT.
TOP OF ROCK		DEPTH	-	ELEV.		FT.				AFTER 1 HRS: DEPTH Dry FT.
BEGAN CORING	1	DEPTH	FT.	ELEV.		FT.				ELEV. FT.
FOOTAGE CORED (L	F)		FT.	3		59				AFTER 24 HRS. DEPTH TNP FT.
BOTTOM OF HOLE D	EPTH	20.0	FT.	ELEV.	1085.0	FT.				ELEVFT.
BORING ADVANCED	BY:		POWER	AUGERING	x					PROPOSED FFE: FT.
STRATUM	SAMPL	E DEPTH	SAMPLE	гi	FIELD	-	LABOR	ATORY		
DEPTH	FROM	то	OR	SAMPLE	RESULTS		11.2.2.2	SULTS		STRATUM DESCRIPTION
FT. ELEV.	FT,	FT.	RUN NO.	TYPE	N-Value	Qu		PI	%M	
-										-
_									1	
-	1.0	2.5	1	ss	7				1	Lean CLAY (CL) - with silt - brown - wet - fi (RESIDUUM)
	1.0	2.3			'				1	(RESIDOOM)
2.5 - 1103.5									1	-
-										-
—	22	1.1223	2	100	22.7					
-	3.5	5.0	2	SS	20				1	-
5.0 - 1101.0									1	-
-									1	-
_				1 1					1	
_	6.0	7.5	3	SS	20				I	Lean CLAY (CL) - with shale fragments ar
7.5 - 1098.5									1	 shale like structure - orangish brown and gr dry - very stiff
-									1	(RESIDUUM)
									1	-
-	8.5	10.0	3	SS	34					_
10.0 - 1096.0										_
-										-
—				1 1	1					-
									1	-
12.5 - 1093.5										-
-										-
-				1 1						-
-	13.5	14.7	4	\$\$	50/2"					
15.0 - 1091.0										-
-				1 1					1	-
_	6									 Weathered Shale - gray -very hard
_										_
17.5 - 1088.5										-
-										L
-										-
_	18.5	18.8	5	SS	50/4"					_
-		· · · · · · · · · · · · · · · · · · ·							·	
20.0 - 1086.0										Auger Refusal at 20.0 Feet

EEESe	SE (S S) I jineers	G		n Station le, Tennes Project # 2		38			LOG OF BORING B-5 SHEET 1 OF 1 DRILLER Fred Reynolds
1000100					2000/1100						ON-SITE REP.
BORIN	IG NO. / LOCAT	ION			B-5		_		D	RY ON	COMPLETION ? NO
DATE		July 8, 2016		SURF	ACE ELEV.	1108.0	FT.				WATER LEVEL DATA (IF APPLICABLE)
REFU	SAL:	Yes (DEPTH 9.0	FT.	ELEV.	1099.0	FT.				COMPLETION: DEPTH Dry FT.
SAMP	1743-184 Augusta	9.0 FT.	2.7								ELEVFT.
	OF ROCK		DEPTH 9.0	•	ELEV.	1099.0	FT.				AFTER 1 HRS: DEPTH Dry FT.
	N CORING AGE CORED (LI		DEPTH 9.0		ELEV.	1099.0	FT.				ELEV. FT.
	OM OF HOLE D		10.0		ELEV.	1089.0	FT.				AFTER 24 HRS. DEPTH TNP FT. ELEV. FT.
	G ADVANCED				ALCON CONTRACTOR	×					
101102		2021	+	100000000	AUGERING		-				PROPOSED FFE: FT.
9	STRATUM		E DEPTH	SAMPLE		FIELD	a 1		ATORY	8	
FT.	DEPTH ELEV.	FROM FT.	TO FT.	OR RUN NO.	SAMPLE	RESULTS N-Value	Qu	LL	PI	%M	STRATUM DESCRIPTION
<u>e</u> t-	IIII ELEV.	F1.	P1,	HUN NU.	TIPE	N-Value	du	LL	1	75.00	Topsoil (4 Inches)
	÷	1.0	1.8	1	SS	50/4"					Lean CLAY (CL) - with silt and shale fragments - orangish brown and gray - dry - very hard (RESIDUUM)
2.5 5.0 7.5	- 1105.5 - - - 1103.0 - - - - 1100.5 - - - - - - - - - - - - - - - - - - -	3.5 6.0 8.5	4.3 6.5 8.5	3	SS SS SS	50/3" 50/0					Weathered Shale - orangish brown and gray - very hard Auger Refusal at 9.0 Feet Begin Coring at 9.0 feet
12.5	Ξ										 Run #1 (9.0 to 14.0 feet) REC - 40% RQD - 0% Weathered Shale - orangish brown and brown - with calcite healed veins and evidence of water transport - moderately fractured and moderately to heavily weathered
15.0	- 1093.0 - -										Run #2 (14.0 to 19.0 feet) REC - 40% RQD - 0%
17.5	- 1090.5										Weathered Shale - orangish brown and brown - moderately fractured and moderately to heavily weathered
	-										 Coring Terminated at 19.0 Feet
20.0	- 1088.0										

/	540			Bea	n Station					LOG OF BORING B-6
				Knoxvil	le, Tennes	ssee				SHEET 1 OF 1
GL&Services, LLC-Seutechnic	al and Materials Eng	gineers	G	EOServices	s Project # 2	21-164	138			DRILLER Fred Reynolds
										ON-SITE REP.
ORING NO. / LOCAT	ION			B-6				D	RYON	COMPLETION ? Yes
ATE	July 8, 2016		SURF	ACE ELEV.						WATER LEVEL DATA (IF APPLICABLE)
1251233208		DEPTH 22.5	FT.	ELEV.	1106.0	FT.				COMPLETION: DEPTH Dry FT.
AMPLED -	22.5 FT.	6.9								ELEVFT.
OP OF ROCK			FT.	ELEV.		FT.				AFTER 1 HRS: DEPTH Dry FT.
EGAN CORING DOTAGE CORED (LF			FT.	ELEV.		- 11				ELEVFT. AFTER 24 HRS. DEPTH TNP FT.
OTTOM OF HOLE D		22.5		ELEV.	-22.5	FT.				ELEV. FT.
ORING ADVANCED			• 105 Verseterines	AUGERING	x					PROPOSED FFE: FT.
						-				
STRATUM		DEPTH	SAMPLE		FIELD		LABOR		2	
PT. ELEV.	FROM FT.	TO FT.	OR RUN NO.	SAMPLE	RESULTS N-Value	Qu	LL	PI	%M	STRATUM DESCRIPTION
PT. III BLEV.	11.	16	NUN NO.	TIPE	N-Value	Gu		n	79 m	Topsoil (7 Inches)
_										
-	52/2/1	1993	80	1000	1922					-
_	1.0	2.5	1	SS	10					-
2.52.5										
- 1										-
_	100511	100	1.25	1022.1	0.02					_
-	3.5	5.0	2	SS	12					-
5.05.0				1 1						-
-										
-	22.1	100	- 31	100	122					-
-	6.0	7.5	3	SS	21					Lean CLAY (CL) - with silt - light brown and
7.57.5										orangish brown - moist - stiff
- 1										(RESIDUUM)
_										_
-	8.5	10.0	4	SS	18					-
10.010.0										-
_										-
-										-
-				1 1						-
12.512.5										-
-				1 1						-
-	1000	20.0	12		10					
	13.5	15.0	5	SS	19					-
15.015.0										
_										<u> </u>
-										-
-										Weathered Shale - gray - dry - very stiff to very
7.517.5										- hard
-										-
-	10.5	10.4	6	SS	50/1*					_
20.020.0	18.5	19.1	0	00	bull.					-
					-			-		Auger Refusal at 22.5 Feet

GEE	S Caland Materials En	5		Knoxvil	In Station le, Tennes s Project # 2		28			LOG OF BORING B-7 SHEET 1 OF 1 DRILLER Fred Reynolds		
				ECOBINOS	s riojeci # 2	1-104	50			ON-SITE REP.		
BORING NO. / LOCAT	ION			B-7				DR	Y ON COM	IPLETION ? No		
DATE REFUSAL: SAMPLED TOP OF ROCK BEGAN CORING FOOTAGE CORED (LI BOTTOM OF HOLE D	17.2 FT.	DEPTH 17.2 5.2 DEPTH	FT. M FT. FT.	ELEV.	1106.0 1088.8 1088.8	FT. FT.			A	WATER LEVEL DATA (IF APPLICABLE) COMPLETION: DEPTH 8.0 FT. ELEV. FT. FT. FTER 1 HRS: DEPTH Dry FT. ELEV. FT. FT. FTER 24 HRS. DEPTH TNP FT. ELEV. FT. FT. FT.		
BORING ADVANCED	BY:		POWER	AUGERING	x		3		200	PROPOSED FFE: FT.		
STRATUM		DEPTH	SAMPLE		FIELD		LABORA			STRATUM DESCRIPTION		
DEPTH FT. ELEV.	FROM FT.	TO FT.	OR RUN NO.	SAMPLE	RESULTS N-Value	RESULTS			STRATUM DESCRIPTION			
2.5 - 1103.5 - - 5.0 - 1101.0	1.0 3.5	2.5	1	SS SS	8					ean CLAY (CL) - with abundant wood fragmen at depth - brown and dark brown - moist (FILL)		
- - 7.5 - 1098.5	6.0	6.8	3	SS	50/3*				-	Lean CLAY (CL) - with shale fragments and shale like structure - gray - moist to wet (RESIDUUM)		
- - 10.0 - 1096.0 -	8.5	8.9	4	88	50/5*							
12.5 - 1093.5 	13.5	13.7	5	55	50/2*					Weathered Shale - gray - dry - very hard		
17.5 - 1088.5	12									Auger Refusal at 17.2 Feet		

GEBServices, LLC-Geetech		-Joseph -	G	EOService	s Project # :	21-164	38			ORILLER Fred Reynolds ON-SITE REP.	
BORING NO. / LOC/	TION			B-8				DR	Y ON	I COMPLETION ? Yes	
DATE	July 8, 2016		SURF	ACE ELEV.	1113.0	FT.				WATER LEVEL DATA (IF APPLICABLE)	
REFUSAL:		DEPTH 16.7	FT.	ELEV.	1096.3	FT.				COMPLETION: DEPTH Dry FT.	
SAMPLED	16.7 FT.	5.1	-	5		-				ELEV. FT.	
TOP OF ROCK		DEPTH	- C.	ELEV.		FT.				AFTER 1 HRS: DEPTH Dry FT.	
BEGAN CORING FOOTAGE CORED		DEPTH	-	ELEV.		FT.				ELEVFT.	
BOTTOM OF HOLE		16.7	FT.	ELEV	1096.3	FT				AFTER 24 HRS. DEPTH TNP FT. ELEV. FT.	
BORING ADVANCE			and the second	AUGERING	x	-				PROPOSED FFE: FT.	
STRATUM		E DEPTH	SAMPLE		FIELD	-		1004	_	PROFUSED FFEF1.	
DEPTH	FROM	то	OR	SAMPLE	RESULTS	S - D	LABORAT			STRATUM DESCRIPTION	
FT. ELEV.	FT.	FT.	RUN NO.	TYPE	N-Value	Qu			%M	STRATUM DESCRIPTION	
-										-	
—										_	
-	1.0	1.6	1	SS	50/1"					-	
2.5 - 1110.5										-	
_										-	
- - -										-	
-	3.5	3.9	2	SS	50/4"					_	
5.0 - 1108.0							2				
-				1 1						-	
-	Traney (19925								-	
—	6,0	6.4	3		50/5"						
7.5 - 1105.5										-	
_	8.5	9.2	4	SS	50/2*					Weathered Shale - gray - dry - very hard	
- 1103.0	1110000				oute					-	
										-	
_											
-										-	
12.5 - 1100.5										-	
-										-	
_											
-	13.5	13.5	5	SS	50/0					-	
15.0 - 1098.0											
_									1		
-										-	
17.5 - 1095.5										Auger Refusal at 16.7 Feet	
-										-	
-									ł		
	1	. 1		I I		. 1			- 1	-	



Appalachian Electric Cooperative Substation

GEOServices Project No. 21-19057 February 13, 2019

SOIL DATA SUMMARY

			SOIL DAT					_
Boring	Sample	Depth	Natural Moisture	Att	erberg Lir	nits	Soil	Percent
Number	Number	(feet)	Content	LL	PL	PI	Type	Organic Content
B-3	1	1.0-2.5'	23.9%		1 L/		Type	content
	2	3.5-5.0'	26.7%					
	3	6.0-7.5'	23.3%					
	4	8.5-10.0'	24.3%					
	5	13.5-15.0'	31.4%					
	6	18.5-20.0'	32.3%					
	7	23.5-25.0'	41.1%					
	8	28.5-30.0'	41.0%					
	9	33.5-35.0'	29.8%					
	10	38.5-40.0'	29.9%					
	11	43.5-45.0	35.9%					
	12	48.5-50.0'	27.8%					
B-4	1	1.0-2.5'	24.0%					
	2	3.5-5.0'	23.6%	71	18	53	СН	
	3	6.0-7.5'	22.7%					
	4	8.5-10.0'	34.3%					
	5	13.5-15.0'	41.0%					
	6	18.5-20.0'	39.6%					
	7	23.5-25.0'	50.3%					
	8	28.5-30.0'	48.4%					
	9	33.5-35.0'	44.0%					
	10	38.5-40.0'	41.8%					
	11	43.5-45.0'	59.3%					
	12	48.5-50.0'	63.2%					
	13	53.5-55.0'	63.3%					
	15	63.5-65.0'	51.7%					




Appalachian Electric Cooperative Substation

GEOServices Project No. 21-19057 February 13, 2019


SOIL DATA SUMMARY

Boring	Sample	Depth	Natural Moisture	At	terberg Lin	nits	Soil	Percent Organic
Number	Number	(feet)	Content	LL	PL	PI	Туре	Content
B-8	1	1.0-2.5'	25.7%					8.1
	3	6.0-7.5'	27.7%					
	4	8.5-10.0'	34.9%					
	5	13.5-15.0'	38.0%					
	6	18.5-20.0'	41.5%					
	7	23.5-25.0'	38.8%					
B-9	1	1.0-2.5'	26.8%					4.9
	2	3.5-5.0'	27.0%	58	20	38	СН	
	3	6.0-7.5'	28.8%					
	4	8.5-10.0'	29.9%					
	5	13.5-15.0'	38.6%					
	6	18.5-20.0'	41.3%					
	7	23.5-25.0'	55.9%					
	8	28.5-30.0'	63.8%					
	9	33.5-35.0'	59.2%					
B10	1	1.0-2.5'	27.1%					
	2	3.5-5.0'	27.5%					
	3	6.0-7.5'	28.7%	82	25	57	CH	
	4	8.5-10.0'	33.6%					
	5	13.5-15.0'	36.2%					
	6	18.5-20.0'	37.1%					
	7	23.5-25.0'	37.3%					



Appendix C: Environmental Calculations

SMOKY MOUNTAIN FOUND BEN MORRIS Transformer oil runoff one(1) transformer @ 750 gallons: 750 gallons Hurre (3) voltage regulators @ 55 gallons: 165 gallons 750 g + 165 g = 915 gallons | gallon = 0.00378541 gallons 915 g (0.00378541) = 3.5 m³ factor of safety = 2 final oil contamment pord volume = 7 mis 1 gallon = 0.133681 ft $915g(0.13368iff^3) = 122.4ff^3$ factor of safety = 2 final oil containment pond volume = 244.8 fr



Silt Fence J-Hook Layout

	Volume (Gallons)	Quantity	Total Oil (Gallons)
Transformer Oil	750	1	750
Voltage Regulator Oil	55	3	165
			915

Maximum Oil Runoff

Appendix D: Water Resources Calculations

BEN MORRIS SMORY MOUNTAIN FOUND. 25 year, 24 have storm Quetore = (1.10) (0.41) (5.5 in/hr) (3.25 ac) = 8.01 cfs Qafter = (1.10)(0.70)(5.5 m/hr)(3.25 ac) = 13.76 cfs all values from nonoff coefficient table in Appendix O Grading 70 slope = AY/AX $2\% = \Delta w/looft$ Ay = Zfr of elevation decrease from West to East beginning at the 1250' elevation point. pre-existing slope for erosion control plan 70 slope = Dy/AX 7 = (1252 - 1240)/224 ft= 0.0536 = 5.36% 5.36% < 33.3% silt fence is sufficient

25-year 24-hour maximum rainwater runoff calculations:

Maximum Runoff Equation: Q = (frequency factor)*C*I*A

C= Runoff Coefficient

I=Average Rainfall Intensity (in/hr)

A= Area (acres)

			Runo	off Coeffic	cient (C) b	y Hydrolo	gic Soil G	Froup and	Ground \$	Slope		
Land Use		Α			В			С		D		
	<2%	2 - 6%	>6%	<2%	2 - 6%	>6%	<2%	2 - 6%	>6%	<2%	2 - 6%	>6%
Forest	0.08	0.11	0.14	0.10	0.14	0.18	0.12	0.16	0.20	0.15	0.20	0.25
Meadow	0.14	0.22	0.30	0.20	0.28	0.37	0.26	0.35	0.44	0.30	0.40	0.50
Pasture	0.15	0.25	0.37	0.23	0.34	0.45	0.30	0.42	0.52	0.37	0.50	0.62
Farmland	0.14	0.18	0.22	0.16	0.21	0.28	0.20	0.25	0.34	0.24	0.29	0.41
Res. 1 acre	0.22	0.26	0.29	0.24	0.28	0.34	0.28	0.32	0.40	0.31	0.35	0.46
Res. 1/2 acre	0.25	0.29	0.32	0.28	0.32	0.36	0.31	0.35	0.42	0.34	0.38	0.46
Res. 1/3 acre	0.28	0.32	0.35	0.30	0.35	0.39	0.33	0.38	0.45	0.36	0.40	0.50
Res. 1/4 acre	0.30	0.34	0.37	0.33	0.37	0.42	0.36	0.40	0.47	0.38	0.42	0.52
Res. 1/8 acre	0.33	0.37	0.40	0.35	0.39	0.44	0.38	0.42	0.49	0.41	0.45	0.54
Industrial	0.85	0.85	0.86	0.85	0.86	0.86	0.86	0.86	0.87	0.86	0.86	0.88
Commercial	0.88	0.88	0.89	0.89	0.89	0.89	0.89	0.89	0.90	0.89	0.89	0.90
Streets: ROW	0.76	0.77	0.79	0.80	0.82	0.84	0.84	0.85	0.89	0.89	0.91	0.95
Parking	0.95	0.96	0.97	0.95	0.96	0.97	0.95	0.96	0.97	0.95	0.96	0.97
Disturbed Area	0.65	0.67	0.69	0.66	0.68	0.70	0.68	0.70	0.72	0.69	0.72	0.75

Runoff Coefficient Table

$$Q(after) = (1.10) * (0.70) * (5.5 in/hr) * (3.25 acres) = 13.76 cfs$$

$$Q (before) = (1.10) * (0.41) * (5.5 in/hr) * (3.25 acres) = 8.01 cfs$$

Appendix E: Transportation Study

	Nourthbound	Traffic	Southbound	Traffic
Time Slot	Count	Time (sec)	Count	Time (sec)
		3.4		3.4
		3.86		4.38
		3.49		3.23
7:30 - 7:45	15	3.03	15	2.85
		3.63		5.12
		4.08 3.56		3 3.85
		3.62		3.3
	-	3.55		3.32
		3.73		3.98
		3.63		2.82
		3.63		3.02
7:45 - 8:00	12	3.86	10	3.3
		2.76		3.42
		3.58		3.62
		2.65		
		3.22		
		3.71		4.63
1		4.26		3.72
1		4.09 3.96		3.49 3.83
1		3.96		3.83
1		3.46		3.63
8:00 - 8:15	15	3.7	14	2.95
0.00 - 0.15		2.33		3.4
1		4.38		3.56
1		3.38		3.72
		2.85		
		3.62		
		3.55		
		4.22		3.36
		3.2		3.39
		2.68	9	3.96
		3.53		3.78
8:15 - 8:30	13	3.4		2.96
		3.13 4.25		3.96 3
		3.02		3.92
		2.85		3.52
		3.23		
		3.25		3.16
		3.32		2.85
		3.66		3.68
		2.15		3.9
1		2.87		4.82
1		3.22		3.55
1		3.13		4
8:30 - 8:45	21	3.48 3.03	18	3.82 4.78
1		3.03		4.78
1		3.18		3.73
1		3.52		3.53
1		4.19*		3.95
1				3.73
1				3.65
				4.15
		2.86		3.55
		3.35		3.33
1		2.96		4.58
1		3.45		3.32
1		3.5		4.43
1		3.46 3.08		3.36 3.15
1		3.08		4.36
8:45 - 9:00	17	2,95	25	4.56
5.45 - 5.00	1/	2.95	25	2.95
1		3.53		4.41
		3.12		3.3
1				4.06
1				3.13
1				3.11
		1		
				4.23

	Northbound	Southbound
Average	3.3890625	3.655151515
	59.01337022	54.71729398
	40.23638878	37.3072459

	Northbound	Southbound
Total Traffic Count	93	91
Average Time	3.39	3.66
Average Speed (ft/s)	59.01	54.72
Average Speed (mph)	40.24	37.31

3.2366666667 61.79196704 42.13088662

85.83690987 58.52516582

93.02325581 63.42494715 66.666666667 45.45454545

*=heavy


184

	Northbound	Southbound
Total Traffic Count	93	91
Average Time	3.39	3.66
Average Speed (ft/s)	59.01	54.72
Average Speed (mph)	40.24	37.31

Nourthbound Traffic Southbound Traffic Time Slot Count Time (sec) Count Time (sec) 3.4 3.4 3.4 3.4 3.86 4.3 3.49 3.2 3.03 15 3.63 5.1 4.08 3 3.55 3.8 3.62 3.55 3.3 3.63 3.55 3.3 3.63 3.63 2.8 3.63 3.63 2.8 3.63 3.63 3.0 7:45 - 8:00 12 3.86 10 3.5 3.63 3.63 3.6 3.6 3.6 7:45 - 8:00 12 3.66 10 3.5 3.63 3.63 3.6 3.6 3.6 4.26 3.71 4.6 3.7 4.09 3.4 3.96 3.7 14 2.9 3.7 3.8 3.64 3.7 3.4 3.5 3.6 3	(sec) 4 4 88 35 55 33 35 55 33 22 38 88 22 33 22 33 22 33 22 23 33 23 2
7:30 - 7:45 15 3.4 3.4 3.86 3.34 3.3 3.49 3.2 3.63 15 3.2 3.63 15 3.3 3.66 3.8 3.6 3.63 3.56 3.3 3.55 3.3 3.5 3.63 3.63 3.6 3.63 2.8 3.63 3.63 3.6 3.6 3.63 2.8 3.63 3.63 2.8 3.6 3.63 3.0 3.6 3.63 2.8 3.6 3.63 2.8 3.6 3.63 2.8 3.6 3.63 2.8 3.6 3.63 3.0 3.6 3.63 3.6 3.0 3.63 3.6 3.6 3.63 3.6 3.6 3.63 3.2 3.6 3.64 3.6 3.7 3.7 1	4 4 4 4 4 4 4 4 5 5 5 5 5 3 3 2 2 5 5 5 5 5 5 5 5 5 5 5 5 5
7:30 - 7:45 15 3.49 3.03 3.63 15 2.8 3.63 3.63 3.66 3.8 3.56 3.8 3.62 3.3 3.73 3.62 3.3 3.63 2.8 3.63 3.8 3.73 3.63 3.63 2.8 3.63 3.63 3.0 3.63 3.0 3.0 3.73 3.63 2.8 3.63 3.0 3.0 3.63 7:45 - 8:00 12 3.86 10 2.76 3.4 3.58 3.6 3.6 3.62 3.0 3.0 3.0 3.6 3.6 3.6 8:00 - 8:15 15 3.7 14 2.9 3.7 2.85 3.38 3.7 14 2.9 3.7 3.38 3.7 3.7 2.85 3.62 3.7	23 35 35 35 37 37 37 37 37 37 37 37 37 37
7:30 - 7:45 15 3.03 3.63 15 2.8 5.1 4.08 3.63 3.56 3.8 3.56 3.8 3.62 3.3 3.62 3.3 3.55 3.3 3.62 3.3 3.55 3.3 3.63 2.8 3.63 2.8 3.63 3.63 3.0 3.55 3.63 3.63 3.6 3.6 3.63 2.8 3.63 3.6 3.63 2.8 3.63 3.6 3.63 2.8 3.63 2.8 3.63 2.8 3.63 2.8 3.63 2.8 3.63 2.8 3.63 2.8 3.63 2.8 3.63 3.63 3.0 3.6 2.76 3.4 3.58 3.6 3.71 4.66 3.7 4.09 3.4 3.58 3.6 3.6 3.6 3.77 14 2.9 3.3 3.7 2.85 <td< td=""><td>35 12 35 35 35 36 37 38 37 37 37 37 37 37 37 37 37 37</td></td<>	35 12 35 35 35 36 37 38 37 37 37 37 37 37 37 37 37 37
7:30 - 7:45 15 3.63 15 5.1 4.08 3 3 3 3 3 3.56 3.8 3.62 3.3 3 3 3.62 3.3 3.9 3.63 2.8 3.63 2.8 3.63 2.8 3.63 2.8 3.63 2.8 3.63 3.9 3.63 3.63 2.8 3.63 2.8 3.63 3.0 7:45 - 8:00 12 3.86 10 3.1 3.6 3.6 2.76 3.4 3.58 3.6 3.6 3.6 3.6 2.65 3.22	12 355 33 322 38 32 33 32 22 33 33 32 22 33 33 22 33 33
3.63 5.1 4.08 3 3.56 3.8 3.62 3.1 3.62 3.1 3.62 3.1 3.62 3.1 3.63 2.8 3.63 2.8 3.63 2.8 3.63 2.8 3.63 2.8 3.63 2.8 3.63 2.8 3.63 2.8 3.63 2.8 3.63 2.8 3.63 2.8 3.63 2.8 3.63 2.8 3.63 3.0 2.76 3.4 3.58 3.6 3.22 - 3.71 4.6 4.26 3.7 4.09 3.4 3.58 3.6 3.46 3.1 3.58 3.6 3.438 3.5 3.38 3.7 2.85 3.62	35 33 32 32 32 32 32 32 33 32 33 32 33 33
3.56 3.8 3.62 3.3 3.62 3.3 3.73 3.9 3.63 2.8 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 2.76 3.4 3.58 3.6 2.65 3.22 3.71 4.6 4.26 3.7 4.09 3.4 3.96 3.8 3.46 3.1 3.58 3.6 3.38 3.7 2.33 3.7 4.38 3.5 3.38 3.7 <td>35 3 32 33 33 33 33 33 34 35 35 35 35 35 35 35 35 35 35</td>	35 3 32 33 33 33 33 33 34 35 35 35 35 35 35 35 35 35 35
3.62 3.3 3.55 3.3 3.73 3.9 3.63 2.8 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 2.76 3.4 3.58 3.6 3.90 3.2 4.09 3.4 3.96 3.8 3.46 3.1 3.58 3.6 3.46 3.1 3.58 3.6 3.38 3.7 4.38 3.5 3.38 3.7 2.85 3.62	3 32 33 33 33 34 32 33 34 35 35 35 35 35 35 35 35 35 35 35 35 35
3.55 3.3 3.73 3.9 3.63 2.8 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 2.76 3.4 3.58 3.6 2.65 3.22 3.71 4.6 4.26 3.7 4.09 3.4 3.96 3.8 3.46 3.1 3.58 3.6 3.46 3.1 3.58 3.6 3.38 3.7 2.33 3. 4.38 3.5 3.38 3.7 2.85 3.62	32 38 32 32 33 42 52 53 53 53 53 53 53 53 55 54 56 55 55 55 55 55 55 55 55 55
3.73 3.9 3.63 2.8 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 2.76 3.4 3.58 3.6 2.65 3.22 3.22 3.22 4.09 3.4 3.96 3.8 3.46 3.1 3.96 3.8 3.46 3.1 3.58 3.6 3.46 3.1 3.58 3.6 4.38 3.5 3.38 3.7 4.38 3.5 3.38 3.7 2.85 3.62	98 32 33 42 52 53 53 72 49 33 95 53 95 4 56
3.63 2.8 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 3.63 3.0 2.76 3.4 3.58 3.6 2.65 3.22 3.22 3.22 3.71 4.6 4.26 3.7 4.09 3.4 3.96 3.8 3.46 3.1 3.58 3.6 3.46 3.1 3.58 3.6 3.46 3.1 3.58 3.6 3.43 3.5 3.38 3.5 3.38 3.7 2.85 3.62	82 33 42 55 55 53 72 49 33 39 53 53 55 4 56
7:45 - 8:00 12 3.63 3.86 10 3.0 3.2 7:45 - 8:00 12 3.86 2.65 3.22 10 3.4 3.6 3.63 8:00 - 8:15 15 3.71 3.71 4.6 4.26 3.71 4.6 3.7 4.09 4.09 3.4 3.96 3.46 3.1 3.58 3.46 3.6 3.1 3.58 3.38 3.6 3.1 3.5 3.38 8:00 - 8:15 15 3.7 14 14 2.9 2.85 3.38 3.7 4.38 3.5 3.38 3.7 14 2.9 3.62 3.7	02 3 42 52 53 72 49 33 39 53 53 55 4 56
7:45 - 8:00 12 3.86 10 3.3 2.76 3.4 3.58 3.6 2.65 3.22 - - 3.71 4.6 3.7 - 4.09 3.4 3.96 3.8 3.46 3.1 3.6 3.6 3.96 3.88 3.6 3.1 3.96 3.88 3.66 3.1 3.58 3.66 3.1 3.58 3.66 3.1 3.58 3.6 3.6 3.37 14 2.9 2.33 3.3 3.4 4.38 3.5 3.38 3.38 3.7 14 2.85 3.62 3.7	3 12 52 53 53 72 19 33 19 53 55 4 56
2.76 3.4 3.58 3.6 2.65 3.22 3.71 4.6 4.26 3.7 4.09 3.4 3.96 3.8 3.46 3.1 3.58 3.6 3.77 14 2.33 3.7 4.38 3.5 3.38 3.7 2.33 3.7 4.38 3.5 3.38 3.7 2.85 3.62	12 52 53 53 72 19 33 19 53 55 4 4 56
3.58 3.6 2.65 3.22 3.71 4.6 4.26 3.7 4.09 3.4 3.96 3.8 3.46 3.1 3.58 3.6 3.46 3.1 3.58 3.6 3.46 3.1 3.58 3.6 3.46 3.1 3.58 3.6 3.43 3.5 3.7 14 2.9 2.33 3.7 4.38 3.5 3.38 3.7 2.85 3.62	52 53 72 19 33 19 53 55 4 4 56
2.65 3.22 3.71 4.6 4.26 3.7 4.09 3.4 3.96 3.8 3.46 3.1 3.58 3.6 2.33 3.4 4.38 3.5 3.38 3.7 4.38 3.5 3.38 3.7 4.38 3.5 3.38 3.7 2.85 3.62	53 72 19 33 19 53 53 55 4 56
3.22 3.71 4.6 3.71 4.26 3.7 4.26 3.7 4.09 3.4 3.96 3.8 3.46 3.1 3.58 3.6 3.6 3.6 2.33 3.4 3.5 3.6 3.38 3.7 14 2.9 2.33 3.4 3.5 3.6 3.38 3.7 2.85 3.62	72 19 33 19 53 53 95 4 56
3.71 4.6 4.26 3.7 4.09 3.4 3.96 3.8 3.46 3.1 3.58 3.6 2.33 3. 4.38 3.5 3.38 3.7 2.85 3.62	72 19 33 19 53 53 95 4 56
4.26 3.7 4.09 3.4 3.96 3.8 3.46 3.1 3.58 3.6 2.33 3.4 4.38 3.5 3.38 3.7 2.85 3.62	72 19 33 19 53 53 95 4 56
4.09 3.4 3.96 3.8 3.46 3.1 3.58 3.6 2.33 3.4 4.38 3.5 3.38 3.7 2.85 3.62	19 33 19 53 95 4 56
3.96 3.8 3.46 3.1 3.58 3.6 8:00 - 8:15 15 3.7 14 2.9 2.33 3.4 3.5 3.5 4.38 3.5 3.38 3.7 2.85 3.62 4.38 3.5	33 19 53 95 4 56
3.46 3.1 3.58 3.6 8:00 - 8:15 15 3.7 14 2.9 2.33 3.4 3.5 3.4 4.38 3.5 3.38 3.7 2.85 3.62 4.38 3.5	19 53 95 4 56
8:00 - 8:15 15 3.58 3.6 2.33 3.4 4.38 3.5 3.38 3.7 2.85 3.62	53 95 4 56
8:00 - 8:15 15 3.7 14 2.9 2.33 3.4 3.4 3.5 3.4 4.38 3.5 3.38 3.7 2.85 3.62 3.62 3.62	95 4 56
2.33 3.4 4.38 3.5 3.38 3.7 2.85 3.62	4 56
4.38 3.5 3.38 3.7 2.85 3.62	6
3.38 3.7 2.85 3.62	
2.85 3.62	17
3.62	2
3.55	
4.22 3.3	
3.2 3.3	
2.68 3.9	
3.53 3.7	
8:15 - 8:30 13 3.4 9 2.9	
3.13 3.9	
4.25 3	
3.02 3.9	12
2.85	
3.23	
3.25 3.1	
3.32 2.8	
3.66 3.6 2.15 3.1	
2.87 4.8 3.22 3.5	
3.13 4 3.48 40 3.8	
8:30 - 8:45 21 3.03 18 4.7	
3.83 3.5	
3.18 3.7	
3.52 3.5	
4.19*	
3.7	
3.6	
4.1	
2.86 3.5	
3.35 3.3	
2.96 4.5	
3.45 3.3	
3.5 4.4	
3.46 3.3	
3.08 3.1	
3.46 4.3	
8:45 - 9:00 17 2.95 25 4.0	
2.88 2.9	
3.53 4.4	1
3.12 3.1	
4.0	
3.1	
3.1	
4.2	
4.0	

CA I 11' love midths 2222 6. ft Tur- 200'- 400' 14' Bridge acry from strky 200' Timing Southbourd Southoond Herry North bound Henry 7:45-8:00 LHT 114 1 17/1 11/1 11/1 11/1 11 1247211) 411 LHA LHI 11 8:00+ FIS 1111 14+1 UT UM m. lish 41/111 \$:15: 13 141 LHH 111 8:30- 8:45 Un un 1 HH LATILIT 471 1/1 \$:45-910 HH 1HT. Lan uni Un 1 Litt Litt 111 オ

Appendix F: Construction Scheduling





Zinc Substation Earthwork Section 2 - ((155 +1059) - (1006) (0.5) (10) - (750 ++ cot 2 · ((1250+1252) - (1248) (20') (10') - 3000 #13 un 7= (1251 - Was) (0.5) (100) 120') = 7000ft' at 4 - (1251-1248) 10.5) (40) (46) = 0400 fa) cur 5 - (1151-1244) (70) (2+) - 5250 47cet 6= /(12507-10" [-1148) (75)(25) = 1750 fe' cit 7 = (1 - 437.5 files) (35)(25) (0.5) = 437.5 files 8 = ((1210+1)) (1244)) (40) (35) (6.5) = 702 fe) cor 9 = ((1010 + 104))(104))(40)(30) = 1200 farat 10 - ((150 + 1000) - (1000) (40) (30) - 1200 fain E (4 = 24000 fa 3, 11 1) = (1248-1 1240+1246)) (20) (20) (20) = 800 fer 4.1 13 - (1048 - (") (100) (15) = 1750 ft f.1 17 = (1248 - (124 +124 c)) 10.5) (140) (35) - 3675 fe) fil 15 = (1048 - (104+1046))(05)(40)(15) = 300 ft' fin 16 = (1348 - (1341 + 1347))(80)(70) = 120. fr) Fill 17 = (1041- (1041+1046)) 1001230) = 6000 fai fin 18 = (1003 - (1003+1002)) (0.5)(20)(00) = 100 f+3 r.11 14= (124x- (1246+1245))(0.5)(150/(40) - 7500 fts fit 20 = (1248- (1246+1244)) (70) (40) = 3000 ftirit 21 - (1248- (1244+1343)) (0.5) (40) (20) - 1800 ft) f. 1 2 f: 11: 2672+ A) $\begin{cases} 20+ - f: || = 26000 fri - 2600 fi - 725 fi + 100$ $725 ft' <math>\left(\frac{1}{22} \frac{y1}{fri}\right) = 26 ys fi + 110$

C	Ernce $\forall Barbaire}$ Northalde : $\sqrt{(331)^2 + (1202.38)^2} = 331.65 = 332$ Southalde = $\sqrt{(2320)^2 + (1256 - 1206)^2} = 239.8 = 3.80$ Teastside = $\sqrt{(2320.63)^2 + (1256 - 1206)^2} = 239.8 = 3.80$ Teastside = $107.03 + 123.92 + 316.32 + 6124 Greet = 553.6 = 552$ Attiside = $101.52 + 182.02 + 202.68 = 0.855.2 = 0.466^2$ Total Frace = $332 + 282 + 554 + 486 = 1652^2$ Total Frace = 704.1 Frace + $12^2 = 1652 + 12^2 = 1667$
	lorner/lend=Purt = 4+d = 6
C	

War and and

いていていていたいないのの

i kan din sa dia minan


ころしょう できてき あたちまんしょう


1

and the fill all we we we have a first the TOOT O Store Steping Area = 200' x 80' x (1")(#:1: 5]33; 30 43 Road = 220' x 20' (4") (15+) = 1466.117 # 321467 F? Bridge = (13)(15")(16")(10") +(4)(10")(15")(20") = 10.0 fr) = (2')(10') + 4 (12')(10') = 600 ++2

1 2		ask Name	Duration	Start	Mar 1 S	0, '19 T	 т s	Mar 17 M	, '19 W	F M	ar 24, '19 5 T	Э т	Mar 3	1, '19 1 W	Ap F	or 7, '19 S T	T	Apr 14, S M	'19 w	Apr :	21, '19 T T	
	🖈 S	ubstation Foundation	52 days	Tue 3/12/19							, 1		5 10					5 141				
•	-,	Temporary	2 days	Tue 3/12/19																		
3	-	Bridge	2 days	Tue 3/12/19	ŀ																	
4	*	Place Concrete	1 day	Tue 3/12/19																		
5	*	Place Stone	1 day	Wed 3/13/19																		
6	*	Site Development	27 days	Thu 3/14/19		P	-					-					-			1		
7		Site Protection	14 days	Thu 3/14/19		-	-	-				_		-1								
8	*	Place Chain Link	14 days	Thu 3/14/19			-	-				-										
9	*	Erosion Control	1 day	Tue 4/2/19																		
10	*	Place Silt Fence	1 day	Tue 4/2/19									9									
11	*	Temporary	1 day	Wed 4/3/19																		
12	*	Place Stone	1 day	Wed 4/3/19										L								
13	*	Staging Area	1 day	Thu 4/4/19																		
14	*	Place Stone	1 day	Thu 4/4/19											հ							
15	*	Grading Site	10 days	Fri 4/5/19													-					
16	*	Excavate Portion	2 days	Fri 4/5/19																		
17	*	Fill Portion	1 day	Sun 4/7/19												հ						
18	*	Compact Site	4 days	Mon 4/8/19											I							
19	*	Grade Site to	3 days	Fri 4/12/19															հ			
20	*	Foundation	23 days	Wed 4/17/19														4	J			_
21	*	Lightening	10 days	Wed 4/17/19															J			_
22	*	Place Copper Wire	10 days	Wed 4/17/19																		
23		Concrete	12 days	Wed 5/1/19																		
24		Place Forms	1 day	Wed 5/1/19																		
25	*	Place Rebar	1 day	Thu 5/2/19																		
26	*	Pour Concrete	2 days	Fri 5/3/19																		
27	*	Cure Concrete	7 days	Tue 5/7/19																		
28	*	Strip Forms	1 day	Thu 5/16/19																		
29	*	Backfill	1 day	Fri 5/17/19																		
30	*	Backfill Around	1 day	Fri 5/17/19																		

Page 1





Appendix G: Item Cost Breakdown

Cost Analysis												
Activity	Quantity	Unit	Daily Output	Duration (Days)	Material \$/Unit	Material Cost	Labor \$/Unit	Labor Cost	Equipment \$/Unit	Equipment Cost	Total Cost	Reference
Place Concrete Pipe	12	L.F.	-	0.5	55.98	671.76	-	-	-	-	671.76	TDOT 607-03.02
Stone for Construction Entrance	5 layers of 120	S.F.	6000	0.1	38	22800	0.22	132	0.02	12	22944	RS Means - 31.23.23.17-0800
Silt Fence	544	L.F.	950	0.5726315789	1.35	734.4	0.59	320.96	0	0	1055.36	TDOT 209.08.03
Stone for Road	55	C.Y.	600	0.091666666667	38	2090	30	1650	3.44	189.2	3929.2	RS Means - 31.05.16.10-0300
Stone for Staging Area	311	C.Y.	600	0.33	38	11818	30	9330	3.44	1069.84	22217.84	RS Means - 31.05.16.10-0300
Chain Link Fence	1652	L.F.	-	4	12.58	20782.16	10	1600	-	-	22382.16	TDOT 707-08.30
End and Corner Post	6	Ea.	-	2	241.34	1448.04	10	800	-	-	2248.04	TDOT 707-01.11
6' Gate	2	Ea.	-	1	1055	2110	10	400	-	-	2510	TDOT 707-01.13
Barbwire	1664	L.F.	-	3	0.48	798.72	10	1200	-	-	1998.72	TDOT 707-14.03
Excavation	963	B.C.Y	800	1.20375	-	-	0.62	597.06	0.91	876.33	1473.39	RS Means - 31.26.16.42-0200
Fill	990	L.C.Y	1000	0.99	-	-	0.28	277.2	1.05	1039.5	1316.7	RS Means - 31.23.23.17-0020
Compaction	24000	S.F.	7500	3.2	-	-	0.22	5280	0.33	7920	13200	RS Means - 31.25.17.16-00200
Grading	24000	S.F.	8900	2.696629213	-	-	0.06	1440	0.6	14400	15840	RS Means - 31.22.16.10-3300
Lightenign Protection Copper Wire	4000	L.F.	-	10	2.06	8240	20	3200	-	-	11440	TDOT 730-08.30
Place Forms	180	L.F.	1200	0.15	1.64	295.2	0.79	142.2	-	-	437.4	RS Means - 03.11.13.65-1400
Place Rebar	136	Ea.	435	0.3126436782	10.99	1494.64	1.34	182.24	-	-	1676.88	RS Means - 03.21.10.60-2420
Pour Concrete	74	C.Y	56.4	1.312056738	169	12506	63.5	4699	0.42	31.08	17236.08	RS Means - 03.30.53.40-4050
Cour Concrete	-	-	-	7	-	-	-	-	-	-	0	-
Strip Forms	180	L.F.	4800	0.0375	0	0	0	0	0	0	0	Included in Place Forms Price
Backfill	1400	S.F.	6000	0.23333333333	38	53200	0.22	308	0.02	28	53536	RS Means - 31.23.23.17-0800
Total						138988.92		31558.66		25565.95	196113.53	