Engineering Conferences International ECI Digital Archives

Shotcrete for Underground Support XIV

Proceedings

11-19-2019

Stability Analysis and Reinforcement of the Existing Karst Cave Passing through Yujingshan Tunnel

Junsheng Yang *Central South University, China*, jsyang@csu.edu.cn

Yipeng Xie Candidate, School of Civil Engineering, Central South Univ., China.

Chaoyun Zhou Candidate, School of Civil Engineering, Central South Univ., China

Cong Zhang School of Civil Engineering, Central South Univ., China

Xiong Liang School of Civil Engineering, Central South Univ., China.

Follow this and additional works at: https://dc.engconfintl.org/shotcrete_xiv

Part of the Engineering Commons

Recommended Citation

Junsheng Yang, Yipeng Xie, Chaoyun Zhou, Cong Zhang, and Xiong Liang, "Stability Analysis and Reinforcement of the Existing Karst Cave Passing through Yujingshan Tunnel" in "Shotcrete for Underground Support XIV", Matthias Beisler, ILF Consulting Engineers Asia, Ltd., Thailand Preedee Ngamsantikul, Thailand Underground and Tunneling Group (TUTG), Thailand Herbert Klapperich, TU Freiberg, Germany Eds, ECI Symposium Series, (2019). https://dc.engconfintl.org/shotcrete_xiv/9

This Abstract and Presentation is brought to you for free and open access by the Proceedings at ECI Digital Archives. It has been accepted for inclusion in Shotcrete for Underground Support XIV by an authorized administrator of ECI Digital Archives. For more information, please contact franco@bepress.com.



STABILITY ANALYSIS AND REINFORCEMENT OF THE EXISTING KARST CAVE PASSING THROUGH YUJINGSHAN TUNNEL


PROF. JUNSHENG YANG, YIPENG XIE CENTRAL SOUTH UNIVERSITY, CHANGSHA, CHINA



Tuesday, November 19, 2019 · PATTAYA, THAILAND


CONTENTS





1.1 A SUMMARY OF KARST STUDY








CHAPTER 1: RESEARCH BACKGROUND

Page 2

2.1 ENGINEERING SITUATION






Page 3

CHAPTER 1: RESEARCH BACKGROUND

CONTENTS





2.1 REVEAL OF KARST CAVE






The karst cave was exposed when tunnel was excavated to position D3K279+948;

A underground river was also found at the bottom of the cave during the subsequent investigation.



2.2 GEOLOGICAL CONDITION OF THE KARST SYSTEM



TUNNEL:


- Passes through the cave hall from D3K279+855 to +960;
- is located in the upper part of the cave;
- intersects the cave at an angle of 80 degrees

□ KARST CAVE:

- About 95m long along the line and 230m perpendicular to the line;
- The bottom fillers is about 30~90m thick, developing downwards with a slope;
 - Underground river passes through the left side of the bottom

Page 6

2.2 GEOLOGICAL CONDITION OF THE KARST SYSTEM



Underground river:

- Total length of the main river is about 740m and width is about 5~15m;
- is located 100m below the base of tunnel, intersecting the line at an angle of 70 degrees;
- Total flow is predicted to be 70m3/s, the hydraulic gradient is 1.8%, and the total catchment area is about 85km2;
- Multiple karst fracture tube develope along the river region with a maximum flow of 4L/s.

Page 7


2.3 STABILITY EVALUATION



Stability of cave wall



Stability of bottom fillers




- Multiple rockfall deposits;
- Overhanging surface in vault;
- Seasonal fissure water;
- Steep rock stratum dip with sets of fracture planes;
- soft plastic clay with a thickness of 0 to 15 m;
- Gravel soil, coarse sand, round gravel;
- Bottom contact fracture zone

Page 8


CONTENTS






3.1 OVERVIEW OF TREATMENT SCHEME






3.2 UNDERGROUND RIVER TREATMENT







Discharge tunnel

2# \sim 8# construction passageway


Upstream bottleneck plugging

Downstream pool plugging

Page 10

3.3 KARST HALL BACKFILL





- □ The height of each backfill layer is 20m, and the slope of each layer is 10%;
- □ Intersection should be plugged by concrete after each layer's backfill;
- In order to ensure the smooth discharge of fissure water, the block with a diameter of not less than 30cm is used for backfilling within 3m of the cave wall.

Page 11



C35 steel fiber shotcrete:


,-	Designation	Dosage(kg/m3)								Slump(m	Initial setting	Final setting	Cubic compressive strength(MPa)		
		Cemen t	Fly ash	Sand	Gravel	Water	Water reducing agent	Accelerator	Steel fiber	m)	time	time	1d	7d	28d
	1#	538	_ 95 _	819	754	_ 190_	6.96	31_6	30	181	3min15s	8min7s	15.4	36.4	45.5
	2#	505	89	838	771	190	6.53	29.7	30	175	4min17s	9min12s	12.4	35.0	43.7
	3#	475	84	854	786	190	6.15	27.9	30	160	5min11s	9min15s	10.4	31.8	40.0
	4#	505	89	838	771	190	6.53	29.7	25	164	4min15s	9min17s	8.2	29.1	35.9
	5#	505	89	838	771	190	6.53	29.7	35	157	4min10s	9min11s	13.2	35.7	45.1




Page 12


3.4 REINFORCEMENT OF CAVE WALL








Longitudinal Profile of Anchor Cable Structure



Structural sketch of shell-expanding prestressing hollow bolt




A-A section


Page 13

3.4 EFFECT OF REINFORCEMENT





Before March 15th, 2019, the axial force of the anchor cable did not change significantly, and some of them showed a slow growth. From March 16 to April 20, 2019, the tunnel spanned the construction process. The axial force of the anchors in each of the measuring points has increased significantly. After April 20, the axial force changes of most measuring points tend to be stable.




The internal forces of the D3K279+879, 891, and 951 sections are mainly tensile forces. The anchors of the D3K279+915, 927, and 939 sections are mainly subjected to pressure. During the tunnel spanning construction from March 16 to April 20, 2019, the tensile strength of the tensioned anchor tends to be gentle, and the tension of some anchors decreases or showing the pressure change trend. the internal force of the compressed anchors increases during the period. the internal force changes of each measuring point tend to be stable after construction.

Page 14

3.4 EFFECT OF REINFORCEMENT






The monitoring results show that the maximum settlement of the karst hall vault occurs at D3K279+885, and the maximum settlement value is 28.6mm. The karst hall dome has obvious growth and fluctuation during the expansion stage of the tunnel. The settlement growth rate accounts for 82%-91% of the total settlement value of the dome; November 13 From the day of December to December 4, after the completion of the anchor cable and anchor, the settlement of the dome tends to be stable, and the anchor cable and anchor have a good control effect on the settlement deformation of the dome of the karst hall.

Page 15




Overall construction process



Page 16




Pre-reinforcement of backfill at both sides of tunnel



Page 17




Tunnel excavation procedure



Construction Section

Page 18






Page 19




Grouting reinforcement of tunnel base



Page 20







Page 21



Analysis of field monitoring



Clearance Convergence Monitoring of Typical sections




Subsidence Monitoring of Tunnel Bottom of Typical sections

Page 22

CONTENTS





4.1 CONCLUSION



- The giant karst caves in the Yujingshan tunnel have complex developmental forms. The underground river passes through the karst hall and develops several tributary pipelines. The overall stability of the cave wall and the fillers is greatly affected by the rock strata, fissures and karst water. According to its geological characteristics and stability, the series of schemes of "karst river remediation karst backfilling cave wall protection" was adopted to carry out the karst remediation of the dark river, which provided a guarantee for the construction and operation of the subsequent tunnel crossing karst.
- As the stability monitoring of the karst hall during the rectification and subsequent tunnel crossing construction shows, the monitoring value of the internal force of the anchor bolt and cable is less than the design limit, the increase of the tunnel spanning during construction is obvious, and the internal force changes tend to be stable after the construction After the construction was completed, the internal force of the bolt was not significant. The change of the dome is mainly caused by the expansion of the stepped arch of the tunnel. The protection measures of the cave wall have a good control effect on the settlement deformation of the dome of the karst hall.



THANKS FOR LISTENING!

PROF. JUNSHENG YANG CENTRAL SOUTH UNIVERSITY, CHANGSHA, CHINA jsyang@csu.edu.cn