



This item was submitted to Loughborough's Institutional Repository (<https://dspace.lboro.ac.uk/>) by the author and is made available under the following Creative Commons Licence conditions.

The image shows a yellow rectangular box containing the Creative Commons Attribution-NonCommercial-NoDerivs 2.5 license summary. At the top is the Creative Commons logo (CC) and the text 'creative commons' in a bold, lowercase font, with 'COMMONS DEED' in a smaller, spaced-out font below it. The license title 'Attribution-NonCommercial-NoDerivs 2.5' is centered. Below this, the text 'You are free:' is followed by a bullet point: 'to copy, distribute, display, and perform the work'. Then, 'Under the following conditions:' is followed by three items, each with a circular icon: 1. 'BY:' icon (a circle with 'BY' inside) followed by the text 'Attribution. You must attribute the work in the manner specified by the author or licensor.' 2. A circle with a dollar sign and a diagonal slash through it, followed by 'Noncommercial. You may not use this work for commercial purposes.' 3. A circle with an equals sign inside, followed by 'No Derivative Works. You may not alter, transform, or build upon this work.' Below these three items is a list of two bullet points: 'For any reuse or distribution, you must make clear to others the license terms of this work.' and 'Any of these conditions can be waived if you get permission from the copyright holder.' At the bottom of the box, it states 'Your fair use and other rights are in no way affected by the above.' and 'This is a human-readable summary of the [Legal Code \(the full license\)](#).' followed by a blue link 'Disclaimer' with a small document icon.

For the full text of this licence, please go to:
<http://creativecommons.org/licenses/by-nc-nd/2.5/>

Modelling of Mass Transfer in Gas-Liquid Stirred Tanks Agitated by Rushton Turbine and CD-6 Impeller: A Scale-up Study

J. Gimbun, C. D. Rielly*, Z. K. Nagy

Dept. Chemical Engineering, Loughborough University, Leics, LE11 3TU, UK.
e-mail: c.d.rielly@lboro.ac.uk

Abstract. A combined computational fluid dynamics (CFD) and population balance model (PBM) approach has been applied to the simulation of gas-liquid stirred tanks agitated by (i) a Rushton turbine or (ii) a CD-6 impeller, operating at aeration numbers from 0.017 to 0.038. The multiphase simulations were realised via an Eulerian-Eulerian two-fluid model and the drag coefficient of spherical and distorted bubbles was modelled using the Ishii-Zuber equations. The effect of the void fraction on the drag coefficient was modelled using the correlation by Behzadi *et al.* (2004). The local bubble size distribution was obtained by solving the PBM using the quadrature method of moments (QMOM). The local k_{La} was estimated using both the Higbie penetration theory and the surface renewal model. The predicted gas-liquid hydrodynamics, local bubble sizes and dissolved oxygen concentration were in good agreement with experimental measurements reported in the literature. A slight improvement in the prediction of the aerated power number was obtained using the non-uniform bubble size distribution resulting from the coupled CFD-PBM simulation. Evaluation of the prospective scale-up approaches indicates a higher probability of maintaining a similar level of mass transfer in a larger tanks by keeping the P_g/V and VVM constant. Considering its predictive capability, the method outlined in this work can provide a useful scale-up evaluation of gas-liquid stirred tanks.

Key words: gas-liquid; mass transfer; local bubble size; QMOM; CD-6; scale-up; CFD-PBM

1. INTRODUCTION

There are many industrial processes that involve gas-liquid dispersion in stirred tanks, *e.g.* in fine-chemicals manufacturing, or in biochemical fermentations. For economic and safety reasons, reliable models are needed for the scale-up and design of such reactors. One of the most important problems in modelling gas-liquid dispersions is the prediction of bubble size and gas-liquid interfacial area. As shown experimentally by many researchers (*e.g.* Montante *et al.*, 2008; Barigou and Greaves, 1992; Laakkonen *et al.* 2005; 2007a) the distribution of bubble sizes varies inside the stirred tank depends on the spatial position. Generally, bubble

sizes around the impeller discharge stream are the smallest due to breakage caused by high local energy dissipation rates. Furthermore, knowledge of bubble sizes is necessary in a two-phase CFD model to calculate momentum exchange by drag. Hence, the population balance, phase continuity and momentum equations are coupled and should in principle be solved simultaneously. In addition, local bubble sizes and the local gas volume fraction are required for the calculation of the interfacial area, which is an important variable in designing an aerated stirred tank to achieve a required rate of gas-liquid mass transfer.

Many modelling studies on the gas-liquid stirred tanks have been performed in recent years, mostly using a uniform, mono-dispersed bubble size throughout the tank (e.g. Khopkar and Ranade, 2006; Sun *et al.*, 2005; Wang *et al.*, 2006; Morud and Hjertager, 1996; Deen *et al.*, 2002; Scargiali *et al.*, 2007). Generally, the CFD predictions of gas hold-up and mean flow are in fair agreement with experimental data, except around the impeller discharge. Previous studies have applied a variety of methods with uniform bubble sizes such as grid refinement, different drag laws and various turbulence models, but without complete success. Deen *et al.* (2001) evaluated the effects of different drag laws and grid refinement and found good predictions of the mean radial velocity but poor predictions of the gas axial velocity. Others such as Sun *et al.* (2005) and Wang *et al.* (2006) employed a $k-\varepsilon-A_p$ turbulence model without a complete success in predicting the two-phase flow. Scargiali *et al.* (2007) studied the influence of turbulent dispersion force, virtual mass, grid refinement and the prescribed bubble size on the holdup in a gas-liquid flow. They concluded that the grid size may significantly affect the prediction, but effects of the turbulent dispersion force and virtual mass were not very significant in determining the distribution of gas holdup. Khopkar and Ranade (2006) studied a gas-liquid stirred tank operating at different flow regimes and obtained a reasonable predictions of the gas hold-up and gassed power number, but only by employing the turbulent drag correlations by Brucato *et al.* (1998): their work showed over prediction of gas hold-ups around the lower and upper circulation loops.

Whereas it is possible to predict correctly the mean flow in a single phase stirred tank using any RANS based turbulence model, this performance has not yet been replicated for gas-liquid stirred tanks. The common practice of employing a uniform bubble size throughout the tanks is suspected to be the main reason for the poor prediction of the two-phase flow in stirred tanks. Of course, other factors such as the drag model for distorted and dense bubbles, turbulent drag laws, lift and other forces also cannot be ruled out. However, their effects appear to be secondary compared to that of an assumed uniform bubble size on the

predominant momentum exchange mechanism of inter-phase drag coefficient, which directly affects the prediction of the local mean velocities and gas hold-up.

Early attempts to predict the local bubble size were performed using the population bubble density model (BDM) and a one-way coupled approach, *e.g.* as in the model of Bakker and Van den Akker (1994). In recent years, a coupled CFD-BDM has been employed to predict the local bubble size in gas-liquid stirred tanks by Lane *et al.* (2002, 2005), Kerdouss *et al.* (2006) and Moilanen *et al.* (2008). In most cases, the BDM is reported to give a satisfactory prediction of the local bubble size, but only by adjusting some of the empirical constants within the model. This practice is thought to be inappropriate because the model is unlikely to be fully predictive and hence cannot be applied to cases where the experimental data are not available. Lane *et al.* (2005), for example, introduced a correction factor of up to 3.5 for the turbulence dissipation rate, while Kerdouss *et al.* (2006) adjusted constants in the breakage and coalescence term in order to get good agreement with measurements reported by Alves *et al.* (2002). Lane *et al.* (2005) argue that the turbulent dissipation rate is not predicted well by the RANS k - ϵ turbulence model. However, the correction factor that was applied is too large, considering the under prediction of turbulent dissipation rate by k - ϵ model is only around than 30% (Ducoste and Clark, 1999). The formulation of the BDM itself is also questionable, since proper bubble breakage and coalescence kernels are not included. Instead all equations related to the bubble size are lumped together as a function of the critical Weber number and energy dissipation rate, without considering the probability and rate of bubble-bubble and bubble-eddy collisions. As a consequence, the BDM is not thought to be a fully predictive model for simulation of gas-liquid dispersions in stirred vessels.

A full PBM has been employed to predict the local bubble size in stirred tanks, mostly using a discretisation based on the method of classes (MOC). Venneker *et al.* (2001) performed a one-way coupled PBM via MOC for a stirred tank bioreactor. Recently, a coupled CFD-PBM simulation using the MOC also has been performed by Montante *et al.* (2008), Moilanen *et al.* (2008) and Kerdouss *et al.* (2008). Moilanen *et al.* (2008) showed reasonable agreement for the predicted and measured local bubble size, based on fitted model constants in the breakage and coalescence terms from a previous multi-block study. Montante *et al.* (2008) presented a good prediction of the number mean bubble size without adjusting the constants of the kernels, however the Sauter mean diameter was consistently underpredicted by approximately 50%. No comparison on the predicted bubble size were presented by Kerdouss *et al.* (2008). A fully predictive model should not require the tuning of model parameters for each case considered. One downside of the MOC is its computational

demand since it requires more than 30 classes to get a good level of accuracy in the prediction of the evolution of the moments of the bubble size distribution.

The quadrature method of moments (QMOM) is based on solving equations for the moments of the bubble size distribution; the quadrature approximation overcomes the difficulties in obtaining a closed form solution for population balance equations involving breakage and coalescence. The QMOM requires considerably less computational effort than the MOC and also is capable of providing an accurate prediction with a relatively small number of quadrature points. Hence it is suitable for coupling with simulations of the two-phase hydrodynamics. The QMOM has been applied previously to breakage and aggregation problems (e.g. Marchisio *et al.*, 2003). Recently, Petitti *et al.* (2007) have employed the QMOM to solve the bubble dynamics for gas-liquid dispersion. In their work, bubble coalescence is not considered and only a simple breakage kernel is employed instead of one based on the physics of bubble breakup. No comparisons with experimental measurement were presented by Petitti *et al.* (2007). In the interest of a reduced computational effort, the QMOM method was selected to solve the population balance equation for bubble dynamics in aerated stirred tanks in this work.

The first part of this work focuses on the development of a modelling approach for gas-liquid stirred tanks. For an initial comparison, the CFD simulation was performed assuming a constant bubble size throughout the tank. A coupled CFD-PBM was then performed to account for the spatially non-uniform bubble sizes inside the tank. The CFD prediction of the two-phase flow field was compared to experiments by Deen *et al.* (2002), whereas the results using the CFD-PBM approach were compared against measurements by Laakkonen *et al.* (2007a and b). After validation, the model was used to evaluate the local mass transfer coefficients inside the tank, and to study the reactor scale-up, especially from the mass transfer perspective, which is often vital in aerobic fermentations.

2. MODELLING APPROACH

2.1 CFD modelling of two-phase flow

The Eulerian-Eulerian approach is employed for gas-liquid stirred tanks simulation in this work, whereby the continuous and disperse phases are considered as interpenetrating media, identified by their local volume fractions. The volume fractions sum to unity and are governed by the following continuity equations:

$$\frac{\partial}{\partial t}(\alpha_l \rho_l) + \nabla \cdot (\alpha_l \rho_l \vec{u}_l) = 0 \quad (1)$$

where α_l is the liquid volume fraction, ρ_l is the density, and \vec{u}_l is the velocity of the liquid phase. The mass transferred between phases is negligibly small and hence is not included in the right hand-side of eq.(1). A similar equation is solved for the volume fraction of the gas phase by replacing the subscript l with g for gas. The momentum balance for the liquid phase is:

$$\frac{\partial}{\partial t}(\alpha_l \rho_l \vec{u}_l) + \nabla \cdot (\alpha_l \rho_l \vec{u}_l \vec{u}_l) = -\alpha_l \nabla P + \nabla \cdot \bar{\bar{\tau}}_l + \vec{F}_{lg} + \alpha_l \rho_l \vec{g} + \vec{F}_{lift,l} + \vec{F}_{vm,l} \quad (2)$$

where $\bar{\bar{\tau}}_l$ is the liquid phase stress-strain tensor, $\vec{F}_{lift,l}$ is a lift force, \vec{g} is the acceleration due to gravity and $\vec{F}_{vm,l}$ is the virtual mass force. A similar equation is solved for the gas phase.

\vec{F}_{lg} is the interaction force between phases, mainly due to drag. As pointed out by Scargiali *et al.* (2007) the effects of the turbulent dispersion, virtual mass and lift are almost negligible, despite a significant increase in computational expenses and convergence difficulties. Scargiali *et al.* (2007) found a minimal increase of the overall gas hold-up from 4.36% to 4.60% and from 4.36% to 4.67% by adding the effect of virtual mass and lift force respectively. They concluded that the effect of the drag force largely predominates in aerated stirred tanks. A similar conclusion was also drawn by many previous studies, e.g. Bakker and Van Den Akker, 1994; Morud and Hjertager, 1996; Lane *et al.*, 2002; Kerdouss *et al.*, 2006). It was therefore decided not to include the effect of the virtual mass and lift force in this work. Hence, \vec{F}_{lg} is represented by a simple interaction \vec{F} term for the drag force, given by:

$$\vec{F}_{lg} = -\frac{3\rho_l \alpha_g \alpha_l C_D |\vec{u}_g - \vec{u}_l| (\vec{u}_g - \vec{u}_l)}{4d_b} \quad (3)$$

where C_D is a drag coefficient and d_b is the Sauter mean bubble diameter.

The drag model employed has a significant effect on the flow field of the aerated flow, as it is related directly to the bubble terminal rise velocity. Bubbles have a tendency to form a non-spherical shape, especially those with a diameter > 3 mm. Therefore, the drag model of Ishii and Zuber (1979) was selected in this work, as it takes into account the drag of distorted bubbles:

$$C_D = \max\left(\frac{24}{\text{Re}_b} (1 + 0.15 \text{Re}_b^{0.687}), \min\left(\frac{2}{3} \sqrt{E_o}, 8/3\right)\right) \quad (4)$$

where the Re_b and E_O are the bubble Reynolds number and Eotvos number, respectively. The drag for the ellipsoidal bubble regime is dependent on the bubble shape through the Eotvos number, which represents the ratio of gravitational to surface tension forces; for the spherical cap regime the drag coefficient is approximately 8/3. The effect of the local bubble volume fraction on the drag coefficient is estimated using Behzadi *et al.*'s (2003) correlation as follows:

$$C_{D,dense} = C_D \left(e^{3.64\alpha} + \alpha^{0.864} \right) \quad (5)$$

where the C_D is the drag coefficient for isolated bubble estimated using eq.(4), whereas $C_{D,dense}$ is for the dense dispersion of bubbles. The drag model described above is not available as a standard option in FLUENT and hence it has been implemented via a user-defined subroutine.

The stirred tank grid was prepared with a headspace to accommodate liquid expansion due to aeration. The liquid surface was modelled as a freely expandable liquid surface and the top of the headspace region was set as a pressure outlet, rather than using a fictitious 'degassing boundary condition'. The mass balance between the gas outflow at the outlet boundary (above the headspace region) and the gas inflow at the sparger was satisfied. The PBM and mass transfer calculations did not include the headspace region.

It is also important to consider the formation of the bubble cavity behind the impeller blade. According to Lane *et al.* (2005), it is possible to model the gas cavity in the Eulerian-Eulerian framework, providing a certain modification is made to the interphase exchange coefficient: the drag coefficient is set to turn into that for isolated bubble when the void fraction is higher than 0.7, *i.e.* the cavity behind the blade behaves in a manner similar to an isolated bubble, rather than the dense bubble case. An attempt to use the dense drag bubble model for the cavity region has been tested, resulting in the disappearance of the bubble cavity behind the blade and an over-prediction of the gassed power number by more than 60%. The mean radial velocity was also found to be over predicted. However, this issue has been successfully addressed by treating the cavity as an isolated bubble.

2.2 Turbulence modelling

The turbulence modelling uses the two-phase realizable $k-\varepsilon$ model, in which both k and ε are allowed to have different values for each phase. The transport equations for the realizable two-phase $k-\varepsilon$ model are given in the Fluent manual (2006) and the standard values of the model parameters have been applied. The realizable $k-\varepsilon$ is considered to be a better model

than the standard k - ε for stirred tank flows (Gimbun, 2009), as it better accounts for flow features such as strong streamline curvature, vortices and rotation. The realizable k - ε differs from the standard k - ε model in two important ways: first it has a new formulation of turbulent viscosity and second it employs a new transport equation for the dissipation rate incorporating different model constants.

2.3 Population balance modelling

2.3.1 QMOM formulation

The QMOM is employed to solve the PBM and predict the evolution of the moments of the bubble size distribution. For breakage and coalescence only, the QMOM equation for the k^{th} moment of a single well-mixed system is given by:

$$\begin{aligned} \frac{d\mu_k}{dt} = & \underbrace{\sum_{i=1}^N w_i a(L_i) b(k, L_i)}_{\text{birth due to breakage}} + \underbrace{\frac{1}{2} \sum_{i=1}^N w_i \sum_{j=1}^N w_j (L_i^3 + L_j^3)^{k/3} \beta(L_i, L_j)}_{\text{birth due to coalescence}} \\ & - \underbrace{\sum_{i=1}^N w_i a(L_i) L_i^k}_{\text{death due to breakage}} - \underbrace{\sum_{i=1}^N w_i L_i^k \sum_{j=1}^N w_j \beta(L_i, L_j)}_{\text{death due to coalescence}} \end{aligned} \quad (6)$$

where $\beta(L_i, L_j)$, $a(L_i)$ and $b(k, L_i)$ are the coalescence kernel, breakage kernel and daughter bubble distribution function, respectively. Full details of the QMOM can be found elsewhere *e.g.* McGraw (1997) and Marchisio *et al.* (2003). In this implementation, the solution of the weights (w) and abscissas (L) from the moments was obtained using the product difference algorithm of Gordon (1968). To reduce computation cost of these simulations a QMOM based on two quadrature points was applied.

There are many breakage and coalescence kernels available for bubbly flow, but they are essentially written in a similar form except some minor differences in the model constants or assumptions. The Prince and Blanch (1990) model has been proven to give a good prediction of bubble size in bubble columns (*e.g.* Shimizu *et al.*, 2000; Podila *et al.*, 2007). Some researchers (*e.g.* Chen *et al.*, 2005; Bordel *et al.*, 2006; Podila *et al.*, 2007) made a comparison of the prediction of various kernels combinations including those proposed by Prince and Blanch (1990), Luo and Svendsen (1996), Luo (1993), Chesters (1991), Martinez-Bazan *et al.* (1999) and Lehr *et al.* (2002). Their findings suggest that there is no great difference between the mean flow, gas hold-up and bubble Sauter mean diameter (d_{32}) predicted using different kernels although, there are some differences in the predicted bubble size distribution. The Luo and Svendsen (1996) breakup kernel was found to generate

excessively small and large bubbles, due to its U-shaped daughter bubble distribution function (Podila *et al.*, 2007). Podila *et al.* also pointed out the problem of the Luo (1993) coalescence kernel, which tends to yield large bubbles due to its high coalescence rates. Laakkonen *et al.* (2007a) and Moilanen *et al.* (2008) employed a modified version of Prince and Blanch's (1990) model for their work on gas-liquid stirred tanks, and they reported a good agreement with experimental measurement. Laakkonen *et al.* (2007a) has compared the prediction of two different kernels i.e. Lehr *et al.* (2002) and a modified version of Prince and Blanch models. Their findings suggest that Lehr model tends to under predict the local bubble size in gas-liquid stirred tanks, even though it has been reported to produce an excellence prediction for bubble columns (Lehr *et al.*, 2002). Based on these previous studies, the Prince and Blanch (1990) model has been employed to predict the bubble dynamics in this work.

2.3.2 Modelling of bubble coalescence

Bubble collisions may occur due to a variety of mechanisms, *e.g.* Prince and Blanch (1990) consider collisions arising from turbulence, buoyancy and laminar shear. In turbulent flow, bubble collisions are driven mainly by random motion of bubbles due to turbulent eddies. Bubbles of different sizes also have different rise velocities which may lead to collision. There is also a possibility for bubbles from a high liquid velocity region to collide with bubbles in slower section of the velocity field. The bubble collision frequency for a Newtonian fluid can be modelled following the approach proposed by Prince and Blanch (1990):

$$\omega(L_i, L_j) = \underbrace{\pi \left(\frac{L_i}{2} + \frac{L_j}{2} \right)^2 [u_t^2(L_i) + u_t^2(L_j)]^{0.5}}_{\text{turbulent}} + \underbrace{\pi \left(\frac{L_i}{2} + \frac{L_j}{2} \right)^2 |u_\infty(L_i) - u_\infty(L_j)|}_{\text{bouyancy}} \quad (7)$$

where $u_t(L)$ is the turbulent velocity in the inertial range of isotropic turbulence (Rotta, 1972) and $u_\infty(L_i)$ is the rise velocity of bubble given as a function of bubble size (Clift *et al.*, 1978).

The bubble collision efficiency, $\lambda(L_i, L_j)$, is the probability of coalescence during a bubble-bubble collision between sizes L_i and L_j . For Prince and Blanch's model, the bubble collision efficiency is given as a function of film drainage and bubble-bubble contact times:

$$\lambda(L_i, L_j) = \exp \left(\frac{-\ln(h_o/h_f) \sqrt{(L_{ij}/2)^3 \rho_l / 16\sigma}}{(L_{ij}/2)^{2/3} / \varepsilon^{1/3}} \right) \quad (8)$$

where $L_{ij} = 2(1/L_i + 1/L_j)^{-1}$, h_o is the initial film thickness and h_f is the final thickness at which the film rupture occur. The value of 10^{-4} m for h_o and a value of 10^{-8} m for h_f from Prince and Blanch (1990) was used throughout this work. The bubble coalescence kernel, $\beta(L_i, L_j)$, is a product of bubble collision efficiency, from eq.(7), and collision frequency from eq.(8).

$$\beta(L_i, L_j) = \lambda(L_i, L_j) \omega(L_i, L_j) \quad (9)$$

2.3.3 Modelling of bubble breakage

Prince and Blanch (1990) considered the bubble break-up to be caused by collisions with turbulent eddies of sizes equal to, or smaller than, the bubble size. They argued that eddies smaller than 0.2 times the bubble diameter are unlikely to contribute significantly to the overall break-up rate and set the lower limit of the effective turbulent eddies as $0.2L$. They considered only eddies having a velocity larger than the critical velocity, u_{ci} , where the disruptive force due to the kinetic energy of the eddy and the cohesive force due to surface tension balance each other. The break-up rate is given as a product of the collision rate of bubbles with turbulent eddies, θ_{ie} , and the break-up efficiency, κ_i . According to Prince and Blanch (1990), the bubble break-up rate is given by the expression:

$$a(L_i) = \theta_{ie} \kappa_i \quad (10)$$

The collision rate of bubbles with turbulent eddies is given by Kennard (1938):

$$\theta_{ie} = n_i n_e S_{ie} (u_{ii}^2 + u_{ie}^2)^{0.5} \quad (11)$$

where n_i , n_e and S_{ie} are the number of bubbles per unit volume, number of eddies per unit volume and collision cross-sectional area, respectively. The u_{ii} is the turbulent velocity in the inertial range of isotropic turbulence (Rotta, 1972) and the eddy velocity, u_{ie} , of a size L_e is also calculated analogously to Rotta (1972). The eddy size may be expressed using Kolmogorov's (1941) theory of isotropic turbulence as $L_e = (v_i^3 / \varepsilon)^{1/4}$.

The break-up efficiency, κ_i , is given by (Kennard, 1938; Prince and Blanch, 1990):

$$\kappa_i = \exp(u_{ci}^2 / u_{ie}^2) \quad (12)$$

where the u_{ci} is the critical eddy velocity necessary to break a bubble of diameter L_i , given by Shimizu et al. (2000).

Prince and Blanch's (1990) break-up model does not include the daughter bubble size distribution. The daughter bubble distribution function, $b(L, \lambda)$, determines the number and

size of the daughter particle, L , after the breakage event of particle size λ . Here, a uniform breakage function was selected with binary breakage to form similar particle sizes.

$$b(L|\lambda) = \frac{6L^2}{\lambda^3} \quad (13)$$

There is a high possibility of non-binary breakage for liquid-liquid systems where the internal viscosity of the dispersed phase can lead to multiple daughter drops (Andersson and Andersson, 2006). However the assumption of binary break-up is considered valid for bubbles, since the air viscosity is low. Furthermore, a recent study by Andersson and Andersson (2006) revealed that more than 95% of bubble break-ups involved binary breakage.

The population balance model was solved using user-defined scalars to represent the moments, weights and abscissas and was implemented via user-defined subroutine written in C language. All the breakage and coalescence kernel were implemented without adjusting any of the model constants. The user-defined subroutine was compiled within the commercial CFD code, FLUENT 6.3 and was available as an add-on program after the compilation; hence a fully coupled CFD-PBM simulation could be performed.

2.4 Modelling of k_La and oxygen transfer rate

Many empirical scale-up rules and correlations have been developed to calculate the volumetric mass transfer coefficient, k_La , in aerated stirred tanks. However, the existing correlations are only capable of calculating the average k_La value in the tank and not the local values. Information about the local k_La is important in the study of gas-liquid stirred tanks to spot the occurrence of ‘dead zones’, where very little mass transfer occurs. Ideally, achieving a uniform k_La and uniform driving force is desirable during scale-up of aerated stirred tanks. Whilst this maybe the case for laboratory scale stirred tanks, it is not always true for larger scale tanks, which can suffer from zones of oxygen depletion, particularly where there is an oxygen sink, *e.g.* through chemical reaction.

Assuming a spherical bubble, the local interfacial area per unit volume may be calculated from

$$a = \sum_i \pi d_{b,i}^2 n_i \quad (14)$$

where $d_{b,i}$ is the bubble size and n_i is number of bubbles of size $d_{b,i}$ per unit volume of dispersion. The bubble sizes and numbers of bubble used in the calculation of the interfacial area were obtained from the CFD-PBM simulation, directly from the weights and abscissas

used in the QMOM. Bubbles with diameters greater than around 3 mm (for air-water) are ellipsoidal, with an aspect ratio which may be calculated as a function of the Eotvos number from the correlation of Wellek *et al.* (1966)

$$R = 1 + 0.163E_o^{0.757} \quad (15)$$

which was developed originally for liquid–liquid dispersions. Guet *et al.* (2005) compared eq.(15) with their experimental measurements obtained using a four-point optical fibre probe and reported that Wellek *et al.*'s (1966) correlation is applicable for bubbles. In this work the interfacial area for small bubble ($d_b \leq 1$ mm) was estimated from eq.(14), whilst the bigger bubbles ($d_b > 1$ mm) were assumed to be as oblate spheroids and their surface area was calculated using R from eq.(15). Even larger bubbles ($d_b > 5$ mm) may not form perfect oblate ellipsoids in turbulent flow, however, eq.(15) is a step towards improved bubble shape prediction.

Penetration theory (Higbie, 1935) and the surface renewal model (Danckwerts, 1951) are two common methods of calculating k_L when the bubble size is known. Higbie's (1935) penetration theory results in an average mass transfer coefficient for each bubble size given by:

$$k_{L,i} = \frac{2}{\sqrt{\pi}} \sqrt{\frac{D_l u_{slip}}{d_{b,i}}} \quad (16)$$

where u_{slip} and D_l are the bubble slip velocity and diffusion coefficient, respectively. The slip velocity can be obtained from the difference in phase velocities from an Eulerian-Eulerian two-fluid CFD simulation. Thus local values of $k_L a$ were calculated from:

$$k_L a = 2(\pi D_l)^{0.5} \sum_i d_{b,i}^{1.5} u_{slip}^{0.5} n_i \quad (17)$$

Danckwerts (1951) suggested a refinement of the penetration model by assuming that k_L is related to the average surface renewal rate resulting from exposure of the bubble interface to turbulent eddies with a variable contact time. Danckwerts suggested the surface renewal model as follows:

$$k_L = \sqrt{D_l s} \quad (18)$$

where s is the fractional rate of surface-element replacement. Lamont and Scott (1970) assumed that the small scale turbulent motion, which extends from smallest viscous motion to inertial ones, affects the rate of mass transfer. Consequently, s can be calculated using Kolmogorov's theory of isotropic turbulence. They suggested the eddy cell model as follows:

$$k_L = KD_l^{0.5} \left(\frac{\varepsilon_l}{\nu_l} \right)^{0.25} \quad (19)$$

where ε_l is the turbulence dissipation rate in the liquid phase, ν_l is the liquid dynamic viscosity and $K = 0.4$ is the model constant. Combining k_L and a gives another equation for calculating the volumetric mass transfer coefficient:

$$k_L a = K\pi D_l^{0.5} \left(\frac{\varepsilon_l}{\nu_l} \right)^{0.25} \sum_i d_{b,i}^2 n_i \quad (20)$$

The local oxygen transfer rate can be estimated from the following relations once the local $k_L a$ has been determined,

$$N_o = k_L a (C_o^* - C_o) - r_o \quad (21)$$

where C_o^* is the oxygen solubility in the liquid phase, C_o is the oxygen concentration in the liquid phase and r_o is the specific oxygen consumption rate. The transport equation for dissolved oxygen mass fraction was also solved as a user-defined scalar implemented as a user-defined subroutine, with the sink terms given in the right hand side of eq.(21) above.

2.5 Tank geometry and numerical strategy

Two scales, 14L and 200L, of aerated stirred tanks containing a Rushton turbine, studied by Laakkonen *et al.* (2007a) were considered for the CFD-PBM modelling. Gas was injected through a sparger ring at a flow rate ranging from 0.29 to 0.7 vvm which is treated as a continuous source of gas (velocity inlet) in the CFD simulation. First, a two-phase CFD simulation was performed assuming a uniform bubble diameter throughout the tank. The interphase drag coefficient was estimated using the standard Schiller-Naumann drag model. The CFD simulation was performed using a half-tank domain consisting of about 225k hexahedral cells. A finer mesh was employed around the impeller up to 15 nodes placed along the impeller blade height. According to Derksen *et al.* (1999), a grid with eight or less nodes along the impeller blade height may not be able to resolve the vortex core structure correctly and hence can give errors in the predicted mean flow field. The impeller movement was modelled using a multiple reference frame and the Eulerian-Eulerian approach was employed for the multiphase modelling. The turbulence was modelled using the two-phase realizable $k-\varepsilon$ model described in a previous section. Transient solvers with a second-order spatial interpolation scheme were also applied for the final simulation in order to minimise the amount of numerical diffusion. The iteration residual was set to fall below 1×10^{-4} at each time

step to achieve good convergence. The volume average of the gas void fraction at the rotating zone (impeller region) was also monitored and the iterations were only halted once a constant value was observed. A grid sensitivity study was performed prior to the final grid selection using three different meshes: coarse (165k with 6 nodes at impeller blade height), intermediate (225k with 11 nodes at impeller blade height) and fine (335k with 13 nodes at impeller blade height). It was found that a domain consisting of 225k cells yielded a grid independent solution (see Fig. 1).

3. RESULTS AND DISCUSSION

3.1 Prediction of Gas-Liquid Hydrodynamics

First, the CFD simulations were validated against experimental data using the two-phase PIV measurements reported by Deen *et al.* (2002) for a stirred tank with $Fl_g = Q_g/ND^3 = 0.0296$. The impeller speed for Laakkonen's geometry was set to 513 rpm to ensure the aeration number stayed at $Fl_g = 0.0296$ so that a sensible comparison between the CFD prediction and the experimental measurement from Deen *et al.* (2002) could be made.

The simulation was performed initially by assuming a constant bubble size of 3.5 mm throughout the tank. The bubbles were assumed to be spherical and the Schiller and Naumann (1935) drag model was employed to estimate the drag coefficient. The CFD results were time-averaged over all blade angles and compared with Deen *et al.*'s (2002) PIV measurements. For easier comparison, the results for the mean velocities were normalised using the impeller tip velocity (V_{tip}). Despite the assumption of a constant bubble size and spherical bubbles, the predictions (marked as CFD constant) shown in Figs. 2 and 3 are reasonably close to the experimental data. The differences can be explained by the neglect of bubble coalescence and break-up caused by the turbulent flow induced by the rotating impeller. These mechanisms are not considered in the case where a uniform bubble size is assumed throughout the tank.

A simulation using a non-uniform bubble size was next performed to evaluate these effects on the CFD predictions. The local bubble sizes were estimated using the population balance model, which tracks the moments of the bubble size distribution. The local Sauter mean diameters, obtained from the ratio of the third and second moments, were then passed into the CFD simulation and used for the two-phase flow modelling. The CFD-PBM simulations were performed using two different drag models: (i) the hard sphere drag model of Schiller and Naumann (1935) (a default FLUENT model) and (ii) another that takes into account the drag of distorted bubbles (Ishii and Zuber, 1979) and dense bubble effect (Behzadi *et al.*, 2003). As expected, results obtained from the CFD-PBM modelling were slightly better compared to

those obtained using a constant bubble size. The prediction of axial *gas* velocities below the impeller ($2z/W < 1$) and the peak liquid radial velocities were in fair agreement with Deen *et al.*'s (2002) data. Using the non-spherical drag model (CFD-PBM-IZ) in the CFD-PBM approach further improved the results. This is due to the fact that the effect of local bubble sizes on the two-phase flow is mainly via the inter-phase exchange coefficient, which depends on the drag model. The Schiller-Naumann model is suitable for spherical rigid bubbles, but in comparison, the Ishii-Zuber model predicts drag coefficients for the spherical, ellipse and cap bubble regime. The difference observed between the flow fields predicted using a spherical drag model and the one that accounts for distorted bubbles is small for the cases considered in this paper, due to the proximity of the analysed region to the impeller tip. In this region, the bubble size is mainly below 3 mm and hence bubbles can be assumed to be approximately spherical. However, because of the better prediction of the gas and liquid mean velocities, the CFD-PBM-IZ was selected and used for the remainder of this work. The remaining discrepancy in the result predicted by CFD-PBM-IZ method might be due to minor differences in the tank geometry used by Deen *et al.* (2002) and Laakkonen *et al.* (2007a) (the geometry used for the CFD work reported here). For instance Deen *et al.* (2002) used a dished bottom tank and had a slightly different impeller geometry ($W = L_D = 0.25D$) whereas Laakkonen's work used a flat bottomed tank and a standard Rushton turbine. The inherent limitation of the Eulerian-Eulerian model which can only use a single bubble size (d_{32}) at any spatial location at any given time is also thought to affect the accuracy of CFD prediction. A more accurate modelling approach of the gas-liquid flow would employ the real bubble size distribution at each spatial position inside the tank, however such model would require a higher implementation complexity and would be computationally more intensive to run. Therefore, a combined CFD-PBM model employing only the d_{32} is thought to be a more efficient solution for a gas-liquid flow at present with the aim of employing the developed approach as a practical design tool.

3.2 Prediction of the Aerated Power Number

Prediction of the gassed power input by integrating the dissipation rate over the tank volume is known to provide an underestimate of the power input (in the cases shown here, by between 35–44 %). Therefore the P_g in this work was calculated from the moment acting on the shaft and impeller or baffles and tank wall. The calculated torque, T , is then related to the power input by,

$$P_g = 2\pi N\Gamma \quad (22)$$

For a Rushton turbine Bujalski *et al.* (1987) suggested the following correlation for estimation of the ungassed power number:

$$N_{p0} = \frac{P_0}{\rho_l N^3 D^5} = 2.512 \left(\frac{\Delta t}{D} \right)^{-0.195} T^{0.063} \quad (23)$$

where Δt is the impeller thickness and T is the tank diameter (m). Smith (2006) proposed the following correlation for the relative power draw, P_g/P_0 , for stirred tanks agitated by a Rushton turbine, based on the measurements of Warmoeskerken and Smith (1982) and Gezork *et al.* (2000):

$$P_g/P_0 = 0.18 Fr^{-0.2} Fl_g^{-0.25}, \quad (24)$$

where Fr and Fl_g are the Froude number and the aeration number, respectively. Myers *et al.* (1999) performed extensive experiments in single phase and aerated stirred tank with a CD-6 impeller; they reported that, on gassing, the P_g/P_0 of a Rushton turbine drops significantly compared to that of a CD-6 impeller. In this study the CFD predictions were compared with measured P_g/P_0 obtained from Myers *et al.* (1999) for the CD-6 impeller, and using eq.(24) for the Rushton turbine, together with eq.(23).

The P_g/P_0 ratio is shown to be predicted reasonably well using the assumption of a constant bubble sizes throughout the tank (see Tables 1 and 2). There is a small improvement in the prediction of P_g/P_0 when a non-uniform bubble size is employed using the CFD-PBM method, especially for cases 1, 4, 5 and 6 for which the uniform bubble sizes used for the initial simulation differed significantly from those calculated using the PBM. The bubble sizes for cases 2 and 3 were known from Laakkonen *et al.* (2007a), and mean values were used for these initial CFD simulations. Consequently, the CFD predictions using uniform bubble sizes for cases 2 and 3 are much closer to the values estimated from eq.(24). The results suggest that the P_g/P_0 can be predicted reasonably well using the uniform bubble size assumption with bubble size close to the experimental mean values. However, the CFD-PBM method is a more suitable approach for predicting the relative power number in cases when the mean bubble size is not known beforehand.

3.3 Prediction of Local Bubble Size and Mass Transfer Coefficient

CFD-PBM simulations were performed using a user-defined subroutine compiled within FLUENT. The Prince and Blanch (1990) breakage and coalescence kernels were employed to predict the bubble dynamics throughout the tank, using literature values of the model

constants. The volume-average Sauter mean diameter, d_{32} , in the impeller region was used as a convergence indicator in these simulations.

Figures 4 and 5 show that the local bubble sizes predicted by the CFD-PBM simulation for both the smaller and the larger tanks are in good agreement with the experiments by Laakkonen *et al.* (2007a). The smallest bubbles can be observed around the impeller, where the dissipation rates are a maximum, whereas the largest bubbles are found below the impeller, just above the sparger, due to the combination of a high void fraction and low dissipation rates. Some discrepancies in the local bubble size predictions can be observed, possibly due to the well-known under-prediction of the energy dissipation rates by the k - ϵ model—the evolution of the bubble size depends mainly on the dissipation rates and the gas void fraction. The CFD-PBM approach is also capable of responding to changes in operating conditions. For instance, case 1, which considers a lower impeller speed, produces larger bubbles compared to case 2, where the impeller speed is higher (see Table 1).

Using the local bubble size obtained, the local $k_L a$ can be estimated using Higbie's penetration theory, or the surface renewal model of Danckwerts. The latter gave a significantly higher value of $k_L a$ around the impeller region (see Fig. 6) due to its sensitivity towards high dissipation rates. Higbie's method return a higher local $k_L a$ in the bulk region, where the dissipation rates were very low; the two methods show slightly different sensitivities to the local dissipation rate and bubble size. The maximum local $k_L a$ values for the larger tank were significantly smaller (roughly 50% less) than for the smaller tank due to the larger mean bubble size, which consequently reduced the interfacial area. The local $k_L a$ contour map also revealed a large dead zone in the bottom region of the tank due to the poor gas dispersion produced by the Rushton turbine. This can be addressed by employing a better gas dispersion impeller such as the CD-6, as shown in Fig. 7A. The CD-6 impeller is a concave type impeller which is available commercially from Chemineer and has been studied extensively by many researchers (e.g. Myers *et al.*, 1999). There are several reason why the CD-6 disperses bubbles much better than the Rushton turbine. Firstly, the CD-6 pumps the fluid slightly downward around the impeller discharge region, whereas the Rushton turbine pumps slightly upward (see Fig. 7A), which then contributes to poor circulation of bubbles in the lower region. Secondly, the concave shape of the CD-6 is designed to produce a smaller gas cavity behind the impeller blade (see Fig. 7B) leading to less reduction in the aerated power number in comparison to the Rushton turbine.

By analogy with experimental measurements, which often assume a well-mixed liquid phase, a global mean $\langle k_L a \rangle$ was estimated by monitoring the volume-averaged oxygen concentration, $C_o(t)$, throughout the simulation, from

$$\ln\left(\frac{C_o^* - C_o(t)}{C_o^* - C_o(0)}\right) = -\langle k_L a \rangle t \quad (25)$$

where C_o^* is the oxygen solubility in water. In the cases discussed here, estimated mixing times from the correlation by Grenville and Nienow (2004), were about one order of magnitude greater than $\langle k_L a \rangle^{-1}$, indicating the liquid phase was well-mixed. Values of $\langle k_L a \rangle$ were obtained from the slopes of the graphs obtained by plotting the left hand side of eq.(25) against time. Fig. 8 shows the evolution of the dissolved oxygen concentration, [DO], calculated using the Higbie and Danckwerts methods, respectively. The predicted $C_o(t)$ profile is in good agreement with the experimental measurement from Laakkonen *et al.* (2007b) especially when an oblate spheroid shape is considered for the larger bubbles. As expected, the discrepancy is much bigger when bubbles assumed to be in spherical shape throughout the tank which may not be correct for diameters > 3 mm. Furthermore, the Eulerian-Eulerian simulation works with a single slip velocity, despite the existence of a range of bubble sizes; this may introduce some discrepancy in the local $k_L a$ and the [DO] evolution. However, this simplification is necessary in order to keep the computational demand minimal. Moreover, the two-phase model can get excessively complicated and expensive to compute when individual bubble sizes with separate slip velocities are considered. Due to its better prediction of the [DO] evolution, the combined spherical and oblate spheroid model is applied for the remainder of this work.

Higbie's method is consistently found to have a slightly faster oxygen transfer rate than the Danckwerts's method for a smaller vessel (see Fig. 9A), where the mean bubble size is less than 3 mm, but the difference becomes almost insignificant for the larger vessels (see Fig. 9B) when the mean bubble size is about 4 mm. This is reflected in the calculated values of the mean $\langle k_L a \rangle$ shown in Tables 3, for cases 2 and 4. Furthermore, Danckwerts' model tend to have a faster oxygen transfer rate than the Higbie model when the mean bubble size is larger than 5 mm (see Fig. 8). This phenomenon can be explained by the sensitivity of the Higbie's model to small bubble sizes which are formed in great numbers for the smaller vessel.

The [DO] evolution was recorded at three different locations inside the tank namely the dead zone below the sparger, the impeller region and bulk region above the impeller. Only a small amount of variation was found between the $\langle k_L a \rangle$ value estimated using the [DO] evolution recorded at these three different locations (see Fig. 10), hence the remaining discussion focuses only on the data recorded at impeller discharge, where the majority of experimental measurements have been obtained. In eq. (25), and often in experimental measurements of the mass transfer coefficient, it is assumed that the dissolved oxygen concentration, [DO] is uniform. Results from the CFD-PBM simulation suggests that this assumption is applicable for these lab and pilot scale gas-liquid vessels, without the presence of oxygen sink (*i.e.* reaction or micro-organism respiration). It is important to note that, the assumption of uniform [DO] may not be valid in a gas-liquid bioreactor even at small scale, depending on the local rate of consumption of dissolved oxygen. In such a case, the [DO] may fall towards zero in some dead regions leading to a severe mass transfer limitation. The well-mixed assumption is also less likely to be correct with increasing scale of operations (Schuetze and Hengstler, 2006), especially when dealing with industrially sized vessels. Thus in practice, the [DO] may be non-uniform, being almost saturated in some locations where there is a high local $k_L a$, and having a low [DO] in regions with poor gas dispersion. It may be concluded that simple volume averages of $k_L a$ from CFD simulations, without knowledge of their correlation with local driving forces, are of little practical use; they would tend to be larger than the $\langle k_L a \rangle$ values obtained by experiment, or from eq.(25). However, a CFD calculation which solves the oxygen transport equation, coupled with local values of $k_L a$ takes this effect into account, and can serve as a more correct framework for the design and scale-up of aerated stirred tanks than methods that use eq.(25) with volume averaged quantities.

Generally, the $\langle k_L a \rangle$ for air-water stirred tanks is given in the following form:

$$\langle k_L a \rangle = C_{k_L a} (P_g / V)^a v_g^b \quad (26)$$

For air-water system van't Riet (1979) suggested a value of $C_{k_L a} = 0.026$, $a = 0.4$ and $b = 0.5$ obtained from a fit to experimental measurements. These constants have been the subject of many studies and their values vary from author to author depending on the tank size and gas loading. The correlations in eq.(26) are reported to be able to predict satisfactorily the $\langle k_L a \rangle$ of similar size vessels, but they do not necessarily apply for scale-up to an industrially sized tank (Lines, 2000; Stenberg and Andersson, 1988).

Comparison between the $\langle k_L a \rangle$ estimated using the eq.(26) and the model evaluated in this work (using the [DO] evolution at the impeller region) is presented in Table 3. Higbie's model was found to give a closer prediction of $\langle k_L a \rangle$ compared to the value estimated using eq.(26), while Danckwerts's model consistently gave a slightly smaller $\langle k_L a \rangle$ value except for case 5 where the mean bubble size is larger than 5 mm. The relative error from the $\langle k_L a \rangle$ value obtained from eq.(26) and the CFD simulations ranged from 3% to 35%, with a larger error shown for the bigger vessel. The correlations in eq.(26) are known to be problematic when applied to tanks of different size from that of the original experiments. For instance, Garcia-Cortes *et al.* (2004) reported a deviation up to 18% from their experimental measurement; earlier Zhu *et al.* (2001) reported about 20% discrepancy. The differences in the CFD simulations might also be attributed to the poor prediction of ε by the k - ε turbulence model employed in this study, especially in the highly anisotropic region around the impeller. The dissipation rate can affect the mass transfer prediction in two ways: firstly, it affects the bubble interfacial area because ε is used in the breakage and coalescence kernel and secondly, k_L is directly affected when the surface renewal model is applied.

The $\langle k_L a \rangle$ obtained from eq. (26) is also consistently shown to be somewhat smaller than the volume averaged $k_L a$ (see Table 3). These two quantities are in fact a different measure of the mass transfer coefficient, since as noted above $\langle k_L a \rangle$ takes into account the effect of the driving force on the overall mass transfer rate, whereas the volume averaged value does not.

The PBM and mass transfer calculations are reasonably successful, despite the inherent difficulties of underprediction of the dissipation rate by k - ε turbulence models. It should be noted however, that the kinetics of breakage and coalescence (and the mass transfer coefficient) depend on ε^a , where the exponent $|a|$ is small (0.25 or 0.33). So a, say, 30% error in ε gives rise to only about a 10 % error in the kinetic rates. Single phase studies on the same grid using realizable k - ε (Gimbun, 2009), show that k values near the impeller blades were fairly well predicted, even though the volume integrated ε was underestimated by 30%. Application of a uniform scaling factor for local values of dissipation, *e.g.* as used by Lane *et al.* (2005), may then lead to an overestimate of ε in regions of high breakage rate and hence was not considered appropriate in the current work.

The $\langle k_L a \rangle$ for an advanced gas dispersion impeller like the CD-6 appear to be slightly lower than the RDT operated at a similar P_g/V , VVM or v_g (in the same size of tank —

compare cases 2 and 7 in Table 3). This finding is in agreement with the experimental work reported earlier by Zhu *et al.* (2001) who concluded the RDT appears to give a slightly higher $\langle k_L a \rangle$ than the CD-6 at the same power input. This lower $\langle k_L a \rangle$ obtained with the CD-6 may be attributed to several factors. The gassed power drop by CD-6 impeller is much lower than the RDT, which means it requires a lower impeller speed to achieve a similar P_g/V . The CD-6 impeller also has a slightly higher (2.3 %) gas hold-up compare to RDT (1.7 %) and this promotes slightly more bubble coalescence resulting in a smaller interfacial area and consequently lower $\langle k_L a \rangle$. However, the CD-6 impeller is less prone to flooding compared to the RDT.

The effect of scale-up on the mass transfer rate in gas liquid stirred tanks was also evaluated. It is impossible to keep all quantities constant at different scales, but it is feasible to maintain a couple of variables *i.e.* a combination of P_g/V and either Fl_g , VVM or v_g . It is generally accepted that constant P_g/V should be maintained, since it directly affects the local energy dissipation rate, which is the key hydrodynamic variable in the breakage and coalescence kernels. Three combinations of scale-up approaches were applied going from the 14L to the 200L vessels, namely constant P_g/V and constant Fl_g , VVM or v_g . Table 3 shows that for all 3 cases, approximately the same values of the global $\langle k_L a \rangle$ were obtained from the CFD-PBM calculation. If the Higbie's model is employed for the evaluation purpose, a similar $\langle k_L a \rangle$ level is more likely to achieved by keeping the P_g/V and VVM constant, *i.e.* this rule provides a more conservative design. This might explain why in many cases of bioreactor scale-up, constant VVM yields a more favourable result. None of the scale-up approaches evaluated in this work could maintain the $\langle k_L a \rangle$ perfectly at the same level if the Danckwerts model was employed: maintaining constant v_g gave a slight reduction in $\langle k_L a \rangle$, whereas constant VVM led to a slight increase. The approach outlined by eq.(26) which is based on keeping the P_g/V and v_g constant (case 6) does not necessarily yield a similar $\langle k_L a \rangle$ for a larger tank; the CFD predictions shown here give around a 10-20% lower $\langle k_L a \rangle$ value for Higbie and Danckwerts models, but this is within the likely experimental error of the empirical correlations.

4. CONCLUSION

A comprehensive method via CFD-PBM for modelling aerated stirred tanks has been developed. The CFD-PBM method with a drag model suitable for spherical and distorted bubbles is shown to be a better approach for modelling the gas-liquid flows in stirred tanks, than simply assuming a uniform bubble size. The power number, local bubble sizes, dissolved oxygen concentration and the mean velocities of the two-phase flow have been predicted satisfactorily in correspondence with experimental data taken from the literature. There is no significant difference between the $\langle k_L a \rangle$ estimated using the [DO] evolution at the impeller region, compared to those obtained at other spatial positions, for the sizes of tank studied in this work (up to 200L). The $\langle k_L a \rangle$ predicted using correlation, such as eq.(26), which suggest a dependence on P_g/V and v_g must be used with care because they may not be applicable for vessels of a different size to those from which the original correlation was derived. The scale-up of gas-liquid stirred tanks remains a very challenging task. For the small scale up factor used here (linear scaling by $\times 2.4$, or volume scaling by $\times 14$), all three rules gave approximately similar $\langle k_L a \rangle$ values. The most conservative approach was to keep both the P_g/V and VVM constant, which in the CFD-PBM computations discussed here led to a slightly larger value of $\langle k_L a \rangle$ at larger scale; in contrast, constant P_g/V and v_g led to a slight reduction in the rate of mass transfer at larger scale.

5. ACKNOWLEDGEMENT

JG acknowledges a scholarship from Ministry of Higher Education, Malaysia, and Universiti Malaysia Pahang. We also wish to thanks Dr. D. L. Marchisio for sharing the single phase QMOM UDF which led to the implementation of the multiphase QMOM UDF in this work.

Notation

a	interfacial area per unit volume
$a(L_i)$	breakage kernel
$b(k, L_i)$	daughter bubble distribution function
C_o^*	oxygen solubility in water
C_D	drag coefficient
C_o	oxygen concentration in water
D	impeller diameter
[DO]	dissolve oxygen concentration
d_{32}	sauter mean diameter

\bar{d}_{32}	volume averaged d_{32}
d_b	bubble size (taken as sauter mean diameter)
D_l	diffusion coefficient
E_o	Eotvos number = $E_o = g\Delta\rho d_b / \sigma$
Fl_g	aeration number
\vec{F}_{lg}	interaction force mainly due to drag
\vec{F}_{lift}	lift force
Fr	Froude number
\vec{F}_{vm}	virtual mass force
g	gravity acceleration
h_f	final film thickness
h_o	initial film thickness
K	model constant for Danckwerts' model
k	turbulent kinetic energy
K_{gl}	interphase momentum exchange coefficient
k_L	liquid side mass transfer coefficient
$k_L a$	local mass transfer coefficient
$\langle k_L a \rangle$	global mass transfer coefficient
L	abscissa for QMOM
L_D	impeller blade length
N	rotation speed
n_e	number of eddies per unit volume
n_i	number of bubbles per unit volume
N_{p0}	single phase power number
P	pressure
P_0	single phase power input
P_g	gassed power input
Q_g	gas flow rate
r_o	specific oxygen consumption rate
R	aspect ratio of major and minor ellipsoids bubble radius
Re_b	Reynolds number = $Re_b = \rho u_{slip} d_b / \mu$
s	fractional rate of surface-element replacement in Danckwerts model
S_{ie}	collision cross-sectional area
T	tank diameter
t	time
u, v	velocity components
u_{slip}	slip velocity
$u_\infty(L_i)$	bubble rise velocity = $u_\infty(L_i) = \left(2.14 \frac{\sigma}{\rho_l L_i} + 0.505 g L_i \right)^{0.5}$
$u_t(L_i)$	turbulent velocity = $u_t(L_i) = 1.4 \varepsilon^{1/3} L_i^{1/3}$
$u_{te}(L_e)$	eddy velocity = $u_t(L_e) = 1.4 \varepsilon^{1/3} L_e^{1/3}$
v_g	superficial gas velocity
VVM	volume per unit volume
w	weight for QMOM
W	impeller blade width

Greek

ν_l	kinematic viscosity
θ_{ie}	collision rate of bubbles with turbulent eddies
κ_i	break-up efficiency
$\lambda(L_i, L_j)$	bubble collision efficiency
$\omega(L_i, L_j)$	bubble collision frequency
μ_k	moments of the bubble size distribution
$\beta(L_i, L_j)$	coalescence kernel
ε	turbulent dissipation rate
Γ	torque
Δt	impeller thickness

Subscripts

b	bubble
$dense$	dense bubble
g	gas
l	liquid

6. REFERENCES

1. Alves, S.S., Maia, C.I., Vasconcelos, J.M.T. and Serralheiro, A.J., 2002, Bubble size in aerated stirred tanks, *Chem. Eng. J.*, **89**: 109-117.
2. Andersson, R., and Andersson, B., 2006, On the breakup of fluid particles in turbulent flows, *AIChE J.*, **52**: 2020-2030.
3. Bakker, A. and Van den Akker, H.E.A., 1994, A computational model for the gas-liquid flow in stirred reactors, *Chem. Eng. Res. Des.* **72**: 594-606.
4. Barigou, M. and Greaves, M., 1992, Bubble-size distributions in a mechanically agitated gas-liquid contactor, *Chem. Eng. Sci.*, **47**: 2009-2025.
5. Behzadi, A., Issa, R.I. and Rusche, H., 2004, Modelling of dispersed bubble and droplet flow at high phase fractions, *Chem. Eng. Sci.*, **59**: 759-770.
6. Bordel, S., Mato, R. and Villaverde, S., 2006, Modeling of the evolution with length of bubble size distributions in bubble columns, *Chem. Eng. Sci.*, **61**: 3663-3673.
7. Brucato, A., Grisafi, F. and Montante, G., (1998), Particle drag coefficient in turbulent fluids, *Chem. Eng. Sci.*, **45**: 3295-3314.
8. Bujalski, W., Nienow, A.W., Chatwin, S. and Cooke, M., 1987, Dependency on scale of power numbers of rushton disc turbines, *Chem. Eng. Sci.*, **42**: 317-326.
9. Chen, P., Sanyal, J. and Dudukovic, M.P., 2005, Numerical simulation of bubble columns flows: effect of different breakup and coalescence closures, *Chem. Eng. Sci.*, **60**: 1085-1101.
10. Chesters, A.K., 1991, The modeling of coalescence processes in fluid-liquid dispersions, *Trans IChemE*, **69**: 259-270.
11. Clift, R., Grace, J.R. and Weber, M.E., 1978, *Bubbles, drops and particles*, Academic Press, New York.
12. Danckwerts, P.V., 1951, Significance of liquid-film coefficients in gas absorption, *Ind. Eng. Chem.* **43**: 1460-1467.
13. Deen, N.G., Solberg, T. and Hjertager, B.H., 2002, Flow generated by an aerated Rushton impeller: two-phase PIV experiments and numerical simulations, *Can. J. Chem. Eng.*, **80**: 638-652.

14. Derksen, J.J., Doelman, M.S. and Van den Akker, H.E.A., 1999, Three-dimensional LDA measurements in the impeller region of a turbulently stirred tank, *Exp. Fluids*, **27**: 522-532.
15. Ducoste, J.J., Clark, M.M., 1999, Turbulence in flocculators: Comparison of measurements and CFD simulations, *AIChE J.*, **45**: 432-436.
16. FLUENT, 2006, FLUENT 6.3 User's Guide.
17. Gezork, K.M., Bujalski, W., Cooke, M. and Nienow, A.W., 2000, The transition from homogeneous to heterogeneous flow in a gassed stirred vessel, *Chem. Eng. Res. Des.*, **78A**: 363-370.
18. Gimbut, J. (2009), Scale-up of stirred bioreactors using coupled computational fluid dynamics and population balance modelling, PhD thesis, Department of Chemical Engineering, Loughborough University.
19. Gordon, R.G., 1968, Error bounds in equilibrium statistical mechanics, *J. Math. Phys.*, **9**: 655-663.
20. Grenville, R.K. and Nienow, A.W., (2004), Blending of miscible liquids, in Paul, E.L., Atiemo-Obeng, V. and Kresta, S.M. (eds). *The Handbook of Industrial Mixing* (Wiley, New York, USA).
21. Guet, S., Luther, S. and Ooms, G., 2005, Bubble shape and orientation determination with a four-point optical fiber probe, *Exp. Therm. Fluid. Sci.*, **29**: 803-812.
22. Higbie, R., 1935, The rate of absorption of a pure gas into a still liquid during short periods of exposure, *Trans. Am. Inst. Chem. Engrs.*, **31**: 364-389.
23. Ishii, M., and Zuber N., 1979, Drag coefficient and relative velocity in bubbly, droplet or particulate flows, *AIChE J.*, **25**: 843-855.
24. Kennard, E.H., 1938, *Theory of gases*, McGraw-Hill, New York.
25. Kerdouss, F., Bannari, A., and Proulx, P., 2006, CFD modelling of gas dispersion and bubble size in a double turbine stirred tank, *Chem. Eng. Sci.*, **61**: 3313-3332
26. Kerdouss, F., Bannari, A., Proulx, P., Bannari, R., Skrga, M. and Labrecque, Y., 2008, Two-phase mass transfer coefficient prediction in stirred vessel with a CFD model, *Comput. Chem. Eng.*, **32**: 1943-1955.
27. Khopkar, A.R. and Ranade, V.V., 2006, CFD simulation of gas-liquid stirred vessel: VC, S33, and L33 flow regimes, *AIChE J.*, **52**: 1654-1672.
28. Kolmogorov, A.N., 1941, The local structure of turbulence in incompressible viscous fluid for very large Reynolds numbers. *Doklady Akademii Nauk SSSR*, **30**: 301-305.
29. Laakkonen, M., Moilanen, P., Alopaeus, V., Aittamaa, J., 2007a, Modelling local bubble size distributions in agitated vessels, *Chem. Eng. Sci.*, **62**: 721-740.
30. Laakkonen, M., Moilanen, P., Miettinen, T., Saari, K., Honkanen, M., Saarenrinne, P. and Aittamaa, J., 2005, Local bubble size distributions in agitated vessel comparison of three experimental techniques, *Chem. Eng. Res. Des.*, **83**: 50-58.
31. Laakkonen, M., Moilanen, P., Alopaeus, V. and Aittamaa, J., 2007b, Modelling local gas - Liquid mass transfer in agitated vessels, *Chem. Eng. Res. Des.*, **85**: 665-675.
32. Lamont, J.C. and Scott, D.S., 1970, An eddy cell model of mass transfer into the surface of a turbulent liquid, *AIChE J.*, **16**: 513-519.
33. Lane, G.L., Schwarz, M.P. and Evans, G.M., 2002, Predicting gas-liquid flow in a mechanically stirred tank, *Appl. Math. Model.*, **2**: 223-235
34. Lane, G.L., Schwarz, M.P. and Evans, G.M., 2005, Numerical modelling of gas-liquid flow in stirred tanks, *Chem. Eng. Sci.*, **60**: 2203-2214.
35. Lehr, F., Millies, M. and Mewes, D., 2002, Bubble size distributions and flow fields in bubble columns, *AIChE J.*, **48**: 2426-2443
36. Lines, P.C., 2000, Gas-liquid mass transfer using surface-aeration in stirred vessels with dual impellers, *Chem. Eng. Res. Des.*, **78**: 342-347
37. Luo, H., 1993, Coalescence, breakup and liquid circulation in bubble column reactors. *D.Sc. Thesis*, Norwegian Institute of Technology
38. Luo, H. and Svendsen, H.F., 1996, Theoretical model for drop and bubble breakup in turbulent dispersions, *AIChE J.*, **42**: 1225-1233

39. Marchisio, D.L., Vigil, R.D. and Fox, R.O., 2003, Quadrature method of moments for aggregation-breakage processes, *J. Colloid. Interface. Sci.*, **258**: 322–334.
40. Martínez-Bazán, C., Montañéz, J.L. and Lasheras, J.C., 1999, On the breakup of an air bubble injected into a fully developed turbulent flow. Part 1 breakup frequency, *J. Fluid Mech.*, **401**: 157-182.
41. McGraw, R., 1997, Description of aerosol dynamics by the quadrature method of moments, *Aerosol Sci. Tech.*, **27**: 255-265.
42. Moilanen, P., Laakkonen, M., Visuri, O., Alopaeus, V. and Aittamaa, J., 2008, Modelling mass transfer in an aerated 0.2 m³ vessel agitated by Rushton, Phasejet and Combijet impellers, *Chem. Eng. J.*, **142**: 95-108.
43. Montante, G., Horn, D. and Paglianti, A., 2008, Gas-liquid flow and bubble size distribution in stirred tanks, *Chem. Eng. Sci.*, **63**: 2107-2118.
44. Morud, K.E., and Hjertager, B.H., 1996, LDA measurements and CFD modelling of gas-liquid flow in a stirred vessel, *Chem. Eng. Sci.*, **51**: 233–249.
45. Myers, K.J., Thomas, A.J., Bakker, A. and Reeder, M.F., 1999, Performance of a gas dispersion impeller with vertically asymmetric blades, *Chem. Eng. Res. Des.*, **77**: 728-730.
46. Petitti, M., Caramellino, M., Marchisio, D.L. and Vanni, M., 2007, Two-scale simulation of mass transfer in an agitated gas-liquid tank, *ICMF 2007*, Leipzig, 9-13 July 2007.
47. Podila, K., Al Taweel, A.M., Koksai, M., Troshko, A. and Gupta, Y.P., 2007, CFD simulation of gas-liquid contacting in tubular reactors, *Chem. Eng. Sci.*, **62**: 7151-7162.
48. Prince, M.J., and Blanch, H.W., 1990, Bubble coalescence and break-up in air-sparged bubble columns, *AIChE J.*, **36**: 1485-1499.
49. Rotta, J.C., 1972, *Turbulente Stromungen*, B. G. Teubner, Stuttgart.
50. Scargiali, F., D'Orazio, F., Grisafi, F. and Brucato, A., 2007, Modelling and Simulation of Gas-Liquid Hydrodynamics in Mechanically Stirred Tanks, *Chem. Eng. Res. Des.*, **85**: 637-646.
51. Schiller, L. and Naumann, Z., 1935, A drag coefficient correlation, *Z. Ver. Deutsch. Ing.*, **77**: 318.
52. Schuetze, J. and Hengstler, J., 2006, Assessing aerated bioreactor performance using CFD, 12th *European Conference on Mixing*, (Bologna, June 27-30), pp. 439-446.
53. Shimizu, K., Takada, S., Minekawa, K. and Kawase, Y., 2000, Phenomenological model for bubble column reactors: prediction of gas hold-ups and volumetric mass transfer coefficients, *Chem. Eng. J.*, **78**: 21–28.
54. Smith, J.M., 2006, Large multiphase reactors some open questions, *Chem. Eng. Res. Des.*, **84(A4)**: 265–271.
55. Stenberg, O. and Andersson, B., 1988, Gas-liquid mass transfer in agitated vessels: Part II. Modeling of gas-liquid mass transfer, *Chem. Eng. Sci.*, **43**: 725–730.
56. Sun, H., Mao, Z.-S. and Yu, G., 2006, Experimental and numerical study of gas hold-up in surface aerated stirred tanks, *Chem. Eng. Sci.*, **61**: 4098-4110.
57. van't Riet, K., 1979, Review of measuring methods and results in nonviscous gas-liquid mass transfer in stirred vessels, *Ind. Eng. Chem. Proc. Des. Dev.*, **18**: 357–360.
58. Venneker, B.C.H., Derksen, J.J. and Van den Akker, H.E.A., 2002, Population balance modeling of aerated stirred vessels based on CFD, *AIChE J.*, **48**: 673-685.
59. Wang, W., Mao, Z.-S. and Yang, C., 2006, Experimental and numerical investigation on gas holdup and flooding in an aerated stirred tank with Rushton impeller, *Ind. Eng. Chem. Res.*, **45**: 1141-1151.
60. Warmoeskerken, M.M.C.G. and Smith, J.M., 1982, Description of the power curves of turbine stirred gas dispersions, *Proc Fourth Europ Conf on Mixing*, Noordwijkerhout, BHRA, Cranfield, pp. 237– 246.
61. Wellek, R.M., Arawal, A.K. and Skelland, A.H.P., 1966, Shapes of liquid drops moving in liquid media, *AIChE J.*, **12**: 854-862.
62. Zhu, Y., Bandyopadhyay, P.C. and Wu, J., 2001, Measurement of gas-liquid mass transfer in an agitated vessel-A comparison between different impellers, *J. Chem. Eng. Jpn.*, **34**: 579-584.

List of figures

Fig. 1: Result from grid analysis at $z = 0$ with respect to the impeller and $r/R = 0.37$, a) gas tangential velocity, b) k of the liquid phase

Fig. 2: Prediction of gas phase axial (u) and radial (v) velocity at normalised radial position (radial position, r over tank radius, R) $r/R = 0.37$. Schiller and Naumann (1935) drag model (CFD-PBM-SN), Ishii and Zuber (1979) drag model (CFD-PBM-IZ). Experimental data from Deen and Hjertager (2002).

Fig. 3: Prediction of liquid phase axial (u) and radial velocity (v) at $r/R = 0.37$. Experimental data from Deen and Hjertager (2002).

Fig. 4: Prediction of local Sauter mean bubble diameter for case 2: RDT, 14 L tank, $N = 700$ rpm, $Q_g = 0.7$ vvm. A) Laakkonen *et al.* (2007a) measurement (bold), this work (bracket), B) Contour map of Sauter mean diameter

Fig. 5: Prediction of local Sauter mean bubble diameter for case 4: RDT, 200 L tank, $N = 390$ rpm, $Q_g = 0.7$ vvm. A) Laakkonen *et al.* (2007a) measurement (bold), this work (bracket), B) Contour map of Sauter mean diameter

Fig. 6: Prediction of local $k_L a$ with a RDT. A) 14 L tank (case 2), B) 200 L tank (case 3)

Fig. 7: Comparison of CFD-PBM-IZ prediction of the two-phase flow in the 14 L tank with a CD-6 impeller (case 7) and RDT (case 2): $P_g/V = 1174.7$ W/m³, $Q_g = 0.7$ VVM, A) velocity vectors; contours of gas void fraction, B) contours of gas void fraction at the impeller level

Fig. 8: Prediction of [DO] evolution for case 3, $N = 390$ rpm and $Q_g = 0.7$ VVM. Data points from Laakkonen *et al.* (2007b).

Fig. 9: Comparison between the [DO] evolution calculated using two different method at impeller level, a) case 2, $N = 700$ rpm, $Q_g = 0.7$ VVM, b) case 4, $N = 365.8$ rpm, $Q_g = 0.37$ VVM

Fig. 10: Comparison between the $\langle k_L a \rangle$ estimated using the [DO] evolution obtained at different position inside the tank for case 5, $N = 386$ rpm and $Q_g = 0.7$ VVM. Higbie's method (bold font), Danckwerts's method (italic font)

Fig. 11: Comparison between the [DO] evolution for a different scale-up approach, a) Higbie's Method, b) Danckwerts's method

Fig. 12: Comparison between the [DO] evolution for a tank agitated by RDT (case 2) and CD-6 (case-7) operating at similar P_g/V , F_{lg} , VVM and v_g , a) Higbie's Method, b) Danckwerts's method

List of Tables

Table 1: Prediction of the relative power number for Rushton Turbine (RDT)

Case	T (m)	D (m)	F_{lg}	VVM	v_g (cm/s)	N (rpm)	\bar{d}_{32} (mm)	Relative power number		
								P_g/P_0 eq.(24)	P_g/P_0 CFD constant d_b	P_g/P_0 CFD-PBM-IZ
1	0.26	0.086	0.030	0.70	0.30	513.0	2.8	0.47	0.44	0.46
2	0.26	0.086	0.022	0.70	0.30	700.0	2.5	0.45	0.41	0.45
3	0.63	0.210	0.038	0.70	0.74	390.0	5.3	0.42	0.38	0.43
4	0.63	0.210	0.022	0.37	0.39	365.8	4.1	0.49	0.43	0.47
5	0.63	0.210	0.038	0.70	0.74	386.4	5.3	0.42	0.39	0.43
6	0.63	0.210	0.017	0.29	0.30	357.6	3.5	0.53	0.42	0.50

Table 2: Prediction of the relative power number for CD-6

Case	T (m)	D (m)	F_{lg}	VVM	N (rpm)	\bar{d}_{32} (mm)	Relative power number		
							P_g/P_0 measured (Myers et al., 1999)	P_g/P_0 CFD constant d_b	P_g/P_0 CFD-PBM-IZ
7	0.26	0.086	0.22	0.70	698	3.4	0.71	0.75	0.69

Table 3: Prediction of mass transfer coefficient

Case	Scale-up parameter	$\langle k_L a \rangle$ (s^{-1})			Volume averaged $k_L a$ (s^{-1})	
		van't Riet eq.(26)	Higbie	Danckwerts	Higbie	Danckwerts
2	Base case	0.024	0.023	0.018	0.031	0.026
4	P_g/V and F_{lg}	0.028	0.022	0.021	0.026	0.025
5	P_g/V and VVM	0.038	0.027	0.031	0.033	0.038
6	P_g/V and v_g	0.024	0.018	0.015	0.022	0.019
7	P_g/V and VVM and CD-6	0.024	0.019	0.015	0.021	0.016

Fig 1a.TIF




Fig 1b.TIF




Fig 2







Fig 3






Fig 4b.TIF




Fig 5a





Fig 5b.TIF







Fig 6b.TIF

$k_L a$ (1/s)



Higbie

Danckwerts





Fig 7a.TIF






Fig 8




Fig 9a.TIF





Fig 9b.TIF







Fig 11a.TIF






Fig 12a.TIF




Fig 12b.TIF

