



Numerical study of the F model with domain-wall boundaries

Downloaded from: <https://research.chalmers.se>, 2021-08-31 13:09 UTC

Citation for the original published paper (version of record):

Keesman, R., Lamers, J. (2017)

Numerical study of the F model with domain-wall boundaries

Physical Review E, 95(5)

<http://dx.doi.org/10.1103/PhysRevE.95.052117>

N.B. When citing this work, cite the original published paper.

Numerical study of the F model with domain-wall boundaries

Rick Keesman¹ and Jules Lamers^{2,*}¹*Instituut-Lorentz, Universiteit Leiden, Niels Bohrweg 2, 2333 CA Leiden, The Netherlands*²*Department of Mathematical Sciences, Chalmers University of Technology and University of Gothenburg, SE-412 96 Göteborg, Sweden*

(Received 27 February 2017; published 11 May 2017)

We perform a numerical study of the F model with domain-wall boundary conditions. Various exact results are known for this particular case of the six-vertex model, including closed expressions for the partition function for any system size as well as its asymptotics and leading finite-size corrections. To complement this picture we use a full lattice multicluster algorithm to study equilibrium properties of this model for systems of moderate size, up to $L = 512$. We compare the energy to its exactly known large- L asymptotics. We investigate the model's infinite-order phase transition by means of finite-size scaling for an observable derived from the staggered polarization in order to test the method put forward in our recent joint work with Duine and Barkema. In addition we analyze local properties of the model. Our data are perfectly consistent with analytical expressions for the arctic curves. We investigate the structure inside the temperate region of the lattice, confirming the oscillations in vertex densities that were first observed by Syljuåsen and Zvonarev and recently studied by Lyberg *et al.* We point out “(anti)ferroelectric” oscillations close to the corresponding frozen regions as well as “higher-order” oscillations forming an intricate pattern with saddle-point-like features.

DOI: [10.1103/PhysRevE.95.052117](https://doi.org/10.1103/PhysRevE.95.052117)

I. INTRODUCTION

The F model for antiferroelectric materials [1] is a special case of the six-vertex, or ice-type, model that exhibits an infinite-order phase transition (IOPT) [2]. Among others, studying the F model may thus be instructive to get a better grasp of the well-known IOPT of the two-dimensional XY model as it offers a more simple setting in which the microscopic degrees of freedom are discrete. By definition, at an IOPT the physics of a system does not change as abruptly as it does for finite-order phase transitions, which makes numerical investigations a rather subtle issue. In Ref. [3], together with Duine and Barkema, we proposed a new observable for numerical studies of IOPTs: the logarithmic derivative of the (smooth but not analytic) order parameter for the IOPT. By construction this quantity exhibits a peak at the critical, or rather “transition,” temperature β_c of the model, which makes it a suitable candidate for the analysis of the physics near the IOPT. We used a finite-size scaling analysis to compare the performance of our observable with that of other observables commonly used in the literature, focusing on the F model with periodic boundary conditions (PBCs) in both directions. In the present work we test the observable in a different, yet closely related, setting. At the same time this allows us to investigate other intriguing features of the F model, such as the dependence of its thermodynamics, i.e., the behavior at asymptotically large system size, on the boundary conditions.

The microscopic degrees of freedom of the six-vertex model are arrows pointing in either direction along the edges of a square lattice. Around each vertex the arrows have to obey the so-called ice rule, which turns out to be rather restrictive [4]. On the one hand this condition famously allows for a Bethe-ansatz analysis that provides *exact* results (see, e.g., Ref. [5] and references therein) in the thermodynamic limit. On

the other hand it causes the model's thermodynamics to depend on the *choice of boundary conditions* used at the intermediate analysis for finite size [6–8]. (In fact, this phenomenon in the context of graphene [9] originally motivated Ref. [3] and the present work.) PBCs are commonly employed and are compatible with the translational invariance that is present for infinite systems. For the six-vertex model this choice is important for the Bethe ansatz; cf. Ref. [2]. This choice was also used in our previous work [3]. The same thermodynamic behavior is obtained for “free” and (conjecturally) “Néel” boundary conditions, where the arrows on the external edges are respectively left free or fixed to alternate [6,10]. This is not true for “ferroelectric” boundary conditions, where the arrows at the boundary all point, e.g., up or to the right, but with a single allowed microstate the resulting thermodynamics is trivial.

An interesting intermediate case is provided by *domain-wall boundary conditions* (DWBCs), where on two opposite boundaries the arrows all point outwards whereas on the other two boundaries all arrows point inwards. Such boundary conditions first appeared in the calculation of norms of Bethe vectors in the quantum inverse-scattering method (QISM) in the work of Korepin [11]. Indeed, the QISM allows for an algebraic construction of the Bethe-ansatz vectors for the Heisenberg XXX and XXZ spin chains and the six-vertex model with PBCs. These algebraic Bethe-ansatz vectors simultaneously diagonalize the spin-chain Hamiltonian and the transfer matrix of the six-vertex model provided the parameters featuring in the ansatz obey constraints known as the Bethe-ansatz equations; see, e.g., Ref. [5]. The partition function of the six-vertex model with DWBCs, also known as the *domain-wall partition function*, is related to the norm of the algebraic Bethe-ansatz vectors [11]. Later this quantity was found to have applications ranging from the combinatorics of alternating-sign matrices [12,13] (see also the book [14]) to one-dimensional quantum systems with inhomogeneous initial conditions that are relevant for cold-atom physics [15] to three-point amplitudes in $\mathcal{N} = 4$ super Yang-Mills theory [16,17].

*julesl@chalmers.se

The domain-wall partition function admits a concise closed expression for all system sizes [18,19]. From this the infinite-size asymptotics can be found [7,20], as well as the form of the leading finite-size corrections [21–24]. The phase diagram of the six-vertex model has the same form for PBCs and DWBCs, but the details are different [7,20,25]; for example, even though the F model exhibits an IOPT in both cases, the free energy per site of the F model is larger for DWBCs than for PBCs. In the past decade or so DWBCs have also attracted considerable attention in relation to the arctic-curve phenomenon: they lead to coexisting phases that are spatially separated, with an *arctic curve* separating the “frozen” (ordered) and “temperate” spatial regions. This has been investigated from numerical [26–29] as well as analytic [15,30–36] viewpoints.

The remainder of this paper is organized as follows. In Sec. II we review the F model with DWBCs, its partition function, and the relevant observables; in particular we give a description of the staggered six-vertex model (cf. Ref. [37]) in the framework of the QISM. The Monte Carlo cluster algorithm and data processing are discussed in Sec. III. The results are treated in Sec. IV. We fit the exact asymptotic expressions for the energy, giving best estimates for the free parameters in the finite-size corrections, and perform a finite-size scaling analysis to test our observable at the IOPT. Besides these global averaged properties we use our simulations to examine local properties: the coexisting phases, arctic curves, and the structure in the temperate region of the lattice. We conclude with a summary and outlook in Sec. V. In the Appendix we review the global symmetries of the F model and describe how these can be exploited to sample the full phase space. This work is supplemented by an interactive Mathematica notebook [38] to illustrate some features in more detail.

II. THEORY

A. The F model and domain walls

The six-vertex model, or (energetic) ice-type model, is a vertex model on a square lattice. The arrows on the edges are restricted by the *ice rule*, which demands that at every vertex two arrows point inwards and two point outwards. This leaves the six allowed vertex configurations shown in Fig. 1. To each such vertex configuration i one assigns (local) Boltzmann weight $\exp(-\beta \epsilon_i)$, with $\beta := 1/(k_B T)$ the inverse temperature, $k_B > 0$ the Boltzmann constant that we put to unity from here on, and ϵ_i the energy of the vertex configuration. The energy is additive, so the weight of a configuration is the product of these local weights. Summing these over all allowed configurations, subject to some choice of boundary conditions, one obtains the model’s partition function.

The F model can be obtained by taking $\epsilon_1 = \epsilon_2 = \epsilon_3 = \epsilon_4$ and $\epsilon_5 = \epsilon_6$ such that the corresponding vertex weights are related by $a = b = \exp(-\beta \epsilon) c$ for some $\epsilon > 0$, making vertices 5 and 6 energetically favorable. Interestingly, this model has experimental realizations using artificial spin ice [39,40] The phase diagram is shown in Fig. 2. For low enough temperatures the system is in the antiferroelectric (AF) phase.




FIG. 1. The six vertices allowed by the ice rule and their weights for the six-vertex model. Often one assumes arrow-reversal symmetry: $a_{\pm} = a$, $b_{\pm} = b$, $c_{\pm} = c$. The F model is defined by $a = b < c$.

As temperature increases there is a transition to the disordered (D) phase. For PBCs the ground state consists of vertices 5 and 6 alternating in a checkerboard-like manner; this global AF order persists throughout the AF phase and is destroyed upon entering the D phase.

The six-vertex model does not have a thermodynamic limit in the usual sense: the physical properties of macroscopic systems remain sensitive to the choice of boundary conditions. Rather than imposing PBCs we consider an $L \times L$ portion of the lattice with *domain-wall boundary conditions* (DWBCs), where, e.g., the arrows on external edges are fixed and point




FIG. 2. The phase diagram of the six-vertex model, parametrized by the ratios a/c and b/c since common rescalings of the vertex weights yield only an overall factor for the partition function. The colors show contours for Δ at steps of $1/2$ for $-4 \leq \Delta \leq 4$. The dashed arc is the so-called free-fermion line. The dotted line corresponds to the F model, with an infinite-order phase transition between the antiferroelectric (AF) and disordered (D) phases. The thick dot is the ice point $a = b = c$, which can be interpreted as $\beta = 0$. There are two ferroelectric (FE) phases.

out (inwards) on all horizontal (vertical) edges. This change in boundary conditions has several interesting consequences that will be reviewed momentarily. Similarly to the case of PBCs (see, e.g., Refs. [25,41] for reviews) one obtains exact results for the DWBC F model by extending it to the six-vertex model with general vertex weights a , b , and c as in Fig. 1. The “reduced coupling constant” is defined as

$$\Delta := \frac{a^2 + b^2 - c^2}{2ab}. \quad (1)$$

The phase diagram looks again like in Fig. 2. At high temperatures the system is in the D phase, $-1 < \Delta < 1$. As the temperature is lowered it transitions into the AF phase, $\Delta < -1$, or one of the two the ferroelectric (FE) phases, $\Delta > 1$, depending on the ratio $a:b:c$. The D-AF phase transition is of infinite order for PBCs [2] as well as DWBCs (cf. the end of the following subsection) [20,23], while those between the D and FE phases are of first order for PBCs [42] but of second order for DWBCs [7,43].

In the FE phase the DWBCs are compatible with the FE order, while for $\Delta < 1$ (including the F model) the boundaries raise the free energy per site with respect to the case of PBCs. Zinn-Justin [8] suggested that this can be understood as a consequence of coexisting phases that are spatially separated. This phenomenon had also been found for various choices of fixed boundary conditions for the ice model ($a = b = c$) before [44]. Through the ice rule the DWBCs induce ordered regions that extend deep into the bulk, and translational invariance is lost even far away from the boundary. For example, the ground state is no longer a checkerboard-like configuration of vertices 5 and 6 as for PBCs, which would after all lead to alternating arrows along the boundary. Instead the DWBC ground state consists of a central diamond-shaped area with AF order [see also Fig. 7(a) below], consisting of vertices 5 and 6 like before, enclosed by corners that each possess FE order, containing a homogeneous configuration of one of the vertices 1 to 4. (When L is even there are two ground-state configurations of this form.) The domain walls thus raise the ground-state energy per site in the thermodynamic limit from 0 for PBCs to $\epsilon/2$ for DWBCs. When the temperature becomes nonzero a disordered region appears that separates the regions of AF and FE order, and above the critical temperature the region with AF order disappears to leave a central disordered region surrounded by FE-ordered regions [26,27]. There are sharp transitions between the regions, and the curves separating the “frozen” (AF or FE ordered) and “temperate” regions in the scaling limit (i.e., let $L \rightarrow \infty$ while decreasing the lattice spacing to keep total system size fixed) are known as *arctic curves*. These curves have four contact points with the boundary, which for the F model lie in the middle of each side [34]. For the “free-fermion point” $\Delta = 0$ the arctic curve is a circle [30] up to fluctuations of order $\sim L^{1/3}$ governed by an Airy process [31,32]. The arctic curve has also been conjectured for $|\Delta| < 1$ [33,34] and $\Delta < -1$ [35], where the latter focuses on the curve separating the FE and D regions.

Because we are interested in the F model from now on we focus on the D and AF phases. The following (real) parametrization of the vertex weights are often used in these

regimes [45]

$$D: \begin{cases} a = \sin(\gamma - t) \\ b = \sin(\gamma + t), \\ c = \sin 2\gamma \end{cases}, \quad AF: \begin{cases} a = \sinh(\gamma - t) \\ b = \sinh(\gamma + t), \\ c = \sinh 2\gamma \end{cases}. \quad (2)$$

Here $t \in [-\gamma, \gamma]$ is called the spectral parameter, while $\gamma \geq 0$ is the crossing parameter, which for the D phase is further restricted to $\gamma < \pi/2$; it is related to (1) via $\Delta = -\cos 2\gamma$ for D and $\Delta = -\cosh 2\gamma$ for AF. The F model then corresponds to $t = 0$, with $\Delta = 1 - e^{2\beta\epsilon}/2$ or γ encoding the temperature as

$$e^{\beta\epsilon} = \frac{c}{a} = \frac{c}{b} = \begin{cases} 2 \cos \gamma, & \gamma \in [0, \pi/3] \quad (D), \\ 2 \cosh \gamma, & \gamma \geq 0 \quad (AF). \end{cases} \quad (3)$$

The phase transition of the F model occurs at $\beta_c \epsilon = \ln 2$ ($\Delta = -1$, $\gamma = 0$). At this point the parametrization (2) vanishes identically, which can be avoided by simultaneously rescaling the weights to set c equal to unity. At the level of the partition function this may be implemented by keeping (2) with $t = 0$ but considering the “renormalized” partition function $c^{-L^2} Z_L(a, b, c) = Z_L(a/c, b/c, 1)$. We will denote this quantity simply by Z_L .

B. The domain-wall partition function

In some sense the six-vertex model with DWBCs is a theorist’s dream. Unlike for PBCs, for which exact results are only available for asymptotically large systems, the domain-wall partition function Z_L can be found exactly for *all* system sizes. In brief the computation goes as follows; see, e.g., Ref. [13] for more details. For the i th row (j th column) of the lattice one introduces a parameter u_i (v_j). This allows one to further extend the model to an inhomogeneous version where the weight (2) at position (i, j) features $u_i - v_j$ instead of t . Korepin [11] showed that Z_L , viewed as a function of the u_i , obeys certain properties that determine it uniquely in the inhomogeneous setting; most importantly there is a recursion relation that expresses Z_L with one u_i specialized to a specific value in terms of Z_{L-1} . Izergin [18,19] found a remarkably concise expression in the form of a determinant of an $L \times L$ matrix. Since it meets all Korepin’s requirements, Izergin’s determinant provides a formula for the domain-wall partition function valid for all L . Upon carefully evaluating the homogeneous limit, $u_i - v_j \rightarrow t$ for all i and j , this results in a Hankel determinant:

$$Z_L = \frac{(ab/c)^{L^2}}{\prod_{k=0}^{L-1} (k!)^2} \det_{L \times L} M, \quad M_{i,j} := \partial_t^{i+j-2} \frac{c}{ab}, \quad (4)$$

where the definition of $M_{i,j}$ assumes a parametrization of the form (2). Specializing this quantity to the ice (or “combinatorial”) point $a = b = c$ (so $\Delta = 1/2$) one finds that the number of domain-wall configurations for $L = 1, 2, \dots$ is 1, 2, 7, 42, 429, 7436, 218 348, ... [13]. For the F -model the domain-wall partition function factorizes as $Z_{2L} = 2 X_{2L} X_{2L+1}$, $Z_{2L+1} = X_{2L+1} X_{2L+2}$ for certain polynomials X_L [13, Thm. 3]; cf. Ref. [46, Thm. 4].

Using the explicit results found by Korepin–Izergin the bulk free energy was evaluated in the thermodynamic limit by Korepin and Zinn-Justin [7] and Zinn-Justin [20]. Prior to that only some special cases in the D phase were known: the

free-fermion point ($\Delta = 0$, $\gamma = \pi/4$) corresponding to the 2-enumeration of alternating-sign matrices [12, Sec. 6], and the ice point ($\Delta = 1/2$, $\gamma = \pi/3$) as well as the point $\Delta = -1/2$ ($\gamma = \pi/6$) related to the 3-enumeration of alternating-sign matrices [13]. Here we recall that the “ c^2 -enumeration of alternating-sign matrices (cf., e.g., Refs. [13,14]) is given by $c^L Z_L(1,1,c)$ since the DWBCs imply that $\#c_- = L + \#c_+$.

A rigorous and more detailed analysis for the D and AF phases and the corresponding transition, which is most relevant for us, was given by Bleher *et al.* [21–24]. The asymptotic expressions for the domain-wall partition function Z_L , together with the first subleading terms in system size, are as follows for the F model. In the disordered regime one has [21]

$$Z_D^{\text{asym}} = C_D(\gamma) f_D(\gamma) L^2 L^{\kappa(\gamma)} [1 + O(L^{-\alpha})], \quad (5)$$

where $C_D(\gamma) > 0$ and $\alpha > 0$ are unknown (cf. Ref. [47] below), while

$$f_D(\gamma) = \frac{\pi \tan \gamma}{4\gamma}, \quad \kappa(\gamma) = \frac{1}{12} - \frac{2\gamma^2}{3\pi(\pi - 2\gamma)}. \quad (6)$$

For the antiferroelectric regime one finds [22]

$$Z_{\text{AF}}^{\text{asym}} = C_{\text{AF}}(\gamma) f_{\text{AF}}(\gamma) L^2 \vartheta_4(L\pi/2) [1 + O(L^{-1})], \quad (7)$$

with $C_{\text{AF}}(\gamma) > 0$ another unknown normalization factor, and the extensive part of the free energy is

$$f_{\text{AF}}(\gamma) = \frac{\pi \tanh \gamma}{4\gamma} \frac{\vartheta_1'(0)}{\vartheta_1(\pi/2)}, \quad (8)$$

where ϑ_1 and ϑ_4 denote the Jacobi theta functions with temperature-dependent elliptic nome $q := \exp(-\pi^2/2\gamma)$.

From these exact asymptotics of the domain-wall partition function it can be shown that, as for PBCs, the phase transition is of infinite order [20,23]. Indeed, when subtracting the regular part, $(\pi/4\gamma) \tanh \gamma$ [differing from (6) only in the parametrization used], from the AF free energy (8) one is left with an expression that is smooth but exhibits an essential singularity as $\gamma \rightarrow 0^+$.

C. The staggered polarization

An order parameter for the D–AF phase transition is defined as follows. For any microstate C one can compute the spontaneous staggered polarization $P_0(C)$. This quantity is a measure of the likeness of C to one of the two AF ground states C' of the system with PBCs. At each vertex the local spontaneous staggered polarization can be defined as $\sum_i \sigma_i \sigma'_i / 4$, where the sum is taken over the four edges surrounding the vertex, and $\sigma_i = \pm 1$ ($\sigma'_i = \pm 1$) depending on whether arrows on those edges point outwards or inwards in C (C'). Then $P_0(C)$ is the sum over all these local quantities; since the AF ground state is twofold degenerate its sign depends on the choice of C' to which C is compared. Additionally, for even L states come in pairs with equal energy but opposite spontaneous staggered polarization. To avoid cancellation of these contributions one defines the *staggered polarization* as the thermal average $P_0 := \langle |P_0(C)| \rangle$ of the absolute value of $P_0(C)$. Note that the situation is analogous to what happens for the magnetization in the two-dimensional Ising model.

For the system with PBCs Baxter derived the exact large- L asymptotics of P_0 for all temperatures [37]. This quantity becomes smoothly nonzero when the system transitions from the D to the AF phase. Let us assume that it continues to be a valid order parameter for the transition of the system with DWBCs. For this case an expression for P_0 that is manageable for all system sizes is not known. We still have

$$P_0 = \left. \frac{d \ln Z_L^+(s)}{ds} \right|_{s=0}, \quad (9)$$

where $Z_L(s)$ is the partition function of the F model on an $L \times L$ lattice with DWBCs in the presence of an external staggered electric field of strength $s \geq 0$. The superscript “+” in (9) indicates that the absolute value of each coefficient is to be taken in order to prevent the aforementioned cancellation. No analog of (4) is known when $s \neq 0$. Nevertheless the framework of the quantum inverse-scattering method (QISM) does allow for the direct computation of $Z_L(s)$ and thus P_0 , for low system size. Let us indicate how this works; we refer to Ref. [5] and references therein for more about the QISM.

Let us give a description of the *staggered six-vertex model* based on Baxter [37]. We focus on the homogeneous case; inhomogeneities may be incorporated as usual. View the square lattice as being bipartite by dividing its vertices into two sets in a checkerboard-like manner. The vertex weights from Fig. 1 are given by $a_{\pm} = a$, $b_{\pm} = b$, while c_{\pm} is equal to $e^{\pm s} c$ on one sublattice (“black” vertices) and to $e^{\mp s} c$ on the other (“white” vertices). These vertex weights can be encoded in the so-called R -matrix [48]

$$R(s) = \begin{array}{c} \text{---} \circ \text{---} \\ | \\ \text{---} \end{array} = \begin{pmatrix} a & 0 & 0 & 0 \\ 0 & b & e^s c & 0 \\ 0 & e^{-s} c & b & 0 \\ 0 & 0 & 0 & a \end{pmatrix}, \quad (10)$$

defined with respect to the basis $|\rightarrow\blacktriangleright\rangle, |\rightarrow\blacktriangledown\rangle, |\leftarrow\blacktriangleright\rangle, |\leftarrow\blacktriangledown\rangle$ for the “incoming” lines and $\langle\blacktriangleright\rightarrow|, \langle\blacktriangledown\rightarrow|, \langle\blacktriangleright\leftarrow|, \langle\blacktriangledown\leftarrow|$ for the “outgoing” lines at the vertex. In the diagrammatic notation in (10) one should think of time running along the diagonal from bottom left to top right. $R(s)$ contains the vertex weights for the “black” vertices and $R(-s)$ for the “white” vertices.

A row of the lattice is described by the staggered (row-to-row) *monodromy matrix*

$$\begin{aligned} T(s) &:= \begin{array}{c} \text{---} \circ \text{---} \text{---} \circ \text{---} \cdots \text{---} \circ \text{---} \\ | \quad | \quad \quad \quad | \\ 1 \quad 2 \quad \quad \quad L \end{array} \\ &= R_L(\pm s) \cdots R_2(-s) R_1(s), \end{aligned} \quad (11)$$

where R_j contains the weights for the j th vertex in that row. It is customary to write $B(s)$ for the $2^L \times 2^L$ matrix sitting in the upper right quadrant of $T(s)$. This matrix accounts for a row of the staggered six-vertex model with arrows on the horizontal external edges pointing outwards as for DWBCs:

$$B(s) = \begin{array}{c} \leftarrow \text{---} \circ \text{---} \text{---} \circ \text{---} \rightarrow \\ | \quad | \quad \quad \quad | \\ 1 \quad 2 \quad \quad \quad L \end{array}. \quad (12)$$

The staggered domain-wall partition function can then be expressed as an entry of a “staggered” product of L such matrices [49]

$$Z_L(s) = \langle \downarrow \downarrow \cdots \downarrow \downarrow | B(\pm s) \cdots B(-s) B(s) | \uparrow \uparrow \cdots \uparrow \uparrow \rangle. \quad (13)$$

For example, if $L = 1$ then $B(s)$ is $\begin{pmatrix} 0 & 0 \\ e^s c & 0 \end{pmatrix}$ and $Z_1(s) = e^s c$.

The ordinary domain-wall partition function is recovered in this algebraic language as $Z_L = Z_L(0)$. We have evaluated (13) for general s up to $L = 12$, accounting for little over 10^{16} configurations.

To conclude this section let us comment on whether quantum integrability may be used to get some concise expression for $Z(s)$ valid for all L . The answer appears to be negative; at least the Korepin-Izergin approach mentioned in Sec. II B does not simply extend to $s > 0$. Indeed, one can still write four recursion relations obeyed by the inhomogeneous extension of (13), namely, for $u_1 = v_1 - \gamma$, $u_1 = v_L + \gamma$, $u_L = v_1 + \gamma$, and $u_L = v_L - \gamma$. However, for $s \neq 0$ the inhomogeneous partition function is not symmetric in the u_i , so one does not get further Korepin-like recursion relations and the conditions do not uniquely determine $Z(s)$ for general L . The failure of $Z(s)$ to be symmetric in the u_i is of course closely related to the fact that the staggered R matrices (10) do not obey a Yang–Baxter equation;— even writing the latter is problematic since the triangle featuring in that relation is not bipartite. The latter also obstructs the computation of P_0 using the so-called F -basis [50].

III. SIMULATIONS

Recall that the six-vertex model is equivalent to a height model known as the (body-centred) solid-on-solid model [51]. In this picture fixed boundary conditions ensure that the height of a configuration is bounded from below and above. Going around the boundary in some direction the DWBCs correspond to the height increasing along two opposite ends, say, from 0 to L , and then decreasing from L back to 0 along the other two ends. There are unique configurations of minimal and maximal height: the former corresponds to a valley of height 0 running along one diagonal, and the latter to a ridge of height L along the other diagonal. (Note that these are the ground-state configurations of the two FE phases. The AF ground state corresponds to a diamond-shaped plateau, of height as close as possible to $L/2$, surrounded by steep slopes to the pits and peaks at the corners.) The existence of configurations of minimal and maximal height allows one to use *coupling from the past* (CFTP) algorithms [52,53], which ensure that one draws configurations from the equilibrium distribution making it a perfect simulation. Although CFTP can in principle be “shelled” around a variety of updating schemes, in practice it is used only in combination with local updates due to the difficulties that arise when the same global update needs to be performed on both the lower and higher configuration. In this work we prefer speed over sample accuracy as this allows us to investigate much larger systems, thus improving the reliability of our subsequent analysis of the thermodynamic limit. Rather than CFTP we thus use the full lattice multicluster algorithm [54], as in Ref. [3], with a reported dynamic exponent $z = 0.005 \pm 0.022$ for PBCs [55],

so that the correlation time can be considered independent of system size in practice. The accuracy of our simulations is checked in Sec. IV against the theoretical expressions that were reviewed in Sec. II.

Our results are procured from Monte Carlo simulations using the full lattice multicluster algorithm in combination with parallel tempering [56]. We use the multihistogram method [57,58] to interpolate observables, the energy and staggered polarization in particular, in a temperature range around the critical temperature. The F model is well suited for both parallel tempering and the multihistogram method as the specific heat is analytically known and bounded [cf. (14) below] such that a set of temperatures can be constructed *a priori* at which the energy distributions of “adjacent” configurations overlap significantly. Given a configuration at inverse temperature β , its neighboring configurations are set at $\beta' = \beta \pm \beta/\sqrt{C_v}$. In each simulation the acceptance probability of swapping two configurations is never less than 47%. After each update a measurement is taken, with a minimum of 10^6 measurements per system size per temperature, at up to 30 different temperatures per system size. At each measurement we determine the total energy and staggered polarization, calculated based on the description in the first paragraph of Sec. II C, of the system as well as the local vertex density at each vertex in the system. In principle one can estimate the thermal average of any time-independent (local) observable that can be defined for the system, such as arrow correlations, in a similar fashion. Note that all cluster updates that would change the arrows on the boundary are rejected to preserve the DWBCs.

IV. RESULTS

A. Energy and specific heat

Unlike the energy, the partition function itself can not be directly measured in Monte Carlo simulations. Exceptions are very small systems ($L \leq 6$) for which our simulations happen to sample all microstates so that we are able to reconstruct the full staggered partition function. The resulting expressions for $E(\beta) = \langle E(C) \rangle$ and $P_0(\beta)$ precisely match those obtained via the QISM as described in Sec. II C. In general just a part of the phase space is sampled so the partition function cannot be reconstructed as the total energy $E(\beta)$ is not known for all temperatures. However, the multihistogram method allows us to use simulations done at finitely many temperatures to determine the partition function, up to an overall factor, on some finite temperature range.

Figure 3 shows the energy per site $e(\beta) := E(\beta)/L^2$ and the specific heat per site $c_v(\beta) := C_v(\beta)/L^2$ as functions of inverse temperature. The simulation data are shown together with the exact expressions for infinite size extracted from Eqs. (5) and (7) using

$$E(\beta) = -\frac{\partial \ln Z}{\partial \beta}, \quad \frac{C_v(\beta)}{\beta^2} = -\frac{\partial E}{\partial \beta} = \frac{\partial^2 \ln Z}{\partial \beta^2}, \quad (14)$$

which yields $e(\beta_c) = 2/3$ and $c_v(\beta_c) = 8 \ln^2(2)/45$. We observe a convergence of the simulation data to the analytically known asymptotic values over all simulated temperature ranges.




FIG. 3. The average energy per site $e(\beta)$ (top) and specific heat per site $c_v(\beta)$ (bottom) as functions of inverse temperature β . The critical points at β_c are indicated by the gray lines. The black lines are the exact asymptotic expressions extracted from Eqs. (5) and (7). From the data points, indicating the temperatures at which the simulations are done, the colored solid lines are calculated using the multihistogram method. For both observables we see a convergence of the data to the analytically known expressions in the thermodynamic limit.

To investigate the effects of the subleading corrections in the system size for the partition function further we focus on the critical point. Because of the smoothness of the partition function we can take the expressions for the disordered regime and evaluate them at the phase transition. Starting from Eq. (5) we find the following expression for the energy per site $e_L(\beta_c)$ at the critical point for system size L :

$$e_L(\beta_c) = \frac{2}{3} - \frac{4}{3\pi^2} \frac{\ln L}{L^2} - \frac{C_1}{L^2} + O(L^{-(\alpha+2)}), \quad (15)$$

with $C_1 = -\lim_{\gamma \rightarrow 0^+} C_D'(\gamma)/[\gamma C_D(\gamma)]$ an unknown parameter. Equation (15) can be checked against the expression for the energy derived directly from (4) for small system sizes ($L \leq 16$) as well as the simulation data for moderate system sizes. This is shown in Fig. 4 where $e_\infty(\beta_c) - e_L(\beta_c)$ and $E_\infty(\beta_c) - E_L(\beta_c)$ are plotted versus system size. The best unweighed fit, including only the asymptotically next-to-leading correction $C_1 = 0.669 \pm 0.019$, already shows very good agreement with both the exact and numerically obtained values. For $L \leq 141$ this next-to-leading correction, $\sim 1/L^2$, is more important than the asymptotically leading correction, $\sim \ln L/L^2$. This means that even at $L \sim 10^{21}$ the two corrections in (15) just differ by a factor 10. Also note the high precision at which both the leading and first subleading corrections are




FIG. 4. The difference between the energy per site (top) and total energy of the system (bottom), with $E_\infty(\beta_c) := L^2 e_\infty(\beta_c) = 2L^2/3$, is shown as a function of system size. The solid blue disks represent the exact known values for small system sizes obtained from Eq. (4). The open red squares denote best estimates obtained from our simulations. The error bars are estimates based on the fluctuations in the energy and the number of measurements taken. The expressions from Eq. (15) with only the leading correction ($C_1 \equiv C_2 \equiv 0$) and with first subleading correction ($C_1 = 0.669 \pm 0.018$), as well as the expression from Eq. (16) ($C_2 = 1.6 \pm 1.2$, $C_3 = 14 \pm 12$, $\alpha = 1.91 \pm 0.36$ [47]) are shown as dotted, dashed, and solid curves, respectively.

measurable for systems as large as $L = 256$, for which these corrections are of the order 10^{-5} .

A best estimate for the value of α can be found by assuming that the subleading terms in (5), i.e., the $O(L^{-\alpha})$, is of the form $g(\gamma)L^{-\alpha}$. This yields

$$e_L(\beta_c) \simeq \frac{2}{3} - \frac{4}{3\pi^2} \frac{\ln L}{L^2} - \frac{C_1}{L^2} + \frac{C_2}{L^2(L^\alpha + C_3)}, \quad (16)$$

where $C_2 = \lim_{\gamma \rightarrow 0^+} g'(\gamma)/\gamma$ and $C_3 = \lim_{\gamma \rightarrow 0^+} g(\gamma)$ are again unknown. We assume that these limits make sense; the corrections are finite and must disappear for infinite systems. If we use our best value for C_1 and fit Eq. (16) to the energies of small systems obtained from direct computation of (13) (see again Fig. 4), the best estimates are $C_2 = 1.6 \pm 1.2$, $C_3 = 14 \pm 12$, and $\alpha = 1.91 \pm 0.36$ [47]. The inclusion of these subleading correction does improve the fit qualitatively, although error margins for best estimates of the parameters C_2 and C_3 are very large. With these values the crossover point where the terms proportional to C_1 and C_2 become comparable occurs already at $L = 3.9$. The exact analytical values for the




FIG. 5. The observable $d \ln P_0 / d\beta$ is shown in (a) as a function of inverse temperature β for various system sizes up to $L = 256$. In the thermodynamic limit, under the assumption that P_0 is a valid order parameter, this function must have its peak at the critical point. In (b) the peak and the point where the curves attain 95% of their peak height (at higher β) are scaled on top of each other, with the two points indicated by black circles. From this collapse we extract the peak position and typical width for further analysis; cf. Fig. 6.

energy can be computed using (4) or (13). We have done so for $L \leq 16$; in either case most computation time was spent on the derivation of the energy from the partition function at the critical point rather than the calculation of the partition function itself.

B. The logarithmic derivative of P_0

Similar to our work in Ref. [3] we now study $d \ln P_0 / d\beta$, which must have a peak at the critical point for infinitely large systems if P_0 is a true observable of the infinite-order phase transition. As for the energy the multihistogram method is used to obtain $d \ln P_0 / d\beta$ by interpolation between the temperatures at which the systems were simulated. Figure 5(a) shows $d \ln P_0 / d\beta$ as a function of inverse temperature for various system sizes up to linear size $L = 256$. To obtain a numerical collapse for each system size we determine the peak coordinates (β_{\max}, h_{\max}) as well as the typical width w , which is defined as the absolute difference between β_{\max} and the lower temperature at which $d \ln P_0 / d\beta$ attains 95% of the peak height. The numerical collapse is shown in Fig. 5(b);

unfortunately it is less clean than its counterpart for PBCs in [3].

Previously we found behavioral similarities between $d \ln P_0 / d\beta$ and the susceptibility χ of the staggered polarization for PBCs [3]. Since there are no known analytical expressions for the asymptotic behavior of P_0 for DWBCs we fall back on the leading corrections known for PBCs [59]. In the case of PBCs the leading correction for the peak position of χ is of the form $\ln^{-2} L$, and so for DWBCs one could make the educated guess that the form of the peak of $d \ln P_0 / d\beta$ scales like

$$x = A_x + B_x \ln^{-2} L + C_x \ln^{-3/2} L + D_x \ln^{-4} L, \quad (17)$$

where x is either the inverse peak height h_{\max}^{-1} , the peak width w , or the position β_{\max} of the peak. Figure 6 shows these quantities as a function of $\ln^{-2} L$ with the best fit of Eq. (17) to the three characteristics. The best estimates from an unweighed fit to all data points for the peak height are $A_{h_{\max}^{-1}} = -0.01 \pm 0.03$, $B_{h_{\max}^{-1}} = 5.4 \pm 1.1$, $C_{h_{\max}^{-1}} = -3 \pm 3$, and $D_{h_{\max}^{-1}} = -2 \pm 3$. For the peak width the best estimates are given by $A_w = -0.009 \pm 0.009$, $B_w = 2.4 \pm 0.4$, $C_w = -5 \pm 1$, and $D_w = 3.0 \pm 0.8$. A similar fit for β_{\max} does not seem to work. Indeed, the best estimate for $A_{\beta_{\max}} = 0.83 \pm 0.02$ is far from the analytically known value $\beta_c = \ln 2$. Alternatively one could fix $A_{\beta_{\max}} = \beta_c$, in which case the fit does not go through the data in a clean fashion. Although this method does not reliably give an estimate for the critical point it does show the convergence of $d \ln P_0 / d\beta$ to a Dirac delta-like distribution as the system size tends to infinity. From Fig. 6 we see that in practice direct computation using (13) cannot be used outside of the regime in which subleading finite-size corrections are important. Simulations reveal the decrease in β_{\max} for increasing system size.

C. Arctic curves

So far we have investigated global quantities. For inhomogeneous (not translationally invariant) systems such as the F model with DWBCs such properties provide rather coarse information, as a lot of the local information is averaged away.

Figure 7 shows the thermally averaged c -vertex density $\rho(c)$, together with several contour lines, for a system of linear size $L = 512$ at various temperatures: zero temperature ($\beta \rightarrow \infty$, $\Delta \rightarrow -\infty$), below the critical point ($\beta = 2\beta_c$, $\Delta = -7$), at the critical point ($\beta_c = \ln 2$, $\Delta = -1$), at the free-fermion point ($\beta = \beta_c/2$, $\Delta = 0$), and at infinite temperature ($\beta = 0$, $\Delta = 1/2$). For nonzero temperature 10 independent simulations, each yielding 10^6 measurements, were performed per temperature to calculate the local vertex density. We use the global symmetries described in the Appendix to get a smoother $\rho(c)$ -profile by averaging at a given Δ . At the center $\rho(c)$ is always at a maximum. For zero temperature, the critical temperature, and the free-fermion point the maximal values are 1 and about $2/3$ and $1/2$, respectively. At low temperatures there is a AF region, with constant $\rho(c)$ close to unity signaling its ordered nature. As the temperature rises from zero a temperate region emerges that encloses the central AF region, completely engulfing it at the critical point; cf. Ref. [27]. The arctic curves, exactly known for $\Delta = -\infty$ and $\Delta = 0$ [31,32] and conjectured for $\Delta < 1$ [33–35] are also shown in Fig. 7.




FIG. 6. Values of the inverse peak height h_{\max}^{-1} (upper panel), peak position β_{\max} (central panel), and peak width w (lower panel) are shown for $d \ln P_0/d\beta$ up to system size $L = 256$ as a scaled function of $\ln^{-2} L$. Exact values for small system sizes obtained from Eq. (13) are shown as solid blue disks and best estimates obtained from our simulations as open red squares. The best unweighed fits of the form (17) are drawn as black dashed lines. For β_{\max} a fit through all data points results in a best estimate for the critical point $A_{\beta_{\max}} = 0.87 \pm 0.03$ far from the analytically known value $\beta_c = \ln 2 \approx 0.69$. For h_{\max}^{-1} ($A_{h_{\max}^{-1}} = -0.01 \pm 0.03$, $B_{h_{\max}^{-1}} = 5.4 \pm 1.1$, $C_{h_{\max}^{-1}} = -3 \pm 3$, $D_{h_{\max}^{-1}} = -2 \pm 3$), and w ($A_w = -0.009 \pm 0.009$, $B_w = 2.4 \pm 0.4$, $C_w = -5 \pm 1$, $D_w = 3.0 \pm 0.8$) the fits work well and are in agreement with $d \ln P_0/d\beta$ becoming a Dirac delta-like distribution as $L \rightarrow \infty$.

The outer contours are drawn at temperature-dependent values for $\rho(c)$ (see Table I) chosen such that those contours are qualitatively comparable to the known and conjectured forms of the arctic curves. We see that our data match very well with the analytic expressions; for nonzero temperature the deviation from zero of the values given in Table I is a measure of the influence of finite-size effects.

TABLE I. The values for β and Δ at which the simulations for Figs. 7(a)–7(e) were performed are given together with the values for $\rho(c)$ at which the outer contours are drawn. For finite Δ this gives a measure of the deviation from the asymptotic values $\rho(c) = 0$ due to finite-size effects.

	(a)	(b)	(c)	(d)	(e)
β	∞	$2\beta_c$	$\beta_c = \ln 2$	$\beta_c/2$	0
Δ	$-\infty$	-7	-1	0	$1/2$
$\rho(c)$	0.500	0.012	0.021	0.018	0.014

D. Oscillations in vertex densities

Finally we turn to the structure inside the temperate region. In Fig. 8 we show the thermally averaged densities ρ along the diagonal from the FE region dominated by b_- -vertices ($r = L/\sqrt{2}$, bottom left corner in Fig. 7) to the center ($r = 0$) of a system of size $L = 512$ at the critical point $\Delta = -1$. Along this diagonal one has $\rho(a_+) = \rho(a_-)$. Moreover if one considers r to cover the full diagonal, $-L/\sqrt{2} \leq r \leq L/\sqrt{2}$, then $\rho(a_{\pm})$ and $\rho(c_{\pm})$ are even as functions of r while $r \mapsto -r$ reverses $\rho(b_+) \leftrightarrow \rho(b_-)$. This once more allows us to exploit the global symmetries as explained in the Appendix to average for the densities of $\rho(a_{\pm})$ and $\rho(b_{\pm})$ in Fig. 8. Note that some of these transformations exchange $a_{\pm} \leftrightarrow b_{\pm}$ as they involve arrow reversal to preserve the boundary conditions. The Supplemental Material [38] shows the profiles of the six vertex densities for $L = 100$ at different values of Δ .

Using numerics, Syljuåsen and Zvonarev [26] first noticed oscillatory behavior (“small wiggles”) of the arrow polarization density for $\Delta < -1$; see Fig. 6 therein [60]. Recently Lyberg *et al.* [29] recovered these oscillations while studying the local vertex densities exactly; cf. the asymptotic expression of the arrow polarization found for $\Delta = 0$ in Ref. [15], as well as numerically. In Fig. 8 we observe oscillations for all of the vertex densities in the temperate region. The wavelengths of these oscillations are comparable functions of r for each of the vertices. For lower temperatures these ripples are more pronounced yet the region in which they appear, *viz.*, the temperate region, becomes smaller. The thermally averaged densities $\rho(c_+)$ and $\rho(c_-)$ are in antiphase (cf. Fig. 8) so these oscillations are masked if just $\rho(c)$ is considered as in Fig. 7. The complicated oscillatory behavior in the temperate region can more clearly be seen from the thermally averaged c -vertex density difference $\delta\rho(c) := \rho(c_-) - \rho(c_+)$. Let us emphasize that we focus on the density difference for the c -vertices because $\rho(c_{\pm})$ are in antiphase, so $\delta\rho(c)/2 = \rho(c_-)/2 - \rho(c_+)/2$ allows us to study the oscillations of $\rho(c_+)$ about its “average” by approximating the latter with the average $\rho(c)/2$ of $\rho(c_{\pm})$. We should also point out that $\rho(c)$ itself exhibits oscillations, visible near the arctic curve for finite Δ in Fig. 7; we have verified, however, that the $\rho(c)$ - and $\delta\rho(c)$ -oscillations have a phase difference of $\pi/2$, so the ripples in Fig. 7 are related to the “FE oscillations” that we will introduce momentarily.

To study the dependence on the system size of the oscillations in the temperate region Fig. 9 shows $\delta\rho(c)$ along the diagonal for system sizes $L = 32$ up to $L = 512$. The wavelength of the oscillations is always largest at the edges of the temperate region. We observe a sublinear growth of




FIG. 7. The thermally averaged density $\rho(c)$ of c vertices at $L = 512$ show phase separation at different temperatures. The density lies between zero (shown in purple) and one (light red). White solid contour lines are drawn at the values $1/3, 1/2, 2/3$, and 0.98 , as indicated, of $\rho(c)$. The outer white solid contours are drawn at temperature-dependent values of $\rho(c)$ (see Table I) that give the best qualitative match with the arctic curves [31–35], which are shown as dashed black curves. At zero temperature (a) the AF region is a diamond. At slightly elevated temperatures (b) the AF and FE regions are separated by a temperate region. As the temperature increases past its critical value (c), at which the AF region disappears, the arctic curve deforms to a circle at the free-fermion point (d). The system at infinite temperature is shown in (e), in which the arctic curve is a sort of inflated circle, with the arcs deformed somewhat towards the corners of the domain.

the wavelength in L . A best unweighed fit to the distance between the center of the system ($r = 0$) and the position of the maximum of $\delta\rho(c)$ gives $(0.67 \pm 0.06)L^{(0.553 \pm 0.016)}$. Such a fit cannot be made for the maximal amplitude as our data are not accurate enough to distinguish between logarithmic or power-law behavior. Still Fig. 9 does clearly show that the average wave amplitude monotonically decreases with system size, suggesting that the oscillations are finite-size effects, as was conjectured in Ref. [26]; cf. Sec. 4 of Ref. [29].

Figure 10 shows the profile of $\delta\rho(c)$ for systems at $\Delta = -1$ and $\Delta = -7$. Inside the temperate region there are at least two types of oscillations: one type, let us call them “AF oscillations,” follows the boundary between the AF-frozen and temperate regions (which at $\Delta = -1$ degenerates to the horizontal and vertical lines separating the quadrants), while the other type, “FE oscillations,” follows the contours of the arctic curve between the temperate and FE-frozen regions. (Both of these types of oscillations may be discerned in Ref. [29, Fig. 6] too, and the FE oscillations arguably already

in Figs. 10 and 11 of Ref. [26]. We should point out that in Ref. [26] the term “AF oscillations” is instead used for the checkerboard patterns of c_{\pm} -vertices typical for AF order.)

Interestingly, upon closer inspection of Fig. 10 we observe a checkerboard-like pattern inside the AF oscillations (cf. Ref. [29, Fig. 6, $\Delta = -10$]), signaling site-to-site anticorrelations for $\rho(c_{\pm})$ that persist over long distances along the oscillations, and justifying the name “AF” for these types of oscillations. Note that, albeit in a weaker form, these checkerboards survive thermal averaging: unlike the one in the AF region for even L it is a physical property of the system; see also the Supplemental Material to this work [38]. We observe that the checkerboards in adjacent oscillations are opposite, so the bands separating the oscillations can be understood as the result of destructive interference between the two checkerboards. Also note that such checkerboard-like anticorrelations are invisible when one focusses on the densities along the diagonal. Next we turn to the FE




FIG. 8. The thermally averaged densities ρ for all six vertices in a system of linear size $L = 512$ at the critical point $\Delta = -1$ are shown along the diagonal from the b_- -dominated FE region to the center at $r = 0$. The grey vertical line marks the transition between the FE and temperate region [35]. Each vertex density oscillates in the temperate region. Note that $\rho(c_{\pm})$ are in antiphase around their average.




FIG. 9. The difference $\delta\rho(c)$ is shown as a function of distance r along the diagonal to the center (at $r = 0$) for systems up to size $L = 512$ at $\Delta = -1$. The colored lines are a guide to the eye, and the gray vertical line denotes the transition between the FE-frozen and temperate region as in Ref. [35]. The wavelength of the oscillations seems to increase sublinearly while the average wave amplitude decreases monotonically with system size, suggesting that these are finite-size effects.




FIG. 10. The thermally averaged density difference $\delta\rho(c)$ is shown for a system of size $L = 512$ at $\Delta = -1$ (upper panel) and $\Delta = -7$ (lower panel). Each pixel corresponds to a vertex. The FE-frozen region in the bottom left contains only b_- vertices. Below the critical point the AF-frozen region appears (lower panel) in which $\delta\rho(c) = 0$ due to the twofold degeneracy for even L . Inside the intermediate temperate region at least two types of oscillations are visible. There appear to be checkerboard-like patterns in the “AF oscillations” even after thermal averaging, with opposite checkerboards in neighboring oscillations. The “FE oscillations” are dominated by the vertices constituting the FE-frozen region (here b_-), with $\delta\rho(c) > 0$ between them.

oscillations. The density profiles of all six vertices for $L = 100$ can be found in the Supplemental Material [38]. The profile of $\rho(b_-)$ reveals that the interior of the FE oscillations near the




FIG. 11. The thermally averaged c_{\pm} -density difference $\delta\rho(c)$ for size $L = 512$ at $\Delta = -1$ (upper panel), truncated at 10% of the values from the upper panel in Fig. 10. Every pixel represents one vertex. This reveals weak “higher-order” oscillations in the temperate region with various saddle-point-like features; we can distinguish at least four of these along the diagonal, and more along the top and right. The lower panels show $\delta\rho(c)$ at $\Delta = 0$ (left) and $\Delta = 1/2$ (right), each again truncated at 10% of its minimal and maximal value.

frozen region dominated by b_- are also dominated by b_- , and similar statements are true for the other quadrants. Figure 10 further shows that the regions between the FE oscillations are dominated by c_- -vertices ($\delta\rho(c) > 0$) to account for the constraint $\#c_- > \#c_+$ imposed by the DWBCs. Notice that as the FE oscillations approach the median, at the top of Fig. 10, they reduce to a checkerboard pattern on the median to merge with the interior of the largest AF oscillation.

To justify our observations let us explain in more detail how Fig. 10 was obtained. We use the same data as for Fig. 7, based on 10 independent simulations each with 10^6 measurements of local vertex density. We use the model’s global symmetries to produce further configurations from those obtained from our simulations and sample over the full phase space as described in the Appendix. Averaging over these configurations we obtain the profile for $\delta\rho(c)$ shown in Fig. 10, which correctly

vanishes both in the FE and AF regions. For even as well as odd L , however, the site-to-site anticorrelations between the AF oscillations in the *temperate* region survive this averaging: unlike for the checkerboard in the AF region for even L , this seems to be a *statistical* property of the system. See also (the end of) the Appendix and the Supplemental Material [38].

Besides the AF and FE oscillations following the curves separating the temperate and corresponding frozen regions there are also additional “higher-order” oscillations in $\delta\rho(c)$ that form intricate patterns in the temperate region that are barely visible in Fig. 10. To visualize these oscillations more clearly we truncate $\delta\rho(c)$ in the upper panel of Fig. 11 at 10% of the minimal and maximal values from the upper panel of Fig. 10. Even though the relative errors sometimes exceed the average value for very small $\delta\rho(c)$ the patterns exhibit a lot of structure, and cannot be attributed to random noise. These higher-order oscillations exhibit several saddle-point-like patterns around the center of the temperate region. The structure is similar for lower Δ ; we have chosen $\Delta = -1$ to get the largest temperate region. Some higher-order oscillations can be found in Fig. 7 of Ref. [29] for $\Delta = -10$.

The oscillations persist above the critical point. At $\Delta = -1/2$ one can see FE oscillations in Fig. 6 of Ref. [29]. Going deeper into the D phase the profiles of $\delta\rho(c)$ on the free-fermion line ($\Delta = 0$) and at the ice point ($\Delta = 1/2$) are shown in the lower panels of Fig. 11. At $\Delta = 0$ the FE oscillations are still clearly visible. Interestingly, even though the AF region has disappeared it leaves behind a “ghost” in the form of AF oscillations. Close inspection suggests there are higher-order oscillations too, with at least one saddle-point-like feature. At $\Delta = 1/2$ most structure of the temperate region is beyond the resolution of our data, yet one can still see weak FE oscillations as well as the tails of AF oscillations in the top-left and bottom-right corners of that panel.

V. SUMMARY AND OUTLOOK

In this work we have used Monte Carlo simulations to study the F model with DWBCs. Although a closed form for the partition function is analytically known for all system sizes, in practice it is particularly useful for the exact computation of certain observables for fairly small systems and to obtain the asymptotic form and its finite-size corrections. Simulations allow for the investigation of systems of moderate size to complement such analytic results as well as to study properties that are not (yet) understood from an analytic point of view.

We have given best estimates for the parameters in the first three subleading finite-size corrections to the energy derived from the asymptotic partition function in Eq. (5) at the critical point by fits to the average energies obtained from simulations. This tests the reliability of our simulations; they are precise enough to distinguish the different subleading corrections (Fig. 4). The best estimates for the parameters suggest that the first subleading correction is non-negligible in comparison to the leading correction even for macroscopically sized systems, with $L \sim 10^{21}$. We find $\alpha = 1.91 \pm 0.39$ for a previously unknown [47] parameter in the asymptotic expression (5) of the domain-wall partition function in the disordered regime found by Bleher and Fokin [21].

Following joint work with Duine and Barkema [3] we have further investigated the order parameter based on the staggered polarization P_0 , of which we gave a description in the framework of the quantum-inverse scattering method (QISM). From a theoretical point of view it would be interesting to explore whether it is possible to adapt Baxter’s work [37] to obtain an exact expression for P_0 in the case of domain walls, at least in the thermodynamic limit, but we have not done so in the present work. If P_0 is a true order parameter for the model’s IOPT, i.e., it is constant on one side of the critical temperature and smoothly starts to change at the phase transition, then the observable $d \ln P_0/d\beta$ must by definition have a divergence at the critical point for infinitely large systems. Using finite-size scaling, and extrapolating to the asymptotic case, we have found that $d \ln P_0/d\beta$ does indeed converge to a delta distribution (see Fig. 6), although it fails to give an accurate estimate for the (analytically known) temperature at which the phase transition occurs. Of course the DWBCs together with the ice rule make the system that we have investigated rather special; the observable proposed in Ref. [3] may still be useful for the investigation of other models exhibiting an IOPT. One could also try using the susceptibility of P_0 instead; most of its peaks lie outside our simulation range, though the peaks that are visible appear to have a comparable quality for finite-size scaling.

In addition to these global (spatially averaged) properties we have studied local properties of the system. The profiles of the c -vertex density $\rho(c)$ obtained for systems of size $L = 512$ at various temperatures with $\Delta \leq 1/2$ are shown in Fig. 7. In the antiferroelectric (AF) phase our simulations corroborate the coexistence of three spatially separated phases as found in Refs. [26,27], with a flat central region exhibiting frozen AF order surrounded by a disordered (D) “temperate” region and ferroelectrically (FE) ordered corners. Our data agree very well with the arctic curves conjectured by Colomo and Pronko [34] and Colomo, Pronko, and Zinn-Justin [35]. It would be desirable to have similar analytic expressions for the “antartic curve” separating the temperate and AF-frozen regions for $\Delta < -1$.

Regarding the structure inside the temperate region our simulations confirm the oscillations first found by Syljuåsen and Zvonarev [26] and recently recovered by Lyberg *et al.* [29]. Our findings agree with those works, reproducing the patterns visible there, and uncover interesting additional features. Each vertex density oscillates with the same dependence of the wavelength on the position along the diagonal (Fig. 8). Our data confirm the conjecture of [26], in accordance with Ref. [29], that these oscillations are finite-size effects: their wavelengths appear to grow sublinearly, roughly as $(0.67 \pm 0.06)L^{(0.553 \pm 0.016)}$, and their average amplitudes decrease with system size (Fig. 9). Our most detailed result regarding the structure of the temperate region are Figs. 10 and 11. Here we have chosen to focus on the density difference for the c -vertices since $\rho(c_{\pm})$ are in antiphase (cf. Fig. 8), so $\delta\rho(c) := \rho(c_-) - \rho(c_+)$ allows us to study the deviation of one type of vertex around its “average” without having to know an expression for the latter. We find several types of oscillations. The “AF” oscillations close to the AF-frozen region appear to be made up of checkerboards of c_{\pm} -vertices that (unlike the AF region in case of even L) survive thermal averaging for

even as well as odd L , and are opposite between neighboring oscillations. The “FE” oscillations near the FE-frozen region are dominated by the vertices constituting that frozen region; between these oscillations there is a surplus of the type of c -vertices favored by the DWBCs. In addition there appear to be weak “higher-order” oscillations in c_{\pm} -densities, forming various saddle-point-like patterns. The oscillations seem to grow weaker as Δ increases. Nevertheless the oscillations persist well into the D phase, with FE and AF oscillations remaining partially visible at $\Delta = 1/2$ (Fig. 11). A more quantitative understanding of these vertex-density oscillations and arrow correlations in the temperate region is desirable, both via simulations and through the analytic methods of Refs. [31,32,36], or [15]. In fact, similar finite-size oscillatory behavior is known to occur for the eigenvalue distributions in random-matrix models [61], see e.g. [62]; this might shed light on the oscillations at least for $\Delta = 0$; cf. Refs. [31,32].

In the near future we plan to report on phase coexistence, arctic-curve phenomena, and the structure of the D region for various other choices of boundary conditions; cf. Ref. [46]. Another interesting direction is the study the case of quantum-integrable “solid-on-solid” (SOS) models, with weights associated to the dynamical Yang-Baxter equation. The trigonometric SOS model is a one-parameter extension of the six-vertex model, and it would be interesting to understand the dependence of those phenomena on the additional “dynamical” or “height” parameter. It would also be very exciting if the theoretical and numerical investigations of the F model with domain walls would be complemented by experimental work as in, e.g., Ref. [39].

ACKNOWLEDGMENTS

We thank P. Zinn-Justin for bringing CFTP under our attention, G. Barkema and F. Colomo for feedback on earlier versions of this work, P. Bleher for correspondence, and C. Hagendorf, I. Lyberg, and K. Johansson for useful discussions. We also thank the two anonymous referees for their feedback. We are grateful to the Institute for Theoretical Physics at Utrecht University for the hospitality during the course of this work. J.L. gratefully acknowledges support from the Knut and Alice Wallenberg Foundation. This work is part of the D-ITP consortium, a program of the Netherlands Organisation for Scientific Research (NWO) that is funded by the Dutch Ministry of Education, Culture and Science (OCW).

APPENDIX: RELATING CONFIGURATIONS WITH OPPOSITE CHECKERBOARDS IN THE AF REGION

In this appendix we show that the F model has symmetries that can be used to sample the whole of phase space starting from any initial configuration obeying the ice rule and DWBCs. We should emphasize that the symmetries we have in mind are symmetries of the model, not of the individual configurations.

We start locally, with the symmetries of the F model at the level of individual vertices shown in Fig. 1. Such local symmetries must certainly preserve the lattice near the vertex, i.e., the vertex with its four surrounding edges, so we are led to the dihedral group D_4 of symmetries of the square. Concretely it contains rotations over multiples of $\pi/2$ as well as reflections

in the horizontal, vertical, and (anti)diagonal line through the vertex. These operations clearly preserve the ice rule. In fact, when the edges carry arrows there is one more thing we can do that is compatible with the ice rule: reversing all arrows, yielding an action of \mathbb{Z}_2 that commutes with the D_4 .

One can check the preceding operations change the vertex weights as follows:

$$\begin{aligned} \text{reflect } \updownarrow : & a_{\pm} \leftrightarrow b_{\pm}, \\ \text{reflect } \leftrightarrow : & a_{\pm} \leftrightarrow b_{\mp}, \\ \text{reflect } \nearrow : & a_{+} \leftrightarrow a_{-}, \quad c_{+} \leftrightarrow c_{-}, \\ \text{reflect } \searrow : & b_{+} \leftrightarrow b_{-}, \quad c_{+} \leftrightarrow c_{-}, \\ \text{rotate } \curvearrowright : & a_{\pm} \mapsto b_{\mp}, \quad b_{\pm} \mapsto a_{\pm}, \quad c_{+} \leftrightarrow c_{-}, \\ \text{reverse arrows} : & a_{+} \leftrightarrow a_{-}, \quad b_{+} \leftrightarrow b_{-}, \quad c_{+} \leftrightarrow c_{-}, \end{aligned}$$

where for each reflection we omit the two weights it preserves. Notice that, when using arrows along the edges to represent the microscopic degrees of freedom, the F model may be characterized as the special case of the six-vertex model for which the vertex weights are invariant under rotations over $\pi/2$, and that they are then further invariant under all of $D_4 \times \mathbb{Z}_2$.

At the global level $D_4 \times \mathbb{Z}_2$ acts on the configurations, where D_4 acts by symmetries of the $L \times L$ lattice if we would forget about the arrows. Not all of these global maps are allowed, though. Regarding the operations corresponding to D_4 the DWBCs are preserved only by a subgroup isomorphic to $\mathbb{Z}_2 \times \mathbb{Z}_2$ corresponding to rotation over π and reflection in the horizontal and vertical symmetry axes of the lattice. However, that the remaining operations in D_4 also preserve the DWBCs if we combine them with arrow reversal [63].

The next question is how these operations act at the level of configurations. Recall that there are two AF ground states, with opposite checkerboard patterns for the alternating c_{+} - and c_{-} -vertices constituting the AF region; let us call them “0” and “1.” Below the critical temperature ($\Delta < -1$) any configuration is closer (more similar) to one of these two ground states. Accordingly, the phase space decomposes into two parts, say, \mathcal{C}_i , with $i \in \mathcal{C}_i$ for $i = 0, 1$. (See also the Supplemental Material [38].) For sufficiently low temperatures (or Δ) and large enough L it costs a macroscopically large amount of energy to go from the energetically favorable part of \mathcal{C}_0 , i.e., configurations close enough to 0, to the corresponding part of \mathcal{C}_1 : the system is practically trapped in one of these parts. Since we start our Monte Carlo algorithm from one of the two AF ground states we thus expect to stay in the corresponding part of the phase space as the system thermalizes for $\Delta < -1$ and large enough L .

Now we return to the model’s symmetries. Consider the two AF ground states, 0 and 1. When L is even the four axes of reflection symmetry meet in the middle of the central face of the lattice, and it follows that the model’s symmetries fall into two classes:

$$\begin{aligned} \text{fixing } i : & \text{identity, } \curvearrowright, \nearrow^*, \searrow^*, \\ 0 \leftrightarrow 1 : & \curvearrowright^*, \curvearrowleft^*, \leftrightarrow, \updownarrow, \end{aligned} \tag{A1}$$

where “*” means combination with arrow reversal. More generally, (A1) indicates how the model’s global symmetries relate the \mathcal{C}_i .

Since for the F model these operations do not change the vertex weights, they preserve the energy of the configurations. Given any configuration we can act by the model's symmetries to generate further configurations of the same energy; we get up to eight configurations in this way, though it may be only four or two if the original configuration happened to possess some amount of symmetry. (One should really check for such symmetries of the original configuration to avoid

overcounting, but at high enough L we can skip this step as such symmetric configurations make up a negligible portion of the phase space.) Half of the configurations we get in this way lie in \mathcal{C}_0 and the other half in \mathcal{C}_1 . The upshot is that after having run the Monte Carlo simulation we can use the model's symmetries to sample the full phase space, even from simulations that correctly sample around one of the two ground states.

[1] F. Rys, *Helv. Phys. Acta* **36**, 537 (1963).
 [2] E. H. Lieb, *Phys. Rev. Lett.* **18**, 1046 (1967).
 [3] R. Keesman, J. Lamers, R. A. Duine, and G. T. Barkema, *J. Stat. Mech.* (2016) 093201.
 [4] To see that the ice rule is crucial here consider the eight-vertex model, where the ice rule is slightly relaxed. This model cannot be tackled with a straightforward Bethe-ansatz analysis, and its thermodynamics are insensitive to the choice of boundary conditions; cf. Ref. [46] below.
 [5] J. Lamers, *PoS Modave2014*, 001 (2014).
 [6] H. J. Brascamp, H. Kunz, and F. Y. Wu, *J. Math. Phys.* **14**, 1927 (1973).
 [7] V. Korepin and P. Zinn-Justin, *J. Phys. A: Math. Gen.* **33**, 7053 (2000).
 [8] P. Zinn-Justin, [arXiv:cond-mat/0205192](https://arxiv.org/abs/cond-mat/0205192) (2002).
 [9] S. K. Jain, V. Juričić, and G. T. Barkema, *Phys. Rev. B* **94**, 020102 (2016).
 [10] T. S. Tavares, G. A. P. Ribeiro, and V. E. Korepin, *J. Phys. A: Math. Theor.* **48**, 454004 (2015).
 [11] V. E. Korepin, *Commun. Math. Phys.* **86**, 391 (1982).
 [12] W. H. Mills, D. P. Robbins, and H. Rumsey, *J. Combin. Theory Ser. A* **34**, 340 (1983).
 [13] G. Kuperberg, *Inter. Math. Res. Notes* **1996**, 139 (1996).
 [14] D. Bressoud, *Proofs and Confirmations: The Story of the Alternating Sign Matrix Conjecture* (Cambridge University Press, Cambridge, 1999).
 [15] N. Allegra, J. Dubail, J.-M. Stéphan, and J. Viti, *J. Stat. Mech.* (2016) 053108.
 [16] I. Kostov, *J. Phys. A: Math. Theor.* **45**, 494018 (2012).
 [17] Y. Jiang, S. Komatsu, I. Kostov, and D. Serban, *J. Phys. A: Math. Theor.* **49**, 454003 (2016).
 [18] A. G. Izergin, *Sov. Phys. Dokl.* **32**, 878 (1987).
 [19] A. G. Izergin, D. A. Coker, and V. E. Korepin, *J. Phys. A: Math. Gen.* **25**, 4315 (1992).
 [20] P. Zinn-Justin, *Phys. Rev. E* **62**, 3411 (2000).
 [21] P. Bleher and V. Fokin, *Commun. Math. Phys.* **268**, 223 (2006).
 [22] P. Bleher and K. Liechty, *Commun. Math. Phys.* **286**, 777 (2009).
 [23] P. Bleher and T. Bothner, *Random Matrices: Theory Appl.* **01**, 1250012 (2012); [arXiv:1208.6276](https://arxiv.org/abs/1208.6276) [math-ph].
 [24] P. Bleher and K. Liechty, *Random Matrices and the Six-Vertex Model* (AMS, Providence, RI, 2013).
 [25] R. J. Baxter, *Exactly Solved Models in Statistical Mechanics* (Dover Publications, New York, 2007).
 [26] O. F. Syljuåsen and M. B. Zvonarev, *Phys. Rev. E* **70**, 016118 (2004).
 [27] D. Allison and N. Reshetikhin, *Ann. Inst. Fourier (Grenoble)* **55**, 1847 (2005).
 [28] L. F. Cugliandolo, G. Gonnella, and A. Pelizzola, *J. Stat. Mech.* (2015) P06008.
 [29] I. Lyberg, V. Korepin, and J. Viti, [arXiv:1612.06758](https://arxiv.org/abs/1612.06758) [cond-mat.stat-mech] (2016).
 [30] W. Jockusch, J. Propp, and P. Shor, [arXiv:math/9801068](https://arxiv.org/abs/math/9801068) [math.CO] (1998).
 [31] K. Johansson, *Ann. Prob.* **33**, 1 (2005).
 [32] P. L. Ferrari and H. Spohn, *J. Phys. A: Math. Gen.* **39**, 10297 (2006).
 [33] F. Colomo and A. G. Pronko, *SIAM J. Discrete Math.* **24**, 1558 (2010).
 [34] F. Colomo and A. G. Pronko, *J. Stat. Phys.* **138**, 662 (2010).
 [35] F. Colomo, A. G. Pronko, and P. Zinn-Justin, *J. Stat. Mech.* (2010) L03002.
 [36] F. Colomo and A. G. Pronko, *Commun. Math. Phys.* **339**, 699 (2015).
 [37] R. J. Baxter, *J. Stat. Phys.* **9**, 145 (1973).
 [38] See Supplemental Material at <http://link.aps.org/supplemental/10.1103/PhysRevE.95.052117> for an interactive Mathematica notebook that provides more detail on the relation between configurations through symmetries and on the checkerboards in the AF oscillations.
 [39] C. Nisoli, R. Moessner, and P. Schiffer, *Rev. Mod. Phys.* **85**, 1473 (2013).
 [40] We thank P. Henelius for making us aware of this.
 [41] E. H. Lieb and F. Y. Wu, in *Phase Transitions and Critical Phenomena* (Academic Press, London, 1972), p. 332.
 [42] E. H. Lieb, *Phys. Rev. Lett.* **19**, 108 (1967).
 [43] P. Bleher and K. Liechty, *J. Stat. Phys.* **134**, 463 (2009).
 [44] K. Eloranta, *J. Stat. Phys.* **96**, 1091 (1999).
 [45] Computations using quantum integrability for finite size are often done over \mathbb{C} , for which $a = \sinh(u + \eta)$, $b = \sinh u$, $c = \sinh \eta$ is another convenient parametrization. Setting $u = -\gamma - t$ and $\eta = 2\gamma + i\pi$ yields the AF parametrization in (2) up to a common sign; including a factor of i in front of γ and t gives that for D up to a common factor of i .
 [46] G. Kuperberg, *Ann. Math.* **156**, 835 (2002).
 [47] In fact, Ref. [24, Thm. 6.1.3] shows that $\alpha \geq 1$. Our value would mean that $b_1 = 0$ in the proof of that result. In principle it is possible to check this analytically, but the expression for b_1 is rather complicated. We thank P. Bleher for correspondence about this point.
 [48] Note that $R(s) = (\delta_{s/2} \otimes \delta_{-s/2})R(0)(\delta_{-s/2} \otimes \delta_{s/2})$ for $\delta_s := \exp(s\sigma^z/2)$ with σ^z the third Pauli matrix, and $R(0)$ the R matrix of the ordinary (zero-field) six-vertex model. By the ice rule one can rewrite $R(s) = (I \otimes \delta_{-s})R(0)(\delta_s \otimes I) = (\delta_s \otimes I)R(0)(\delta_{-s} \otimes I)$ with I the 2×2 identity matrix. Direct horizontal

and vertical fields would correspond to $(\delta_h \otimes \delta_v)R(0)(\delta_h \otimes \delta_v)$, which can be used to compute the direct polarization in a similar fashion.

- [49] The partition function for an $L \times L$ lattice with L even and PBCs (cf. Ref. [3]) is obtained by defining the staggered transfer matrix $t(s) := \text{tr}T(s) = A(s) + D(s)$, where $A(s)$ and $D(s)$ are similar to (12) but with both arrows pointing left and right, respectively. Then the partition function is $Z_L^{\text{PBC}}(s) = \text{tr}\{[t(-s)t(s)]^{L/2}\}$.
- [50] J. M. Maillet and J. Sanchez de Santos, in *L. D. Faddeev's Seminar on Mathematical Physics*, edited by M. Semenov-Tian-Shansky, Translations Series 2 (AMS, Providence, RI, 2000), Vol. 201, p. 137.
- [51] H. van Beijeren, *Phys. Rev. Lett.* **38**, 993 (1977).
- [52] J. G. Propp and D. B. Wilson, *Random Struct. Algor.* **9**, 223 (1996).
- [53] J. Propp and D. Wilson, in *Microsurveys in Discrete Probability*, edited by D. Aldous and J. Propp, Discrete Math. Theoret. Comput. Sci., Vol. 41 (AMS, Providence, RI, 1998), pp. 181–192.
- [54] J.-S. Wang, R. H. Swendsen, and R. Kotecký, *Phys. Rev. B* **42**, 2465 (1990).
- [55] G. T. Barkema and M. E. J. Newman, *Phys. Rev. E* **57**, 1155 (1998).
- [56] E. Marinari and G. Parisi, *Europhys. Lett.* **19**, 451 (1992).
- [57] J. P. Valleau and D. N. Card, *J. Chem. Phys.* **57**, 5457 (1972).
- [58] A. M. Ferrenberg and R. H. Swendsen, *Phys. Rev. Lett.* **63**, 1195 (1989).
- [59] M. Weigel and W. Janke, *J. Phys. A* **38**, 7067 (2005).
- [60] We thank I. Lyberg for bringing this to our attention.
- [61] We thank K. Johansson for pointing this out to us.
- [62] A. Edelman and M. La Croix, *Random Matrices: Theory Appl.* **04**, 1550021 (2015), arXiv:1410.7065 [math.PR].
- [63] Thus the full global symmetry group of the F model with DWBCs is a subgroup of $D_4 \times \mathbb{Z}_2$ isomorphic to D_4 . Recall that D_4 has a presentation in terms of two generators, r and s , subject to the relations $r^4 = s^2 = (sr)^2 = e$. Concretely, r acts by a rotation over $\pi/2$ while s acts by a reflection. Write g^* for the combination of $g \in D_4$ with arrow reversal. Then the subgroup of global symmetries is generated by r^* and s , where the latter acts by reflection in the horizontal or vertical axes; clearly $(r^*)^4 = s^2 = (sr^*)^2 = e$. See also (18).