




Status of Commissioning

and Experimental Issues for Early Physics in ATLAS



Christoph Amelung (CERN)
for the ATLAS Collaboration

Hadron Collider Physics Symposium
Elba, Italy, May 20–26, 2007

The ATLAS Collaboration

- **ATLAS:**

35 countries


164 institutions

1800 scientific authors



Albany, Alberta, NIKHEF Amsterdam, Ankara, LAPP Annecy, Argonne NL, Arizona, UT Arlington, Athens, NTU Athens, Baku, IFAE Barcelona, Belgrade, Bergen, Berkeley LBL and UC, HU Berlin, Bern, Birmingham, Bologna, Bonn, Boston, Brandeis, Bratislava/SAS Kosice, Brookhaven NL, Buenos Aires, Bucharest, Cambridge, Carleton, Casablanca/Rabat, CERN, Chinese Cluster, Chicago, Clermont-Ferrand, Columbia, NBI Copenhagen, Cosenza, AGH UST Cracow, IFJ PAN Cracow, DESY, Dortmund, TU Dresden, JINR Dubna, Duke, Frascati, Freiburg, Geneva, Genoa, Giessen, Glasgow, LPSC Grenoble, Technion Haifa, Hampton, Harvard, Heidelberg, Hiroshima, Hiroshima IT, Indiana, Innsbruck, Iowa SU, Irvine UC, Istanbul Bogazici, KEK, Kobe, Kyoto, Kyoto UE, Lancaster, UN La Plata, Lecce, Lisbon LIP, Liverpool, Ljubljana, QMW London, RHBNC London, UC London, Lund, UA Madrid, Mainz, Manchester, Mannheim, CPPM Marseille, Massachusetts, MIT, Melbourne, Michigan, Michigan SU, Milano, Minsk NAS, Minsk NCPHEP, Montreal, McGill Montreal, FIAN Moscow, ITP Moscow, MEPhI Moscow, MSU Moscow, Munich LMU, MPI Munich, Nagasaki IAS, Nagoya, Naples, New Mexico, New York, Nijmegen, BINP Novosibirsk, Ohio SU, Okayama, Oklahoma, Oklahoma SU, Oregon, LAL Orsay, Osaka, Oslo, Oxford, Paris VI and VII, Pavia, Pennsylvania, Pisa, Pittsburgh, CAS Prague, CU Prague, TU Prague, IHEP Protvino, Regina, Ritsumeikan, UFRJ Rio de Janeiro, Romel, Rome II, Rome III, Rutherford Appleton Laboratory, DAPNIA Saclay, Santa Cruz UC, Sheffield, Shinshu, Siegen, Simon Fraser Burnaby, SLAC, Southern Methodist Dallas, NPI Petersburg, Stockholm, KTH Stockholm, Stony Brook, Sydney, AS Taipei, Tbilisi, Tel Aviv, Thessaloniki, Tokyo ICEPP, Tokyo MU, Toronto, TRIUMF, Tsukuba, Tufts, Udine, Uppsala, Urbana UI, Valencia, UBC Vancouver, Victoria, Washington, Weizmann Rehovot, FH Wiener Neustadt, Wisconsin, Wuppertal, Yale, Yerevan


The ATLAS Construction Site



- **ATLAS cavern:**

92 m below ground, across the street from **CERN Meyrin site**

53 m long, 35 m high, 30 m wide
just large enough for the detector:
building a **“ship in a bottle”**



The ATLAS Detector for the LHC

- **ATLAS detector:**


diameter 25 m, length 46 m, mass 7,000 tons, 10^8 channels, 3,000 km cables

muon spectrometer

toroid magnets

tile calorimeter

liquid argon calorimeter



solenoid magnet

transition radiation tracker

silicon tracker

pixel detector

ATLAS Detector Commissioning

- Many activities in parallel:

- on surface:

assembly of sub-detectors
commissioning of components
connecting on-detector services

- in the pit:

installation of sub-detectors
commissioning of sub-detectors
connecting off-detector services

ATLAS has a very **tight installation schedule** – first priority is **sub-detector installation** in the pit, all **other activities** must happen “in the shadow” of this – including commissioning

- Commissioning:

from “**just installed**” to “**ready for physics**”

make the detector run: from **low-level** (finding dead/hot channels, mapping mistakes, cabling problems) to **high-level** (integration of sub-detectors into global ATLAS DAQ)

understand the detector: from **alignment and calibration** to debugging offline **reconstruction software** and **simulation**

constrained by **installation** (availability of other sub-detectors, e.g. as triggers) and connection of **services** (e.g. to control room): many **temporary ad-hoc solutions**

ATLAS Commissioning Organization

- **Structure:**

ATLAS Commissioning Coordinator
(Run Coordinator after LHC start-up)

sub-detector commissioning coordinators,
subsystem sub-sub-detector coordinators

- **Commissioning phases:**

- **Phase 1:** commissioning of individual sub-detectors in the pit

- **Phase 2:** integrating (eventually all) sub-detectors together into ATLAS

- **Phase 3:** global commissioning, ATLAS running with cosmics and halo
in addition, most sub-detectors also have one or several

- **Phase 0:** commissioning of sub-detectors or components on surface

- **Milestone weeks:**

most sub-detectors now in **phase 1** (typically quite advanced), interrupted sporadically by “milestone weeks”, bringing together an increasing number of sub-detectors for **phase 2** (eventually starting phase 3)



Detector Commissioning with Cosmics

- Cosmics are weird events:

limited angular spread – even more pronounced underground: most particles arriving in ATLAS have travelled most of the last 100 m in one of the shafts

particles do (typically) not pass **through the interaction point (IP)**: not the type of event which detector and reconstruction software were designed for

lazy approach: use only particles that do go through the IP, treat as two back-to-back particles


however **timing is wrong** ($t_{\text{up}} \neq t_{\text{down}}$), and event rate dramatically reduced

diligent approach: modify trigger/DAQ and reconstruction software such that they can cope with non-pointing tracks

however now you are testing and debugging a configuration and software that is **not the one you wanted to test**

more useful for barrel detectors than for endcaps (unless detector can be rotated)

“untypical” cosmic event in calorimeters →



Muon Spectrometer

- Muon precision chambers:



MDT (monitored drift tubes) for **tracking** (both barrel and endcap): 3 cm diameter, $4 \cdot 10^5$ channels, $80 \mu\text{m}$ resolution, chamber positions monitored by alignment system

- Barrel region:

RPC (resistive plate chambers) as **trigger**

3 layers (BI-inner, BM-middle, BO-outer) of chambers, **embedded** in toroid magnet

muon stations assembled from 1 MDT and 0/2/1 RPC chambers (BI/BM/BO)



Muon Spectrometer


- **Barrel installation/commissioning:**

completed stations tested in assembly hall on surface with cosmics

588 muon stations installed one by one in the toroid magnet ($\approx 4/\text{day}$), 99% complete

full commissioning directly after installation impossible as services (cables, gas) not available at that time; now catching up

many stations damaged (and repaired), due to ongoing heavy mechanical work in parallel, and extremely difficult access




Muon Spectrometer

- **Endcap region:**

2×4 wheels (EI-inner, EM-middle, EO-outer, EE-extra) of chambers, **in front of/behind** endcap toroid magnet

CSC (cathode strip chambers, EI wheel) replace MDT for **tracking** in small **high-rate region** around beam line

TGC (thin gap chambers, 3 layers in EM wheel, 1 in EI) as **trigger**




- **Endcap installation/ commissioning:**

for some wheels, chambers are **pre-assembled** and **commissioned on surface** in larger units: **sectors** (EM), entire **wheels** (EI)

30–50% installed and being commissioned

EI/EM/EO finished by end of 2007, **EE** not before 2009





Muon Spectrometer



- Muon Barrel triggers and reconstructs its first curved muons:

muons **triggered** by RPC chambers, **tracks reconstructed** by MDTs

barrel toroid magnet ramped up to **102% of nominal field**: 21 kA current ramped up in steps, without problems (smaller maximum currents tested on the previous days), also tested dumping



Muon Spectrometer



- **Optical alignment system:**

\approx 12,000 optical sensors (cameras) to continuously monitor chamber positions (to $40 \mu\text{m}$) while running

↑ chamber positions as reconstructed from alignment sensor measurements
check redundant sensor measurements for consistency, compare to survey


Calorimeters – LAr and Tiles

- **Electromagnetic calorimeter:**


Liquid-Argon calorimeter with presampler, $\Delta E/E = 10\% / \sqrt{E} \oplus 0.3\%$

barrel and endcap: **accordion-shaped electrodes**, lead absorber plates

forward: **tube electrodes** in a copper absorber matrix



Tilecal module




- **Hadronic calorimeter:**

barrel and extended barrel: **scintillator tile** calorimeter, steel absorber plates, $\Delta E/E = 45\% / \sqrt{E} \oplus 2\%$

endcap and forward: **Liquid Argon** calorimeter, **flat electrodes** with copper absorber plates (endcap) and **tube electrodes** in a tungsten alloy absorber matrix (forward)

LAr accordion shape



Calorimeters – LAr and Tiles

- **Installation and Commissioning:**

LAr barrel and two endcap calorimeters assembled on surface in cryostats (barrel sharing cryostat with solenoid magnet)

lowered into the pit, onto lower half of barrel/extended barrel tile calorimeters

upper half of tiles assembled around cryostat, then pushed into final position (barrel) or access position (endcaps)

barrel LAr and Tile calorimeters were the first detectors in the pit, most advanced in services connection and commissioning





Calorimeters – LAr and Tiles

- Barrel calorimeters most advanced in integration:

commissioning phase 2: routinely taking cosmic data every weekend, using the trigger/DAQ system set up during the previous milestone week (M2), exercising/debugging the system and many of the final components

including data storage, online monitoring, online event display, DCS, databases, ...

not yet the final system (→), but many components of it



phase 1 work in parallel: e.g. study **uniformity** of LAr calorimeter response as a function of η
 also studies of calibration, cross-talk, noise; adding endcaps

Inner Detector: Pixels, SCT, and TRT

- Pixel (vertex) detector:

Si pixels: $400 \times 50 \mu\text{m}^2$

3 barrel layers,
2 \times 3 endcap disks

$8 \cdot 10^7$ channels

- Silicon tracker (SCT):

Si strips: $80 \mu\text{m}$ pitch (stereo)

4 barrel layers, 2 \times 9 endcap disks

$6 \cdot 10^6$ channels



- Transition radiation tracker (TRT):

straw tubes: 4 mm diameter

in 16 m^3 volume, interleaved with radiator

$4 \cdot 10^5$ channels

≈ 35 hits per track, $150 \mu\text{m}$ resolution



Inner Detector – SCT and TRT



- Installation and commissioning:

in **clean room on surface**: SCT cylinders (B3, B4, B5) inserted into largest one (B6), complete **SCT barrel inserted into TRT barrel**

temporary connections of services, **extensive commissioning on surface**

SCT and TRT barrels are now **installed inside ATLAS calorimeters**, continuing commissioning in the pit

endcaps: SCT/TRT assembled, to be installed in ATLAS in May





Inner Detector – SCT and TRT


- Commissioning with cosmics:

combined commissioning of SCT and TRT: online event display of cosmic track in SCT and TRT barrels (on surface, using external scintillator trigger)

repeated in the pit with Tilecal as trigger



Inner Detector – SCT



- Efficiency, alignment, noise:


look for **dead/quiet/noisy** channels

determine hit **efficiency**

↑ exercise **alignment algorithms**,
extract mean/width of track **residuals**, compare to MC

← measure **noise occupancy**, look
for induced **extra noise**

same type of studies done for TRT, Pixels





Inner Detector – Pixels

- **Installation and Commissioning:**

in clean room on surface: **assembly** of pixel barrel and endcaps mostly done, now installing and testing **services**

ready for installation in ATLAS in June

first cosmic signal in the pixel endcaps → (time of pixel hit after scintillator trigger)



Selected Recent Problems

- **SCT evaporative cooling system:**

SCT (operated at -7°C) **cooling system** uses **heaters**: to raise the temperature of the exhaust fluid above the dew point of the cavern

a heater of the barrel system **overheated** in the pit, temperature rising to $\gg 200^{\circ}\text{C}$, **smoke** coming out – not prevented by the **interlocks**

could have been a major disaster if **SCT endcaps** already installed

problem being **investigated** by experts, now modifying architecture to buy time: heaters moved outwards, so that they can be accessed/installed later

- **LAr calorimeter low-voltage power supplies:**

passed acceptance test upon reception at CERN, but exhibited **alarming failure rate** when installed and running in the detector: no clear pattern observable

complete reverse engineering revealed ≈ 20 different **issues/problems/design flaws**: retrofitting ongoing

delivery schedule critical (require access to calorimeters)

some other sub-detectors are having (completely different) problems with **power supplies**, too




Endgame: Installation Schedule 2007

- If all goes well:

finish installing all sub-detector components before end of 2007


biggest/outermost (muon spectrometer endcaps) and smallest/innermost (pixel) detectors are last to be installed



Conclusions

- **Summary:**

the  installation is progressing, on track to be finished in 2007

the  commissioning is well underway, with most sub-detectors in an advanced state of their individual commissioning

barrel detectors typically more advanced than endcaps

one of the main themes for the rest of 2007 will be the integration of more and more sub-detectors to eventually form the  detector

several milestone weeks upcoming: next one (M3) planned for June, integrating calorimeters (already in M1/M2), SCT/TRT barrels, muon barrels/endcaps