



Quasi-planktonic behavior of foraging top marine predators

Alice Della Penna, Silvia De Monte, Élodie Kestenare, Christophe Guinet,
Francesco D'Ovidio

► **To cite this version:**

Alice Della Penna, Silvia De Monte, Élodie Kestenare, Christophe Guinet, Francesco D'Ovidio. Quasi-planktonic behavior of foraging top marine predators. *Scientific Reports*, Nature Publishing Group, 2015, 5, pp.18063. <10.1038/srep18063>. <hal-01272061>

HAL Id: hal-01272061

<http://hal.upmc.fr/hal-01272061>

Submitted on 10 Feb 2016

HAL is a multi-disciplinary open access archive for the deposit and dissemination of scientific research documents, whether they are published or not. The documents may come from teaching and research institutions in France or abroad, or from public or private research centers.

L'archive ouverte pluridisciplinaire **HAL**, est destinée au dépôt et à la diffusion de documents scientifiques de niveau recherche, publiés ou non, émanant des établissements d'enseignement et de recherche français ou étrangers, des laboratoires publics ou privés.



Distributed under a Creative Commons Attribution 4.0 International License

SCIENTIFIC REPORTS



OPEN

Quasi-planktonic behavior of foraging top marine predators

Alice Della Penna^{1,2,3}, Silvia De Monte⁴, Elodie Kestenare⁵, Christophe Guinet⁶ & Francesco d'Ovidio¹

Received: 08 May 2015

Accepted: 09 November 2015

Published: 15 December 2015

Monitoring marine top predators is fundamental for assessing the health and functioning of open ocean ecosystems. Although recently tracking observations have substantially increased, factors determining the horizontal exploration of the ocean by marine predators are still largely unknown, especially at the scale of behavioral switches (1–100 km, days-weeks). It is commonly assumed that the influence of water movement can be neglected for animals capable of swimming faster than the current. Here, we challenge this assumption by combining the use of biologging (GPS and accelerometry), satellite altimetry and *in-situ* oceanographic data (ADCP and drifting buoys) to investigate the effect of the mesoscale ocean dynamics on a marine predator, the southern elephant seal. A Lagrangian approach reveals that trajectories of elephant seals are characterized by quasi-planktonic bouts where the animals are horizontally drifting. These bouts correspond to periods of increased foraging effort, indicating that in the quasi-planktonic conditions energy is allocated to diving and chasing, rather than in horizontal search of favourable grounds. These results suggest that mesoscale features like eddies and fronts may act as a focal points for trophic interactions not only by bottom-up modulation of nutrient injection, but also by directly entraining horizontal displacements of the upper trophic levels.

Marine top predators play a key role in maintaining the health of open ocean ecosystems and their monitoring is fundamental for assessing the quality of the marine environment, in particular in the wake of a changing climate^{1,2}. Over the last two decades marine top predators have been the subject of numerous tracking programs^{3,4} aimed at identifying key habitats, e.g. foraging and breeding grounds^{5–11}, studying their relationship with oceanographic features^{12–20}, investigating their navigation capabilities^{21,22} and gathering information about their biotic and abiotic environment, notably on remote oceanic regions^{23–26}. The temporal and spatial resolution of these studies is rapidly improving, enabling the observation of not only large scale migrations, but also the fine scale (~1 km) features of foraging trips. This increasing spatiotemporal resolution and the use of accelerometers makes it now possible for the first time to investigate the behaviors that underpin the observed patterns of displacement, and to relate these patterns to the physical properties of the turbulent environment that marine predators experience.

Large predatory fish, marine mammals and swimming seabirds are classified as *nekton* - free-swimming animals - because they are able to swim at a speed that is several times larger than the strongest currents of the open ocean. In contrast, *plankton* - literally meaning “wanderer” or “drifter” - refers to organisms that are passively transported, typically because they have no autonomous capacity of motion, or this is too weak to overcome transport. Consistently with such a view, the mechanical effect of currents on the trajectories of marine predators is often neglected and the classification of their behaviors is typically performed by borrowing approaches from terrestrial ecology, where animal search for food occurs on a faster timescale than the temporal variability of the landscape.

However, both the “nekton” and “plankton” labels are used in a qualitative sense, as most drifting organisms have some propulsion capabilities, and the currents affect any free swimming organism by shifting its frame of reference. Although the swimming capabilities of planktonic organisms have received quite a lot of attention^{27–30}, only few studies have tackled explicitly the question of the extent to which ocean currents can determine the trajectories of large marine animals and have concluded that this effect can be generally neglected. Indeed, the fact

¹Sorbonne Universités, UPMC Univ Paris 06, UMR 7159, LOCEAN-IPSL CNRS/UPMC/IRD/MNH, F-75005, Paris, France. ²Univ Paris Diderot Cité, 5 Rue Thomas Mann, 75013 Paris, France. ³CSIRO-UTAS Quantitative Marine Science Program, IMAS, Private Bag 129, Hobart, Tasmania 7001, Australia. ⁴Ecole Normale Supérieure, Institut de Biologie de l'ENS (IBENS), UMR CNRS 8197 and INSERM U1024, 46 rue d'Ulm, F-75005 Paris, France. ⁵Laboratoire d'Etudes en Géophysique et Océanographie Spatiales (LEGOS), Université de Toulouse III (OMP) and IRD, Toulouse, France. ⁶Centre d'Etudes Biologiques de Chizé, 79360 Villiers-en-Bois, France. Correspondence and requests for materials should be addressed to A.D.P. (email: alice.dellapenna@gmail.com)




Figure 1. The data employed in this study refer to the Kerguelen region (white polygon), in the Indian Sector of the Southern Ocean (a). (b) The trajectories of the tagged elephant seals (white) overlapped with the bathymetry of the region. The red rectangle identifies the sub-region containing the trajectories of the drifting floats released during the KEOPS 2 campaign. Bathymetric data from ETOPO2 Global 2-Minute Gridded Elevation Data Volume E1 [U.S. Department of Commerce, National Oceanic and Atmospheric Administration, National Geophysical Data Center, 2001. 2-minute Gridded Global Relief Data (ETOPO2), access:8/30/2001].

that nektonic animals are able to overcome oceanic currents does not imply that their movement is not directly influenced. To our knowledge, horizontal currents have only been shown to offset the trajectories of sea-turtles, which not surprisingly are among the slowest nekton^{31–33}. Similarly, Lea *et al.*³⁴ identified a relationship between fur seal pups swimming speed and wind speeds during their initial dispersal in extreme wind events. Instead, the need for correcting tracked trajectories of fast swimmers, such as elephant seals or whale sharks, has been ruled out by comparison with satellite altimetry³⁵ and synthetic water parcels advected in numerical models³⁶.

Interestingly however, Campagna *et al.*³⁷ present a striking example of elephant seals whose long trajectories (>500 km) closely resemble that of a drifter released almost simultaneously in their proximity. Is this example merely anecdotal or should the common assumption be revised? This question is important in marine ecology because the assumption that a swimming behavior is not directly affected by the ocean currents stands at the core of the analysis of search behavior of fast swimming animals - the majority of tagged species. This assumption has enabled this field of research to borrow techniques from terrestrial ecology, and notably the classification of animal behavior based on the sinuosity of trajectories for the identification of foraging grounds. On the other hand, if currents had sizable effects on the displacement of a marine predator, then ocean circulation features - like eddies and fronts - may play an important role in structuring the ecosystem not only bottom-up, but at multiple levels of the food chain. Besides, being hotspots of primary production, they would entrain top marine consumers, and thus concentrate in the same locations different organisms and their trophic interactions.

Here, we aim at assessing the impact of ocean currents on one of the fastest marine predators for which high-resolution tracking is available: the southern elephant seal. Using a novel biologger, we analyse simultaneous tracking (GPS - Global Positioning System) and behavioral data (accelerometry) from female southern elephant seals, *Mirounga leonina*, from the Kerguelen Islands (Indian Sector of the Southern Ocean, see Fig. 1). Southern elephant seals are a model species to address our research aims. During their long-range foraging trips, these animals encounter different oceanic regimes, and in particular highly energetic features emerging between the Polar and the Sub-Antarctic fronts. Their size allows them to carry with minimal disturbance large bio-loggers with long-lasting batteries and multiple detectors, among which accelerometers that can provide a direct estimation of capture attempts independently of the trajectory analysis. The Kerguelen sub-population, the second largest in the world, is the subject of an ongoing decadal study in terms of demography^{38,39} and animal tracking^{14,40,41}.

Our study focuses on the scale at which switches in the patterns of foraging behavior of marine predators are observed (~10 km). In terms of ocean physics, this is the (sub-) mesoscale. This scale is also referred to as *ocean weather* because of the presence of eddies and frontal systems^{42–44} similar to meteorological systems. Such dynamical structures shape the distribution of chemico-physical tracers such as Sea Surface Temperature⁴⁵, biotic fields like Chlorophyll concentration^{46–50} and community composition⁵¹. Furthermore, mesoscale turbulence is a major determinant of the distribution of consumers as zooplankton⁵² and micronekton⁵³. Top predators such as whales¹³, squid⁵⁴, king penguins¹⁶, sea-turtles⁵⁵, frigatebirds^{15,20}, elephant seals³⁵, fur seals^{56,57} and albatrosses⁵⁸ have been observed to co-localise with mesoscale structures but how much these animals actively track these features and how much they are entrained by them is part of the open question which we address here. In this study we find that, in contrast to what is often assumed, all the analyzed trajectories are characterized by bouts that are largely dominated by the currents advection and we develop a Lagrangian method to quantify the contribution of horizontal oceanic currents to an animal trajectory.

Method

The elephant seals tracking dataset employed in this study consists of five post-breeding foraging trips collected between October 2010 and January 2012 (see Fig. 1). The elephant seals were tagged with GPS transmitters with a space-time resolution of 50 m and 20 minutes respectively. All animals in this study were cared for in accordance with the IPEV ethical and Polar Environment Committees guidelines. The experimental bio-logging protocol was approved by the IPEV ethical and Polar Environment Committees. A total of more than 20000 km and 300 days data were recorded, from single trips of 72 to 85 days in duration. The tracking data were filtered by removing the locations that would have implied seals velocities larger than 2.8 m/s according to the algorithm described in References^{5,14}. Seal velocities larger than this threshold are unrealistic and likely to be due to GPS errors. Individual seals were also equipped with accelerometers to detect rapid head movements that characterize prey capture attempts. Accelerometers allow the identification of prey captures with an accuracy of more than 80%^{5,59–61}. However, due to limited battery power, for the three longest trajectories we were only able to measure the rate of prey capture for the first part of the foraging trip (about half of the round trip, or ~2000 km). Both GPS transmitters and accelerometers have been observed not to interfere with marine mammal behavior^{60,62,63}. Following References^{31,32}, we define *tracking velocity* the velocity estimated by differentiating in time the GPS positions and *heading velocity* the tracking velocity minus the estimated velocity of the ocean currents. In practice, the tracking velocity corresponds to the speed of the animal in a fixed frame of reference, and the heading velocity to the component relative to the moving water parcel the animal belongs to.

Geostrophic currents were quantified through an altimetry multi-satellite global product (Delayed Time Maps of Absolute Dynamic Heights (DT-MADT)) developed by CNES/CLS Aviso (<http://www.aviso.oceanobs.com>). This product has temporal and spatial resolution of respectively 1 week and 1/3°⁶⁴. Regional versions of the product, one of which is corrected with wind-induced Ekman component at 15 m (the depth of the SVP - Surface Velocity Program- drifters' drogue), have been also used. A comparison between the Lagrangian diagnostic introduced in this study -the Quasi-Planktonicity Index, see later- computed using different remote sensing products is shown in the Supplementary Information. Although the findings of this study do not depend on the choice of specific altimetric products, the presented results are obtained by using geostrophic products, that better refer to the typical diving depths of elephant seals, as detailed in the discussion.

The altimetry-derived velocity field was used to evaluate the heading velocity³² and to compute the synthetic trajectories of virtual drifters. Simulated trajectories have been obtained by integrating the velocity field through a 4th order Runge-Kutta algorithm and allowed to compute two Lagrangian diagnostics: the Quasi-Planktonicity Index (QPI) -which we introduce in this paper- and the finite-size Lyapunov exponent (FSLE). This exponent is obtained by measuring the backward-in-time divergence of initially nearby particles and it is commonly used as an indicator of frontal activity and stirring intensity. Indeed, highest dominant FSLE values are associated to formerly distant water masses, whose confluence creates a transport front^{65,66}. Fronts identified as maxima (ridges) of FSLEs have a convergent dynamics transverse to them, so that passive particles - like plankton or drifting buoys - in their neighbourhood are attracted to the front and then advected along it. Following Reference 67 we refer to these fronts as attractive Lagrangian Coherent Structures.

The Lagrangian features of elephant seal trajectories were compared with those of 47 WOCE-SVP drifters (GDP - <http://www.aoml.noaa.gov/phod/dac/index.php>) released during the multidisciplinary cruise KEOPS 2 (November 2011). The cruise and the release of the drifters took place in a sector of the region explored by the elephant seals trajectories and during the same season when trajectories were recorded⁶⁸. Some examples of drifters trajectories are shown in the Supplementary Information (Fig. 1).

Because elephant seals are diving predators⁶⁹, we used more than 20 casts (see Supplementary Information for more details) of two RD Instrument 300 kHz lowered acoustic Doppler current profilers (LADCP, also from the KEOPS2 cruise) to relate the horizontal currents integrated over the average diving depth (500 m,⁶¹) with those of the upper layer (here approximated at 50 m) that we infer from altimetry.

Multivariate statistical analyses were performed using linear mixed effect models ("lmer" function in the R package⁷⁰) to relate the number of prey capture attempts -response variable (fitted with a Poisson distribution) -, to the standardised (centered and scaled) frontal activity (FSLE) and QPI - explanatory variables. Individual seal identity was included as a random effect to account for the individual variability.

Results

The comparison between the heading velocity of elephant seals and the accelerometry data (see Fig. 2) along trajectories shows that when foraging more intensively (with attempt capture rate deviation from the average larger than its standard deviation), the tracking velocity of the elephant seals is close to the geostrophic current measured in the same location (i.e. the heading velocity is small). As displayed in Fig. 2, 85% of the intensive foraging locations




Figure 2. Deviations from the individually-averaged attempt capture rate for different values of heading velocities. Different colors correspond to different individuals. 85% of attempt capture rate of intensive foraging (deviations larger than 300 event/day, above the red dashed line) correspond to of heading velocity below 2 km/h (blue circle).




Figure 3. Two examples of computation of the QPI (Quasi-Planktonicity Index) along the same individual's trajectory (blue line). Disks of simulated trajectories (red disks) are initialised around two locations along the trajectory of the elephant seal (blue squares). The simulated trajectories are the result of the only effect of the currents and the one that minimizes the distance from the elephant seal's one is used to compute the QPI. The QPI corresponds to the average distance between this trajectory (red lines) and the elephant seal's. In case (a) ($QPI = 7.8 \text{ km}$) the two trajectories resemble each other whereas in case (b) ($QPI = 46.1 \text{ km}$) they diverge.

correspond to heading velocities below 2 km/h and a significant ($p - \text{value} < 0.01$) negative correlation of -0.34 suggest a relation between heading velocity and foraging behavior.

Do the low values of heading velocity imply that elephant seals in intensive foraging activity are “locked” to a specific water parcel and horizontally transported within?

By only considering heading velocities, it is not possible to answer this question as the small values that the heading velocities have in these cases could lead to a large trajectory difference when integrated in time.

Therefore, in order to quantitatively associate horizontal passive movement to a predator's trajectory, we compare the animal's trajectory to that of real buoys and of virtual particles purely displaced by advection, obtained by integrating altimetry-derived currents in time. To this aim, we define a new Lagrangian diagnostic: the Quasi-Planktonicity Index (QPI). For each day along an elephant seals' trajectory, we initialize a synthetic passive tracer in a disk centered around the current animal's location and we simulate the motion of the particles contained within the disk forward in time for 4 days. We define as *shadow trajectory* the synthetic trajectory closest to the path the elephant seal actually takes in the following 4 days (see SI for the details about the definition of the distance and its computation). The value of the QPI is the mean distance between the observed and the shadow trajectories. In other words, the QPI measures the offset over a four day period between the animal trajectory and the trajectory of a virtual drifter released next to it at the starting position over a four day period.

Figure 3 displays two examples of the computation of the QPI along two different sectors of the same trajectory (in blue). The red patches represent the disk of initialized trajectories and their size takes into account of the uncertainty on the initial condition due to the error induced by altimetry resolution. The shadows trajectories are




Figure 4. Normalized distribution of values of QPI for buoyant drifters (red) and elephant seals (blue). The extent of the drifters' distribution suggests that values of QPI below the 20 km threshold refer to bouts of elephant seals' trajectories where they are considerably affected by the horizontal currents.

represented in red: in case a), corresponding to a QPI = 7.8 km, the shadow trajectory closely resembles that of elephant seal, whereas in case b), referring to a QPI = 46.1 km, the trajectory of the elephant seal appears strongly uncorrelated with that of the simulated tracer.

Cases such as that illustrated in Fig. 3a) account for on average more than 30% of the time along a foraging trajectory. The values of the QPI in these bouts are compatible with the trajectory being generated by passive advection. This is confirmed when we compare them to the values obtained by applying the same diagnostic to SVP (real) drifter trajectories. Figure 4 shows the distribution of the QPI computed for elephant seals and for 47 SVP drifters. The considerable overlap between the two distributions suggests that values of the QPI below the 20 km threshold refer to bouts of elephant seals' trajectories where the animals display horizontally passive, quasi-planktonic behavior. This result does not change quantitatively if different altimetry products are used, as detailed in the Supplementary Information, and even when the movement of SVP drifters are corrected for the wind-induced Ekman component, that affect the movement of SVP drifters.

When the trajectories are strongly affected by the horizontal dynamics, physical forcing acts as a major driver in the exploration of the horizontal space. As a consequence, animals are expected to be found more often on attractive transport structures induced by horizontal stirring. Attractive Lagrangian Coherent Structures (LCSS) can be identified by remote sensing as ridges of Finite-Size Lyapunov Exponent (FSLE)⁶⁶. A multivariate analysis through a linear mixed effects model (see Methods) reveals highly significant (p -values < 0.001) correlations between FSLE, the QPI and the rate of attempted prey capture (see Table S11). These results indicate that on transport fronts the tracked elephant seals are passively advected to a higher degree (they have smaller QPI) and forage more intensively.

Figure 5 shows a typical example of this correlation. The gray-scale image in the background refers to the FSLE (the lighter the color, the stronger the transport-induced front). The points along the elephant seal's trajectory are colored according to the QPI (Fig. 5a) and the attempt capture rate (Fig. 5b). As the capture rate increases, the QPI decreases (note that the color scales are reversed), meaning that the trajectory is more affected by the currents. This situation occurs in regions of high FSLE, indicating transport fronts, whereas outside of fronts there are no recognizable patterns in either of the two behavioral diagnostics.

These results are obtained by assuming that the geostrophic currents are representative of the ones experienced by diving elephant seals. This assumption is checked by using vertical profiles of horizontal velocities from ADCP: the correlation between the zonal and meridional components of the velocities at 50 m depth and the integral between 50 m and 500 m is significant in both cases with values over 0.7 ($r = 0.7$ and $r = 0.9$ for the zonal and the meridional components of the velocity field – p -values < 0.01), indicating that the surface currents provide reliable information on the horizontal advective drift experienced by the animals during their diving.

Discussion

The results of this study challenge the common assumption that fast swimming predators have horizontal displacements that are substantially independent of surface currents. Moreover, the distortion of the trajectory caused by horizontal transport appears to occur prominently where foraging is most intense, stressing the importance of taking water movement into account when analyzing animal displacements at the scale of tens of kms. Determining the correct repartition of efforts between active displacement and passive plankton-like behavior is a central requirement for the application to marine mammals of general frameworks such as Optimal Foraging Theory⁷¹. Such a theory, based on the hypothesis that animals invest a limited amount of energy between foraging-inefficient displacement and targeted local search for food, suggests that the optimal trajectory is composed by an alternation of long exploratory bouts and of clusters of localized movement known as area-restricted search (ARS). If a searcher's movement is embedded in a flowing medium, however, its trajectory is deformed by the currents. Moreover, such a deformation is not uniform, since it occurs to a different extent, depending on the animal's propulsion relative to the surrounding water. Instead of being characterized by short and localized displacements, hence, the intensive




Figure 5. Fronts, identified as FSLE ridges (gray scale background image in both (a) and (b), computed the day corresponding to the location marked as a purple star (02/12/2011)) correspond on average to lower QPI values (a) and higher attempt capture rates (b). Note that the colorscales are reversed to better highlight that lower QPI correspond to higher attempt capture rates. In most cases locations with low QPI correspond to high capture rate. However, cases excepting this trend (in this example the locations of longitude between 90–92.5°) suggest that elephant seals could present a quasi-planktonic behaviour in response to physical clue usually, but not always, associated to rich foraging grounds.

search in the vertical direction produces horizontal trajectories that are closer to the flow-induced movement of the animal's frame of reference, and can therefore being considerably stretched out. The Quasi-Planktonicity Index introduced in our study provides a criterion to measure the degree to which the trajectory of a tracked animal is the outcome of advection by the physical flow. The corresponding partition of elephant seals foraging trips supports the conclusion that would be drawn by optimal foraging theory: animals feed more intensively when their horizontal displacements are more passive.

Our results suggest that ARS algorithms used to detect intensive foraging areas of elephant seals may be misleading in the ocean, if the trajectories are not corrected for the effect of the currents. Indeed, in contrast to the terrestrial environment, ARS in the open ocean produce displacements that are localised in the reference frame of the water parcel which contains the animal, hence trajectories that are shadowed by passive drifters. Especially in energetic regions, like frontal systems, quasi-planktonic horizontal displacements may be comparable in length to the bouts resulting from active propulsion. Correcting the trajectories for the effect of the currents is expected to improve the sensitivity in detecting and classifying behaviours, and in particular those related to foraging activity. In this regard, we note that recent work by Cotté *et al.*⁷² highlights a strong association between transport fronts and the Kerguelen elephant seals' displacements, but surprisingly not with intensive foraging locations. A possible reason may be that the state space model approach used in that work was applied to the absolute displacement of the animals and not the one corrected for the effect of currents.

The partitioning of elephant seals foraging trips into quasi-planktonic bouts and active horizontal displacements supports optimal foraging theory: the possibility of exploring new foraging grounds is traded off for intensive foraging, which entails focusing on the local resources. This horizontal pattern is consistent with elephant seal diving behavior. When foraging intensively, elephant seals generally increase their diving angles and both the horizontal and vertical sinuosity of the local displacements⁵. As a consequence, when diving they reduce their active horizontal movements (Lebras, Y., personal communication), so that their change results in a horizontal displacement movement that is largely determined by the currents. Note also that because of the increased diving effort in foraging regions, the “quasi-planktonic” horizontal bouts do not necessarily corresponds to periods of reduced energy consumption. Energy is invested more in short-range activity (deep diving and hunting) rather than in large-scale horizontal displacement (commuting).

We choose to use the term “quasi-planktonic” to refer to cases where a nektonic animal's behavior, in our case intensive foraging, results in an increased vertical movement and a reduced horizontal displacements. This behavioral change makes the horizontal trajectory largely affected by oceanic currents.

In this study, we assume that the velocity field of geostrophic currents inferred from altimetry accounts for the horizontal displacement of the water surrounding the elephant seals. If this is probably a good assumption close to the surface, it may only explain part of the animals' behaviour, since elephant seals however move considerably in the vertical direction as well. They dive to an average depth of 300–500 m (and up to 2000 m)⁶¹ and spend more than 60% of their lifetime below 100 m depths⁷³. If geostrophic velocities are considered to be representative of the mixed layer⁷⁴, their ability to quantify horizontal displacements at depth is not the same in different regions of the ocean. In the Southern Ocean, where the mixed layer is considerably deep (~100 m⁷⁵), the vertical distribution of horizontal velocities suggests that geostrophic velocity can reliably represent that of the whole water column^{76,77}. We checked that this was the case in the region of our study by analyzing Acoustic Doppler Current Profiler (ADCP) velocities from the KEOPS 2 campaign and the results confirmed that the zonal and meridional components of the horizontal velocities at 50 m depth are significantly related to the integral between 50 m and 500 m.

The “quasi-planktonic” nature of intensive foraging bouts implies that transport structures can entrain animal trajectories. This observation agrees with the increasing number of studies on tracked marine predators, showing that they tend to co-occur with thermal and transport fronts⁷⁸. The common explanation for the localization of top predators over fronts is the bottom-up structuring effect of these transport features due to the local enrichment in nutrients entailed by vertical sub-mesoscale circulation⁷⁹. The consequent boost in the biomass of lower trophic levels is believed to attract free-swimming predators over fronts. Our results indicate that a second, top-down mechanism may also exist, by which frontal structures directly entrain the trajectories of actively foraging predators. Passive advection towards attractive frontal regions may cause an increased localization of predators in those areas, in spite of the relatively small portion of the ocean surface they occupy. It is still an open question whether this mechanism is sufficient to ensure an efficient identification of putative nutrient-rich spots, or if the observed distributions also require the guidance of a cue. A question however remains, on the existence of a cue able to initially guide predators towards the putative nutrient-rich spots, that represent a minority of the ocean extension. Some species of seabirds have been observed to respond to chemical cues of compound dimethyl sulfide (DMS), that accumulates in the air above productive ocean areas^{80,81}, but relatively little is known about potential physical or chemical cues followed by swimming predators. An alternative hypothesis is that seals moving within a global foraging area modify their behavior according to prey density, which is influenced by (sub-)mesoscale oceanographic structures. With our data it is not possible to address directly this question. However, we observed cases in which elephant seals exhibit quasi-planktonic behaviors without foraging intensively, suggesting that they may be not reacting to the density prey as a cue.

Conclusions

The term *planktonic* has been traditionally reserved to the lower levels of the trophic chain. However, we have shown that top predators, in spite of being capable of large scale active swimming, can also display a (horizontal) planktonic behavior, that we have called quasi-planktonic. This behavior is associated with intensive foraging, where elephant seals displace mostly in the vertical direction, so that the horizontal displacements follow their moving frame of reference. The entrainment by currents of nekton, as well as of plankton, suggests a mechanism which focuses trophic interactions on physical features which have an attractive dynamics transverse to them, - like eddies and fronts - in alternative (or in addition) to bottom up effects expected by nutrients injections and concentration^{79,82–84}.

Understanding how the behavior of individual predators is modulated by structures that vary on the spatiotemporal scale of tens of kilometers and of days - the (sub) mesoscale - is an essential step in linking marine predators ethology to conservation ecology, and lies at the heart of predicting large-scale patterns of displacement and the response of marine predators to climate change^{85–88}.

References

1. Camphuysen, C. J. *Top Predators in Marine Ecosystems: Their Role in Monitoring and Management* (Cambridge University Press, 2006).
2. Estes, J. A. *et al.* Trophic downgrading of planet earth. *Science* **333**, 301–306 (2011).
3. Hussey, N. E. *et al.* Aquatic animal telemetry: A panoramic window into the underwater world. *Science* **348**, 1255642 (2015).
4. Block, B. A., Costa, D. P., Boehlert, G. W. & Kochevar, R. E. Revealing pelagic habitat use: the tagging of pacific pelagics program. *Oceanol. Acta* **25**, 255–266 (2002).
5. Dragon, A.-C. *et al.* Horizontal and vertical movements as predictors of foraging success in a marine predator. *Marine Ecol. Prog. Ser.* **447**, 243–257 (2012).
6. Dragon, A.-C., Bar-Hen, A., Monestiez, P. & Guinet, C. Comparative analysis of methods for inferring successful foraging areas from argos and gps tracking data. *Marine Ecol. Prog. Ser.* **452**, 253–267 (2012).
7. Le Boeuf, B. *et al.* Foraging ecology of northern elephant seals. *Ecol. Monogr.* **70**, 353–382 (2000).
8. Block, B. A. *et al.* Tracking apex marine predator movements in a dynamic ocean. *Nature* **475**, 86–90 (2011).
9. Bestley, S., Gunn, J. S. & Hindell, M. A. Plasticity in vertical behaviour of migrating juvenile southern bluefin tuna (*thunnus maccoyii*) in relation to oceanography of the south indian ocean. *Fish Oceanogr.* **18**, 237–254 (2009).
10. Carlson, J., Ribera, M., Conrath, C., Heupel, M. & Burgess, G. Habitat use and movement patterns of bull sharks *carcharhinus leucas* determined using pop-up satellite archival tags. *J. Fish. Biol.* **77**, 661–675 (2010).
11. Bost, C. *et al.* Foraging habitat and food intake of satellite-tracked king penguins during the austral summer at Crozet archipelago. *Marine Ecol. Prog. Ser.* **150**, 21–33 (1997).
12. Bailleul, F. *et al.* Looking at the unseen: combining animal bio-logging and stable isotopes to reveal a shift in the ecological niche of a deep diving predator. *Ecography* **33**, 709–719 (2010).
13. Cotté, C. *et al.* Scale-dependent interactions of Mediterranean whales with marine dynamics. *Limnol. Oceanogr.* **56**, 219 (2011).
14. Dragon, A.-C., Monestiez, P., Bar-Hen, A. & Guinet, C. Linking foraging behaviour to physical oceanographic structures: Southern elephant seals and mesoscale eddies east of Kerguelen islands. *Progr. Oceanogr.* **87**, 61–71 (2010).
15. De Monte, S. *et al.* Frigatebird behaviour at the ocean-atmosphere interface: integrating animal behaviour with multi-satellite data. *J. R. Soc. Interface* **9**, 3351–3358 (2012).
16. Cotté, C., Park, Y.-H., Guinet, C. & Bost, C.-A. Movements of foraging king penguins through marine mesoscale eddies. *P. Roy. Soc. B-Biol. Sci.* **274**, 2385–2391 (2007).

17. Guinet, C. *et al.* Spatial distribution of foraging in female antarctic fur seals *arctocephalus gazella* in relation to oceanographic variables: a scale-dependent approach using geographic information systems. *Marine Ecol. Prog. Ser.* **219**, 251–264 (2001).
18. Biuw, M. *et al.* Variations in behavior and condition of a southern ocean top predator in relation to *in situ* oceanographic conditions. *P. Natl. Acad. Sci. USA* **104**, 13705–13710 (2007).
19. Hays, G. *et al.* Movements of migrating green turtles in relation to avhrr derived sea surface temperature. *Int. J. Remote Sens.* **22**, 1403–1411 (2001).
20. Kai, E. T. *et al.* Top marine predators track Lagrangian coherent structures. *P. Natl. Acad. Sci. USA* **106**, 8245–8250 (2009).
21. Åkesson, S. & Alerstam, T. Oceanic navigation: are there any feasible geomagnetic bi-coordinate combinations for albatrosses? *J. Avian Biol.* **29–4**, 618–625 (1998).
22. Flemming, J., Field, C., James, M., Jonsen, I. & Myers, R. How well can animals navigate? estimating the circle of confusion from tracking data. *Environmetrics* **17**, 351–362 (2006).
23. Charrassin, J.-B. *et al.* Southern ocean frontal structure and sea-ice formation rates revealed by elephant seals. *P. Natl. Acad. Sci. USA* **105**, 11634–11639 (2008).
24. Roquet, F., Park, Y.-H., Guinet, C., Bailleul, F. & Charrassin, J.-B. Observations of the fawn trough current over the Kerguelen plateau from instrumented elephant seals. *J. Marine Syst.* **78**, 377–393 (2009).
25. Padman, L. *et al.* Seals map bathymetry of the antarctic continental shelf. *Geophys. Res. Lett.* **37** (2010).
26. McMahon, C. R. *et al.* Animal-borne sensors successfully capture the real-time thermal properties of ocean basins. *Limnol. Oceanogr.-Meth.* **3**, 392–398 (2005).
27. Durham, W. M. *et al.* Turbulence drives microscale patches of motile phytoplankton. *Nat. Commun.* **4**, doi: 10.1038/ncomms3148 (2013).
28. Seuront, L., Brewer, M. C. & Strickler, J. R. Quantifying zooplankton swimming behavior: the question of scale. *Handbook of scaling methods in aquatic ecology: measurement, analysis, simulation*. CRC Press, Boca Raton 333, 359 (2004).
29. Vandromme, P. *et al.* Symbolic analysis of plankton swimming trajectories: case study of strobilidium sp.(protista) helical walking under various food conditions. *Zool. Stud.* **49**, 289–303 (2010).
30. Fossette, S. *et al.* Current-oriented swimming by jellyfish and its role in bloom maintenance. *Curr. Biol.* **25**, 342–347 (2015).
31. Gaspar, P. *et al.* Marine animal behaviour: neglecting ocean currents can lead us up the wrong track. *P. Roy. Soc. B-Biol. Sci.* **273**, 2697–2702 (2006).
32. Girard, C., Sudre, J., Benhamou, S., Roos, D. & Luschi, P. Homing in green turtles *chelonina mydas*: oceanic currents act as a constraint rather than as an information source. *Marine Ecol. Prog. Ser.* **322**, 281–289 (2006).
33. Luschi, P., Hays, G. C. & Papi, F. A review of long-distance movements by marine turtles, and the possible role of ocean currents. *Oikos* **103**, 293–302 (2003).
34. Lea, M.-A. *et al.* Extreme weather events influence dispersal of naive northern fur seals. *Biol. Lett.* **5**, 252–257 (2009).
35. Bailleul, F. *et al.* Mesoscale eddies as foraging area of a deep-diving predator, the southern elephant seal. *Marine Ecol. Prog. Ser.* **408**, 251–264 (2010).
36. Sleeman, J. C. *et al.* To go or not to go with the flow: environmental influences on whale shark movement patterns. *J. Exp. Mar. Biol. Ecol.* **390**, 84–98 (2010).
37. Campagna, C., Piola, A. R., Rosa Marin, M., Lewis, M. & Fernández, T. Southern elephant seal trajectories, fronts and eddies in the Brazil/Malvinas confluence. *Deep-Sea Res. I* **53**, 1907–1924 (2006).
38. Guinet, C., Jouventin, P. & Weimerskirch, H. Population changes, movements of southern elephant seals on crozet and kerguelen archipelagos in the last decades. *Polar Biol.* **12**, 349–356 (1992).
39. Guinet, C., Jouventin, P. & Weimerskirch, H. Recent population change of the southern elephant seal at Iles Crozet and Iles Kerguelen: the end of the decrease? *Antarct. Sci.* **11**, 193–197 (1999).
40. Bailleul, F. *et al.* Successful foraging zones of southern elephant seals from the kerguelen islands in relation to oceanographic conditions. *Phil. Trans. R. Soc. B* **362**, 2169–2181 (2007).
41. d'Ovidio, F., De Monte, S., Della Penna, A., Cotté, C. & Guinet, C. Ecological implications of eddy retention in the open ocean: a Lagrangian approach. *J. Phys. A* **46**, 254023–254044, doi: 10.1088/1751-8113/46/25/254023 (2013).
42. Belkin, I. M., Cornillon, P. C. & Sherman, K. Fronts in large marine ecosystems. *Prog. Oceanogr.* **81**, 223–236 (2009).
43. Shadden, S. C., Lekien, F. & Marsden, J. E. Definition and properties of Lagrangian coherent structures from finite-time Lyapunov exponents in two-dimensional aperiodic flows. *Phys. D* **212**, 271–304 (2005).
44. Shadden, S. C. *Lagrangian Coherent Structures, in Transport and Mixing in Laminar Flows: From Microfluidics to Oceanic Currents* (ed Grigoriev, R.). (Wiley-VCH Verlag GmbH Co. KGaA, Weinheim, Germany 2005).
45. Mahadevan, A. & Campbell, J. W. Biogeochemical patchiness at the sea surface. *Geophys. Res. Lett.* **29**, 4 (2002).
46. Strass, V. H. *et al.* Mesoscale frontal dynamics: shaping the environment of primary production in the antarctic circumpolar current. *Deep-Sea Res. II* **49**, 3735–3769 (2002).
47. Lévy, M. *et al.* Large-scale impacts of submesoscale dynamics on phytoplankton: Local and remote effects. *Ocean Model.* **43**, 77–93 (2012).
48. Abraham, E. R. The generation of plankton patchiness by turbulent stirring. *Nature* **391**, 577–580 (1998).
49. Martin, A. P. Phytoplankton patchiness: the role of lateral stirring and mixing. *Prog. Oceanogr.* **57**, 125–174 (2003).
50. Lehahn, Y., d'Ovidio, F., Lévy, M. & Heifetz, E. Stirring of the northeast atlantic spring bloom: A lagrangian analysis based on multisatellite data. *J. Geophys. Res.* **112**, 15 (2007).
51. d'Ovidio, F., Monte, S. D., Alvain, S., Dandonneau, Y. & Lévy, M. Fluid dynamical niches of phytoplankton types. *Proc. Natl. Acad. Sci. USA* **107**, 18366–18370 (2010).
52. Labat, J.-P. *et al.* Mesoscale distribution of zooplankton biomass in the northeast atlantic ocean determined with an optical plankton counter: Relationships with environmental structures. *Deep-Sea Res. I* **56**, 1742–1756 (2009).
53. Sabarros, P. S., Mnard, F., Lvnez, J., TewKai, E. & TERNON, J. Mesoscale eddies influence distribution and aggregation patterns of micronekton in the mozambique channel. *Mar. Ecol. Prog. Ser.* **395**, 101–107 (2009).
54. Waluda, C. M., Rodhouse, P. G., Trathan, P. N. & Pierce, G. J. Remotely sensed mesoscale oceanography and the distribution of illex argentinus in the South Atlantic. *Fish. Oceanogr.* **10**, 207–216 (2001).
55. Polovina, J. *et al.* The kuroshio extension bifurcation region: A pelagic hotspot for juvenile loggerhead sea turtles. *Deep-Sea Res. II* **53**, 326–339 (2006).
56. Nordstrom, C. A., Battaile, B. C., Cotté, C. & Trites, A. W. Foraging habitats of lactating northern fur seals are structured by thermocline depths and submesoscale fronts in the eastern Bering Sea. *Deep-Sea Res. II* **88**, 78–96 (2013).
57. Sterling, J. T. *et al.* The sun, moon, wind, and biological imperative—shaping contrasting wintertime migration and foraging strategies of adult male and female northern fur seals (*callorhinus ursinus*). *Plos One* **9**, doi: 10.1371/journal.pone.0093068 (2014).
58. Nel, D. C. *et al.* Exploitation of mesoscale oceanographic features by grey-headed albatross *thalassarche chrysostoma* in the Southern Indian Ocean. *Mar. Ecol. Prog. Ser.* **217**, 15–26 (2001).
59. Viviant, M., Trites, A. W., Rosen, D. A., Monestiez, P. & Guinet, C. Prey capture attempts can be detected in steller sea lions and other marine predators using accelerometers. *Polar Biol.* **33**, 713–719 (2010).
60. Gallon, S. *et al.* Identifying foraging events in deep diving southern elephant seals, *mirounga leonina*, using acceleration data loggers. *Deep-Sea Res. II* **88–89**, 14–22 (2012).

61. Guinet, C. *et al.* Southern elephant seal foraging success in relation to temperature and light conditions: insight on their prey distribution. *Mar. Ecol. Prog. Ser.* **499**, 285–301 (2014).
62. McMahon, C. R., Field, I. C., Bradshaw, C. J., White, G. C. & Hindell, M. A. Tracking and data-logging devices attached to elephant seals do not affect individual mass gain or survival. *J. Exp. Mar. Biol. Ecol.* **360**, 71–77 (2008).
63. Wilson, R. P. & McMahon, C. R. Measuring devices on wild animals: what constitutes acceptable practice? *Front. Ecol. Environ.* **4**, 147–154 (2006).
64. *Ssalto/Duacs User Handbook: (M)SLA and (M)ADT Near-Real Time and Delayed Time Products* (SALP-MU-P-EA-21065-CLS 2010).
65. d'Ovidio, F., Isern-Fontanet, J., López, C., Hernández-García, E. & García-Ladona, E. Comparison between Eulerian diagnostics and finite-size Lyapunov exponents computed from altimetry in the Algerian basin. *Deep-Sea Res.* **156**, 15–31 (2009).
66. d'Ovidio, F., Fernández, V., Hernández-García, E. & López, C. Mixing structures in the mediterranean sea from finite-size lyapunov exponents. *Geophys. Res. Lett.* **31**, 17203 (2004).
67. Haller, G. & Yuan, G. Lagrangian coherent structures and mixing in two-dimensional turbulence. *Phys. D* **147**, 352–370 (2000).
68. Zhou, M. *et al.* Surface currents and upwelling in Kerguelen Plateau regions. *BGD* **11**, 6845–6876 (2014).
69. Hindell, M., Slip, D. & Burton, H. The diving behavior of adult male and female southern elephant seals, mirounga-leonina (pinnipedia, phocidae). *Aust. J. Zool.* **39**, 595–619 (1991).
70. Laird, N. M. *et al.* Random-effects models for longitudinal data: A language and environment for statistical computing *Biometrics* **38**, 963–974 (1982).
71. Hengeveld, G. M. *Moving to eat: animal foraging movements in a heterogeneous environment* (Wageningen University 2007).
72. Cotté, C., d'Ovidio, F., Dragon, A.-C., Guinet, C. & Marina, L. Flexible preference of elephant seals for distinct mesoscale features within the antarctic circumpolar current. **131**, 46–85 *Prog. Oceanogr.* (2014).
73. McIntyre, T. *et al.* A lifetime at depth: vertical distribution of southern elephant seals in the water column. *Polar Biol.* **33**, 1037–1048 (2010).
74. Dong, S., Sprintall, J., Gille, S. T. & Lynney, T. Southern ocean mixed-layer depth from argo float profiles. *J. Geophys. Res.* **113**, doi: 10.1029/2006JC004051.10.1029/2006JC004051 (2008).
75. Sallée, J., Speer, K. & Rintoul, S. Zonally asymmetric response of the southern ocean mixed-layer depth to the Southern Annular Mode. *Nat. Geosci.* **3**, 273–279 (2010).
76. Wunsch, C. The vertical partition of oceanic horizontal kinetic energy. *J. Phys. Oceanogr.* **27**, 1770–1794 (1997).
77. Vivier, F., Park, Y.-H., Sekma, H. & Le Sommer, J. Variability of the antarctic circumpolar current transport through the fawn trough, kerguelen plateau. *Deep-Sea Res. II* **114**, 12–26 (2014).
78. Bost, C. A. *et al.* The importance of oceanographic fronts to marine birds and mammals of the southern oceans. *J. Marine Syst.* **78**, 363–376 (2009).
79. Lévy, M., Ferrari, R., Franks, P. J. S., Martin, A. P. & Rivière, P. Bringing physics to life at the submesoscale. *Geophys. Res. Lett.* **39**, doi: 10.1029/2012GL052756 (2012).
80. Nevitt, G. A., Veit, R. R. & Kareiva, P. Dimethyl sulphide as a foraging cue for antarctic procellariiform seabirds. *Nature* **376**, 680–682 (2002).
81. Nevitt, G. A. & Bonadonna, F. Sensitivity to dimethyl sulphide suggests a mechanism for olfactory navigation by seabirds. *Biol. Lett.* **1**, 303–305 (2005).
82. Godø, O. R. *et al.* Mesoscale eddies are oases for higher trophic marine life. *PLOS ONE* **7**, e30161 (2012).
83. Boero, F. The future of the Mediterranean sea ecosystem: towards a different tomorrow. *Rend. Lincei Sci.* **26**, 3–12 (2014).
84. McGillicuddy, D. J. *et al.* Eddy/wind interactions stimulate extraordinary mid-ocean plankton blooms. *Science* **316**, 1021–1026 (2007).
85. Di Lorenzo, E. & Ohman, M. D. A double-integration hypothesis to explain ocean ecosystem response to climate forcing. *Proc. Natl. Acad. Sci. USA* **110**, 2496–2499 (2013).
86. Hoegh-Guldberg, O. & Bruno, J. F. The impact of climate change on the world's marine ecosystems. *Science* **328**, 1523–1528 (2010).
87. Fraser, W. R. & Hofmann, E. E. A predator's perspective on causal links between climate change, physical forcing and ecosystem. *Mar. Ecol. Prog. Ser.* **265**, 1–15 (2003).
88. Lea, M.-A. *et al.* Impacts of climatic anomalies on provisioning strategies of a southern ocean predator. *Mar. Ecol. Prog. Ser.* **310**, 77–94 (2006).

Acknowledgements

The altimeter products were produced by Ssalto/Duacs and distributed by Aviso with support from Cnes. The authors would also like to acknowledge AVISO/CLS and the Global Drifter Program/NOAA/AOML, Miami, Florida both the Drifter Operations Center and Data Assembly Centers and Météofrance for arranging drifter deployments and data assembly, quality control and distribution of the data. This study is part the national research program no. 109, H. Weimerskirch and the observatory Mammifères Explorateurs du Milieu Océanique (MEMO SOERE CTD 02) supported by the French Polar Institute (Institut Paul Emile Victor, IPEV), the ANR: MyctO-3D-MAP, SVSE 7 2011 and the CNES-TOSCA program (Éléphants de mer océanographes and ALTIMECO). CG and ADP thank respectively the Total Foundation and the Fondation Bettencourt-Schueller (through the program Frontières du Vivant) for their financial support. SDM acknowledges support of the CNRS-PSL Eco-Evo-Devo program “Pépinière Interdisciplinaire”. The authors wish to thank the Kerguelen fieldworkers (in particular N.El Shaby, J.-B. Pons and G.Bessigneul), Y. Lebras, C. Cotté, J. Garcia-Vaquet, B. Picard, T. Trull, A.C. Dragon and R. Bell. The authors wish also to thank M.A. Lea for helping reviewing the paper.

Author Contributions

A.D.P. designed the experiment, performed the research, analysed the data and wrote the paper. S.D.M. designed the experiment, performed the research, wrote the paper. E.K. analysed the data. C.G. designed the experiment, performed the research, wrote the paper. F.D. designed the experiment, performed the research, analysed the data, wrote the paper.

Additional Information

Supplementary information accompanies this paper at <http://www.nature.com/srep>

Competing financial interests: The authors declare no competing financial interests.

How to cite this article: Della Penna, A. *et al.* Quasi-planktonic behavior of foraging top marine predators. *Sci. Rep.* **5**, 18063; doi: 10.1038/srep18063 (2015).



This work is licensed under a Creative Commons Attribution 4.0 International License. The images or other third party material in this article are included in the article's Creative Commons license, unless indicated otherwise in the credit line; if the material is not included under the Creative Commons license, users will need to obtain permission from the license holder to reproduce the material. To view a copy of this license, visit <http://creativecommons.org/licenses/by/4.0/>