

1896

## Specifications for rebuilding Avenue, Court-Yard and Walks from Mc Cusker Bros. to Ogden Goelet

McCusker Bros.

Ernest W. Bowditch

Follow this and additional works at: <http://digitalcommons.salve.edu/ochre-court>

---

### Recommended Citation

McCusker Bros. and Bowditch, Ernest W., "Specifications for rebuilding Avenue, Court-Yard and Walks from Mc Cusker Bros. to Ogden Goelet" (1896). *Series 1. Ochre Court, Newport, RI, 1892-1897*. Book 265.  
<http://digitalcommons.salve.edu/ochre-court/265>

This Book is brought to you for free and open access by the Goelet Family Papers at Digital Commons @ Salve Regina. It has been accepted for inclusion in Series 1. Ochre Court, Newport, RI, 1892-1897 by an authorized administrator of Digital Commons @ Salve Regina. For more information, please contact [digitalcommons@salve.edu](mailto:digitalcommons@salve.edu).

S P E C I F I C A T I O N S

For re-building present Front Avenue, Court-yard, Back Avenue, and Walks at the sides of avenues, on the estate of Mr. Ogden Goelet, at Newport, R. I., under the Superintendence of Ernest W. Bowditch, Engineer:

..... March 16th, 1896.....

Avenue,  
Court-Yard,  
and Walks.

From the present Avenue, Court-Yard, and Walks, take off the present inferior material to the necessary depths, to be decided by the Engineer-in-charge, and cart it to the Kitchen Garden; then replace this material with a proper amount of the best Broken Stone of assorted sizes, to bring the avenues &c. to their proper grade, the stone being no larger than can pass through a one (1) inch ring; the top to be finished with not more than one (1) inch of Crusher Dust:

The entire avenues and Walks are to be thoroughly wetted down and rolled with a two ton (4000 lbs.) roller, or a Clay Puddle Roller of similar weight, until perfectly hard and of perfect shape.

The Contractor is to give his personal attention and direction to the work; he is to furnish all materials, labor, teams, tools, and utensils necessary for completing the work. The contractor is not to sub-let the work or any portion of it under any consideration without written permission from the Engineer:

Upon its completion, the entire work will be measured up by the Engineer-in-charge, upon the

Following basis:

Removing material from present avenue, &c.....	60¢	per cu. yd.
.....		per cu. yd.
Macadam, (assorted sizes).....	\$3.50	" " "
Crusher Dust.....	\$4.50	" " "
Two ton roller.....	\$7.00	" day.
Watering Cart.....	\$7.00	" "

The foregoing prices are to include all labor of every description.

*McLusker Bros*

1896  
Specifications  
by  
Contract  
M<sup>rs</sup> Cusker Bros,