

Crossing Numbers of Beyond-Planar Graphs Revisited

Citation for published version (APA):

van Beusekom, N., Parada, I., & Speckmann, B. (2022). Crossing Numbers of Beyond-Planar Graphs Revisited. *Journal of Graph Algorithms and Applications*, 26(1), 149-170. <https://doi.org/10.7155/jgaa.00586>

Document license:

CC BY

DOI:

[10.7155/jgaa.00586](https://doi.org/10.7155/jgaa.00586)

Document status and date:

Published: 01/06/2022

Document Version:

Publisher's PDF, also known as Version of Record (includes final page, issue and volume numbers)

Please check the document version of this publication:

- A submitted manuscript is the version of the article upon submission and before peer-review. There can be important differences between the submitted version and the official published version of record. People interested in the research are advised to contact the author for the final version of the publication, or visit the DOI to the publisher's website.
- The final author version and the galley proof are versions of the publication after peer review.
- The final published version features the final layout of the paper including the volume, issue and page numbers.

[Link to publication](#)

General rights

Copyright and moral rights for the publications made accessible in the public portal are retained by the authors and/or other copyright owners and it is a condition of accessing publications that users recognise and abide by the legal requirements associated with these rights.

- Users may download and print one copy of any publication from the public portal for the purpose of private study or research.
- You may not further distribute the material or use it for any profit-making activity or commercial gain
- You may freely distribute the URL identifying the publication in the public portal.

If the publication is distributed under the terms of Article 25fa of the Dutch Copyright Act, indicated by the "Taverne" license above, please follow below link for the End User Agreement:


www.tue.nl/taverne

Take down policy

If you believe that this document breaches copyright please contact us at:

openaccess@tue.nl

providing details and we will investigate your claim.



Crossing Numbers of Beyond-Planar Graphs Revisited

Nathan van Beusekom¹ Irene Parada² Bettina Speckmann¹

¹TU Eindhoven, the Netherlands

²Technical University of Denmark

Submitted: October 2021 Accepted: April 2022 Final: April 2022

Published: June 2022

Article type: Regular paper

Communicated by: A. Symvonis

Abstract. Graph drawing beyond planarity focuses on drawings of high visual quality for non-planar graphs which are characterized by certain forbidden (edge) crossing configurations. A natural criterion for the quality of a drawing is the number of edge crossings. The question then arises whether beyond-planar drawings have a significantly larger crossing number than unrestricted drawings. Chimani et al. [GD'19] gave bounds for the ratio between the crossing number of three classes of beyond-planar graphs and the unrestricted crossing number. In this paper we extend their results to the main currently known classes of beyond-planar graphs characterized by forbidden edge configurations and answer several of their open questions.

1 Introduction

A central topic in graph drawing are high quality drawings which are not necessarily planar. A natural criterion for the quality of a drawing is the number of edge crossings. While empirical studies suggest that the number of crossings is not the only factor that influences human understanding of a drawing, it is nevertheless one of the most relevant aesthetic indicators [15, 17, 18, 24]. However, it is NP-hard to compute the minimum number of crossings of a graph G across all possible drawings of G [13]. This minimum number of crossings is also referred to as the *crossing number* of G , denoted by $\text{cr}(G)$. Meaningful upper and lower bounds, as well as heuristic, approximation, and parameterized algorithms, have hence been a major focus [7].

Drawing edges as straight-line segments arguably simplifies any drawing. One classic variant is hence the *rectilinear crossing number* $\overline{\text{cr}}(G)$ of a graph G , that is, the minimum number of crossings across all straight-line drawings of G . Clearly $\text{cr}(G) \leq \overline{\text{cr}}(G)$ for any graph G . The straight-line restriction increases the crossing number arbitrarily: Bienstock and Dean [6] showed that for every k there exists a graph G such that $\text{cr}(G) = 4$ and $\overline{\text{cr}}(G) = k$. On the other hand, if $G = (V, E)$

E-mail addresses: n.a.c.v.beusekom@tue.nl (Nathan van Beusekom) irmde@dtu.dk (Irene Parada) b.speckmann@tue.nl (Bettina Speckmann)













This work is licensed under the terms of the [CC-BY](https://creativecommons.org/licenses/by/4.0/) license.

is a graph with maximum degree Δ then $\overline{\text{cr}}(G) = O(\Delta \cdot \text{cr}^2(G))$ [5, 21] and when $|E| \geq 4|V|$ this bound can be improved to $\overline{\text{cr}}(G) = O(\Delta \cdot \text{cr}(G) \cdot \log \text{cr}(G))$; see Schaefer's book [20] on crossing numbers. Computing $\overline{\text{cr}}(G)$ is also NP-hard (actually, it is $\exists\mathbb{R}$ -complete [4, 19]) but in polynomial time it can be approximated to $\overline{\text{cr}}(G) + o(n^4)$ [12].

In recent years there has been particular interest in drawings of *beyond-planar* graphs, which

Table 1: Bounds for the supremum $\varrho_{\mathcal{F}}$ of the ratio between crossing numbers. For our upper bounds we assume the drawings to be *simple*, that is, two edges share at most one point.

Family \mathcal{F}	Forbidden Configurations	Lower	Upper
k -planar	An edge crossed more than k times 	$\Omega(n/k)$ (Section 2)	$O(k\sqrt{kn})$ (Section 2)
k -quasi-planar	k pairwise crossing edges 	$\Omega(n/k^3)$ [9]	$f(k)n^2 \log^2 n$ [9]
Fan-planar	Two independent edges crossing a third or two adjacent edges crossing another edge from different "sides" 	$\Omega(n)$ [9]	$O(n^2)$ [9]
(k, l) -grid-free	Set of k edges such that each edge crosses each edge from a set of l edges. 	$\Omega\left(\frac{n}{kl(k+l)}\right)$ (Section 3.1)	$g(k, l)n^2$ (Section 3.1)
k -gap-planar	More than k crossings mapped to an edge in an optimal mapping 	$\Omega(n/k^3)$ (Section 3.2)	$O(k\sqrt{kn})$ (Section 3.2)
Skewness- k	Set of crossings not covered by at most k edges 	$\Omega(n/k)$ (Section 4.1)	$O(kn + k^2)$ (Section 4.1)
k -apex	Set of crossings not covered by at most k vertices 	$\Omega(n/k)$ (Section 4.2)	$O(k^2n^2 + k^4)$ (Section 4.2)
Planarly connected	Two crossing edges that do not have two of their endpoint connected by a crossing-free edge 	$\Omega(n^2)$ (Section 5.1)	$O(n^2)$ (Section 5.1)
k -fan-crossing-free	An edge that crosses k adjacent edges 	$\Omega(n^2/k^3)$ (Section 5.2)	$O(k^2n^2)$ (Section 5.2)
Straight-line RAC	Two edges crossing at an angle $< \frac{\pi}{2}$ 	$\Omega(n^2)$ (Section 5.3)	$O(n^2)$ (Section 5.3)

are characterized by certain forbidden crossing configurations of the edges; see the recent survey by Didimo *et al.* [11] and the recent book by Hong and Tokuyama [14]. Table 1 provides a summary of the definitions of beyond-planar graph classes relevant for this paper.

We study the relation between the crossing number restricted to beyond-planar drawings, and the (unrestricted) crossing number. The *restricted crossing number* $cr_{\mathcal{F}}(G)$ of a graph G is the minimum number of crossings required to draw G such that the drawing satisfies the restrictions imposed by the beyond-planar family \mathcal{F} . For a beyond-planar family \mathcal{F} , the *crossing ratio* $\varrho_{\mathcal{F}}$ is defined as $\varrho_{\mathcal{F}} = \sup_{G \in \mathcal{F}} cr_{\mathcal{F}}(G)/cr(G)$, that is, the supremum over all graphs in \mathcal{F} of the ratio between the restricted crossing number and the (unrestricted) crossing number.

Very recently, Urschel and Wellens [23] studied a related concept specifically for k -planar graphs. The *local crossing number* $lcr(\Gamma)$ of a drawing Γ of graph G is the maximum number of crossings per edge. Correspondingly, the local crossing number $lcr(G)$ of G is the minimum over all possible drawings of G . Hence a graph G is k -planar if its local crossing number is k . Urschel and Wellens aim to find drawings that simultaneously minimize the crossing number and the local crossing number, that is, they aim to minimize $\frac{cr(\Gamma)}{cr(G)} \cdot \frac{lcr(\Gamma)}{lcr(G)}$.

Results. Chimani *et al.* [9] gave bounds on the crossing ratio for the 1-planar, quasi-planar, and fan-planar families. These results show that there exist graphs that have significantly larger crossing numbers when drawn with the beyond-planar restrictions. Their 1-planarity bound also applies to k -planarity when allowing parallel edges. We show that parallel edges are not needed when extending their proof to k -planarity. To do so, we introduce the concept of *k -planar compound edges*, which exhibit essentially the same behavior as k parallel edges. See Section 2 for details. In Section 3 we show how to extend the proof constructions of Chimani *et al.* for quasi-planar and fan-planar graphs to two additional classes of beyond-planar graphs: (k, l) -grid-free graphs and k -gap-planar graphs. These constructions use the concept of ℓ -compound edges; in Section 4 we show how to use such ℓ -compound edges to prove lower bounds for two further families of beyond-planar graphs, namely skewness- k graphs and k -apex graphs. Finally, in Section 5 we introduce the concept of *ℓ -bundles* which allow us to prove tight bounds on the crossing ratio for families of graphs where these bounds are quadratic in the number n of vertices. We prove tight quadratic bounds for planarly connected graphs, k -fan-crossing-free graphs, and straight-line RAC graphs. All bounds are summarized in Table 1. Bounds that are tight for a fixed k are indicated in boldface. Last but not least, in Section 6 we show that all bounds also apply to straight-line drawings.

2 k -Planar Graphs

In a k -planar drawing no edge can be involved in more than k crossings. Chimani *et al.* [9] prove a tight bound on the crossing ratio for 1-planarity: $\varrho_{1\text{-pl}} = n/2 - 1$. They also noted that the same arguments hold for k -planarity, if one allows parallel edges (multiple edges between two vertices). They achieve a $k(n - 2)/2$ lower bound on $\varrho_{k\text{-pl}}$ for graphs with n vertices by replacing all edges except for one in their construction for 1-planarity by k parallel edges. We show that parallel edges are not needed to extend their proof to k -planarity. However, the dependence on k in the lower bound that we achieve is worse than the lower bound by Chimani *et al.* using parallel edges.

To extend their construction to k -planarity we introduce *k -planar compound edges* (see Figure 1), which exhibit essentially the same behavior as k parallel edges. One k -planar compound edge consists of k^2 parallel edges, each subdivided $k - 1$ times (so it consists of a total of k^3 edges).




Figure 1: Left: 2-planar compound edges crossing; Right: 3-planar compound edges crossing




Figure 2: Construction in [9]. Left: drawing of G_ℓ with $\text{cr}(G_\ell) = 2$; Right: 1-planar drawing of G_ℓ with $\text{cr}_{1\text{-pl}}(G_\ell) = 11\ell$.

We replace each set of parallel edges in their construction with a k -planar compound edge. In a k -planar setting, each k -planar compound edge can cross one other k -planar compound edge such that each edge has exactly k crossings (see Figure 1).

Theorem 1 For every $\ell \geq 7$ there exists a k -planar graph G_ℓ^k with $n = 23\ell(k - 1)k^2 + 11\ell + 2$ vertices such that $\text{cr}(G_\ell^k) \leq 2k^2$ and $\text{cr}_{k\text{-pl}}(G_\ell^k) \geq k^4(11\ell)$, thus $\varrho_{k\text{-pl}} \in \Omega(n/k)$.

Proof: We construct the graph G_ℓ as described by Chimani *et al.* [9], Section 2 (see Figure 2). The construction of G_ℓ consists of three parts: a rigid graph P (round vertices, black edges); its dual P^* (square vertices, purple); a set of *binding edges* which connects P to P^* (grey); and one *special edge* (orange). The graph G_ℓ has $11\ell + 2$ vertices and $23\ell + 1$ edges.

Subsequently, we replace each edge in G_ℓ except the special edge with a k -planar compound edge. That is, we replace every black, grey, and purple edge by k^2 parallel edges, all split by $k - 1$ vertices. The resulting graph G_ℓ^k has $n = 23\ell(k - 1)k^2 + 11\ell + 2$ vertices. Two k -planar compound edges may cross while maintaining k -planarity (see Figure 1). The graph G_ℓ^k admits a drawing

with $2k^2$ crossings (see Figure 2, left) where P^* is drawn entirely in one face (shaded purple). Thus, $\text{cr}(G_\ell^k) \leq 2k^2$. Note that this drawing is not k -planar.


We show that $\text{cr}_{k\text{-pl}}(G_\ell^k) \geq k^4(11\ell)$. Suppose we have a k -planar crossing-minimal drawing Γ of G_ℓ^k . We remove the interior vertices of each k -planar compound edge in Γ and hence each path of length k becomes one edge. Thus, each k -planar compound edge becomes k^2 parallel edges, which results in a drawing Γ' of a multigraph $H_\ell^{k^2}$. Since we removed only subdivisions of edges, it follows that the number of crossings in Γ' is equal to the number of crossings in Γ . Observe that $H_\ell^{k^2}$ is a modification of G_ℓ where each edge except the special orange edge is replaced with k^2 parallel edges. This multigraph $H_\ell^{k^2}$ with $11\ell + 2$ vertices is the same graph as the one used in Corollary 3 [9] which proves that $\text{cr}_{k^2\text{-pl}}(H_\ell^{k^2}) = k^4(11\ell)$.

In Γ each edge in each path of length k had at most k crossings. Thus, in Γ' each edge has at most k^2 crossings (the special edge has at most k crossings). Therefore, Γ' is a k^2 -plane drawing of $H_\ell^{k^2}$. Thus, there are at least $k^4(11\ell)$ crossings in Γ' and at least $k^4(11\ell)$ crossings in Γ . Since Γ is a crossing-minimal drawing of G_ℓ^k (by definition), it follows that $\text{cr}_{k\text{-pl}}(G_\ell^k) \geq k^4(11\ell)$. Recall that $\text{cr}(G_\ell^k) \leq 2k^2$ and $n = 23\ell(k - 1)k^2 + 11\ell + 2$. We can conclude that $\varrho_{k\text{-pl}} \in \Omega(n/k)$. \square

A k -planar graph with n vertices can have at most $3.81\sqrt{kn}$ edges [1]. Each edge can have at most k crossings. Thus, a crossing-minimal k -plane drawing cannot have more than $k \cdot 3.81\sqrt{kn}$ crossings and therefore $\varrho_{k\text{-pl}} \in O(k\sqrt{kn})$.

3 (k, l) -Grid-Free and k -Gap-Planar

Chimani *et al.* [9] prove bounds on the crossing ratio for k -quasi-planarity and fan-planarity using the notion of extended edges, which we refer to as ℓ -compound edges: an ℓ -compound edge xy is a combination of the edge xy and a set Π_{xy} of $\ell - 1$ paths of length two connecting x and y (see figure on the right). We indicate ℓ -compound edges with thick blue lines. We say that an ℓ -compound edge xy crosses an edge e , if the edge xy crosses e . Correspondingly, we say that two ℓ -compound edges xy and $x'y'$ cross, if the edges xy and $x'y'$ cross.



In their Lemma 5 (restated as Lemma 1 below), Chimani *et al.* show that if two ℓ -compound edges cross in a drawing Γ , then Γ contains at least ℓ crossings.

Hence, for a drawing to have less than ℓ crossings no two ℓ -compound edges can cross. Chimani *et al.* then construct graphs where the endpoints of an ℓ -compound edge are separated by a closed curve which forces ℓ crossings. They conjectured that similar constructions could be used on additional families of beyond-planar graphs. Here we show that this is indeed the case by using similar constructions to prove lower bounds for (k, l) -grid-free graphs and k -gap-planar graphs.

Lemma 1 (Lemma 5 in Chimani *et al.* 2019 [9]) *Let G be a graph containing two independent edges uv and wz . Suppose that u and v (w and z , resp.) are connected by a set Π_{uv} (Π_{wz} , resp.) of $\ell - 1$ paths of length two. Let Γ be a drawing of G . If uv and wz cross in Γ , then Γ contains at least ℓ crossings.*

For both classes we prove lower bounds on the crossing ratio which are linear in the number of vertices n . Specifically, in Section 3.1, we prove a general lower bound for the (k, l) -grid-free crossing ratio for all $k > 1$ and $l > 1$. Then, in Section 3.2, we first prove a tight lower bound for 1-gap-planarity and then extend it to k -gap-planarity.




Figure 3: Left: drawing of G_ℓ with $\text{cr}(G_\ell) \leq 6$; Right: $(2,3)$ -grid-free drawing of G_ℓ with $\text{cr}_{2,3\text{-grid-free}}(G_\ell) \geq \ell$, ℓ -compound edges drawn with thick blue lines.

3.1 (k, l) -Grid-Free Graphs

In a (k, l) -grid-free drawing it is forbidden to have a $k \times l$ grid, that is, a set of k edges that cross a set of l edges. To construct arbitrarily large graphs in which this restriction forces many crossings, we start by creating a cycle of length $2k + 2l$ of ℓ -compound edges and connect each vertex of the cycle to an additional vertex x using a further $2k + 2l$ ℓ -compound edges. By Lemma 1 none of the ℓ -compound edges can cross or the drawing has ℓ crossings. Note that k and l are constants, while ℓ can become arbitrarily large with respect to k and l . We add a $k \times l$ grid connecting the vertices of the cycle (see Figure 3, left; ℓ -compound edges are indicated in blue, grid edges in black). In an (k, l) -grid-free drawing, one grid edge has to be drawn in the same face (with respect to the cycle) as the vertex x and must hence cross an ℓ -compound edge, incurring ℓ crossings. Theorem 2 and its proof formalize these arguments.

Theorem 2 *For every $\ell \geq 2, k > 1, l > 1$ there exists a (k, l) -grid free graph G_ℓ with $n = 4(k + l)\ell - 2(k + l) + 1$ vertices such that $\text{cr}_{k,l\text{-grid-free}}(G_\ell) \geq \ell$ and $\text{cr}(G_\ell) \leq k\ell$.*

Thus, $\varrho_{k,l\text{-grid-free}} \in \Omega\left(\frac{n}{kl(k+l)}\right)$.

Proof: We first construct a graph G' which consists of a cycle C of length $2k + 2l$, $C = \langle u_1, \dots, u_{2k+2l} \rangle$ and a vertex x connected to each vertex of C . Now we construct a graph G_ℓ by replacing each edge in G' by an ℓ -compound edge. Finally, we add the grid edges $u_i u_{2k+l-i+1}$ for $i = 1, \dots, k$ and $u_{k+i} u_{2k+2l-i+1}$ for $i = 1, \dots, l$ (see Figure 3 with $k = 2$ and $l = 3$). G_ℓ has $n = 2(k + l)\ell + 2(k + l) - 19$ vertices. Note that G' is a subgraph of G_ℓ . If two edges of G' cross each other, then the claim follows from Lemma 1.

If no grid edge in G_ℓ crosses the subgraph G' , then all grid edges must be drawn within the unique face of size $2k + 2l$ in G' and hence the drawing is not (k, l) -grid-free. Therefore at least one grid edge $e = u_i u_j$ must cross an edge ab of G' . More specifically, e must cross an edge ax , as x connects to all vertices on the cycle C .

The edge e connects two vertices u_i and u_j of C . There exist two paths in C which connect u_i and u_j . One of these paths does not contain a . Now consider the closed curve γ formed by this path and e . This curve partitions the plane into two or more regions. Since the edge e crosses the edge ax , a and x lie in different regions of γ . Hence the ℓ -compound edge between a and x in G_ℓ must cross γ resulting in ℓ crossings. \square

The maximum number of edges in (k, l) -grid-free graphs with n vertices is $c_{k,l}n$, where $c_{k,l}$ depends only on k and l [16]. Thus, for simple drawings, $\varrho_{k,l\text{-grid-free}} \leq g(k, l) \cdot n^2$ for a computable function g depending only on k and l .

3.2 k -Gap-Planar Graphs

In a k -gap-planar drawing every crossing is assigned to one of the two edges involved. No more than k crossings can be assigned to a single edge. We first describe our lower bound construction for $k = 1$ and then show how to extend it to larger k . As before we create a cycle C of length 8 of ℓ -compound edges and connect each vertex of the cycle to an additional vertex x using a further 8 ℓ -compound edges. Again by Lemma 1 none of the ℓ -compound edges can cross. We add four single edges which connect diametrically opposite vertices of C (see Figure 4, left; ℓ -compound edges are indicated in blue, single edges in black). In a 1-gap-planar drawing one single edge has to be drawn in the same face (with respect to the cycle) as the vertex x and must hence cross an ℓ -compound edge, incurring ℓ crossings.

Theorem 3 *For every $\ell \geq 2$ there exists a 1-gap-planar graph G_ℓ with $n = 16\ell - 7$ vertices such that $\text{cr}_{1\text{-gap}}(G_\ell) \geq \ell$ and $\text{cr}(G_\ell) \leq 6$. Thus, $\varrho_{1\text{-gap}} \in \Theta(n)$.*

Proof: The upper bound follows directly from the fact that a 1-gap-planar graph with n vertices can have at most $5n - 10$ edges [3]. Since each edge can have at most one crossing assigned to it, the number of crossings cannot exceed the number of edges. Thus, a 1-gap-planar graph can have no more than $5n - 10$ crossings. Clearly, if $\text{cr}_{1\text{-gap}}(G) > \text{cr}(G)$ it must hold that $\text{cr}(G) \geq 2$ and therefore $\varrho_{1\text{-gap}} \in O(n)$.

For the lower bound we first construct a graph G' which consists of a cycle C of length eight, $C = \langle u_1, u_2, \dots, u_8 \rangle$ and a vertex x connected to each vertex of C . Now we construct a graph G_ℓ by replacing each edge in G' by an ℓ -compound edge. Finally, we add the *single* edges $u_i u_{i+4}$, $i = 1, 2, 3, 4$ (see Figure 4). G_ℓ has $n = 16(\ell - 1) + 9 = 16\ell - 7$ vertices. Note that G' is a subgraph of G_ℓ . If two edges of G' cross each other, then the claim follows from Lemma 1.

If no single edge crosses the subgraph G' , then all single edges must be drawn within the unique face of size eight in G' . All single edges cross each other, causing six crossings, which need to be mapped to the four single edges. This is not possible and hence the drawing is not 1-gap-planar. Therefore, at least one single edge $e = u_i u_j$ must cross an edge ab of G' . More specifically, e must cross an edge ax , as x connects to all vertices on the cycle C .




Figure 4: Left: drawing of G_ℓ with $\text{cr}(G_\ell) \leq 6$; Right: 1-gap-planar drawing of G_ℓ with $\text{cr}_{1\text{-gap}}(G_\ell) \geq \ell$, ℓ -compound edges are drawn with thick blue lines.

The edge e connects two vertices u_i and u_j of C . There exist two paths in C which connect u_i and u_j . One of these paths does not contain a . Now consider the closed curve γ formed by this path and e . This curve partitions the plane into two or more regions. Since the edge e crosses the edge ax , a and x lie in different regions of γ . Hence the ℓ -compound edge between a and x in G_ℓ must cross γ resulting in ℓ crossings. \square

In general, a k -gap-planar graph with n vertices can have at most $O(\sqrt{kn})$ edges [3]. Since each edge can have at most k crossings assigned to it, the number of crossings cannot exceed the number of edges times k . Thus, a k -gap-planar graph can have no more than $O(k\sqrt{kn})$ crossings and therefore $\varrho_{k\text{-gap}} \in O(k\sqrt{kn})$. To prove a lower bound for k -gap-planarity, we can use exactly the same construction as above starting with a cycle of length $8k$. Our lower bound is cubic in $1/k$ and hence does not match the upper bound.

Corollary 4 *For every $\ell \geq 2$ there exists a k -gap-planar graph G_ℓ^k with $n = 16k\ell - 8k + 1$ vertices such that $\text{cr}_{k\text{-gap}}(G_\ell^k) \geq \ell$ and $\text{cr}(G_\ell^k) \leq 8k^2 - 2k$. Thus, $\varrho_{k\text{-gap}} \in \Omega(n/k^3)$.*

Proof: We first construct the graph G^k starting with a cycle $C = \langle u_1, u_2, \dots, u_{8k} \rangle$ of length $8k$ and a vertex x connected to each vertex of C . Now we construct a graph G_ℓ^k by replacing each edge in G^k by an ℓ -compound edges. Finally, we add the single edges $u_i u_{i+4k}$, $1 \leq i \leq 4k$.

If all $4k$ single edges are drawn inside the cycle C they all mutually cross, resulting in $\binom{4k}{2} = \frac{1}{2}(4k)(4k-1) = 8k^2 - 2k$ crossings. Since $8k^2 - 2k > 4k^2$ for $k > \frac{1}{2}$ the crossings cannot be mapped to the $4k$ edges without exceeding a load of k crossings per edge. Hence at least one single edge must cross an edge of G^k and the argument follows as above. \square

4 Skewness- k and k -Apex Graphs

In this section we further explore the use of ℓ -compound edges for the construction of lower bound examples. In particular, we consider the two families of skewness- k graphs and k -apex graphs. As in the previous section, we exploit the fact that crossings of ℓ -compound edges result in ℓ crossings, which allows us to enforce a structure on crossing-minimal drawings.

4.1 Skewness- k Graphs

In a skewness- k drawing all crossings must be *covered* by a specific set of most k edges. A crossing is covered by an edge when the edge is part of the crossing. In particular, in a skewness-1 drawing, there is one *special* edge that covers all crossings. Skewness-1 drawings are also known as almost planar or near planar drawings. We first describe our lower bound construction for $k = 1$ and then show how to extend it to larger k .

Theorem 5 *For every $\ell \geq 3$ there exists a skewness-1 graph G_ℓ with $n = 11\ell - 4$ vertices such that $\text{cr}_{\text{skew-1}}(G_\ell) \geq \ell$ and $\text{cr}(G_\ell) \leq 3$. Thus, $\varrho_{\text{skew-1}} \in \Theta(n)$.*

Proof: The upper bound directly follows from the fact that a skewness-1 graph with n vertices can have at most $3n - 5$ edges [11]. Since one edge must cover all crossings, there cannot be more crossings than the number of edges. Thus, a crossing-minimal skewness-1 drawing cannot have more than $3n - 4$ crossings and therefore $\varrho_{\text{skew-1}} \in O(n)$.

For the lower bound we first construct a graph G' which consists of a path $P = \langle u_1 \dots u_6 \rangle$ of length six and a vertex x connected to each vertex of P . We construct a graph G_ℓ by replacing

each edge in G' by an ℓ -compound edge. Finally, we add the single edges u_1u_4 , u_2u_5 and u_3u_6 (see Figure 5). G_ℓ has $n = 11\ell - 11 + 7 = 11\ell - 4$ vertices. Note that G' is a subgraph of G_ℓ . If two edges of G' cross each other, then the claim follows from Lemma 1.

Crossing-minimal skewness-1 drawings must be simple. Assume for contradiction that a crossing-minimal skewness-1 drawing is not simple. Then there must be two edges e and e' which have more than one point in common. One of these edges, say e , must be the special edge. Hence e' cannot cross any other edges than e . We can reroute e along e' between two of their share points, thereby reducing the number of crossings.

Assume that each edge u_iu_{i+1} of P defines a 3-cycle with x and its incident edges such that all other vertices lie in the same face bounded by the 3-cycle. We argue that in this case there is no possible simple skewness-1 drawing. We start with the crossing-free drawing Γ of the edges connecting the endpoints of ℓ -compound edges and we add the edge u_1u_4 . Since we can assume that the drawing produced is simple, u_1u_4 can only be drawn with 0 crossing or with at least two crossings. If it is drawn with at least two crossings, then u_1u_4 is the special edge. Symmetrically, the same holds for u_3u_6 . Since at least one of them is not the special edge, at least one of them is drawn with 0 crossings with respect to the ℓ -compound edges, without loss of generality we assume that u_1u_4 is drawn without crossings. Now, there is a 3-cycle (u_1, u_4, x) that divides both vertex pairs u_2u_5 and u_3u_6 . Both edges will have to cross the 3-cycle, thus one of the edges of the 3-cycle has to be the special edge. In particular, this implies that neither u_2u_5 nor u_3u_6 are the special edge.

By the argument above, u_3u_6 cannot cross Γ . Therefore, u_3u_6 , has to cross u_1u_4 , making u_1u_4 the special edge. Now u_2 and u_5 are separated by the 3-cycle (u_3, u_6, x) . Since the special edge is not part of this cycle, it is not possible for Γ to be a skewness-1 drawing. An illustration can be found in Figure 5 on the left.

If there is a skewness-1 drawing where all crossings are between single edges, then all vertices must lie in the same face of G' . By the above argument, such a drawing is not skewness-1. By Lemma 1 if two edges of G' cross, the drawing has ℓ crossings. Thus, in a crossing-minimal skewness-1 drawing Γ' , at least one single edge e has to cross an edge ab of G' . One of these edges is the special edge. Since Γ' is simple, a and b must lie in different faces of Γ' and the $\ell - 1$ paths connecting a and b must cross e , resulting in at least ℓ crossings. \square

We extend the proof for the skewness-1 crossing ratio to the skewness- k crossing ratio.

Theorem 6 *For every $\ell \geq 3$ there exists a skewness- k graph G_ℓ^k with $n = 11k\ell - 5k + 1$ vertices such that $cr_{skew-k}(G_\ell^k) \geq \ell k$ and $cr(G_\ell^k) \leq 3k$. Thus, $\varrho_{skew-k} \in \Omega(n/k)$.*

Proof: We construct a graph G_ℓ^k by identifying the vertex x of k copies of G_ℓ (see Figure 6). A




Figure 5: Left: drawing of G_ℓ with $cr(G_\ell) \leq 3$; Right: skewness-1 drawing of G_ℓ with $cr_{skew-1}(G_\ell) \geq \ell$, ℓ -compound edges are drawn with thick blue lines.



Figure 6: Left: drawing of G_ℓ with $\text{cr}(G_\ell) \leq 3k$; Right: skewness- k drawing of G_ℓ with $\text{cr}_{\text{skew-}k}(G_\ell) \geq k\ell$, each of the k petals contains a copy of G_ℓ , resulting in a graph G_ℓ^k , ℓ -compound edges are drawn with thick blue lines.

drawing of G_ℓ^k is skewness- k if and only if all k instances of G_ℓ are skewness-1. Hence, applying the above proof on all instances gives $\text{cr}_{\text{skew-}k}(G_\ell^k) = k\ell$. However, there exists an unrestricted drawing with $\text{cr}(G_\ell^k) \leq 3k$ where each G_ℓ is drawn with three crossings (see Figure 6, left). \square

A skewness- k graph with n vertices can have at most $3n - 6 + k$ edges [11]. Since at most k edges are involved in all crossings, there cannot be more crossings than the number of edges times k . Thus, a crossing-minimal skewness- k drawing cannot have more than $3kn - 6k + k^2$ crossings and therefore $\varrho_{\text{skew-}k} \in O(kn + k^2)$.

4.2 k -Apex Graphs

In a k -apex drawing all crossings must be covered by at most k vertices. A crossing is covered by a vertex when an edge incident to that vertex is part of the crossing. Every skewness- k drawing is also k -apex. Hence we know that there is a graph G_ℓ with $n = 11\ell - 4$ vertices which admits a drawing with three crossings (see Figure 5, left) and admits a 1-apex drawing with ℓ crossings (see Figure 5, right).

Moreover, the proof of Theorem 5 of the lower bound on the skewness-1 crossing ratio translates to 1-apex drawings. In the case in which each edge $u_i u_{i+1}$ of P defines a 3-cycle with x and its incident edges such that all other vertices lie in the same face bounded by the 3-cycle, the drawing cannot be 1-apex, as removing any vertex could still not produce a plane drawing (see Figure 5, left). The rest of the proof directly translates to this setting.

Corollary 7 *For every $\ell \geq 3$ there exists a 1-apex graph G_ℓ with $n = 11\ell - 4$ vertices such that $\text{cr}_{1\text{-apex}}(G_\ell) \geq \ell$ and $\text{cr}(G_\ell) \leq 3$. Thus, $\varrho_{1\text{-apex}} \in \Omega(n)$.*

This bound is not tight, as the upper bound is quadratic. A 1-apex graph with n vertices can have at most $4n - 10$ edges [11]. Thus, a 1-apex crossing-minimal drawing has at most $(4n - 10)^2$ crossings and therefore $\varrho_{1\text{-apex}} \in O(n^2)$.

Similar to the 1-apex example, we know that for each k there is a graph G_ℓ^k with $n = 11\ell k - 5k + 1$ vertices which admits a drawing with $3k$ crossings and admits a k -apex drawing with $k\ell$ crossings. As before, the proof for skewness- k translates to k -apex, because the drawing is only k -apex when every copy of G_ℓ is drawn 1-apex.

Corollary 8 *For every $\ell \geq 3$ there exists a k -apex graph G_ℓ^k with $n = 11\ell k - 5k + 1$ vertices such that $\text{cr}_{k\text{-apex}}(G_\ell^k) \geq \ell k$ and $\text{cr}(G_\ell^k) \leq 3k$. Thus, $\varrho_{k\text{-apex}} \in \Omega(n/k)$.*

A k -apex graph with n vertices can have at most $3(n-k)-6+\sum_{i=1}^k(n-i) = 3(n-k)-6+kn-\frac{k(k+1)}{2}$ edges [11]. Thus, a k -apex crossing-minimal drawing has at most $\left(3(n-k)-6+kn-\frac{k(k+1)}{2}\right)^2$ crossings and therefore $\varrho_{k\text{-apex}} \in O(k^2n^2 - k^4)$.

5 Planarly Connected Graphs, k -Fan-Crossing-Free Graphs and Straight-line RAC-Graphs

In this section we introduce the concept of ℓ_2 -bundles and ℓ_3 -bundles, which are sets of ℓ paths of length two or three, respectively, all connecting the same two vertices (see Figure 7). We indicate ℓ_2 -bundles and ℓ_3 -bundles with thick red and green lines, respectively. The vertices that are interior to a bundle have degree two. Two crossing bundles result in a quadratic number of crossings. We show how to enforce such crossings to prove tight bounds on the crossing ratio.



Figure 7: Left: an ℓ_2 -bundle; Right: an ℓ_3 -bundle; drawn as a thick red or green line, respectively.

5.1 Planarly Connected Graphs

In a planarly connected drawing two edges can cross only if their endpoints are connected by another edge which has no crossings. We prove in Theorem 9 that $\varrho_{\text{pl-con}} \in \Theta(n^2)$ by constructing a graph in which a crossing occurs between two edges whose endpoints are not connected when two vertices are drawn in the same face of a cycle composed of ℓ_2 -bundles. When drawing the vertices in separate faces, two ℓ_2 -bundles have to cross, resulting in a quadratic number of crossings. To do so, we first argue in Lemma 2 that there is a planarly connected drawing that is crossing-minimal in which ℓ_2 -bundles do not cross themselves and no vertex lies between two consecutive paths of the same ℓ_2 -bundle.

Lemma 2 *If a planarly connected graph G contains ℓ_2 -bundles, then there is a planarly connected crossing-minimal drawing Γ of G in which paths from the same ℓ_2 -bundle do not cross each other, all paths of the same ℓ_2 -bundle cross the same edges, and no vertex lies between two consecutive paths of the same ℓ_2 -bundle.*

Proof: We first prove that in every planarly connected crossing-minimal drawing of G , paths from the same ℓ_2 -bundle do not cross each other.

Suppose there is a drawing where two paths p_1 and p_2 of an ℓ_2 -bundle cross. One of the paths, say p_1 , has less or equal crossings than the other path, say p_2 . If we draw p_2 parallel and sufficiently close to p_1 , such that there are no vertices between p_1 and p_2 and they both cross the same edges,

then the number of crossings does not increase. However, since p_1 and p_2 do not cross anymore, the number of crossings decreases by at least one. Recall that, by definition, in a graph containing ℓ_2 -bundles the vertices interior to a bundle have degree exactly two. Thus, in a planarly connected drawing it is always possible to redraw a path p in an ℓ_2 -bundle parallel and sufficiently close to another path p' in that bundle. Therefore, in a planarly connected crossing-minimal drawing edges of the same ℓ_2 -bundle do not cross.

The redrawing argument can also be used to prove that there is a planarly connected crossing-minimal drawing Γ of G in which all paths from the same ℓ_2 -bundle cross the same edges and no vertex is drawn in between two consecutive paths of the same ℓ_2 -bundle. Given a planarly connected crossing-minimal drawing of G , for each ℓ_2 -bundle we can select a path with the minimum number of crossings and redraw all the other paths close to it such that they all cross the same edges and no vertex lies in the small gap between one path and the next. \square

Theorem 9 *For every $\ell \geq 2$ there exists a planarly connected graph G_ℓ with $n = 7\ell + 6$ vertices such that $\text{cr}_{\text{pl-con}}(G_\ell) \geq \ell^2$ and $\text{cr}(G_\ell) \leq 1$. Thus, $\varrho_{\text{pl-con}} \in \Theta(n^2)$.*

Proof: The upper bound $\varrho_{\text{pl-con}} \in O(n^2)$ follows directly from the fact that a planarly connected graph with n vertices has at most cn edges, where c is a constant [2].

For the lower bound, we construct a graph G_ℓ . We start with a 6-cycle $\langle u_1, u_2, \dots, u_6 \rangle$, and an edge u_1u_4 , resulting in the graph G' . Then we replace each edge in G' with an ℓ_2 -bundle. Finally, add regular edges u_2u_5 and u_3u_6 . The graph G_ℓ has $n = 7\ell + 6$ vertices and admits a drawing with only one crossing (see Figure 8, left).

By Lemma 2 there is a planarly connected crossing-minimal drawing Γ of G_ℓ in which for every ℓ_2 -bundle its edges do not cross each other, all paths cross the same edges, and no vertex lies between two consecutive paths. Let C be the cycle of ℓ_2 -bundles $C = \langle u_1, u_4, u_5, u_6 \rangle$. If C crosses itself in Γ , then there are ℓ^2 crossings. Otherwise C is drawn without crossings in Γ and defines two faces of size eight. The other faces do not contain vertices of Γ in their interior. Thus, u_2 and u_3 can either be drawn in the same face defined by C , or in different faces. If they are drawn in the same face, Γ cannot be planarly connected: a simple case distinction shows that there has to be a crossing between two edges whose endpoints are not connected by any other edge. Specifically, there is a crossing between either u_1u_2 and u_3u_4 , u_1u_2 and u_3u_6 , u_2u_5 and u_3u_6 or u_2u_5 and u_3u_4 . These are all not allowed, as each time there is no edge connecting the two edges. If u_2 and u_3 are drawn in different faces defined by C , then the ℓ_2 -bundle u_2u_3 has to cross C . As C is composed of ℓ_2 -bundles, there are ℓ cycles, distinct in edges, all separating u_3 and u_4 . All the ℓ distinct paths in the ℓ_2 -bundle u_2u_3 have to cross the ℓ distinct (in edges) cycles in C . Therefore, Γ has at least ℓ^2 crossings. \square





Figure 8: Left: drawing of G_ℓ with $\text{cr}(G_\ell) = 1$; Right: planarly connected drawing of G_ℓ with $\text{cr}_{\text{pl-con}}(G_\ell) = \ell^2$, ℓ_2 -bundles are drawn with thick red lines.

5.2 k -Fan-Crossing-Free Graphs

In a k -fan-crossing-free drawing it is forbidden for an edge to cross k edges which are adjacent to the same vertex. While it is possible for an edge to “weave” through an ℓ_2 -bundle with $\ell \leq 2k - 2$ (see figure on the right), no edge can cross an ℓ_2 -bundle with $\ell \geq 2k - 1$. In contrast, ℓ_3 bundles can be crossed for any ℓ . Lemma 3 argues that, given a sufficiently large ℓ , there is a fan-crossing-free drawing that is crossing-minimal in which ℓ_2 -bundles do not cross themselves and no vertex lies between two consecutive paths of the same ℓ_2 -bundle. We prove in Theorem 10 that $\varrho_{\text{fan-free}} \in \Omega(n^2)$ and $\varrho_{k\text{-fan-free}} \in \Omega(n^2/k^3)$ using ℓ_2 -bundles to force ℓ_3 -bundles to cross.



Lemma 3 *Let G be a k -fan-crossing-free graph and let p be the length of the longest simple path in G . If G contains ℓ_2 -bundles with $\ell \geq 2p(k - 1) + 1$, then in any crossing-minimal k -fan-crossing-free drawing of G the edges in the ℓ_2 -bundles have no crossings.*

Proof: Let Γ be a crossing-minimal k -fan-crossing-free drawing of G and let Λ be the drawing of an ℓ_2 -bundle B in Γ . We assume for the sake of contradiction that Λ has crossings in Γ . These crossings can involve solely edges of B and also other edges of G . Let u and v denote the two endpoints of the bundle B . The drawing Λ is bounded by two curves γ_1 and γ_2 which connect u and v . These curves are formed by the drawings of (parts of) edges of B (see Figure 9) and they bound




Figure 9: Left: An ℓ_2 -bundle \mathcal{B} crossed by itself and by other edges. The four parts in which Γ_R is partitioned are drawn in different colors: black, green, blue, and yellow. Right: Redrawing the different (parts of) edges in Γ_R . This removes the crossings of \mathcal{B} .

a region R of the plane, which is exactly the region in which B is drawn. Our goal is to redraw G without increasing the number of crossings such that the drawing remains k -fan-crossing-free and (i) all parts of G which are not B are drawn in a ε -strip along the boundary of R and (ii) the bundle B is drawn crossing-free in the interior of R . Once the former is achieved the latter is straightforward.

Consider the *restriction* Γ_R of the drawing Γ to R , that is, only those parts of Γ that lie strictly in the interior of R . Specifically, neither the vertices u and v nor the curves γ_1 and γ_2 are part of Γ_R . We say that two vertices of G are R -connected if they are connected by a path which is drawn fully in the interior of R . We can partition Γ_R into four parts: edges and vertices of B , R -connected components that lie full inside R , R -connected components that touch the interior of γ_1 , and R -connected components that touch the interior of γ_2 . For example, the green path in Figure 9 lies fully in the interior of R , the blue R -connected components touch the interior of γ_1 , and the yellow R -connected components touch the interior of γ_2 .

The drawing Γ is k -fan-crossing-free and $\ell > 2p(k - 1)$, that is, ℓ -bundles are more than $2(k - 1)$ wider than the longest path in G . Any R -connected component that touches both γ_1 and γ_2 must contain parts of the drawing of a path in G that cross all paths in B . Since in a k -fan-crossing-free drawing an edge can cross at most $k - 1$ edges incident to a vertex, in particular u or v , in total the edges of a path can cross at most $2p(k - 1)$ edges of B . Hence no R -connected component can touch both γ_1 and γ_2 .

We can independently and locally redraw the edges of G that correspond to each part, B in the interior of R , and the other three parts within a ε -strip along the boundary of R . Note that independent fragments of a single edge of G can appear in two parts and will be redrawn independently. \square

Theorem 10 *For every $\ell \geq 95$ there exists a fan-crossing-free graph G_ℓ with $n = 45\ell + 16$ vertices such that $\text{cr}_{\text{fan-free}}(G_\ell) \geq \ell^2/2$ and $\text{cr}(G_\ell) \leq 2$. Thus, $\varrho_{\text{fan-free}} \in \Theta(n^2)$.*




Figure 10: Left: drawing of G_ℓ with $\text{cr}(G_\ell) \leq 2$; Right: fan-crossing-free drawing of G_ℓ with $\text{cr}_{\text{fan-free}}(G_\ell) \geq \ell^2$. Thick red lines represent ℓ_2 -bundles and thick green lines ℓ_3 -bundles.

Proof: The upper bound $\varrho_{\text{pl-con}} \in O(n^2)$ follows directly from the fact that a fan-crossing-free graph with n vertices can have at most $4n - 8$ edges [8].

For the lower bound we construct a graph G_ℓ (see Figure 10). We start with a 10-cycle $C = \langle u_1, u_2, \dots, u_{10} \rangle$. We add five vertices f_1, f_2, \dots, f_5 and add the edges $f_i u_{2i-2}, f_i u_{2i-1}, f_i u_{2i}$ for $i = 1, 2, \dots, 5$. We add a new vertex x and connect it to each f_i for $i = 1, 2, \dots, 5$. We then replace each edge $f_i u_j$ by an ℓ_2 -bundle and replace each edge $x f_i$ and $u_i u_j$ by an ℓ_3 -bundle. Finally, we add the regular edges $u_1 u_5, u_1 u_7$, and $u_3 u_9$. The resulting graph G_ℓ has $n = 45\ell + 16$ vertices and admits a drawing with only two crossings (see Figure 10, left).

In G_ℓ there is a cycle $F = \langle f_1, u_2, f_2, u_4, f_3, u_6, f_4, u_8, f_5, u_{10} \rangle$ of ℓ_2 -bundles. There are $10 + 5 + 1 = 16$ vertices which are not interior to bundles. The longest path can use at most two vertices inside each bundle and has length at most $48 - 1 = 47$. Since $\ell \geq 95 = 2 \cdot 47 \cdot (2 - 1) + 1$, by Lemma 3, all ℓ_2 -bundles must be drawn without crossings and F must be drawn plane. If u_1, u_3, u_5, u_7 and u_9 all lie in the same face of F then we are effectively in the situation depicted in Figure 10 (left) and the drawing is not fan-crossing-free. Hence u_1, u_3, u_5, u_7 , and u_9 must distribute over the two faces of F . Specifically, we can assume that there is a vertex $u_i, i \in \{1, 3, 5, 7, 9\}$, such that u_i lies in the same face of F as x .

We consider the cycle Z consisting of the two ℓ_2 -bundles between u_i and $f_{(i+1)/2}$ and between $f_{(i+1)/2}$ and u_{i-1} , and the ℓ_3 -bundle between u_i and u_{i-1} . Symmetrically, we can consider the cycle Z' involving u_{i+1} instead of u_{i-1} . The vertex x can lie within any face of the ℓ_3 -bundle. Consider the cycles formed by each path of the ℓ_3 -bundle together with the two ℓ_2 -bundles. These cycles divide the plan into two faces. We say that the *exterior* face of each cycle is the face that contains F . We say that x lies in the *exterior* of Z (Z' , respectively), if it lies in the exterior face of $\ell/2$ of these cycles. Otherwise, x lies in the *interior* of Z (Z' , respectively). Observe that x lies either in the interior of Z , or in the interior of Z' , or in the exterior of both.

If x lies in the exterior face of both Z and Z' , then the ℓ_3 -bundle connecting x and $f_{(i+1)/2}$ crosses at least $\ell/2$ paths in either Z or Z' (see Figure 10, right; $u_i = u_3$ and $f_{(i+1)/2} = f_2$). If x lies in the interior face of Z , then (by definition of the faces of Z) there is an $f_j \neq f_{(i+1)/2}$ which lies in the exterior face of Z . The ℓ_3 -bundle connecting x and f_j crosses at least $\ell/2$ paths in Z . The argument for Z' is symmetric. \square

The proof can be extended to k -fan-crossing-free graphs by creating a cycle C of length $6 + 2k$ which results in a graph with $3/2 \cdot (6 + 2k) + 1 = 10 + 3k$ vertices not interior to bundles and a longest path of length at most $29 + 9k$. Since no path should be able to cross the ℓ_2 -bundles, we require that $\ell \geq 2 \cdot (29 + 9k) \cdot (k - 1) + 1 = 18k^2 + 40k - 57$.

Corollary 11 *For every $\ell \geq 18k^2 + 40k - 57$ there exists a k -fan-crossing-free graph G_ℓ^k with $n = 9k\ell + 27\ell + 3k + 10$ vertices such that $\text{cr}_{k\text{-fan-free}}(G_\ell^k) \geq \ell^2$ and $\text{cr}(G_\ell^k) \leq k$. Thus, $\varrho_{k\text{-fan-free}} \in \Omega(n^2/k^3)$.*

This bound is not tight in k . A k -fan-crossing-free graph with n vertices can have at most $3(k - 1)(n - 2)$ edges [8]. Thus, a crossing-minimal k -fan-crossing-free drawing cannot have more than $3(k - 1)(n - 2)^2$ crossings. This yields $k_{k\text{-fan-free}} \in O(k^2 n^2)$.

5.3 Straight-line RAC Graphs

A straight-line RAC drawing (Right Angle Crossing) is a straight-line drawing of a graph in which any two crossing edges form a $\frac{\pi}{2}$ angle at their crossing point. In a straight-line RAC drawing, it is not possible for two adjacent edges to be crossed by the same edge. Thus, we observe that a straight-line RAC drawing is also fan-crossing-free.




Figure 11: Straight-line RAC drawing of G_ℓ with $\text{cr}_{\text{RAC}}(G_\ell) \geq \ell^2$ for $\ell = 3$. Thick red lines represent ℓ_2 -bundles and thick green lines ℓ_3 -bundles.

The proof and construction provided for the bound on the fan-crossing-free crossing ratio, also holds for the straight-line RAC crossing ratio. Every time the proof states that the drawing cannot be fan-crossing-free, the drawing is also not straight-line RAC. Thus, we can conclude that a crossing-minimal straight-line RAC drawing Γ of G_ℓ in Theorem 10 contains at least ℓ^2 crossings. In Figure 11 we show such a drawing Γ with ℓ^2 crossings exists. To show that the crossings do form angles of $\frac{\pi}{2}$, in Figure 11 we draw the ℓ_3 -bundles xf_1 , xf_2 , xf_5 , u_2u_3 and u_9u_{10} in detail for $\ell = 3$.

A straight-line RAC graphs can have at most $4n - 10$ edges [10]. Thus, straight-line drawings of RAC graphs have at most $(4n - 10)^2$ crossings, giving $\varrho_{\text{RAC}} \in O(n^2)$.

Corollary 12 *For every $\ell \geq 95$ there exists a straight-line RAC graph G_ℓ with $n = 45\ell + 16$ vertices such that $\text{cr}_{\text{RAC}}(G_\ell) \geq \ell^2$ and $\text{cr}(G_\ell) \leq 2$. Thus, $\varrho_{\text{RAC}} \in \Theta(n^2)$.*

6 Beyond-Planar Graphs with Straight-line Edges

The straight-line setting imposes an additional constraint on the drawings. Therefore, all upper bounds directly apply in the straight-line setting. Lemma 4 shows that it is sufficient to draw each of our lower bound constructions with straight lines to establish the same lower bounds. We say that two drawings of a graph are *weakly isomorphic* if there is a one-to-one correspondence between their vertices and edges that is incidence-preserving and crossing-preserving.

Lemma 4 *Let G be a graph and Γ be a drawing of G with x crossings, certifying that $\text{cr}(G) \leq x$. Moreover, let \mathcal{F} be a beyond-planar family of graphs such that $\text{cr}_{\mathcal{F}}(G) \geq y$. If there is a straight-*

line drawing of G weakly isomorphic to Γ and a straight-line drawing of G in \mathcal{F} , then $\overline{cr}(G) \leq x$ and $\overline{cr}_{\mathcal{F}}(G) \geq y$.

Proof: Since there is a straight-line drawing of G which has the same number of crossing as Γ it immediately follows that $\overline{cr}(G) \leq x$. Drawing graphs with straight lines imposes additional constraints. Since G has a straight-line drawing in \mathcal{F} it follows that $\overline{cr}_{\mathcal{F}}(G) \geq y$. \square

In the following, we either describe or directly draw straight-line versions of all drawings required for the lower bound constructions in this paper. This directly implies that all bounds also hold in the straight-line setting.

k -Planar Graphs. We argue that the 1-planar graph G_ℓ constructed by Chimani *et al.* [9] still admits a straight-line drawing when edges are replaced with k -planar compound edges.

The graph G_ℓ without the special edge is planar. Thus, by Fary’s theorem it admits a plane straight-line drawing. Moreover, as in Figure 2 on the left, G_ℓ can be drawn with straight-line edges and such that $\overline{cr}(G_\ell) = 2$. Since k -planar compound edges can be drawn with straight-line edges and arbitrarily close to the original edges they replace, we have that G_ℓ^k admits a straight-line drawing with $2k^2$ crossings. Thomassen showed that for every 1-planar drawing Γ there exists a straight-line drawing weakly isomorphic to Γ if and only if Γ does not contain a B - or W -configuration [22]. The 1-planar drawing in Figure 2 on the right contains neither a B - or a W -configuration. Hence there is a straight-line drawing of G_ℓ^k that is also k -plane. Thus, by Lemma 4, the bounds of Theorem 1 in [9] and Theorem 1 also hold in the straight-line setting.

k -Quasi-Planar Graphs. Chimani *et al.* [9] showed that $\varrho_{\text{quasi}} \in \Omega(n)$. Figure 12 is a straight-line version of Figure 2 in [9], the drawings they use to support this lower bound. Thus, by Lemma 4, the statement of Theorem 4 in [9] also holds in the straight-line setting. Chimani *et al.* [9] showed that $\varrho_{k\text{-quasi}} \in \Omega(n/k^3)$. For a different k we can expand the drawings by adding more vertices between u_2 and u_3 and between u_4 and u_5 and rearranging the edges such that they all mutually cross, similarly to the argumentation for Corollary 6 in [9]. Again, by Lemma 4 the statement of their corollary holds in the straight-line setting.




Figure 12: Straight-line drawings of graph G_ℓ that are weakly isomorphic to the drawings in Figure 2 in [9]. Left: straight-line drawing of G_ℓ with $\overline{cr}(G_\ell) \leq 3$; Right: straight-line quasi-planar drawing of G_ℓ with $\overline{cr}_{\text{quasi}}(G_\ell) \geq \ell$, ℓ -compound edges are drawn with thick blue lines.



Figure 13: Straight-line drawings of graph G_ℓ that are weakly isomorphic to the drawings in Figure 3 in [9]. Left: straight-line drawing of G_ℓ with $\overline{cr}(G_\ell) \leq 2$; Right: straight-line fan-planar drawing of G_ℓ with $\overline{cr}_{\text{fan}}(G_\ell) \geq \ell$, ℓ -compound edges are drawn with thick blue lines.

Fan-Planar Graphs. Chimani *et al.* [9] showed that $\varrho_{\text{fan}} \in \Omega(n)$. Figure 13 is a straight-line version of Figure 3 in [9], the drawings they use to support this lower bound. Thus, by Lemma 4, the statement of Theorem 7 in [9] also holds in the straight-line setting.

(k, l) -Grid-Free Graphs. Figure 14 is a straight-line version of Figure 3. Thus, by Lemma 4, the statement of Theorem 2 also holds in the straight-line setting for $k = 2, l = 3$. For a different k we can expand the drawings by adding more vertices between u_1 and u_2 and between u_6 and u_7 . For a different l we can do the same between u_3 and u_4 and between u_9 and u_{10} .




Figure 14: Straight-line drawings of graph G_ℓ that are weakly isomorphic to the drawings in Figure 3. Left: straight-line drawing of G_ℓ with $\overline{cr}(G_\ell) \leq 6$; Right: straight-line 2,3-grid-free drawing of G_ℓ with $\overline{cr}_{2,3\text{-grid-free}}(G_\ell) \geq \ell$, ℓ -compound edges are drawn with thick blue lines.

k -Gap-Planar Graphs. Figure 15 is a straight-line version of Figure 4. Thus, by Lemma 4, the statement of Theorem 3 also holds in the straight-line setting. For a different k we can expand the drawings by adding more vertices between u_2 and u_3 and between u_4 and u_5 . Thus, by Lemma 4, the statement of Theorem 4 also holds in the straight-line setting.

Skewness- k Graphs. Figure 16 is a straight-line version of Figure 5. Thus, by Lemma 4, the statement of Theorem 5 also holds in the straight-line setting. For a different k we can expand




Figure 15: Straight-line drawings of graph G_ℓ that are weakly isomorphic to the drawings in Figure 4. Left: straight-line drawing of G_ℓ with $\overline{cr}(G_\ell) \leq 6$; Right: straight-line 1-gap-planar drawing of G_ℓ with $\overline{cr}_{1\text{-gap}}(G_\ell) \geq \ell$, ℓ -compound edges are drawn with thick blue lines.

the drawings by adding more instances of G_ℓ to x . Thus, by Lemma 4, that the statement of Theorem 6 also holds in the straight-line setting.




Figure 16: Straight-line drawings of graph G_ℓ that are weakly isomorphic to the drawings in Figure 5. Left: straight-line drawing of G_ℓ with $\overline{cr}(G_\ell) \leq 3$; Right: straight-line skewness-1 drawing of G_ℓ with $\overline{cr}_{\text{skew-1}}(G_\ell) \geq \ell$, ℓ -compound edges are drawn with thick blue lines.

k -Apex Graphs. Figure 16 is a straight-line version of Figure 5. Thus, by Lemma 4, the statement of Corollary 7 also holds in the straight-line setting. For a different k we can expand the drawings by adding more instances of G_ℓ to x . Thus, by Lemma 4, that the statement of Corollary 8 also holds in the straight-line setting.

Planarly Connected Graphs. Figure 17 is a straight-line version of Figure 8. Thus, by Lemma 4, the statement of Theorem 9 also holds in the straight-line setting.

k -Fan-Crossing-Free Graphs. Figure 18 is a straight-line version of Figure 10. Thus, by Lemma 4, the statement of Theorem 10 also holds in the straight-line setting. For a different k we can expand the drawings in Figure 18 by making the cycle of length $3 + k$, adding the extra vertices between u_3 and u_4 , and adding more edges like u_1u_3 and u_1u_4 .




Figure 17: Straight-line drawings of graph G_ℓ that are weakly isomorphic to the drawings in Figure 8. Left: straight-line drawing of G_ℓ with $\overline{cr}(G_\ell) \leq 1$; Right: straight-line planarly connected drawing of G_ℓ with $\overline{cr}_{\text{pl-con}}(G_\ell) \geq \ell^2$, ℓ_2 -bundles are drawn with thick red lines.




Figure 18: Straight-line drawings of graph G_ℓ that are weakly isomorphic to the drawings in Figure 10. Left: straight-line drawing of G_ℓ with $\overline{cr}(G_\ell) \leq 2$; Right: straight-line fan-crossing-free drawing of G_ℓ with $\overline{cr}_{\text{fan-free}}(G_\ell) \geq \ell^2$. Thick red and green lines represent ℓ_2 - and ℓ_3 -bundles.

7 Conclusion

We studied the relation between the crossing number restricted to beyond-planar drawings and the (unrestricted) crossing number and established a number of new lower bounds on the crossing ratio for several classes of beyond-planar graphs. Our results are summarized in Table 1. The bounds printed in bold font are tight in the number of vertices n . An obvious open question is to improve all bounds which are not tight. Even if a bound is tight in n it might not be tight in k , the parameter which describes the graph class in question. In fact, not a single bound is currently tight in k for non-constant k . Furthermore, it might be of interest to investigate what aspects of a beyond-planar family cause a quadratic instead of a linear crossing ratio. Last but not least, the upper bounds generally assume that drawings are simple. We conjecture that this restriction is in fact not needed and that the bounds hold also in the non-simple setting.

References

[1] E. Ackerman. On topological graphs with at most four crossings per edge. *Computational Geometry*, 85(101574), 2019. doi:10.1016/j.comgeo.2019.101574.

- [2] E. Ackerman, B. Keszegh, and M. Vizer. On the size of planarly connected crossing graphs. *Journal of Graph Algorithms and Applications*, 22(1):11–22, 2018. doi:10.7155/jgaa.00453.
- [3] S. W. Bae, J. Baffier, J. Chun, P. Eades, K. Eickmeyer, L. Grilli, S. Hong, M. Korman, F. Montecchiani, I. Rutter, and C. D. Tóth. Gap-planar graphs. *Theoretical Computer Science*, 745:36–52, 2018. doi:10.1016/j.tcs.2018.05.029.
- [4] D. Bienstock. Some provably hard crossing number problems. *Discrete & Computational Geometry*, 6:443–459, 1991. doi:10.1007/BF02574701.
- [5] D. Bienstock and N. Dean. New results on rectilinear crossing numbers and plane embeddings. *Journal of Graph Theory*, 16(5):389–398, 1992. doi:10.1002/jgt.3190160502.
- [6] D. Bienstock and N. Dean. Bounds for rectilinear crossing numbers. *Journal of Graph Theory*, 17(3):333–348, 1993. doi:10.1002/jgt.3190170308.
- [7] C. Buchheim, M. Chimani, C. Gutwenger, M. Jünger, and P. Mutzel. Crossings and planarization. In R. Tamassia, editor, *Handbook on Graph Drawing and Visualization*, pages 43–85. CRC Press, 2013. doi:10.1201/b15385-5.
- [8] O. Cheong, S. Har-Peled, H. Kim, and H.-S. Kim. On the number of edges of fan-crossing free graphs. *Algorithmica*, 73(4):673–695, 2014. doi:10.1007/s00453-014-9935-z.
- [9] M. Chimani, P. Kindermann, F. Montecchiani, and P. Valtr. Crossing numbers of beyond-planar graphs. In *Proceedings of the 27th International Symposium on Graph Drawing and Network Visualization (GD 2019)*, LNCS 11904, pages 78–86, 2019. doi:10.1007/978-3-030-35802-0_6.
- [10] W. Didimo, P. Eades, and G. Liotta. Drawing graphs with right angle crossings. *Theoretical Computer Science*, 412(39):5156–5166, 2011. doi:10.1016/j.tcs.2011.05.025.
- [11] W. Didimo, G. Liotta, and F. Montecchiani. A survey on graph drawing beyond planarity. *ACM Computing Surveys*, 52(1):1–37, 2019. doi:10.1145/3301281.
- [12] J. Fox, J. Pach, and A. Suk. Approximating the rectilinear crossing number. *Computational Geometry*, 81:45–53, 2019. doi:10.1016/j.comgeo.2019.04.003.
- [13] M. Garey and D. S. Johnson. Crossing number is NP-complete. *SIAM Journal on Algebraic and Discrete Methods*, 4(3):312–316, 1983. doi:10.1137/0604033.
- [14] S.-H. Hong and T. Tokuyama. *Beyond planar graphs*. Springer, 2020. doi:10.1007/978-981-15-6533-5.
- [15] S. G. Kobourov, S. Pupyrev, and B. Saket. Are crossings important for drawing large graphs? In *Proceedings of the 22nd International Symposium on Graph Drawing (GD 2014)*, volume 8871 of LNCS, pages 234–245. Springer, 2014. doi:10.1007/978-3-662-45803-7_20.
- [16] J. Pach, R. Pinchasi, M. Sharir, and G. Tóth. Topological graphs with no large grids. *Graphs and Combinatorics*, 21(3):355–364, 2005. doi:10.1007/s00373-005-0616-1.
- [17] H. Purchase. Which aesthetic has the greatest effect on human understanding? In *Proceedings of the 5th International Symposium on Graph Drawing (GD 1997)*, volume 1353 of LNCS, pages 248–261. Springer, 1997. doi:10.1007/3-540-63938-1_67.

- [18] H. C. Purchase, R. F. Cohen, and M. I. James. An experimental study of the basis for graph drawing algorithms. *Journal of Experimental Algorithmics*, 2:1–17, 1997. doi:10.1145/264216.264222.
- [19] M. Schaefer. Complexity of some geometric and topological problems. In *Proceedings of the 17th International Symposium on Graph Drawing (GD 2009)*, volume 5849 of *LNCS*, pages 334–344. Springer, 2009. doi:10.1007/978-3-642-11805-0_32.
- [20] M. Schaefer. *Crossing numbers of graphs*. CRC Press, 2018. doi:10.1201/9781315152394.
- [21] F. Shahrokhi, O. Sýkora, L. A. Székely, and I. Vrt'o. Book embeddings and crossing numbers. In *Proceedings of the 20th International Workshop on Graph-Theoretic Concepts in Computer Science (WG 1994)*, LNCS 903, pages 256–268, 1995. doi:10.1007/3-540-59071-4_53.
- [22] C. Thomassen. Rectilinear drawings of graphs. *Journal of Graph Theory*, 12(3):335–341, 1988. doi:10.1002/jgt.3190120306.
- [23] J. C. Urschel and J. Wellens. Testing gap k-planarity is NP-complete. *Information Processing Letters*, 169(106083), 2021. doi:10.1016/j.ip1.2020.106083.
- [24] C. Ware, H. Purchase, L. Colpoys, and M. McGill. Cognitive measurements of graph aesthetics. *Information Visualization*, pages 103–110, 2002. doi:10.1057/palgrave.ivs.9500013.