


The instrumented magnets for the OPERA experiment: construction and commissioning

- Construction (2003-2005)
- Characterization of the iron
- Electric and magnetic characterization
- Thermal behaviour
- First run: August 2006
- Conclusion

R. Adinolfi Falcone, A. Bergnoli, A. Cazes, A. Cecchetti, B. Dulach, A. Garfagnini, F. Grianti, M. Incurvati, A. Mengucci, D. Orecchini, L. Pellegrino, C. Sanelli, M. Spinetti, [F. Terranova](#), M. Ventura, L. Votano

Magnetic spectrometer




Targets
(31TT+31Walls/SM)


Magnetic Spectrometers
(Magnet + RPC + Drift Tubes)

Its role in OPERA: muon charge identification to suppress charm background; muon momentum measurement and hadron calorimetry (complete the kinematic reconstruction of tau candidates); beam spectrum reconstruction, physics of cosmic rays etc.

Why a gapless dipolar magnet?



- Uniform field along the slabs
- 1dim high precision trackers
- A very robust structure to hold the neutrino target (bricks and scintillators)
- Dead zones (return yokes) with strongly varying field
- Relatively high fringe field in the surrounding area (PMT's!!)



Construction



Start of the works in Hall C: summer 2003



**END OF MAGNET
INSTALLATION: June 2005**

**END OF INFRASTRUCTURE
INSTALLATION: February 2006**


**FIRST SWITCHING ON: MARCH
2006**

**END OF COOLING SYSTEM
INSTALLATION: MAY 2006**

Steel properties

Element	Spec.	Slab steel	Yoke steel
C	<0.080	0.08 ± 0.01	0.004 ± 0.002
P	<0.025	0.011 ± 0.003	0.003 ± 0.001
S	<0.010	0.005 ± 0.003	0.005 ± 0.002
Mn		1.24 ± 0.13	0.24 ± 0.02
Si		0.20 ± 0.03	0.84 ± 0.03
B	<0.0005	< 0.0001	0.00016 ± 0.00005


Mechanical specs played a crucial role to determine the magnetic response of the steel



Slabs

Prototype

Return yokes



UNITS
 Length: mm
 Mass: kg
 Temperature: °C
 Time: s
 Force: N
 Energy: J

PROBLEM DATA
 Volume: 1.000000e+003
 TOPOLOGY
 Magnets: 1
 Simulation No 1 of 1
 242000 elements
 272000 nodes
 Node 1: 1

LOCAL COORDS:
 Global = 0.0
 Local = 0.0
 X = 0.0
 Y = 0.0
 Z = 0.0


OPERA-3d
 Version 3.11

Driving coils and power supplies

Current: 1600A

Coil: copper bar 100x20 mm² [careful machining, golden deposition to assure proper electric connections, $R=8\text{ m}\Omega$ at $T=55\text{ deg}$], 20x2 turns, 800m



Power supplies: 2 quadrant AC \rightarrow DC, current stable below 0.1%, max 1700A 20V, designed and built by EEI Vicenza




Inductive response

During ramp-up the inductance ($L \div dB/dH$) changes by order of magnitudes

The power supplies cannot change continuously the sign of the voltage, hence during rampdown ($di/dt < 0$) they miss $di/dt = \text{const}$ at time T when $Ri + Ldi/dt$ becomes negative. For $t > T$ the circuit discharged at its natural speed (L/R)



Nominal current



$t(1=0.05s)$

Measurement of magnetic field






Techniques:

- ✓ Pick up coils along the height and the slabs \Rightarrow absolute calibration

$$V = -\frac{d\Phi(t)}{dt} = -SN \frac{d}{dt} \langle B \rangle$$

$$\frac{-1}{SN} = \int_0^t dt' V(t') = \langle B(t) \rangle - \langle B(0) \rangle$$

- ✓ Hall probes in air to monitor relative variations and validate the simulation




Results:

- ✓ Field uniformity within specs
- ✓ Flux deficit of about 4% (machining and air gaps)
- ✓ Two magnets identical within 1%


Water cooling system

Standalone system with:

- A primary circuit connected to an external chiller (outside the experimental hall): 80 kW cooling power
- Secondary circuit to water cool the coils (20 kW per magnet)
- Secondary circuit with DEMI water ($<10 \mu\text{S}/\text{cm}$) to cool PS
- Water cooling of electronics racks





Temperature measurement





Temperature of the coil: 40-80 degree

Temperature of the RPC: 20-23 degree (2 weeks of data taking)



August run with CNGS

- Livetime of magnets: 100% (magnet1), 95% (magnet 2)
- Coil temperature stable after 40 hours, RPC after 7 days
- Reconstructed events: mainly μ^- (obviously...). Reconstructed CNGS spectrum still not released by the Collaboration...



Conclusions

- The two ~1 kton magnets for OPERA are fully operative since July 2006
- No anomalies observed in the load (resistance and inductive response during ramp-up): we can run at nominal current and measure the field using pickup coils.
- Minimum field (center of the slab) is 1.49 ± 0.01 T (Average 1.52 T)
Expected for ideal mechanical contacts: 1.55 T (Average 1.575 T)
The two magnets are equal within 1%
- August run:
 - (a) Livetime: 100% (magnet1), 95% (magnet 2)
 - (b) Coil temperature stable in 40 h. Cooling seems appropriate to keep RPC temperature below 25 degree.
 - (c) First look at momentum reconstruction seems OK (in progress)

All in all, a pretty good success