


Geosyntec[®]

consultants

TVA Kingston Peninsula Disposal Site Project Challenges Developing Over Karst Formations

Authors:


Mehmet Iscimen, P.E.; Sarah B. Fick; Cuneyt Gokmen, P.E.;
Neil Davies, P.E.; Rachel Burnette-Combs; Scott Turnbow



engineers | scientists | innovators

TVA








GYPSUM DISPOSAL AREA
Dec. 15, 2010 Drop-out




- Project Challenges
- Site Investigation
 - Site Geology
 - Root-Cause Analysis
- Drop-out Investigation & Mitigation
 - Over-excavation and identification
 - Repair effort
- Liner and Drainage Systems
 - Redesigned improved system
 - Ongoing work and research

Project Challenges

- Plant's power generation schedule
 - In <1 year, (i) identify root cause of the subsidence, (ii) develop a corrective action plan, (iii) receive approval of multiple departments within TVA and TDEC, and (iv) implement the construction on a schedule that had no flexibility for delays, due to power demand and operational constraints.
- Complex site geology
 - mainly alluvial residuum soils overlying Knox Group bedrock formation susceptible to the development of karst features and drop-outs.
- Plant operational demands
 - wet to dry transition of CCRs at KIF
 - a dewatering facility for the gypsum was in construction => design and construct a hybrid disposal facility that would meet future dry disposal regulatory requirements, while still being able to operate as a wet disposal facility during the transition.
- Characteristics of CCRs (e.g., wet vs. dry processing, fly ash vs. gypsum, etc.)
 - Particle size compatibility with selected filter media, granular filter thickness, and construction practices => effectiveness of filter and drainage systems / partial or complete clogging.





For illustration Only
Not to Scale


Previous and Post Drop-out Site Investigations

- **Previous Studies**
 - (1) 15 exploratory borings and 4 seismic refraction surveys by Singleton Materials Engineering Lab (1988); (2) 6 soil borings and 2 bedrock corings by Mactec (2003); (3) 55 geoprobe borings by TVA (2003 and 2005); (4) 26 soil borings, 14 bedrock corings, 13 monitoring wells, and 10 cone penetration tests by Mactec (2005); (5) 26 soil borings and 3 monitoring wells by Mactec (2006).
- **Post Drop-out Studies**
 - Geotechnical Exploration of the Drop-out Area
 - 14 piezocone (CPTu) and 7 seismic cone penetration test (SCPTu) to depths ranging from about 4.4 feet to about 43.8 feet.
 - Shelby tubes
 - Five temporary piezometers were set in five of the CPT sounding holes.
 - Dye-Trace Study
 - Additional Environmental Sampling and Groundwater Level Data Collection
 - Investigation/Repair of the Drop-out
 - Overall Landfill Inspection
 - Overall Subsurface Investigation and Repair Program
 - Over-excavation and Drop-out Mitigation

Dec. 15, 2010 Drop-out



- Incremental excavation to soil/bedrock interface
- Nominal dimension of 3.3 inches



- Dye trace injection piping installed
- Dye injection completed Feb 7, 2011





BACKGROUND
Scope of Work – Phase IA



- Conventional drilling
- Geophysical methods
- Dynamic compaction
- Over-excavation & proof-rolling

Combined with a robust:

- Liner system
- Drainage system

- Over-excavate seven (7) feet or more below the liner level;
- Proof-roll the bottom of over-excavation with heavy equipment; and
- Back-fill with compacted soil to reach liner grades and establish a “**bridging layer**” .

Note that:

- Seventy percent - over-excavation (i.e., in those areas where liner grades are below the predevelopment grades and/or the distance between the liner grades and the predevelopment grades are less than seven (7) feet). In these areas, overburden soil was over-excavated generally 7 feet or more below liner grade, excavation bottom was proof-rolled, and then excavation area was backfilled with compacted soil to reach liner grades; and
- Thirty percent - filling and compaction efforts to establish liner grades (i.e., in those areas where liner grades are 7-ft or more above the predevelopment grades—areas outside the over-excavation zones—received seven (7) feet or more compacted fill material to establish the liner grades and thus they had already been proof-rolled during filling and compaction efforts.

Mine Subsidence Model





Figure. Mine Subsidence Schematic Model

Void Propagation Spreadsheet.
Shallow Void; D=6 ft

h = 7 ft (Depth to Top of Void - Bridging Layer Thickness)
 h_{fill} = 55.58 deg (Ground Loss Factor)
 $h_{\text{fill}} \cdot D$ = 5.25 ft (Diameter of Hemispherical Void)
 d = 3 ft (Depth to Bottom of Hemispherical Void)
 h_{void} = 10 ft (Height of the Void - Radius of Hemispherical Void)
 P_{soil} = Ratio of volume of settlement trough to the original void i.e., $P_{\text{soil}}=0.5$ for overburden soil bulks by a factor of 2 to fill void, $P_{\text{soil}}=0.67$ for overburden soil bulks by a factor of 1.5 to fill void, $P_{\text{soil}}=0.80$ for overburden soil bulks by a factor of 1.25 to fill void
 s = settlement at the surface at centerline (ft)
 x = Horizontal distance at liner from the centerline along x-axis (ft)
 y = Horizontal distance at liner from the centerline along y-axis (ft)



x (ft)	y (ft)	s (ft)	Strain at liner (%)
0	0	1.084961	2.38175E-05
0.005	0.005	1.084956	0.000214933
0.01	0.01	1.084941	0.000592404
0.015	0.015	1.084917	0.001186205
0.02	0.02	1.084883	0.002048109
0.025	0.025	1.084832	0.003231552
0.03	0.03	1.084772	0.004803509
0.04	0.04	1.084646	0.006873564
0.045	0.045	1.084566	0.008673564
0.05	0.05	1.084473	0.008500789
0.055	0.055	1.08437	0.010493578
0.06	0.06	1.084258	0.012483712
0.065	0.065	1.084136	0.014463956
0.07	0.07	1.084005	0.017333049
0.075	0.075	1.083863	0.0211995072
0.08	0.08	1.083712	0.022838664
0.085	0.085	1.083551	0.025879519
0.09	0.09	1.083381	0.029091096
0.095	0.095	1.0832	0.031500708
0.1	0.1	1.08301	0.036098269
0.105	0.105	1.082811	0.039978272
0.11	0.11	1.082601	0.043346296
0.115	0.115	1.082381	0.047179383
0.12	0.12	1.082151	0.051488103
0.125	0.125	1.081912	0.056186303
0.13	0.13	1.081667	0.061289162
0.135	0.135	1.081409	0.066802079
0.14	0.14	1.081141	0.072733998
0.145	0.145	1.080864	0.079093842
0.15	0.15	1.080577	0.085882385
0.155	0.155	1.080281	0.087847934
0.16	0.16	1.079975	0.093864702
0.165	0.165	1.079659	0.099627846
0.17	0.17	1.079334	0.105282024
0.175	0.175	1.078999	0.111247463
0.18	0.18	1.078654	0.118660351
0.185	0.185	1.0783	0.125333051
0.19	0.19	1.077936	0.132207111
0.195	0.195	1.077563	0.139246758
0.2	0.2	1.077178	0.146466198
0.205	0.205	1.076786	0.153885962
0.21	0.21	1.076388	0.161446395
0.215	0.215	1.075984	0.169107679
0.22	0.22	1.075564	0.177055379
0.225	0.225	1.075133	0.185145232
0.23	0.23	1.074683	0.193426726





DATA TRUNCATED FOR PAGE OF PRESENTATION




Table. Maximum Strain vs Void Size


Shallow Voids			Deep Voids		
H (Bridging Layer Thickness) = 7 ft			H (Bridging Layer Thickness) = 38.5 ft		
Void Diameter [ft]	Maximum Settlement [ft]	Maximum Strain [%]	Void Diameter [ft]	Maximum Settlement [ft]	Maximum Strain [%]
1	0.0152	0.0023	10	0.3997	0.0421
2	0.0922	0.0646	20	2.0802	0.7387
3	0.2443	0.3553	30	4.9298	2.8822
4	0.4666	1.0406	40	8.6537	6.4628
5	0.7499	2.1989	50	13.0179	11.0212
6	1.0850	3.8227	60	17.8568	16.0765
7	1.4635	5.8505			
8	1.8788	8.1979			
9	2.3250	10.7779			
10	2.7975	13.5122			




BACKGROUND
Phase IA Typical Cross-Section




BEFORE




AFTER











1// Shot Rock

as needed & graded with
No.4 stone (typ.)




2// Geotextile (GT) & Soil Fill



18 in. loose soil lifts (typ.)




**3// Alternating Lifts of Soil
Fill & GT**
fill to base of excavated area
~3-5 lifts (typ)




LINER SYSTEM




Before





After





PolyLock™




DRAINAGE SYSTEM Designing for CCRs










AGGREGATE FILTER

- Capacity
- Redundancy


SYNTHETIC FILTER

- Cost
- Airspace / Storage


**DRAINAGE SYSTEM
Laboratory Confirmed (Phase I)**



PHASE II




PHASE III




- Next stage of tests with fly ash
- Optimization of filter and drainage layers

PHASE II



PHASE III







*Incoming Gypsum Slurry
(during initial wet operation)*

Filtered Gypsum Leachate



**AMERICAN COUNCIL OF
ENGINEERING COMPANIES
(ACEC) GEORGIA**

**2014 ENGINEERING
EXCELLENCE GRAND AWARD**


Grand Award
Georgia Engineers Week
2014 Engineering Excellence
Presented by the
American Council of
Engineering Companies of Georgia
to
Geosyntec Consultants, Inc.
for
TVA Kingston Peninsula
Disposal Site
Roane County, Tennessee
February 15, 2014


THANK YOU!

QUESTIONS?

