

NUCLEAR SCIENCE DIVISION

1995-1996 ANNUAL REPORT

February 1997

Division Director

Lee S. Schroeder

Division Deputy

Janis M. Dairiki

Editor

Arthur M. Poskanzer

Assistant Editors

Georgia Fujikawa

Bill King

Sherrill L. Whyte

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

MASTER

Ernest Orlando Lawrence Berkeley National Laboratory
University of California, Berkeley, California 94720

This work was supported by the Director, Office of Energy Research, Office of High Energy and Nuclear Physics, Division of Nuclear Physics, and by the Office of Basic Energy Sciences, Division of Nuclear Sciences, of the U. S. Department of Energy under Contract No. DE-AC03-76SF00098.

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISCLAIMER

**Portions of this document may be illegible
in electronic image products. Images are
produced from the best available original
document.**

Table of Contents

Introduction	1
<i>L.S. Schroeder</i>	
Overviews	5
Nuclear Structure and Reactions Program	7
<i>L.S. Schroeder</i>	
Institute for Nuclear and Particle Astrophysics	14
<i>R.G. Stokstad</i>	
Relativistic Nuclear Collisions Program	20
<i>H.G. Ritter</i>	
Nuclear Theory Program	31
<i>J. Randrup</i>	
Nuclear Data Evaluation Program: Isotopes Project	35
<i>J.M. Dairiki</i>	
88-Inch Cyclotron Operations	41
<i>C.M. Lyneis</i>	
Group Lists	49
Nuclear Structure and Reactions	55
Beta-Delayed Proton Decay of ^{27}P	57
<i>T.J. Ognibene, J. Powell, D.M. Moltz, M.W. Rowe, and J. Cerny</i>	
Proton Capture on ^7Be and the Solar Neutrino Problem	58
<i>J. Powell, D.M. Moltz, M.W. Rowe, and Joseph Cerny</i>	
Search for Proton Decay from an Isomer of ^{77}Rb with RAMA	59
<i>M.W. Rowe, D.M. Moltz, J. Powell, and J. Cerny</i>	
Calibration of Low-Energy Particle-Identification Telescopes	60
<i>M.W. Rowe, D.M. Moltz, T.J. Ognibene, J. Powell, and J. Cerny</i>	
Gas Phase Chromatography of FrBr and BiBr_3	61
<i>E.R. Sylwester, D.C. Hoffman, J. Adams, Y.H. Chung, K.E. Gregorich, M.B. Hendricks, M.R. Lane, C. Laue, D.M. Lee, C.A. McGrath, D.A. Shaughnessy, D.A. Strellis, and P.A. Wilk</i>	
Gas Phase Chromatography of HfBr_4	62
<i>E.R. Sylwester, D.C. Hoffman, J. Adams, Y.H. Chung, K.E. Gregorich, M.B. Hendricks, M.R. Lane, C. Laue, D.M. Lee, C.A. McGrath, D.A. Shaughnessy, D.A. Strellis, and P.A. Wilk</i>	
Gas Phase Chromatography of WBr_6	63
<i>E.R. Sylwester, D.C. Hoffman, J. Adams, Y.H. Chung, K.E. Gregorich, M.B. Hendricks, M.R. Lane, C. Laue, D.M. Lee, C.A. McGrath, D.A. Shaughnessy, D.A. Strellis, and P.A. Wilk</i>	

Chemical Studies of Rutherfordium (Element 104)	64
<i>C.D. Kacher, K.E. Gregorich, D.M. Lee, B. Kadkhodayan, S.A. Kreek, M.R. Lane, M.F. Mohar, M.P. Neu, N.J. Stoyer, E.R. Sylwester, Y. Watanabe, B. Wierczinski, A. Bilewicz, and D.C. Hoffman</i>	
First Chemical Separations of Seaborgium (Element 106)	65
<i>K.E. Gregorich, D.C. Hoffman, E.R. Sylwester, D.M. Lee, and the LBNL, GSI, Mainz, Dresden, Krakow, JAERI, PSI, Bern, Rossendorf, JINR, Oslo, and Chalmers Collaboration</i>	
Production and Decay of ^{265}Sg and ^{266}Sg	66
<i>K.E. Gregorich, B. Kadkhodayan, B. Wierczinski, D.M. Lee, C.D. Kacher, D.A. Shaughnessy, M.R. Lane, E.R. Sylwester, M.B. Hendricks, N.J. Stoyer, A.C. Veeck, and D.C. Hoffman</i>	
A Search for ^{264}Sg	67
<i>C.A. McGrath, K.E. Gregorich, D.M. Lee, M.R. Lane, E.R. Sylwester, D.A. Shaughnessy, M.B. Hendricks, D.A. Strellis, P.A. Wilk, and D.C. Hoffman</i>	
Electronics for On-Line Liquid Scintillation α-Particle Spectroscopy	68
<i>K.E. Gregorich</i>	
Improved Half-Life Measurement of ^{224}Pa and its $^{209}\text{Bi}(^{18}\text{O},3n)^{224}\text{Pa}$ Production Cross Section	69
<i>P.A. Wilk, K.E. Gregorich, M.B. Hendricks, M.R. Lane, D.M. Lee, C.A. MacGarth, D.A. Shaughnessy, D.A. Strellis, E.R. Sylwester, and D.C. Hoffman</i>	
Off-Line Generation of ^{233}Pa and the ^{227}Pa Yield Through SISAK	70
<i>P.A. Wilk and D.C. Hoffman</i>	
Production of ^{211}Bi from the Reaction of ^{209}Bi with ^{22}Ne Projectiles	71
<i>Y.H. Chung, K.E. Gregorich, D.M. Lee, and D.C. Hoffman</i>	
Production Cross Sections for ^{254}Fm and ^{256}Fm in $^{248}\text{Cm} + ^{22}\text{Ne}$ Reactions	72
<i>M.B. Hendricks, R.J. Wallsgrove, K.E. Gregorich, M.R. Lane, D.M. Lee, D.A. Shaughnessy, D.A. Strellis, E.R. Sylwester, P.A. Wilk, and D.C. Hoffman</i>	
Production of Neutron Difficient Plutonium Isotopes	73
<i>M.B. Hendricks, K.E. Gregorich, M.R. Lane, D.M. Lee, D.A. Shaughnessy, D.A. Strellis, E.R. Sylwester, P.A. Wilk, and D.C. Hoffman</i>	
Electron-Capture Delayed Fission of ^{242}Es	74
<i>D.A. Shaughnessy, K.E. Gregorich, M.B. Hendricks, M.R. Lane, D.M. Lee, D.A. Strellis, E.R. Sylwester, P.A. Wilk, and D.C. Hoffman</i>	
Electron-Capture Delayed Fission Study of ^{246}Es	75
<i>D.A. Shaughnessy, K.E. Gregorich, M.B. Hendricks, M.R. Lane, D.M. Lee, C.A. McGrath, D.A. Strellis, E.R. Sylwester, P.A. Wilk, and D.C. Hoffman</i>	
Design of a Sample Changer/Transport System to be used for Gammasphere Studies on Electron-Capture Delayed Fission	76
<i>D.A. Strellis, K.E. Gregorich, Y.H. Chung, M.R. Lane, E.R. Sylwester, M.B. Hendricks, D.A. Shaughnessy, C.A. McGrath, P.A. Wilk, D.M. Lee, and D.C. Hoffman</i>	
Confirmation of the Assignment of a 1.5-Second Fission Activity to ^{259}Fm	77
<i>C.A. McGrath, K.E. Gregorich, D.M. Lee, M.R. Lane, E.R. Sylwester, D.A. Shaughnessy, M.B. Hendricks, D.A. Strellis, B. Wierczinski, and D.C. Hoffman</i>	

Spontaneous Fission Properties of ^{262}Rf	78
<i>M.R. Lane, K.E. Gregorich, D.M. Lee, M.F. Mohar, M. Hsu, C.D. Kacher, B. Kadkhodayan, M.P. Neu, N.J. Stoyer, E.R. Sylwester, J.C. Yang, and D.C. Hoffman</i>	
Spontaneous Fission Reviews	79
<i>D.C. Hoffman, T.M. Hamilton, and M.R. Lane</i>	
Relative Deformations of Superdeformed Bands in $^{131,132}\text{Ce}$	80
<i>R.M. Clark, I.Y. Lee, P. Fallon, D.T. Joss, S.J. Asztalos, J.A. Becker, L. Bernstein, B. Cederwall, M.A. Deleplanque, R.M. Diamond, L.P. Farris, K. Hauschild, W.H. Kelly, A.O. Macchiavelli, P.J. Nolan, N. O'Brien, A.T. Semple, F.S. Stephens, and R. Wadsworth</i>	
Low-Spin Termination of the Superdeformed Band in ^{135}Nd	81
<i>M.A. Deleplanque, S. Frauendorf, R.M. Clark, R.M. Diamond, F.S. Stephens, J.A. Becker, M.J. Brinkman, B. Cederwall, P. Fallon, L.P. Farris, E.A. Henry, H. Hübel, J.R. Hughes, W. Korten, I.Y. Lee, A.O. Macchiavelli, M.A. Stoyer, P. Willsau, J.E. Draper, C. Duyar, and E. Rubel</i>	
Proton Superdeformed Bands below the $Z=80$ Gap in ^{191}Au: More Evidence for Pseudo-Spin Coupling	82
<i>C. Schüick, E. Gueorguieva, A. Lopez-Martens, F. Hannachi, Ch. View, M. Kaci, J.S. Dionisio, W.H. Kelly, M.A. Deleplanque, F.S. Stephens, B. Kharraja, B.J.P. Gall, A. Korichi, U.J. van Severen, W. Pohler, B. Schulze, H. Hübel, and R. Wadsworth</i>	
Confirmation of a Superdeformed Band in ^{192}Pb	83
<i>S.J. Asztalos, P. Fallon, J.A. Becker, L.A. Bernstein, R.M. Clark, M.A. Deleplanque, R.M. Diamond, L.P. Farris, E.A. Henry, W.H. Kelly, I.Y. Lee, A.O. Macchiavelli, and F.S. Stephens</i>	
Octupole Vibrations and Signature Splitting in Even Mass Hg Superdeformed Bands	84
<i>P. Fallon, F.S. Stephens, S. Asztalos, B. Busse, R.M. Clark, M.A. Deleplanque, R.M. Diamond, R. Krücken, I.Y. Lee, A.O. Macchiavelli, R.W. MacLeod, G. Schmid, K. Vetter, and T. Nakatsukasa</i>	
Relative Quadrupole Moments of $^{192,193}\text{Hg}$ Superdeformed Bands	85
<i>B.C. Busse, P. Fallon, R. Krücken, D. Ackermann, I. Ahmad, S.J. Asztalos, D.J. Blumenthal, M.P. Carpenter, R.M. Clark, M.A. Deleplanque, R.M. Diamond, S.M. Fischer, F. Hannachi, R.V.F. Janssens, T.L. Khoo, A. Korichi, T. Lauritsen, I.Y. Lee, C.J. Lister, A. Lopez-Martens, A.O. Macchiavelli, R.W. MacLeod, E.F. Moore, D. Nisius, G. Schmid, D. Seweryniak, F.S. Stephens, and K. Vetter</i>	
Test of $\Delta I = 2$ Staggering in the Superdeformed Bands of ^{194}Hg	86
<i>R. Krücken, G. Hackman, M.A. Deleplanque, R.V.F. Janssens, D. Ackermann, S. Asztalos, R.M. Clark, R.M. Diamond, P. Fallon, B. Herskind, T.L. Khoo, T. Lauritsen, I.Y. Lee, A.O. Macchiavelli, R.W. MacLeod, G.J. Schmid, F.S. Stephens, and K. Vetter</i>	
Discrete SD–ND Linking Transitions from the Yrast Superdeformed Band in ^{194}Pb: J^π and E_x	87
<i>K. Hauschild, L.A. Bernstein, J.A. Becker, D.E. Archer, R.W. Bauer, D.P. McNabb, J.A. Cizewski, K.-Y. Ding, W. Younes, R. Krücken, R.M. Diamond, R.M. Clark, P. Fallon, I.-Y. Lee, A.O. Macchiavelli, R. MacLeod, G.J. Schmid, M.A. Deleplanque, F.S. Stephens, and W.H. Kelly</i>	

The Decay of the Superdeformed Band in ^{194}Pb: Electromagnetic Properties	88
<i>R. Krücken, S.J. Asztalos, J.A. Becker, B. Busse, R.M. Clark, M.A. Deleplanque, A. Dewald, R.M. Diamond, P. Fallon, K. Hauschild, I.Y. Lee, A.O. Macchiavelli, R.W. MacLeod, R. Peusquens, G.J. Schmid, F.S. Stephens, K. Vetter, and P. von Brentano</i>	
Evidence for 'Magnetic Rotation': Lifetimes of States in the M1-Bands of $^{198,199}\text{Pb}$	89
<i>R.M. Clark, S.J. Asztalos, G. Baldsiefen, J.A. Becker, L. Bernstein, M.A. Deleplanque, R.M. Diamond, P. Fallon, I.M. Hibbert, H. Hübel, R. Kürcken, I.Y. Lee, A.O. Macchiavelli, R.W. MacLeod, G. Schmid, F.S. Stephens, and R. Wadsworth</i>	
Search for Two-Phonon Octupole Vibrational States in ^{208}Pb	90
<i>K. Vetter, A.O. Macchiavelli, S.J. Asztalos, R.M. Clark, M.A. Deleplanque, R.M. Diamond, P. Fallon, R. Krücken, I.Y. Lee, R.W. MacLeod, G.J. Schmid, and F.S. Stephens</i>	
Study of Neutron-Rich Nuclei Using Deep-Inelastic Reactions	91
<i>I.Y. Lee, S. Asztalos, M.A. Deleplanque, B. Cederwall, R.M. Diamond, P. Fallon, A.O. Macchiavelli, L. Phair, F.S. Stephens, G.J. Wozniak, S.G. Frauendorf, J.A. Becker, E.A. Henry, P.F. Hua, D.G. Sarantites, J.X. Saladin, and C.H. Yu</i>	
A Measurement of the Gamma Ray Polarization Sensitivity of Gammasphere	92
<i>G.J. Schmid, A.O. Macchiavelli, M.A. Deleplanque, S. Asztalos, R.M. Clark, R.M. Diamond, P. Fallon, R. Krücken, I.Y. Lee, R.W. MacLeod, F.S. Stephens, and K. Vetter</i>	
Multiparticle-Rotor Model for Rotational Band Structure of ^{154}Gd	93
<i>S.Y. Chu, J.O. Rasmussen, and M.A. Stoyer</i>	
Models for Rotational Spin Distributions of Primary Fission Products	94
<i>J.O. Rasmussen, S.Y. Chu, D. Strellis, S. Asztalos, R. Donangelo, L.F. Canto, J.D. Cole, M.A. Stoyer, Y.X. Dardenne, and J.H. Hamilton</i>	
Multiband Theory for Heavy-Ion Neutron-Pair Transfer among Deformed Gd Nuclei	95
<i>S.Y. Chu, J.O. Rasmussen, M.A. Stoyer, P. Ring, L.F. Canto, and R. Donangelo</i>	
Form Factors for Two-Nucleon Transfer in the Diabolical Region of Rotating Nuclei	96
<i>A.R. Farhan, L.F. Canto, J.O. Rasmussen, and P. Ring</i>	
The 8th Edition of the Table of Isotopes	97
<i>R.B. Firestone, V.S. Shirley, C.M. Baglin, S.Y.F. Chu, and J. Zipkin</i>	
The Isotope Explorer	98
<i>S.Y.F. Chu, H. Nordberg, L.P. Ekstrom, and R.B. Firestone</i>	
Nuclear Data on the Internet	99
<i>R.B. Firestone, S.C. Wu, and S.Y.F. Chu</i>	
Superdeformed and High-Spin Nuclear Structure Data on the Internet	100
<i>B. Singh, R.B. Firestone, and S.Y.F. Chu</i>	
Reducibility and Thermal Scaling in Nuclear Multifragmentation	101
<i>L.G. Moretto, R. Ghetti, L. Phair, K. Tso, and G.J. Wozniak</i>	
Aspects of Reducibility and Thermal Scaling in Multifragmentation	102
<i>R. Ghetti, L.G. Moretto, L. Phair, K. Tso, and G.J. Wozniak</i>	

Reducibility, Thermal and Mass Scaling in Angular Correlations from Multifragmentation Reactions	103
<i>L. Phair, L.G. Moretto, G.J. Wozniak, R.T. de Souza, D.R. Bowman, N. Carlin, C.K. Gelbke, W.G. Gong, Y.D. Kim, M.A. Lisa, W.G. Lynch, G.F. Peaslee, M.B. Tsang, and F. Zhu</i>	
Comment on "Circumstantial Evidence for Critical Behavior in Peripheral Au+Au Collisions at 35 MeV/nucleon"	104
<i>L. Phair, Th. Rubehn, L.G. Moretto, and G.J. Wozniak</i>	
Comment on "Probing the Nuclear Liquid-Gas Phase Transition"	105
<i>L.G. Moretto, R. Ghetti, L. Phair, K. Tso, and G.J. Wozniak</i>	
Stable Coulomb Bubbles?	106
<i>L.G. Moretto, K. Tso, and G.J. Wozniak</i>	
Charge Correlations and Dynamical Instabilities in Multifragmentation	107
<i>L.G. Moretto, Th. Rubehn, L. Phair, N. Colonna, G.J. Wozniak, D.R. Bowman, G.F. Peaslee, N. Carlin, R.T. de Souza, C.K. Gelbke, W.G. Gong, Y.D. Kim, M.A. Lisa, W.G. Lynch, and C. Williams</i>	
Scaling Laws, Shell Effects, and Transient Times in Fission Probabilities	108
<i>L.G. Moretto, K.X. Jing, R. Gatti, G.J. Wozniak, and R.P. Schmitt</i>	
Scaling Laws and Transient Times in ³He Induced Nuclear Fission	109
<i>Th. Rubehn, K.X. Jing, L.G. Moretto, L. Phair, K. Tso, and G.J. Wozniak</i>	
First Chance Fission Probability of Neighboring Po Isotopes	110
<i>Th. Rubehn, K.X. Jing, L.G. Moretto, L. Phair, K. Tso, and G.J. Wozniak</i>	
Transition State Rates and Mass Asymmetric Fission Barriers of Compound Nuclei ^{90,94,98}Mo	111
<i>K.X. Jing, L.G. Moretto, A.C. Veeck, N. Colonna, I. Lhenry, K. Tso, K. Hanold, W. Skulski, Q. Sui, and G.J. Wozniak</i>	
Characterization of Nuclear Physics Targets Using Rutherford Backscattering	112
<i>Th. Rubehn, G.J. Wozniak, L. Phair, L.G. Moretto, and K.M. Yu</i>	
LBNL 88-Inch Cyclotron Improvements	113
<i>C.M. Lyneis, Z.Q. Xie, and D.J. Clark</i>	
Development of Exotic Nuclear Beams at the 88-Inch Cyclotron	114
<i>D.M. Moltz, P.E. Haustein, J. Powell, E.B. Norman, M.W. Rowe, and J. Cerny</i>	
Performance of the Upgraded LBL AECR Source	115
<i>Z.Q. Xie and C.M. Lyneis</i>	
Production of Intense High Charge State Ions with an Aluminum Liner in the Advanced Electron Cyclotron Resonance Ion Source	116
<i>Z.Q. Xie and C.M. Lyneis</i>	
A Microtron Cyclotron - the Slipatron	117
<i>D.J. Clark</i>	
Non-Nuclear Science Programs at the 88-Inch Cyclotron: Part A. Space Applications	118
<i>M.A. McMahan</i>	

Non-Nuclear Science Programs at the 88-Inch Cyclotron: Part B. Biology, Physics, and New Technologies	119
<i>M.A. McMahan</i>	

Institute for Nuclear and Particle Astrophysics	121
--	------------

Sudbury Neutrino Observatory - PMT Support Structure & Panel Arrays	123
<i>K.T. Lesko, Y.D. Chan, M. Dragowsky, M. Isaac, M.E. Moorhead, E.B. Norman, A. Schuelke, and R.G. Stokstad</i>	
⁶Li Neutron Poison for SNO	124
<i>M.E. Moorhead, Y.D. Chan, M. Dragowsky, M.C. Isaac, R.M. Larimer, K.T. Lesko, E.B. Norman, A. Schuelke, and R.G. Stokstad</i>	
A 4π β-tagged Decay Chamber for Gaseous SNO Calibration Sources	125
<i>Y.D. Chan, M. Dragowsky, M.C. Isaac, K.T. Lesko, M.E. Moorhead, E.B. Norman, A. Schuelke, and R.G. Stokstad</i>	
Sudbury Neutrino Observatory, Neutral Current Detectors	126
<i>K.T. Lesko, Y.D. Chan, M. Dragowsky, M. Isaac, M.E. Moorhead, E.B. Norman, A. Schuelke, and R.G. Stokstad</i>	
Sudbury Neutrino Observatory - Contamination Control	127
<i>R.G. Stokstad, K.T. Lesko, Y.D. Chan, M. Dragowsky, M. Isaac, E. Norman, and A. Schuelke</i>	
Sudbury Neutrino Observatory, Monte-Carlo Simulations and Data Analysis	128
<i>M.E. Moorhead, Y.D. Chan, M. Dragowsky, M. Isaac, K.T. Lesko, E.B. Norman, A. Schuelke, and R.G. Stokstad</i>	
The Sudbury Neutrino Observatory: Monitoring the Experiment	129
<i>Y.D. Chan, M.C. Isaac, M. Dragowsky, K.T. Lesko, E.B. Norman, A. Schuelke, and R.G. Stokstad</i>	
Response of the SNO Detector to High Energy Gamma-Rays	130
<i>M.C. Perillo Isaac, Y.D. Chan, M. Dragowsky, D. Hurley, K.T. Lesko, R.J. McDonald, M.E. Moorhead, E.B. Norman, A. Schuelke, A.R. Smith, and R.G. Stokstad</i>	
Measurements of the High Energy Gamma-Ray Flux at SNO	131
<i>M.C. Perillo Isaac, Y.D. Chan, M. Dragowsky, D. Hurley, K.T. Lesko, R.J. McDonald, M.E. Moorhead, E.B. Norman, A. Schuelke, A.R. Smith, and R.G. Stokstad</i>	
Sudbury Neutrino Observatory: Simulation of the Calibration Decay Chamber for ¹⁶N and ¹⁷N	132
<i>M. Dragowsky, Y.D. Chan, M.C. Perillo Isaac, K.T. Lesko, M.E. Moorhead, E.B. Norman, A. Schuelke, and R.G. Stokstad</i>	
Sudbury Neutrino Observatory, Monte-Carlo Simulation and Background Studies of the PSUP	133
<i>A. Schuelke, K.T. Lesko, M. Dragowsky, Y.D. Chan, M. Isaac, E. Norman, and R. Stokstad</i>	
Sudbury Neutrino Observatory, Extending the Detector Geometry in SNOMAN for Background Investigations	134
<i>A. Schuelke, K.T. Lesko, Y.D. Chan, M. Dragowsky, M. Isaac, E. Norman, and R. Stokstad</i>	

R&D for a Km³ Neutrino Detector	135
<i>W. Chinowsky, H. Crawford, R. Fusezy, Y.D. He, S. Jackson, K. Lesko, D. Lowder, J. Ling, M. Moorhead, D. Nygren, B. Price, J. Przybylski, A. Richards, G. Shapiro, G. Smoot, L. Stevenson, R. Stokstad, and R. Tripp</i>	
Half-Life of ⁴⁴Ti	136
<i>E.B. Norman, E. Browne, Y.D. Chan, I.D. Goldman, R.-M. Larimer, K.T. Lesko, M. Nelson, F.E. Wietfeldt, and I. Zliten</i>	
Survival of ¹⁸⁰Ta During the s-Process	137
<i>R.-M. Larimer, Y.D. Chan, M.P.C. Isaac, K.T. Lesko, A.O. Macchiavelli, R.W. Macleod, M.E. Moorhead, E.B. Norman, K.S. Krane, K. Zaerpoor, J. Becker, L.A. Bernstein, and L.P. Ferris</i>	
Search for the β^+ Decay of ¹⁴⁴Pm	138
<i>K. Zaerpoor, M.R. Dragowsky, K.S. Krane, M.M. Hindi, S.J. Robinson, D.E. DiGregorio, E.B. Norman, Y.D. Chan, M.C.P. Isaac, R.-M. Larimer, A.O. Macchiavelli, and R. MacCleod</i>	
Preliminary Results from a Study of the Double Beta Decay of ¹⁵⁰Nd	139
<i>M.C. Perillo Isaac, Y.D. Chan, D. Hurley, R.J. McDonald, E.B. Norman, and A.R. Smith</i>	
Does The Lifetime of ⁴⁰K Depend Upon its Chemical State?	140
<i>E.B. Norman, M.C. Perillo-Isaac, M.E. Moorhead, R.-M. Larimer, R.J. McDonald, A.R. Smith, and E. Browne</i>	
Weak Gamma Rays in the Electron-Capture Decay of ¹⁹⁴Au	141
<i>R.R.P. Teixeira, I.D. Goldman, M.T.F. da Cruz, E. Browne, I.Y. Lee, A.O. Macchiavelli, and E.B. Norman</i>	
Nuclear Astrophysics Data Home Page	142
<i>J. Dairiki, R. Firestone, R. Stokstad, S. Woosley, and S.C. Wu</i>	
Laser Trapping Radioactive Atoms for Precise Weak Interaction Tests	143
<i>M.A. Rowe, S.J. Freedman, B.K. Fujikawa, G. Gwinner, S.-Q. Shang, P.A. Vetter, and E.G. Wasserman</i>	
Measurement of the Partial $0^+ \rightarrow 0^+$ Half Life of ¹⁰C with GAMMASPHERE	144
<i>B.K. Fujikawa, S.J. Asztalos, C.J. Bowers, R.M. Clark, M.-A. Deleplanque-Stephens, P. Fallon, S.J. Freedman, J.P. Greene, I.-Y. Lee, L.J. Lising, A.O. Macchiavelli, R.W. MacLeod, J.C. Reich, M.A. Rowe, S.-Q. Shang, F.S. Stephens, and E.G. Wasserman</i>	
Test of the Conserved Vector Current Hypothesis in the Beta-Decay of ¹⁴C	145
<i>J.L. Mortara, I. Ahmad, S.J. Freedman, B.K. Fujikawa, J.P. Greene, J.P. Schiffer, and A.R. Zeuli</i>	
Test of the Conserved Vector Current Hypothesis in the Beta-Decay of ¹⁴O	146
<i>S.J. Freedman, B.K. Fujikawa, J.L. Mortara, D.W. Ross, and D. Wutte</i>	
β-γ Directional Correlation in ²²Na	147
<i>C.J. Bowers, S.J. Freedman, B.K. Fujikawa, J.C. Reich, S.-Q. Shang, P.A. Vetter, E.G. Wasserman, and the Gammasphere Collaboration</i>	
Search for the Beta-Decay of ⁵⁴Mn	148
<i>I. Ahmad, S. Austin, S.J. Freedman, K.T. Lesko, J.L. Mortara, and A. Wuosmaa</i>	

Time Reversal Invariance Violation in Polarized Neutron Beta Decay	149
<i>L.J. Lising, S.J. Freedman, B.K. Fujikawa, E.G. Wasserman, and the emiT Collaboration</i>	
Test of Time Reversal Invariance Violation in the Beta-Decay of ^{56}Co	150
<i>J.L. Mortara, J.C. Davis, and S.J. Freedman</i>	
Atomic Parity Nonconservation in Stable Yb Isotopes	151
<i>C.J. Bowers, D. Budker, E.D. Commins, D. DeMille, S.J. Freedman, G. Gwinner, S.-Q. Shang, and J.E. Stalnaker</i>	
Experimental Study of the ^8B Neutrino Spectrum	152
<i>S.J. Freedman, K.E. Rehm, B.K. Fujikawa, G. Gwinner, B. Harss, C.L. Jiang, M. Paul, R.C. Pardo, J.P. Schiffer, S.Q. Shang, and P. Vetter</i>	
Search for Narrow Positron Emission Lines in Heavy Ion Collisions with APEX	153
<i>S. Freedman, M. Maier, as part of the APEX Collaboration</i>	
Studying New Physics Using Ultrahigh-Energy Cosmic-Ray γ-Family Data	154
<i>Y.D. He</i>	
Search for Dirac Magnetic Monopole Production in High Energy Heavy Ion Collisions	155
<i>Y.D. He and P.B. Price</i>	
Measurement of Low Energy Ion Tracks in CR-39 Plastic with an Atomic Force Microscope	156
<i>Y.D. He and C.I. Hancox</i>	
Low-background Counting Facilities	157
<i>A.R. Smith, R.J. McDonald, D.L. Hurley, and E.B. Norman</i>	
Low-background Gamma-ray Spectroscopy Applied to Measuring the Uptake of Metals by Bacteria	158
<i>A.R. Smith, R.J. McDonald, D.L. Hurley, and E.B. Norman</i>	
Low-Level Measurement of Alpha-Particle Emitters in Ceramics and Metals	159
<i>A.R. Smith, R.J. McDonald, D.L. Hurley, and E.B. Norman</i>	
Relativistic Nuclear Collisions	161
Δ Resonance Production in $^{58}\text{Ni} + \text{Cu}$ Collisions at $E=1.97 \text{ A GeV}$	163
<i>E.L. Hjort and the EOS Collaboration</i>	
Dielectron Production in A-A Reactions at 1.0 A GeV	164
<i>R.J. Porter and the DLS Collaboration</i>	
The E895 experiment at the AGS	165
<i>G. Rai and the E895 Collaboration</i>	
Rare Processes in Relativistic Heavy Ion Collisions—Results from BNL E878	166
<i>M.J. Bennett, J.B. Carroll, H. Crawford, M. Cronqvist, J. Engelage, I. Flores, L. Greiner, T.J. Hallman, H.H. Heckman, C. Kuo, and P.J. Lindstrom</i>	
Development of a Distributed Drift Chamber for BNL E896	167
<i>J. Engelage, M.J. Bennett, J.B. Carroll, H. Crawford, M. Cronqvist, I. Flores, L. Greiner, E. Judd, P.J. Lindstrom, J. Marx, I. Sakrejda, and G. Visser</i>	

Spectroscopy of Scalar Mesons with the Crystal Barrel Detector	168
<i>K.M. Crowe, T. Case, F.H. Heinsius, P. Kammel, M. Lakata, and the Crystal Barrel Collaboration</i>	
Measurement of Rare $\omega \rightarrow \eta\gamma$ Radiative Decay	169
<i>M. Lakata, K. Crowe, T. Case, P. Kammel, and F.-H. Heinsius</i>	
A Precision Measurement of Nuclear Muon Capture on ^3He	170
<i>K.M. Crowe, T. Case, and P. Kammel</i>	
Elliptic Event Shapes at the CERN SPS	171
<i>T. Wienold, I. Huang, and the NA49 Collaboration</i>	
Proton and Negative Hadron Spectra from NA49	172
<i>M. Toy, P. Jacobs, and the NA49 Collaboration</i>	
A New Method for V0 Reconstruction in NA49 CERN Experiment	173
<i>S. Margetis</i>	
K_S^0 production in Pb+Pb collisions at CERN SPS	174
<i>S. Margetis and the NA49 Collaboration</i>	
Projectile Fragmentation in Pb+Pb Collisions at 158 A-GeV	175
<i>I. Huang, S. Margetis, G. Odyniec, and the NA49 Collaboration</i>	
Fragmentation of 160 A GeV Pb in Various Targets	176
<i>Y. D. He and P. B. Price</i>	
STAR TPC System Test	177
<i>W. Betts, F. Bieser, R. Bossingham, M. Botlo, M. Cherney, J. Chrin, P. Colarco, H. Crawford, H. Diaz, K. Dao, D. Greiner, L. Greiner, E. Hjort, S. Jacobson, R.C. Jared, E. Judd, S.R. Klein, A.N. Lebedev, M.J. Levine, V. Lindenstruth, M.A. Lisa, K. Marks, C. McParland, T.S. McShane, J. Meier, M.T. Nguyen, D.L. Olson, I. Sakrejda, J. Schambach, R.A. Scheetz, N.T.B. Stone, C.E. Tull, G. Visser, C. Vu, H. Wieman, E.Yee, and the STAR Collaboration</i>	
Front End Electronics for the STAR TPC	178
<i>F.S. Bieser, J. Hunter, S.R. Klein, C. Vu, and the STAR Collaboration</i>	
Triggering in the STAR Experiment at RHIC	179
<i>E. Judd and the STAR Trigger Group</i>	
STAR Analysis Framework	180
<i>D.L. Olson, C.E. Tull, and D. Prindle</i>	
Simulations and Analysis Software for the STAR TPC	181
<i>P.M. Jacobs, M.A. Lisa, I.M. Sakrejda, N.T.B. Stone, and the STAR Collaboration</i>	
The PDSF Computing Facility at LBNL	182
<i>R.J. Porter</i>	
Development of a Micro TPC Vertex Detector	183
<i>H. Wieman, E. Beuville, M. Burks, D. Fritz, S. Margetis, F. Retiere, S. Trentalange, and R. Wells</i>	
Production and Detection of Hyperfragments in High Energy Nucleus-Nucleus Collisions	184
<i>Y.D. He and P.B. Price</i>	

Coherent Nuclear Interactions at RHIC	185
<i>S. Klein and E. Scannapieco</i>	
NSD Pre-College Educational Activities	186
<i>H.S. Matis, Chairman NSD Educational Committee</i>	
Nuclear Theory	187
Study of Medium-induced Parton Energy Loss in γ+jet Events of High-Energy Heavy-Ion Collisions	189
<i>X.N. Wang and Z. Huang</i>	
Jet Quenching in the Direction Opposite to a Tagged Photon in High-Energy Heavy-Ion Collisions	190
<i>X.N. Wang, Z. Huang, and I. Sarcevic</i>	
Dilepton and Photon Production from a Coherent Pion Oscillation	191
<i>Z. Huang and X.N. Wang</i>	
Thermal Equilibration in an Expanding Parton Plasma	192
<i>H. Heiselberg and X.N. Wang</i>	
Domain Structure of a Disoriented Chiral Condensate from a Wavelet Perspective	193
<i>Z. Huang, I. Sarcevic, R. Thews, and X.N. Wang</i>	
J/ψ Suppression in an Equilibrating Parton Plasma	194
<i>X.-M. Xu, D. Kharzeev, H. Satz, and X.N. Wang</i>	
Screening of Initial Parton Production in Ultrarelativistic Heavy-ion Collisions	195
<i>K.J. Eskola, B. Müller, and X.N. Wang</i>	
Partial $U(1)_A$ Restoration and η Enhancement in High-Energy Heavy-Ion Collisions	196
<i>Z. Huang and X.N. Wang</i>	
Study of Parton Energy Loss in High-energy Heavy-ion Collisions	197
<i>X.N. Wang</i>	
A pQCD-based Approach to Parton Production and Equilibration in High-Energy Nuclear Collisions	198
<i>X.N. Wang</i>	
Phenomenology of Charm and Bottom Production	199
<i>R. Vogt</i>	
Lepton Production from Charm Decay in Nuclear Collisions at $p\sqrt{s} = 200$ GeV and 5.5 TeV per Nucleon	200
<i>S. Gavin, P.L. McGaughey, P.V. Ruuskanen, and R. Vogt</i>	
Charm and Bottom Quark Production Cross Sections Near Threshold	201
<i>J. Smith and R. Vogt</i>	
Resummed Heavy Quark Production Cross Sections to Next-to-Leading Logarithm	202
<i>N. Kidonakis, J. Smith, and R. Vogt</i>	
Reanalysis of the EMC Charm Production Data With Extrinsic and Intrinsic Charm at NLO	203
<i>B.W. Harris, J. Smith, and R. Vogt</i>	

Charmed Hadron Asymmetries in the Intrinsic Charm Coalescence Model	204
<i>R. Vogt and S.J. Brodsky</i>	
Charmonium Suppression by Comover Scattering in Pb+Pb Collisions	205
<i>S. Gavin and R. Vogt</i>	
Transverse Momentum of ψ and Dimuon Production in Pb+Pb Collisions	206
<i>S. Gavin and R. Vogt</i>	
Systematics of Quarkonium Production	207
<i>G.A. Schuler and R. Vogt</i>	
Upsilon Suppression in Pb+Pb Collisions at the LHC?	208
<i>R. Vogt</i>	
Determining the Existence and Nature of the Quark-Gluon Plasma by Upsilon Suppression at the LHC	209
<i>J.F. Gunion and R. Vogt</i>	
Aspects of Chiral Symmetry	210
<i>V. Koch</i>	
Properties of Hadrons in the Nuclear Medium	210
<i>C.M. Ko, V. Koch, and G.Q. Li</i>	
Cold Kaons from Hot Fireballs	211
<i>V. Koch</i>	
Thermal Effects on Dilepton Production from Pion-Annihilation	212
<i>C. Song, V. Koch, S.H. Lee, and C.M. Ko</i>	
Dilepton Production in Relativistic Heavy-ion Collisions	213
<i>V. Koch and C. Song</i>	
Pion Electromagnetic Formfactor at Finite Temperature	214
<i>C. Song and V. Koch</i>	
Chemical Relaxation Time of Pions in Hot Hadronic Matter	215
<i>C. Song and V. Koch</i>	
Excess of Pions with Chiral Symmetry Restoration	216
<i>C. Song and V. Koch</i>	
Effective Mass of Phi Mesons at Finite Temperature	217
<i>C. Song</i>	
Dissipation and Decoherence in Mean Field Theory	218
<i>S. Habib, Y. Kluger, E. Mottola, and J.P. Paz</i>	
Anomalous Transverse Distribution of Pions as a Signal for Disoriented Chiral Condensates	219
<i>F. Cooper, Y. Kluger, and E. Mottola</i>	
Symmetry Breaking in $\lambda\phi^4$ Theory	219
<i>F. Cooper, S. Habib, Y. Kluger, and E. Mottola</i>	
Statistical Properties of the Linear Sigma Model	220
<i>J. Randrup</i>	
Amplification of Pionic Instabilities in High-Energy Collisions?	221
<i>J. Randrup</i>	

Mean-Field Treatment of the Linear Sigma Model in Dynamical Calculations of DCC Observables	222
<i>J. Randrup</i>	
Treatment of Pionic Modes at the Nuclear Surface for Transport Descriptions	223
<i>J. Helsingsson and J. Randrup</i>	
Simplified Treatment of Collective Instabilities in Matter	224
<i>J. Randrup</i>	
Multifragmentation with Brownian One-Body Dynamics	225
<i>A. Guarnera, Ph. Chomaz, M. Colonna, and J. Randrup</i>	
Inclusion of Quantum Fluctuations in Wave Packet Dynamics	226
<i>A. Ohnishi, and J. Randrup</i>	
Quantum Fluctuation Effects on Nuclear Fragment Formation	227
<i>A. Ohnishi and J. Randrup</i>	
Quantum Fluctuations Affect Critical Properties of Noble Gases	228
<i>A. Ohnishi and J. Randrup</i>	
K⁺ Momentum Spectrum from (K⁻,K⁺) Reactions in the Intranuclear Cascade Model	229
<i>Y. Nara, A. Ohnishi, T. Harada, and A. Engel</i>	
Four-Alpha Linear-Chain States in ¹⁶O	230
<i>N. Itagaki, A. Ohnishi, and K. Katō</i>	
Detectability of Strange Matter in Heavy Ion Experiments	231
<i>J. Schaffner-Bielich, C. Greiner, A. Diener, and H. Stöcker</i>	
Quark Phase Transition & Time-structure of Pulsar Spin-Down	232
<i>N.K. Glendenning, S. Pei, and F. Weber</i>	
Response of Pulsar Braking to Rotation and Internal Structure	233
<i>N.K. Glendenning, S. Pei, and F. Weber</i>	
Crystalline Structure Size in Neutron Stars	234
<i>N.K. Glendenning and S. Pei</i>	
Crystalline Cores of Neutron Stars	235
<i>N.K. Glendenning</i>	
Internal Constitution of Neutron and Strange Stars	236
<i>N.K. Glendenning</i>	
Thermal Evolution of Compact Stars	237
<i>C. Schaab, F. Weber, M.K. Weigel, and N.K. Glendenning</i>	
The Nuclear Thomas-Fermi Model	238
<i>W.D. Myers and W.J. Swiatecki</i>	
The Rotating Nuclear Thomas-Fermi Model	238
<i>W.D. Myers and W.J. Swiatecki</i>	
The Nuclear Thomas-Fermi Model with Angular Momentum: Fission Barriers, Superdeformations, Moments of Inertia	238
<i>W.D. Myers and W.J. Swiatecki</i>	

The Congruence Energy: A Contribution to Nuclear Masses, Deformation Energies and Fission Barriers	239
<i>W.D. Myers and W.J. Swiatecki</i>	
The Excitation of an Independent-Particle Gas—Classical or Quantal—by a Time-Dependent Potential Well	240
<i>J. Blocki, J. Skalski, and W.J. Swiatecki</i>	
The Excitation of an Independent-Particle Gas by a Time-Dependent Potential Well. Part II	240
<i>J. Blocki, J. Skalski, and W.J. Swiatecki</i>	
The Effect of Dynamical Correlations in a Slowly Pumped Knudsen Gas	240
<i>J. Blocki, C. Jarzynski, and W.J. Swiatecki</i>	
Seminars	241
Author Index	253

Introduction

Introduction

L.S. Schroeder

This report describes the activities of the Nuclear Science Division (NSD) for the two-year period, January 1, 1995 to January 1, 1997. This was a time of major accomplishments for all research programs in the Division—many of which are highlighted in the reports of this document.

During this period, several changes affecting the Division took place. In the fall of 1995, James Symons, the Division Director for ten very successful years, returned to full-time research. Much of the success of the Division's activities are due to his foresight and dedicated leadership at the Berkeley Lab, as well as his many contributions on the national scene. In 1996, the NSD office was relocated to the Bldg. 50 complex, along with the Relativistic Nuclear Collisions (RNC) group and the Isotopes Project. While this relocation squeezed us on space, it had the very positive benefit of providing closer ties with the other General Science areas (Accelerator Research and Fusion and Physics Divisions) also housed in the Bldg. 50 complex. Also, in the 1995–96 period, the U.S. nuclear science community revisited its long-range planning process—providing a strong road map for nuclear science research over the next few years. The NSD hosted the Town Meeting on Electroweak Interactions, Astrophysics and Non-accelerator Experiments, as part of this process. Several NSD members participated in the NSAC Long-Range planning activity at Cal Tech and in the construction of the final report. Finally, it is with great sadness that we also recognize the passing of two of our colleagues during this period—Mike Nitschke, a major force behind the national call for an ISL facility for radioactive beams, and Virginia Shirley, a key member of the Table of Isotopes team.

Much of the activity at the 88-Inch Cyclotron centers on Gammasphere and its strong research program. This period witnessed a change from the "early implementation" phase, to the "full implementation" phase of the Gammasphere program, with its nearly complete (110 elements) complement of detectors. In addition, several auxiliary detectors, provided by the Gammasphere research community, were added—making the Gammasphere suite of detectors the world's most powerful instrument for studying nuclear structure. A formal Gammasphere Dedication was held in December 1995 at the Berkeley Lab, including a meeting devoted to the early results from Gammasphere. Presently, over 250 researchers, representing universities and national laboratories from around the world, are actively engaged in this research effort, with demand for beam time running extremely high.

To further enhance the 88-Inch's low energy research program, a new instrument, the Berkeley Gas-Filled Separator (BGS) is under construction. This device, designed to provide enhanced separation capabilities, will serve as the centerpiece for a strong program in heavy element research, production of exotic nuclei and nuclear structure studies. Present plans call for BGS operation in the summer/fall of 1997.

Considerable progress has been made in the area of weak interaction studies at the 88-Inch Cyclotron. Activities include the use of Gammasphere, as well as the continued progress in the trapping of radioactive ^{21}Na atoms. The trapping facility continues to be upgraded with the number of trapped atoms reaching about 50,000—sufficient to initiate an active physics program.

Other major activities at the 88-Inch Cyclotron include: high statistics studies of the systematics (energy, target/projectile dependence) of complex fragment emission, the possibility of light (C, N, O) radioactive beams at the 88-Inch, a nuclear astrophysics program using Gammasphere as well as other devices. Finally, excellent progress has been made on a 3rd generation ECR ion source which will provide the heaviest beams at energies above the coulomb barrier for the 88-Inch research community.

During this reporting period considerable progress was made on the final assembly of the solar neutrino detector at the Sudbury Neutrino Observatory (SNO). The Berkeley SNO team has been actively involved in this effort and it is anticipated that the heavy water fill will occur in the latter half of 1997. In addition to participating in the construction efforts at Sudbury to complete the SNO detector, NSD researchers have been turning their attention to extracting physics from SNO. Looking to the future, through the focus provided by the Institute for Particle and Nuclear Astrophysics (INPA), a joint activity with the Physics Division, concepts are being developed, and early R&D carried out, on a next-generation detector (km^3) to study high energy neutrinos of astrophysical origin.

In the area of relativistic heavy-ion collisions, considerable progress and re-direction of effort has occurred in the last few years. The Pb-era at the CERN Super-Proton Synchrotron is in full swing. The NSD's physics activity at CERN continues to be focused on NA49, where we had primary responsibility for the

electronics associated with the TPC's. The development of electronics for TPC's has been an active part of our efforts through many different experiments—from EOS, to NA35/NA49 and STAR. For the NA49 experiment, attention is now focused on physics results, including observables such as strange particle yields and flow. After a very successful program at the Bevalac, the EOS TPC was moved to the AGS in 1995 and has successfully completed data-taking for Au+Au collisions at a range of energies between 2–8 GeV/nucleon, and is the only large-acceptance electronic detector with data in this interesting transition region between Bevalac and full-energy AGS physics. Areas of interest for this program include the energy dependence of flow and strange particle production.

The STAR detector continues on track for physics at RHIC in the summer/fall of 1999. During the last two years, many major reviews of STAR, by both DoE and RHIC management, have been successfully carried out. Locally, the TPC, which is the heart of the STAR detector, is nearing completion and shipment to RHIC is expected in the fall of this year. Systems testing and finally cosmic ray tests of the TPC will be conducted before shipping. As we move from the construction phase of STAR to physics with STAR, our activities on the analysis and software aspects of the STAR program are playing a more prominent role. The recent arrival of the National Energy Research Scientific Computing Center (NERSC) at the Berkeley Lab, with its scientific computing capabilities and expertise, has provided the Division with a substantial opportunity to enhance our ability to extract the physics from STAR. Active collaborations with NERSC and others interested in the high volumes of data that will be generated by detectors like STAR are being formed. Hopefully, the solutions to problems of mutual interest will result from this effort.

The Nuclear Theory program has been very active over the last two years in activities spanning low-energy nuclear structure, studies of astrophysical interest such as neutron stars, and relativistic nuclear collisions with particular emphasis on RHIC physics. Close interaction with experimental groups has continued to grow, including weekly seminars covering the range of research interests of the Division. A strong visitor's theory program continues to enrich the Division.

In 1996 the Isotopes Project produced the *8th Edition of the Table of Isotopes*, both in hard copy and CD-ROM. New focus areas in nuclear structure, nuclear astrophysics, and electronic data dissemination have been developed by the group. They continue to be a central player in the U.S. data evaluation and dissemination program supported by the DoE.


Finally, this two-year annual report is being put out in both hardcopy and through electronic publishing on the World Wide Web (WWW). With increased use of the electronic dissemination of information, *we do not plan to provide hard copies of future NSD annual reports*. The Division has a home page on the WWW (http://user88.lbl.gov/nsd_home.html) or access through the Berkeley Lab home page (<http://www.lbl.gov>), as do many of our research groups—please visit us! Any comments and suggestions should be addressed to our Editor, Art Poskanzer, who has, with his useful efficiency, put together an excellent document.

NUCLEAR SCIENCE DIVISION


DIVISION DIRECTOR
L.S. SCHROEDER

DIVISION DEPUTY
J.M. DAIRIKI

DIVISION ADMINISTRATOR
N. TALCOTT, Acting



Overviews



Nuclear Structure and Reactions Program

L.S. Schroeder

The Nuclear Structure and Reactions Program uses a broad range of observables and techniques to study the nuclear medium and address problems of current interest in nuclear physics. This activity focuses on studying nuclear systems at extremes of angular momentum, isospin, neutron and proton number, as well as temperature. A brief overview of the various programs is given below, while a more detailed accounting of individual activities can be found in the "Nuclear Structure and Reactions" contributions later in this report.

Most of these programs are centered at the 88-Inch Cyclotron. The Cyclotron is operated as a national facility, providing a wide range of ion species and energies, for a diverse national and international user community. The high reliability and ease of changing beam species and energy make the 88-Inch Cyclotron ideally suited for nuclear structure and reactions studies.

A broad range of nuclear instrumentation is in place at the 88-Inch to address this research program. The central focus of the research program at the 88-Inch, over the last few years, has been the exploitation of the unique capabilities of Gammasphere. This National γ -ray Facility, consisting of a 4π array of 110 Compton-suppressed high-purity germanium detectors, augmented with auxiliary detectors, utilizes over 50% of the research time at the Cyclotron. Gammasphere, as well as other detector systems in operation at the Cyclotron, are described below and in other sections of this document.

Nuclear Structure

The Nuclear Structure Group has two main focuses: one is to pursue a physics program mainly centered on high-spin studies of the atomic nucleus, and the other is to develop new instrumentation to push the frontiers of nuclear structure and other research. The Nuclear Structure Group has played the leading role in the construction and operation of Gammasphere. Both the Director and the Deputy Director of Gammasphere are members of the Nuclear Structure Group, and other members support the operation of the array, as well as contribute to its construction and maintenance. Gammasphere was dedicated on December 1, 1995 and on that occasion, a "Workshop on Gammasphere Physics" was organized by this group. About 100 scientists attended and highlights of the physics done at the large gamma-ray arrays was reported. The proceedings are published in World Scientific.

This group is interested in the structure of the nucleus, mostly at high angular momentum. One of the main goals is to understand nuclear behavior in terms of the characteristics of a few-body quantal system. Persistent themes reflecting these interests have been identical bands and the C_4 symmetry suggested for the nuclear shape. Progress on these as yet unresolved issues is described below. More superdeformed bands are discovered as the sensitivity of Gammasphere increases. We found interesting evidence for the contribution of pseudo-spin symmetry in a pair of identical bands. However, the focus is now on understanding the properties of SD bands rather than finding more bands. This is now possible as more precise energy and lifetime measurements can be made. Using these new capabilities, our group found evidence for octupole deformations in some superdeformed nuclei. We could compare deformations of identical bands. We could also learn about the mechanism of the decay of superdeformed bands. In normally deformed nuclei, lifetime measurements confirmed the predictions of the "tilted axis cranking" model, supporting the new concept of "magnetic rotation" as a nuclear excitation. We have been looking for the octupole two-phonon excitation in ^{208}Pb and have set new limits on its existence. We are interested in neutron-rich nuclei and the possibility that they will reveal new properties of nuclei. We have produced such nuclei at high spins using deep inelastic reactions.

In the future, our group intends to take new directions in addition to pursuing the subjects outlined in the previous paragraph. One of the most tantalizing goals is to find hyperdeformed nuclei; i.e., nuclei even more elongated and probably better rotors than superdeformed nuclei. So far there is no evidence for them but we continue trying new ways to produce them. We are interested in heavy nuclei as they are the most collective nuclei with normal deformation. In particular, it will be very interesting to study the evolution of octupole excitations in these nuclei. The future use of various recoil separators, with and without Gammasphere, should give us access to more exotic nuclei. It would also be interesting to study very light nuclei and observe the various exotic shapes predicted. With Gammasphere, one can study continuum spectra at high spins better than ever before. We intend to pursue this in various aspects of the order-to-chaos transition in nuclei.

Finally, the group is engaged in a collaboration with S. Freedman and his group to measure the branching ratio of the superallowed ($0^+ \rightarrow 0^+$) β^+ decay of ^{10}C . This work is expected to provide the best test of unitarity of the CKM matrix. We are also interested in pursuing a wider variety of physics, for example looking for strange matter and rare decays of positronium.

The group is also developing a new Gamma-Ray Energy Tracking Array (GRETA), which would have a resolving power a thousand times that of Gammasphere. This array would consist of a solid shell of highly segmented Ge detectors. Research and development is underway. Preliminary cluster recognition studies indicate a large improvement over Gammasphere. Also, the induced signal into the segment adjacent to the "hit" segment has been calculated and compares well to the measured one in the Gammasphere segmented detector. It is essential to measure this signal in order to have position resolution in the measurement of the gamma-ray interaction points. R&D is progressing on GRETA design.

A recoil separator is also under study as an auxiliary detector for Gammasphere. With a high efficiency and reasonable mass resolution, such a system (e.g. solenoid-dipole) appears quite attractive.

Proton-Rich Nuclei

Studies near the proton drip line can provide excellent tests of the limitations of nuclear models and stimulate improvements in these models. For nuclides beyond the proton drip line, searches for new ground-state proton emitters are of interest to compare reduced widths to nuclear structure theory, as are searches for the quantum-mechanically interesting decay mode of ground-state two-proton emission (^2He). For nuclides near the drip line, the large available β -decay energies open up new beta-delayed multi-particle decay channels (e.g., $2p$ decay). In order to extend the dynamic range for the detection of these beta-delayed protons, this group has developed detectors with gas ΔE -gas ΔE -silicon E telescopes with a threshold of 180 keV. An array consisting of four of these telescopes was used in observing beta-delayed proton decay branch from ^{23}Al which proceeds via the isobaric analog state (IAS) in ^{23}Mg . ^{23}Al represents the lightest member of the $A = 4n+3$, $T_z = -3/2$ mass series for which proton decay of the IAS is possible. Recent measurements have extended the successful search for new low-energy proton groups to ^{27}P and ^{31}Cl , but these decays do not proceed via the IAS. This group will attempt to confirm the results from several experiments started during the past year which include confirmation of beta-delayed proton decay from the $T_z = -5/2$ nuclide ^{23}Si and of beta-delayed two-proton decay of the $T_z = -2$ nuclide ^{46}Mn . A new search will commence for the beta-delayed proton decay of ^{77}Zr . Finally, this group is expending considerable effort in developing the capability of running a few radioactive ion beams at the 88-Inch Cyclotron. The primary production machine is a small medical cyclotron located at LBNL and tests are under way to measure the efficiency of coupling a gas-jet transport system to an ECR source. The first beams will be ^{11}C and ^{14}O accelerated to energies > 15 MeV/nucleon for nuclear reaction studies.

Heavy Element Nuclear and Radiochemistry Program

The nuclear and chemical properties of the heavy actinides and transactinide elements at the limits of both nuclear stability and the periodic table are being investigated. Studies to produce and characterize new elements and isotopes, to study nuclear reactions, and to elucidate the chemical properties of the transactinide elements have been conducted at the LBNL 88-Inch Cyclotron as well as at the GSI-UNILAC Facility in Darmstadt, Germany.

Both physical and radiochemical techniques are utilized and a large number of students have been trained in modern nuclear and radiochemical techniques. Currently, the research efforts are concentrated in the following areas: 1) Production and identification of new isotopes and elements; 2) Study of nuclear decay of actinide and transactinide isotopes, especially spontaneous fission (SF) and electron-capture delayed fission (ECDF), and nuclear properties; 3) Development of rapid separation and sensitive detection techniques for study of isotopes with half-lives as short as seconds for definitive studies of both nuclear and chemical properties.

An international collaboration was hosted at LBNL to study the chemical properties of hahnium (105) using the 1.8-second ^{261}Ha . The 1.8-second isotope ^{225}Pa of its pseudo-homolog protactinium ($Z=91$) was also studied under the same conditions. The automated, continuous liquid-liquid extraction system (SISAK) coupled with the flowing liquid scintillation alpha spectroscopy system (LISSY) enables us to achieve separation times of 1-2 seconds with nearly 100% detection efficiency.

Recent experimental confirmation of the predicted stabilizing influence in the region of the deformed shells at $N=162$ and $Z=108$ has sparked a renaissance of interest in the production and study of the half-lives and decay properties of isotopes near these shells. (Our measurement of a 2.1-second SF half-life for ^{262}Rf and an alpha half-life around 10 seconds for ^{266}Sg support these predictions.) In order to more sensitively explore and study this extension of the known region of stability, the Berkeley Gas-filled Separator, a new instrument designed for efficient separation of compound nucleus products has been designed, and is scheduled for completion in late 1997. Its sensitivity to half-lives as short as microseconds and cross sections as small as picobarns will facilitate access to this region and a number of exciting studies of nuclear phenomena.

First studies of both the aqueous and gas-phase chemical properties of Seaborgium (Sg, element 106) were performed as part of an international collaboration. These indicated that Sg was properly placed under Mo and W in group 6 of the periodic table. New information about the production cross sections and nuclear properties of $^{264,265,266}\text{Sg}$ produced via the reaction of ^{248}Cm with ^{22}Ne projectiles was also obtained. Studies of more complex chemical properties of Sg are planned. Gas-phase studies of bromides of its lighter homologs have already been conducted in preparation for studies with Sg.

Investigations of electron-capture delayed fission have been extended to the light Es isotopes. A sample changer is being built to transport samples to Gammasphere to permit study of fission barriers and fission shape isomers and their gamma decay back to the ground state in an out-of-beam environment. Our studies of SF half-lives and decay properties are continuing and two more SF reviews have been published.

Nuclear Reactions

At low energies complex fragment or intermediate mass fragment ($Z > 2$) emission is a rare process. Increasing the excitation energy brings the emission of these fragments to the forefront, until they dominate the reaction scene. The goal of the Nuclear Reactions group is to characterize the physics of this emission process, both theoretically and experimentally, from its onset as binary compound nucleus decay to its full deployment as multifragmentation.

Scaling Laws, Shell Effects and Transient Times in Compound Nucleus Emission

Our recent work has demonstrated the compound nucleus emission of complex fragments and characterized it to be a generalized fission process controlled by a set of conditional barriers constrained to a given mass asymmetry. For several systems near $A \sim 100$, we have measured excitation functions and extracted conditional barriers. These barriers compare favorably with those calculated with the finite-range model. As the fission barriers in medium-heavy nuclei were instrumental in defining uniquely the liquid drop model parameters, the conditional barriers offer a unique tool to fix the parameters of its more modern descendants like the finite range models. In particular, the measurement of conditional barriers for several isotopes of the same element, can constrain the large uncertainty in the surface asymmetry coefficient of the droplet model.

Complex fragment excitation functions have also been used to search for atomic number Z and energy E dependent deviations from transition-state-method predictions that would indicate the existence of transient time effects. No, Z - and/or E -dependent effects, that could be attributed to an increased collectivity with increasing mass (charge) of the emitted fragment and associated with transient or stationary solutions of Kramers' diffusion equation, are visible in our data. Over ninety excitation functions, for complex fragments from four different compound nuclei, can be collapsed into a single universal straight line that is consistent with the transition-state predictions. Once the phase space associated with the non-reactive degrees of freedom at the conditional saddle point is removed, the reduced rates are identical for all fragments. This result seems to rule out, for all Z -values, transient effects that should become noticeable with increasing excitation energy and decreasing mass asymmetry.

The scaling reported above for complex fragments is not directly applicable to fission because of the strong ground state shell effects encountered in the ^{208}Pb

region. However, because of the simple asymptotic form of the shell correction, we have been able to modify the scaling in a simple way. The remarkable result is that all of the sixteen studied fission excitation functions are exactly scalable. In other words, they are reducible to the same straight line. The scaling extends over more than 100 MeV of excitation energy and over an increase of fission probability of a factor 10^7 . No failure of the transition state rate is detectable over these ranges, and fission delay times in crossing the saddle point larger than 10^{-20} sec can be ruled out.

As a "by-product" of the above analysis, we obtain the ground state shell corrections. These are in excellent agreement with those extracted from ground state masses. Thus, this procedure can be offered as an alternative method for the extraction of shell effects, which, incidentally, is purely local and independent of the liquid drop fit extended over the entire mass table.

Reducibility and Thermal Scaling in Multifragmentation

The process of multifragmentation is still sketchy and incomplete. However, we believe that we have succeeded in unveiling important features which may be the key to a deeper understanding.

The pervasive aspect of *reducibility* indicates that, whatever the mechanism, the fragments are emitted essentially independent of one another. We have shown that the probability P_n of emitting n fragments can be reduced to the probability of emitting a single fragment through the binomial equation. Similarly the n fragment charge distributions can be reduced to the one fragment charge distribution. Furthermore, the particle-particle angular correlation can be reduced to the individual particle angular distributions.

In all the above quantities, reducibility is somehow restricted by what we may call "dynamical constraints." For the emission probabilities, the constraint is the binomial parameter m , indicative either of a dynamical time window, or of the finite source size. For the charge distributions, reducibility is restricted by the parameter c , which seems to indicate some special way of enforcing charge conservation. We speculate that its transition from near zero to a finite value with increasing energy could be an indication of a transition from phase coexistence (liquid-vapor) to a single phase (vapor). Finally, the angular correlations violate reducibility at small relative angle where particle-particle interactions become manifest.

These broad features of reducibility speak to the near independence of fragment emission but not to its mechanism.

Thermal scaling instead makes a clear statement about the fact that the elementary probabilities entering in the n fragment emission probabilities, the n fragment charge distributions, and the two fragment angular correlations are *thermal*. In other words, these probabilities have the form of a Boltzmann factor and clearly portray its characteristic energy dependence (linear Arrhenius plots).

Thus, the resulting picture is tantalizingly close, but not quite that of a compound nucleus emission. Apparently sources are dynamically generated which, within dynamical constraints of time and size, emit fragments in a thermal manner. Among the potential fruits that can be reaped from the pursuit of the analysis outlined so far are dynamical features of source formation, size and lifetime, as well as static features like barriers, source sizes and densities.

Stable Coulomb Bubbles?

The depletion of charge in the central cavity of nuclear bubbles reduces the Coulomb energy significantly and thus stabilizes "Coulomb" bubbles against monopole oscillations. These Coulomb bubbles, however, are at least unstable to perturbation of the quadrupole radial mode. At sufficiently high temperature, the vapor pressure in the central cavity drives the bubble to a thinner configuration that is stable against all radial modes. Since a thin Coulomb bubble behaves like a sheet, it becomes susceptible to the proximity surface instability via the crimpation modes and may meet its demise when its thickness is comparable to the range of the proximity interaction.

Heavy Element Collaboration

J. Alstad⁴, M. Andrassy³, U. Becker², R. Binder⁹, W. Bröchle¹, R. Dressler⁸, K. Eberhard², B. Eichler⁵, St. Fischer⁸, B. Fricke¹⁴, H. Gäggeler^{5,6}, R. Güenther², A. Hofmeister², S. Hübener⁷, E. Jäger¹, D. Jost⁵, B. Kadkhodayan¹¹, J. Kratz², R. Malmhac³, M. Mandel², R. Misiak¹², A. Nähler², Y. Nagame¹³, H. Nitsche^{7,8}, J.P. Omtvedt⁴, Y. Oura¹³, W. Paulus², V. Pershina¹⁴, G. Pfrepper¹⁰, R. Pfrepper¹⁰, A. Ross⁷, M. Schädel¹, B. Schausten¹, E. Schimpf¹, D. Schumann⁸, G. Skarnemark³, A. Seibert², R. Süss⁹, St. Taut⁸, U. Tharun², N. Trautmann², A. Türler⁵, N. Wiehl², B. Wierczinski³, G. Wirth¹, S. Zauner²

¹Gesellschaft für Schwerionenforschung, Darmstadt, Germany

²Institut für Kernchemie, Universität Mainz, Mainz, Germany

³Chalmers University of Technology, Göteborg, Sweden

⁴Department of Chemistry, University of Oslo, Norway

⁵Labor für Radiochemie, Paul Scherrer Institut, Switzerland

⁶Institut für anorganische Chemie, Universität Bern, Bern, Switzerland

⁷Institut für Radiochemie, Forschungszentrum Rossendorf, Dresden, Germany

⁸Forschungsgruppe Radiochemie, Technische Universität Dresden, Dresden, Germany

⁹Arbeitsgruppe Kern- und Radiochemie, Universität Leipzig, Leipzig, Germany

¹⁰Institut für Biophysik, Universität Leipzig, Germany

¹¹Glenn T. Seaborg Institute for Transactinium Science, Lawrence Livermore National Laboratory, Livermore, CA USA

¹²Niewodniczanski Institute of Nuclear Physics, Poland

¹³Japan Atomic Energy Research Institute, Japan

¹⁴Theoretische Physik, Kassel, Germany

Institute for Nuclear and Particle Astrophysics

R.G. Stokstad

Introduction

The areas of research at the Institute (INPA) are broad and have a strong interdisciplinary flavor, yet a common purpose connects them—to use the science and the technologies of nuclear physics and particle physics to address fundamental questions bearing on the nature of the universe: past, present, and future. Specific research topics include solar neutrinos, high energy neutrinos, detection of nearby and distant supernovae, weak interactions in atomic and nuclear processes, the cosmic microwave background radiation, direct detection of dark matter, cosmic rays and chronometers, the theory of pulsars and neutron stars, and geoastronomy. Research and education are combined not only through the participation of students and postdoctoral researchers, but also at the high school level through summer programs for teachers and a major project, the Hands-On Universe, that brings on-line astronomical images to the classroom.

INPA is sponsored by the Nuclear Science Division and the Physics Division at LBNL. While participants in INPA are predominantly from these two Divisions, the Physics Department and the Space Sciences Laboratory at UC Berkeley are well represented. Indeed, the Institute benefits from the rich concentration of astrophysics in the greater Bay Area. A wide range of experimental facilities is used by INPA participants; at LBNL (the 88-Inch Cyclotron, Gammasphere, low-background counting facilities, Leuschner Observatory), in North America (Sudbury Neutrino Observatory, the Keck Telescopes, nuclear physics facilities

at Argonne and Brookhaven national laboratories, university laboratories), throughout the world (Chile, Australia, Antarctica), and in space (HST, COBE).

This overview naturally focuses on research where Nuclear Science Division-associated researchers are heavily involved. A few highlights from other areas are mentioned, and the overview concludes with a brief description of INPA's institutional activities.

Neutrino Astrophysics

The Sudbury Neutrino Observatory (SNO), a 1,000-ton heavy-water Cerenkov detector under construction in a nickel mine in Canada, is back on track after construction delays associated with the fabrication of the acrylic vessel that will contain the D_2O . The most significant milestone has been the completion of the upper half of the detector, with both the photomultiplier support structure (PSUP, with phototubes) and the acrylic vessel (AV) suspended by their cables from the deck above. Construction of the lower half of SNO has begun. LBNL is responsible for the PSUP and has also helped the collaboration with the AV. Contamination control in construction is critical to keep backgrounds to tolerable levels—this aspect of SNO continues to receive attention from the LBNL group. When the detector is filled with water and ready to begin its shake-down period, other activities will become important and are being prepared for now at LBNL as well as at other collaborating institutions. These activities include calibration (^{16}N and ^{17}N sources), neutron detection (3He neutron detectors) and suppression (6Li poison), data acquisition (graphical interfaces) and data analysis (Monte Carlo simulation and measurement of β and γ backgrounds). When SNO begins taking data, the years of planning and construction should bring their reward. By the year 2000, the neutral current to charged current ratio and the shape of the 8B spectrum—two independent tests for neutrino oscillations—will have been measured and we should have a better perspective on the standard models of particle physics and of the sun.

The same properties of neutrinos that make them a valuable probe of the sun could also make them a unique window on the most energetic objects in the cosmos. Several INPA participants are members of the AMANDA collaboration, which is constructing a water Cherenkov detector in deep Antarctic ice to observe high energy neutrinos. It is in the planning and R&D toward the next generation neutrino observatory, however, that INPA is making a major contribution. This detector will have dimensions on the order of a square or cubic kilometer, and therefore the sensitivity to detect neutrinos from distant point sources, such as Active Galactic Nuclei.

Nuclear Astrophysics

Laboratory measurements of nuclear properties are essential in understanding the processes by which heavy nuclei are synthesized from primordial nuclei. Certain individual isotopes can take on key roles. ^{44}Ti is such an example; gamma rays from its decay are observable and can be used to determine the

amount of ^{44}Ti produced in a supernova if the half life of this nucleus is known. Past measurements place this value in the range 39 to 67 years, which translates into a factor of six uncertainty for the remnant of a supernovae that exploded 300 years ago. (Half lives in the range of tens of years are particularly difficult to measure). Measurements on ^{44}Ti produced at the 88-Inch Cyclotron and counted off-line yield a value of 62 ± 2 years and, because they were made relative to other isotopes with well-known half lives, resolve the present discrepancy.

Knowing the half life of unstable (but long-lived) nuclei present in cosmic rays makes it possible to determine the residence time of these nuclei in our galaxy, i.e., they can serve as a cosmic chronometer. In this case, the half lives need to be of the order of 10^6 years. The decay rate of a nucleus in space (where it has no surrounding electrons to capture) can be much longer than when it is housed in an atom or ion on earth. Measurements of very weak decay branches are therefore necessary. ^{144}Pm and ^{54}Mn are two such cases; the latter nucleus is of particular interest because it has recently been possible to measure the relative abundance of the Mn isotopes in cosmic rays. Experiments are being made both at the 88-Inch Cyclotron and at ANL, using different experimental techniques. The rarest, and one of the most enigmatic unstable nuclei in nature, ^{180}Ta , is still the subject of experimental work in the hope of discovering how it was synthesized and why it survived. Finally, geological (as opposed to cosmological) dating techniques can also be affected if there is a dependence of the half life on the chemical composition of the compound in which the radioactive nucleus is located. Such a chemical dependence has been suspected for ^{40}K , which is used in the potassium-argon dating method. Present experiments on ^{40}K contained in different compounds indicate this is not the case.

Data for Nuclear Astrophysics

Nuclei heavier than lithium can only be made in stars, and in the later, rapid burning and explosive stages of stellar evolution. The prediction of the abundance of these nuclei is a triumph of nuclear astrophysics, and requires an amount of nuclear information on a similarly grand scale. INPA, the Isotopes Project, and UC Santa Cruz have assembled a number of the data-bases used in nucleosynthesis calculations and made them available to the community through our new Nuclear Astrophysics Data Home Page.

Fundamental Measurements

The standard model of particle physics is the cornerstone for understanding the origin and development of the universe. Many of the key elements or parameters of the standard model are reflected in nuclear properties and measured in precision low-energy nuclear (or even atomic) experiments. We establish, test, and look for physics beyond the standard model in these nuclear physics experiments. Parity non-conservation, second class currents, time reversal invariance, the conserved vector current theory, double beta decay—these are some of the topics studied in the physics of weak interactions.

The trapping of radioactive neutral atoms with laser beams offers significant opportunities for increasing precision in tests of weak interaction theory. This is because the atoms are both confined in a vacuum and polarized by the trapping mechanism. During the past two years, steady improvements in the laser trapping facility at the 88-Inch Cyclotron have led to the trapping of 5×10^4 ^{21}Na atoms ($t_{1/2} = 21\text{s}$) and a precise measurement of the ground state hyperfine transition. The next steps will be the installation of an in-vacuo beta detector and a measurement of the beta-decay asymmetry.

The branching ratio for the super-allowed beta decay of ^{10}C (g.s. 0^+) to the first 0^+ state of ^{10}B is critical for the determination of the u-d element of the Cabibbo-Kobayashi-Maskawa mixing matrix. This matrix is assumed to be unitary in the standard model of electro-weak interactions. The present measurement of this branching ratio uses Gammasphere, a high-resolution gamma-ray detector array; the first of two runs has been analyzed and yielded a value that is in agreement with a unitary CKM matrix but that differs by 2.5σ from a recent measurement made at Chalk River Nuclear Laboratories. Gammasphere is also ideal for the measurement of angular correlations, as in the case of the β - γ directional correlation in the decay of ^{22}Na . This quantity enters into higher-order terms that test standard model predictions and can be used to search for second class currents.

The detailed shape of the energy spectrum in beta decay is related in the conserved vector current (CVC) theory to the strength of an associated electromagnetic transition. ^{14}C and ^{14}O are two cases for testing CVC. Measurements on the former nucleus have been completed (at ANL), while the latter will be studied at the 88-Inch Cyclotron using a new, high-efficiency Cusp ion source for the production of the ^{14}O ($t_{1/2} = 71\text{ s}$) radioactive source.

Double beta decay is a well-known though relatively rare phenomenon, the most interesting aspect of which would be neutrino-less $\beta\beta$ decay. (The latter has not been observed.) $\beta\beta$ decay to excited 0^+ states is also possible, though energetically disfavored. A search for this in ^{150}Nd is being conducted at the Oroville low-background counting facility using 5 kg of natural neodymium oxide.

The breaking of CP symmetry explains the predominance of matter over anti-matter in the universe. The most fundamental theorem in physics, "CPT=1" implies that Time Reversal Invariance must also be broken at some level. Searches for TRI-violating effects are therefore important for our understanding of how the universe evolved immediately after the Big Bang. Two searches are in progress. The first, called "emiT," is a study of the directional correlations in the beta decay of spin-polarized neutrons. This experiment, a collaboration of several institutions, has been several years in preparation, and is currently taking data with the cold neutron source at NIST. The other experiment uses low temperatures to align nuclei of ^{56}Co and observes the directional correlation of the nuclear spin, the emitted positron, and a subsequent gamma ray. This experiment is scheduled to have results later this year.

The weak interaction responsible for nuclear beta decay (W-exchange) can induce a small Parity Non Conserving component in electromagnetic transitions in atomic systems through the weak neutral current (Z-exchange). The latter thus complements the study of nuclear beta decay. Atomic PNC experiments are in progress on a range of stable isotopes of Yb and may yield information on the weak interaction independent of atomic structure.

Materials that register a track when an ionizing particle passes through (emulsions, glasses, plastics, and insulating minerals) have found a wide application in the search for exotic particles. Searches for WIMPS and for magnetic monopoles have employed a variety of track detectors and have also used an Atomic Force Microscope for scanning.

Low Background Counting

The Low Background Counting Facilities used in the study of $\beta\beta$ decay have also been instrumental in a wide variety of experiments and in support activities for other institutions. The other types of work (done at the facilities at Berkeley and at Oroville) include low-activity materials certification, cosmic ray activation, neutron activation analysis, and environmental health and safety activities.

Past and Future

We note here two projects that address the early history and the ultimate fate of the universe and which are based in the Physics Division. The cosmic microwave background radiation observed today reflects the state of the universe about 3×10^5 years after the Big Bang, at the time radiation and matter decoupled. The next generation of satellites, to follow COBE in the study of anisotropies in the CMBR, are being planned.

The fate of the universe depends on its matter density, which is expressed as a ratio to a critical density at which the expansion rate of the universe slows to zero at infinite time. The supernova cosmology project searches for (and regularly discovers!) type 1A supernovae at very large distances. In essence, the luminosity of a type 1A supernova is a constant or "standard candle," which gives its distance, and the red shift of its host galaxy gives its velocity. Thus, the Hubble diagram can be extended to very large distances (or far back in time). Deviations from a linear dependence of recessional velocity on distance would indicate that Ω (the ratio of the mass density of the universe to the critical value) is different from 1.

Institutional Activities

The purpose of the Institute is to further interdisciplinary work in Nuclear and Particle Astrophysics at LBNL by:

- promoting interaction and communication among its members
- sharing of intellectual, technical, and administrative resources
- planning of new research proposals and development of detector systems
- developing innovative educational outreach programs
- establishing seminar, postdoctoral, and visitor programs
- sponsoring of workshops

The list of active participants has grown to approximately 80, while the number of people receiving e-mail announcements of the weekly Journal Club is ~200. Attendance at the Journal Club is typically 30–40 people. The daily tea has become an established feature of INPA life and attracts usually 15–20 people for conversation and lively argument. The Common Room is heavily used for regularly scheduled group meetings and ad-hoc get-togethers. The list of Journal Club speakers is contained elsewhere in this Annual Report.

New initiatives in which INPA plays an important role are the R&D for the next generation of high energy neutrino detector and the development of a Nuclear Astrophysics Data Center.

Recent visitors to INPA include B. Balantekin, D. Branch, R. Ellis, J. Frieman, L. Krauss, A. Olinto, G. Savard, and M. Turner.

Workshops sponsored by INPA:

LBNL Workshop on Physics and Simulation Issues for Km^3 Neutrino Observatory. Dec. 1, 1994.

NSAC/DNP TOWN MEETING on Electroweak Interactions, Astrophysics, and Non-Accelerator Experiments. February 4–5, 1995.

INPA Km^3 Simulation Workshop. August 31, 1995.

US Meeting on Future Prospects for Km -scale Neutrino Detectors. April 18–19, 1996. (Arcadia, CA)

Additional information on the Institute and its activities can be found on the World Wide Web under the URL <http://www-inpa.lbl.gov/>.

Relativistic Nuclear Collisions Program

H.G. Ritter

The Relativistic Nuclear Collisions Program (RNC) conducts experiments studying the collision of nuclei in four energy regimes: (1) the Bevalac, where nuclear matter is compressed sufficiently to study its equation of state; (2) the AGS at Brookhaven National Laboratory (BNL), extending the studies of the Bevalac to an energy range where the maximum pressure from the baryons is likely to occur; (3) the SPS at CERN, where the energy density of the *nucleons* in the collision of very heavy nuclei may be sufficient to produce a phase transition to a plasma of free quarks and gluons; and (4) RHIC, where the energy density of the *produced particles* will be sufficiently high that production of the quark-gluon plasma is expected to occur. Understanding the reaction dynamics of nuclear matter and its equation of state is of fundamental interest.

The major efforts at the Bevalac have been the Dilepton Spectrometer (DLS) and the EOS Time Projection Chamber (TPC). Analysis of those experiments is near completion. The EOS TPC has been moved to the AGS to continue its studies at higher energies as experiment E895. Two periods of running have produced a rich sample of data, spanning the energy range from two to eight AGeV. The construction of CERN experiment NA49 has been successfully completed, and the data taking and analysis are under way. The main focus of the high-energy heavy-ion research program at LBNL is the STAR experiment at RHIC, which will begin data-taking in 1999.

CERN/RHIC Physics

The collisions of the heaviest nuclei at the highest energies (Pb ions at the SPS, Au ions at RHIC) are expected to create systems whose space-time dynamics are qualitatively different from those of the colliding light ions studied up to now. The heavy systems have significantly higher energy densities over longer time scales. The extremely large number of produced hadrons in such collisions (several thousand in a central Au-Au event at RHIC) presents a real technical challenge and a unique opportunity: nontrivial, statistically significant signals can be extracted from single events, a technique known as "event-by-event" analysis. The correlation of extreme values of several observables sensitive to the quark-gluon plasma phase transition in a single event is a powerful tool for selecting ensembles of interesting events for detailed study. An event-by-event measurement of the produced particles provides the opportunity to select events with extreme values of temperature (particle spectrum), flavor (strangeness content), shape of the flow (particle momentum), and size (two-particle correlations). This technique requires a large acceptance detector that can determine the momentum and identify a large fraction of the particles emitted in the collision.

NA49 is a fixed-target experiment at the SPS designed to study Pb-Pb collisions at 160 GeV/nucleon ($\sqrt{s_{nn}} = 17$ GeV). Its goal is to simultaneously measure many hadronic signals that are thought to be sensitive to the quark-gluon plasma. To perform event-by-event analysis, it measures and identifies almost all charged particles in the forward half of phase space and carries out detailed ensemble measurements of all the single-event observables as well as strange particle decays, two-particle correlation functions, and other hadronic observables.

STAR is a collider experiment at RHIC designed to study Au-Au collisions at $\sqrt{s_{nn}} = 200$ GeV. Its goal is similar to NA49's, to simultaneously measure many hadronic signals. To perform event-by-event analysis, it will measure and identify almost all charged particles over two units of rapidity, centered at mid-rapidity. At RHIC there is a high rate of hard processes. Hard-scattered partons are predicted to be sensitive to the medium through which they propagate. The process can be calculated in perturbative quantum chromodynamics. The study of high transverse momentum particles and jets as a function of energy and mass of the colliding system may also be an attractive experimental approach to identify the presence of quark matter.

Bevalac/AGS Physics

The hot and dense system produced in nuclear collisions can be studied with penetrating probes, dileptons in the case of the DLS. Dileptons provide a unique tool for probing the early phase of the hot, condensed system created in central A-A collisions. The yield and the mass spectrum of dileptons is sensitive to the density and temperature of the early phase of the collision, providing information on the nuclear matter equation of state and on medium effects.

From the study of the hadronic signals of nuclear collisions with 4π detectors, like the EOS TPC, a rather simple picture is emerging, compatible with the formation of a single source that seems to show a high degree of thermalisation and flow in the final state. Part of the flow pattern is established early by geometry and compression (directed flow), the other part is dominated by compression and expansion (radial flow). A careful and systematic comparison of data with microscopic models will lead to a better understanding of in-medium effects and the nuclear matter equation of state. Experiment E895 continues these studies in the AGS energy region with the focus on the study of flow and strange particle production.

Experiments

The Dilepton Spectrometer (DLS)

The DLS collaboration, from late 1986 until the closure of the Bevalac, carried out systematic measurements of e^+e^- production in p-p, p-d and A-A collisions as a function of beam energy and kinematics of the pair. The DLS results, about 30k pairs, represent the world's only e^+e^- data at Bevalac/SIS energies. Important results include: (1) existence of measurable dielectron yields, (2) observation of contributions from mesonic decays (π^0 , η , ρ/ω), bremsstrahlung, and Δ/N^* decays, (3) strong energy dependence of the pd/pp yield ratios signifying the presence of the η -meson, (4) absolute value and shape of the mass spectrum at 5 GeV in p-p and p-d collisions, which shows a need to modify existing N-N model calculations (pp vs. pn contributions, inelasticity), and (5) observation of high mass pairs (>500 MeV) in Ca-Ca collisions, which may be evidence for pionic annihilation. Analysis continues on the high-statistics A-A (Ca-Ca, α -Ca, d-Ca, C-C) studies, and evolution of mass and p_t distributions with projectile/target mass. Recent results from analysis of the A-A systems show that the low-mass region of the spectrum is well fitted by the shapes of the π^0 and η ; in this region the yield for all four data sets is proportional to $A_P A_T$; at higher masses the ratio of the CaCa/CC yields is proportional to $(A_P A_T)^{1.3}$. The fitted yield of η 's is several times larger than recent model calculations.

EOS TPC at the Bevalac

EOS was designed to study heavy-ion reactions over the whole energy range of the Bevalac. The TPC enables the measurement of the production cross-sections for protons, light composite particles, and pions over a large dynamic range. The EOS collaboration performed an extensive series of measurements prior to the shutdown of the Bevalac. Excitation functions of four systems (Ni + Cu, Ni + Au, La + La, and Au + Au) were measured from 250 MeV per nucleon up to the highest energy. In addition, the multifragmentation of the systems Au + C, Kr + C, and La + C at 1 GeV per nucleon were investigated.

The physics analysis of the data is being performed at LBNL and other collaborating institutions. A complete excitation function of directed and radial flow in the Au + Au system has been measured. A systematic study of the

emission of light composite fragments shows that the coalescence mechanism describes composite particle production very well. Preferred out-of-plane emission at mid-rapidity (squeeze-out) has been shown to be compatible with emission from one source with a well defined temperature and higher mean flow velocities in the out-of-plane direction. Systematic comparison of the data with model calculations are in progress. Preliminary results favor models with momentum-dependent interactions and a soft equation of state. In addition, multifragmentation of the Au + C system at 1 GeV per nucleon has been analyzed as a critical phenomenon. A method to extract critical indices from the data has been developed. Preliminary results show that the critical indices extracted are compatible with the critical indices of the liquid-gas phase transition.

EOS TPC at the AGS (E895)

E895 is a major new experiment at the Brookhaven National Laboratory (BNL) designed to carry out a systematic and exclusive measurement of the energy and mass dependence of particle production, correlations, collective flow effects, and strangeness production in Au + Au collisions. Theoretical studies indicate maximum baryon density, as high as eight times normal nuclear matter density, is achievable in central Au+Au collisions between 2 and 10 A GeV beam energies. Therefore, E895 extends the physics program started at the Bevalac to understand the collision dynamics and obtain information on the nuclear matter equation of state. Additionally, E895 will study the change of medium effects since the baryon densities are high enough to alter the masses and widths of hadrons, which in turn, could indicate the occurrence of chiral symmetry restoration or the formation of baryon rich Quark Gluon Plasma.

The experimental arrangement consists of the EOS Time Projection chamber placed in a large 1 Tesla dipole magnet and the MUSIC detector positioned downstream of the TPC. The detectors are located in the MPS area of the Alternating Gradient Synchrotron (AGS) heavy ion facility. E895 was made operational and, in December 1995, had successfully recorded data using 2 and 4 A GeV Au beams. High statistics were obtained with a Au target, and less with Ag, Cu and Be targets. During the second run in November 1996 data was recorded at 6 and 8 A GeV using the same targets. A complete off-line data analysis is underway at LBNL utilizing the Parallel Distributed Scientific Farm (PDSF) at NERSC, as well as at other member institutions.

NA49 at the SPS

NA49 is a large acceptance experiment based on a set of Time Projection Chambers. Particle identification is performed primarily by the measurement of dE/dx in the relativistic rise regime (leading to TPCs that are 3.6 m deep), supplemented by time-of-flight over a part of phase space. Event characterization for triggering is performed by forward calorimetry.

NA49 completed its construction phase and began taking data with the full complement of detectors in Fall 1995. Since then approximately 2 million lead-

lead collisions at 158 GeV/nucleon and 1 million proton-proton collisions at 158 GeV/c have been recorded, comprising a data set of about twenty terabytes.

In order to extract the most interesting volume-dependent effects in nucleus-nucleus collisions, NA49 data on central collisions of lead ions are compared to NA35 data on central collisions of sulphur ions at about the same energy (200 GeV/nucleon). NA49 finds that transverse energy production per participant nucleon increases slightly for the lead collisions, indicating a somewhat higher stopping. The rapidity distributions of primordial protons show the same effect. Produced particle multiplicities (total negative hadrons, which are mostly pions, and neutral and charged kaons) scale roughly with the number of participants. On the other hand, transverse mass spectra show an increase of inverse slope with the mass of the particle, which is indicative of increased radial flow for lead compared to sulphur collisions. Thus, the picture that emerges from transverse energy measurements and inclusive spectra from central collisions of lead ions compared to that of sulphur ions is one of somewhat greater stopping, with the additional available energy going into increased radial flow, while the strangeness enhancement appears to be about the same.

NA49 has also found a novel and unexpected feature in medium impact parameter collisions of lead ions. By means of techniques developed at the Bevalac to study flow phenomena, a quadrupole asymmetry in the azimuthal distribution of transverse energy was found. This apparent memory by the system of the initial reaction geometry is of great interest to the theoretical community. Effort is under way to study this phenomenon in the NA49 TPCs, in addition to the calorimeters.

STAR at RHIC

The purpose of STAR (Solenoidal Tracker at RHIC) is to discover the Quark Gluon Plasma, a new state of matter which hasn't existed in the universe since a few microseconds after the Big Bang. RHIC will provide colliding beams of gold ions at center-of-mass energies ranging from about 50 GeV up to a maximum of 200 GeV per nucleon. Other beam combinations are possible. STAR's goal is similar to NA49's; to simultaneously measure many hadronic signals of the QGP resulting from ultra-relativistic collisions. But hopefully STAR will explore nuclear collisions with energy densities that are much higher than are available at CERN. STAR will be able to perform event-by-event analysis, it will measure and identify virtually all charged particles over two units of rapidity (centered at mid-rapidity), and it will do an excellent job of characterizing high p_t particles and jets that are the result of hard-scattered partons.

The detector will consist of a Time Projection Chamber (TPC) and Silicon Vertex Tracker located inside a 5.2-m-diameter solenoidal magnet to provide tracking, momentum analysis, and particle identification using the dE/dx technique. The trigger detector systems include a central scintillator barrel around the TPC, vertex position detectors near the beamline just outside the magnet, and calorimeters located in the region of the beam insertion magnets to selectively

veto events according to the number of spectators. An electromagnetic calorimeter to trigger on transverse energy and measure jet cross-sections is being added. In addition, two forward time projection chambers are being built by the Max Planck Institute (Munich). The forward TPCs will extend the detector's angular coverage from two units of pseudorapidity up to approximately four.

The TPC is nearing completion at LBNL. The outer field cage and the pressure vessel were recently mated and the detector electronics will soon be added. Complete tests of the TPC, using cosmic rays, are scheduled for the summer of 1997. Simultaneously, LBNL personnel are engaged in preparing the detector hall at Brookhaven to receive the TPC and associated detectors in preparation for full operation in the summer of 1999.

LBNL's Relativistic Nuclear Collisions Program is providing the focus for these activities and will be the intellectual center for STAR during the operations phase of the experiment. Within the STAR organization, the RNC program is providing the Project Management for STAR as well as building a large fraction of the hardware. RNC has primary responsibility for the TPC, TPC electronics, and overall detector integration. RNC also has significant responsibilities within the software efforts in STAR. RNC physicists form the core of the software development team that is focused on tracking and particle identification by dE/dx in the TPC. This effort has recently benefited from a successful proposal to move a large computing facility from the SSC to LBNL. RNC physicists are currently proposing an even larger compute facility in association with NERSC. The goal of this larger center is to provide the primary simulation and off-line analysis center for STAR data after the year 2000. Currently, 40 physicists and engineers from LBNL are working on STAR. The STAR collaboration consists of 370 physicists and engineers from 36 institutions around the world.

Development

Micro TPC Vertex Detector

We are developing a new Micro TPC vertex detector that will be capable of tracking in the high track density environments which will be encountered in the STAR experiment at RHIC and in the ALICE experiment at LHC. This detector can handle track densities of 10 tracks/cm², approaching the capabilities of silicon devices. It has, however, the important advantage that it is essentially massless in comparison. This greatly reduces problems due to multiple scattering and secondary interactions, which is of utmost importance for vertex detectors. This technology could provide a significant improvement over silicon in these experiments particularly at low p_t where exciting results have been predicted for heavy ion collisions. The Micro TPC will use micro-strip gas chambers (MSGCs) to read out the signal. The fine pitch of these devices is well matched to the low diffusion that can be achieved with a short drift distance in dimethyl-ether (DME). This combination makes it possible to achieve much better two-track resolution than has been possible with other TPCs. We have demonstrated that electrons can be drifted in DME over the planned drift distance of 15 cm without

significant attenuation. We have also produced a MSGC on a silicon amplifier chip and demonstrated suitable operation.

DLS Collaboration

S. Beedoe¹, R. Bossingham, M. Bougteb³, J. Carroll¹, W. Christie⁴, W. Gong, T. Hallman¹, L. Heilbron, H.Z. Huang, G. Igo¹, P. Kirk⁵, G. Krebs, A. Letessier-Selvon, L. Madansky⁴, F. Manso³, H.S. Matis, D. Miller⁶, J. Miller, C. Naudet, R.J. Porter², M. Prunet³, G. Roche³, L. Schroeder, P.A. Seidl, Z.F. Wang⁵, R. Welsh⁴, W.K. Wilson, A. Yegneswaran

¹University of California at Los Angeles, Los Angeles, CA, USA.

²University of California at Davis, Davis, CA, USA.

³Université de Clermont II, Aubière, France.

⁴Johns Hopkins University, Baltimore, MD, USA.

⁵Louisiana State University, Baton Rouge, LA, USA.

⁶Northwestern University, Evanston, IL, USA.

EOS Collaboration

S. Albergo¹, F. Bieser, F.P. Brady², Z. Caccia¹, D.A. Cebra², A.D. Chacon⁶, J.L. Chance², Y. Choi⁵, S. Costa¹, J.B. Elliott⁵, M.L. Gilkes⁷, J.A. Hauger⁵, A.S. Hirsch⁵, E.L. Hjort⁵, A. Insolia¹, M. Justice⁴, D. Keane⁴, J. Kintner², V. Lindenstruth³, M.A. Lisa, H. Liu⁴, H.S. Matis, M. McMahan, C. McParland, W.F.J. Mueller³, D.L. Olson, M.D. Partlan, N.T. Porile⁵, R. Potenza¹, G. Rai, J. Rasmussen, H.G. Ritter, J. Romanski¹, J.L. Romero², G.V. Russo¹, H. Sann³, R.P. Scharenberg⁵, A. Scott⁴, Y. Shao⁴, B.K. Srivastava⁵, T.J.M. Symons, M.L. Tincknell⁵, C. Tuvè¹, S. Wang⁴, P.G. Warren⁵, H.H. Wieman, T. Wienold, K.L. Wolf⁶

¹University of Catania, Catania, Italy.

²University of California at Davis, Davis, CA, USA.

³Gesellschaft für Schwerionenforschung (GSI), Darmstadt, Germany.

⁴Kent State University, Kent, OH, USA.

⁵Purdue University, West Lafayette, IN, USA.

⁶Texas A & M University, College Station, TX, USA.

E895 Collaboration

N.N. Ajitanand⁴, J. Alexander⁴, D. Best, F. Bieser, F.P. Brady¹, T. Case, W. Caskey¹, D.A. Cebra¹, J. Chance¹, P. Chung⁴, K. Crowe, A. Das⁸, J. Draper¹, M. Gilkes³, S. Gushue⁵, M. Heffner¹, A.S. Hirsch³, E. Hjort³, L. Huo¹¹, M.L. Justice², P. Kammel, M. Kaplan⁶, D. Keane², J. Kintner⁷, D. Krofcheck¹⁰, R. Lacey⁴, H. Liu², Y.M. Liu¹¹, M. Lisa⁸, R. McGrath⁴, C.P. McParland, Z. Milosevich⁶, D.L. Olson, C. Pinkenburg⁴, N. Porile³, G. Rai, J. Rasmussen, H.G. Ritter, J. Romero¹, R. Scharenberg³, B. Shrivastava³, L. Schroeder, N. Stone, T.J.M. Symons, S. Wang², J. Whitfield⁶, T. Wienold, L. Wood¹, W. Zhang¹¹

- ¹University of California at Davis, Davis, CA, USA.
²Kent State University, Kent, OH, USA.
³Purdue University, Lafayette, IN, USA.
⁴State University of New York at Stony Brook, Stony Brook, NY, USA.
⁵Brookhaven National Laboratory, Upton, NY, USA.
⁶Carnegie Mellon University, Pittsburgh, PA, USA.
⁷St. Mary's College, Moraga, CA, USA.
⁸Ohio State University, Columbus, OH, USA.
⁹Columbia University, Nevis Lab., NY, USA.
¹⁰The University of Auckland, New Zealand.
¹¹Harbin Institute of Technology, Harbin, PR China.

NA49 Collaboration

S.V. Afanasiev⁹, T. Alber¹³, H. Appelshauser⁷, J. Bachler⁵, L.S. Barnby³, J. Bartke⁶, H. Bialkowska¹⁴, C.O. Blyth³, R. Bock⁷, C. Bormann⁹, F.P. Brady⁸, R. Brockmann⁷, N. Buncic^{5,10}, P. Buncic^{5,7}, H.L. Caines³, D. Cebra⁸, P. Chan¹⁶, G. Cooper², J.G. Cramer^{16,13}, P.B. Cramer¹⁶, P. Csato⁴, M. Cyprian¹², I. Derado¹³, O. Dietz¹⁰, J. Dunn⁸, V. Eckardt¹³, F. Eckhardt¹², S. Euler¹², M.I. Ferguson⁵, H.G. Fischer⁵, D. Flierl¹⁰, Z. Fodor⁴, P. Foka⁷, P. Freund¹³, M. Fuchs⁷, F. Gabler¹⁰, J. Gal⁴, M. Gazdzicki⁹, E. Gladysz⁶, J. Grebieszko¹⁴, J. Günther⁹, J.W. Harris², S. Hegyi⁴, L.A. Hill³, I. Huang⁸, M.A. Howe¹⁶, H. Hümmeler¹⁰, G. Igo¹¹, D. Irmscher², P. Jacobs², P.G. Jones³, K. Kadija^{17,13}, V. I. Kolesnikov⁹, M. Kowalski⁶, B. Lasiuk¹¹, P. Levai⁴, A.I. Malakhov⁹, S. Margetis², C. Markert⁷, G.L. Melkumov⁹, J.W. Mitchell⁸, A. Mock¹³, J. Molnar⁴, J.M. Nelson³, G. Odyniec², G. Palla⁴, A.D. Panagiotou¹, A. Petridis¹, A. Piper¹², A.M. Poskanzer², S. Poziombka¹⁰, D.J. Prindle¹⁶, F. Pühlhofer¹², W. Rauch¹³, R. Renfordt^{9,5}, W. Retyk¹⁴, H.G. Ritter^{2,5}, D. Röhrich⁹, C. Roland⁷, G. Roland¹⁰, H. Rudolph², A. Rybicki⁶, A. Sandoval⁷, H. Sann⁷, E. Schäfer¹³, D. Schmisshke¹⁰, N. Schmitz¹³, S. Schönfelder¹³, A. Yu. Semenov⁹, P. Seyboth¹³, J. Seyerlein¹³, F. Sikler⁴, E. Skrzypczak¹⁵, G. T. A. Squier³, R. Stock⁹, H. Ströbele⁹, I. Szentpetery⁴, J. Sziklai⁴, M. Toy^{2,11}, T.A. Trainor¹⁶, S. Trentalange¹¹, M. Vassiliou¹, G. Vesztegombi⁴, D. Vranic^{7,17}, D. Weerasundara¹⁶, S. Wenig⁵, C. Whitten¹¹, T. Wienold², L. Wood⁸, T.A. Yates³, J. Zimanyi⁴, X.Z. Zhu¹⁶, R. Zybent³

- ¹Department of Physics, University of Athens, Athens, Greece.
²Lawrence Berkeley Laboratory, University of California, Berkeley, CA, USA.
³Birmingham University, Birmingham, England.
⁴Institute of Physics, Budapest, Hungary.
⁵CERN, Genève, Switzerland.
⁶Institute of Nuclear Physics, Cracow, Poland.
⁷Gesellschaft für Schwerionenforschung (GSI), Darmstadt, Germany.
⁸University of California at Davis, Davis, CA, USA.
⁹Fachbereich Physik der Universität, Frankfurt, Germany.
¹⁰Fachbereich Physik der Universität, Freiburg, Germany.
¹¹University of California at Los Angeles, Los Angeles, CA, USA
¹²Fachbereich Physik der Universität, Marburg, Germany.
¹³Max-Planck-Institut für Physik, Munich, Germany.

¹⁴Institute for Nuclear Studies, Warsaw, Poland.

¹⁵Institute for Experimental Physics, University of Warsaw, Warsaw, Poland.

¹⁶University of Washington, Seattle, WA, USA.

¹⁷Rudjer Boskovic Institute, Zagreb, Croatia.

STAR ★ Collaboration

N. Added²⁷, H.N. Agakishiev¹⁰, S. Ahmad²⁶, S.A. Akimenko²⁴, A.V. Alyushin¹⁹, M.V. Alyushin¹⁹, N. Amelin¹⁰, J. Amsbaugh³², G.T. Anderson², E. Anderssen¹⁵, L. Andreeva¹⁹, A. Aprahamian²¹, Yu.I. Arestov²⁴, E.V. Atkin¹⁹, V. Avdeichikov¹¹, G.S. Averichev¹⁰, R. Badalian¹⁰, A. Baldwin¹⁴, K. Barish⁷, V.V. Baublis¹⁹, N.I. Belikov²⁴, R. Bellwied³³, V.I. Belousov²⁴, M. Bennett⁵, S. Bennett³³, J. Bercovitz¹⁵, D. Best¹⁵, W. Betts²⁹, H. Bichsel³², J. Bielecki³³, F. Bieser¹⁵, N.N. Biswas²¹, C. Blyth³⁵, B.E. Bonner²⁶, R. Bossingham¹⁵, F.P. Brady⁶, W.J. Braithwaite², C Brown⁸, R. Brown⁴, V. Budilov¹¹, C. Byrd², H. Caines²², N. Carlin²⁷, J.B. Carroll⁷, D.A. Cebra⁶, A. Chalyguine¹¹, J. Chance⁶, W. Chen⁴, S.P. Chernenko¹⁰, M.G. Cherney⁹, J. Chrin⁹, W. Christie⁴, B.V. Chujko²⁴, P. Colarco⁹, G. Cooper¹⁵, T.M. Cormier³³, J.G. Cramer³², H.J. Crawford⁵, M. Cronqvist⁵, D. Crosetto²⁶, A. Darun²², A.M. Davidenko²⁴, J.W. Dawson¹, D. Dayton⁴, A.A. Derevschikov²⁴, P.A. DeYoung⁸, D. Di Massimo⁴, J. Dioguardi⁴, W. Dominik³⁰, M. Duff¹⁶, H. Dyke²², J.E. Draper⁶, I. Duck²⁶, V. Eckardt¹⁷, W.R. Edwards¹⁵, S. Efremov²⁶, V. Emelianov¹⁹, M. Engelage⁵, G. Eppley²⁶, R. Eremeev¹¹, S.V. Erin²⁴, A. Etkin⁴, P. Fachini²⁷, N. Fadeev¹¹, O. Fateev¹⁰, A. Feshchenko¹¹, H. Fessler¹⁷, I. Flores⁵, K.J. Foley⁴, Z. Fraenkel³⁴, A. French³³, P. Freund¹⁷, D. Fritz¹⁵, N. Gagunashvili¹¹, U. Garg²¹, O. Gavrichtchouk¹¹, M. Gazdzicki¹², V. Ghazikhanian⁷, J. Grabski³¹, W. Gong¹⁵, O.A. Grachov²⁴, D. Greiner¹⁵, L. C. Greiner⁵, V. Grigoriev¹⁹, V.V. Grushin¹⁹, V.J. Guarino¹, Y. Guo³³, M. Gupta²⁶, E. Gushin¹⁹, W.N. Haberichter¹, R.W. Hackenburg⁴, J. Hall³³, T.J. Hallman⁴, D. Hardtke²², G. Harper³², J. Harris³⁶, F. Heistermann⁴, C. Henderson¹⁵, S. Heppelmann²³, D.A. Hill¹, N. Hill¹, A.S. Hirsch²⁵, E. Hjort²⁵, G.W. Hoffmann²⁹, M. Howe³², H. Huang²⁵, T.J. Humanic²², J.B. Hunter¹⁵, G.J. Igo⁷, A. Ioukaev¹¹, P.M. Jacobs¹⁵, S.R. Jacobson¹⁵, R. Jamil⁹, R.C. Jared¹⁵, P. Jensen²⁹, P. Jones³⁵, E. Judd⁵, M.L. Justice¹⁴, K. Kadija¹⁷, M. Kaplan⁸, V. Kaplin¹⁹, A. Karakash¹⁹, A. Karev¹¹, P.J. Karol⁸, T. Kasprzyk¹, D. Keane¹⁴, A.M. Khodinov¹⁹, S.R. Klein¹⁵, L. Kolobashkina¹⁹, A. Kolomyichenko¹¹, M. Konrad¹⁷, A.S. Konstantinov²⁴, I. Kossarev¹¹, L. Kotchenda¹⁹, I. Kotov²⁴, N. Kouzmine¹¹, A.D. Kovalenko¹⁰, M.A. Kramer²⁰, H. Kraner⁴, V. Krivokhizh¹¹, E. Kukhtin¹¹, R. Kutuev¹¹, A. Kuznetsov¹⁰, A. LacKamp⁹, V. Ladygin¹⁰, B. Lasiuk⁷, A.N. Lebedev¹⁹, T. Lecompte¹, I. Lee¹⁶, B. Leonhardt⁴, M.J. LeVine⁴, Q. Li³³, Y. Li³³, C. Liaw⁴, V. Lindenstruth⁵, M. Lisa¹⁵, H. Lie¹⁴, A. Ljubicic Jr.³, W.J. Llope²⁶, G. LoCurto²², V. Loginov¹⁹, R.S. Longacre⁴, W.A. Love⁴, D. Lynn⁴, L. Madansky¹³, E. Makliaev¹⁹, S. Margetis¹⁵, K.M. Marks¹⁵, J. Marx¹⁵, R. Matheus²⁷, H.S. Matis¹⁵, Yu.A. Matulenko²⁴, E.A. Matushevsky¹⁰, C.P. McParland¹⁵, T.S. McShane⁹, K. Medved¹¹, R. Mekhdiyev¹¹, A.P. Meschanin²⁴, B. Miller⁴, Z. Milosevich⁸, N.G. Minaev²⁴, R.H. Minor¹⁵, E. Minor²³, J.W. Mitchell¹³, V. Mitsyn¹¹, L. Mogavero⁴, C.F. Moore²⁹, M.G. Munhoz²⁷, L. Muresan¹⁰, R. Muresan¹⁰, J.J. Musulmanbekov¹⁰, G.S. Mutchler²⁶, A.I. Mysnick²⁴, A. Nagaitsev¹¹, J. Nelson³⁵, V.N. Nevolin¹⁹,

P. Nevski⁴, V. Nikitin¹¹, E. Nikonov¹⁰, P. Nomokonov¹⁰, S.B. Nurushev²⁴, V. Odintsov¹¹, G. Odyniec¹⁵, C. Ogilvie¹⁶, D.L. Olson¹⁵, A.St. Oltchak¹⁹, E.M. Onischenko¹⁹, G. Ososkov¹⁰, E. Paganis²⁹, G. Paic³, S. Pandey³³, Yu.A. Panebratsev¹⁰, J. Passaneau²³, A.I. Pavlinov²⁴, A. Pavluk¹¹, T. Pawlak³¹, M. Pentia¹⁰, W. Peryt³¹, D. Peshekhonov¹¹, V. Peshekhonov¹¹, E. Petereit¹, D. Pilipenko¹¹, N.M. Piskunov¹⁰, E.D. Platner²⁶, J. Pluta³¹, I. Polk⁴, N.T. Porile²⁵, A.M. Poskanzer¹⁵, E. Potrebenikova¹⁰, L. Price¹, D.G. Prindle³², C. Pruneau³³, G. Rai¹⁵, A. Rawlins¹⁵, R.L. Ray²⁹, S.V. Razin¹⁰, D. Read²⁹, D. Reichhold²², R.E. Renfordt¹², F. Retiere¹⁵, A. Ridiger¹⁹, P.J. Riley²⁹, J. Riso³³, H.-G. Ritter¹⁵, J.B. Roberts²⁶, D. Roehrich¹², H. Roehrig¹², A.A. Rollefson², J.L. Romero⁶, I. Roufanov¹¹, V.L. Rykov²⁴, I. Sakrejda¹⁵, A.C. Saulys⁴, N. Saviljic¹⁰, I. Savin¹¹, E.Schaefer¹⁷, J.J. Schambach²⁹, R.P. Scharenberg²⁵, J. Scheblein⁴, B. Scheetz⁴, A. Schiemann⁹, R. Schlueter¹⁵, D. Schmischke¹², N. Schmitz¹⁷, L.S. Schroeder¹⁵, M. Schulz⁴, J. Sedlmeir⁴, J.E. Seger⁹, J.C. Seyboth¹⁷, P. Seyboth¹⁷, D. Seymour³², A. Shabunov¹⁰, M. Shafranov¹¹, M. Shafranov¹¹, E. Shahaliev¹⁰, A.V. Shalnov¹⁹, J. Sheen³³, K.E. Shestermanov²⁴, S.S. Shimanskiy¹⁰, A.B. Simakov¹⁹, G. Skoro¹⁰, N.V. Slavin¹⁰, N. Smirnoff³⁶, G. Smirnov¹¹, L.P. Smykov¹⁰, R. Soja⁴, L.F. Soloviev²⁴, S. Somov¹⁹, H.M. Spinka¹, B.K. Srivastava²⁵, R. Stock¹², N.T. Stone¹⁵, M.N. Strikhanov¹⁹, B. Stringfellow²⁵, H. Stroebele¹², E.A. Strokovskiy¹⁰, E. Sugarbaker²², K. Sulimma¹², A. Sustich², D. Swan¹⁸, T.J.M. Symons¹⁵, E.M. Szanto²⁷, A. Szanto de Toledo²⁷, J. Takahashi²⁷, J.L. Tang²⁹, H. Themann²⁶, J. Thomas¹⁵, V. Tikhonov²⁴, M.L. Tincknell²⁵, M.V. Tokarev¹⁰, M. Toy⁷, T.A. Trainor³², S. Trentalange⁷, O.D. Tsay²⁴, I. Tserruya³⁴, C.E. Tull¹⁵, T. Tustonic³, T. Ullrich³⁶, D.G. Underwood¹, Z. Usubov¹¹, A. Vander Molen¹⁸, A.M. Vanyashin¹⁹, V. Vasendina¹¹, A.N. Vasiliev²⁴, M. Vidal¹⁷, G.J. Visser¹⁵, Yu.A. Volkov¹⁹, S.V. Voloshin¹⁹, S. Vorozhtsov¹¹, D. Vranic³, C.Q. Vu¹⁵, F. Wang¹⁵, H.J. Ward²⁹, J.W. Watson¹⁴, D.D. Weerasundara¹⁴, R.P. Wells¹⁵, G.D. Westfall¹⁸, J. Whitfield⁸, C.A. Whitten Jr.⁷, H. Wieman¹⁵, W.K. Wilson³³, J.S. Wirth¹⁵, D.C. Wold², K.L. Wolf²⁸, L. Wood⁶, M. Wright²⁶, N. Xu¹⁵, E. Yee¹⁵, P. Yepes²⁶, A. Yokosawa¹, V.I. Yurevich¹⁰, J. Yurkon¹⁸, Yu.V. Zanevsky¹⁰, W. Zhang¹⁴, N. Zhidkov¹¹, V. Zhiltsov¹¹, R. Zoulkarneev¹¹, R. Zybert³⁵

¹Argonne National Laboratory, Argonne, IL, USA.

²University of Arkansas, Little Rock, AR, USA.

³Rudjer Boskovic Institute, Zagreb, Croatia.

⁴Brookhaven National Laboratory, Upton, NY, USA.

⁵University of California at Berkeley, Space Science Laboratory, Berkeley, CA, USA.

⁶University of California at Davis, Davis, CA, USA.

⁷University of California at Los Angeles, Los Angeles, CA, USA.

⁸Carnegie Mellon University, Pittsburgh, PA, USA.

⁹Creighton University, Omaha, NE, USA.

¹⁰Laboratory of High Energy (JINR), Dubna, Russia.

¹¹Particle Physics Laboratory (JINR), Dubna, Russia.

¹²University of Frankfurt, Frankfurt, Germany.

¹³Johns Hopkins University, Baltimore, MD, USA.

¹⁴Kent State University, Kent, OH, USA.

¹⁵Lawrence Berkeley Laboratory, Berkeley, CA, USA.

¹⁶Massachusetts Institute of Technology, Cambridge, MA, USA.

- 17Max-Planck-Institut für Physik, Munich, Germany.
- 18Michigan State University, East Lansing, MI, USA.
- 19Moscow Engineering Physics Institute, Moscow, Russia.
- 20City College of New York, New York, NY, USA.
- 21University of Notre Dame, Notre Dame, IN, USA.
- 22Ohio State University, Columbus, OH, USA.
- 23Pennsylvania State University, University Park, PA, USA.
- 24Institute of High Energy Physics, Protvino, Russia.
- 25Purdue University, West Lafayette, IN, USA.
- 26Rice University, Houston, TX, USA.
- 27Universidade de São Paulo, São Paulo, Brazil.
- 28Texas A & M University, College Station, TX, USA.
- 29University of Texas at Austin, Austin, TX, USA.
- 30Warsaw University, Warsaw, Poland.
- 31Warsaw University of Technology, Warsaw, Poland.
- 32University of Washington, Seattle, WA, USA.
- 33Wayne State University, Detroit, MI, USA.
- 34Weizmann Institute of Science, Rehovot, Israel.
- 35University of Birmingham, Birmingham, England.
- 36Yale University, New Haven, CT, USA.

Nuclear Theory Program

J. Randrup

The Nuclear Theory Program at Berkeley Lab seeks to address important problems at the frontier of nuclear science to achieve a deeper understanding of the physical nature of quantal many-body systems at and below the hadronic level. This involves developing and applying theories and methods for prediction, analysis, and interpretation of experiments. While the current research program is primarily focused on high-energy nuclear collisions, significant efforts remain in the areas of compact stellar objects, macroscopic nuclear properties, and chaos studies. The main themes are briefly described below.

Parton Dynamics

On the basis of a QCD-inspired partonic description, a number of critical issues in heavy-ion collisions at RHIC energies and beyond have been addressed: the initial condition of the dense matter formed, the approach of such dense parton matter to equilibrium, and the probes of the early parton dynamics. While the initial parton density is found to be very high, it is also far from equilibrium and the equilibration time depends sensitively on the initial parton density. A few hard probes, such as charm, J/ψ , and jets, have been investigated as indicators of the initial parton density and early parton dynamics. Continuing research will seek to reduce the uncertainty in the initial conditions as well as further explore the associated hard probes.

Hard probes of QCD matter

A number of studies have been directed towards heavy-quark production, both in the initial nucleon-nucleon interactions and in the plasma phase. Heavy-quark production in pp collisions has been studied using perturbative QCD at leading order, next-to-leading order, and, near the production threshold, all-order resummation at leading log and next-to-leading log. The knowledge gained from pp physics can help us to understand the level of heavy-quark contribution to the dilepton spectrum at RHIC and LHC although medium effects, such as energy loss by the charm quark moving through the nucleus, may play an important role. This latter effect is being examined in more detail, particularly by including the effects of longitudinal expansion, as is the possibility that $e\mu$ coincidence measurements for open charm decay may provide information on the parton energy-loss mechanism.

Quarkonium production and suppression is an especially interesting topic in light of recent CERN SPS data from NA50 and this data has been addressed in terms of hadronic suppression mechanisms. At higher energies, where plasma production is likely, the high initial temperature of the plasma could lead to Υ suppression or result in the gluons and light quarks gaining an effective mass, thereby enhancing thermal production of heavy quarks in the plasma. Manifestations of higher-twist effects on heavy-quark production are also being pursued, both in the context of the intrinsic charm model and, more recently, in a final-state coalescence model involving the quantum mechanical overlap of the initial- and final-state wave functions on the amplitude level.

Disoriented chiral condensates

A number of investigations have been carried out within the confines of the linear sigma model. In particular, the conditions for the occurrence of the DCC phenomenon has been studied in various collision scenarios and it has been shown that the soft pionic modes become unstable only when a sufficiently rapid expansion or cooling takes place. A variety of possible DCC signatures have been studied, including the power spectra of the emerging pions and the distribution of the neutral pion fraction. Wavelet-type analysis techniques have also been developed for the study of domain structure of the pion field.

Dileptons may be a very sensitive probe of soft pionic modes and dilepton spectra have been calculated with different models in order to examine the prospects for using this observable as a DCC diagnostic. It is planned to explore this mechanism in detail, with an emphasis on the role of other hadrons in DCC formation and decay.

Chiral restoration and in-medium effects

Dilepton production at the CERN SPS has been investigated within a hadronic transport model. It was found that although the CERES data can be explained within errors, the present dilepton data do not provide additional sensitivity to

the initial hadronic configuration. In-medium effects on the pion form factor and the pion dispersion relation lead to changes in the dilepton yield which, however, are smaller than the errors of present data. This calculation will be continued in order to explore the intermediate mass regime.

Studies in the hadronic phase have shown that the chemical equilibration rate is shortened by the presence of vector mesons and also affected by the onset of chiral restoration. Expansion and finite-size effects will be addressed within the transport model, and it is planned to extend these investigations into the strange sector. Furthermore, it is predicted that the $\Lambda(1405)$ has a strongly momentum-dependent in-medium mass shift due to the Pauli principle. The prospects for investigating this effect with pion-induced reactions and stopped kaons are currently being assessed.

The collaborative effort to include the collective spin-isospin modes in transport treatments of heavy-ion collisions is being continued. The formal developments made earlier for nuclear matter have been adapted to the finite, non-equilibrium environment of the colliding system and implemented into an existing nuclear Boltzmann transport code. Dynamical simulations are being carried out in order to ascertain how the pionic collectivity affects experimental observables, such as flow patterns and pion yields.

Chiral models of the nuclear force will be extended to describe hypernuclei and the equation of state for both strange and charmed matter, with relevance for both heavy-ion physics and compact stars. Associated precursor signals for the chiral phase transition in dense matter will be sought and the possible transition to a kaon condensed phase in the core of a neutron star will be also studied.

Transport theory

With a view towards high-energy nuclear collisions, work has been made on developing a suitable transport description from quantum field theory, using a $1/N_f$ expansion, a loop expansion around background fields, and closed time path formalism.

The efforts to take account of quantum effects in dynamical simulations of many-body systems have progressed significantly. Building on earlier work, the quantum fluctuations inherent in wave-packet dynamics have been included into molecular dynamics by means of a quantal Langevin force. The extended description leads to a considerably improved reproduction of the observed intermediate-mass fragment yields for nuclear collisions. The method is quite general and can be employed in other areas of physics as well, for example for atomic clusters where it affects the critical properties of noble gases significantly.

Studies of nuclear dynamics with effective one-body transport theories have recently included the first realistic test application to the multifragmentation of expanding gold nuclei.

Nuclear Astrophysics

Gravity binds nucleons in a neutron star an order of magnitude more strongly than the strong force binds them in nuclei. The Pauli principle is therefore brought strongly into play in distribution the baryon number over many species of baryons and quarks. Suggested observational consequences have so far had little specificity (like cooling for which many different scenarios all fall into only several categories). Several avenues have recently been pursued: formation of low-mass black holes triggered by hyperonization or conversion of the core to quark matter; crystalline structure in the mixed confined-deconfined phase and possible effects on pulsar glitches; and structural changes (such as size and moment of inertia) which will reflect themselves in the time structure of pulsar spin down. Such changes are expected because the density profile changes with angular velocity and centrifugal force, ushering in thresholds for the population of new baryonic species. With each threshold the equation of state will be softened. Therefore the transformations will be reflected in the time-dependence of the pulsar rotation. In particular the signal of a first order phase transition is strongly registered in the braking index of pulsars, a measurable quantity. It is estimated that the signal will be present in about ten of the presently know pulsars if the phase transition does take place.

Macroscopic Nuclear Properties

The long-range aim of this work is to develop a quantitative understanding of the macroscopic properties of nuclei (binding energy, surface energy, density, compressibility, neutron matter, etc.). Using the semi-classical Thomas-Fermi method, we have recently achieved such a description, which yields the binding energy (or mass) of a nucleus as a function of N, Z and the nuclear shape. The model is currently being generalizing to include angular momentum as well. An approximate description of ground-state, super-deformed and fission-isomeric rotational bands, and of the associated moments of inertia has been achieved.

Transition from order to chaos

The development of a macroscopic theory of nuclear dynamics continues based on the parallel between a transition from ordered to chaotic nucleonic motions and the transition from an elastic to a dissipative collective nuclear response. Recent work concerns a comprehensive three-way comparison between classical and quantal computer simulations and the Wall Formula for nuclear dissipation, as applied to the excitation of independent particles in a time-dependent potential well rippled at a wide range of frequencies. Four of the most important corrections to the basic Wall Formula have been included. The results are being applied to a renewed comparison of theory and experiments on fission and nucleus-nucleus collisions.

Nuclear Data Evaluation Program: Isotopes Project

J.M. Dairiki

The Isotopes Project compiles, evaluates, and disseminates nuclear structure and radioactive decay data for basic and applied research. The group coordinates its activities with both the national and international data networks and, in particular, plays a major leadership role in the U.S. Nuclear Data Network (USNDN). The traditional strong data evaluation effort of the group continues and includes a pioneering role in horizontal data evaluations. The Isotopes Project has had a seminal role in modernizing the current nuclear data information system and has become a lead data center for the development of new electronic dissemination and publication methods for nuclear data. Significant and rapid progress is being made in exploiting the capabilities of the World Wide Web.

This annual report period has been particularly productive for the group with the completion of several major projects, many of them in collaboration with researchers from other institutions.

- Publication of the 8th edition of the *Table of Isotopes*, both on CD-ROM and in hard copy, April 1996
- Production and release of the Nuclear Data and References CD-ROM, June 1996—LBNL, Lund University, BNL collaboration
- Publication of the 2nd edition of the *Table of Superdeformed Nuclear Bands and Fission Isomers* —LBNL, McMaster University collaboration

- Release of version 1.0 of VuENSDF software (subsequently renamed Isotope Explorer), July 1996—LBNL, Lund University collaboration
- Internet access of nuclear data

Data Evaluation

New research priorities present special opportunities and challenges for the nuclear data program. Three particular areas of opportunity are the needs of the high-spin research community, where new detector arrays such as Gammasphere and Eurogam are producing data at tremendous rates; nuclear astrophysics, where there is a stated need for a central point for the collection and dissemination of laboratory and theoretical nuclear data of direct relevance to nuclear astrophysics; and the needs of both the basic and applied research communities for critically evaluated decay data standards. In addition, a joint proposal to the U.S.-Hungary Science and Technology Program by G. Molnar (Institute of Isotopes, Budapest) and the Isotopes Project has been funded. This provides resources for the horizontal evaluation of capture gamma-ray data. The Isotopes Project has initiated evaluation efforts in these new areas while also continuing its traditional mass-chain evaluations.

High-Spin Data Evaluation

Following a recommendation at the May 1994 international data network meeting, some of the group's effort has been directed towards the evaluation of high-spin data. B. Singh has coordinated all the U.S. Nuclear Data Network's effort in this field, with evaluators from LBNL, Lund University, McMaster University, BNL, and ORNL. Procedures and guidelines for evaluating high-spin data were developed and communicated to the network. Lists of nuclides of high priority are updated and distributed regularly. Since July 1994, isotope-ordered lists of current nuclear structure experimental papers for both high- and low-spin studies published in ten main journals are prepared by B. Singh and made available (quarterly) to the research community and evaluators via the WWW. Experimental data from many of these recent papers are also being made available via the WWW. This work is ongoing and has gained even more importance since budgetary constraints would not permit hire of an anticipated high-spin data coordinator.

In collaboration with McMaster University, the Isotopes Project has selectively updated data for nuclei in the superdeformed regions with mass numbers $A=81-84$, $130-137$, $142-154$, and $189-198$, entered them into the comprehensive Evaluated Nuclear Structure Data File (ENSDF), and published them in the *Table of Superdeformed Nuclear Bands and Fission Isomers*. These data are updated continuously and are now available via WWW.

The Isotopes Project has compiled/evaluated high-spin data for nuclides with $A=135$, 153 , 163 , 182 , 186 , 188 , 190 , 193 , 194 , and 211 for inclusion in ENSDF. In addition, high-spin data for about 140 isotopes were updated for the *Table of*

Isotopes. These data are available on the Isotopes Project webserver and through the National Nuclear Data Center (NNDC) at BNL.

Decay Data Evaluation

In accordance with another recommendation from the 1994 international meeting, E. Browne (LBNL) and R. Helmer (INEL) have organized an effort to selectively update decay data for radionuclides important for applied research and detector calibration. In collaboration with colleagues at the NNDC and in France (LPRI), Germany (PTB) and the United Kingdom (Imperial College), they prepared a list of about 250 radionuclides in this area. Evaluation of decay data for these nuclides is now underway by the collaboration; 11 completed evaluations are being circulated for review. LBNL has completed 4 decay evaluations— ^{75}Se , ^{194}Ir , ^{188}Re , and ^{192}Ir —as part of this effort. Significant effort was also devoted to developing the guidelines and computer codes necessary to assure consistent evaluation methods and standards. All evaluations will be included in ENSDF and will be submitted to the IAEA for inclusion in its decay-data database.

Nuclear Astrophysics Data Evaluation

At a nuclear astrophysics data workshop held at Caltech in late 1996, a Steering Committee, chaired by Peter Parker (Yale), was formed and charged with ascertaining and prioritizing the data needs of the nuclear astrophysics community. The Steering Committee submitted a "white paper" to DOE in July 1996, calling for a central location for nuclear astrophysics data where evaluated data of diverse types are brought together and made available in a form that facilitates their dissemination and maximizes their utility. LBNL is submitting a proposal (jointly with the Woosley group at U.C. Santa Cruz) to hire a data coordinator and establish such a center at LBNL. Already, in collaboration with U.C. Santa Cruz and S.C. Wu, National Tsing Hua University (Taiwan), LBNL has developed a prototype nuclear astrophysics home page on the WWW (see separate contribution to this report) and several of the existing important nuclear astrophysics databases are now available on-line for the first time. This website is currently accessed over 500 times per month.

Mass Chain Evaluations

The Isotopes Project has permanent responsibility for evaluating 43 mass chains with $A=81, 83, 89-93, 167-194, 206, 210-212, 215, 219, 223,$ and 227 , and for adapting evaluated data with $A=23-26,$ and $33-44$ into the ENSDF format. The group has also accepted temporary responsibility for evaluating mass chains with $A=59, 76, 79,$ and 80 , originally assigned to other centers. Since May 1994 nine mass-chain evaluations ($A=81, 93, 170, 172, 179, 182, 186, 191$ and 194) were completed and submitted for publication, five mass-chain evaluations were reviewed, and thirteen mass chains ($A=76, 81, 168, 170, 172, 173, 178, 179, 180, 182, 185, 191,$ and 194) were published in Nuclear Data Sheets.

Data Dissemination

World Wide Web

The evolution of the Internet and, particularly of the World Wide Web, has changed the paradigm for nuclear data dissemination. Information can be provided easily in a variety of ways. During the past two years, the Isotopes Project has made significant and rapid progress in exploiting the capabilities of the Internet.

Linked home pages for access to data from ENSDF and the Nuclear Science References (NSR) databases as well as the *Table of Isotopes*, high-spin data, nuclear astrophysics data and nuclear masses have been developed. Data are provided in a variety of formats including text, Postscript, and Portable Document Format. Links have also been provided to databases residing at other data centers. Usage of these home pages has increased dramatically since their introduction in April, 1995. Currently about 2500 users log in each month. In 1996 these users made as many as 38,000 link requests per month. The rate of access to each of the home pages is continuing to climb and is summarized in a separate contribution to this report.

Isotope Explorer (VuENSDF)

Version 1.0 of VuENSDF, developed by a collaborative effort between the Isotopes Project and Lund University, was released in July 1996. VuENSDF is a Windows C++ application designed to retrieve ENSDF and NSR information directly over the Internet from a server, from the *Table of Isotopes* CD-ROM, or from a local disk file. It displays level scheme drawings, tabular listings of nuclear levels and transitions, and NSR references. Data can be displayed by nuclear band structure and selected by coincidence relationships. Tables can be constructed according to user specifications, readily sorted by any numerical field, and output as tab-delineated records for input into other user codes. VuENSDF can search the NSR file by keynumber or author and display the keyword abstracts. Tables and drawings may be printed, and a print preview option is offered. VuENSDF can be downloaded from the Web. Running VuENSDF directly provides users with Internet access to nuclear data without requiring a WWW browser, or the program can be used as a helper application with a commercial browser.

In 1996 development began on Version 2.0 of this software which was renamed the Isotope Explorer. The new name reflects the much greater capabilities of the new version. New features include a nuclear chart interface which can access the ENSDF file directly to display level schemes or tables. It can also search for level or transition data, filter and retrieve the data, generate functional relationships between data, and display the results on the chart. Isotope Explorer also includes a new plot display mode to graph the relationships between selected variables. New reference search capabilities are being built into the program so that keyword searches of the NSR file can be performed. More details are available in a separate contribution to this report.

Table of Isotopes, 8th Edition

The 8th edition of the *Table of Isotopes* was published by John Wiley & Sons in April 1996. The 3168-page, 2-volume book is packaged with an interactive CD-ROM that contains the Table of Isotopes in Adobe Acrobat PDF format for viewing on PC and Macintosh personal computers, and on UNIX workstations. The CD-ROM version contains a chart of the nuclides graphical index and separate indices organized for radioisotope users and nuclear structure physicists. Future editions of the *Table of Isotopes* will be provided on CD-ROM and also over the Internet (see separate contribution for more details).

Nuclear Data and References CD-ROM

In 1994 the Lund-LBNL collaboration released Papyrus NSR, a CD-ROM containing the NSR file and the PAPHYRUS bibliographic database management system, to facilitate literature searches on PCs. In June 1996, a new CD-ROM, *Nuclear Data and References*, was released by a Lund/LBNL/BNL collaboration. This CD-ROM, which updates its predecessor (PAPHYRUS NSR) includes:

The Nuclear Science References (NSR) database, with over 140,000 references, updated to December 8, 1995. Retrieval of information can be done using the PAPHYRUS bibliographic database management system, the same software that was used for the 1994 release.

NuDat, a numerical database of nuclear properties, accessed and managed by PCNuDat (software developed at BNL). This database includes data from ENSDF, the Nuclear Wallet Cards, the 1995 update to the Atomic Mass Evaluation, and from Neutron Cross Sections, Vol. 1 and 2.

Table of Superdeformed Nuclear Bands and Fission Isomers

The *Table of Superdeformed Nuclear Bands and Fission Isomers*, first published as an LBNL report in October, 1994, has been updated and published in Nuclear Data Sheets. This publication contains adopted level data for all nuclei with superdeformed bands, moment of inertia plots and level scheme drawings for all superdeformed bands, and related plots for actinide shape (fission) isomers. In addition, a complete reference list is provided for experimental and theoretical superdeformation studies and for fission isomers. Preprints of the 2nd edition were distributed at the Gammasphere Dedication Workshop held in Berkeley on December 1-2, 1995. This publication, prepared in collaboration with McMaster University, is updated continuously and made available on the Internet (see separate contribution to this report).

Summary

The Isotopes Project will continue its leading role in data evaluation and dissemination. Continued development of Internet data dissemination will be a major activity. The goal is to distribute data to the research community using convenient and effective formats, so that the information can be utilized for the advancement of science and technology. The biggest challenge for nuclear data will be to continue to provide quality, up-to-date information. In order to do this, we will work closely with the research community.

88-Inch Cyclotron Operations

C.M. Lyneis

The 88-Inch Cyclotron is a versatile and reliable accelerator of beams from hydrogen to uranium. It is operated by Lawrence Berkeley National Laboratory (LBNL) as a national facility in support of the U.S. Department of Energy programs in nuclear science. Forefront scientific research in nuclear structure, heavy elements, proton-rich nuclei, nuclear astrophysics, fundamental symmetries, and reaction mechanisms is carried out. During FY96, a total of 313 users took part in experiments utilizing 4,942 hours of beam on target. They came from 20 universities, 3 other DOE National Laboratories, 25 foreign institutions and 2 other laboratories. There were 161 scientists and 61 students participating in nuclear science experiments and 88 scientist and engineers participating in non-nuclear science experiments. The Cyclotron also provides beams for the application of nuclear techniques to other areas of research, including biology and medicine and industrial applications. Industrial partners from aerospace and semiconductor corporations, as well as from NASA, DOE, and DOD laboratories, use beams from the Cyclotron to study the interaction of ions in microcircuits, simulating the cosmic-ray environment in space.

The 88-Inch Cyclotron is the site of Gammasphere, a high-resolution gamma-ray detector array that is a major initiative of the nuclear structure research community. It consists of an array of 110 large Compton-suppressed germanium detectors which make it the most powerful such array in the world.

Accelerator Use

Operation of the 88-Inch Cyclotron was at seven days/week in FY96 and will continue at that level through FY97. The Accelerator Operation Summary (Table 1) shows that 80% of the scheduled time was used for research (beam on target) while the remaining time was divided between tuning (11%), machine studies (3%), and unscheduled maintenance (6%). Nuclear research accounted for 3831 research hours, applied research for 910 hours, biology for 72 hours and high energy physics for 110 hours. The applied research—in partnership with the aerospace industry, NASA, DOE, and DOD laboratories—consisted of two parts: (1) testing of microelectronics by using cyclotron beams to simulate space radiation, and (2) calibrating detectors for use in space flights. The biology research was done primarily in support of the NASA NSCORT program.

Ions, Energies, and Intensities

The cyclotron fed by the ECR sources provides a wide range of ions, energies, and intensities in support of the experimental program at the 88-Inch Cyclotron. Using the low and high temperature ovens in the ECR sources, most elements can be accelerated. To date 41 elements have been accelerated including every element from hydrogen to zinc. The beams which have been accelerated are listed in Table 2. The isotopes which are run from natural feeds are listed in parentheses. In addition, many ions have been run using isotopically enriched source materials including ^3He , ^{13}C , ^{15}N , ^{18}O , $^{21,22}\text{Ne}$, $^{33,34,36}\text{S}$, $^{44,48}\text{Ca}$, ^{64}Ni , ^{70}Ge , $^{78,86}\text{Kr}$, ^{136}Xe , and ^{154}Sm . Two of the new beams, ^{64}Zn and ^{54}Cr , developed were both for outside users utilizing Gammasphere. The ^{54}Cr was produced from natural chromium at the required intensity even though its isotopic abundance is only 2.4%. This illustrates the combined power of the ECR ion source and the excellent transmission from ion source to experimenter's target. A 780 MeV ^{162}Dy beam was produced for the study of multinucleon transfer reactions between heavy nuclei, marking the heaviest beam used by Gammasphere to date. We also improved the efficiency of producing ^{36}S beams from the AECS by reducing handling losses which occur when using the isotopically enriched CS_2 .

The variety of beams, energies and intensities described in Table 2 has been developed in support of the research programs. Heavy element radiochemistry experiments require intense (several μA) heavy-ion beams up to mass 48 at 6–8 MeV/nucleon. Groups studying heavy-ion reaction mechanisms and complex fragmentation of highly excited nuclei use higher energy beams such as nitrogen and oxygen at 32 MeV/nucleon, neon at 25 MeV/nucleon, and krypton at 13 MeV/nucleon as well as light-ion beams of ^3He and ^4He over a wide energy range. Light-ion beams are also frequently utilized by other groups. For example, the laser trapping of radioactive beams uses 25 MeV proton beams to produce the ^{21}Na . The study of β -delayed proton emission requires several μA beams of ^3He at 40 to 110 MeV. The nuclear astrophysics group typically uses beams of protons, deuterons, ^3He and ^4He at 8–25 MeV/nucleon.

ECR Ion Source Development

Development of ECR ion sources in FY96 included completion of the AECR upgrade project and the design and construction of a prototype magnet for a very high performance Third Generation ECR ion source, both described below.

The AECR source was upgraded by increasing its magnetic fields to improve its plasma confinement and thereby enhancing the source performance. After a few months of tailoring the magnetic field configuration to match the two-frequency plasma heating (14 and 10 GHz), the upgraded AECR source (AECR-U) with its higher magnetic fields and higher magnetic mirror ratios has demonstrated significantly enhanced performance. For heavy ions at intensity of about 1 eμA, the charge state was shifted from 42+ to 48+ for the heaviest natural element—uranium, and from 41+ to 46+ for bismuth. An order of magnitude enhancement for fully stripped argon ions ($I \geq 60$ eμA) also has been achieved. High charge state heavy-ion beams of xenon-136 and uranium-238 produced by the source were injected into the 88-Inch Cyclotron. After acceleration to energies greater than 10 MeV/nucleon for xenon and 6 MeV/nucleon for uranium, the extracted beam intensities from the cyclotron are 1×10^7 for xenon 41+ and a few hundreds pps of xenon 46+. Even with very low transmission for the highly charged heavy ions due to beam loss from charge exchange with residual gas in the cyclotron, uranium ions with charge states up to 60+ were confirmed with a crystal detector. A few particles per second at a total energy of 1.935 GeV, the highest beam energy ever produced by the 88-inch cyclotron, were measured.

A new very high magnetic field superconducting ECR ion source, the Third Generation ECR is under development at the Cyclotron. It will boost the maximum energies and intensities for heavy ions from the cyclotron. Recent progress on ECR ion sources indicates that significantly higher performance can be obtained by incorporating three key ECR source developments. First, the new ECR source will utilize superconducting magnets so that very high mirror ratios can be used to improve the plasma confinement. Second, multiple frequency heating will be used to provide enhanced electron heating and better plasma stability. Finally, the surfaces of plasma chamber walls will have high secondary emission coefficient such as obtained with Al_2O_3 which will reduce the operating pressure and subsequent loss of high charge states due to charge exchange.

A prototype superconducting magnet structure including three solenoid coils and six race track coils was developed as an FY96 LDRD project. Its design calls for axial field strength of more than 3 Tesla and a radial field strength of more than 2 Tesla. Sufficient superconducting wire from surplus SSC wire was obtained and has been used to fabricate the solenoid and sextupole coils of the prototype magnet structure which will be tested in April 1997 to determine its training characteristics, field strength and quality. Design of the iron yoke, cryostat, plasma chamber, extraction system of the new source are underway with a goal of operation in two years. In FY98, construction and installation of all the main components including the plasma chamber, extraction system, the vacuum system, helium refrigerator, and high voltage system is planned. During

the final phase of the project the RF system required to operate the source with multiple frequencies would be procured and installed.

Other Accelerator Improvement Projects (AIP) at the 88-Inch Cyclotron

The Vacuum Upgrade project is close to completion. The 20°K cryopanel and the 77°K shield have been completed and the shield has been installed and the CTI-1400 refrigeration system from the Bevalac has been installed and tested. The interconnecting piping between the 2 CTI-1400's is complete. The only remaining task is connecting the helium lines between the refrigerators and the new cryopanel

All of the diagnostic components for the Phase Width Reduction project are installed and working including the two fast Faraday Cups with fast Heliac cables to the cyclotron control room. The multi-turn collimator has been upgraded and reinstalled, a fast oscilloscope has been purchased and a fast scintillator system is in operation as a cross check for the fast Faraday Cup signals. A series of beam development runs demonstrated that phase width can be reduced to 1 to 2 ns with the system.

Construction of a redundant personnel radiation safety system is complete. The Data Highway, remote I/O system are complete and software for the Process Logic Controller and Lab View for control and monitoring are ready. The wiring to the Vault and experimental cave is complete. Final connection to the micro switches on the cave doors and the beam plugs will be done in the next month followed by system commissioning.

User Support

The Research Coordination Group provides information, assistance, and coordination to users of the 88-Inch Cyclotron. It is the main contact between the Cyclotron operations staff and outside users. As such, the group is responsible for developing and maintaining experimental facilities at the Cyclotron, and for making these facilities attractive to a diverse group of users from around the country and, in some cases, from around the world.

Our users fall into two classes: (1) scientific users whose experimental proposals are reviewed by a Program Advisory Committee (PAC) and who are awarded time based on the scientific merits of their proposals (or who are awarded discretionary time by the Cyclotron Head), and (2) industrial users who purchase beam time for their own proprietary use.

The Research Coordination Group coordinates the PAC, which meets two-three times a year to review proposals for beam time, and schedules beam time. It sponsors an annual users' meeting at the fall meeting of the Division of Nuclear Physics of the American Physical Society. It supports the Gammaphase Users' Executive Committee through surface mailings and E-mail venues. It

provides information to users of the 88-Inch Cyclotron as well as the general public through the World Wide Web, brochures, and newsletters.

The Research Coordination Group also maintains the electronics module pool and several data acquisition and analysis computers. Upgrade and modernization of the data acquisition system has been occurring regularly over the course of the last several years.

Non-Nuclear Science Research

The 88-Inch Cyclotron is a major source of heavy-ion beams for Single-Event Effect (SEE) testing of solid-state components for the U.S. space program. Because of the ability to run "cocktails" of beams, enabling switches from one ion to another in a matter of minutes, it is possible to quickly establish the energy deposition level at which a SEE will occur. The availability of proton beams, used for studying radiation effects on charge-coupled devices, has further increased the demand for use of the Cyclotron.

The Aerospace Corporation, in cooperation with 88-Inch Operations, has installed a specially instrumented scattering chamber on a dedicated beam line in Cave 4b. A trailer has been installed above Caves 4a and 4b to serve as a counting area for applied programs in those caves. A thin scintillating film transmission detector has been built to measure the beam flux and a beam energy measurement system was adapted from the SuperHILAC for use in the Cyclotron beam lines. These improvements have enabled us to support a large number of small companies and projects who otherwise would not be able to use the Cyclotron.

The 60" chamber in Cave 4a was modified with parts from the sister chamber at the Bevalac in order to install larger diameter beam pipe, allowing the irradiation of parts up to 6" diameter. A sample changer was built to sit in the chamber which can irradiate up to 35 4-6" samples without breaking vacuum. Dosimetry was installed to measure the beam flux and uniformity with scintillating fiber detectors. Using this setup, Si substrates are irradiated for eventual use as flat-panel displays.

The radiation biology program continues to use a small amount of beam time annually. The effect of radiation on cells is studied through the use of high-energy protons, helium, and nitrogen. The Irradiation Station built for the biomed studies has also been used extensively by the high energy physics community to study radiation damage in parts being designed for the Atlas detector at the LHC at CERN.

Table 1. FY96 88-Inch Cyclotron Operating Statistics

Accelerator Operation Summary	
Research	4942 (hours)
Tuning	694
Machine Studies	158
Unscheduled Shutdowns	353
Scheduled Shutdowns	2637
Electrical Energy Consumption (GWH)	8.1
Cost of Electrical Energy (Thousands of Dollars)	558
Financial Support for Accelerator Facility	
Operation (thousands of Dollars)	
Heavy Ion Physics (KB-02-02)	3880
Biomedical and Environmental Research	0
Other Sources	<u>607</u>
Total	4487
Experiment Summary	
Beam Utilization for Research	
Nuclear Research	3831 (hours)
Atomic Physics	19
Biology and Medicine	72
High Energy Physics	110
Other Research	<u>910</u>
Total	4942
Nuclear Science Research	
Universities	20
Other DOE National Laboratories	3
Foreign Institutions	25
Other labs	2
Number of Experiments	85
Number of Scientists Participating	164
Number of Students	61
Non-nuclear Science Research	
Institutions and Companies	20
Number of scientists and engineers	88
Total users (all research)	313
Percentage of Beam Time (all research)	
In-House Staff	40%
Universities	17%
DOE National Laboratories	12%
Companies	5%
Foreign Institutions	11%
Other government labs	<u>15%</u>
Total	100%

Table 2. 88-Inch Cyclotron Beam List

Ion ^a	High Energy ^b (MeV/u)	Typical Current @ High Energy (eμA)	Typical Current @ ≈5–6 MeV/u (eμA)
p	55	6.	20.
p (pol.)	50	0.4	0.7
d	32	0.7	20.
d (pol.)	32	0.2	0.7
³ He	45	10.	10.
⁴ He	32	2.	8.
⁷ Li	23	0.4	1.
⁹ Be	25	0.15	1.
¹¹ B	26	0.05	1.
¹² C	32	0.01	12.
¹⁴ N	32	0.03	5.
¹⁶ O	32	2.	20.
¹⁹ F	24	0.1	3.
²⁰ Ne (22)	27	0.1	4.
²³ Na	25	0.01	0.07
²⁴ Mg (25,26)	23	0.7	3.
²⁷ Al	23	0.07	4.5
²⁸ Si (29,30)	22	0.1	2.
³¹ P	22	0.25	2.
³² S (34)	22	0.2	4.
³⁵ Cl (37)	24	0.01	5.
⁴⁰ Ar	23	0.04	23.
³⁹ K	22	0.03	1.8
⁴⁰ Ca	23	0.04	2.5
⁴⁵ Sc	20	0.023	0.22
⁴⁸ Ti	20	0.03	0.6
⁵¹ V	19	0.03	0.4
⁵² Cr	18	0.03	0.6
⁵⁵ Mn	18	0.03	0.3
⁵⁶ Fe (54)	18	0.03	0.5
⁵⁸ Ni	18	0.02	0.3
⁵⁹ Co	17	0.006	0.2
⁶³ Cu (65)	17	0.04	0.4

Table 2. Continued


Ion ^a	High Energy ^b (MeV/u)	Typical Current @ High Energy (eμA)	Typical Current @ ~5-6 MeV/u (eμA)
⁶⁴ Zn	16	0.02	0.2
⁸⁴ Kr (78,82,86)	14	0.005	6. ^b
¹⁰⁷ Ag	11	0.007	0.2
¹²⁰ Sn (118)	9	0.002	0.1
¹³² Xe (129,131,136)	8	0.005	0.3 ^c
¹³⁹ La	8	0.002	0.03
¹⁵⁴ Sm	7	0.07	0.07 ^b
¹⁵⁹ Tb	7	0.006	0.006
¹⁶² Dy	7	.07	.07 ^b
²⁰⁹ Bi	5	0.005	0.005
²³⁸ U	4	0.001	

- a) Most abundant isotope is listed. Other isotopes run from natural feed are shown in parentheses. Their intensities are proportional to the isotopic abundance, and their high energy values proportional to $1/A^2$.
- b) Current for isotopically enriched sample.
- c) Higher energies beams are available at lower intensities for $M > 16$.

The following ions have been run at the 88-Inch Cyclotron using isotopically enriched source material. The intensity is proportional to enrichment factor and currents for the same element in the table:

¹³C, ¹⁵N, ¹⁸O, ^{21,22}Ne, ^{33,34,36}S, ³⁶Ar, ^{44,48}Ca, ⁶⁴Ni, ⁷⁰Ge, ^{78,86}Kr, ¹³⁶Xe

Group Lists



1995-96 Group Lists

Following are the names of people in the Nuclear Science Division groups. The long-term visitors are included with their home institutions in parenthesis. [Group leaders are in bold face, * = Graduate student, ** = Undergraduate student.]

Administrative Staff

Yvette C. Clinton**
Janis M. Dairiki, Deputy
Erika Decool
Denise Diaz
Joy B. Lofdahl
Meredith Montgomery, Div. Admin.
Barbara E. Phillips
Lee S. Schroeder, Division Director
Jeanette Shereda
Wanda J. Smith-Burnett
Jane D. Toby
Catherine J. Sterling
Sherrill Whyte

For Glenn T. Seaborg,

Associate Director at Large:
Kristin Balder-Froid
Carole P. Logie
Rachel A. Starbuck
Dan L. Tieu

Crystal Barrel

David S. Armstrong
Thomas A. Case
Kenneth M. Crowe (Retired Staff)
Fritz H. Heinsius (UC Berkeley)
Peter Kammel (UCB & Austrian Academy
of Sciences)
Mark T. Lakata*
Leteka S. Thomas** (UC Berkeley)

Exotic Nuclei

Jon C. Batchelder
Joseph Cerny
Dennis M. Moltz
Theodore J. Ognibene*
James D. Powell
Michael Rowe*

Heavy Element Nuclear and Radiochemistry

Yong H. Chung (Hallym)
Albert Giorso (Retired Staff)
Kenneth E. Gregorich

Melissa B. Hendricks*
Darleane C. Hoffman (Retired Staff)
Chris D. Kacher*
Michael R. Lane*
Carola Laue (Feodor Lynen Fellow)
Diana M. Lee
Walter D. Loveland (Oregon State)
Christopher A. McGrath
Victor Ninov
J. Michael Nitschke♥
Tsutomu Otsuki (Tohoku)
Glenn T. Seaborg
Dawn A. Shaughnessy*
Nancy J. Stoyer
Dan A. Strellis*
Eric R. Sylwester*
Alan C. Veeck*
Jerry C. Yang** (UC Berkeley)
Yasuo Watanabe (Fuji Electric Corp.)
Richard J. Wallsgrove** (UC Berkeley)
Birgit Wierczinski
Philip A. Wilk*
Jeb L. Adams*
Christy J. Keoshian*
Nicole S. Wieland*

Isotopes Project

Coral M. Baglin
Edgardo Browne
S-Y. Frank Chu
Janis M. Dairiki
Peter Ekstrom (Lund)
Richard B. Firestone
Jacob Gilat (Soreq)
Henrik Nordberg** (Lund)
Virginia S. Shirley♥
Balraj Singh
S-C. Alice Wu (Nat'l Tsing Hua Univ)
Jean H. Zipkin

Low Background Counting

Donna L. Hurley
Richard J. McDonald
Eric B. Norman
Alan R. Smith (Retired Staff)

Neutrino Astrophysics Group

Yuen-Dat Chan
Lawrence H. Friedman* (UC Berkeley)
Maria C. Isaac
Kevin T. Lesko
Martin E. Moorhead
Anett Schuelke (DAAD Fellow)
Paul Sigismondi (Head-Royce H.S.)
Robert G. Stokstad

Nuclear Astrophysics

Michael R. Dragowsky* (Oregon State)
Daniel DiGregorio (TANDAR, Buenos Aires)
Iuda D. Goldman (Sao Paulo)
Munther Hindi (Tennessee Tech.)
Kenneth S. Krane (Oregon State)
Ruth-Mary Larimer (Retired Staff)
Eric B. Norman
Victor Noto (Mandeville H.S., LA)
Koorosh Zaerpoor* (Oregon State)

Nuclear and Astrophysics

Michael J. Bennett
Henry J. Crawford (UCSSL)
Mats Cronquist (UCSSL)
Jon M. Engelage (UCSSL)
Ismael Flores (UCSSL)
Leo C. Greiner (UCSSL)
Harry H. Heckman (Retired Staff)
Tchang F. Hoang
Eleanor G. Judd (UCSSL)
Sean A. Kelly (UCLA)
Peter J. Lindstrom (UCSSL)
Volker Lindenstruth (UCSSL)
Linda J. Miller (UCSSL)
Zoran Milosevich (CMU)
Ed Platner (Rice)
Gerard J. Visser (UCSSL)
James P. Whitfield (CMU)

Nucleus-Nucleus Collisions

Yudong He
P. Buford Price
Austin A. Richards
Ben Weaver

Nuclear Reactions

Luc Beaulieu
Dimitry E. Breus
Roberta Ghatti* (Lund University)
Kexing Jing*
Luciano G. Moretto
Larry W. Phair
Fabrice Piron* (Univ. of Paris - Orsay)

Thorsten Rubehn
Kin Tso*
Gordon J. Wozniak

Nuclear Structure

Stephen J. Asztalos*
Brian C. Busse* (Oregon State)
Bo W. Cederwall
Roderick M. Clark
Marie-Agnes Deleplanque-Stephens
Richard M. Diamond (Retired Staff)
Paul Fallon
Patrick H.G.M. Hendriks** (Eindhoven Technology)
Reiner Kruecken
I-Yang Lee
Augusto O. Macchiavelli
Randy W. MacLeod
Gregory J. Schmid
Frank S. Stephens
Kai Vetter
Stefan G. Frauendorf (Rossendorf)

Relativistic Nuclear Collisions

Aleksandr V. Alyushin (MEPhI)
Mikhail V. Alyushin (MEPhI)
Dieter Best
Wayne J. Betts* (UT Austin)
Fred S. Bieser
Roy Bossingham
Morgan T. Burks* (Arkansas)
Jim B. Carroll (UCLA)
Daniel A. Cebra (UC Davis)
A. Dean Chacon (Texas A&M)
Michael G. Cherney (Creighton)
Glenn E. Cooper* (UC Berkeley)
Jan T. Chrin (Creighton)
Douglas E. Greiner (Retired Staff)
John W. Harris
Eric L. Hjort (Purdue)
Detlev H.W. Irmscher
Peter M. Jacobs
Susanna R. Jacobson
Marvin L. Justice (Kent State)
Jessoca Kintner
Spencer R. Klein
Anton Konashenok* (UC Berkeley)
Alexei Lebedev (MEPhI)
Michael A. Lisa (Ohio State)
Heng Liu* (Kent State)
Spyridon Margetis
Jay N. Marx
Howard S. Matis
Charles P. McParland
Thomas S. McShane (Creighton)

John C. Meier* (Creighton)
Grayzna Odyniec
Douglas L. Olson
Martin L. Partlan
R. Jefferson Porter
Arthur M. Poskanzer
Gulshan Rai
Fabrice G. Retiere**
Hans-Georg Ritter
Heinrich Rudolph
Iwona Sakrejda
Lee S. Schroeder
Nathan T.B. Stone
T. James M. Symons
James H. Thomas
Milton Y. Toy* (UCLA)
Stephen Trentalange (UCLA)
Fuqiang Wang
Howard H. Wieman
Thomas Wienold
John D. Wolf
Eugene B. Yee

Special Projects

Homer E. Conzett (Retired Staff)
Erwin M. Friedlander (Retired Staff)
Bernard G. Harvey (Retired Staff)
John O. Rasmussen (Retired Staff)
Mark A. Stoyer

Subthreshold Kaons and Antiprotons

John S. Drewery
Selig N. Kaplan
Victor Perez-Mendez (Retired Staff)

Theory

Baha Benhassine (Nantes)
Jan Blocki (Swierk)
Sidney Bludman (Philadelphia)
Paul Bonche (Saclay)
Nicolae Carjan (Bordeaux)
Michael Christiansen (Aarhus)
Stefan Frauendorf (Rossendorf)
Norman Glendenning (Retired Staff)
Johan Helgesson (Lund)
Yuval Kluger
Volker Koch

Peter Levai (Budapest)
Ziwei Lin
Bill Myers (Retired Staff)
Akira Ohnishi (Sapporo)
Patrick Palou (Bordeaux)
Jørgen Randrup
Martin Redlich (Visitor)
Jürgen Schaffner
Janusz Skalski (Swierk)
Chungsik Song
Wladek Swiatecki (Retired Staff)
Robert Vinh Mau (Paris)
Ramona Vogt
Xin-Nian Wang
Fridolin Weber (Munich)
Xiaoming Xu (Shanghai)
Shin-Nan Yang (Taipei)
Jozsef Zimanyi (Budapest)


Weak Interactions

Christopher J. Bowers*
Stuart J. Freedman
Brain K. Fujikawa
Gerald Gwinner
Laura J. Lising*
Justin L. Mortara*
Mary A. Rowe*
Song-Quan Shang
Paul A. Vetter
Eric G. Wasserman


88-Inch Cyclotron Operations

David J. Clark (Retired Staff)
Robert C. Coates
Eduardo I. Diaz
Thomas L. Gimpel
Aran P. Guy
Abraham Katzanck
Ruth-Mary Larimer (Retired Staff)
Claude M. Lyneis
James R. Morel
Margaret A. McMahan Norris
William H. Rathbun
Vicki L. Saling
Catherine R. Siero
Zu Q. Xie

♥ Deceased



Nuclear Structure and Reactions



Beta-Delayed Proton Decay of ^{27}P

T. J. Ognibene, J. Powell, D. M. Moltz, M. W. Rowe, and Joseph Cerny

The decays of the $A=4n+3$, $T_z=-3/2$ series nuclei, with their large beta-decay Q values, offer an opportunity to study Gamow-Teller transition strengths up to high excitation energies. The known members of this series in the sd shell, ^{23}Al , ^{27}P , ^{31}Cl and ^{35}K , all exhibit beta-delayed proton branches. In 1995 we published a βp study of ^{23}Al utilizing our low threshold particle detector telescopes [1]. This work has now been extended to ^{27}P and ^{31}Cl [2].

The isotope ^{27}P ($Q_{\text{EC}}=11.6$ MeV) was produced via the $^{28}\text{Si}(p,2n)$ reaction with 45 MeV protons from the 88" cyclotron impacting on a series of thin natural silicon targets. Radioactive product nuclei recoiled out of the target foils, were thermalized in helium and were swept away on potassium chloride aerosols. These aerosols were transported through a thin capillary and deposited on a collection spot in the detector station. The transport time in this setup was approximately 200 ms, comparable to the ^{27}P half-life of 260 ± 80 ms. The collection point was located on a slowly rotating wheel to reduce the buildup of longer-lived radionuclides.


The deposition spot was observed by two low-energy particle detection telescopes, each consisting of two gas ΔE detectors backed by a single 300 μm silicon detector for measuring the particle energy. The thin ΔE 's allow the separation of protons from alpha and beta events. The use of two ΔE 's further suppresses beta contamination of the identified proton spectrum, necessary in the high beta fluxes typical of helium-jet experiments. These gas detectors are thinner than existing silicon ΔE 's,

leading to a lower detection threshold. In this experiment protons were detectable down to about 240 keV with an energy resolution of approximately 30 keV. This improves on the best previous measurement of ^{27}P [3] where the all-silicon detector telescopes had a low-energy threshold of 700 keV and a resolution of 75 keV.

The measured proton spectrum after a 290 mC bombardment is shown in the accompanying figure. Four lines were identified as belonging to ^{27}P , the lower two of which were not seen previously. A partial decay scheme is inset in the figure. Contamination from the beta-delayed proton decay of ^{28}P , produced via the $^{28}\text{Si}(p,n)$ reaction, was studied through a separate bombardment at $E_p = 28$ MeV, which is below the ^{27}P production threshold. Energy and detection efficiency calibrations were based on the ^{28}P transitions in addition to those from the well-known βp emitter ^{25}Si which was produced via proton bombardment of an aluminum target. The total beta-delayed proton branch of ^{27}P was estimated to be 0.07%.

The measured Gamow-Teller strengths were compared with predictions obtained from shell-model calculations. While a portion of the expected strength was positively identified, a more complete comparison awaits a $\beta\gamma$ measurement of the ^{27}P decay below the proton threshold.

1. R. J. Tighe *et al.*, Phys. Rev. C52 (1995) R2298.
2. T. J. Ognibene *et al.*, Phys. Rev. C54 (1996) 1098.
3. J. Äystö *et al.*, Phys. Rev. C32 (1985) 1700.



Proton Capture on ^7Be and the Solar Neutrino Problem

J. Powell, D. M. Moltz, M. W. Rowe, and Joseph Cerny

The observed deficit of neutrinos coming from the sun, in comparison to the calculations of solar models, constitutes the Solar Neutrino Problem. This observed ratio is about 1/4 to 1/2. Of the three types of neutrino measurements reported to date, capture on ^{37}Cl , water Cherenkov, and capture on ^{71}Ga , the first two methods are primarily sensitive to neutrinos from beta decay of ^8B . Thus, the predicted event rates for these two methods are sensitive to potential inaccuracies in the experimentally determined cross sections of reactions that lead to the creation of this isotope, as these measurements serve as input into the solar model calculations. One significant reaction is the capture of a proton onto a nucleus of ^7Be to form ^8B . This is the sole reaction creating ^8B .

A survey of previous experiments on $^7\text{Be}(p,\gamma)^8\text{B}$ reveals moderate but significant systematic inconsistencies both between separate measurements and in modeled fits to the individual data sets. These differences are on the order of 25%. Although a resolution of the uncertainty in this one reaction rate cannot account for the solar neutrino problem, an accurately determined solar neutrino emission spectrum is necessary in order to relate the results of current and future neutrino experiments to the various models, such as neutrino oscillations, that have been proposed to account for the observed discrepancy.

We are currently working on an improved measurement of the low-energy cross section of $^7\text{Be}(p,\gamma)^8\text{B}$, in collaboration with TUNL†. The radionuclide ^7Be ($t_{1/2} = 53$ d) will be produced via a (p,n) reaction on ^7Li . The beryllium will be chemically separated and purified, and subsequently electroplated onto a target backing. During the experiment, the ^8B produced by irradiation with the proton beam will be detected by the alpha particles emitted following beta decay to $^8\text{Be}^*$ ($t_{1/2} = 0.77$ s). These alphas will be detected in a large area gas ΔE -gas ΔE -silicon E detector telescope of a design similar to the detectors currently used by our group [1,2]. The ΔE detectors are necessary to filter out events resulting from the intense flux of γ rays emitted by the decaying ^7Be . The target will be fixed to a wheel that will transfer it, on a time scale of about one second, between the

proton beam and the detector. Both the ^7Be target and detector system are being developed by LBNL, while the measurement itself will be performed at TUNL, where a special low-energy, high-current accelerator is being built for this experiment.

This experiment will improve on previous work [3] primarily through use of a target containing ten times as much ^7Be . This, combined with our detector and the new accelerator, will allow the cross section to be accurately determined to lower energies than previously measured.

† Triangle Universities Nuclear Laboratory, Durham, North Carolina 27708

1. D. Moltz *et al.*, Nuc. Instr. Meth A349 (1994) 210.
2. M. W. Rowe *et al.*, (submitted to Nuc. Instr. Methods).
3. B. W. Filippone *et al.*, Phys. Rev. C28 (1983) 2222.

Search for Proton Decay from an Isomer of ^{77}Rb with RAMA

M. W. Rowe, D. M. Moltz, J. Powell, and Joseph Cerny

Direct proton emission was first discovered in a high spin isomer of ^{53}Co ^{1,2}. The measured half-life of $^{53\text{m}}\text{Co}$ is 247 ms and this proton decay is a 1.5% branch. Subsequently, ground state proton emission has been observed in many nuclei from ^{105}Sb to ^{187}Re ; however, $^{53\text{m}}\text{Co}$ remains the only example of proton decay from an isomeric state of a nuclide with a proton-bound ground state. There is a prediction³ that several nuclides in the mass 80 region could also have high-spin isomers which would be unbound to proton emission.

One such nuclide, ^{77}Rb , is predicted to have an isomer that is unbound by 2.93 MeV. This isomer would have a spin of $19/2^-$ and would be formed by coupling a single $f_{5/2}$ proton hole state with a pair of $g_{9/2}$ neutrons. Although proton decays of this energy typically occur in $<10^{-15}\text{s}$, Bugrov *et al.*,⁴ have predicted a proton-decay partial half life of 240 ms due to the large centrifugal barrier for this decay ($l=9$). In order to allow the proton decay to be observed, gamma decay would have to be strongly hindered. Although gamma deexcitation to one of the high-spin rotational-band states known to lie below the isomer in excitation energy could in principle occur, differences in the wavefunctions of these collective-mode states and the many-particle isomeric state may lead to significant gamma-decay suppression.

^{77}Rb is produced in high yield in the $^{40}\text{Ca}(^{40}\text{Ca}, 3p)$ reaction at 150 MeV. Unfortunately, competing reactions produce not only the well-known beta-delayed proton emitter ^{77}Sr ⁵, but also weak delayed-proton emitters, observed by our group in previous helium-jet studies. This leads to a weak proton background up to 6 MeV. For this reason, we had to employ our on-line mass separator RAMA⁶ to eliminate this proton background. Previous studies of alkali metals demonstrated typical efficiencies of 1%. However, the large recoil energies present in this reaction significantly lower the helium-jet efficiency from a typical value of 50% to less than 5%. A recent test measurement demonstrated an efficiency for Rb commensurate with these expectations.

RAMA⁷ has been fully upgraded in the past several years. To allow the separator to be fed by a capillary that is only 25 cm long, the ion

source has been moved to the bombardment area, just above the target. This change has reduced the He-jet transport time from 200-300 ms to approximately 15 ms. The recently-completed search for the proton decay of $^{77\text{m}}\text{Rb}$ represented the first long experiment to utilize RAMA since the upgrade was completed.

Throughout the experiment, the amount of ^{77}Rb activity collected was monitored via observation of the beta-delayed gamma-ray decays of the ground state. Preliminary analysis indicates that approximately 2×10^6 ^{77}Rb atoms were transported to the detector station during the 5-shift bombardment. To measure proton decays, we employed a single gas ΔE - gas ΔE -silicon E telescope subtending a solid angle of $23 \pm 1\%$ of 4π . Since there could have been unusual events due to high voltage sparking of the RAMA electrostatic components, we continued running the detectors and RAMA at mass 77 for an additional 6 shifts to adequately check the background rate. No adjustments to the mass separator were necessary during the entire 11 shifts.

Preliminary analysis of the data has yielded no evidence of the predicted proton peaks. Our sensitivity is approximately 1×10^{-5} relative to feeding of the ground-state (based on the detector solid angle and the number of atoms transported). This indicates that either the isomeric state is not strongly fed by the reaction used, gamma-decay is insufficiently hindered to allow proton emission to compete or a combination of these two effects is present.

¹K. P. Jackson *et al.*, Phys. Lett., **33B** (1970) 281.

²J. Cerny *et al.*, Phys. Lett., **33B** (1970) 284.

³L. K. Peker *et al.*, Phys. Lett., **36B** (1971) 547.

⁴V. P. Bugrov *et al.*, Yad. Fiz. **42** (1985) 57.

⁵J. C. Hardy *et al.*, Phys. Lett., **63B** (1976) 27.

⁶F. B. Blonnigen *et al.*, Nucl. Instr. Meth., **B26**(1987) 328.

⁷T. J. Ognibene, *P.h.D. Thesis*, Report LBNL-38848, unpublished.

Calibration of Low-Energy Particle-Identification Telescopes

M. W. Rowe, D. M. Moltz, T. J. Ognibene, J. Powell and Joseph Cerny


In 1993, this group began making proton spectroscopy measurements with a unique detector array incorporating six low-energy particle identification telescopes¹. These telescopes represent the culmination of a series of designs intended to lower the proton energy threshold from ~700 keV using traditional telescopes to ~200 keV, allowing a wide range of novel measurements to be made. The traditional Si ΔE detector has been replaced in this design by two gas-ionization ΔE detectors. The gas is confined by a thin polypropylene window; the electric field is created collinear with the incident radiation between a central grid held at a high positive voltage and two outer signal-grids floating near ground.

Over the following two years, much effort went into understanding the response of these telescopes to protons and alpha particles in a high beta radiation environment. One of the first experiments performed using this array was a measurement of the beta-delayed proton decay of ²³Al through its isobaric analog state (IAS) in ²³Mg². Because this state is unbound to proton emission by only 220 keV (c.m.), calibration of the decay spectrum at low energies required the development of a reliable method of extrapolation from higher-energy calibration points down to the low-energy threshold of the detectors.

Since there are no standard calibration sources of decay protons, proton calibrations are generally accomplished *in situ* using beta-delayed protons emitted from ²⁵Si produced via the ³He + ²⁴Mg reaction at 40 MeV³. Unfortunately, the lowest energy proton group emitted by ²⁵Si has a laboratory energy of 386.1 keV; other than ²³Al, no emitter of lower energy protons is known. A linear extrapolation of the calibration of the Si E detector from the higher energy points would not be accurate due to two factors which increasingly cause the calibration to deviate from linearity at low energies. First, the stopping power of the detector materials increases with decreasing proton energy. Because of this, as the threshold is approached an ever-greater proportion of the incident energy is lost in the non-active components of the telescope (the window, part of the gas and the Si E dead layer). Secondly, there is a slight non-linearity between the input and output of the slow-signal electronics that is most severe near the detection threshold.

To calibrate the detector telescopes before each experiment, we make ²⁵Si as described above. We calculate the energy which will be lost by its decay protons in the window, gas and Si deadlayer using the stopping powers given in ref. 4; these are subtracted from the incident energy to determine the energy which will be detected in the Si E detector. We measure the non-linearity of the detector electronics with a precision pulser; observed channel numbers are then corrected for this non-linearity. A linear fit is made of calculated energy detected in the E detector to corrected channel. If new proton groups are observed during the primary experiment, the energy detected in the Si E is calculated from this fit, then the energy loss calculation is reversed to find the incident energy of the new groups.

To test the reliability of this procedure, two experiments were performed in which a series of thin Al foils were used to degrade protons from ²⁵Si (and alpha particles from ²⁰Na) to energies below the threshold for detection. The figure below shows a linear fit of energy to channel before and after correction for the electronics and energy losses. Using this method, it was determined that the low-energy threshold is ~180 keV for detecting protons and is ~450 keV for detecting alpha particles.



1. D. Moltz *et al.*, Nuc. Instr. Meth A349 (1994) 210.
2. R. J. Tighe *et al.*, Phys. Rev. C52 (1995) R2298.
3. J. D. Robertson *et al.*, Phys. Rev. C42 (1990) 1922.
4. M. J. Berger, ed., Stopping Powers and Ranges for Protons and Alpha Particles (ICRU Report 49, 1993).

Gas Phase Chromatography of FrBr and BiBr₃.

E. R. Sylwester, D. C. Hoffman, J. Adams, Y. H. Chung, K. E. Gregorich, M. B. Hendricks, M. R. Lane, C. Laue, D. M. Lee, C. A. McGrath, D. A. Shaughnessy, D. A. Strellis, P. A. Wilk.

The Heavy Element Volatility Instrument (HEVI)¹ was used to investigate the volatility of the Fr and Bi bromides. HEVI is an isothermal gas phase chromatography system which separates short lived isotopes based on their volatility. A He/KBr gas jet was used to transport the recoil products- the 4.8-min. ²²¹Fr and its granddaughter the 45-min. ²¹³Bi - from a ²²⁵Ra/²²⁵Ac source.

The recoil products were continuously collected on a quartz wool plug kept at 900° C in a quartz chromatography column. HBr was added at a rate of 100 ml/min in order to form the volatile bromide species of Fr, which were then swept into the isothermal section of the chromatography column. The separated species were reattached to KBr aerosols and transported through a capillary system onto a glass wool filter. After a collection time of 5 minutes, the filter was taken out and counted on a PIPS (Passivated Ion implanted Planar Silicon) detector.

The volatility of each species was established by determining yield as a function of the temperature of the column. Due to the long half-life of the Bi granddaughter, the chemistry and collection time used (5 minutes each) was insufficient to provide an accurate measure of volatility. The alpha peak from the ²¹⁷At daughter was also seen, however due to the extremely short half-life of this species (32ms) no information about the chemical behavior could be determined; instead, the Astatine appeared wherever the Fr parent was found. FrBr was shown to be volatile at 550° C while preliminary data on BiBr₃ show it to be volatile around 250° C.

In past experiments the species studied in HEVI have shown an unusually high (non-zero) yield at the low temperatures of 50-150° C. This

yield was observed to drop to 0% at about 150-200° C before rising in the expected volatility curves for each species. The 4.8-min. ²²¹Fr recoil product was used to investigate this effect by varying the amount of HBr and quartz wool used in column and again determining the yield as a function of temperature.

The high low-temperature yield effect was seen to appear at temperatures up to 250° C even with no halogenating agent (HBr) present and no quartz wool in the column. With the addition of quartz wool, the effect was seen to drop but still appeared at temperatures up to 150° C. With the addition of more quartz wool, the effect again dropped in yield but was still present at the temperatures of 50 and 100° C. In none of these experiments did the addition or lack of the halogenating agent make any significant difference in the low-temperature yield.

These results indicate that the low-temperature yield observed is not a result of the chemical volatility of the compound- which would require a halogenating agent. Instead it is a function of mass transport that allows a percentage of the activity to pass through the column unimpeded, in effect acting as a gas jet instead of a chromatography column. This effect is reduced by the presence of the quartz wool at the beginning (900° C) section of HEVI, which breaks up the KBr clusters which are responsible for transport in the gas jet, and reduces the amount of activity entering the isothermal section of the column without the presence of a halogenating agent.

Footnotes and References

1. B. Kadkhodayan et al., *Nucl. Instr. Meth. A317*, 254 (1992).

Gas Phase Chromatography of HfBr₄

E. R. Sylwester, D. C. Hoffman, J. Adams, Y. H. Chung, K. E. Gregorich, M. B. Hendricks, M. R. Lane, C. Laue, D. M. Lee, C. A. McGrath, D. A. Shaughnessy, D. A. Strellis, P. A. Wilk.

The Heavy Element Volatility Instrument (HEVI)¹ was used to investigate the volatility of HfBr₄. HEVI is an On-line isothermal gas phase chromatography system which separates short lived isotopes based on their volatility. The 6.8-min ¹⁶⁶Hf, the 1.7-min ¹⁶⁵Hf, and the 2.0-min ¹⁶⁷Hf were produced at the 88-Inch Cyclotron by the reaction of ¹⁹F with a target of natEu. Reaction products were transported by a He/KBr gas jet system and continuously collected on a quartz wool plug kept at 900° C in a quartz chromatography column. HBr was added at a rate of 100 ml/min in order to form the volatile species HfBr₄, which was then swept into the isothermal section of the chromatography column, where it was separated from the other reaction products. The separated species was reattached to KBr aerosols and transported through a capillary system onto a glass wool filter placed in front of an intrinsic Ge gamma detector.

¹⁶⁵Hf was identified by gamma spectroscopy of the 180 keV gamma line. ¹⁶⁶Hf was identified by gamma spectroscopy of the 78.76 keV line, and ¹⁶⁷Hf was identified by its 315.24 keV line. Volatility was determined by measuring the yield of each isotope simultaneously as a function of the temperature of the column. All three isotopes showed exactly the same volatility behavior when their different half-lives were taken into account, as expected. The temperature at which HfBr₄ was observed to be volatile was 250° C.

A Monte Carlo simulation program² was used to calculate the adsorption enthalpy of these species based upon their volatilities. The adsorption enthalpy for HfBr₄ on a SiO₂ surface based upon the volatility data collected was calculated to be -107±5 kJ/mol.

Figure 1 shows the volatility data collected for ¹⁶⁵Hf and ¹⁶⁷Hf. The yield curves shown are the volatility curves calculated by the best fit of the data to an adsorption enthalpy value of -107±5 kJ/mol using the Monte Carlo simulation program.

Footnotes and References

1. B. Kadkhodayan, *et al.*, *Nucl. Instr. Meth.* **A317**, 254 (1992).
2. A. Türler, K. E. Gregorich, D. C. Hoffman, D. M. Lee, H. W. Gäggeler, LBL annual report #31855, Nuclear Science Division (1991).




Fig. 1. Observed yields of HfBr₄ as a function of temperature. The fitted curves show the expected yield based upon the Monte Carlo calculation of an adsorption enthalpy of -107±5 kJ/mol, which is the best fit to the data.

Gas Phase Chromatography of WBr₆

E. R. Sylwester, D. C. Hoffman, J. Adams, Y. H. Chung, K. E. Gregorich, M. B. Hendricks, M. R. Lane, C. Laue, D. M. Lee, C. A. McGrath, D. A. Shaughnessy, D. A. Strellis, P. A. Wilk.

The Heavy Element Volatility Instrument (HEVI)¹ was used to investigate the volatility of the W bromides. HEVI is an On-line isothermal gas phase chromatography system which separates short lived isotopes based on their volatility. The 2.4-min. ¹⁷¹W and the 8.0-min. ¹⁷²W were produced at the 88-Inch Cyclotron by the reaction of ²⁰Ne with a target of natGd. Reaction products were transported by a He/KBr gas jet system and continuously collected on a quartz wool plug kept at 900° C in a quartz chromatography column. HBr was added at a rate of 100 ml/min in order to form the volatile bromide species of W, which were then swept into the isothermal section of the chromatography column. The separated species were reattached to KBr aerosols and transported through a capillary system onto a glass wool filter placed in front of an intrinsic Ge gamma detector. ¹⁷¹W was identified by gamma spectroscopy of the 184, 294, and 479 keV lines and its volatility determined. ¹⁷²W was identified by gamma spectroscopy of the 424 and 548 keV lines and its volatility was determined. As expected, both isotopes showed exactly the same volatility behavior when their different half-lives were taken into account. The temperature at which WBr₆ was observed to be volatile was determined to be 130° C.

A Monte Carlo simulation program² was used to calculate the adsorption enthalpy of these species based upon their volatilities. The adsorption enthalpy was calculated to be -82 ± 5 kJ/mol for WBr₆ on a SiO₂ surface based upon the volatility data collected.

Figure 1 shows the data for the most prominent gamma lines of each of the three isotopes, and the volatility curve calculated using an adsorption enthalpy of -82 ± 5 kJ/mol for ¹⁷²W. The variation in yield with isotope is a function

of the differences in their half-lives, but this variation results in no change in adsorption enthalpy when half-life is taken into consideration.

Footnotes and References

1. B. Kadkhodayan, *et al.*, *Nucl. Instr. Meth.* **A317**, 254 (1992).
2. A. Türler, K. E. Gregorich, D. C. Hoffman, D. M. Lee, H. W. Gäggeler, LBL annual report #31855, Nuclear Science Division (1991).




Fig. 1. Observed yields of WBr₆ as a function of temperature. Only the data from the most prominent gamma line of each isotope is shown. The fitted curve shows the expected yield based upon the Monte Carlo calculation of an adsorption enthalpy of -82 ± 5 kJ/mol, and is the best fit to the data.

Chemical Studies of Rutherfordium (Element 104)*

C.D. Kacher**, K.E. Gregorich, D.M. Lee, B. Kadkhodayant, S.A. Kreek‡, M.R. Lane, M.F. Mohar§, M.P. Neu%, N.J. Stoyer‡, E.R. Sylwester, Y. Watanabett, B. Wierczinski, A. Bilewicz#, D.C. Hoffman

Abstracts of three papers on chemical studies of rutherfordium* which have been accepted for publication in *Radiochemica Acta* are given below:

Part I. Thin Film Ferrocyanide Surfaces for the Study of the Hydrolysis of Rutherfordium.

The chemical properties of element 104, rutherfordium (Rf), and its group 4 homologs were studied by sorption on glass support surfaces coated with cobalt ferrocyanide. The surface studies showed that the hydrolysis trend in the group 4 elements and the pseudogroup 4 element, Th, decreases in the order $Rf > Zr \approx Hf > Th$. This unexpected trend was attributed to relativistic effects which predict that Rf^{4+} would be more prone to having a coordination number (CN) of 6 than 8 in aqueous solutions due to a destabilization of the $6d_{5/2}$ shell.

Part II. Solvent Extraction into Tributylphosphate from HBr Solutions.

The chemical properties of element 104, rutherfordium (Rf), and its group 4 homologs and other tetravalent cations were studied by solvent extraction into tributylphosphate (TBP) from various concentrations of HBr and HCl. Since bromide is a larger and softer (more polarizable) anion than chloride, the stability of Rf-bromide complexes was expected to differ from the stability of Rf-chloride complexes, and a comparison of the two systems was undertaken. Our studies showed that the extraction trend decreased in the order $Zr > Hf > Rf/Ti$ for HBr, compared to $Zr > Hf > Rf > Ti$ for HCl, showing that Rf and Ti did not extract as well in either system, probably because they hydrolyzed more easily than Zr and Hf.

Part III. Solvent Extraction into Triisooctylamine from HF Solutions.

The extraction of element 104, rutherfordium (Rf), and its group 4 homologs into 0.25 M triisooctylamine (TIOA) in *o,m,p*-xylene from various concentrations of hydrofluoric acid was studied. This extraction system was of particular interest because all group 4 cations studied formed complexes with the same coordination number (CN) of 6. Therefore, species extracted were similar and the extractability depends on the radii of the fluoride complexes. The studies showed that the extractability for the group 4 elements in this system decreases in the order $Ti > Zr \approx Hf > Rf$, in inverse order from the decrease in ionic radii $Rf > Zr \approx Hf > Ti$. This order is different than the order in the hydrolysis, TBP-HCl, and TBP-HBr extraction systems where Rf, due to decreasing CN, behaves more similarly to Ti than to Zr and Hf.

Footnotes and References

*This research constituted a major part of Christian D. Kacher's Ph. D. Thesis, December, 1995, Chemistry Department, University of California, Berkeley, CA.

** William O'Neil & Co., Inc., 12655 Beatrice St., Los Angeles, CA 90066.

† LAM Associates, 4330 Terrabella Way, Oakland, CA 94611.

‡ Lawrence Livermore National Laboratory, L-231, Livermore, CA 94550.

§ EG&G Energy Measurements, Washington Aerial Measurements Division, P.O. Box 380, Suitland, MD 20752.

% Los Alamos National Laboratory, MS G-739, Los Alamos, NM 87544.

†† #102 GS-heim, 3-3-8 Asahi-ga-oka, Hino, Tokyo 191 JAPAN

Department of Radiochemistry, Institute of Nuclear Chemistry and Technology, 03-195, Warszawa, Poland

First Chemical Separations of Seaborgium (Element 106)

K.E. Gregorich, D.C. Hoffman, E.R. Sylwester, D.M. Lee, and the LBNL, GSI,† Mainz,‡ Dresden,£ Krakow,• JAERI, PSI,ø Bern,Δ Rossendorf,∞ JINR,§ Oslo,¶ Chalmers,∂ Collaboration*

The first chemical separations of seaborgium (Sg, element 106) have been performed in both the aqueous- and gas-phase.

Experiments to determine the chemical properties of lawrencium (Lr, element 103), rutherfordium (Rf, element 105), and hahnium (Ha, element 105) have clearly shown that the actinide series ends with Lr, and that Rf and Ha are the first two members of the 6d series of transition metals, with Lr^{3+} , Rf^{4+} , and Ha^{5+} being the most stable oxidation states. While the most general chemical properties of Rf and Ha indicate that they are members of the fourth and fifth groups of the periodic table, respectively, we have found that the detailed chemical properties of these first two transactinide elements cannot be reliably extrapolated from the chemical properties of their lighter homologs. These deviations from the periodicity of the elements have been explained as being due to relativistic effects in the electronic orbitals. In this light, it is of great interest to investigate the the chemical properties of Sg, and compare its chemical properties to the lighter periodic table homologs, W and Mo.

Recently, ^{265}Sg ($E_{\alpha}=8.8$ MeV, $t_{1/2}\sim 8$ s) and ^{266}Sg ($E_{\alpha}=8.6$ MeV, $t_{1/2}\sim 13$ s) have been identified in $^{22}\text{Ne} + ^{248}\text{Cm}$ bombardments.¹ The half-lives are long enough to allow chemical separation with the most modern techniques, and the production rates are sufficient for detection of about 1 atom per day (after chemical separation).

In the chemical experiments, ^{266}Sg and ^{265}Sg were produced in ^{22}Ne bombardments of ^{248}Cm targets at the GSI UNILAC. Products were transported to the chemical separation apparatus via an aerosol-loaded gas-jet.

Gas-phase chemical separations² were performed with the OLGA III gas-phase

isothermal chromatography apparatus. Volatile oxychlorides of Sg were formed, and their retention time in a quartz column was measured as a function of the temperature of the column. We found Sg oxychlorides to be somewhat less volatile than oxychlorides of Mo and W formed under the same conditions.

Aqueous-phase chemical separations⁴ were carried out with the ARCA⁵ apparatus, a miniaturized, computer-controlled, liquid column chromatography apparatus. ^{265}Sg was eluted from cation exchange-resin (Aminex A6) columns with 0.1 M $\text{HNO}_3/5\times 10^{-4}$ M HF. Under these conditions, the ^{261}Rf and ^{257}No α -decay products of ^{265}Sg are strongly retained on the columns. Observation of the decays of ^{265}Sg daughter activities, ^{261}Rf and ^{257}No , after the columns indicates that Sg forms neutral or anionic complexes (presumably SgO_4^{2-}). This behavior is similar to measured properties of the periodic table homologs, W^{6+} and Mo^{6+} , and unlike that of U^{6+} .

Footnotes and References

- † Gesellschaft für Schwerionenforschung, Germany
 - ‡ Universität Mainz, Germany
 - £ Technische Universität Dresden, Germany
 - Niewodniczanski Inst. of Nucl. Phys, Poland
 - * Japan Atomic Energy Research Institute, Japan
 - ø Paul Scherrer Institut, Switzerland
 - Δ University of Bern, Switzerland
 - ∞ Institut für Radiochemie, Rossendorf, Germany
 - § Joint Institutes for Nuclear Research, Dubna, Russia
 - ¶ University of Oslo, Norway
 - ∂ Chalmers University of Technology, Sweden
 - ¥ Inst. for Radiochem. Research, Rossendorf, Germany
1. Yu.A. Lazarev, et al., Phys. Rev. Lett. **73**, 624 (1994).
 2. A. Türler et al., NRC4 Conf., St. Malo, France, (1996).

Production and Decay of ^{265}Sg and ^{266}Sg

K.E. Gregorich, B. Kadkhodayan, B. Wierczinski, D.M. Lee, C.D. Kacher, D.A. Shaughnessy, M.R. Lane, E.R. Sylwester, M.B. Hendricks, N.J. Stoyer, A.C. Veeck, D.C. Hoffman

Predictions of enhanced nuclear stability¹ due to deformed nuclear shells near $N=162$ and $Z=108$, have recently been confirmed with the detection² of ^{265}Sg and ^{266}Sg using the Dubna gas-filled separator. In the Dubna experiments, the ^{265}Sg and ^{266}Sg half-lives were not measured (although α -decay systematics indicated half-lives between 2-s and 30-s). In addition, the measured production cross sections for the $^{248}\text{Cm}(^{22}\text{Ne},4-5n)^{266-265}\text{Sg}$ reactions were accurate to only a factor of three.

The estimated half-lives for $^{265,266}\text{Sg}$, together with the production cross sections of $\sim 100\text{pb}$, make measurement of the chemical properties of Sg possible for the first time. Measurement of the half-lives, and refinement of the production cross sections are important in the understanding of the strength and extent of the $N=162$ deformed shell, and necessary in planning for the chemical experiments.

In experiments at the LBNL 88-Inch Cyclotron, we searched for ^{265}Sg and ^{266}Sg produced in the $^{22}\text{Ne} + ^{248}\text{Cm}$ reaction at ^{22}Ne bombarding energies of 116- and 121-MeV. Activities recoiling out of the target were transported with a He/KCl gas-jet to the MG rotating wheel system where we looked for the following decay chains: $^{265}\text{Sg} \Rightarrow ^{261}\text{Rf} + \alpha \Rightarrow ^{257}\text{No} + \alpha \Rightarrow ^{255}\text{Fm}$ and $^{266}\text{Sg} \Rightarrow ^{262}\text{Rf} \Rightarrow \text{fission}$. At the MG, the activities were collected on $50\text{-}\mu\text{g}/\text{cm}^2$ polypropylene foils at the periphery of a 20" diameter wheel, which was periodically stepped to advance the newly collected sources between pairs of ion-implanted Si detectors.

A parent-daughter stepping mode was used to provide unambiguous identification of the decay of $^{266,265}\text{Sg}$. In this mode, upon detection of a potential Sg α -event in a bottom detector, it is assumed that the corresponding Rf daughter atom recoils into the top detector. The source is then removed from the detector station to allow

detection of the daughter-atom α -decay in a background-free environment.

In these experiments, the gas-jet efficiency was found to be 70% by measuring the detection rates of $^{254,256}\text{Fm}$ (binary transfer products) and $^{213,214}\text{Ra}$ (compound nucleus products from a Pb impurity in the target). In addition, the efficiency for collecting α -daughter recoils in the top detector upon detection of an α -particle in the bottom was found to be $\sim 70\%$ by monitoring the $^{211,212}\text{Ra} \rightarrow ^{207,208}\text{Rn}$ decay chains.

At the 116-MeV bombarding energy (where ^{266}Sg was observed in the Dubna experiments), we observed no correlated α -fission pairs, indicating an upper limit for the ^{266}Sg of 25 pb (95% confidence limit). This is below the lower limit reported in the Dubna experiment.

At the 121-MeV bombarding energy (where ^{266}Sg and ^{265}Sg were observed in the Dubna experiments), We performed two experiments. In the first, we observed one decay chain from ^{266}Sg , and background problems prevented positive assignment of four candidate events to the decay of ^{265}Sg . In the second experiment, two decay chains were observed which are unambiguously assigned to the decay of ^{265}Sg .

E_α Sg (keV)	τ Sg (sec)	E_α Rf (keV)	τ Rf (sec)	E_α No (keV)	τ No (sec)	
8690	3.809	SF	0.875			^{266}Sg
8840	5.640	8250	28.51	8280	37.68	^{265}Sg
8860	25.80	8185	56.5			^{265}Sg

From these results, we conclude that ^{265}Sg and ^{266}Sg are formed in 121-MeV $^{22}\text{Ne} + ^{248}\text{Cm}$ bombardments with cross sections of ~ 200 pb and ~ 100 pb, respectively.

Footnotes and References

1. R. Smolanczuk, et al., Phys. Rev. C **52**, 1871 (1995).
2. Yu. A. Lazarev, et al., Phys. Rev. Lett. **73**, 624 (1994).

A Search for ^{264}Sg

C. A. McGrath, K. E. Gregorich, D. M. Lee, M. R. Lane, E. R. Sylwester, D. A. Shaughnessy, M. B. Hendricks, D. A. Strellis, P. A. Wilk, D. C. Hoffman

A search was undertaken at the 88-Inch Cyclotron at the Lawrence Berkeley National Laboratory for the new isotope ^{264}Sg . This nucleus is predicted to decay with nearly equal probability by spontaneous fission (SF) and by alpha emission with $E_\alpha \approx 9$ MeV and with a half life between 0.5 and 2 seconds¹⁻². The ^{260}Rf daughter of this alpha decay undergoes SF with a reported half life of 20 ms. We tried to produce ^{264}Sg via the $^{250}\text{Cf}(^{18}\text{O},4n)^{264}\text{Sg}$ reaction at 111 MeV and to correlate parent and daughter decays using our MG rotating wheel system.

Due to high background activities produced from binary transfer reactions, fairly stringent requirements were needed for an event. An acceptable event was defined as a parent alpha decay of between 8.5 and 9.2 MeV detected in the bottom detector (which would cause the daughter to recoil from the source into the top detector) followed within 40 ms by detection of a SF single event in the top detector (indicating fission from an atom on the top detector surface). Unfortunately, only 4 of these α -SF correlations were detected, while our calculations predict 2 or 3 random correlations of unrelated background activity. This result permits us to set an upper limit on the cross section for this reaction. If the α -decay branch is $\geq 25\%$ and the half life is between 0.5 and 2 seconds, the cross section is ≤ 200 pb at 111 MeV. Figure 1 shows a plot of cross section versus half life, when a 25% α -decay branch is assumed. The expected cross section for this reaction is 200 pb.

In addition to looking for α -SF correlations, we also searched for α - α and α - α - α correlations. These would result from an alpha decay branch in a possible longer-lived isomer of ^{260}Rf . However, we saw no evidence for these correlations.

These negative results have forced us to consider other production methods.

References

1. Smolańczuk, R., Skalski, J., Sobiczewski, A., Phys. Rev. C **52**, 1871 (1995).
2. Möller, P., Nix, J. R., Myers, W. D., Swiatecki, Atomic Data Nucl. Data Tables **59**, 185-381 (1995)




Fig. 1. Cross section upper limit plotted versus assumed ^{264}Sg half life for the $^{250}\text{Cf}(^{18}\text{O},4n)^{264}\text{Sg}$ reaction at 111 MeV. An α -decay branch of 25% was assumed.

Electronics for On-Line Liquid Scintillation α -Particle Spectroscopy

K.E.Gregorich

Recent developments in liquid scintillation counting now make α -particle pulse-height spectroscopy possible with energy resolution as good as 200 KeV FWHM^{1,2}. Since the light output per MeV of decay energy is much greater for β^- particles than for α -particles, it is necessary to use pulse shape discrimination, based on the different fractions of slow- and fast-decaying components of the α - and β -light pulses, to produce a clean α -energy spectrum.

In recent experiments we used this technique to study the chemical properties of transactinide elements. The α/β pulse-shape discrimination was implemented with a standard constant fraction discriminator on the fast (7-ns risetime) pulse from the photomultiplier tube (PMT) to start a time-to amplitude converter (TAC). This PMT signal was then shaped to undershoot by 10% to 20% of the full pulse amplitude. A zero-cross-discriminator was then used to stop the TAC, providing discrimination between α - and β -pulses. Using this pulse shape discrimination technique, we found the β -decay of large amounts (>1 kHz) of background activities caused pileup pulses which passed the pulse shape discrimination circuit.




Fig. 1. Shaped pulses for the standard α/β pulse shape discrimination. The solid line is the shape for an α -pulse. The short dashed line is for a β pulse. The long dashes indicate a β - β pileup with the same zero cross time as the α .

In subsequent experiments an additional pulse shape discrimination technique³ was used on the shaped pulse mentioned above, which acted as a fast pileup rejector. This pileup rejector was simply a CFD run with a fraction of 1.0 and a constant fraction delay equal to the full risetime of the shaped pulse (15ns), making it sensitive to the width of the pulse. The combination of this pileup rejector with the standard pulse shape discriminator allows the measurement of alpha decay rates as small as a few counts per hour in samples with beta background rates of well over 1 kHz.

Footnotes and References

1. W.J. McDowell, *Alpha Counting and Spectrometry using Liquid Scintillation Methods*, Technical Information Center, Office of Scientific and Technical Information, U.D. DOE, (1986).
2. B. Wierczinski, Doctoral Thesis, U.Mainz, (1994).
3. B. Wierczinski, et al., *Nucl. Instr. Meth. A* **370**, 532 (1995).




Fig. 2. The same pulses as in Fig.1, after passing through the $f=1$ CFD. Note that the zero-cross time of the β - β pileup (long dashes) pulse is well separated from that for the alpha pulse (solid line).

Improved Half-life Measurement of ^{224}Pa and its $^{209}\text{Bi}(^{18}\text{O},3n)^{224}\text{Pa}$ Production Cross Section

Philip A. Wilk, Ken E. Gregorich, Melissa B. Hendricks, Mike R. Lane, Diana M. Lee, Chris A. McGrath, Dawn A. Shaughnessy, Dan A. Strellis, Eric R. Sylwester, and Darleane C. Hoffman

Two half-lives for ^{224}Pa have been reported previously. However, the error bars of these two measurements, 600 ± 50 ms measured for ^{224}Pa from the $^{232}\text{Th}(p,9n)^{224}\text{Pa}$ reaction¹ and 950 ± 150 ms measured for ^{224}Pa from the $^{205}\text{Tl}(^{22}\text{Ne},3n)^{224}\text{Pa}$ reaction², do not overlap. The former measurement's low value could be due to misinterpretation of the very complex alpha spectrum that was obtained. The disparity could lie in the misidentification of a ^{223}Th ($t_{1/2}=650$ ms, $a=7.324$ MeV) decay peak produced by the $^{232}\text{Th}(p,p9n)^{224}\text{Pa}$ reaction.

In our experiment ^{224}Pa was produced via the $^{209}\text{Bi}(^{18}\text{O},3n)^{224}\text{Pa}$ reaction which has been previously reported³, but no production cross section or additional half-life measurement was given. The Lawrence Berkeley National Laboratory 88-Inch Cyclotron provided a 20 particle-nA beam of 111 MeV (laboratory frame) $^{18}\text{O}^{5+}$. The target system has been described in detail previously⁴. The energy calibration was performed on-line using known alpha decay energies from the following nuclides: ^{211}Bi , ^{214}Ra , ^{211}Po , ^{212}Ac , ^{216}Fr ,

The odd-odd nucleus ^{224}Pa is not expected to have a significant beta-decay branch and appears to alpha decay mainly to a single nuclear level in ^{220}Ac with an alpha particle energy of 7.49 MeV⁵. Unfortunately, while alpha particles with this energy are identifiable in our alpha-energy spectrum, they are largely obscured by the ^{211}Po transfer product which decays via a 7.45 MeV alpha. Therefore the ^{224}Pa decay was identified by observing its alpha-decay daughters ^{220}Ac ($t_{1/2}=26$ ms; $\alpha=7.610, 7.680, 7.790, 7.850$ MeV)⁵ and ^{216}Fr ($t_{1/2}=0.7$ ms; $\alpha=9.01$ MeV)⁵. The ^{224}Pa daughter events were observed with 6 pairs of opposing detectors⁶ within 2 μs of each other. By fitting the resultant decay curve with two components, the half-life of ^{224}Pa was determined to be 850 ± 20 ms

(see Fig. 1). From these data, we also determined the production cross section to be 0.5 ± 0.1 mb, after taking into account the detector efficiency, capillary transport efficiency, and capillary transport time.

The half-life for ^{224}Pa as determined by this experiment is consistent with, but much more precise than the value of 950 ± 150 ms reported by Borggreen *et al.*². Our measured production cross-section is consistent with the value of 0.35 mb calculated with the SPIT code⁷.

Footnotes and References

1. P. A. Tove, Arkiv Fysik. **13**, 549 (1958).
2. J. Borggreen, K. Valli, E. K. Hyde. Phys. Rev. C **2**, 1841 (1970).
3. M. Fukuda *et al.*, RIKEN Accel. Prog. Rep. **20**, 14 (1986).
4. D. Lee *et al.*, Phys. Rev. C **25**, 286 (1982).
5. R. B. Firestone, Table of Isotopes, 8th ed. (Wiley-Interscience, New York, 1996).
6. D. C. Hoffman *et al.*, Phys. Rev. C **41**, 631 (1990).
7. T. Sikkeland, Ark. Fys. **36**, 539 (1967); J. Alonso, Gmelin Handbook of Inorg. Chem., **7b**, 28 (1974).




Fig. 1. Decay of ^{224}Pa

Off-line Generation of ^{233}Pa and the ^{227}Pa Yield Through SISAK

Philip A. Wilk and Darleane C. Hoffman

During the experiment described in the previous article we were able to determine the production cross section for ^{224}Pa by bombarding a ^{209}Bi target with ^{18}O at 88 MeV and looking for subsequent fusion product alpha decays with our MG system¹. This is the same reaction and energy that was used to produce Pa for the SISAK extraction. SISAK is an automated system for doing ultra-fast chemical extractions. By looking at time-correlated alpha decays from the ^{224}Pa daughters ^{220}Ac and ^{216}Fr , the cross section was determined to be 0.5 ± 0.1 mb. Also during this experiment, a more precise half-life - 850 ± 20 ms - was determined than was previously available. Based on this cross section, the chemical yield of Pa through SISAK 3 was very low. Taking into account the reported cross section² of ^{261}Ha , the amount of this element that we should have seen would have been vanishingly small.

Calculating from the cross-section for ^{224}Pa , we should have seen about 26,000 atoms of ^{224}Pa if we had 100% chemical yield. Assuming every alpha higher in energy than ^{224}Pa that correlated with ^{224}Pa within 26 ms to be evidence for its alpha decay, resulted in 650 ^{224}Pa atoms through the SISAK system during the 40 minute experiment. This gives a yield through SISAK of only about 2.5%.

The lost Pa could be accounted for by sorption on SISAK/LISSY surfaces. To look at its sorption behavior, ^{233}Pa was generated off-line (see Fig. 1) from the decay of ^{237}Np by elution of 27 day ^{233}Pa from an anion-exchange column. The ^{233}Pa was eluted from the column with 12M HCl/0.1M HF. This Pa was then applied to samples of the materials used in the SISAK experiment to determine if Pa would strongly sorb on components of the experimental apparatus. 10 to 50 μL aliquots of this solution were evaporated directly on a glass slide, Teflon square, and Ti foil, respectively (the surface area covered was about 1 cm^2). These were then dried under a

warm heat lamp - so as not to boil the solution - and washed five times with 50 μL of 1M α -HIB. After the samples were allowed to dry, the samples and the 250 μL of wash solution were counted for γ activity with an HPGe spectrometer. Pa was found to sorb very strongly to Ti, and to a lesser extent on Teflon and glass. The following results should be considered only preliminary because each material was tested only once. Similar experiments should be conducted for the organic solution for complete characterization.

Material	% Pa per cm^2
Teflon	1 ± 1
Glass	4 ± 1
Ti	18 ± 2

It seems likely that the group 5 elements Pa and Ha (element 105) sorb so strongly on Ti that we were unable to observe them.

Footnotes and References

1. D. C. Hoffman *et al.*, Phys. Rev. C 41, 631 (1990).
2. A. Ghiorso, M. Nurmiä, K. Eskola, P. Eskola, Phys. Rev. C 4, 1850 (1971).




Fig. 1. ^{233}Pa Generator

Production of ^{211}Bi from the Reaction of ^{209}Bi with ^{22}Ne Projectiles

Y. H. Chung,* K. E. Gregorich, D. M. Lee, and D. C. Hoffman

Production of 2.14-min ^{211}Bi was investigated by bombarding $2.5\text{mg}/\text{cm}^2$ ^{209}Bi target with 140-MeV ^{22}Ne ions, whose average energies at the target were ~ 108 MeV with correction of energy losses in the Be windows, N_2 cooling gas, and the target itself, at the Lawrence Berkeley National Laboratory 88-Inch Cyclotron. The experiments were performed using the helium-jet system to transport the activity via a capillary from the production site to the MG rotating wheel¹ for measurement of alpha activity. Eskola *et al.*² studied multi-particle transfer reactions using the $^{208}\text{Pb}(^{18}\text{O},\text{pxn})^{211-213}\text{Bi}$ reactions in the 5-10 MeV/nucleon range. In their study the production cross section of ^{211}Bi via p2n-transfers was ~ 2 mb in the vicinity of 110 MeV, which induced ~ 55 MeV excitation energy in the compound system. In our study, we deduced the cross section of ^{211}Bi using its two alpha-decay lines: 6.28 and 6.62 MeV. Based on their decay intensities, the excess intensity of the 6.62 MeV line was obtained, and it was found to be due to the 6.65 and 6.66 MeV lines from 2.1-min ^{223}Ac . The excitation energy of the compound nucleus is about 36 MeV, which is lower by 20 MeV than that estimated in Eskola's work. From our data, the preliminary cross section of ^{211}Bi via the 2n-transfer reaction has been estimated to be $\sim 3 \pm 1$ mb, assuming 70% gas transport efficiency. This result indicates that the 2n transfer cross section is comparable to the p2n transfer, which was observed in the interaction of ^{208}Pb with ^{18}O in this energy regime. Further detailed analysis of data obtained from the interaction of ^{209}Bi with 103- and 117-MeV ^{22}N ions and 128-, 140-, and 149-MeV ^{26}Mg ions is in progress.

2. K. Eskola, P. Eskola, M. M. Fowler, H. Ohm, E. N. Treher, J. B. Wilhelmy, D. Lee and G.T. Seaborg, Phys. Rev. C29, 2160(1984).

Footnotes and References

*Department of Chemistry, Hallym University, Chunchon, Korea 200-702.

1. D. C. Hoffman *et al.*, Phys. Rev. C41, 631(1990).

Production Cross Sections for ^{254}Fm and ^{256}Fm in $^{248}\text{Cm} + ^{22}\text{Ne}$ Reactions

M.B. Hendricks, R.J. Wallsgrove, K.E. Gregorich, M.R. Lane, D.M. Lee, D.A. Shaughnessy, D.A. Strellis, E.R. Sylwester, P.A. Wilk, D.C. Hoffman

The cross sections for ^{254}Fm and ^{256}Fm produced in the interactions of ^{22}Ne ions with ^{248}Cm were measured. Excitation functions provide information about the reaction mechanism of transfer reactions involving actinides. By studying these reactions, we can design better experiments for production of exotic isotopes, particularly neutron-excess actinides. More immediately, if the production cross sections are known, ^{254}Fm and ^{256}Fm can be used to measure the efficiency of transporting reaction products to the detectors during compound nucleus experiments to produce Sg isotopes in the $^{248}\text{Cm} + ^{22}\text{Ne}$ reaction.

^{254}Fm and ^{256}Fm were chosen for this experiment for three reasons. The $^{22}\text{Ne} + ^{248}\text{Cm}$ reaction produces sufficient quantities of both isotopes. Detection of these nuclides is relatively easy as ^{256}Fm decays predominantly by spontaneous fission and ^{254}Fm emits a relatively high energy alpha particle that can be distinguished from the background activity. In addition, these Fm isotopes have half-lives that are suitable for this experiment.

Experiments were performed at two different cyclotron energies. With a lab energy of 139 MeV out of the cyclotron, the energy range of the Ne ions in the 1.26 mg/cm² target was 114.4-118 MeV. This energy range includes the Coulomb barrier, which is close to 116 MeV. The experiment was performed with a second target of 0.96 mg/cm². The projectile energy out of the cyclotron used with this target was 151 MeV in the lab frame. This is degraded to 119-121.5 MeV inside the target.

During each experiment, a gold foil was placed behind the Cm target to catch recoiling reaction products. The foil was then dissolved in aqua regia and the lanthanides and actinides were separated from the gold with an ion-exchange column. The eluate was dried on a platinum disk to produce a source for alpha and SF

spectroscopy. These sources were monitored at various intervals with surface barrier detectors to discover isotopes that decay by alpha emission or by spontaneous fission.

Cross sections for production of the two isotopes were determined in each experiment. At the energy near the Coulomb barrier, the cross section for production of ^{256}Fm (σ_{256}) was found to be $0.27 \pm 0.11\mu\text{b}$ and the cross section for production of ^{254}Fm (σ_{254}) was measured as $5.3 \pm 1.1\mu\text{b}$. The ^{254}Fm value does not agree within 1σ error limits with that obtained by Lee et al. at the same energy.¹ In that study, σ_{256} was measured as $0.15 \pm 0.04\mu\text{b}$ and σ_{254} was quoted as $3.1 \pm 0.4\mu\text{b}$. In two experiments at the higher energy, the production cross sections increased. σ_{256} was measured as $0.57 \pm 0.11\mu\text{b}$ and $0.48 \pm 0.08\mu\text{b}$. σ_{254} was found to be $9.7 \pm 1.4\mu\text{b}$ and $7.8 \pm 1.1\mu\text{b}$. These results indicate that further studies of this system should be undertaken. In particular, excitation functions over a wider energy range for these Fm isotopes should be produced.

Footnotes and References

1. D. Lee et al., Phys. Rev. C, 25 286 (1982).

Production of Neutron Deficient Plutonium Isotopes

M.B.Hendricks, K.E. Gregorich, M.R. Lane, D.M. Lee, D.A. Shaughnessy, D.A. Strellis, E.R. Sylwester,
P.A. Wilk, D.C. Hoffman

Production of three highly neutron-deficient isotopes of plutonium, ^{229}Pu , ^{230}Pu and unknown ^{231}Pu , was attempted with the highly asymmetric reaction $^{233}\text{U}({}^3\text{He},5-7n)$. An attempt was made to measure half-lives, alpha-decay energies and alpha/electron capture branching ratios for the three isotopes. Until Andreyev et al. identified ^{228}Pu , ^{229}Pu and ^{230}Pu , the lightest plutonium isotope known was ^{232}Pu .^{1,2} In these experiments, ^{229}Pu and ^{230}Pu were produced in a $^{208}\text{Pb}({}^{26}\text{Mg},4-5n)$ reaction. Production of ^{228}Pu was achieved by a similar reaction: $^{208}\text{Pb}({}^{24}\text{Mg},4n)$. Andreyev et al. were able to measure alpha-decay energies of these new isotopes, but could not measure half-lives or branching ratios.

The $^{233}\text{U}({}^3\text{He},5-7n)$ experiment was performed to study both decay properties and reaction mechanisms. Knowledge of decay characteristics of highly neutron-deficient plutonium isotopes is valuable to the study of electron capture delayed fission (ECDF) of light americium isotopes, since these plutonium isotopes are members of the americium decay chains. Determination of plutonium masses and decay Q-values aids estimation of electron-capture Q-values for potential ECDF precursors, like ^{230}Am . By studying the reaction mechanism involved in different systems, investigators can design better experiments. The two main criteria in designing an experiment to study exotic nuclei are high production rate of the nuclide under investigation and low production rate of interfering background activity. Comparisons between the lead target heavy-ion beam system used by Andreyev et al. and the actinide target light-ion beam system used in this experiment will aid in designing future experiments involving neutron-deficient actinides.

Eleven ^{233}U targets were mounted in the light-ion multiple target system.³ The reaction products were transported via a helium jet system from the reaction chamber and deposited

on polypropylene foils in our MG rotating wheel system. It can be rotated to place the foils successively between six pairs of surface barrier detectors. Identification of a plutonium isotope relies on observation of the alpha decay of members of its decay chain. Measurements were attempted at three cyclotron energies: 40, 50 and 60 MeV in the laboratory frame. The helium ions lose less than 1 MeV in interactions with the cyclotron window and the target system itself. The ^{231}Pu , ^{230}Pu and ^{229}Pu cross sections were predicted to peak at these energies, respectively.

Many alpha-decay chains were observed. However, large amounts of interfering activity were produced. This activity may have been due to $({}^3\text{He},pxn)$ and $({}^3\text{He},\alpha xn)$ reactions that directly yield neptunium and uranium isotopes. These high background levels and relatively long half-lives of the plutonium, neptunium, and uranium isotopes at the beginning of the decay chains made determination of half-lives and branching ratios of the light plutonium isotopes impossible. These problems will be avoided in the future by chemically separating plutonium, neptunium and uranium reaction products from each other before attempting detection of alpha-decay.

Footnotes and References

1. A.N. Andreyev et al., *Z. Phys. A*, **337**, 231 (1990).
2. A.N. Andreyev et al., *Z. Phys. A*, **347**, 225 (1994).
3. H.L. Hall, M.J. Nurmi and D.C. Hoffman, *Nucl. Instrum. Meth.*, **A276**, 649 (1989).

Electron-Capture Delayed Fission of ^{242}Es

D.A. Shaughnessy, K.E. Gregorich, M.B. Hendricks, M.R. Lane, D.M. Lee, D.A. Strellis, E.R. Sylwester,
P.A. Wilk, D.C. Hoffman

We previously reported evidence that ^{242}Es undergoes electron-capture delayed fission (ECDF).¹ We have performed additional experiments in order to determine the decay properties of ^{242}Es and its probability of delayed fission (P_{DF}).

The ^{242}Es was produced at the LBNL 88-Inch Cyclotron via the $^{233}\text{U}(^{14}\text{N}, 5n)^{242}\text{Es}$ reaction. To prepare the target ^{233}U was placed on an anion exchange column and washed several times with concentrated HCl to remove lead impurities. The target material was eluted from the column with dilute HCl and electroplated on Be foil. Reaction products from the cyclotron were transported via a He/KCl aerosol gas-jet through a capillary to our MG rotating wheel detection system. The aerosols were deposited consecutively on 80 thin polypropylene foils located on the periphery of the wheel which was moved every 10 seconds between six pairs of Si(Au) surface barrier detectors.

^{242}Es is reported to decay with a 7.9 MeV alpha particle and a half-life of 16_{-4}^{+0} seconds.² We looked for alpha particles coming from ^{242}Es , as well as its EC daughter, ^{242}Cf . The ^{242}Es branching ratio and initial EC activity could be determined by comparing the production of ^{242}Cf to that of ^{242}Es . Once the initial EC activity is measured, the P_{DF} is calculated by comparing the number of fission events to the total number of EC decays.

Even though most of the lead was removed from the ^{233}U target, a large amount of ^{213}Fr was made. Fr is produced when lead is bombarded with nitrogen. This huge peak in the spectra obscured the much smaller ^{242}Cf peak at 7.385 MeV making the EC branching ratio impossible to determine. This in turn prevented us from measuring the P_{DF} .

Another problem we encountered was the production of ^{243}Es at 7.895 MeV. We ran the ^{14}N at a higher energy than before (91 MeV on target) to try and suppress ^{243}Es production, but enough

was made to interfere with the ^{242}Es peak at 7.9 MeV. When this entire region was integrated, it was found to decay with a half-life of 35 seconds. This is longer than that of ^{243}Es (21 seconds) which indicates that the region was probably a combination of both ^{242}Es and ^{243}Es . Unfortunately our system could not resolve the two into separate peaks.

We saw 16 coincident fissions with a half-life of 25 ± 2 seconds. Since the fissions decay with the half-life of the EC parent, this would also be the half-life of ^{242}Es . This is slightly longer than previously reported. The fission fragments had an asymmetric mass distribution and a pre-neutron average total kinetic energy (TKE) of 199 ± 21 MeV. This is 6 to 13 MeV higher than semi-empirical fits predict for ^{242}Cf .³

Based on the fission half-life, the fission events could not have come from a different Es isotope. Also, the P_{DF} has been shown to increase sharply with increasing electron-capture Q-value (Q_{EC}).⁴ The Q_{EC} of ^{242}Es is greater than all other Es isotopes by at least 1 MeV making it the most probable delayed fission precursor. The Q_{EC} of its neighboring isotopes would correspond to a P_{DF} too small to account for 16 fissions over the whole experiment, implying that the ECDF was from ^{242}Es .

Footnotes and References

1. Nuclear Science Division Annual Report, LBL-37384 (1994.)
2. V. Ninov, private communication (1997.)
3. D.C. Hoffman and M.R. Lane, *Radiochimica Acta*, **70/71**, 135 (1995).
4. S.A. Kreek *et al.*, *Phys. Rev. C* **50**, 2288 (1994).

Electron-Capture Delayed Fission Study of ^{246}Es

D.A. Shaughnessy, K.E. Gregorich, M.B. Hendricks, M.R. Lane, D.M. Lee, C.A. McGrath, D.A. Strellis,
E.R. Sylwester, P.A. Wilk, D.C. Hoffman

We continued our study of electron-capture delayed fission (ECDF) in the neutron-deficient Es isotopes with ^{246}Es . The ^{246}Es was produced at the LBNL 88-Inch Cyclotron via the $^{249}\text{Cf}(p, 4n)^{246}\text{Es}$ reaction. According to SPIT¹, a neutron evaporation code, the production cross section would be 350 μb for 37 MeV protons. Based on this cross section, we expected to make 1×10^8 ^{246}Es per day.

The ^{249}Cf targets were prepared by first performing an extraction with bis(2-ethylhexyl)orthophosphoric acid (HDEHP) to remove Bk, and then electroplating the Cf onto Be foils. 19 targets between 6 $\mu\text{g}/\text{cm}^2$ and 20 $\mu\text{g}/\text{cm}^2$ were prepared and stacked in our light ion multiple (LIM) target system.² Reaction products were transported with a He/KCl aerosol jet via a capillary to our MG rotating wheel detection system. The aerosols were collected consecutively on 80 thin polypropylene foils located on the periphery of the wheel which was moved every two minutes between six pairs of PIPS detectors to look for ^{246}Es alpha particles as well as fissions. Some samples were removed from the foils with a buffered solution of acetic acid and sodium acetate maintained at pH 5 and extracted with 0.5 M thenoyltrifluoroacetone (TTA) in toluene. TTA complexes 3+ and higher oxidation states from aqueous solutions between pH 4 and 5.³ Es and Cf are complexed by the TTA, removing them from the KCl and any interfering activities. The TTA was dried on glass cover slips and placed in front of a solid state particle detector which was sandwiched between two x-ray detectors. This configuration allowed us to look for K x-rays, which follow EC decay, in coincidence with fission fragments. Once the initial EC activity is determined, the probability of delayed fission (P_{DF}) is calculated by comparing the number of delayed fissions to the total number of EC decays.

During the experiment we saw 25 times fewer ^{246}Es than predicted. The spectra showed multiple components in the Es region indicating that several isotopes were being produced concurrently. The last samples collected were counted for several days after the end of the experiment to look for ^{246}Cf ($t_{1/2} = 1.5$ d.) Based on the amount of ^{246}Cf , a production cross section of 13 ± 5 μb was calculated for ^{246}Es . This is much lower than the original prediction and accounts for the lower production rate. The other Es isotopes seen in the spectra were predicted to have much lower production rates than ^{246}Es . We now believe that the predicted cross sections in this region are not valid for (p, xn) reactions.

We plan to run an Es excitation function to determine optimal proton energies and cross sections for each isotope. If the cross section is large enough, the delayed fission experiment will be repeated to produce more ^{246}Es than we did with 37 MeV protons. This in turn should lead to more fission events and a determination of the P_{DF} .

Footnotes and References

1. SPIT is a version of the JORPLE code with a proximity potential in the entrance channel. The JORPLE reference is J. Alonso, *Gmelin Handbuch der Anorganischen Chemie*, 7b, 28 (1974.)
2. H. L. Hall, LBL Report LBL-27878 (1989.)
3. S. A. Kreek, LBL Report LBL-33766 (1993.)

Design of a Sample Changer/Transport System to be used for Gammasphere Studies on Electron-capture Delayed Fission

D.A. Strellis, K.E. Gregorich, Y.H. Chung, M.R. Lane, E.R. Sylwester, M.B. Hendricks, D.A. Shaughnessy, C.A. McGrath, P.A. Wilk, D.M. Lee, D.C. Hoffman

A sample changer/transport system has been designed to rapidly transport isotopes from high beam intensity irradiations in Cave 0 to the center of Gammasphere to study electron-capture delayed fission (ECDF).

In the Cave 0 target system, recoiling reaction products are captured by KCl aerosols in a flowing stream of He gas. The activity-laden aerosols are transported from the irradiation vault to the Gammasphere cave through a polyvinyl chloride capillary tube. The aerosol is then deposited on a thin polypropylene foil at one of four stations on a sample changer wheel. This wheel sits approximately four feet from the center of the Gammasphere array. After a specified collection time, the wheel is rotated 90°. A solenoid-operated piston then moves the foil from the wheel to the center of the array. After a specified counting time, the piston returns the foil to its wheel position. After the wheel rotates another 90°, the counted foil is deposited into a reservoir of used foils. After another 90° rotation, an unused foil is dropped from a reservoir of new foils to the open wheel position. This four station process is continuous and simultaneous. For example, when one foil is being counted in Gammasphere; one foil is collecting aerosol from the capillary tube, one foil is being dumped into the used reservoir, and another is being dropped into the open position on the wheel.

A motion controller program controls the stepping motor that turns the wheel and the solenoids that activate the piston and vacuum systems. These programs are written on a PC and downloaded to the motion controller before the experiment.

At the counting station, the activity-bearing polypropylene foil will be placed between two ion-implanted Si detectors at the center of Gammasphere. Fission fragments, alpha particles, K x-rays, and gamma rays will be measured while the sample sits inside the array.

Gammasphere is an ideal detection system for studying the gamma

spectroscopy associated with the ECDF process for two primary reasons. First, the small solid angle of each detector prevents summing of the ECDF gamma rays with those from the deexcitation of the fission fragments. Second, a high detector efficiency is desired when dealing with relatively low production rates.

The centerpiece of the Gammasphere measurements will be a search for gamma transitions within the second well of the nuclear potential. Based on results from earlier measurements of the K x-rays in coincidence with delayed fission fragments, we have found that in regions of N and Z where a fission isomer is expected, the delayed fission process is slow enough for the K-vacancies left by the electron capture of the precursor to fill. The most likely explanation for this delay is that the ECDF process is proceeding through the fission shape isomer in the EC daughter. The observation of some common gamma transitions in coincidence with various fission fragments and K x-rays would be indicative of transitions within the second well.

The first experiment to utilize this sample changer/transport system will take place in Spring 1997 with the ECDF study^{1,2} of ²³²Am and ²³⁴Am with half-lives: 1.31 ± 0.04 and 2.32 ± 0.08 minutes, respectively. The speed at which the sample changer/transport system moves the sample from the target area to Gammasphere could be as low as 10 seconds - a benefit in studying isotopes with short half-lives.

Footnotes and References

1. H.L. Hall, *et.al.*, Phys. Rev. C 41, 618 (1990).
2. H.L. Hall and D.C. Hoffman, Annual Rev. Nucl. Part. Sci. 42, 147 (1992).

Confirmation of the Assignment of a 1.5-Second Fission Activity to ^{259}Fm

C. A. McGrath, K. E. Gregorich, D. M. Lee, M. R. Lane, E. R. Sylwester, D. A. Shaughnessy, M. B. Hendricks, D. A. Strellis, B. Wierczinski, D. C. Hoffman

In 1995, two separate experiments were performed at the 88-Inch Cyclotron at Lawrence Berkeley National Laboratory to study the nuclear properties of ^{266}Sg using the reaction $^{248}\text{Cm}(^{22}\text{Ne},\text{n})^{266}\text{Sg}$ at 118 MeV and 121 MeV. The results of these experiments will be discussed in a separate submission to this annual report. However, the use of this particular reaction provides an important opportunity to study the production of ^{258}Fm and ^{259}Fm in binary transfer reactions.

The assignment of a 1.5-second spontaneous fission(SF) decay to ^{259}Fm results from the tritium bombardment of a ^{257}Fm target¹. Since ^{258}Fm was already known to decay by SF with a half life of 0.37 ms, the observed 1.5-second fission activity was assigned to ^{259}Fm , produced by the $^{257}\text{Fm}(\text{t,p})^{259}\text{Fm}$ reaction.

However, the possible discovery² of a SF isomer in ^{262}Rf suggests that the 1.5 second fission activity could be from an isomer of ^{258}Fm . Because the target material is very scarce and finding a tritium accelerator is next to impossible, it would be difficult to repeat the original measurement. Even then it might still be difficult to differentiate between the (t,p) and (t,d) reactions.

Therefore, a different reaction was chosen to try to confirm the assignment of the 1.5-second fission activity. This reaction must selectively produce either ^{258}Fm or ^{259}Fm . Bombarding ^{248}Cm with ^{22}Ne provides just such a reaction.

Several different isotopes of fermium are produced via transfer reactions in the bombardment of ^{248}Cm with ^{22}Ne . The excitation energy (E^*) of the target-like fragments help indicate the relative yields from the binary transfer reaction³. If the E^* is very negative that isotope will be formed with lower yield. A positive E^* below the threshold for neutron emission and fission is ideal for

production of a particular nuclide. The following table shows the E^* values for the production of several fermium isotopes.

Table 1: E^* for $^{248}\text{Cm}(^{22}\text{Ne},\text{A}\text{Be})^{270-\text{A}}\text{Fm}$

Isotope	E^* (MeV) [#]
^{257}Fm	5.7
^{258}Fm	6.5
^{259}Fm	-7.8
^{260}Fm	-15.0

This table shows that conditions are optimal for the production of ^{258}Fm , but not for ^{259}Fm . This is, however, a blessing. While ^{258}Fm should be produced in measurable quantities, production of ^{259}Fm should be very limited. Therefore, the presence or absence of a 1.5-second fission activity should indicate its origin.

After analyzing all the available data, no evidence is seen for a 1.5-second SF activity. An upper limit on the cross section for production of a 1.5-second activity was found to be 150 pb. Comparison of this reaction with similar transfer reactions would indicate a cross section of approximately 10 nb for the production of ^{258}Fm . A longer-lived isomer would be expected to receive some significant portion of this cross section. Thus, it is likely that the 1.5-second SF activity arises from ^{259}Fm and not from ^{258}Fm .

Footnotes and References

E^* values calculated at the coulomb barrier

- Hoffman, D. C., et al, "Discovery of ^{259}Fm ," Proc. 3rd Intl. Conf. on Nuclei Far from Stability, Cargese, Corsica, France, 19-26 May, 1976, Geneva, CERN 75-113, 15 July 1976, p. 558.
- Lane, M. R. et al, Phys. Rev. C. 53, 2893 (1996).
- Hoffman, D. C. and Hoffman, M. M. "Calculated Excitation Energies for Transcurium Products of Binary Heavy Ion Reactions;" LA-UR-82-824 (1982).

Spontaneous fission properties of ^{262}Rf

M.R. Lane, K.E. Gregorich, D.M. Lee, M.F. Mohar, M. Hsu, C.D. Kacher, B. Kadkhodayan, M.P. Neu, N.J. Stoyer, E.R. Sylwester, J.C. Yang, and D.C. Hoffman

In the time since our experiment on the spontaneous fission properties of ^{262}Rf was last reported¹, we have obtained more data and have published the results². We have measured the mass and kinetic-energy distributions of 200 pairs of coincident fission fragments from the spontaneous fission (SF) of ^{262}Rf . The ^{262}Rf was produced via the $^{244}\text{Pu} (^{22}\text{Ne}, 4n)$ reaction with a production cross section of ~ 0.7 nb using 114.4-MeV projectiles. The kinetic energies and times of the coincident fission fragments were measured using our rotating wheel system. From these data the half-life, mass, and kinetic-energy distributions were derived. The total kinetic-energy (TKE) distribution (Fig. 1) appears to consist of a single component with a most probable pre-neutron-emission TKE of 215 ± 2 MeV. The mass distribution (Fig. 2) is symmetric with a full width at half maximum of about 22 mass numbers. These results are consistent with trends observed for other trans-berkelium spontaneously fissioning isotopes. We determined the half-life to be 2.1 ± 0.2 s by measuring its spontaneous fission decay. We also attempted to observe the alpha decay of ^{262}Rf by searching for alpha decay correlated in time with SF from the alpha daughter, 1.2-ms ^{258}No . We observed no such decays and have set an upper limit of 0.8% (68% confidence level) on the alpha decay branch of ^{262}Rf .

References

1. D.C. Hoffman et al.; K.E. Gregorich et al., LBL-35768, Annual Report (1993).
2. M.R. Lane et al, Phys. Rev. C **53**, 2893 (1996).




Fig. 1. Gaussian fit to the pre-neutron-emission TKE distribution from the SF of ^{262}Rf .




Fig. 2. Lorentzian fit to the pre-neutron-emission mass-yield distribution for ^{262}Rf . Also shown is the provisional mass-yield curve to which no neutron correction was applied. The bars indicate 1σ error limits.

Spontaneous fission reviews

D.C. Hoffman, T.M. Hamilton,[†] M.R. Lane

Two spontaneous fission review articles have been published. Each presents the known data for spontaneous fission properties. The systematics are discussed and compared to theoretical models.

I. Spontaneous Fission¹ by Darleane Hoffman, Todd Hamilton and Michael Lane. Since the comprehensive Hoffman and Somerville review² of experimentally determined spontaneous fission properties published in 1989 (literature to mid-1986 considered), major conferences have been held at Berlin and Washington, D.C. in 1989 to commemorate the 50th anniversary of the discovery of nuclear fission. Many review papers and much new information concerning spontaneous fission were presented. The intent of the present review is to update the information of Hoffman and Somerville on spontaneous fission half-lives, fission fragment kinetic energy, mass and charge distributions, neutron and photon emission at scission or from the excited fragments and new theoretical developments. New experimental results on SF phenomena are reviewed. The relevant published literature to mid-1992 has been considered.

II. Spontaneous Fission³ by Darleane Hoffman and Michael Lane. Recent experimental results for spontaneous fission half-lives, total kinetic energies, fragment mass and kinetic-energy distributions, and other properties of the fragments are reviewed and compared with recent theoretical models. The experimental data lend support to the existence of the predicted deformed shells near $Z=108$ and $N=162$. Prospects for extending detailed studies of spontaneous fission properties to elements beyond hahnium (element 105) are discussed. The relevant published literature to mid-1995 has been considered. This article updates the

information from the last published review by Hoffman, Hamilton, and Lane¹ (see above).

Footnotes and References

[†] Present address: IUCF, Bloomington, IN

1. D.C. Hoffman et al.: Spontaneous Fission, in *Nuclear Decay Modes*, D.N. Poenaru, Ed., IOP Publishing, Bristol UK, chap. 10 (1996).
2. D.C. Hoffman and L.P. Somerville: Spontaneous Fission, in *Charged Particle Emission from Nuclei, Vol. III*, D.N. Poenaru and M.S. Ivascu, Eds., CRC Press Inc., Boca Raton, Florida, chap. 1 (1989).
3. D.C. Hoffman and M.R. Lane, *Radiochim. Acta* **70/71**, 135 (1995).

Relative Deformations of Superdeformed Bands in $^{131,132}\text{Ce}$.

R.M.Clark¹, I.Y.Lee¹, P.Fallon¹, D.T.Joss², S.J.Asztalos¹, J.A.Becker³, L.Bernstein³, B.Cederwall¹, M.A.Deleplanque¹, R.M.Diamond¹, L.P.Farris³, K.Hauschild⁴, W.H.Kelly⁵, A.O.Macchiavelli¹, P.J.Nolan², N.O'Brien⁴, A.T.Semple², F.S.Stephens¹, R.Wadsworth⁴

¹ Nuclear Science Division, Lawrence Berkeley National Laboratory, Berkeley CA 94720, U.S.A.

² Oliver Lodge Laboratory, University of Liverpool, Liverpool, L69 3BX, UK

³ Lawrence Livermore National Laboratory, Livermore, California 94550

⁴ Department of Physics, University of York, Heslington, York, YO1 5DD, UK


⁵ Iowa State University, Ames, Iowa 50011, U.S.A

The quadrupole deformations of states in some SD bands have been determined through lifetime measurements and confirm their SD nature, but very little is known about the relative deformations of yrast and excited SD bands in the same, and neighbouring, nuclei. These differences should reflect the deformation-driving effects of specific configurations and the stability of the second minimum with respect to various nucleon excitations. This information is crucial in providing a stringent test of current theoretical models. With this in mind, superdeformed states in $^{131,132}\text{Ce}$ were populated via the $^{100}\text{Mo}(^{36}\text{S},\text{xn})$ reactions at a beam energy of 155 MeV. The target comprised a $\sim 600 \mu\text{g}/\text{cm}^2$ ^{100}Mo foil evaporated on a $12 \text{ mg}/\text{cm}^2$ Au backing which slows down and stops the recoiling nuclei. The beam was provided by the 88-Inch Cyclotron at the Lawrence Berkeley National Laboratory, and γ rays were detected by the Gammasphere array which, for this experiment, had 55 large-volume HpGe detectors. A total of 9×10^8 events with a fold ≥ 5 was collected. A Doppler Shift Attenuation Method (DSAM) centroid shift analysis was then performed.

Experimental fractional Doppler shift, $F(\tau)$, curves were extracted and are shown in the figure. Calculated $F(\tau)$ curves, assuming a rotational cascade with a constant quadrupole moment (6.4, 7.4, and 8.4 eb) and using the stopping powers of Ziegler et al., are shown for comparison with the data. Comparing the curves allowed a number of important conclusions to be drawn. We have extracted the relative deforma-

tions of all five known SD bands in $^{131,132}\text{Ce}$ to an accuracy of $\approx 5\text{--}7\%$. We find that the yrast bands in these two nuclei have very similar deformations implying that the shape-driving force of the $N=6$ neutron orbital is less than previously thought. The yrast and excited bands in ^{132}Ce have very similar deformations indicating that the second minimum is stable to the excitations responsible for these excited bands. The excited band in ^{131}Ce has a significantly larger deduced Q_0 than any of the other bands. Information on the effect and nature of side-feeding was also extracted and it was found that there is a significant slow side-feeding component for the yrast band in ^{131}Ce .

Further details of the work can be found in [1]



References

- [1] R. M. Clark *et al.*, Phys. Rev. Lett. **76** (1996) 3510.

Low-Spin Termination of the Superdeformed Band in ^{135}Nd

M.A. Deleplanque¹, S. Frauendorf¹, R.M. Clark¹, R.M. Diamond¹, F.S. Stephens¹, J.A. Becker²,
 M.J. Brinkman², B. Cederwall¹, P. Fallon¹, L.P. Farris², E.A. Henry², H. Hübel³,
 J.R. Hughes², W. Korten³, I.Y. Lee¹, A.O. Macchiavelli¹, M.A. Stoyer²,
 P. Willsau³, J.E. Draper⁴, C. Duyar⁴, E. Rubel⁴

¹ Nuclear Science Division, Lawrence Berkeley National Laboratory, Berkeley CA 94720, U.S.A.

² Lawrence Livermore National Laboratory, Livermore, California 94550


³ Institut für Strahlen- und Kernphysik, Universität Bonn, D-53115 Bonn, Germany

⁴ University of California, Davis, CA 95616

In an effort to understand the decay out of superdeformed (SD) bands, the nucleus ^{135}Nd was studied with the early implementation of Gammasphere at the 88-Inch Cyclotron of the Lawrence Berkeley National Laboratory. In two separate experiments, the reaction ^{40}Ar on ^{100}Mo at 182 and 176 MeV produced 1.0×10^9 and 1.8×10^9 three and higher fold suppressed events, respectively. Both angular correlations and triple γ coincidences were used to construct the level scheme of Fig. 1. A total of 75% of the decay of the SD band (and 84% of the decay of the 3.324 MeV state) has been placed in the level scheme. These results determine the spins of the SD states. Also the proposed positive signature is consistent with the $i_{13/2}$ neutron configuration previously assigned. The intensity of the linking transitions, together with previous RDM lifetime measurements [1] indicate that the observed E2 linking transitions have a reduced transition probability that is a factor about 10 lower than that of a SD band transition. Therefore, we propose that the band ceases to exist below the 3.324 MeV energy level.

Ultimate Crank calculations with pairing, in which the $i_{13/2}$ configuration could be followed, were used to try to understand this behavior. The results show that, as the frequency decreases, a lower-deformation triaxial minimum competes with the SD minimum and the nucleus "slides over" from a high-deformation to the triaxial minimum. The rapid change is a consequence of pair correlations. The pair field will scatter pairs between the neutron levels ($h_{9/2}$

$\leftrightarrow g_{7/2}$) and proton levels ($h_{11/2} \leftrightarrow g_{7/2}$) distinguishing the two minima. The example of ^{135}Nd clearly demonstrates the importance of underlying structural changes in the decay of highly deformed configurations [2]. Such configurations could play the role of doorway states in other decays of SD bands in which a larger number of pairs is rearranged.



References

- [1] P. Willsau et al., Phys.Rev.C48, R494 (1993).
- [2] M.A. Deleplanque et al., Phys.Rev.C52, R2302 (1995).

Proton Superdeformed Bands below the Z=80 Gap in ^{191}Au : More Evidence for Pseudo-spin Coupling

C. Schück¹, E. Gueorguieva¹, A. Lopez-Martens¹, F. Hannachi¹, Ch. View¹, M. Kaci¹, J.S. Dionisio¹,
W.H. Kelly², M.A. Deleplanque³, F.S. Stephens³, B. Kharraja⁴, B.J.P. Gall⁴, A. Korichi⁵,
U.J. van Severen⁶, W. Pohler⁶, B. Schulze⁶, H. Hübel⁶, R. Wadsworth⁷,

¹ C.S.N.S.M. CNRS-IN2P3, F-91405 Orsay (France)

² Iowa State University, Ames, Iowa 50011, USA

³ Lawrence Berkeley National Laboratory, Berkeley, California 94720, USA

⁴ C.R.N. Strasbourg, F-67037 Strasbourg, France

⁵ Institut Physique Nucleaire, IN2P3-CNRS, F-9140 Orsay, France

⁶ University of Bonn, Nussallee 14-16, D-53115 Bonn, Germany

⁷ University of York, Dept of Physics, Helsington, York, YO1 5DD, U.K.

Three superdeformed bands have been observed in ^{191}Au using the EUROGAM II multidetector array. The yrast superdeformed band has been extended to very high rotational frequencies and two new excited bands have been found. These bands behave as signature partners and display characteristics which suggest they could be based on the $[532]3/2$ or $[530]1/2$ configurations, which become the $[431]3/2, 1/2$ doublet in the pseudo-spin formalism. It is important to note that band 3 has energies identical ($\langle \Delta E \gamma \rangle = 1.5$ keV) to those of band 1 in ^{192}Hg within the observed range of frequencies.

The occurrence of the same transition energies (isospectral) in an even-even and an odd-mass nucleus requires an alignment that is exactly half-integer. For several cases in the mass ~ 150 region the special proton orbital, $[301]1/2$, provides the half-integer alignment which comes about naturally [1] in a pseudospin scheme where the above orbital becomes $[200]1/2$, implying an alignment of exactly one half, i.e. of the pseudo intrinsic spin. All the normal parity orbitals are either such pseudospin-singlets ($\tilde{\Lambda} = 0$) or fall into pairs (pseudospin doublets) corresponding to a $\tilde{\Lambda} \neq 0$ with a small pseudo spin-orbit splitting. It was pointed out [2] that these pairs could also decouple the $1/2 \hbar$ pseudo intrinsic spin, providing alignments of one half, but such behavior has so far not been observed.

For the pseudo-spin doublet, $[431]1/2, 3/2$, the Coriolis mixing should first decouple the pseudo intrinsic spin and produce two signature-degenerate bands, having alignments $+1/2$ and $-1/2$. The properties of bands 2 and 3 fit well those expected for the lower degenerate band with alignment $+1/2$. The HFB routhians for quasi-protons in a ^{190}Pt core show that these two orbitals are the lowest quasi-particle excitations at low frequencies. However, both bands develop some signature splitting and the alignment of the lower one increases significantly beyond $1/2$ at the higher frequencies. These features indicate deviations of the calculation from the simple decoupling of the pseudo-intrinsic spins; whereas, the data agree well with those expectations.

It is not really clear whether the calculations underestimate the effects of the pseudospin symmetry or whether the better agreement with the simple expectations is just an accident. However, that quantized alignments may be coming from pseudospin symmetry is an exciting possibility.

References

- [1] W. Nazarewicz et al., Phys. Rev.Lett. 64 1654 (1990).
- [2] F.S. Stephens et al., Phys. Rev. Lett. 64 2623 (1990).

Confirmation of a superdeformed band in ^{192}Pb

S.J. Asztalos¹, P. Fallon¹, J.A. Becker², L.A. Bernstein², R.M. Clark¹, M.A. Deleplanque¹,
R.M. Diamond¹, L.P. Farris², E.A. Henry², W.H. Kelly[†], I.Y. Lee¹, A.O. Macchiavelli¹, and F.S. Stephens¹,

¹Lawrence Berkeley Laboratory, Berkeley, California, 94720

²Lawrence Livermore National Laboratory, Livermore, California, 94550

[†]Permanent address: Iowa State University, Ames, Ia, 50011

A number of experiments have been performed to map out the region of superdeformed shapes in and around the neutron deficient Pb isotopes. Of particular interest are the edges of such regions, where theoretical nuclear models are most rigorously tested. For this purpose, during a brief test of the electronics of the GAMMASPHERE array at the 88-Inch Cyclotron we conducted a 7 hour test run using a reaction $^{173}\text{Yb}(^{24}\text{Mg},5n)$ to populate high spin states in ^{192}Pb at a beam energy of 140 MeV. In spite of the brief duration of the experiment, subsequent analysis allowed us to confirm the original observation [1] of the SD band assigned to ^{192}Pb [2], the assignment of which had previously been under dispute[3].

The increased resolution afforded by GAMMASPHERE with its 49 Compton-suppressed detectors permitted the SD band to be seen from only three clean gates at 304, 345 and 424 keV (Fig 1a). As previously reported [1] and as is seen in Figure 1b, the entire SD band consists of nine transitions, extending over a range of approximately 300 keV. The relatively small number of transitions populating ^{192}Pb in this experiment as compared with other heavier even-even lead isotopes may reflect greater fission competition as the reduction in the fissility parameter (which scales roughly as Z^2/A) for lighter isotopes in Pb makes it more difficult to populate a superdeformed (SD) band in ^{192}Pb . The γ -ray energies are also shown in Figure 1a and agree with previous published values to within 1 keV[1]. The band has a moment of inertia similar to ^{194}Pb SD band 1. The presence of low-lying isomers prevents definitive isotopic assignment to ^{192}Pb , although this has recently been confirmed[4]. The inband relative intensities of

the SD band transitions are shown in the inset of Figure 1b. In summary, we confirm the earlier observation of the SD band assigned to ^{192}Pb . To date, no SD bands in lighter Pb isotopes have been observed.




Figure 1: Sum of coincidence spectra of the SD band in ^{192}Pb , obtained from triples data, showing: a) from clean gates at 304, 345 and 424 keV, and b) a sum of all gates on known in-band transitions. Band members, are labelled with their energies in keV. Also labelled are the prominent $5^- \rightarrow 4^+$ and $4^+ \rightarrow 2^+$ transitions at 504.3 and 501.8 keV, respectively, in ^{192}Pb .

References

- [1] E.A. Henry *et al.*, Z. Phys. A 338 (1991) 469
- [2] S.J. Asztalos *et al.*, Z. Phys. A 352 (1995) 239
- [3] A.J.M. Plompen *et al.*, Phys. Rev. C 47 (1993) 2378
- [4] L. Ducroux *et al.*, Z. Phys. A 352 (1991) 13

Octupole Vibrations and Signature Splitting in Even Mass Hg Superdeformed Bands

P.Fallon¹, F.S.Stephens¹, S.Asztalos¹, B.Busse¹, R.M.Clark¹, M.A.Deleplanque¹, R.M.Diamond¹, R.Krücken¹, I.Y.Lee¹, A.O.Macchiavelli¹, R.W.MacLeod¹, G.Schmid¹, K.Vetter¹ and T.Nakatsukasa².

¹Lawrence Berkeley National Laboratory.

²Department of Physics, UMIST, P.O. Box 88, Manchester M60 1QD, U.K.

The possibility that the lowest excited SD bands in even mass mercury isotopes (^{190,192,194}Hg) are based on octupole vibrations has been discussed previously[1, 2] in terms of the moments of inertia and decay properties. In this present work[3] we have investigated the signature splitting of excited SD bands in ¹⁹⁴Hg isotopes. The signature splitting depends on the mixing with other states, e.g. other K components of the octupole vibration. Since the $K=0$ octupole vibration contains only the $\alpha=1$ sequence, there will be an additional Coriolis mixing among $\alpha=1$ states. Odd spin ($\alpha=1$) bands which lie below the $K=0$ band will therefore be favored with respect to the corresponding even spin $\alpha=0$ band. Thus if the octupole interpretation is valid, and in the absence of other effects (band-crossings etc), one may expect the odd spin band to be favored in a signature-split pair of bands.

The signature splitting (difference in the Routhian energies) for the ¹⁹⁴Hg excited SD bands is shown in Fig. 1. The experimental data (circles) exhibits an initial splitting which is consistent with these bands being based on octupole vibrational states. At higher frequencies the $\alpha=0$ band (band 2) gains in energy relative to band 3 at the highest frequencies. In other words, after an initial ‘octupole-like’ splitting, there appears to be a trend towards ‘signature inversion’, whereby the $\alpha=0$ band is becoming favored relative to the $\alpha=1$ band. For the three calculated cases in Fig. 1 the $\alpha=1$ structure starts lower in energy but at higher frequencies the $\alpha=0$ band becomes increasingly favored due to the mixing with close lying 2-quasiparticle states, e.g.

$\pi[642]5/2 \otimes \pi[514]9/2$. The calculations are able to reproduce, in a quantitative manner, both the initial signature splitting observed in ¹⁹⁴Hg and the subsequent ‘inversion’ lending support to the presence of octupole effects in this nucleus.




Fig. 1: The difference ($e'(\alpha=0) - e'(\alpha=1)$) for both the experimental (circles) and calculated ¹⁹⁴Hg band 2 and 3 Routhians. Three curves are shown for the calculated Routhians, each with the same octupole strength, $f_3=1.05$, but with differing pairing; (i) The solid line has the critical frequency for pairing $\hbar\omega_c = 0.5(0.3)$ MeV for neutrons(protons). (ii) The dashed line has $\hbar\omega_c = 0.5(0.5)$ MeV for neutrons(protons). (iii) The dot-dashed has constant pairing strength as a function of rotational frequency.

References

- [1] B.Crowell et al., Phys. Lett. **B333**, 320 (1994) and Phys. Rev. **C51**, R1599 (1995).
- [2] T.Nakatsukasa, K.Matsuyanagi, S.Mizutori and Y.R.Shimizu, Phys. Rev. **C53**, 2213 (1996).
- [3] P.Fallon et al., submitted to Phys. Rev. C.

Relative Quadrupole Moments of $^{192,193}\text{Hg}$ Superdeformed Bands.

B.C.Busse¹, P.Fallon¹, R.Krücken¹, D.Ackermann², I.Ahmad², S.J.Asztalos¹,
D.J.Blumenthal², M.P.Carpenter², R.M.Clark¹, M.A.Deleplanque¹, R.M.Diamond¹,
S.M.Fischer², F.Hannachi⁴, R.V.F.Janssens², T.L.Khoo², A.Korichi⁵, T.Lauritsen²,
I.Y.Lee¹, C.J.Lister², A.Lopez-Martens⁴, A.O.Macchiavelli¹, R.W.MacLeod¹,
E.F.Moore³, D.Nisius², G.Schmid¹, D.Seweryniak², F.S.Stephens¹, K.Vetter¹

¹ Lawrence Berkeley Laboratory, Berkeley, California 94720

² Argonne National Laboratory, Argonne, Illinois 60439

³ North Carolina State University, Raleigh, North Carolina 27695


⁴ Centre de Spectrométrie Nucléaire, IN2P3-CNRS bat 104, F-91405, Orsay, France

⁵ Institut de Physique Nucléaire, IN2P3-CNRS bat 104, F-91406, Orsay, France

Relative quadrupole moments (Q_o 's) of yrast and excited SD bands can give insight into the deformation-driving effects of specific nucleon configurations and aid in the interpretation of "identical" bands. A pair of "identical" bands will have transition energies that are equal to, or are at the quarter points or half points of, each other. A clear understanding of this phenomenon has yet to be developed. With this in mind, SD states in $^{192,193}\text{Hg}$ were populated simultaneously via the $^{176}\text{Yb}(^{22}\text{Ne},xn)$ reaction at a beam energy of 118 MeV. The target consisted of a $500\ \mu\text{g}/\text{cm}^2$ ^{176}Yb foil evaporated on a $6.8\ \text{mg}/\text{cm}^2$ Au backing. The beam was accelerated by the 88-Inch Cyclotron at Lawrence Berkeley National Laboratory, and γ rays were detected by the Gammasphere array which, for this experiment, had 85 Ge detectors. A total of 1.9×10^9 events with a fold ≥ 5 were collected. A Doppler Shift Attenuation Method (DSAM) centroid shift analysis was then performed.

Experimental fractional Doppler shifts, $F(\tau)$, were extracted and are shown in the figure for the ^{192}Hg and ^{193}Hg SD yrast bands. Calculated $F(\tau)$ curves, that assume a rotational cascade and constant $Q_o(Q_{sf})$ for the in-band(sidefeeding) states, are shown for comparison. The stopping powers of Ziegler were used. A lineshape analysis on some transitions in the $^{192,193}\text{Hg}$ SD bands was also performed, leading to results consistent with the $F(\tau)$ analysis. Comparing the $F(\tau)$ curves allowed several im-

portant conclusions. The relative Q_o 's of the yrast SD bands of ^{192}Hg and ^{193}Hg are different to a significance $> 2\sigma$, with values of $19.8 \pm 1.2\ \text{eb}$ and $17.2 \pm .7\ \text{eb}$ respectively. The uncertainty in the sidefeeding time, obtained by χ^2 minimization, has been included in the Q_o errors. Nevertheless, radically different sidefeeding in the two SD Hg nuclei could cause the apparent Q_o difference, although this solution is less likely. Based on current theoretical work, the difference between ^{192}Hg and ^{193}Hg is unexpected. The experimental Q_o 's of all six SD bands in ^{193}Hg are the same to $\approx 1\sigma$, which seems to eliminate a large polarizing effect of the different single particle levels. This similarity in Q_o is difficult to reconcile, given the difference in the ^{192}Hg and ^{193}Hg Q_o 's. Since ^{192}Hg and ^{193}Hg have a SD "identical" band relationship, the data may imply that "identical" transition energies don't always lead to identical deformations. This is the first accurate measurement of Q_o 's in an odd-mass SD nucleus in the mass 190 region.



Test of $\Delta I = 2$ Staggering in the superdeformed bands of ^{194}Hg

R. Krücken¹, G. Hackman², M.A. Deleplanque¹, R.V.F. Janssens², D. Ackermann², S. Asztalos¹,
R.M. Clark¹, R.M. Diamond¹, P. Fallon¹, B. Herskind³, T.L. Khoo², T. Lauritsen²,
I.Y. Lee¹, A.O. Macchiavelli¹, R.W. MacLeod¹, G.J. Schmid¹, F.S. Stephens¹, and K. Vetter¹

¹ Nuclear Science Division, Lawrence Berkeley National Laboratory, Berkeley CA 94720, U.S.A.

² Argonne National Laboratory, Argonne IL 60439, U.S.A.


³ The Niels Bohr Institute, University of Copenhagen, Denmark

Recently a regular staggering pattern of the transition energies was observed in the yrast superdeformed band in ^{149}Gd [1]. Evidence for similar effects has also been reported for ^{194}Hg [2]. The theoretical investigation of these effects has so far not been conclusive. It remains unclear whether to associate the observed staggering with a Y_{44} deformation of the superdeformed shape or with numerous band-crossings, since a single band-crossing cannot explain the extension of a staggering over a larger frequency range.

Since the observed energy shifts are only of the order of 100 eV or less, experimental confirmation of the reported effects is extremely important. Here we report on results from a new experiment on the known SD bands of ^{194}Hg , looking for the previously reported [2] staggering in those bands.

Superdeformed states in ^{194}Hg were populated in the reaction $^{150}\text{Nd}(^{48}\text{Ca}, 4n)$ using a 201 MeV ^{48}Ca beam. The emitted γ -rays were detected by the GAMMASPHERE array, which at the time of the experiment consisted of 70 Compton-suppressed Ge detectors. A total of 1.4×10^9 events with fold four and higher were taken in this thin-target experiment. The transition energies in the three known SD bands of ^{194}Hg have been determined with an accuracy of around 30 eV. The resulting staggering values ΔE_γ , defined as the fourth derivative of the γ -ray energies, are presented in the figure. No statistically significant staggering was found in band 1. However, a significant staggering has been observed for band 2 in the frequency range above $\hbar\omega = 0.3 \text{ MeV}$ that includes one phase inversion. A short regular staggering with an amplitude of

50 eV has been observed in band 3 in the frequency range $0.25 \text{ MeV} < \hbar\omega < 0.375 \text{ MeV}$. The observed staggering patterns show similarities with patterns that can be induced by the crossing of weakly interacting bands. However, such a scenario cannot account in a simple manner for the observed staggering. Detailed information can be found in Ref. [3].



References

- [1] S. Flibotte *et al.*, Phys. Rev. Lett. **71**, 4299 (1993)
- [2] B. Cederwall *et al.*, Phys. Rev. Lett. **72**, 3150 (1994)
- [3] R. Krücken *et al.*, Phys. Rev. C **54**, R2109 (1996)

Discrete SD–ND linking transitions from the yrast superdeformed band in ^{194}Pb : J^π and E_x

K. Hauschild, L.A. Bernstein, J.A. Becker, D.E. Archer, R.W. Bauer: LLNL
 D.P. McNabb, J.A. Cizewski, K.-Y. Ding, W. Younes: Rutgers University.
 R. Krücken, R.M. Diamond, R.M. Clark, P. Fallon, I.-Y. Lee, A.O. Macchiavelli,
 R. MacLeod, G.J. Schmid, M.A. Deleplanque, F.S. Stephens: LBNL
 W.H. Kelly: Iowa State University

Twelve one-step linking transitions between the yrast SD band and low-lying states in ^{194}Pb have been identified, shown in Fig. 1. A further 12 high-energy transitions have also been identified to be in coincidence with the yrast SD band. Anisotropy measurements have determined that the linking decays include E1, M1 and mixed M1/E2 transitions. $J^\pi = 6^+$, $E_x = 4878.4(3)$ keV and $J^\pi = 8^+$, $E_x = 5047.8(3)$ keV were unambiguously assigned to the two lowest lying observed superdeformed states without *a priori* assumptions about the properties of SD bands. These results represent the first experimentally self-consistent J^π assignments to an SD band.

The experiment was performed at the Lawrence Berkeley Laboratory 88-Inch Cyclotron Facility using the $^{174}\text{Yb}(^{25}\text{Mg},5n)$ reaction at $E(^{25}\text{Mg}) = 130$ MeV and the GAMMASPHERE array [1]. The isotopically enriched (>98%) ^{174}Yb target was 1.21-mg/cm^2 thick,

and was evaporated directly onto a 6.13-mg/cm^2 Au backing. The signal-to-noise ratio of the SD primary γ rays is enhanced when a thick backing is used.

21(2)% of the ^{194}Pb yrast SD band intensity has been observed to decay out through the one-step linking transitions. At first glance this is a surprisingly large proportion of the SD flux when compared to the $\sim 5\%$ observed for the ^{194}Hg yrast SD band [2]. However, arguments based on level density considerations at the point of SD decay, combined with the different low-lying ND structure of ^{194}Hg and ^{194}Pb indicate a more highly fragmented decay in ^{194}Hg is to be expected.

Greater understanding of these properties is anticipated with the improved resolving power of the “complete” GAMMASPHERE and EUROBALL arrays, for example, excited bands and their decay properties. Unique determination of the J^π and E_x values of SD bands are needed to place more stringent restrictions upon theoretical calculations which predict the SD states and their properties, in particular, the excitation energy of the SD bandheads. In addition, this knowledge will help to address the phenomena of “identical” bands.




Figure 1: Triple-gated ^{194}Pb SD spectra.

References

- [1] I. Y. Lee, *Nucl. Phys. A* **520**, 641c (1990).
- [2] T. L. Khoo *et al.*, *Phys. Rev. Letts.* **76**, 1583 (1996).

The decay of the superdeformed band in ^{194}Pb : Electromagnetic Properties

R. Krücken,¹ S.J. Asztalos,¹ J.A. Becker,³ B. Busse,¹ R.M. Clark,¹ M.A. Deleplanque,¹
A. Dewald,² R.M. Diamond,¹ P. Fallon,¹ K. Hauschild,³ I.Y. Lee,¹ A.O. Macchiavelli,¹
R.W. MacLeod,¹ R. Peusquens,² G.J. Schmid,¹ F.S. Stephens,¹ K. Vetter,¹ and P. von Brentano²

¹ Nuclear Science Division, Lawrence Berkeley National Laboratory, Berkeley, CA 94720, U.S.A.

² Institut für Kernphysik, Universität zu Köln, 50937 Köln, Germany

³ Lawrence Livermore National Laboratory, Livermore, CA 94550, U.S.A.

Lifetimes of the 14^+ , 12^+ , 10^+ states and, for the first time, the 8^+ state in the yrast superdeformed (SD) band of ^{194}Pb were measured at GAMMASPHERE (95 detectors) with the recoil-distance Doppler-shift method utilizing the Cologne Plunger. The reaction $^{164}\text{Dy}(^{34}\text{S},4n)$ with a 166-MeV beam from the 88-Inch Cyclotron of the Lawrence Berkeley National Laboratory was used. 2×10^8 three-fold and higher coincidence events recorded at 12 target-to-stopper distances between 2.6 and 1200 μ . The lifetimes of the 14^+ , 12^+ , 10^+ and for the first time the 8^+ SD states were determined (see Tab.I). Constant transition quadrupole moments with an average of 18.8 (11) e b were found at the bottom of the SD band.

The decay out of the SD band can be viewed as governed by a small admixture (a_n^2) of normal deformed (ND) states to the SD wavefunction which is assessed for the 8^+ and 10^+ SD states based on a simple mixing model (see Ref.[1] and refs. therein). The results ($a_n^2 \leq 1\%$) show that the structure of the SD states is not drastically changed. Spins and parity and the excitation energy of the SD states in ^{194}Pb were recently established [2, 3] by the observation of direct linking transitions between SD and near yrast ND states. The lifetimes of the 8^+ and 10^+ SD states and their branching ratios [3] determine the reduced transition probabilities for these discrete linking transitions. By correcting for the amount of admixture between SD and ND states one can extract the electromagnetic properties of

the pure ND states that mix into the SD wavefunction. The extracted $B(E1)$ values were found to be of the order of 10^{-6} - 10^{-5} W.U. Upper limits of 3×10^{-2} W.U. for the $B(E2)$ values and 5×10^{-4} W.U. for $B(M1)$ values were determined. These values are all consistent with a statistical decay, even when the possibility of an increase by one order of magnitude is considered. They show no enhancement that would point to the presence of structural effects. Despite the large intensity of observed linking transitions, the new data show that the decay out of this SD band is statistical in nature.

Table 1: Mean lifetimes τ of SD states in the yrast SD band in ^{194}Pb . Reduced transition probabilities $B(E2)$ and transition quadrupole moments Q_t are given for the intra-band transitions.

I^π	E_γ [keV]	τ [ps]	$B(E2)$ 10^3 W.U.	Q_t [eb]
14^+	298	2.6 ± 0.7	$1.8^{+0.8}_{-0.4}$	$18.5^{+3.2}_{-2.0}$
12^+	256	5.5 ± 1.0	$1.7^{+0.3}_{-0.3}$	$18.2^{+1.9}_{-1.5}$
10^+	214	8.3 ± 1.7	$2.2^{+0.6}_{-0.4}$	$20.7^{+2.5}_{-1.8}$
8^+	170	20.0 ± 6.9	$1.5^{+0.7}_{-0.4}$	$17.3^{+4.0}_{-2.4}$

References

- [1] R. Krücken *et al.*, Phys. Rev. C **54**, 1182 (1996)
- [2] A. Lopez-Martens *et al.*, Phys. Lett. **B380**, 18 (1996)
- [3] K. Hauschild *et al.*, to be published

Evidence for ‘Magnetic Rotation’: Lifetimes of States in the M1-bands of $^{198,199}\text{Pb}$

R.M.Clark¹, S.J.Asztalos¹, G.Baldsiefen², J.A.Becker³, L.Bernstein³, M.A.Deleplanque¹,
 R.M.Diamond¹, P.Fallon¹, I.M.Hibbert⁴, H.Hübel², R.Krücker¹, I.Y.Lee¹,
 A.O.Macchiavelli¹, R.W.MacLeod¹, G.Schmid¹, F.S.Stephens¹, R.Wadsworth⁴

¹ Nuclear Science Division, Lawrence Berkeley National Laboratory, Berkeley CA 94720, U.S.A.

² Institut für Strahlen- und Kernphysik, Universität Bonn, D-53115 Bonn, Germany

³ Lawrence Livermore National Laboratory, Livermore, California 94550

⁴ Department of Physics, University of York, Heslington, York, YO1 5DD, UK

The observation of long cascades of magnetic dipole transitions in the neutron deficient Pb nuclei has posed a serious challenge to conventional collective models. They are thought to be based on high-K proton configurations coupled to neutron configurations involving low-K $i_{13/2}$ holes. The properties of the bands are extremely unusual: 1) the structures follow the rotational $I(I+1)$ rule over many states despite very low deformations; 2) the levels show no signature splitting; 3) the levels are linked by strong M1 transitions with a typical $B(M1)$ of the order of several Weisskopf units; 4) the $B(M1)/B(E2)$ ratios are very large (typically $\geq 20-40 \mu_N^2/e^2b^2$); 5) the ratio $\mathfrak{S}^{(2)}/B(E2)$ is roughly ten times larger than that for well deformed nuclei. It has been suggested that the bands represent a novel mode of nuclear excitation, namely ‘magnetic rotation’ which arises as a consequence of breaking the intrinsic rotational symmetry by a large magnetic dipole (as opposed to the more familiar ‘electric rotation’ which arises when an electric quadrupole (deformation) breaks the symmetry).

An intuitively appealing description of the behaviour of the M1-bands naturally arises from the Tilted Axis Cranking (TAC) model [1]. Close to the band-head the proton and neutron angular momentum vectors are coupled almost perpendicular to each other. The total angular momentum vector, \underline{J} , then lies along a tilted axis (see Fig. 1). Angular momentum is generated as the proton and neutron angular momentum

vectors slowly tilt towards \underline{J} . This has been called the ‘shears mechanism’. Since the magnetic transition probability is determined by the components of the magnetic moments perpendicular to \underline{J} , the $B(M1)$ should drop with increasing spin. This is a crucially important prediction, since the $B(M1)$ ’s are a sensitive probe of the underlying mechanism. Previous attempts to deduce $B(M1)$ ’s through lifetime measurements have proven inconclusive. A new high-precision measurement of lifetimes of states in the M1-bands of $^{198,199}\text{Pb}$ has been performed using Gammasphere [2]. The deduced $B(M1)$ values show a remarkable agreement with the TAC predictions (see Fig. 2). The results represent the first convincing proof of the phenomenon of nuclear ‘magnetic rotation’.




Fig1: The TAC Mechanism




Fig2: $B(M1)$ ’s: TAC vs. Expt

References

- [1] S. Frauendorf, Nucl. Phys. A 557 (1993) 259c
- [2] R. M. Clark et al., accepted, Phys. Rev. Lett.

Search for two-phonon octupole vibrational states in ^{208}Pb

K. Vetter, A.O. Macchiavelli, S.J. Asztalos, R.M. Clark, M.A. Deleplanque, R.M. Diamond, P. Fallon, R. Krücken, I.Y. Lee, R.W. MacLeod, G.J. Schmid and F.S. Stephens

For many years the first excited state of ^{208}Pb has been interpreted as a one-phonon vibration of octupole character. The identification of the two-phonon vibration is mandatory in order to prove the vibrational picture and to measure the harmonicity of octupole vibrations. Only recently the first promising experimental evidence for the existence of the two-phonon vibration was observed using a $(n,n'\gamma)$ reaction, indicating only a slight deviation of an harmonic oscillation [1]. We have performed an experiment to populate the two-phonon vibrational states in ^{208}Pb with ^{154}Sm at a bombarding energy of 1000 MeV and measuring γ -rays in Gammasphere consisting of 60 Ge-detectors at this time. To be independent of the lifetime of the two-phonon state we used a thin target requiring the measurement of the position of the scattered particles to correct for the Doppler-shift of the emitted γ -rays. Scattered particles were detected by a Silicon strip detector covering the range close the grazing angle. Like all previous heavy-ion induced experiments designed to measure the γ -decay following the possible excitation of the second octupole phonon in ^{208}Pb this experiment was performed at a bombarding energy which is about 20% above the Coulomb Barrier. At this energy the nuclear interaction is expected to increase strongly the population probability of the double phonon members [2]. Coulomb excitation as well as coupled-channel calculations indicate that the 6^+ state dominates the population of the multiplet. The decay of the 6^+ state is expected to feed the 5^- state at 3198 keV ($E_\gamma(E1) \approx 2\text{MeV}$) followed by an E2 transition of $E_\gamma=584$ keV to the 3^- state at 2614 keV. As can be seen in the partial energy spectrum shown in fig. 1 obtained by gating on the 584 keV transition it is not possible to identify any candidate for the decay of members of the two-phonon octupole vibra-

tion. However, based on the efficiency-corrected




Figure 1: Partial γ -energy spectrum of ^{208}Pb for grazing collisions after gating on the $5^- \rightarrow 3^-$ transition at 584 keV.

intensities we can establish lifetime independent limits for the observation of a γ -transition in a region between 2 MeV and 3 MeV relatively to the $3^- \rightarrow 0^+$ or the $5^- \rightarrow 3^-$ transition. Particularly, the limit for the collisions at the grazing angle are about a factor of 10 below the yield predicted by coupled-channel calculations [2]. However, one has to realize that this limit may not be very sensitive to the population of the two-phonon states since the intensity of the $5^- \rightarrow 3^-$ transition is primarily determined by the decay of energetically higher-lying states, bypassing the higher order vibrational states. Having not been able to observe the decay of any second phonon state it is suggested that we need to perform an experiment at a “safe” bombarding energy well below the Coulomb barrier where only Coulomb excitation takes place as a process which can be described by theory accurately.

References

- [1] M. Yeh *et al.*, Phys. Rev. Lett. **76**, 1208 (1996).
- [2] S. Landowne, C.H. Dasso, R.A. Broglia and A. Winther, Phys. Lett. **70B**, 294 (1977).

Study of Neutron-rich Nuclei Using Deep-inelastic Reactions

I.Y. Lee¹, S. Asztalos¹, M.A. Deleplanque¹, B. Cederwall¹, R.M. Diamond¹, P. Fallon¹

A.O. Macchiavelli¹, L. Phair¹, F.S. Stephens¹, G.J. Wozniak¹, S.G. Frauendorf²

J.A. Becker³, E.A. Henry³, P.F. Huo⁴, D.G. Sarantites⁴, J.X. Saladin⁵, and C.H. Yu⁶

¹ Nuclear Science Division, Lawrence Berkeley National Laboratory, Berkeley CA 94720, U.S.A.

² Research Center Rossendorf, Dresden, Germany

³ Lawrence Livermore National Laboratory, Livermore, CA 94550, U.S.A.

⁴ Washington University, St. Louis, MO 63130 U.S.A.

⁵ University of Pittsburg, Pittsburg, PA 15260 U.S.A.

⁶ University of Rochester, Rochester, NY 14627 U.S.A.

Neutron-rich nuclei are of particular interest since they might reveal new aspects of nuclear structure associated with an excess of neutrons, such as a neutron skin, a modified shell structure and new modes of excitation. These nuclei are difficult to produce, particularly in high-spin states. However, using deep-inelastic reactions together with the new gamma-ray detector arrays, one expects to have enough sensitivity, in spite of the low cross sections, to reach these nuclei in high-spin states.

We have carried out the reaction $^{48}\text{Ca} + ^{176}\text{Yb}$ at a beam energy of 250 MeV. A thin target was used to allow both the projectile- and target-like fragments to decay outside the target so that gamma rays from short-lived high-spin states can be observed as sharp lines after Doppler-shift correction. An annular silicon-strip detector was used to detect the scattered fragments. The early implementation of Gammasphere with 36 detectors was used to detect the gamma-rays. Coincidence events with at least one fragment and two Compton-suppressed gamma rays detected were taken at a rate of 1000/sec.

Two- and three-fold gamma-ray-coincidence data were analyzed for the gamma rays from the target-like fragments, and about 10 different nuclei were observed. In this data set, we were able to study nuclei produced with a cross section as low as 0.1 mb/sr. The gamma-ray yield of Yb nuclei as a function of spin is shown in Fig. 1. The sensitivity of the current setup allowed states with spin as high as 20 to be observed.

Before this study, only three levels in the yrast band were known in $^{175,177}\text{Yb}$ and ^{178}Yb . This work extends the yrast band of ^{178}Yb to spin 12 and the yrast bands in $^{175,177}\text{Yb}$ to spin 37/2 and 33/2, respectively. These new transitions allow us to study the systematics of back bending in neutron rich Yb nuclei. The $i_{13/2}$ band in the odd-mass nuclei provided an experimental reference for the extraction of the Routhians in the neighboring even-mass nuclei. The experimental Routhians compare well with cranked shell model calculations[1].




Figure 1: Gamma-ray yield of Yb nuclei as a function of spin

References

- [1] R. Bengtsson, S. Frauendorf and F.-R. May, Atomic Data and Nuclear Data Tables, 35 (1986)15.

A Measurement of the Gamma Ray Polarization Sensitivity of Gammasphere

G.J. Schmid, A.O. Macchiavelli, M.A. Deleplanque, S. Asztalos, R.M. Clark, R.M. Diamond, P. Fallon, R. Krücken, I.Y. Lee, R.W. MacLeod, F.S. Stephens, and K. Vetter

Nuclear Science Division, Lawrence Berkeley National Laboratory, Berkeley CA 94720, U.S.A.

The Gammasphere array currently in operation at Berkeley has the potential to operate as a γ -ray polarimeter (for linear polarization) by taking advantage of the segmented Ge detectors that will eventually comprise 65% of the completed array.

The polarization sensitivity for this type of segmented detector can be related to the polarization, P , of the radiation through the usual formula $Q(E_\gamma) = A(E_\gamma)/P$, if the experimental asymmetry, $A(E_\gamma)$, is defined (for example) as follows:

$$A(E_\gamma) = \left(\frac{1}{\sqrt{\eta(E_\gamma)}} \right) \left(\frac{\eta(E_\gamma)C(E_\gamma) - S(E_\gamma)}{C(E_\gamma) + S(E_\gamma)} \right) \quad (1)$$

In this relation, $C(E_\gamma)$ and $S(E_\gamma)$ represent the number of confined and shared events in the segmented detectors (i.e. the full absorption events which deposit their energy either confined to one side, or shared between the two sides), and $\eta(E_\gamma)$ is a parameter whose value is determined so as to give zero asymmetry for unpolarized γ -rays.

To determine $Q(E_\gamma)$ we measured asymmetries associated with γ -rays of known polarization [1]. In particular, we looked at γ -rays from excited states in ^{24}Mg , ^{56}Fe , and ^{109}Ag which were populated following inelastic scattering of protons at $E_p = 2.46$, 3.0 and 2.54 MeV respectively. This allowed determination of $Q(E_\gamma)$ at 1.368 MeV, 0.847 MeV, and 0.415 MeV respectively. The $\eta(E_\gamma)$ parameter for these experiments was determined as a function of E_γ by using a ^{152}Eu source placed at the target location. Figure 1 shows (by the solid data points) the results for $Q(E_\gamma)$. A computer Monte Carlo simulation was also performed to compare with these

experimental values. In this simulation, the γ -ray polarization vector was rigorously tracked so as to give realistic azimuthal Compton scattering for all the multiple interactions of each γ -ray. The results of these calculations (along with the associated errors) are shown by the open data points in Figure 1. A solid line connects these points. The agreement between experiment and theory is seen to be good. The dashed line in Figure 1 is the energy dependence of the Klein-Nishina formula in a point detector approximation [1]. This energy dependence is the one which is traditionally used to fit $Q(E_\gamma)$ data from 4-fold segmented polarimeters. However, due to the 2-fold segmented nature of the current geometry, this energy dependence is seen to be inadequate. In particular, the side-photoabsorption at low energies is seen to reduce Q .




Figure 1: The experimental results for Q are compared to theoretical energy dependences.

References

- [1] P.M. Jones *et al.*, NIM A362,556 (1995)

Multiparticle-rotor model for rotational band structure of ^{154}Gd

S.Y. Chu, J.O. Rasmussen, and M.A. Stoyer

Nuclear Science Division, Lawrence Berkeley National Laboratory, Berkeley, CA 94720, USA

P. Ring

Physik Department Technische Universität München, D-85747 Garching, Germany

L.F. Canto

Instituto de Física, Universidade Federal do Rio de Janeiro, 21945 Rio de Janeiro, Brasil

Band-crossing phenomena in the high-spin region of deformed nuclei are studied in this paper. The power of modern computers for large-matrix diagonalization (up to 17527×17527) is exploited in a multinucleon-plus-rotor model, the interesting test case of ^{154}Gd being treated in this paper. Though a small basis set of 9-18 Nilsson orbitals is used, the strict angular momentum and particle number conservation guarantees superior orthogonal microscopic wave functions for nucleon transfer calculations. This method takes account of pairing correlations among the valence particles and shows the effects of quadrupole pairing and the usually neglected $\mathbf{j} \cdot \mathbf{j}$ recoil terms.

References

- [1] Published in Phys. Rev. **C52** (1995) 1407

Models for Rotational Spin Distributions of Primary Fission Products

*J.O. Rasmussen, S.Y. Chu, D. Strellis and S. Asztalos,
Nuclear Science Division, Lawrence Berkeley National Laboratory, Berkeley, CA 94720, USA*

*R. Donangelo and L.F. Canto
Instituto de Fisica, Universidade Federal do Rio de Janeiro, C.P. 68528
21945-970 Rio de Janeiro, Brazil*

*J.D. Cole
Idaho National Engineering Laboratory, Idaho Falls, ID 83415 USA*

*M.A. Stoyer and Y.X. Dardenne
Lawrence Livermore National Laboratory, Livermore, CA 94550 USA*

*J.H. Hamilton
Dept. of Physics and Astronomy, Vanderbilt University, Nashville, TN 37235 USA*

Data from the 1993 Gammasphere measurements of the GANDS93 collaboration [1] were analyzed for rotational band spin feeding intensities by Dubna members of the collaboration and presented [2] at the DANF96 Conference in the Slovak Republic. They found in the zero-neutron, so-called "cold fission," of ^{104}Mo (with ^{148}Ba partner) relative feeding intensities of 0.21:0.74:0.05 to 2+, 4+, and 6+ levels (with feeding to 0+ indeterminate,) for an average spin of 3.7. This average is below measured average spin values of fission fragments for fission with more neutrons evaporated, which averages around 5 for the light fragments. The ^{106}Mo "cold fission" has an even lower (2.4) average spin.

We have in our paper [3] at the DANF96 conference presented results from a careful theoretical study of the Coulomb excitation following scission, using a modified semiclassical theory with finite moment-of-inertia. Coulex starting from rest at scission gives too much spin, even when the initial spin is unrealistically set at zero. We must assume Coulex is reduced by substantial Coulomb-nuclear interference and fragment kinetic energy present at scission. Data analysis and theoretical studies are continuing.

References

- [1] S.J. Zhu, Q.H. Lu, J.H. Hamilton, A.V. Ramayya, L.K. Peker, M.G. Wang, W.-C. Ma, B.R.S. Babu, J. Kormicki, D. Shi, J.K. Deng, J.O. Rasmussen, M.A. Stoyer, S.Y. Chu, K.E. Gregorich, M.F. Mohar, S. Asztalos, S.G. Prussin, J.D. Cole, R. Aryaenejad, Y.X. Dardenne, M. Drigert, K.J. Moody, R.W. Loughheed, J.F. Wild, N.R. Johnson, I.Y. Lee, F.K. McGowan, G.M. Ter-Akopian, and Yu.Ts. Oganessian, from Idaho National Engineering Laboratory; Vanderbilt University; Lawrence Berkeley National Laboratory; Lawrence Livermore National Laboratory; Joint Institute for Heavy Ion Research, Oak Ridge; Flerov Laboratory of Nuclear Reactions, JINR, Dubna, Russia; Qinghua University, Beijing
- [2] G. Popeko, A. Daniel, and GANDS93 authors of preceding reference; Poster at Conf. on Dynamical Aspects of Fission (DANF96), Casta-Papiernicka, Slovakia, Aug30-Sep 4, 1996, Proceedings to be published.
- [3] Authors of this Annual Report, Invited paper by J.O. Rasmussen at DANF96 Conference of preceding reference.

Multiband theory for heavy-ion neutron-pair transfer among deformed Gd nuclei.

S.Y. Chu, J.O. Rasmussen, and M.A. Stoyer

Nuclear Science Division, Lawrence Berkeley National Laboratory, Berkeley, CA 94720, USA

P. Ring

Physik Department Technische Universität München, D-85747 Garching, Germany

L.F. Canto and R. Donangelo

Instituto de Física, Universidade Federal do Rio de Janeiro, 21945 Rio de Janeiro, Brasil

In this paper our microscopic wave functions for Gd isotopes are applied to calculating neutron-pair transfer probabilities in heavy-ion collisions. The approximately 2600-term wave functions come from Hamiltonian matrix diagonalization of systems of 12 Nilsson neutron orbitals, nearly half-filled. We use the lowest five bands in initial and final nuclei and calculate transfer for all even spins from 0 through 30. Results for the sudden approximation (infinite moment-of-inertia) for neutron-pair extraction from ^{156}Gd by ^{58}Ni at near coulomb barrier energy, and extraction by ^{206}Pb are shown. Next neutron-pair deposition by the Ni and Pb projectiles is calculated. Finally, a finite moment-of-inertia semiclassical calculation is formulated and performed on the above collision system for n-pair transfer in both directions. The results are compared with experimental results. It is clear that the inclusion of the additional bands above the lowest two is important. Theory and experiment agree qualitatively on the rise of population above the yrast line at higher spins.

References

- [1] Published in *Phys. Rev. C* **52** (1995) 685

Form factors for two-nucleon transfer in the diabolical region of rotating nuclei

A.R. Farhan

Physics Department, Kuwait University, Kuwait

L.F. Canto

Instituto de Fisica, Universidade Federal do Rio de Janeiro, C.P. 68528

J.O. Rasmussen

Nuclear Science Division, Lawrence Berkeley National Laboratory, Berkeley, CA 94720, USA

P. Ring

Physik Department Technische Universität München, D-85747 Garching, Germany

The theoretical investigation of rotational bands in strongly deformed nuclei by Coulomb excitation and the subsequent transfer of nucleon pairs requires the knowledge of two-nucleon transfer amplitudes between rotating eigenstates of the A and the $A+or-2$ systems. In a semi-classical approximation these amplitudes are obtained by integrating over transfer form factors depending on the orientation angle of the deformed target nucleus. We use the cranking approximation based on a rotating mean field in order to calculate these transfer form factors. Their behavior is studied as a function of angular momentum, deformation and pairing correlations. In the region of diabolical points these form factors show considerable oscillations and phase changes reflecting the microscopic single-particle structure involved in these matrix elements. In this way we are able to understand the underlying microscopic structure causing the diabolical behavior of pair transfer in this region.

References


- [1] Published in Nucl. Phys. A 597 (1996) 387

The 8th Edition of the *Table of Isotopes*

R.B. Firestone, V.S. Shirley, C.M. Baglin, S.Y.F. Chu, and J. Zipkin

A new edition of the *Table of Isotopes* has been published by John Wiley & Sons, Inc. This edition is the eighth in a series started by Glenn T. Seaborg in 1940. The two-volume, 3168 page, cloth-bound edition contains nuclear structure and decay data for over 3100 isotopes and isomers. Approximately 24,000 references are cited and the appendices have been extended and completely rewritten. The book is packaged with an interactive CD-ROM that contains the *Table of Isotopes* in Adobe Acrobat Portable Document Format for convenient viewing on PC and Macintosh personal computers and Unix workstations. The CD-ROM version contains a chart of the nuclides graphical index and separate indices organized for applied radioisotope users and nuclear structure physicists. Over 100,000 hypertext links are provided to move the user

quickly through related information free from the limitations of page size. The data are presented more completely in a form that is easy to read on any monitor. Complete references with keyword abstracts are provided. The CD-ROM also contains the *Table of Superdeformed Nuclear Bands and Fission Isomers*; *Tables of Atoms, Atomic Nuclei, and Subatomic Particles* by Ivan P. Selinov the Evaluated Nuclear Structure Data File (ENSDF) and the ENSDF Manual; the Nuclear Science Reference file (NSR); and Adobe Acrobat Reader software. The databases on the CD-ROM can be viewed with VuENSDF software provided separately. More information about the *Table of Isotopes* and a faxable order form can be obtained through the *Table of Isotopes* Internet site at <http://isotopes.lbl.gov/isotopes/toi.html>.



The Isotope Explorer

S.Y.F. Chu¹, H. Nordberg^{1,2}, L.P. Ekstrom², and R.B. Firestone¹

The Isotope Explorer (formerly VuENSDF) is a Windows C++ application for searching and displaying the Evaluated Nuclear Structure Data File (ENSDF) and the Nuclear Science Reference file (NSR). The data can be downloaded by the Isotope Explorer from the Internet or from the *Table of Isotopes* CD-ROM. Data can be selected by level or transition properties, nuclear structure information, and transition coincidence relationships. The nuclear chart can be used to display selected nuclear properties, generate functional relationships between data, and display data from the nuclear databases. The database can be searched by

restricting the range of nuclear properties, and the results can be displayed on the chart or in tables, level scheme drawings, and plots. Keyword abstracts for over 140,000 references can be retrieved and displayed.

Version 1.0 of VuENSDF was released in 1996, and Version 2.0 of the Isotope Explorer is available for beta testing. Both versions are freely distributed and can be downloaded from the WWW home page at <http://isotopes.lbl.gov/isotopes/vuensdf.html>. Sample windows for the isotope explorer are shown in figure 1 below.




Figure 1. Representative chart, table, level scheme, and plot for a ^{152}Dy superdeformed band.

¹ Lawrence Berkeley National Laboratory

² Lund University, Sweden

Nuclear Data on the Internet

R.B. Firestone¹, S.C. Wu^{1,2}, and S.Y.F. Chu¹

The LBNL Isotopes Project has been providing nuclear data over the Internet since April, 1995. Eight primary home pages are supported for the *Table of Isotopes*, radioactive decay, Isotopes Explorer (VuENSDF) software and ENSDF data, nuclear astrophysics, nuclear structure and high-spin, atomic masses, thermal neutron capture, and Isotopes Project information. About 800MB of information is currently available through these websites.

The following table summarizes how often each of the Isotopes Project websites was accessed each month. The number of individual users, determined by counting connections from separate computer IP addresses, has risen to over 2500 during the peak months of 1996. Total link requests, indicating how many files or pages were accessed, have run as high as 38,400 in the busiest month.

Access Frequency for the Isotopes Project Nuclear Data WWW Home Pages

Date	Website http://isotopes.lbl.gov/isotopes/...html								Total Link Requests	Total Users
	TOI	DECAY	VUENSDF	ASTRO	HSPIN	TOIMASS	NG	IP		
Apr 1995	0	0	6	0	0	0	0	9	169	16
May 1995	0	0	141	0	0	0	0	193	3437	169
Jun 1995	0	0	83	0	0	0	0	153	1889	148
Jul 1995	0	0	100	0	0	0	0	151	2753	122
Aug 1995	0	0	112	0	0	0	0	129	2711	128
Sep 1995	0	0	123	0	0	0	0	190	2948	184
Oct 1995	98	0	201	37	0	36	0	226	5535	231
Nov 1995	158	0	225	49	38	30	0	265	8130	320
Dec 1995	128	0	170	56	22	30	0	294	6347	411
Total 1995	384	0	1061	142	60	96	0	1610	33919	
Jan 1996	154	0	288	83	37	54	0	348	8227	495
Feb 1996	555	0	356	87	56	121	0	362	9717	752
Mar 1996	967	0	353	101	76	155	0	289	11399	1049
Apr 1996	1157	0	425	230	141	215	0	325	10085	1263
May 1996	1113	292	351	202	152	258	0	264	15048	1219
June 1996	1207	493	400	392	209	299	0	302	19741	1565
July 1996	1054	436	414	359	162	223	0	248	22707	1491
Aug 1996	1081	359	467	459	155	266	0	309	18967	1576
Sep 1996	1390	347	427	435	211	351	147	271	26137	1848
Oct 1996	1728	401	490	480	164	417	145	317	32910	2577
Nov 1996	1765	488	565	533	194	422	120	322	26692	2575
Dec 1996	1462	336	453	595	172	343	113	308	38405	2094
Total 1996	13633	3152	5089	3956	1729	3124	525	3665	240036	

¹ Lawrence Berkeley National Laboratory

² Tsing-Hua University, Taiwan

Superdeformed and High-Spin Nuclear Structure Data on the Internet

B. Singh^{1,2}, R.B. Firestone² and S.Y.F. Chu²


With the advent of large detector arrays, a wealth of new information about the properties of nuclei at high-spin has become available. Rapid progress in this field has created a demand for up-to-date sources of information. We have published two editions of the *Table of Superdeformed Nuclear Bands and Fission Isomers*^{1,2} to meet this need. This publication provides *Table of Isotopes* style summary tables, superdeformed band drawings, and dynamic moment of inertia plots for all nuclei with superdeformed bands or fission

isomers. The *Table of Superdeformed Nuclear Bands and Fission Isomers* is being updated continuously and provided on our High-Spin and Nuclear Structure home page at <http://isotopes.lbl.gov/isotopes/hspin.html> on the Internet. In addition, recent high-spin references are being scanned continuously and new lists are posted on the WWW approximately every three months. Nilsson diagrams, links to the large detector array home pages, and other nuclear data are also available on this home page.

1. R.B. Firestone and B. Singh, in the *Table of Superdeformed Nuclear Bands and Fission Isomers*, LBL-35916 (1994).
2. B. Singh, R.B. Firestone and S.Y.F. Chu, in the *Table of Superdeformed Nuclear Bands and Fission Isomers*, Second Edition, Nucl. Data Sheets 78, 1 (1996).

¹ McMaster University, Canada

² Lawrence Berkeley National Laboratory



Reducibility and Thermal Scaling in Nuclear Multifragmentation

L.G. Moretto, R. Ghetti, L. Phair, K. Tso, and G.J. Wozniak
Nuclear Science Division, Lawrence Berkeley National Laboratory

Recent studies have revealed the existence of a number of reducibility and thermal scaling properties in nuclear multifragmentation. The probability of emitting n intermediate-mass fragments is found to be *reducible* to the probability of emitting a single fragment through the binomial expression [1,2]. The resulting one fragment probability shows *thermal scaling* by producing linear Arrhenius plots [1-3].

Similarly, the charge distributions associated with n -fragment emission are *reducible* to the one-fragment charge distribution [4]. *Thermal scaling* is also observed [4]. The reducibility equation contains a constant whose value, zero or positive, can be related to a univariant (two phases) or bivariant (one phase) regime [5].

The light fragment particle-particle angular correlations also show *reducibility* to the single-particle angular distributions as well as *thermal scaling* [6]. A mass scaling associated with the angular correlations suggests emission from several small sources ($A \approx 20$).

The limits of applicability of scaling and reducibility are discussed in ref. [7] as well as their implications for the mechanism of multifragmentation.

The picture of multifragmentation, as it appears in ref. [7], is still sketchy and incomplete. However, we believe we have succeeded in unveiling important features which may be the key to deeper understanding.

The pervasive aspect of *reducibility* indicates that, whatever the mechanism, the fragments are emitted essentially independent of one another. Thus we have shown that the probability P_n of emitting n fragments can be reduced to the probability of emitting a single fragment through the binomial equation. Similarly the n fragment charge distributions can be reduced to the one fragment charge distribution. Furthermore, the particle-particle angular correlation can be reduced to the individual particle angular distributions.

In all the above quantities, reducibility is somehow restricted by what we may call "dynamical constraints". For the emission probabilities, the constraint is the binomial parameter m (the number of "throws"), indicative either of a dynamical time window, or of the finite source size.

For the charge distributions, reducibility is restricted by the parameter c (see refs. [4,5]), which seems to indicate some special way of enforcing charge conservation. We speculate that its transition from near zero to a finite value with increasing energy could be an indication of a transition from phase coexistence (liquid-vapor) to a single phase (vapor).

Finally, the angular correlations violate reducibility at

small relative angle where particle-particle interactions become manifest [6].

These broad features of reducibility speak to the near independence of fragment emission but not to its mechanism.

Thermal scaling instead makes a clear statement about the fact that the elementary probabilities entering in the n fragment emission probabilities, the n fragment charge distributions, and the two fragment angular correlations are *thermal*. In other words, these probabilities have the form of a Boltzmann factor and clearly portray its characteristic energy dependence (Arrhenius plots).

Thus the resulting picture is tantalizingly close, but not quite that of a compound nucleus emission. Apparently sources are dynamically generated which, within dynamical constraints of time and size, emit fragments in a thermal manner. Among the potential fruits that can be reaped from the pursuit of the analysis outlined so far are dynamical features of source formation, size and lifetime, as well as static features like barriers, source sizes and densities.

-
- [1] L.G. Moretto *et al.*, Phys. Rev. Lett. **74**, 1530 (1995).
 - [2] K. Tso *et al.*, Phys. Lett. B **361**, 25 (1995).
 - [3] L.G. Moretto *et al.*, Phys. Rev. Lett. **71**, 3935 (1993).
 - [4] L. Phair *et al.*, Phys. Rev. Lett. **75**, 213 (1995).
 - [5] L.G. Moretto *et al.*, Phys. Rev. Lett. **76**, 372 (1996).
 - [6] L. Phair *et al.*, Phys. Rev. Lett. **77**, 822 (1996).
 - [7] L.G. Moretto *et al.*, Phys. Rep. (in press).

Aspects of Reducibility and Thermal Scaling in Multifragmentation

R. Ghetti, L.G. Moretto, L. Phair, K. Tso, G.J. Wozniak
Nuclear Science Division, Lawrence Berkeley National Laboratory

Recent experimental evidence of binomial reducibility and thermal scaling in multifragmentation, has raised a number of physical and technical issues that need to be addressed. To this end, two simulations of multifragment decay have been implemented, a binomial simulation and a Poisson one [1]. By means of the binomial simulation, the reducibility of the n -fold intermediate-mass-fragment multiplicity and charge distributions to the one-fragment emission values has been investigated. With both simulations, the effects of using the transverse energy as a measure of the system excitation energy have been evaluated. Possible experimental biases in the results have been evaluated as well.

We have implemented binomial and Poisson decay simulations to address a number of issues connected to the experimental multifragmentation studies presented in Refs. [2-7]. For the binomial simulation, we have assumed that the n -fragment emission probabilities P_n are distributed according to the binomial distribution, and that multifragmentation is empirically reducible to a combination of nearly independent fragment emissions. Moreover, we have assumed a thermal dependence of the elementary emission probability p on the nuclear temperature.

By processing simulated events, we have tested the standard procedures utilized in the experimental data analysis. We have verified that the simulation input is recovered without significant loss of information and how the final results reflect different input conditions.

The simulation results strengthen the validity of the reducibility approach used in the experimental work and the physical meaning of quantities such as the elementary probability p . Reducibility is a valid approach also when multiple sources of fragment emission are created in the collision, if one of the sources is dominant. The Arrhenius plot is a powerful tool to explore the thermal features of the elementary probability p , even though the determination of the actual fragment emission barrier B , proportional to the slope of the plot, can be hampered by the presence of source residues and by small size effects.

From both binomial and Poisson simulations it appears that the total transverse kinetic energy E_t is a good observable that can be reliably used for the measurement of the excitation energy in multifragmentation studies at intermediate energies. In our simulations, the transverse energy is linearly correlated with the system excitation energy and weakly correlated with the IMF multiplicity. We have demonstrated that neither event-to-event fluctuations nor E_t auto-correlation effects are large enough to distort a Poisson distribution into a binomial distri-

bution. In particular the mean and variance of the N_{IMF} distribution are reasonably well preserved, even when the measurement of E_t is limited by the detection efficiency.

We have tested the effects of a reduced geometric efficiency as well as the effects of a software replica of the detection device. We have shown that a reduced geometric efficiency preserves binomiality and that efficiency corrections can be applied through the binomial parameters p and m . We have explored the effects of a finite detection acceptance on the Arrhenius plot and have shown that when the geometric acceptance is reduced, it is still possible to recover the binomial input without significant loss of information. The introduction of an energy dependent efficiency, instead, can compromise this possibility, especially when the transverse energy is used as a measure of the system excitation energy.

We have also shown that, in a binomial decay scenario, the n -fold IMF charge distributions are reducible to the 1-fold, consistent with the experimental findings. In the binomial simulation, the n -fold charge distributions are independent of the fold number n as long as a sizeable remnant serves as a reservoir of mass, charge and excitation energy. A dependence on n arises when the entire system is consumed.

The results of the decay simulations have made us more confident that the experimental procedures utilized in the data analysis of Refs. [2-7] are correct, and that the empirical findings of reducibility and thermal scaling in multifragmentation are not an artifact of incomplete detection efficiency nor are they generated by the auto-correlation of the variable used to estimate the excitation energy.

-
- [1] R. Ghetti *et al.*, LBNL-39196.
 - [2] L.G. Moretto *et al.*, *Phys. Rev. Lett.* **74** (1995) 1530.
 - [3] K. Tso *et al.*, *Phys. Lett. B* **361** (1995) 25.
 - [4] L. Phair *et al.*, *Phys. Rev. Lett.* **75** (1995) 213.
 - [5] L. Phair *et al.*, *Phys. Rev. Lett.* **77** (1996) 822.
 - [6] L.G. Moretto *et al.*, *Phys. Reports* (1996), accepted, LBNL-39388.
 - [7] A. Ferrero *et al.*, *Phys. Rev. C* **53** (1996) R5.

Reducibility, Thermal and Mass Scaling in Angular Correlations from Multifragmentation Reactions

L. Phair, L.G. Moretto, G.J. Wozniak,
Nuclear Science Division, Lawrence Berkeley National Laboratory

R.T. de Souza, D. R. Bowman, N. Carlin, C. K. Gelbke, W.G. Gong, Y.D. Kim,
M.A. Lisa, W.G. Lynch, G.F. Peaslee, M.B. Tsang, and F. Zhu
NSCL and Department of Physics and Astronomy, Michigan State University, East Lansing, MI 48824




FIG. 1. Evolution of the azimuthal correlation functions of two He particles (solid circles) and He and Be particles (open circles) emitted at $\theta_{lab} = 31^\circ\text{-}50^\circ$ for four different cuts on the transverse energy E_t . The solid lines are fits described in ref. [1].

We have explored the azimuthal correlations between emitted particles to search for thermal scaling of the correlation amplitudes and reducibility of the two-fold emission probability to that of the one-fold [1]. Fig. 1 shows azimuthal correlation functions of different particle pairs for different values of the transverse energy E_t . Consistent with previous observations, the azimuthal correlation functions exhibit a slightly distorted V-shape pattern. At larger excitation energies (assumed proportional to E_t) the correlations become progressively damped.

To understand the evolution of the correlation functions of Fig. 1, we have considered the exactly solvable problem of thermal particle emission from a rotating source. The classical probability of emitting a particle with reduced mass μ from the surface of a rotating system (of angular momentum I , moment of inertia \mathfrak{I} , temperature T and distance R between centers of the "daughter" and emitted nuclei) in a direction given by polar angle θ (in the center of mass frame) and azimuthal angle ϕ (measured with respect to the reaction plane) is:

$$P(\theta, \phi) \propto \exp[-\beta \sin^2 \theta \sin^2 \phi] \quad (1)$$

where




FIG. 2. Left panel: The fit parameter D as a function of $1/E_t (\propto 1/T^2)$ for the indicated identical particle pairs. Solid lines are linear fits to the data. Right panel: Same as left panel but for particle pairs of different masses.

$$\beta = \frac{\hbar^2 I^2}{2\mathfrak{I}T} \frac{\mu R^2}{(\mathfrak{I} + \mu R^2)} = \frac{E_{rot}}{T} \frac{\mu R^2}{(\mathfrak{I} + \mu R^2)} \quad (2)$$

and E_{rot} is the rotational energy of the source.

If the fragments are emitted independently of one another, the joint probability of observing two particles at a given polar angle θ and different azimuthal angles ϕ and $\phi + \Delta\phi$ is $P(\theta, \phi, \Delta\phi) = P(\theta, \phi)P(\theta, \phi + \Delta\phi)$. The resulting probability distribution must be averaged over the different directions of \vec{I} arising from different orientations of the impact vector and one obtains proportionality to a modified Bessel function of zeroth order. Expanding this function, the joint probability is approximately:

$$P(\theta, \Delta\phi) \propto 1 + \frac{D}{1 + D/2} \cos 2\Delta\phi + \frac{D^2}{(D + 2)^2} \cos^2 2\Delta\phi \quad (3)$$

where $D = (\beta^2 \sin^4 \theta)/8 \propto 1/T^2 \propto 1/E_t$.

A plot of D (extracted from fits to the correlation data, see Fig. 1) as a function of $1/E_t$ is given in Fig. 2. The simplest explanation for the observed linear behavior (thermal scaling) is that the fragmenting system attains an average rotational energy which is largely independent of E_t .

[1] L. Phair et al., Phys. Rev. Lett. **77**, 822 (1996).

Comment on "Circumstantial Evidence for Critical Behavior in Peripheral Au+Au Collisions at 35 MeV/nucleon."

L. Phair, Th. Rubehn L.G. Moretto, G.J. Wozniak,
Nuclear Science Division, Lawrence Berkeley National Laboratory

Mastinu *et al.* recently reported the observation of several positive signals possibly indicating critical behavior in peripheral collisions of Au+Au at $E/A=35$ MeV [1]. In our comment [2], we examine the choice of variables used to determine the presence (or absence) of critical behavior. We do this by repeating the analysis of ref. [1] on "data" from a simulation with no critical behavior.

The simulation samples a charge distribution and conserves charge (breaking up a source of size Z_0). The charge particle multiplicity N_C is specified at the outset. Within an event, at multiplicity n (where $1 \leq n \leq N_C - 1$) the probability to emit a particle of a given Z is

$$P_n(Z) \propto e^{-\alpha Z} \quad (1)$$

under the constraint that at each "emission step" n , the Z of the emitted particle be sufficiently small so that the event will satisfy the requirement of containing N_C particles. We chose $\alpha = 0.3$ and $Z_0 = 79$. The choice of an exponential charge distribution (and $\alpha=0.3$) is arbitrary as is the specific implementation of charge conservation.

Using this simulation we constructed "events" and examined the proposed observables for critical behavior. In Fig.1a is shown the Campi scatter plot of Z_{max} versus M_2/Z_0 . We observe the two-branch feature commonly interpreted as indicating "sub-critical" and "over-critical" events.

By applying cuts similar to those in ref. [1], we have plotted the resulting multiplicity distribution (Fig.1b). Qualitative agreement with the experimental data [1] is achieved with this simple event selection. We question whether these cuts "select" events that can be associated with critical behavior.

Using the same cut (2) in the Campi plot for "potentially critical" events as in ref. [1], we have constructed the horizontally scaled factorial moments. These moments are shown in Fig.1c. The linear rise with decreasing bin size is quite apparent. It has already been pointed out [3,4] that spurious intermittency signals can be observed by mixing events of different multiplicity, which is clearly the case for ref. [1] and for which the authors appropriately express concern.

Finally, we show a plot of M_2 versus N_C (Fig.1d). A peak in such a plot is often mistakenly taken as an indication of critical behavior. While we observe a peak, our simulation is one that assuredly contains no critical behavior.

We have repeated the analysis shown in Fig. 1 for power law charge distributions and different implemen-




FIG. 1. a) Z_{max} vs M_2/Z_0 with cuts similar to those used in ref. [1]. b) Input multiplicity distribution for the simulation (solid line) along with output distributions for cuts 1 (dashed), 2 (dotted) and 3 (dotted-dashed). c) Log of the scaled factorial moments ($i=2,3,4,5$) as a function of the negative log of the bin size δs for cut 2. d) $\langle M_2 \rangle / Z_0$ versus N_C .

tations of charge conservation but the qualitative results remain the same.

Before doing this analysis, we were under the mistaken impression that the simple observables listed above give an indication of the presence or absence of critical behavior. Part of our confusion came from the vast commentary in the literature that points to these observables as indicators of critical phenomena. In fact, positive signals in all of these observables are probably found in *any* simulation that conserves charge and where light particle emission is preferred over heavier fragments. And so we caution that the positive signals observed in ref. [1] are insufficient to establish critical behavior since they appear even in simple models which contain neither a phase transition nor critical behavior.

- [1] P.F. Mastinu *et al.*, Phys. Rev. Lett. **76**, 2646 (1996).
- [2] L. Phair *et al.*, Phys. Rev. Lett. (in press).
- [3] L. Phair *et al.*, Phys. Lett. B **291**, 7 (1992).
- [4] X. Campi and H. Krivine, Nuc. Phys. A **589**, 505 (1995).

Comment on "Probing the Nuclear Liquid-Gas Phase Transition"

L.G. Moretto, R. Ghetti, L. Phair, K. Tso, and G.J. Wozniak
Nuclear Science Division, Lawrence Berkeley National Laboratory

In a recent paper Pochodzalla *et al.* [1] report a tantalizing dependence of nuclear temperature upon excitation energy. This dependence is characterized by an initial rise, followed by a wide plateau and a subsequent rise. The authors tentatively ascribe the initial rise to "ordinary" evaporation, the middle plateau to a liquid-vapor phase transition, and the final rise to a nearly ideal gas dependence for the overheated vapor.

The question arises whether the entire experimental curve can be interpreted in terms of equilibrium thermodynamics. If so, several problems arise. For instance, the claimed distinction between the initial rise (interpreted as the fusion-evaporation regime) and the plateau (hinted at as liquid-vapor phase transition) is not tenable, since evaporation is the liquid-vapor phase transition and no thermodynamic difference exists between evaporation and boiling.

Furthermore, the "caloric curve" requires for its interpretation an additional relationship between the variables T , P , and V . More to the point, the plateau is a very specific feature of the constant pressure condition rather than being a general indicator of a phase transition. For instance, a constant-volume liquid-vapor phase transition is not characterized by a plateau but by a monotonic rise in temperature. This can be easily proven by means of the Clapeyron equation, which gives dP/dT along the univariance line (liquid-vapor transition) together with the ideal-gas equation for the vapor [2].

As an example, Fig. 1 shows a standard temperature T vs entropy S diagram for water vapor. The region under the bell is the phase coexistence region. For the constant pressure curves ($\Delta S = \Delta H/T$), the initial rise along the "liquid" curve is associated with pure liquid, the plateau with the liquid-vapor phases, and the final rise with overheated vapor. The constant volume curves ($\Delta S = \Delta E/T$) cut across the coexistence region at an angle, without evidence for a plateau.

Thus one concludes that the alleged reminiscence of the observed "caloric curve" with "the paradigm of a phase transition" may be more pictorial than substantive, and that indicators other than the plateau may be needed to substantiate a possible transition from one to two phases. More specifically, *an additional relationship between the three variables P, T, V (like $P=\text{const}$, or $V=\text{const}$, etc.) is needed to interpret a T - E diagram unequivocally.*




FIG. 1. Temperature-entropy diagram for steam. Curves are shown for constant pressure ($P_4 > P_3 > P_2 > P_1$), constant volume ($V_1 < V_2$) and constant percentage in the gas phase (dashed lines).

[1] J. Pochodzalla *et al.*, Phys. Rev. Lett. **75**, 1040 (1995).

[2] L.G. Moretto *et al.*, Phys. Rev. Lett. **76**, 2822 (1996).

Stable Coulomb bubbles ?

L.G. Moretto, K. Tso and G.J. Wozniak

Nuclear Science Division, Lawrence Berkeley Laboratory, Berkeley, California 94720

Within the framework of the liquid drop model, the energy of a bubble in units of twice the surface energy of the equivalent sphere (constant volume) can be expressed as a function of the bubble monopole coordinate [1]. At zero pressure and angular momentum, the surface energy increases as a bubble develops from a sphere, but the Coulomb energy decreases as the charges are brought farther apart due to the bubble expansion. Therefore, an interplay between the Coulomb and surface energies may generate a minimum energy point along the monopole coordinate. The bubble minimum appears first at a value of the fissility parameter $X = 2.022$, and becomes the absolute minimum at $X = 2.204$.

A Coulomb bubble that is stable against monopole oscillations, may be subjected to higher order perturbations. The higher deformation modes of the bubble can be divided into two classes: the *radial modes* and the *crispation modes*. The deformations on the two surfaces are in phase with each other for a radial mode, and they are out of phase for a crispation mode.

The monopole oscillation obviously belongs to the class of radial modes. The lowest order crispation mode is the dipole mode which corresponds to a rigid displacement of the two spheres, one with respect to the other.

Unlike the dipole oscillation, higher multipole perturbations tend to increase the surface energy, and thus stabilize the unperturbed bubbles. This surface effect is the same for the radial and crispation modes, since the two modes differ only in the relative orientation of their surfaces. However, the Coulomb effect is drastically different for the two modes. The Coulomb perturbation energy is always negative for the radial mode, since the average distance between charges is increased slightly due to the perturbation. A similar effect of Coulomb destabilization is observed for the crispation mode in case of thick bubbles. In fact, the two modes are indistinguishable for a solid sphere. However, this destabilization effect becomes progressively weaker as the bubble expands. When a bubble is sufficiently thin, the Coulomb perturbation energy becomes positive, and stabilizes the crispation modes. This is because the Coulomb force tends to resist the attempt to concentrate the charge in "clumps" distributed on the surface of the thin bubble, as required by the higher order crispation modes. At the threshold fissility of $X = 2.022$, the value of X_{eff} lies just about at the $n=4$ line, indicating that the bubble is unstable up to the $n = 4$ mode. As more charge is brought into the bubble with increasing values of X , the Coulomb bubble expands and it becomes stable with respect to the $n = 4$ and even to the octupole mode ($n = 3$) at $X=2.5$. How-

ever, the Coulomb bubble is still unstable with respect to the quadrupole mode ($n = 2$). In fact, a further increase of X does not stabilize the quadrupole mode.

Yet, it may be possible to have a stable nuclear bubble. If the bubble is warm, it fills up with vapor arising from the fluid itself. The resulting pressure acts only upon the monopole mode, by displacing outwards the Coulomb minimum. The effect on the other radial modes is nil, since only changes in volume are relevant to pressure. Thus the bubble has become secularly stable with respect to all the modes.

However, when a bubble becomes rather thin, a possible demise of the bubble may be associated with the sheet instability. The sheet instability is a new kind of Rayleigh-like surface instability associated with the crispation modes. A nuclear sheet of any thickness tends to escape from the high surface energy by breaking up into a number of spherical fragments with less overall surface. However, any perturbation of finite wavelength increases the surface area, and consequently the energy of the sheet, independent of the sheet thickness. Clearly, this barrier prevents the sheet from reaching the more stable configurations. However, when a nuclear sheet becomes sufficiently thin, the two nuclear surfaces interact with each other. This proximity interaction may become sufficiently strong to overcome the sharp barrier and causes the sheet to puncture into numerous fragments.

Since a bubble, like a sheet, must rely on the proximity interaction to become unstable, it will retain its surface stability until the range of the surface-surface interaction is of the order of its thickness.

In conclusion, the depletion of charge in the central cavity of nuclear bubbles reduces the Coulomb energy significantly and thus stabilizes "Coulomb" bubbles against monopole oscillations. These Coulomb bubbles, however, are at least unstable to perturbation of the quadrupole radial mode. On the other hand, a sufficiently high temperature generates a vapor pressure in the central cavity which drives the bubble to a thinner configuration that is stable against all the radial modes. Finally, a thin Coulomb bubble behaves like a sheet, and becomes susceptible to a proximity surface instability via the crispation modes when its thickness is comparable to the range of the proximity interaction.

[1] L.G. Moretto, K. Tso and G.J. Wozniak, Phys. Rev. Lett. (accepted), LBNL-39678.

Charge correlations and dynamical instabilities in multifragmentation*

L.G. Moretto, Th. Rubehn, L. Phair, N. Colonna, and G.J. Wozniak
Nuclear Science Division, Lawrence Berkeley National Laboratory, Berkeley, California 94720

D.R. Bowman, G.F. Peaslee, N. Carlin, R.T. de Souza, C.K. Gelbke, W.G. Gong, Y.D. Kim, M.A. Lisa, W.G. Lynch, and C. Williams

*National Superconducting Cyclotron Laboratory and Department of Physics and Astronomy,
 Michigan State University, East Lansing, MI 48824*

In recent years, it has been suggested that multifragment production can be related to the occurrence of instabilities in the intermediate system produced by heavy ion collisions. Although the scenarios and the models vary, breakup into several *nearly equal-sized* fragments is a common result of instabilities. We report the examination of model independent signatures that would indicate decay into a number of nearly equal-sized fragments by investigating charge correlations from both experimental data and simulations [1].

For comparison with experimental data, and to determine the sensitivity of our analysis, Monte Carlo calculations have been performed. The created events obey two conditions: the sum charge of all fragments is conserved within an adjustable accuracy, and a fragment is produced according to a probability consistent with the experimental finding, that the charge distributions are nearly exponential functions. Furthermore, the simulation allows one to smear out the charge distributions of the individual fragments of an event according to a Gaussian distribution.




FIG. 1. Two particle charge correlations of IMF's from simulations for $N_{IMF}=6$ plus 1% (left) and 0.1% (right panel) of $Z_{art}=6$.

To demonstrate the sensitivity of our method to breakup configurations producing equal-sized fragments, Fig. 1 shows the results of simulations for the case $N_{IMF} = 6$. Here, a "contamination" of 1% of the events consisting of fragments which all have the size $Z_{art} = 6$ has been added to the data set. The peak produced by these fragments is clearly visible, even if we decrease the yield of equal-sized fragments to only 0.1%. We note that the "background" seen in Fig. 1 is only due to charge con-

servation. The same analysis used for the simulation has been applied to experimental data of the reaction $Xe+Cu$ at $E/A=50$ MeV for different N_{IMF} cuts. An enhanced signal for breakup into nearly equal-sized fragments was not observed in *any* of the N_{IMF} bins.




FIG. 2. Higher order charge correlations from the simulations for a system size of 83, $N_{IMF} = 6$ and widths of $\omega=0$ and $\omega=2$.

To increase the sensitivity of the method, we have also investigated higher order charge correlations [1]. In Fig. 2, we show the results of such an analysis. Here, $\langle Z \rangle$ denotes the average fragment charge of the event, and ΔZ is the standard deviation. The same simulation which has already been shown in Fig. 1 was used. Here, only 0.1% of the events were chosen to have fragments with equal size. We show two cases with a "smearing" width of $\omega = 0$ and $\omega = 2$, respectively. The comparison between the two particle and the higher order charge correlation functions for the same simulations using $\omega = 0$ shows an enhancement of $\sim 20\%$ for the first case (right panel of Fig. 1) while the signal in the second case exceeds the "background" by roughly a factor of 100 (left panel of Fig. 2).

We have also analysed our experimental data for higher order charge correlation. No signals are observed that can be attributed to an enhanced production of nearly equal-sized fragments. This results in an upper limit of breakup events with nearly equal-sized fragments of less than 0.05% if we assume a width $\omega < 3$. Similar results have been obtained for other systems albeit with significantly poorer statistics.

[1], * L.G. Moretto *et al.*, Phys. Rev. Lett. 77, 2634 (1996).

Scaling Laws, Shell Effects, and Transient Times in Fission Probabilities*

L. G. Moretto, K. X. Jing, R. Gatti, and G. J. Wozniak
Nuclear Science Division, Lawrence Berkeley National Laboratory

R. P. Schmitt
Cyclotron Institute, Texas A&M University

In a recent paper [1] we analyzed the intermediate mass fragment excitation functions for an extensive range of fragment atomic numbers, obtained for four different compound nuclei. A special way of plotting these data permits the ready observation of deviations from the transition state rates as a departure from a straight line. For over 70 excitation functions, the lack of deviations from the transition state null hypothesis both as a function of fragment Z and excitation energy led to the conclusion that the transition state rates were closely obeyed, and that no substantial transient time effects were present in these systems over the covered experimental energy and lifetime ranges.

In this work we extend the method to the fission of systems in the lead region, where lies the dramatic onset of the shell effects, and for which transient time effects have been claimed. Specifically we show the following: a) fission excitation functions for nuclei ranging from $A=186$ to 213 are rigorously scalable in terms of the transition state rates once the shell effects are accounted for; b) the shell corrections Δ_{shell} obtained from the data are in excellent agreement with those obtained from the ground state masses.




FIG. 1. Shell corrections Δ_{shell} , for the daughter nuclei ($A_{CN} - n$), extracted from fits to the fission excitation functions, plotted against the values determined from the ground state masses [2]. The diagonal line is to guide the eye.

In fig. 1 are shown the values of the ground state shell effect Δ_{shell} of the daughter nuclei after neutron emission, obtained by fitting the fission excitation func-

tions with a transition state formalism in which Δ_{shell} is included in the expression of the level density of the residual nucleus. In this figure we plot these values of Δ_{shell} versus the corresponding values obtained as the difference of the ground state mass and the corresponding liquid drop value. The observed correlation is excellent. Note that the present shell effects are obtained in a totally independent way, which, in contrast to the standard procedure [2] is completely local, namely it depends only on the properties of the nucleus under consideration.




FIG. 2. The quantity $\ln(R_f)$ divided by $2a_n^{1/2}$ vs the square root of the intrinsic excitation energy over the saddle for fission of the fourteen compound nuclei indicated in the figure. The straight line is a linear fit to all but the lowest two or three data points.

As shown in fig. 2, all of the excitation functions for fourteen different compound nuclei reduce beautifully to a single straight line, according to the transition state predictions. This scaling extends well over seven orders of magnitude in the fission probability and is even better than that observed in ref.[1] for complex fragment emission, despite the fact that the systems cover a region in A and Z where shell effects vary dramatically. This indicates that the transition state fission rates hold extremely well. No evidence for the effects of transient times longer than 3×10^{-20} seconds is found.

* Excerpted from Phys. Rev. Lett. 75, 4186 (1995).
[1] L.G. Moretto *et al.*, Phys. Rev. Lett. 74, 3557 (1995).
[2] P. Möller *et al.*, LA-UR-3083 (1994).

Scaling laws and transient times in ^3He induced nuclear fission*

Th. Rubehn, K.X. Jing, L.G. Moretto, L. Phair, K. Tso, and G.J. Wozniak
Nuclear Science Division, Lawrence Berkeley National Laboratory

It is well known from early studies that fission excitation functions vary dramatically from nucleus to nucleus over the periodic table [1-3]. Some differences can be understood in terms of a changing liquid-drop fission barrier with the fissility parameter, others are due to strong shell effects which occur e.g. in the neighborhood of the double magic numbers $Z=82$ and $N=126$. Further effects may be associated with pairing and the angular momentum dependence of the fission barrier.

Fission rates have been successfully calculated most often with the transition state method introduced by Wigner [4] which has then been applied to fission by Bohr and Wheeler [5]. However, recent measurements of an enhancement of precission emission of neutrons and γ -rays in relatively heavy fissioning systems claim the failure of the transition state method. The alleged failure has been attributed to the transient time necessary for the so-called slow fission mode to attain its stationary decay rate. Since these methods are indirect and are fraught with difficulties, we have experimentally investigated the fission probability to search for possible deviations from the predicted transition state rates. Therefore, we have measured ^3He induced fission cross sections of three compound nuclei using two large area PPACs which allowed for the detection of both fission fragments in coincidence; the results are shown in Fig. 1 [6].




FIG. 1. Excitation function for fission of several compound nuclei formed in ^3He induced reactions. The different symbols correspond to the experimental data points. The solid line shows the results of a fit to the data.

Recently, we have introduced a method to analyze fission excitation functions [6,7]: it has been shown that this analysis allows the scaling of different excitation func-

tions according to the transition state predictions, once the shell effects are taken into account. As we show in Fig. 2, no deviations from the straight line, which would indicate a failure of the transition state method, are observable. Furthermore, this method allows one to determine the effective fission barrier, the shell effect, and a_f/a_n .




FIG. 2. The scaled fission excitation functions vs the square root of the intrinsic excitation energy over the saddle for fission of several compound nuclei. The straight line represents a fit to the whole data set.

The excitation energy covered by our experiment (25-145 MeV) corresponds to compound nucleus life times between 10^{-18} and 10^{-22} seconds, and is therefore sensitive to delay times in the first chance fission probability. We have assumed a step function for the transient time effect and calculated accordingly the resulting fission width. Modest fission transient times would show up as significant deviations from the straight line presented in Fig. 2. This allows us to determine an upper limit for the transient time of no longer than 10^{-20} seconds. Since the experimental fission rates are well described by the transition state method, it seems likely that most precission emission occurs during the descent from saddle to scission.

- [1] G. M. Raisbeck, J.W. Cobble, Phys. Rev. **153**, 1270 (1967).
- [2] L.G. Moretto *et al.*, Phys. Lett. **38B**, 471 (1972).
- [3] A. Khodai-Joopari, Ph.D. thesis, UC Berkeley, 1966.
- [4] E. Wigner, Trans. Faraday Soc. **34**, 29 (1938).
- [5] N. Bohr and J.A. Wheeler, Phys. Rev. **56**, 426 (1939).
- [6] * Th. Rubehn *et al.*, Phys. Rev. C **54**, 3062 (1996).
- [7] L.G. Moretto *et al.*, Phys. Rev. Lett. **75**, 4186 (1995).

First chance fission probability of neighboring Po isotopes*

Th. Rubehn, K. X. Jing, L. G. Moretto, L. Phair, K. Tso, and G. J. Wozniak
Nuclear Science Division, Lawrence Berkeley National Laboratory

Fission excitation functions of four neighboring polonium isotopes, $^{209,210,211,212}\text{Po}$, have been precisely measured in ^3He and ^4He induced reactions with isotopic lead targets at the 88-Inch Cyclotron to experimentally determine first chance fission probabilities. An estimate on the latter is essential to test the validity of the recently observed transition state scaling and to extract fission transient times. In the formalism described in Refs. [1,2], we have only accounted for 1st chance fission while for the experimental data we have the measured total fission probability. This approximation is certainly correct at low excitation energies where 1st chance fission is the dominant contribution. However, at higher energies, multi-chance fission is expected to become more important. Thus, the percentage of 1st chance fission will decrease.




FIG. 1. First and second chance fission probabilities for the reaction $^4\text{He} + ^{206,207,208}\text{Pb} \rightarrow ^{210,211,212}\text{Po}$. (Preliminary.)

The difference in the cumulative fission probability of neighboring isotopes can be used to determine the 1st chance fission probability. Since the energy dependence of the first chance fission probability is determined by subtracting similar cross sections, it is essential to measure the cumulative cross sections with high precision; see Ref. [3]. First chance fission at a given excitation energy can be determined by subtracting the fission probabilities of two neighboring isotopes by using the separation energy of the last neutron and the temperature of the daughter nucleus given by $T = \sqrt{E^*/a_n}$. We note that the angular momentum dependence is neglected in this simple ansatz.

In Fig. 1, we show the preliminary results of this analysis for ^4He induced reactions. At excitation energies smaller than ~ 45 MeV, 1st chance fission accounts for practically all the fission yield. However, at higher excita-




FIG. 2. The quantity $\frac{\ln R_f}{2\sqrt{a_n}}$ vs the square root of the intrinsic excitation energy over the saddle for fission of the compound nucleus ^{212}Po investigating both the total fission probability and the 1st chance fission probability only. The lines represent calculations assuming that no fission occurs during a given transient time which is indicated in the figure.

tion energies, multi-chance fission sets in and 1st chance fission only accounts for $\sim 10\%$ of the total fission probability at the highest excitation energies investigated. It is interesting that 2nd chance fission becomes somewhat stronger than 1st chance fission around 100 MeV.

As pointed out before, the formalism used in Ref. [2] has been established for first chance fission only. In Fig. 2, we show the scaled fission excitation functions for both 1st chance and the total fission probability. Although there is a small difference between the two cases at high excitation energies, no significant deviations from the straight line are visible. Similar results have been obtained for the other ^3He and ^4He induced fission reactions. We thus conclude that the 1st chance fission probability scales as the transition state method predicts and that fission transient times must be shorter than 30 zs. It seems likely that that any excess pre-scission emission occurs during the descent from saddle to scission. If this is the case, then the present fission results are not in contradiction with recent measurements of pre-scission neutron and γ rays.

[1] ,* Th. Rubehn *et al.*, LBNL-39895 (1997).

[2] Th. Rubehn *et al.*, Phys. Rev. C 54, 3062 (1996) and this report.

[3] Th. Rubehn *et al.*, Nucl. Instr. Meth. A (in print); LBNL-39398; Los Alamos e-print nucl-ex/9609004; and this report.

Transition State Rates and Mass Asymmetric Fission Barriers of Compound Nuclei $^{90,94,98}\text{Mo}$

K. X. Jing, L. G. Moretto, A. C. Veeck, N. Colonna, I. Lhenry, K. Tso, K. Hanold, W. Skulski, Q. Sui and G. J. Wozniak
Nuclear Science Division, Lawrence Berkeley National Laboratory

The emission of complex fragments (or mass-asymmetric fission) can be treated in an analogous fashion to mass-symmetric fission by introducing the ridge line of conditional saddle points. Each mass or charge emission can be associated with a conditional saddle (or barrier) with the constraint of a fixed mass asymmetry. The locus of all such conditional saddles define the ridge line in the potential energy surface of a nucleus. This ridge line controls the emission of complex fragments, and can be measured with techniques similar to those used to determine fission barriers. In this work, we measured the excitation functions for complex fragments with atomic number $Z=5-25$ emitted from the compound nuclei $^{90,94,98}\text{Mo}$ produced in the reactions $^{78,82,86}\text{Kr} + ^{12}\text{C}$. Mass-asymmetric fission barriers (or the ridge line) for the compound nuclei ^{90}Mo , ^{94}Mo , and ^{98}Mo (see fig. 1) were extracted by fitting the measured excitation functions with a transition state formalism.




FIG. 1. The shell corrected mass-asymmetric fission barriers (B_Z) for compound nuclei ^{90}Mo , ^{94}Mo , and ^{98}Mo are compared with the Rotating Finite Range Model and the Rotating Liquid Drop Model calculations.

With the shell correction, the measured barriers are several MeV higher on average than the predictions of the Rotating Finite Range Model, and substantially lower than that predicted by the Rotating Liquid Drop Model. A stronger N/Z dependence of the experimental conditional barriers is observed than predicted by either model. These results suggest the need for refinements

of the parameters in both models, if not modifications of the models themselves.

As for the symmetric fission, the rate for mass-asymmetric fission has been calculated successfully by the means of the transition-state method. However, the claims for the failure of the transition state method to account for the observed precession particle emission (n , p , α , γ) prompted an attempt to justify the validity of the transition-state method and/or to identify regimes in which deviations might be expected. In this work we compared the experimental emission rates of complex fragments with the transition state predictions, and searched for E and Z dependent deviations that would indicate the existence of a transient effect which has been advocated as an explanation for the alleged large number of precession particle emission observed in the fission of many systems.

In fig. 2, we show that, over ninety excitation functions measured for complex fragments emission from five different nuclei (^{75}Br , ^{90}Mo , ^{94}Mo , ^{94}Mo , and $^{110,112}\text{In}$), can be scaled, as expected from the transition state theory, onto a single universal straight line which has a slope near unity and passes closely through zero. This is strong evidence for the validity of the transition state formalism and allows us to assign an upper limit for the transient time of 1×10^{-20} seconds.




FIG. 2. The logarithm of the reduced mass-asymmetric fission rate R_f divided by $2a_n^{1/2}$ versus the square root of the intrinsic excitation energy for five different compound nuclei. The solid lines are the linear fits to all of the data. The error bars are smaller than the size of symbols.

Characterization of nuclear physics targets using Rutherford backscattering*

Th. Rubehn, G.J. Wozniak, L. Phair, L.G. Moretto, and K. M. Yu
 Nuclear Science Division and Materials Science Division, Lawrence Berkeley National Laboratory

Many experiments in nuclear physics require targets with a precise characterization. In particular, information on quantities like the target thickness, the homogeneity, and the amount and kind of impurities are essential [1].

In a recent experiment performed at the 88-Inch Cyclotron of LBNL, we have investigated first chance fission of various polonium isotopes [2]. To do so, we have precisely measured fission excitation functions of the neighboring isotopes ^{209}Po , ^{210}Po , ^{211}Po , and ^{212}Po produced in the reactions ^3He and $^4\text{He} + ^{206,207,208}\text{Pb}$. To study the excitation energy dependence of the first chance fission probability, which is determined by subtracting similar cross sections of two neighboring isotopes, it is essential to measure the cumulative fission cross sections with high precision. While statistical errors can be minimized by measuring a sufficiently large number of fission events, systematic errors, as for example caused by uncertainties in the target thickness, are of particular concern.

We have used a Rutherford backscattering (RBS) spectrometer and particle induced x-ray emission for a precise off-line characterization of targets used in our experiments. Monoenergetic $^4\text{He}^+$ particles of 1.95 MeV energy generated by a 2.5 MeV van der Graaf accelerator have been utilized. Combining the measured energy and angle of the backscattered particles, the mass and energy of the projectile allows for the identification of the elementary constituents of the sample. The thickness of the sample can be derived from the energy loss, i.e., by determining the energy of the backscattered particles at both edges of the sample.




FIG. 1. RBS energy spectra for four lead targets. The different symbols correspond to different positions on the target (center, upper and lower edge).

In Fig. 1, we show the measured energy spectra from




FIG. 2. Target thickness determined by RBS as a function of position on the target surface for ^{207}Pb .

the RBS analysis for four lead targets. The thickness of the foils are deduced from the widths of the RBS spectra using the energy loss data of the ions in lead. The high energy edge reflects the front and the low energy edge the back of the sample. Small inhomogeneities in the target thickness can clearly be seen in the figure. In general, the spectral edges are sharply defined indicating well defined surfaces. A comparison with the thicknesses determined by direct weighing shows good agreement. In contrast to the RBS method, however, weighing only allows for an average thickness determination.

In Fig. 2, we show the thickness as a function of the distance from the center on the surface of the target. Measurements were made in 2 mm steps to determine the homogeneity. Within the central 8-10 mm, the thickness fluctuation is small. However, the sides are not symmetric. These features have been assigned to the production process. Since the beamspot in our experiment is smaller than 5 mm, the uncertainty in the target thickness is very small.

In order to determine whether any significant target impurities were present, we have furthermore measured particle induced x-ray emission simultaneously during the RBS experiments. This method relies on the spectrometry of characteristic x-rays emitted by the target atoms due to the irradiation with high energy ion beams. Various constituents can be identified via their characteristic x-rays. For the lead targets investigated here, no sizable contribution of contaminations other than a carbon backing, were seen.

[1], * Th. Rubehn *et al.*, Nucl. Instr. Meth. A (in print); LBNL-39398; Los Alamos e-print nucl-ex/9609004.

[2] Th. Rubehn *et al.*, this report.

LBNL 88-Inch Cyclotron Improvements*

C.M. Lyneis, Z.Q. Xie, D.J. Clark

The 88-Inch Cyclotron is now operating with beams of higher energy, greater intensity and variety, with more hours of beam on target and supporting a larger number of users than any time since it began operation in 1962. There are two major reasons for this.

First, the development of the ECR ion source by Geller et al¹ and its subsequent development have made it possible to produce a wide range of beams with intensities and energies well matched to the study of nuclear structure, nuclear reaction mechanisms and heavy element research. In addition the 88-Inch Cyclotron which began its operation as a light-ion cyclotron has maintained this capability, which provides research opportunities in new areas such as laser atom trapping for the study of weak interactions and fundamental symmetries.

The second reason is the development of a new generation of high energy resolution detectors such as Gammasphere and Eurogam which has opened up a new area of research in the study of highly deformed nuclei. Much of the research with these new detectors involves the formation of rapidly rotating compound nuclei. Production of the compound nuclei is typically done by using projectiles with $9 \leq A < 80$ with 4 to 6 MeV/nucleon. This research puts strong demands of the ion source capabilities both with respect to making beams from almost every element up to mass 80 and to produce beams economically from separated isotopes. Efficient use of separated isotopic feed material in the ECR sources has been developed. For example in FY94 more than 300 hours of research utilized ⁴⁸Ca beams with typical usage rate of about 25 μ g/hr of 40% enriched ⁴⁸Ca.

The 88-Inch Cyclotron is nominally a k140 cyclotron with three sectors and three external ion sources. The cyclotron RF frequency can be varied from 5.5 MHz to 16.2 MHz and both first

and 3rd harmonic beams are routinely accelerated. Minimum and maximum energies in first harmonic are 6.1 and 55 MeV/nucleon and in third harmonic 0.7 to 6 MeV/nucleon. Currently all beams being used by the research programs are produced by the two high charge state ECR ion sources located on the vault roof of the cyclotron, the LBL ECR ion source and the Advanced ECR




Fig. 1. This shows the energy mass curves for the cyclotron at an intensity of 1 particle nA. The dotted curve shows the projected performance with a new superconducting ECR ion source under development.

The evolution of the heavy-ion performance of the 88-Inch Cyclotron is illustrated in Fig. 1. These curves are drawn for beams of at least 1 particle nA extracted current. Higher intensity beams can be produced at energies less than those indicated by the curves. To date, the 88-Inch Cyclotron has produced beams of 41 elements, from hydrogen through zinc (the first 30 elements) as well as Ge, Kr, Ag, Sn, Xe, La, Sm, Tb, Au, Bi and U.

Footnotes and References

*Condensed from a paper in Proceedings of the 14th International Conference on Cyclotrons and their Applications, Cape Town, S.A., 1995, p173.

1. Geller, R., Appl. Phys. Lett. 16, No 10, 401 (1970).

Development of Exotic Nuclear Beams at the 88-Inch Cyclotron

D. M. Moltz, P. E. Haustein, J. Powell, E.B. Norman, M. W. Rowe, and Joseph Cerny

There has been great interest in recent years in the potential use of radioactive nuclear beams for the study of nuclear science. Experiments have been proposed in nuclear astrophysics, nuclear reactions, nuclear spectroscopy and properties of nuclei near the drip lines. Initial measurements in these areas have required the construction of many prototype first generation RNB facilities. Many second generation facilities are in the planning and construction phases. In principle, a high intensity radioactive beam facility is the highest nuclear physics priority in the U.S. behind the timely completion of RHIC and the Jefferson Laboratory. With the exception of MSU and RIKEN, all other major facilities under construction in the world are using the ISOL approach; this necessitates that most of the technical development in this field has concentrated on target-ion source issues. Although many laboratories have studied post accelerators, most construction projects to date have been limited to fairly low energies (< 5 MeV/nucleon). Unfortunately, almost all experimental ideas involving low-energy beams also require extremely high RNB intensities; this possibility is a long term goal, but hardly realistic for the earliest experiments. Many nuclear reaction experiments can be performed with very small beam currents, but they must have much higher energies (> 15 MeV/nucleon).

We are proposing to build a modest demonstration project whereby we can produce a few beams with energies up to 20 MeV/nucleon utilizing the 88-Inch Cyclotron as the secondary accelerator. The primary machine is a small medical cyclotron located about 300 m away from the 88". This small cyclotron produces proton beams at 10 MeV and 30 microamps intensity. The basic idea is to transport these radionuclides via a gas-jet system down to the 88" for injection into an ECR source. Once injected into the ECR source, a fraction of the injected radioactivity will be ionized directly into an appropriate charge state, extracted, and injected into the 88-Inch Cyclotron for final acceleration. For example, ^{11}C is made in copious yield in the $^{14}\text{N}(p,\alpha)$ reaction. It would be transported on organic based aerosols (heavy elements effectively poison the ECR ion source output of

lighter species), extracted as $^{11}\text{C}^{4+}$, and accelerated to a maximum energy of 18.5 MeV/nucleon. In order to perform nuclear reaction studies with this beam, routine operation will strip this beam to +6 to permit its magnetic separation from ^{11}B beam impurities; the cyclotron cannot separate ^{11}C and ^{11}B .

To date we have performed several tests to ascertain the viability of this approach. These tests have included measuring the ^{11}C yields transported through a 25 m capillary, comparisons of these results with transport through a 300 m capillary, and yield measurements on the simultaneous production of ^{14}O for possible use as a second radioactive beam. Results of the yield tests along with some sample efficiencies are given in Table 1. The transit time through the 300 m capillary was measured to be 69 s; there were no measurable losses of ^{11}C activity. We are currently constructing a system to couple a gas-jet to the ECR to measure the efficiency for a beam extracted as $^{11}\text{C}^{4+}$. This system should be operational in mid 1997.

#Visitor from Brookhaven National Lab.

Table 1. Yields and Efficiencies

Measured ^{11}C Yield (extrapolated from 1 mA)	9.0E08/s
Measured ^{14}O Yield (extrapolated from 1 mA)	4.8E07/s
Target Efficiency	50%
Transit Time	69 s
Skimmer Efficiency	50%
ECR Efficiency	1%
Cyclotron and Transport Eff.	30%
Proposed Initial ^{11}C Intensity	1.0E06/s

Performance of the upgraded LBL AECR Source *

Z.Q. Xie and C.M. Lyneis

The LBL AECR source has been upgraded (AECR-U, shown in Figure 1) in July 1996 by increasing its magnetic fields to improve the plasma confinement therefore to enhance the source performance. The new solenoid magnets have pancakes with larger hollow core copper conductor and thicker magnet iron return yokes. Iron plugs are also used to concentrate the field flux in the plasma chamber. With these improvements, the maximum peak axial magnetic field strengths increase from 1.0 to 1.7 Tesla at the injection and from 0.7 to 1.1 Tesla at the extraction region, respectively, with no increase in ac power. A new set of NdFeB permanent sextupole magnet with a nominal magnetic remanence B_r of 1.3 Tesla was installed in the aluminum plasma chamber to raise the maximum radial field strength. To ensure sufficient cooling, the permanent sextupole magnet bars are enclosed in 0.25 mm thick watertight stainless steel cans and are directly water cooled. The maximum sextupole field strength at the chamber inner surface is 0.85 Tesla.

After a few months of tailoring the magnetic field configuration to match the incoming microwaves of 14 and 10 GHz (two-frequency plasma heating), the AECR-U source with its higher magnetic fields and increased magnetic mirror ratios has demonstrated significantly enhanced performance. So far the AECR source has produced many record beam intensities and high charge state heavy ions from an ECR source. For heavy ions at intensity of about 1 μA , the charge state was shifted from 42+ to 48+ for the heaviest natural element--uranium and from 41+ to 46+ for bismuth. An order of magnitude enhancement for fully stripped argon ions ($I \geq 60 \text{ enA}$) also has been achieved. For elements of mass from 40 to 86 and intermediate charge state, i.e., mass to charge ratios of 4 to 5, intensities of 100 to 300 μA were also produced.

These ion beams will be used for the BGS detector under construction at the 88-Inch Cyclotron. High charge state ion beams of xenon-136 and uranium-238 produced by the source were injected into the 88-Inch Cyclotron. After acceleration to energies greater than 10 MeV/nucleon for xenon-136 and 6 MeV/nucleon for uranium, the extracted beam intensities from the cyclotron are 1×10^7 pps for xenon 41+ and a few hundreds pps of xenon 46+. In the identification of the high charge state uranium ions, the transmission was less than 0.01% for these highly-charged ions due to the poor vacuum in the cyclotron. Nevertheless, charge states up to 60+ uranium ions were confirmed with a crystal detector. Uranium 60+ at a few pps with a total energy of 1.935 GeV, the highest beam energy ever produced by the 88-inch cyclotron, was measured.

Footnotes and References

*Condensed from a paper to be presented at the 13th International Workshop on ECR Ion Sources, College Station, Texas, February 1997.

*




Fig. 1. A cross-section view of the upgraded AECR (AECR-U) ion source.

Production of intense high charge state ions with an aluminum liner in the Advanced Electron Cyclotron Resonance Ion Source *

Z.Q. Xie and C.M. Lyneis

The basic physics of an electron cyclotron resonance (ECR) ion source involves coupling microwave energy to plasma electrons confined by a magnetic bottle which then produce singly or multiply charged ions by electron impact ionization. The neutrals and ions are mainly stepwise ionized by electron impact ionization and the ionization process provides the primary electrons to compensate the escaped electrons to maintain a dynamic equilibrium plasma in which the plasma loss is electrically neutral. Early experiments on ECR sources demonstrated that adding extra electrons to the ECR plasma with a microwave-driven first stage or by using electrons emitted from the plasma chamber walls coated with materials of high secondary electron emission can substantially enhance the production of high charge state ions. Since the AECR source was built, we have explored various techniques to provide more electrons for the plasma. The early methods used, such as coating the plasma chamber walls with SiO₂ or Al₂O₃ and using an electron gun to axially injecting electrons to the plasma, substantially enhanced the performance of the AECR source.^{1,2,3}

Enhanced production of high charge state ions due to the aluminum oxide wall coating has been demonstrated in various ECR sources. Empirically speaking, a good chamber surface should have high secondary electron emission, long lifetime in against plasma etching and low material sticking coefficients to minimize the surface memory. Aluminum oxide not only has high secondary emission but it is also very resistant to plasma etching. The previous aluminum oxide coating, done by running an aluminum plasma, did not entirely cover all the chamber copper surfaces in the AECR source and only had about one month lifetime. In this test, a 0.38 mm thick aluminum liner was installed in

the copper plasma chamber. The tests with this aluminum liner and two-frequency heating produced an increase of up to 60% in beam intensity of the high charge state ions was achieved. Shown in Table I are the measured beam intensities for a few example elements.

Footnotes and References

*Condensed from Proc. 6th International Conference on Ion Sources, Whistler, BC, Canada, 1995.

¹Z. Q. Xie and C. M. Lyneis, Rev. Sci. Instrum. **65**, 2947 (1994).

²Z. Q. Xie, C. M. Lyneis, R. S. Lam, and S. A. Lundgren, Rev. Sci. Instrum. **62**, 775 (1991).

³T. Nakagawa, T. Kageyama, M. Kase, A. Goto and Y. Yano, Jpn. J. Appl. Phys. **32**, 1335 (1993).

Table I. Ion beams produced from the AECR source with an aluminum chamber liner

Q	I (eμA)	Q	I (eμA)
16O ⁶⁺	510	197Au ²⁴⁺	41.7
16O ⁷⁺	210	197Au ²⁶⁺	34
40Ar ¹¹⁺	238	197Au ²⁹⁺	20
40Ar ¹²⁺	158	197Au ³⁰⁺	14.3
40Ar ¹³⁺	84	197Au ³¹⁺	10
40Ar ¹⁴⁺	47.5	197Au ³²⁺	6.6
40Ar ¹⁶⁺	4.7	197Au ³⁴⁺	3.5
209Bi ²⁸⁺	33	197Au ³⁵⁺	2.4
209Bi ³¹⁺	26	197Au ³⁶⁺	1.3
209Bi ³⁴⁺	14	197Au ³⁸⁺	0.4
209Bi ³⁶⁺	6.6		

All ion beams are extracted at 10 or 15 kV extraction voltage and through an 8 mm aperture.

A Microtron Cyclotron - the Slipatron*

D. J. Clark**

The motivation for this "microtron cyclotron" or "slipatron" design arises from the idea that a more compact cyclotron type magnet might be built, using the usual sector cyclotron fields for focusing but having a strongly increasing radial gradient in the field, as in FFAG design, to compact the orbits. This deviation from the isochronous field causes the ion frequency to increase with energy. To obtain high intensity we must use constant rf frequency and an integral number of rf cycles per turn, which is the microtron mode of acceleration. The harmonic number (rf freq/ion freq) then must decrease with energy gain. To allow a sufficient number of turns a high starting harmonic number of 50-100 is used, so that it can be decreased each turn during acceleration. A high energy gain per turn is required and can be accomplished with multiple dees. Unlike a microtron cavity, the dees have to extend over the radial aperture. The change of period during acceleration can be matched by changing the angular width of the dees with radius. Phase stability exists because the ion frequency depends upon radius.

A layout of an optimized design is shown in Figure 1. A four sector structure is chosen to give two valleys for rf and space for injection and extraction. The magnet and rf systems are drawn to scale. This design is for a proton accelerator with injection at 2 MeV and extraction at 30 MeV. The harmonic is 100 at injection and 54 at extraction. Average radius at extraction is .84 meter. The field gradient is obtained by tapering the hill gap, with constant hill angular width. The peak field on the hills at the edge is 19 kG. The axial focusing was calculated using the simple hard edge approximation with valley field assumed zero. The high flutter is adequate to compensate the rising average field and give Nuz of .3 or more, using some spiral at the edge. The rf system has 10 gaps in each of 2 valleys. The rf frequency is 770 MHz. The energy gain per turn is programmed from the center to the edge by dee shaping to give .2 MeV/turn at the center and 3.2 MeV/turn, or 160

keV/gap, at the edge. The injection and extraction are shown schematically. The turn separation is 1.1 cm at injection and 1.7 cm at extraction. A figure of merit, F , for this type of accelerator is its radial aperture compared to that of a standard cyclotron of the same energy. $F = .7$ for this optimized design.

An advantage of this design over that of a cyclotron with the same magnetic fields at extraction is that the magnet can be more compact. But the disadvantages are the greater complication of the dee system and the need for an injector. Perhaps other variations of this design can be developed.




Figure 1: Optimized design layout

Footnotes and References

*Condensed from Proc. 14th International Conference on Cyclotrons and their Applications, Capetown, South Africa, Oct. 8-13, 1995, p. 618.

**Lawrence Berkeley National Laboratory

Non-Nuclear Science Programs at the 88-Inch Cyclotron: Part A. Space Applications*

M.A. McMahan

The 88-Inch Cyclotron runs about 20% of the time for non-nuclear science fields, including high-energy physics, radiobiology, materials, and space applications. The largest part, space applications, consists of two parts: radiation-induced effects in microelectronics and calibration of detectors for NASA missions.

Radiation Induced Effects

Recent demands by both the Defense Department and the communications industry for cost, flexibility, and speed of getting new satellites into space, have led to an increased use of commercial off-the-shelf (COTS) parts. These parts must be ground tested before committing them to an expensive space mission. Ground-based testing is done at accelerators and with radioactive sources. Accelerators in the USA, Europe, and Japan now provide radiation effects test facilities for heavy ions, protons, or electrons. At the 88-Inch Cyclotron, the bulk of non-nuclear science time ($\approx 15\%$) goes to space effects studies for a wide variety of companies and laboratories, on a cost-recovery basis.

Several types of "single event effects (SEEs)" have been identified, ranging from a simple flip of a bit, as in an upset, to more catastrophic effects such as latch-ups or burn-outs, which destroy the part.

Models of these effects begin with an initial charge distribution or current source positioned along the track of an energetic ion. The sensitivity of a device to a particular type of SEE is expressed in terms of the cross section as a function of LET, which gives a characteristic curve with two key parameters: the threshold, L_{th} , for onset of the SEE, and the cross section at saturation, σ_{sat} . The saturation cross-section is related to the total area of the sensitive regions of the component, and the threshold LET is a

measure of the critical, or minimum, charge required to trigger the event.

The 88-Inch Cyclotron has features which make it ideal for SEE studies. The Cyclotron runs both heavy-ions and protons, enabling both kinds of measurements to be done at the same facility. Also, the combination of ECR (Electron Cyclotron Resonance) source and cyclotron makes possible the development of "cocktail" beams[‡], which allow the ion species, and thus LET, to be changed very quickly. In addition, with bismuth beams, LETs as high as 100 MeV/mg/cm² can be reached.

These studies require accurate measurements of energy, fluence, and spatial uniformity. Energy measurements are performed with silicon detectors, and dose and uniformity obtained with various types of scintillators or ion chambers.

Detector Calibrations

Another use of the 88" Cyclotron is for ground-based calibrations and tests of detector packages being prepared for future space launches. NASA's Advanced Composition Explorer (ACE) satellite, scheduled for launch in 1997, will investigate a wide range of fundamental problems in i) the elemental and isotopic composition of matter, ii) origin of the elements and subsequent evolutionary processing, iii) formation of the solar corona and acceleration of the solar wind, and iv) particle acceleration and transport in nature. Two of the nine instruments being designed for this mission have been tested and calibrated at the 88-Inch Cyclotron.

Footnotes and References

*Condensed from Proceedings of the International Symposium on Large-Scale Collective Motion of Atomic Nuclei, Brolo, IT, October 1996, to be published.

‡ M.A. McMahan, et al., Nucl. Instr. Meth. **A253**, 1 (1986).

Non-Nuclear Science Programs at the 88-Inch Cyclotron: Part B. Biology, Physics, and New Technologies *

M.A. McMahan

Small amounts of beam time at the 88-Inch Cyclotron are dedicated to non-nuclear science programs in radiation biology, high-energy physics, and materials.

Radiobiology

With the closure of the Bevalac in 1993, part of the Life Science Division's work in radiobiology moved to the Cyclotron. A beamline was developed for light ions tuned with uniformities of $\pm 10\%$ over diameters of 10 cm. Dose, flux, and uniformity are measured with a segmented ion chamber.

Radiation biologists study the effect of radiation on living tissue from microscopic systems (DNA strands) through macroscopic ones (cataract studies).

One of several radiation biology studies being pursued at the 88-Inch Cyclotron has already made discoveries which may change future textbooks on structural biology. By studying the size distribution of DNA fragments after passage of heavy ions through a cell[†], shown in Figure 1, and comparing these with Monte Carlo calculations[‡], one can differentiate between various models for the structure of the DNA inside the nucleus. These studies show that the generally accepted model is most likely not correct.

High Energy Physics

The irradiation station and diagnostics developed for the biology program have proven to be of direct use to members of the Physics Division involved with the Atlas Detector being designed for the LHC at CERN. Protons from the 88-Inch Cyclotron are used to perform radiation damage studies on silicon diodes being considered for use in Atlas.

Materials Studies

The discovery of "nuclear tracking" in the late 1950's led to a new class of nuclear physics detectors as well as a wide range of practical applications. Variations of the nuclear tracking technique have been pursued at the Cyclotron, for example, in the i) calibration of nuclear track detectors for physics experiments, ii) exploration of new techniques to make micropore filters, and iii) development of flat screen displays for lap-top computers. These kinds of studies require the ability to accelerator a variety of heavy, low-energy beams with good uniformity. A scintillating fiber/CCD detector is under development for tuning and dosimetry of these beams.

Footnotes and References

* Condensed from Proceedings of the International Symposium on Large-Scale Collective Motion of Atomic Nuclei, Brolo, IT, October 1996, to be published.

†Bjorn Rydberg, Rad. Res. **145**, 200 (1996).

‡W.R. Holley and A. Chatterjee, Rad. Res. **145**, 188 (1996).





Fig. 1. Experimental distribution of DNA fragments after bombardment by 32.5 MeV/u N ions.



Institute for Nuclear and Particle Astrophysics

Sudbury Neutrino Observatory - PMT Support Structure & Panel Arrays

K.T. Lesko, Y.D. Chan, M. Dragowsky, M. Isaac, M.E. Moorhead†, E.B. Norman, A. Schuelke‡, and R.G. Stokstad

The Sudbury Neutrino Observatory detector is a large heavy water Čerenkov detector designed to detect neutrinos in a 1000 tonne D₂O target[1]. The detector has sensitivity to the total neutrino flux, ν_x , independent of neutrino family ($x = e, \mu, \tau$) and to the ν_e flux, separately, by measuring charged and neutral current reactions and neutrino-electron elastic scattering. The detector is located 2 km below ground near Sudbury, Ontario Canada in an active nickel mine operated by INCO, Ltd. The D₂O target is contained in a thin-wall acrylic vessel (AV) of 6 m radius, which is suspended in a 11 m radius cavity filled with ~7800 tons of ultrapure water. The D₂O and the surrounding 1m shell of H₂O are viewed by an array of 9456 8" Hamamatsu PMTs. Each PMT is coupled to a light concentrator[2] within a plastic hexagonal structure. The hexagons are assembled into 751 flat panel arrays each holding from 7 to 21 PMTs. The panel arrays are suspended on the 9 m radius stainless steel geodesic sphere (PSUP). This sphere is concentric with the acrylic vessel and is also suspended from the deck structure near the top of the cavity. The PSUP and the panel arrays were designed and fabricated by our group at LBNL.

The PSUP is based on a three-frequency icosahedron sphere. The ~14,000 kg structure is capable of supporting a load of nearly 90,000 kg. All materials used in the fabrication of the geodesic sphere were carefully selected to contain < 15 ppb U or Th. All parts were cleaned and double bagged for installation in SNO's Class 2000 environment. In addition to the low level of permissible U and Th contamination, mine access and construction concerns heavily influenced our design. The final design consists of 270 struts, 91 nodes, a chimney ring and guide ring to permit the AV's chimney and suspension ropes to penetrate the PSUP and six ports for

calibration devices. The upper half of the geodesic structure was installed underground in January and February, 1995.

The PMT panel arrays are fixed to the geodesic structure struts with adjustable and responsive mounts. These permit the panels to adjust to the flexing of the geodesic sphere the cavity if filled with water. The entire array changes from a net weight of 90,000 kg to becoming slightly buoyant (-2500 kg) due to the large displacement of the PMTs which necessitates the deployment of anchors at the bottom of the cavity. The PSUP struts will flex by .64 cm due to this change in weight. The panel mounts permit an accurate (<0.3°) alignment of the panels so that each PMT-reflector views the D₂O. The reflector-PMT coupling in the hexagons creates a nearly water-tight and light-tight seal with only small engineered leakages to permit water and air to escape during filling and water purification. Each panel is sealed to neighboring panels using thin opaque plastic membranes. All materials used in the fabrication of the panels, except the PMTs, were selected to contain <15 ppb U and Th and were packaged under cleanroom conditions. The upper half of the geodesic sphere was instrumented with PMTs (390 panels, 5000 PMTs) between April and August, 1995. The final installation will be completed in 1997.

Footnotes and References

† Present address, Oxford University, Oxford, UK OX13RH

‡Die Arbeit wurde mit Unterstützung eines Stipendiums im Rahmen des Gemeinsamen Hochschulsonderprogramms III von Bund und Ländern über den DAAD ermöglicht.

1. G. Ewan, *et al.* Sudbury Neutrino Observatory Proposal, SNO 87-12 (1987).

2. G. Doucas, *et al.* NIM A370, (1996) 579-96.

^6Li Neutron Poison for SNO

M. E. Moorhead*, Y. D. Chan, M. Dragowsky, M. C. Isaac, R. M. Larimer, K. T. Lesko, E. B. Norman, A. Schuelke‡, R. G. Stokstad

There are two independent possible signatures of neutrino oscillations in SNO: i) a NC/CC (neutral current/charged current) ratio greater than unity, and ii) a distortion of the ^8B CC spectrum. If oscillations are occurring, it is most probable that both of these signatures will manifest themselves. However, there are some scenarios where only one of these signatures is present, e.g. in the case of oscillations into "sterile" neutrinos, the NC/CC ratio will be unity, whereas the CC distortions should still occur. In any case, it is always preferable to investigate a new phenomenon through as many channels as possible.

The motivation for introducing ^6Li into the heavy water of SNO is to enhance the detector's ability to measure CC distortions. For the experimentally favored "non-adiabatic" MSW solution¹ these distortions correspond to a suppression in the 5-7 MeV part of the spectrum, where complications arise from neutron capture on deuterium ($Q = 6.25$ MeV). To remove this complication and measure a clean CC spectrum, it is proposed to introduce 300 kg of LiNO_3 salt (enriched to 95% ^6Li) into the D_2O . The ^6Li will absorb neutrons without emitting γ rays and reduce the deuterium neutron capture efficiency down to 1% as compared to 27% in pure D_2O .

It has previously been shown² that the complication arising from the deuterium neutron-capture gamma peak in pure D_2O reduces the significance of the non-adiabatic MSW CC distortion to a negligible level (a 1σ effect in one year's data). In contrast, by adding a poison such as ^6Li , the statistical significance of the CC distortion is greatly enhanced and one can exclude the null hypothesis (no distortion) at the 99.9% confidence level (one year's data).

Enriched lithium nitrate or sulfate (0.3 tonnes) have been chosen as the most suitable chemical forms for introducing a neutron poison into the

heavy water because they are very similar to the magnesium chloride salt (2 tonnes), which has already been developed as a neutral current additive. Thus, the reverse osmosis technology already installed by SNO for removing the magnesium chloride from the D_2O can be used for the lithium nitrate or sulfate. This has been demonstrated, in small scale laboratory tests, by A. Kumar and K. Lamb³ of NRC Canada at our request. In addition, small scale tests carried out at LBNL have shown that the technique of seeded ultrafiltration for purifying magnesium chloride worked equally well for lithium nitrate solutions⁴.

The ^6Li , in the chemical form of $\text{LiOH}\cdot\text{H}_2\text{O}$, is supplied by Oak Ridge National laboratory and a 1 kg sample was purchased and analyzed for chemical and radioactive contamination. A chemical procedure has been established for converting the $\text{LiOH}\cdot\text{H}_2\text{O}$ into LiNO_3 and, at the same time, removing the Th and U chain contaminants. This procedure has been successfully carried out at the 1 kg scale using the material from Oak Ridge. Our objective is to produce the 300 kilograms of purified LiNO_3 or Li_2SO_4 by the end of 1997 so that it is ready soon after the detector is filled with D_2O .

Footnotes and References

*Present address: Oxford University

‡Die Arbeit wurde mit Unterstützung eines Stipendiums im Rahmen des Gemeinsamen Hochschulsonderprogramms III von Bund und Ländern über den DAAD ermöglicht.

1. N. Hata, S. Bludman, P. Langaker, Phys. Rev. D **49**, 3622 (1994).
2. B. Frati, SNO internal report.
3. A. Kumar and K. Lamb, NRC No. ER-1356-95S.
4. A. R. Smith, D. L. Hurley, R. J. McDonald, LBL internal report.

A 4π β -tagged Decay Chamber for Gaseous SNO Calibration Sources

Y.D. Chan, M. Dragowsky, M.C. Isaac, K.T. Lesko, M.E. Moorhead*, E.B.

Norman, A. Schuelke† and R.G. Stokstad

In the Sudbury Neutrino Observatory detector, Cerenkov photons, generated by the fast moving electrons in the final states of the charged current ($\nu_e + d \rightarrow p + p + e$) and elastic scattering ($\nu + e \rightarrow \nu + e$) interactions, are detected by about 10,000 inward-looking phototubes mounted on a geodesic sphere. The energy of the incoming neutrino is related to the number of fired phototubes (NHIT) in an event.

One important calibration is to establish an absolute energy scale for the NHIT spectrum. This is achieved by deploying calibration devices into the D_2O volume. Among the planned calibration schemes is a gaseous calibration system, comprised of a shielded underground d-t neutron generator, a capillary transport line, and an active decay chamber. The decay chamber consists of a cylindrical gas-holding volume made of 3 mm thick plastic scintillator sheets, enclosed in a water-tight stainless pressure vessel. Short-lived gamma (^{16}N) and neutron (^{17}N) sources are made by neutron-activating ^{16}O and ^{17}O gases. The beta particle accompanying the decay is detected by the scintillator to provide an effective tagging signal.




Fig. 1. Schematics of the experimental set up.

A highly successful test of the SNO d-t neutron generator, gas transport system, and decay chamber was carried out in the summer of 1996 at Chalk River Laboratory (Fig.1). The neutron

generator produced approximately 10^8 14-MeV neutrons per second which irradiated a target cell through which oxygen gas flowed. Through the $^{16}O(n,p)$ reaction, ^{16}N was produced and transported through a thin capillary to the decay chamber. There the betas and 6.13 MeV gamma rays, produced by the decay of ^{16}N , were detected in the plastic scintillator walls of the decay chamber and in a large NaI detector, respectively (Fig. 2). By comparing the singles counting rate of 6.1 MeV gamma rays in the NaI detector to the rate of decay chamber-NaI coincidences, we determined that the efficiency of the decay chamber for detecting the betas from ^{16}N decay is approximately 95%. Thus this system provides a clean source of tagged 6.1 MeV gamma rays that will be used to provide an energy calibration for the SNO detector.




Fig. 2. Raw ^{16}N decay spectrum.

Footnotes and References

* Present address : Oxford University, Oxford, UK.

† Die Arbeit wurde mit Unterstützung eines Stipendiums im Rahmen des Gemeinsamen Hochschulsonderprogramms III von Bund und Ländern über den DAAD ermöglicht.

Sudbury Neutrino Observatory, Neutral Current Detectors

K.T. Lesko, Y.D. Chan, M. Dragowsky, M. Isaac, M.E. Moorhead†, E.B. Norman, A. Schuelke‡, and
R.G. Stokstad

With SNO's ability to observe both the Neutral Current (NC) and Charged Current (CC) reaction rates we are able to deduce the existence of neutrino oscillations with two distinct signatures. The first signature is obtained by a measurement of the CC/NC ratio. The second method is based on observing deviations in the predicted shape of the CC spectrum.

SNO is developing two techniques to observe the neutrons liberated by the NC reaction: $\nu_x + D \Rightarrow p + n + \nu_x$, $Q = -2.2$ MeV. The first technique uses the addition of a salt to the D_2O , which captures the neutrons and generates γ -rays that are subsequently observed through their Compton scattering and associated Cerenkov light. The salt selected by SNO is MgCl. The second technique uses an array of ~ 100 3He proportional detectors[1]. The neutrons are detected via the $^3He(n, p+t)$ reaction. SNO anticipates using both techniques to reduce the affects of the different systematic errors associated with each technique.

The groups at the University of Washington, Los Alamos National Laboratory, and Lawrence Berkeley National Laboratory have received funds from the Department of Energy to develop the array of 3He proportional counters, or "NCDs". The past year much work as gone into developing and producing the nickel tube detector bodies with low levels of uranium and thorium contamination (~ 1 ppt U has been achieved). The technology required for the production of the counters has advanced to the point where prototype counters were produced at the end of 1996.

Our group has applied our experience in engineering, contamination control, and low level counting to assist with the production of the

counters. In particular we have drafted cleanliness procedures for the production of the counters, assisted in the selection and production of various NCD components, drafted quality assurance plans for the NCDs, and coordinated much of the low level counting performed at the Oroville facility. We designed, fabricated, and installed the underground facility in the SNO control room for the long-term storage of the detectors while the ^{56}Co decays and the detectors are operated to determine their contamination levels and operational characteristics.

Nickel in the array is activated by cosmic rays and ^{56}Co is produced. This activity adds a significant contribution to the NC backgrounds (γ -rays > 2.2 MeV) unless i) steps are taken to minimize the exposure of the components to cosmic rays and ii) the finished counters have a "cool-down" period (~ 6 months) during which ^{56}Co will decay ($\tau_{1/2} = 77.27$ day).

We have begun simulations of the NCDs in SNO and are pursuing studies of *in situ* measurements of the NCD backgrounds using a neutron poison.

Footnotes and References

† Present address, Oxford University, Oxford, UK OX13RH

‡Die Arbeit wurde mit Unterstützung eines Stipendiums im Rahmen des Gemeinsamen Hochschulsonderprogramms III von Bund und Ländern über den DAAD ermöglicht.

1. Neutral-Current Detection in the Sudbury Neutrino Observatory, Proposal to the Department of Energy FIN-94-ER-E-324, January 31, 1992, T. Bowles, *et al.*

Sudbury Neutrino Observatory - Contamination Control

R.G. Stokstad, K.T. Lesko, Y.D. Chan, M. Dragowsky, M. Isaac, E. Norman and A Schuelket

Twelve thousand square meters of surface area will be in the SNO cavity when construction is complete. Dust left on these surfaces may emanate radon and therefore contaminate regions of the detector well removed from the source material. Mine dust (6 ppm Th) is the main problem, but any granular material containing U and Th are problematic. Our goal is to reduce surface contamination to acceptable levels, which are derived by requiring that they be less than the unavoidable contributions from the bulk materials comprising the detector. Earlier articles¹ have described the cleanliness infrastructure in the SNO laboratory. During the last two years, experience has been gained through cleanliness monitoring and further measures have been implemented.

The rate at which mine dust settles on surfaces is inferred from measurements of iron, a 7% constituent of mine dust. These measurements are made using X-Ray Fluorescence Analysis (XRF). A monitoring program extending over several years has shown that the rate of mine dust deposition is typically between 1 and 3 $\mu\text{g}/\text{cm}^2/\text{mo}$. Since the construction period is longer, and the above deposition rates are higher than anticipated years ago, additional cleanliness measures are warranted. The solution to this problem has been the introduction of dust covers. Critical components such as the surfaces of the acrylic vessel (AV) are covered with tarpaulins just after being cleaned for the last time. The covers are designed for removal much later in the construction period. Ropes and fastening mechanisms are installed such that the covers can be pulled off from a remote location. (Tests have been made to verify that airborne dust deposited on the covers sticks.) Light/dust covers for the photomultiplier tubes (PMT) were designed, fabricated, and installed before the

PMT panels were put in place on their support structure. Since the PSUP was installed, covers have been placed on top of the upper PSUP (i.e., on the back sides of the PMTs), which will be removed just before the water fill commences.

Procedures for the cleaning of the acrylic surfaces and for measuring the level of cleanliness were developed and recently implemented. The complete procedure involved many steps, but the basic cleaning agent was a dilute solution of Alconox. The level of contamination before and after cleaning was measured by applying a special (low in Fe) adhesive tape to the surface and then analyzing the tape in the XRF spectrometer. By applying the same piece of tape repeatedly to adjacent areas on the surface, the sensitivity of the technique could be increased by a factor of five. It was clear that the cleaning procedure was effective in removing surface contamination containing the elements Fe and Zn. (The Zn is believed to come from the galvanized scaffolding used in construction.) After cleaning, the residual mine dust (again, inferred from the amount of Fe) was well below the 0.1 $\mu\text{g}/\text{cm}^2$ value set as a tolerable upper limit for the AV. The sensitivity of the method is 0.025 $\mu\text{g}/\text{cm}^2$ of mine dust (1σ).

The upper hemisphere of the AV is now cleaned and covered.

Footnotes and References

††Die Arbeit wurde mit Unterstützung eines Stipendiums im Rahmen des Gemeinsamen Hochschulsonder-programms III von Bund and Ländern über den DAAD ermöglicht.

1. NSD Annual Reports: 1991, p.81; 1992, p.87; 1994, p. 101.

Sudbury Neutrino Observatory, Monte-Carlo Simulations and Data Analysis

M.E. Moorhead†, Y.D. Chan, M. Dragowsky, M. Isaac, K.T. Lesko, E.B. Norman, A. Schuelke‡, and
R.G. Stokstad

SNOMAN is the principal the Monte-Carlo simulation and data analysis program for the Sudbury Neutrino Observatory (SNO). The code is being developed by the many of the institutions participating in SNO. The LBNL group plays a major role in the development of this 110,000 line code and this effort has increased as our hardware responsibilities have been met.

One significant LBNL contribution to SNOMAN has been the graphical display package. During the past year we developed a user interface for SNOMAN using the Windows Motif package. The user interface will also help in the comparisons between different SNOMAN runs at different institutions, since it records all the run-dependent input parameters in a standard format.

Other LBNL contributions to SNOMAN have been made in photon transport, neutron code verification, detector geometry, input parameters for radioactive decay schemes and reaction cross-sections, and the generation, propagation and detection of high energy γ rays. The goals of these contributions have been to provide accurate and detailed treatments of i) backgrounds from radioactivity in the photomultiplier support structure and other components, ii) calibration sources, in particular the ^{16}N , ^{17}N calibration sources which are being developed at LBNL, and iii) backgrounds generated from the cavity walls.

On the data analysis side several event fitters [1] are being developed using neural network, maximum likelihood and other techniques. The aim of these fitters is to reconstruct event position and direction as well as to provide some particle identification capabilities.

An analysis of MSW distortions of the charge current spectrum was made. It is clear that the

experimentally favored 'small-angle MSW, or nonadiabatic' solution to the solar neutrino problem produces a measurable distortion of the charge current spectrum[2]. However, this distortion occurs mostly at low energies where it is obscured by n-capture events on deuterium. To remedy this problem we propose to introduce 30 Kg of ^6Li (in the form of lithium carbonate) into the D_2O in order to capture >99% of the free neutrons on ^6Li and reduce the rate of capture on deuterium by a factor >25 [3].

A 2 m diameter test detector was built in Seattle with 128 PMTs. The mini-SNO detector is used to test the electronics and DAQ system and also to exercise the MC simulation and analysis chain with real events from calibration sources which will be used in SNO[4].

Footnotes and References

† Present address, Oxford University, Oxford, UK OX13RH

‡Die Arbeit wurde mit Unterstützung eines Stipendiums im Rahmen des Gemeinsamen Hochschulonderprogramms III von Bund and Ländern über den DAAD ermöglicht.

1. SNO-STR-95-042 Grid fitter for reducing tails in spatial distributions M.E. Moorhead and LBL-33634 Neural Network for Recognizing Cerenkov Radiation Patterns Dawei W. Dong, Y.D. Chan, M.T.F. da Cruz, A. Garcia, R.M. Larimer, K.T. Lesko, E.B. Norman, R.G. Stokstad, F.E. Wietfeldt, and I. Zlimer.

2. See also Bahcall, Krastev, Lisi IASSNS-AST 96/43

3. SNO-STR-95-056 Li-6 neutron poison for SNO M.E. Moorhead

4. SNO-STR-95-041 Mini-SNO geometry M.E. Moorhead, M.Isaac and K.T. Lesko

The Sudbury Neutrino Observatory: Monitoring the Experiment

Y.D. Chan, M.C. Isaac, M. Dragowsky, K.T. Lesko, E.B. Norman, A. Schuelke[†] and R.G. Stokstad

Unlike most accelerator-based experiments, the Sudbury Neutrino Observatory (SNO) will be operated 24-hours a day for a planned duration of 5 - 10 years. It is, therefore, essential to develop a flexible and reliable data monitoring program to provide up-to-date information about the status of the experiment, for SNO participants both on-site or off-site.




Fig. 1. SNO monitoring object CM_PSUP.

The scope of SNO monitoring covers two areas : (1) the past and present status of the detector/cavity hardware, and (2) the status of data acquisition (DAQ). There are two classes of tasks for DAQ monitoring. The Low-Level tasks are performed by PowerPC CPUs located underground inside the SNO cavity. These desktop computers control the DAQ task and initialize the operation of the ~20 embedded CPU's in the SNO Crates. The main tasks are component monitoring, diagnostics, conditional alert, and supernovae watch. An object-oriented SNO DAQ C++ Framework has been developed over the years by the SNO DAQ group. In particular, a SNOObject class forms the basis of all monitoring objects. All modules can be pre-

configured or set up dynamically during run time. Fig.1 shows an example of a detector geometry access object connected to a data source.

The High-Level monitoring tasks are performed on UNIX workstations situated in the SNO surface building. The main tasks performed here include acquisition statistics, long term stability evaluation, as well as first-pass event fitting and histogram analysis. In compliance with coding standards within the SNO collaboration, a stand-alone monitoring program, SNOMON, has been developed to include features from both the official SNO Monte Carlo code, SNOMAN, and tools from the versatile CERNLIB application, PAW++. Streams of native DAQ data are filtered into CERNLIB/ZEBRA format before they being processed by SNOMON. Fig. 2 shows the familiar PAW++-like user environment for SNOMON.

The surface workstations also serve as hosts for off-site monitoring. Techniques and tools from the WWW community, including Java-based dynamic content update and event browsers, are employed.




Fig. 2. SNO monitoring program SNOMON.

Footnotes and References

^{††}Die Arbeit wurde mit Unterstützung eines Stipendiums im Rahmen des Gemeinsamen Hochschulsonder-programms III von Bund and Ländern über den DAAD ermöglicht.

Response of the SNO Detector to High Energy Gamma-Rays

M. C. Perillo Isaac, Y.D. Chan, M. Dragowsky, D. Hurley, K. T. Lesko, R. J. McDonald, M. E. Moorhead*, E. B. Norman, A. Schuelke† A. R. Smith and R. G. Stokstad

A two step Monte-Carlo procedure was done in order to quantify the response of the SNO detector to high energy gamma rays produced by (α, γ) , $(\alpha, n\gamma)$ and $(\alpha, p\gamma)$ reactions induced by natural radioactivity in the rock and coating of the SNO cavity. In a first step, we used GEANT 3.21¹ to model the SNO cavity and to track gamma rays and the subsequent electromagnetic radiation from the surface of the cavity up to a spherical surface of 18 m of diameter. The particle type, position and momentum are then recorded and used as input for SNOMAN², the dedicated SNO Monte-Carlo code.

The GEANT 3.21 simulation generates gamma-rays uniformly in the cavity walls in all directions in 1 MeV bins from 3 to 12 MeV. Two models were studied: cavity filled with water and cavity empty (air).

As a visual aid, figure 1 shows the projection in the ZX plane of events generated in the cavity walls superimposed with the projection of the events which survive the water shield, i.e., penetrate the region of the photomultiplier support structure.

For the purpose of this study we set standard conditions to the event trigger and data filter, requiring that at least 10 photomultipliers fire and that the events pass the standard SNO event reconstruction program, the FTT fitter.

The results are exemplified in figure 2 where we plot the response of the SNO detector, when filled with water, to gamma-rays originated in the cavity walls with energy between 7 and 8 MeV

8 MeV. This response considers the events which were reconstructed inside the heavy water volume only.

The results of this study are combined with the experimental values obtained from the measurement of the high energy gamma-ray flux in the SNO cavity in order to evaluate the contribution of this background to the experiment.




Figure 1: Projection of the GEANT generation in a water filled geometry. In this plot are represented the ZX projection of the position at which events are generated in the cavity walls superimposed to the position where particles intercept a 9 meter sphere. From this sphere on particles are tracked by SNOMAN.




Figure 2: Example of the response of the SNO detector, as a function of the event energy, to gamma-rays of energies between 7 and 8 MeV originated in the cavity walls.

Footnotes and References

*present address Oxford University, Oxford, UK

†Die Arbeit wurde mit einem Stipendium des Gemeinsamen Hochschulsonderprogramms III von Bund und Landern uber den DAAD ermöglicht

¹GEANT, CERN Program Library, Long Writeup W5013

²SNOMAN, SNO dedicate Monte Carlo code

Measurements of the High Energy Gamma-Ray Flux at SNO

M. C. Perillo Isaac, Y.D. Chan, M. Dragowsky, D. Hurley, K. T. Lesko, R. J. McDonald, M. E. Moorhead*, E. B. Norman, A. Schuelke†, A. R. Smith and R. G. Stokstad

High energy gamma rays are an important background for both reactions of neutrino detection in SNO, neutral and charged current reactions. Compton scattering and/or pair production of high energy gamma-rays can mimic the electron produced in the charged current reaction. The photodisintegration of the deuteron can produce background neutrons to the neutral current reaction signal.

Our goal with this work is to evaluate the high energy gamma-ray flux induced from U and Th long lived isotopes, from the (α, γ) , $(\alpha, n\gamma)$ and $(\alpha, p\gamma)$ reactions in the rock. This new measurement of the gamma-ray flux was performed after the cavity was completed and coated with low activity concrete and the final sealing plastic liner, Urylon.

The detector used to measure the gamma-ray flux inside the SNO cavity was a 19 cm diameter by 15 cm thick NaI crystal to which three 3-inch photomultiplier tubes (PMT) were attached. The gains of the PMT were matched and the signals all of the PMTs were summed and fed into a ORTEC-NOMAD, a portable data acquisition system. We acquired data in this configuration for 1490 hours in the bottom of the SNO cavity. Shielded background runs were performed at the 4600 ft level low background facility of the Creighton mine.

Figure 1 shows the comparison between spectra obtained with the same detector at different sites: at the LBNL Low Background Facility on Bldg. 72 (sea level), at the Oroville Low Background Facility (700 meter-water-equivalent) and at the SNO cavity (6000 meter-water-equivalent).

Footnotes and References

*Present Address Oxford University, Oxford UK

†Die Arbeit wurde mit einem Stipendium des Gemeinsamen Hochschulsonderprogramms III von Bund und Landern uber den DAAD ermoglicht




Figure 1: Comparison between spectra obtained at sea level (dotted line) at the Oroville Low Background Facility (dashed line) and at the SNO cavity (full line).

In table 1 we present the comparison of the fluxes of the gamma-ray lines, 1460 keV from ^{40}K decay and 2614 keV from ^{208}Tl decay obtained in 1994 and recently in 1996.

Table 1: Measured Fluxes - 6800 ft Level

E_γ (keV)	Flux 3/94 $\text{cm}^{-2}\text{s}^{-1}$	Flux 5/96 $\text{cm}^{-2}\text{s}^{-1}$
1460	0.059 ± 0.003	0.061 ± 0.006
2614	0.016 ± 0.001	0.0075 ± 0.0007

Based on the measured spectra, on the measured detector's intrinsic background and on the measured detector's intrinsic efficiencies the expected flux of gamma-rays from the cavity walls above 5 MeV in the SNO cavity is 3.4×10^{-3} gammas/cm²/hour, while previous estimates based on Monte-Carlo and the rock contaminants quote 1.4×10^{-3} gammas/cm²/hour¹

Footnotes and References

¹P. Skensved and B.C. Robertson, SNO internal report.

Sudbury Neutrino Observatory: Simulation of the Calibration Decay Chamber for ^{16}N and ^{17}N

M. Dragowsky, Y.D. Chan, M.C. Perillo Isaac, K.T. Lesko, M.E. Moorhead†, E.B. Norman, A. Schuelke‡ and R.G. Stokstad

The energy calibration of the SNO detector will be accomplished, in part, through the use of a calibration decay chamber for ^{16}N and ^{17}N gas. A SNOMAN Monte-Carlo simulation provided a preliminary estimate of the decay chamber response. We are extending the geometry within the SNOMAN code to improve the accuracy of these simulations. Additionally, we have begun to investigate the effect of the decay chamber on the propagation of Cerenkov light in the D_2O .

Presently, the decay chamber geometry is modeled as three concentric cylinders: an outer canister, a thin shell of plastic scintillator and an interior gas volume. The actual detector has a more detailed internal structure, the most important issue being the nonconcentric location of the gas volume relative to the outer canister. The geometry is also being modified to include a photomultiplier tube (PMT) used to monitor the scintillator, the high voltage generator for the PMT, an optical coupling between the scintillator and PMT and the utility lines which provide power and supply the $^{16,17}\text{N}$ gas.

The decay chamber is optically opaque and potentially can screen Cerenkov light produced by ^{16}N decays in the decay chamber from reaching the main PMT array. Using SNOMAN with our extended geometry we can estimate these screening effects by comparing simulations with the stainless steel canister replaced with a transparent media (D_2O). A comparison of the mean number of PMT hits determine the influence of the decay chamber. We will also account for gamma-ray attenuation in the stainless steel decay chamber. A first assessment will be made by reducing the thickness of the outer canister wall in the simulation so that attenuation is less than 1%. We plan further studies of the decay chamber to assess the light blocking of the decay chamber using simulated external sources of

Cerenkov light, as well as using SNOMAN to track specific photon propagation paths.




Fig. 1. Plot of PMT hits for decay chamber with stainless steel outer canister.

Footnotes and References

† Present address, Oxford University, Oxford, UK OX13RH

‡ Die Arbeit wurde mit Unterstützung eines Stipendiums im Rahmen des Gemeinsamen Hochschulsonderprogramms III von Bund und Ländern über den DAAD ermöglicht.

Sudbury Neutrino Observatory, Monte-Carlo Simulation and Background Studies of the PSUP

A. Schuelke[†], K.T. Lesko, M. Dragowsky, Y.D. Chan, M. Isaac, E. Norman and R. Stokstad

The anticipated solar neutrino signal rates of a few tens of events per day require a low background environment for SNO. There are two principal sources of background: cosmic rays and radiation produced by naturally occurring radionuclides. It is expected that the most significant sources of background lie within the detector components themselves. One part is due to the γ 's and β 's from the Thorium and Uranium chains. The second component is due to the high-energy γ 's from the PMT's, their support structure (PSUP) and the SNO cavity. These γ -rays can have energies exceeding 10 MeV and are produced by $(\alpha, p\gamma)$ or by (n, γ) reactions [1].

Since the LBNL group designed and supplied the PSUP[2], we developed here a much improved version of a Monte-Carlo simulation for the PSUP geodesic frame with the SNOMAN code [2]. The exact geometry has not been included into SNOMAN until now.

Two cases were developed to simulate high-energy γ 's coming from the PSUP. The first used a shell of water at radius 900...910 cm as the source of 9 MeV γ 's. Care was taken to avoid an overlap with other components in this region. The second case placed the shell more correctly at a radius of 883.9...894.1 cm. The monoenergetic γ 's are distributed isotropically within these shells. We then investigated how many events with an energy greater than 3 MeV were reconstructed as originating inside the D_2O .

In fig.1 the reconstructed position versus the generated point of the Cerenkov light is shown for the second case. Mostly the Cerenkov light creation is outside of the D_2O . In the first case with the source shell behind the panel zone 8.7 % of all generated photons resulted in a detected




Figure 1: Fitted position of Cerenkov light vs. production point for case 2

signal. From these entries 9.6 % are fitted inside the D_2O with the standard time fitter and 2 % had a fitted energy $E \geq 3$ MeV. Therefore of all high-energy γ -rays originating in the PSUP 0.2% are fitted in the D_2O with energy greater than 3 MeV. Tab.1 summarizes and compares the results of both cases. We are continuing our

shell range	case 1	case 2
hits	8.7%	13.1%
fitted in D_2O	9.6%	8.9%
$E_{fit,hits} \geq 3$ MeV	2.0%	2.8%
$E_{fit,gen} \geq 3$ MeV	0.2%	0.4%

Table 1: Results from PSUP shell simulation

Monte-Carlo simulations for background studies for the CC and NC spectra with the improved fitters and PSUP geometry.

References

- [1] NIM A364 (1995) 317-327
- [2] NSD Annual Report, 1995, p.99ff

[†] Die Arbeit wurde mit Unterstützung eines Stipendiums im Rahmen des Gemeinsamen Hochschulsonderprogramms III von Bund und Ländern über den DAAD ermöglicht.

Sudbury Neutrino Observatory, Extending the Detector Geometry in SNOMAN for Background Investigations

A. Schuelke[†], K.T. Lesko, Y.D. Chan, M. Dragowsky, M. Isaac, E. Norman and R. Stokstad

Our background study for the PMT support structure and PMT panel area using special water shells was improved by including the PSUP steel frame geometry into the SNOMAN code.

The geometry is an embedding geometry. There are regions with different priorities. The regions with higher priority are embedded in regions with lower. The handling between the various regions is done by a boundary manager.

The geometry software package, GEO, has four tiers: interface, detector element routines geometry primitives and boundary manager. The main task in extending the geometry is the development of the detector element routines. Progressing through the different generations shown in fig.1 requires using different coordinate systems.




Figure 1: General scheme of extending the geometry in SNOMAN

The *GED** routines call their own element and internal element routines, and these routines know about their relationships to their neighbouring regions. These routines work with the overall detector frame. Next generation, the *GEDA** routines, handle all requests estimating the nearest or the next element and picking particular parts of the detector. They are

linked to the primitives in this detector element. Therefore, a special detector element coordinate system is used. In case of the PSUP, it is the same as the overall detector coordinate system. The *GEDA** routines are only necessary for complex detector elements such as the PSUP steel frame. Modelling the PSUP steel frame in a geometry useable by SNOMAN requires that all components have to be described with the available primitive types. By using the high degree of symmetry in the steel frame a special field including a fifth of all struts, hubs, ropes and acrylic vessel guide cans is generated. This section of the PSUP is then simply rotated five times about ϕ to produce the complete frame. Additionally, the PSUP frame model includes a south pole hub, the acrylic vessel guide ring and the chimney ring. The struts, hubs, ropes and acrylic vessel guide ring cans are described as cylinders with radius, thickness and length. Some of them are hollow, which requires creating an internal PSUP region filled with water. The AV guide ring and the chimney ring are described as two half tori. They have an internal water volume, too. The *GEDX** routines are called by the *GEDA** routines. They handle the external and internal boundaries (*GEB** routines) depending on the tracking request and call the special primitive routines (*GEP** routines). The *GEP** and *GEB** routines are standard routines of the SNOMAN code. The shapes and the locations of all elements of the steel frame are stored in the GEDS and GEDP banks.

[†]Die Arbeit wurde mit Unterstützung eines Stipendiums im Rahmen des Gemeinsamen Hochschulsonderprogramms III von Bund und Ländern über den DAAD ermöglicht.

R&D for a Km3 Neutrino Detector

W. Chinowsky[†], H. Crawford^{‡§}, R. Fusezy[†], YuDong He^{††}, S. Jackson^{*}, K. Lesko[§], D. Lowder^{††}, J. Ling^{*}, M. Moorhead^{§††}, D. Nygren[†], B. Price^{††}, J. Przybylski[†], A. Richards[§], G. Shapiro^{††}, G. Smoot^{††}, L. Stevenson[†], R. Stokstad[§], and R. Tripp[†]

The exploration of the neutrino sky is a frontier area of nuclear and particle astrophysics: to date only the sun, one supernova, and the neutrinos generated in the earth's atmosphere have been studied. There is certainly more to be discovered. For example, the most energetic spots in the universe, Active Galactic Nuclei, are very likely sources of high-energy neutrinos. The discovery of these objects in the neutrino spectrum would open a new window for their study and for the investigation of other cosmological sources as well. The detectors currently in operation - AMANDA and BAIKAL - use strings of phototubes arranged in an array, and are the precursors of a future detector with characteristic dimensions of a kilometer. It will enable the measurement of the neutrino spectrum at high energies, a property of the universe that is as fundamental as the cosmic ray spectrum. The collaborations NESTOR (Greece) and ANTARES (France) are two examples of the strong international interest in such a detector, which has acquired the generic name "Km3."

A Km3 able to identify the relatively rare signals of interest and extract the maximum information from them will not be a straightforward scale-up of the existing detectors. Before designing and constructing a Km3, an intensive program of R&D is needed to establish a technical base matched to the scientific goals. An inter-divisional effort at LBNL has been underway and, together with JPL, has produced a key technical advance that, we believe, is ideal for the scientific program of the Km3. Prototype digital optical modules, which incorporate an advanced microchip enabling full wave form reconstruction, have been built and

are undergoing testing here and at the South Pole. Concurrently, a modular computer simulation code is being developed to evaluate detector configurations and performance. Also, we are addressing the challenge of a cost-effective deployment of the photomultiplier tubes in deep ocean water. These activities so far have been supported by Director's Development funds at LBNL and JPL.

It is essential to proceed toward an eventual Km3 in a step-wise manner that can accommodate changes and new developments. Four stages are envisioned:

- Stage I: Systems Design, Simulations, and Deployment (one string, 3 years)
- Stage II: Demonstration (6 to 12 strings, 2 years, 0.03 km²)
- Stage III: Exploratory Science (0.2 km², 3 years)
- Stage IV: Full Scope Science (1 km²)

Stage I is the scope of the R&D envisioned here. The R&D activities factor naturally into these areas: electronic systems design, computer simulations, and deployment methodologies. The three R&D efforts are fully coordinated, however, and each effort includes a phased approach in reaching its goals.

Footnotes and References

† Physics Division

‡ Space Sciences Laboratory

§ Nuclear Science Division

* Jet Propulsion Laboratory

** Now at Oxford University

†† Dept. Physics, UC Berkeley

Half-Life of ^{44}Ti

E. B. Norman, E. Browne, Y. D. Chan, I. D. Goldman*, R.-M. Larimer, K. T. Lesko, M. Nelson[†], F. E. Wietfeldt[‡], I. Zliten

One of the few long-lived gamma-ray emitting radioisotopes expected to be produced in substantial quantities during a supernova explosion is ^{44}Ti . The characteristic 1157-keV γ ray from the decay of ^{44}Ti has recently been observed from the supernova remnant Cas A [1]. In order to compare the theoretically predicted gamma-ray flux to that actually observed from this remnant, one must know the half-life of ^{44}Ti . However, published values for this quantity range from 39 to 66.6 years [2,3]. Given that the Cas A supernova is believed to have occurred approximately 300 years ago, this translates to an uncertainty by a factor of 6 in the amount of ^{44}Ti ejected by this supernova. Thus, in order to provide an accurate and reliable value for this important quantity, we have performed a new experiment to determine the half-life of ^{44}Ti .

We produced ^{44}Ti via the $^{45}\text{Sc}(p,2n)$ reaction using 40 MeV protons from the 88-Inch Cyclotron. This energy was chosen to be just above the maximum of the excitation function for this reaction as reported by McGee *et al.* [4]. However, in the course of preparing this source, we produced far less ^{44}Ti than expected. We therefore remeasured the excitation function for this reaction and found that it peaks at much lower energy and has a significantly smaller maximum cross section than previously reported [5]. To produce the source for the present half-life measurement, a 99.9% pure metallic scandium target $37.8\text{mg}/\text{cm}^2$ thick was irradiated for approximately 24 hours with 1 microampere of beam. After allowing the short-lived activities to decay away, approximately 0.01 μCurie of ^{44}Ti was chemically separated from the target, mixed together with 0.04 μCurie of ^{22}Na and 0.05 μCurie of ^{137}Cs , and then dried to make the source for this experiment. This mixed source and a separate 1- μCurie source of ^{241}Am were then rigidly mounted to a shielded

110-cm³ high-purity germanium detector for γ -ray counting. Data were collected in 1-day time bins for approximately 2 years.

In the present experiment, we attempted to use all three ^{44}Ti γ -ray lines to determine its half life. However, analysis of the ^{241}Am and ^{137}Cs lines produced an incorrect value for the half life of each of these isotopes. On the other hand, the analysis of the ^{22}Na line produced a result that agreed to within 0.5% of the known value of 2.603 years. Also, a small ^{54}Mn contaminant line at 835 keV yielded a half life that agreed to within 1% of its known value. Thus, we decided to concentrate our effort on the analysis of the 1157-keV line. In order to reduce systematic effects such as the possibility of a change in the source-detector distance or a change in the detection efficiency, we compared the area of the 1157-keV ^{44}Ti line to that of the nearby 1275-keV line from the ^{22}Na standard. The ratio of these peak areas was plotted versus time and then fitted to an exponential whose argument was the difference in decay rates between ^{44}Ti and ^{22}Na . The chi-squared per degree of freedom for the fit is 1.1. The half life of ^{44}Ti that we deduce from this experiment is 62 ± 2 years.

Footnotes and References

*Permanent address: Univ. of SaoPaulo, Sao Paulo, Brasil

[†]Present address: Santa Rita High School, Tucson, AZ

[‡]Present address: NIST, Gaithersburg, MD

1. A. F. Iyudin *et al.*, *Astron. & Astrophys.* **284** (1994) L1.
2. J. Meissner, Ph.D. thesis, Univ. of Notre Dame, 1996
3. D. Alburger & G. Harbottle, *Phys. Rev. C* **41** (1990) 2320.
4. T. McGee, *et al.*, *Nucl. Phys. A* **150** (1970) 11.
5. R. Ejnisman *et al.*, *Phys. Rev. C* **54** (1996) 2047.

Survival of ^{180}Ta During the s-Process

R.-M. Larimer, Y. D. Chan, M. P. C. Isaac, K. T. Lesko, A. O. Macchiavelli, R. W. Macleod, M. E. Moorhead, E. B. Norman, K. S. Krane*, K. Zaerpoor*, J. Beckert†, L. A. Bernstein‡, L. P. Ferrist

Over the years, many attempts have been made to find a plausible production mechanism for Nature's rarest isotope and only naturally-occurring isomer, the odd-odd nucleus ^{180}Ta . The long-lived $^{180}\text{Ta}^m$ ($J^\pi = 9^-$) is located approximately 75 keV above the $t_{1/2} = 8.1$ hour ($J^\pi = 1^+$) ground state [1]. The standard s-, r-, and p-processes all fail to quantitatively account for the observed abundance of ^{180}Ta ($[^{180}\text{Ta}]/[^{181}\text{Ta}] = 10^{-4}$.) Several detours off the standard s- and r-process paths that could lead to ^{180}Ta have been investigated. The s-process path through the stable Hf isotopes weakly populates a $J^\pi = 8^-$ isomer in ^{180}Hf which can then beta decay to $^{180}\text{Ta}^m$. However, this route was shown to be too small to account for ^{180}Ta abundance [1]. In principle the r-process could also reach ^{180}Ta . ^{180}Lu produced in the r-process could feed $J^\pi = 8^-$ isomer in ^{180}Hf and then produce ^{180}Ta by beta decay. We have shown with experiments at the Univ. of Washington and at 88" Cyclotron that this branching ratio is too small to account for a significant amount of ^{180}Ta [2,3]. Thus, the production mechanism responsible for ^{180}Ta remains an open question.

Regardless of how ^{180}Ta is actually produced in stars, the question remains as to whether it can survive in the hot dense stellar environment? At the temperatures appropriate to the s- and r-processes, there is an enormous bath of high energy photons present. Such photons could excite $^{180}\text{Ta}^m$ up to a higher-lying level of intermediate spin which subsequently decays through a γ -cascade to the ^{180}Ta ground state. Such photoexcitation could lead to thermal equilibration between the ground state and isomer, with the result that the effective ^{180}Ta half life becomes on the order of days. This would drastically reduce the amount of $^{180}\text{Ta}^m$ that would actually emerge from a stellar environment.

The question of whether or not this process actually happens in nature depends critically on the excitation energy and γ -decay modes of levels in ^{180}Ta . Attempts

to photodeexcite $^{180}\text{Ta}^m$ to $^{180}\text{Ta}g$ using intense sources of ^{137}Cs and ^{60}Co have failed [4]. This suggests that the mediating levels may lie above 1.33 MeV excitation energy. Recent Coulomb deexcitation experiments have observed the production of $^{180}\text{Ta}g$ from $^{180}\text{Ta}^m$ and suggest that there may in fact be lower lying mediating levels [5].

In order to answer the question of whether or not $^{180}\text{Ta}^m$ can survive in stellar environments, we have populated levels in ^{180}Ta using the $^{176}\text{Yb}(^7\text{Li}, 3n)$ reaction and have used GAMMASPHERE to studying the gamma decays of levels up to approximately 2 MeV excitation energy. Thus far we have been able to place approximately 85 γ -ray transitions among 60 different levels. We observe a family of transitions that ultimately lead to the $^{180}\text{Ta}g$ and another family that leads to the long-lived $^{180}\text{Ta}^m$. We have not found any level which has a measurable decay branch to both levels. Thus it may be that $^{180}\text{Ta}^m$ can survive in an s-process environment.

Footnotes and References

*Oregon State Univ., Corvallis, OR

†Lawrence Livermore National Laboratory

1. S. E. Kellogg and E. B. Norman, Phys. Rev. C **46**, 1115 (1992).
2. S. E. Kellogg and E. B. Norman, Phys. Rev. C **34**, 2248 (1986).
3. K. T. Lesko *et al.*, Phys. Rev. C **34**, 2256 (1986).
4. E. B. Norman *et al.*, Astrophys. J. **281**, 360 (1984).
5. C. Schlegel *et al.*, Phys. Rev. C **50**, 2198 (1994).

Search for the β^+ Decay of ^{144}Pm

K. Zaerpoor*, M. R. Dragowsky*, K. S. Krane*, M. M. Hindit, S. J. Robinson†, D. E. DiGregorio‡, E. B. Norman, Y. D. Chan, M. C. P. Isaac, R.-M. Larimer, A. O. Macchiavelli, R. MacCleod

The mean confinement time of cosmic rays within our Galaxy can be determined by comparing the cosmic-ray abundances of suitably long-lived radioactive isotopes to those of their stable neighbors. For heavy elements ($Z > 28$) the current state of the art in cosmic-ray mass measurements is not sufficient to allow isotopic abundance measurements. This difficulty prompted Drach and Salamon [1] to consider the possibility of using elemental abundances of Tc and Pm, which have no stable isotopes, as cosmic ray clocks. In the case of Pm, only three isotopes, $^{143,144,145}\text{Pm}$, have sufficiently long half-lives and suitable decay schemes to be present in the cosmic rays. Due to their interactions with the interstellar medium, cosmic rays nuclei are fully stripped of their atomic electrons. This turns a nucleus such as ^{145}Pm , which decays in the laboratory via electron capture, into a stable nucleus. Because of their larger EC decay energies, it is possible for ^{143}Pm and ^{144}Pm to also decay by β^+ emission. In the laboratory, these forbidden decays have to compete with allowed EC decays and so have not yet been observed. As fully stripped nuclei, however, these β^+ decays will determine the cosmic ray half lives of these isotopes.

In a previous experiment [2], we used two 28% efficient Ge detectors surrounded by a 4π NaI annular detector to search for the β^+ decay branches of $^{143,144}\text{Pm}$. For the case of ^{144}Pm we searched for the β^+ decay to the $J^\pi = 2^+$ level at 697 keV through the observation of 511-511-697 keV triple coincident events. While we did not succeed in observing this decay, we were able to establish a limit of $> 1.2 \times 10^6$ years for the β^+ decay half life of ^{144}Pm . This is close to the lower limit for this decay mode estimated by Drach and Salamon. In order to maximize our detection efficiency, we had to sandwich the source right in between the two Ge detectors. Because of this close geometry, a major limitation in this experiment was background produced by γ rays Compton scattering from one Ge detector into the other.

In order to improve upon this measurement, we have performed a new experiment by placing a 1.4 μCi source of ^{144}Pm

into GAMMASPHERE to search once again for 511-511-697 keV coincidences. This source was produced at the 88-Inch Cyclotron approximately 9 months ago and has been used in one study of the decay scheme of ^{144}Pm [3]. Because of the larger size but smaller solid angle covered by each detector element in GAMMASPHERE and because of the BGO Compton suppressers, this provides a much higher detection efficiency and a substantially lower background environment in which to search for this β^+ decay branch. This ^{144}Pm source was counted in GAMMASPHERE for approximately 4 days. Analysis of the data obtained in this experiment is now in progress. We estimate that we will improve our sensitivity by approximately a factor of 10 over our previous results.

Footnotes and References

*Oregon State Univ. Corvallis, OR

†Tennessee Technological Univ., Cookeville, TN

‡TANDAR Laboratory, Buenos Aires, Argentina

1. J. Drach, M. Salamon, *Astrophys. J.* **319** (1987) 237.
2. M. M. Hindi *et al.*, *Phys. Rev. C* **50** (1994) 728.
3. S. J. Robinson *et al.*, *Phys. Rev. C* **54** (1996) 1478.

Preliminary Results from a Study of the Double Beta Decay of ^{150}Nd

M. C. Perillo Isaac, Y.D. Chan, D. Hurley, R. J. McDonald,
E. B. Norman and A. R. Smith

The main contribution to double beta decay (with or without neutrinos) is the ground state to ground state (GS) transition. Transitions to the excited states of the daughter isotope are also possible, if kinematically allowed. The double beta transition to 0^+ excited states is analogous to the ground state to ground state transitions, while a double beta decay from a 0^+ state to a 2^+ excited state is only possible through right handed currents. In the first approximation, the transition rate of the double beta decay with the emission of two neutrinos is proportional to a function of the available energy for the decay¹. In this scenario the transition rates to excited states are substantially lower than the transition rate to the GS of the daughter isotope.

Here we report the first phase of an experiment where we look for the de-excitation γ -rays of ^{150}Sm populated by the double beta decay of ^{150}Nd using direct counting techniques.

The half life of the 2ν double beta transition of ^{150}Nd to the ground state of ^{150}Sm was recently measured to be $(1.7^{+1.0}_{-0.5} \pm 0.35) \times 10^{19}$ y². Taking into account the expected dependence on the phase space factor, one can predict a half life for the double beta transition of ^{150}Nd to the first 0^+ excited state of ^{150}Sm to be of the order of 10^{20} y. The de-excitation from this level gives rise to two coincident gamma-ray lines, 334 and 406 keV.

We used a 500 cm^3 n-type HPGe detector to look for the γ -rays following the double beta decay of ^{150}Nd to the excited states of ^{150}Sm . A sample of 5 kg of natural Nd_2O_3 was placed in a Marinelli beaker geometry around the de-




Figure 1: The energy regions of the two gamma-ray lines from the de-excitation of the first 0^+ state are hatched. The peaks from natural radioactive contamination are marked

tor. The passive shielding consists of 15 cm of lead and 2 cm of copper and the whole set-up is located at the LBNL - Oroville low background facility (700 mwe). We accumulated data for 1268.67 h in this configuration.

We did not observe peaks in the energy region where the gamma-ray lines from the de-excitation of ^{150}Sm levels are expected. The lower limit for the half life can be obtained through the upper limit peak area of the gamma lines 334 and 406 keV.

Since the two gamma lines we are looking for have the same intensity (100% branching ratio each), one can add the two energy regions of the spectrum in order to obtain a combined upper limit peak area and hence a better limit for the half life. Our limit for the half life of the double beta decay of ^{150}Nd to the first 0^+ excited state of ^{150}Sm is 4.9×10^{19} years (2.9×10^{19} years), with 68% (90%) confidence level.

Footnotes and References

¹See "Physics of Massive Neutrinos", F. Boehm and P. Vogel, Cambridge University

²V. A. Artem et al, JETP Lett. 58, 262,(1993)

Does The Lifetime of ^{40}K Depend Upon its Chemical State ?

E. B. Norman, M. C. Perillo-Isaac, M. E. Moorhead*, R.-M. Larimer, R. J. McDonald, A. R. Smith, E. Browne

The influence of the chemical state on nuclear decay rates has been observed for a number of isotopes that decay either by electron capture or by internal conversion [1,2]. This is believed to be due to the fact that the density of electrons at the nucleus, upon which such decay rates depend, varies as the chemical state of the radioactive species is altered. The electron-capture decay branch of ^{40}K is the basis of the potassium-argon dating scheme. This decay leads to the 1461-keV first excited state of ^{40}Ar and has a Q_{EC} value of only 44 keV. Because of its low decay energy and its first-forbidden-unique character, it is possible that the lifetime of ^{40}K could depend on its chemical form. In fact, there have been some reports in the literature in which ages of materials derived from K/Ar dating disagree with those obtained from U/Pb techniques [3]. Such discrepancies in apparent ages could be due to effects of the chemical environments in which the potassium is found.

To search for influences of the chemical state on the ^{40}K decay rate, we compared the specific gamma activities of ^{40}K in KCl, K_2SO_4 , KNbO_3 , and KTaO_3 . This was done by combining known masses of each of these compounds with known amounts of La_2O_3 and gamma counting these mixtures. By comparing the measured yields of the 1461-keV line from the decay of ^{40}K to that of the 1436-keV line from the decay of ^{138}La , we were able to determine the specific activity of each potassium compound. We also compared the specific activity of KCl in powder form to that of KCl dissolved in H_2O . Finally, we measured the specific activity of K_2CO_3 , converted it to KCl, and then measured the specific activity again.

The results obtained in all of these studies were consistent with the EC decay rate of ^{40}K being independent of the chemical state. We were able to set a limit on the fractional change in the ^{40}K decay rate to be $\leq 1\%$. Thus, the

reason for the discrepancies in apparent K/Ar and U/Pb ages of materials from the Oklo natural reactor [3] must be something other than a chemical dependence of the decay rate of ^{40}K .

Footnotes and References

*Present address: Oxford University, Oxford, UK

1. G. T. Emery, *Ann. Rev. Nucl. Sci.* **22** (1972) 165.
2. H. P. Hahn, H. J. Born, J. I. Kim, *Radiochim. Acta.* **23** (1976) 23.
3. F. Gautier-Lafaye, P. Stille, R. Bros, R. Taieb, Commission of the European Communities Report EUR-14877 (1993) p. 57.

Weak Gamma Rays in the Electron-Capture Decay of $^{194}\text{Au}^*$

R. R. P. Teixeira*, I. D. Goldman*, M. T. F. da Cruz*, E. Browne, I. Y. Lee, A. O. Macchiavelli, E. B. Norman

The electron capture decay of ^{194}Au has been extensively studied before, and the spectroscopic and nuclear data have been evaluated and published in Nuclear Data Sheets [1]. However, recently available large Ge detectors and high-efficiency Ge detector arrays have provided the opportunity for detecting weaker gamma rays in singles and coincidence experiments, and thus, to verify and extend results from previous measurements.

We produced two sources of ^{194}Au . A source for measuring gamma rays in a singles experiment was made by irradiating a foil of natural platinum with 10-MeV protons in the cyclotron of the Instituto de Pesquisas Energeticas e Nucleares (IPEN) at the University of Sao Paulo, Brazil. Another source for gamma-gamma coincidence experiments using the (LBNL) High-Energy-Resolution-Array (HERA) was made by bombarding a gold foil with 40-MeV protons from the 88-Inch Cyclotron.

Our measurements produced a wealth of gamma-ray data (167 transitions between singles, coincidence, and angular correlation measurements). The complete list of gamma rays measured in this work has been published [2], and some preliminary results have already been included in the most recent data evaluation of ^{194}Au [3]. We found thirty three gamma rays that had not been previously observed in the electron-capture decay of ^{194}Au , and several coincidence results that have significantly affected its decay scheme. These data have confirmed levels in ^{194}Pt at 1373- and 1737 keV, and established new placements in the decay scheme for the 59-, 223-, 304, and 562-keV transitions. A paper describing these results have recently been submitted for publication [4].

Footnotes and References

*Permanent address: Univ. of Sao Paulo, Sao Paulo, Brasil

1. B. Singh, Nuclear Data Sheets **56**, 75 (1989).
2. R.R. Plaza Teixeira, *Espectroscopia Gama e Correlação Angular Gama Gama em ^{194}Pt* ; Ph. D. Thesis, University of Sao Paulo, Brazil, 1996.
3. E. Browne and B. Singh, Nuclear Data Sheets **79**, 277 (1996).
4. R. R. P. Teixeira *et al.*, Phys. Rev. C (submitted).

Nuclear Astrophysics Data Home Page

J. Dairiki, R. Firestone, R. Stokstad, S. Woosley[†], and S.C. Wu[‡]

A variety of data is needed in nuclear astrophysics; charged particle, neutron, and neutrino cross sections; atomic masses; decay modes and nuclear lifetimes from the valley of stability to the nucleon drip lines; beta decay strength functions; elemental and isotopic abundances; and theoretical values for all of these quantities when experimental values are unavailable. These data are found in many different places and forms including printed publications, computer files, journals and review articles, and private databases. Some data are available through electronic means, but at a variety of locations and in widely varying formats. The disbursed nature of these data often makes it difficult for theorists to perform their calculations with the best available input data.

In the past, much of the compiled data used for nuclear astrophysics was the result of work by relatively few people, in particular Willy Fowler and his collaborators. That era has ended, and astrophysicists recognize that a concerted and coordinated community effort must be initiated for the compilation, evaluation, and stewardship of the nuclear data they both generate and use. The expertise for evaluation of data is spread over many institutions, worldwide, and it seems inevitable that the data will be published in various formats in the foreseeable future. We can, however, bring these data to a central location where they can be (if not already) compiled, and formats standardized. The data can then be made conveniently available electronically through the WWW and file transfer protocols on the Internet.

We have made a start toward this goal by developing a home page for nuclear astrophysics data that can serve as a prototype for a more complete and elaborate effort. Even as a prototype, however, this home page contains a

variety of useful data, much of which has not been generally available before, or which appears on the WWW for the first time.

The data are arranged as follows:

Nuclear Astrophysics Data

1. Nuclear Data Reference List - a comprehensive bibliography for nuclear astrophysics, hypertext linked to available data.
2. Reaction Rates, Charged-Particle Induced Reactions, Neutron-Induced Reactions, EM Interactions, and Weak Interactions.
3. Nuclear Structure and Decay Data, Isotope Explorer (VuENSDF), Super Chart of the Nuclides, Table of Isotopes, Table of Radioactive Isotopes.
4. Atomic Masses, experimental and theoretical.
5. Nuclear and Particle Astrophysics Data from the Particle Data Group, Phys. Rev. D54 (1996)
6. Chemical and Isotopic Data, Elemental Abundance, Isotopic Abundance, Physical Constants, Periodic Table, and Chemical Properties.

Nuclear Astrophysics Meetings

Web Sites of Interests to Nuclear Astrophysics

We note that section 2 above contains the comprehensive data bases of Hoffman and Woosley, and of Thielemann, et al.

The Nuclear Astrophysics Data Home Page can be visited at:

<http://isotopes.lbl.gov/isotopes/astro.html>

Footnotes and References

[†] U.C. Santa Cruz

[‡] On sabbatical from Tsing-Hua University, Taiwan

Laser Trapping Radioactive Atoms for Precise Weak Interaction Tests

M.A. Rowe, S.J. Freedman, B.K. Fujikawa, G. Gwinner, S.-Q. Shang, P.A. Vetter, E.G. Wasserman

Radioactive isotopes confined in neutral atom traps will play an important role in future precision measurements of weak interactions such as the parity violating asymmetry in the β -decay of spin-polarized nuclei, electron-neutrino correlations, and parity violation in atoms. Traps provide a localized, isotopically pure sample in which source scattering is eliminated, and neutral atoms are easily manipulated by optical pumping techniques to achieve high nuclear spin polarization.

Recent improvements to our apparatus have provided us with 50,000 trapped ^{21}Na atoms. In the past, our efforts have been directed towards increasing the size of the trapped sample from the first demonstration of the technique towards a useful level. Our advances during the last year have produced a ^{21}Na trap large enough to begin experiments with radioactive atoms. A precise determination of the ground state hyperfine splitting is now in progress. We will then begin a measurement of the β -asymmetry parameter in the mirror decay of $^{21}\text{Na} \rightarrow ^{21}\text{Ne}$ to search for deviations from the V-A structure of the charged current weak interaction, e. g. from right handed currents.

^{21}Na ($t_{1/2} = 22$ sec) is produced on-line at the 88" Cyclotron at LBNL with the $^{24}\text{Mg}(p, \alpha)^{21}\text{Na}$ reaction. Efficient extraction of ^{21}Na from our MgO target is crucial for achieving large traps. During 1996, we installed a new, more reliable target oven. In target development runs with this oven we determined that sintering and slow diffusion in the MgO powder kept the yield low from a powder target. Now we use a series of thin, free-standing, pressed MgO disks. Another improvement has been better collimation of the ^{21}Na atomic beam into the laser trap region. Since the vapor pressure inside our target oven is much lower than standard atomic beam sources, we can use long narrow exit channels to focus the outgoing beam. We now use channels with a

length-to-diameter ratio of 25:1. These refinements provide more ^{21}Na in the forward direction, yielding more trapped atoms.

We have made a preliminary measurement of the atomic ground state hyperfine splitting of ^{21}Na using our trapped atoms (Fig. 1). We induce transitions between the two ground state hyperfine levels with microwaves and then probe the atoms with a laser. A measurement of the atomic fluorescence tells us how many atoms make the transition as a function of microwave frequency. With an improved magnetic field configuration and a new microwave antenna, a final frequency measurement will be made with a precision of 1 part in 10^7 . We have already achieved this accuracy with the stable isotope, ^{23}Na . This microwave work can also be applied to characterize the nuclear polarization of our trapped atoms, which will be necessary to extract weak interaction parameters from our measurements on the β -decay. In our last run of 1996 at the 88" Cyclotron, we observed β decays of our trapped sample with an in-vacuum detector. This data provides us with signal and noise levels which will guide design changes for the β asymmetry measurement.




Fig. 1. Microwave absorption by trapped ^{21}Na .

Measurement of the Partial $0^+ \rightarrow 0^+$ Half Life of ^{10}C with GAMMASPHERE

B.K. Fujikawa,* S.J. Asztalos,*† C.J. Bowers,*† R.M. Clark,* M.-A. Deleplanque-Stephens,* P. Fallon,* S.J. Freedman,*† J.P. Greene,‡ I.-Y. Lee,* L.J. Lising,*† A.O. Macchiavelli,* R.W. MacLeod,* J.C. Reich,*† M.A. Rowe,*† S.-Q. Shang,* F.S. Stephens,* and E.G. Wasserman*§

The u-d element (V_{ud}) of the Cabibbo-Kobayashi-Maskawa (CKM) quark mixing matrix is a fundamental parameter of the Standard Model of Electroweak Interactions. Its most precise determination comes from nuclear physics experiments, in particular, from measurements of superallowed Fermi beta decays. These measurements, requiring both precision nuclear physics experiments and state of the art theoretical nuclear physics calculations, have been made for a variety of nuclei ranging from ^{14}O to ^{54}Co . The u-d element obtained from these measurements are in statistical agreement and the average value obtained implies a non-unitary CKM matrix, which if correct, would require exotic extensions to the Standard Model. Unfortunately the theoretical calculations of the isospin breaking corrections, necessary for extracting V_{ud} , are controversial. For example, Wilkinson** has suggested that these calculations are incomplete and that the isospin breaking corrections must be extracted empirically. In order to resolve this controversy, much effort has recently been invested in measuring V_{ud} from the superallowed Fermi decay of ^{10}C , where the isospin breaking corrections are expected to be small and any residual charge dependent corrections will be apparent. This is a very challenging measurement, since the beta decay of ^{10}C has a small superallowed Fermi branching ratio which has to be precisely determined in a high background environment. We are currently engaged in series of experiments to measure the superallowed Fermi branching ratio of ^{10}C beta decay using the GAMMASPHERE facility at the Lawrence Berkeley National Laboratory 88-inch cyclotron. Analysis of the first data run is

complete and the preparation of publication is in progress. The results are summarized in Fig. 1.

Footnotes and References

*Lawrence Berkeley National Laboratory

†University of California, Berkeley

‡Argonne National Laboratory

§Present address: Abacus Concepts Incorporated

**D.H. Wilkinson, Zeit. Phys. A348, 129, (1994).





Fig. 1. The radiatively-corrected ft values for superallowed Fermi beta decays plotted against the charge of the daughter nucleus. The solid curve is a fit to the data assuming a hypothetical quadratic Z dependent isospin breaking correction proposed by Wilkinson.** Recent results from this experiment on ^{10}C , taken alone and with previous experiments, tend to support such a dependence.

Test of the conserved vector current hypothesis in the beta-decay of ^{14}C

J. L. Mortara*†, I. Ahmad**, S. J. Freedman†‡, B. K. Fujikawa‡, J. P. Greene**, J. P. Schiffer**, A. R. Zeuli**


In 1957, Feynman and Gell-Mann proposed the conserved vector current (CVC) hypothesis.¹ In the classic case of the mass-12 isospin triplet (B-C-N), CVC relates the width of the electromagnetic transition ($^{12}\text{C}^* \rightarrow ^{12}\text{C}$) to the shape factors of the beta decay spectra ($^{12}\text{B} \rightarrow ^{12}\text{C}$) and ($^{12}\text{N} \rightarrow ^{12}\text{C}$). The shape factor represents a deviation of the beta spectrum from the simple allowed shape by the additional factor $S(E) = 1 + aE$, where E is the total electron energy. Several experiments have measured a in the mass-12 system, but the agreement with CVC is weak at best.²

The mass-14 isospin triplet (C-N-O) represents another viable system for testing CVC (Fig. 1).



We have performed a measurement of the beta decay spectrum of $^{14}\text{C} \rightarrow ^{14}\text{N}$ ($Q \approx 156$ keV) toward this end. The apparatus used for this measurement consists of a superconducting solenoid and Si(Li) solid state detector.³ The magnetic field transports the electrons in helical orbits ($r < 3\text{mm}$) to the Si(Li) detector without the possibility of scattering on material collimators. The detector response function was determined by measurement of internal conversion spectra from ^{139}Ce and ^{109}Cd . The ^{14}C data consists of four separate runs with a total of about 7×10^9 total decays accumulated over a period of 515 livetime hours. The data is fitted from 65 to 250 keV. The results are quoted for this

energy interval, but the shape factor was observed to be independent of the chosen interval. In Fig. 2 we show the fit from run 1 which yielded $a = -39.1 \pm 0.4(\text{stat.})\%/\text{MeV}$ for the shape factor. Including the results from the other three data



sets and we have $a = -39.2 \pm 0.2(\text{stat.}) \pm 0.6(\text{sys.})\%/\text{MeV}$. This represents the most precise determination of the shape factor in ^{14}C and appears to be in good agreement with the value predicted by CVC of $-38.0 \pm 1.2\%/\text{MeV}$,² where the error reflects the uncertainty in the radiative width of $^{14}\text{C} \rightarrow ^{14}\text{N}^*$.

Footnotes and References

*P-23 Neutron Science and Technology, Los Alamos National Laboratory

† Department of Physics, University of California at Berkeley

‡ Nuclear Science Division, Lawrence Berkeley National Laboratory

**Physics Division, Argonne National Laboratory


1. Feynman and Gell-Mann, Phys. Rev. **109**, 193 (1957).
2. Calaprice and Holstein, Nucl. Phys. **A273**, 301 (1976).
3. J.L. Mortara et. al., Phys. Rev. Lett. **70**, 394 (1993).

Test of the conserved vector current hypothesis in the beta-decay of ^{14}O


S. J. Freedman†‡, B. K. Fujikawa‡, J. L. Mortara†§, D. W. Ross‡, D. Wutte**

In 1957, Feynman and Gell-Mann proposed the conserved vector current (CVC) hypothesis.¹ In the classic case of the mass-12 isospin triplet (B-C-N), CVC relates the width of the electromagnetic transition ($^{12}\text{C}^* \rightarrow ^{12}\text{C}$) to the shape factors of the beta decay spectra ($^{12}\text{B} \rightarrow ^{12}\text{C}$) and ($^{12}\text{N} \rightarrow ^{12}\text{C}$). The shape factor represents a deviation of the beta spectrum from the simple allowed shape by the additional factor $S(E) = 1 + aE$, where E is the total electron energy. Several experiments have measured a in the mass-12 system, but the agreement with CVC is weak at best.²

The mass-14 isospin triplet (C-N-O) represents another viable system for testing CVC (Fig. 1).



We are preparing to measure the ground state to ground state decay of ^{14}O . Since the half-life of this decay is only slightly more than a minute, the activity must be produced on-line at the 88" cyclotron. In order to avoid spectral distortion associated with thick sources, we have decided to pursue a new approach. Using a cusp source developed by the AFRD at Lawrence Berkeley National Laboratory, we will produce a radioactive beam of ^{14}O . A cross-sectional view of the cusp source is shown in Fig. 2. The ^{14}O will be produced by the reaction $^{12}\text{C}(^3\text{He},n)^{14}\text{O}$ in a heated graphite target. The evolving $\text{C-}^{14}\text{O}$ will be transported to the cusp source where it will be ionized to produce a beam of ^{14}O to impant in a thin carbon foil.



To measure the beta-spectrum we have a 180° spectrometer with an approximately 50% momentum bite. We will detect the positrons with a multi-wire proportional chamber. We expect preliminary tests of the entire system by late 1997. In addition to measuring the ground state to ground state decay, we also plan to measure the superallowed 0^+ to 0^+ decay. This branching ratio has been measured only once³ and is directly related to the value of V_{ud} in the CKM matrix.

Footnotes and References

† Department of Physics, University of California at Berkeley

‡ Nuclear Science Division, Lawrence Berkeley National Laboratory

§ P-23 Neutron Science and Technology, Los Alamos National Laboratory

** Accelerator and Fusion Research Division, Lawrence Berkeley National Laboratory

1. Feynman and Gell-Mann, Phys. Rev. **109**, 193 (1957).
2. Calaprice and Holstein, Nucl. Phys. **A273**, 301 (1976).
3. G.S. Sidhu and J.B. Gerhart, Phys. Rev. **148**, 1024 (1966).

β - γ Directional Correlation in ^{22}Na

C.J. Bowers, S.J. Freedman, B.K. Fujikawa, J.C. Reich, S.-Q. Shang, P.A. Vetter, E.G. Wasserman,
and the Gammasphere Collaboration

Motivation

An experiment by the Weak Interactions Group in collaboration with Gammasphere to measure nuclear form factors in the β^+ decay of ^{22}Na made good progress in 1996. It has been known for roughly 40 years that for ^{22}Na , the usual allowed approximation for β^+ decay does not yield a good estimate of the $\log ft$ value, suggesting that higher order corrections from nuclear recoil play a significant role. These higher order terms offer an opportunity to test Standard Model predictions and to search for so-called second class currents. This experiment should also clear up a 2.5σ discrepancy between two past measurements of the β - γ correlation.

Experiment

An effort at the 88" Cyclotron is proceeding to improve the measurement of the directional correlation between the emitted β and the subsequent 1.274 MeV γ from the 2^+ excited state of the ^{22}Ne daughter. The Gammasphere at the 88" Cyclotron is an ideal instrument. Symbiotically, the required precision (about 10^{-4}) of this simple experiment constitutes a stringent test of the Gammasphere array, while using what would otherwise be down time for the array. Our experiment is performed in an off-line configuration, using a $10 \mu\text{Ci}$ ^{22}Na source located at the center of the detector array. A plastic scintillator β detector is inserted in the array for 8% detector solid angle. Events when a Ge detector in Gammasphere fires in coincidence with a β observation are recorded, and we seek a correlation between the β and γ directions of the form $(1 + A \cos^2 \theta)$ where θ is the angle between the β detector and the coincident Ge detector, and A is the directional correlation amplitude. In principle, we could count the γ hits in each detector and correlate the Ge detector angular direction to the β detector. However, we address the problem of varying Ge detector efficiency by

also counting events when only a γ is detected independently of a β . The number of γ hits in each detector is proportional to the efficiency, so we take a ratio of coincident β - γ events to single γ counts to cancel the efficiencies. This ratio as a function of θ yields the directional correlation.

We took data during the winter holiday shutdowns at the 88" Cyclotron in January of 1996 and in January 1997 with the goal of a statistical uncertainty of 5×10^{-4} in the correlation coefficient A . The earlier run revealed an unexpected systematic difference in count ratios for the two hemispheres of the array at roughly 1.2%, probably due to staggered detector timing delays. This led to an improvement in the cable routing of the array, which has reduced the effect in our raw data to roughly 0.4%. Software timing cuts on the coincident 1.274 MeV γ seem to eliminate this effect to less than 0.1%, and our current analysis in progress seems set to achieve the desired precision (Fig. 1).




Fig. 1. Jan. 1997 Data, Early Analysis

Recent achievements summarized:

- First β - γ correlation measured with Gammasphere: Nov. 1995, Jan. 1996.
- Cabling upgrade on Gammasphere to improve pretrigger timing staggering
- Jürgen Reich completed Diplomarbeit in summer, 1996 for TU München.
- New 1997 data should complete directional correlation measurement

Search for the beta-decay of ^{54}Mn

I. Ahmad**, S. Austin§, S. J. Freedman†, K. T. Lesko‡, J. L. Mortara*†, A. Wuosmaa**

The decay of ^{54}Mn is well known to proceed by electron capture with a half-life of 312 days (Fig. 1). Although it is energetically possible for ^{54}Mn to decay to the ground state of ^{54}Fe by β^- decay or to the ground state of ^{54}Cr by β^+ , only upper limits have been set for these second forbidden decay modes.¹ The current limit on these branches is $\approx 10^{-6}$ for the β^- decay and $\approx 10^{-8}$ for the β^+ decay. The difference in the branching fractions arises from the greater available phase space for the β^- decay. These hindered decay modes are the primary means by which a fully ionized ^{54}Mn nucleus would decay. Such fully stripped ions are found in cosmic rays and abundances of ^{54}Mn have been reported.² These relative abundances, combined with measured partial half-lives, provide a cosmic ray chronometer by which one can infer the cosmic-ray confinement time.




Fig. 1. The decay scheme of ^{54}Mn .

Previous efforts¹ have used the characteristic annihilation radiation from positrons as a signature for the β^+ decay. We intend to use annihilation radiation as a trigger with an apparatus designed specifically for such detection. The APEX spectrometer³ was designed to detect the annihilation radiation of positrons created following heavy ion collisions. APEX is a 3 meter long solenoid which will be used to

transport positrons to a charge particle detector surrounded by a segmented annihilation radiation detector. The method has high efficiency and allows us to use an extremely intense radioactive source without suffer from the potentially large 835 keV gamma-ray background.




Fig. 1. Recent measurement of Mn abundances⁴

Footnotes and References

*P-23 Neutron Science and Technology, Los Alamos National Laboratory

†Department of Physics, University of California at Berkeley

‡Nuclear Science Division, Lawrence Berkeley National Laboratory

** Physics Division, Argonne National Laboratory

§ Michigan State University

1. M. T. F. da Cruz *et al.*, Physical Review C, **48**, 3110 (1993).

2. R. A. Leske, Astrophys. J. **405**, 567 (1993).

3. I. Ahmad *et al.*, Nuclear Instruments and Methods A **370**, 539 (1996).

4. M. DuVernois, private communication.

Time Reversal Invariance Violation in Polarized Neutron Beta Decay

L.J. Lising, S.J. Freedman, B.K. Fujikawa, E.G. Wasserman,* and the emiT Collaboration†

The existence of CP-symmetry violation in the weak interaction is established in kaon decay, but the implied consequence, time-reversal-symmetry violation, is yet to be observed. The emiT collaboration is mounting an experiment to search for time-reversal-symmetry violation in free neutron beta decay, using cold, polarized neutrons at the National Institute of Standards and Technology's Cold Neutron Research Facility. This experiment, which was put on-line at the reactor this December, utilizes an octagonal array of detectors to observe neutron decay electron and recoil proton in coincidence. The experiment is designed to detect an angular correlation of the form,

$$\hat{\sigma}_n \cdot (\mathbf{p}_e \times \mathbf{p}_p),$$

which is odd under time reversal. The coefficient of this term in the neutron decay correlation has been previously shown to be less than 0.0011. The present experiment aims at a factor of three improvement in sensitivity from the present run.

The neutrons in the cold ($T=40$ Kelvin) beam are polarized to 96% with a supermirror polarizer. Electrons are detected with four 50 cm long plastic scintillators. The recoil protons, whose maximum energy is only 750 eV, drift in a field free region until they near one of the four proton arrays, where they are accelerated through 30 kilovolts onto thin-window PIN diodes. The characteristic delay time between the decay proton and electron is used to distinguish signal from background. The proton drift time is greater than $0.5 \mu\text{s}$ and most backgrounds are prompt. Figure 1 shows time versus detected proton energy, illustrating the separation of the proton signal from the large prompt background. Anticipated sources of systematic uncertainty were reduced in the detector design and extensive cross checks and tests of the apparatus are planned.

The experiment is scheduled to run during three six week reactor cycles this year. Set up and shakedown of the experiment was completed during the first cycle. Production data taking is scheduled to begin in February during the second reactor cycle.

Footnotes and References

*Present address: Abacus Concepts Incorporated

†The emiT collaboration institutions are: Lawrence Berkeley National Laboratory, University of California at Berkeley, University of Michigan, National Institute of Standards and Technology, Notre Dame University, Los Alamos National Laboratory, and University of Washington.




Fig. 1. A plot of proton detector energy versus coincidence time shows clearly the large prompt events, mostly from background gamma rays. Delayed proton coincidences show up to the left of the prompt events in this figure. The enhancement at 0.5 microseconds delay is from neutron decay.

Test of time reversal invariance violation in the beta-decay of ^{56}Co

J. L. Mortara*†, J. C. Davist, S. J. Freedmant‡

Since the detection of CP violation in the neutral kaons,¹ there have been many attempts to detect the implied T violation in low energy phenomena. To date these searches have yielded no positive results, and for tests involving the beta-decay of the neutron the limits on T violation are quite small and are approaching limits of 10^{-4} .² Of course, without a good idea of the mechanism for T violation, present results do not rule out the existence of large effects in other systems.

The present work on ^{56}Co is motivated by the idea that T violation might appear through a mechanism that experiments involving allowed nuclear beta-decay are not sensitive to. One possibility is the existence of T violating second class currents. For the allowed decays of the neutron and ^{19}Ne , the dominant terms must be first class and hence any second class term would be kinematically suppressed.




Fig. 1. The decay scheme of ^{56}Co .

In the decay of ^{56}Co this is not the case. Since it involves the decay between two different isospin multiplets (Fig. 1), the dominant terms need not necessarily be first class. The current limit on T violation in ^{56}Co is at the level of 10^{-2} . We intend to improve this by at least an order of magnitude.

The relevant correlation for the detection of TRIV is of the form $E1(J \cdot k)(J \cdot p \times k)$, where J is the nuclear spin, k is the gamma-ray momentum and p is the beta-momentum. The required

alignment will be achieved by low temperature nuclear orientation with an Oxford Kelvinox 400 that has been assembled and reaches temperatures of 5 mK. Unlike the previous effort,³ this dilution refrigerator will be capable of maintaining a stable temperature for weeks in a single run. The gamma-rays from the excited state of ^{56}Fe will be detected by conventional NaI(Tl) detectors. Besides stable refrigeration, the experiment has been improved by the development of a Si detector that operates at mK temperatures.⁴ This allows the detector to be placed very near the ^{56}Co source. A spectrum from ^{207}Bi is shown in Fig. 2. Results will be obtained by late 1997.




Fig. 2. Spectrum of ^{207}Bi with Si detector operated at 100 mK.

Footnotes and References

*P-23 Neutron Science and Technology, Los Alamos National Laboratory

†Department of Physics, University of California at Berkeley

‡Nuclear Science Division, Lawrence Berkeley National Laboratory

1. Christenson *et. al.*, Phys. Rev. Lett. **13**, 138 (1964).

2. E. G. Wasserman, thesis LA-12735-T.

3. Calaprice *et. al.*, Phys. Rev. C **15**, 381 (1977).

4. We gratefully acknowledge the support of B. Young for the fabrication of this device.

Atomic Parity Nonconservation in Stable Yb Isotopes

C.J. Bowers, D. Budker, E.D. Commins, D. DeMille, S.J. Freedman,
G. Gwinner, S.-Q. Shang, and J.E. Stalnaker

The weak interaction, best known for its role in nuclear beta decay, also plays a minor role in the electronic structure of atoms. Atomic structure is dominated by the electromagnetic interaction, which conserves parity (mirror reflection symmetry), whereas the weak interaction does not. Measurement of parity nonconserving (PNC) effects in atoms allows one to observe the weak interaction in a system dominated by the electromagnetic interaction. The study of atomic PNC, which is due to the weak neutral current (Z-exchange), complements the study of nuclear beta decay, which results from the weak charged current (W-exchange).

The $(6s^2)1S_0 \rightarrow (6s5d)^3D_1$ transition in atomic Yb is a promising system for the study of PNC¹. The E1 transition amplitude is strictly forbidden by the parity selection rule, while the M1 amplitude is highly suppressed. The application of an external electric field mixes even and odd parity states, giving rise to a Stark-induced amplitude (E1_{st}). The weak interaction also mixes even and odd parity states, giving rise to a parity nonconserving amplitude (E1PNC). In order to measure a very small E1PNC, one observes the interference between the much larger E1_{st} and E1PNC, as one excites this forbidden transition with intense laser light. The parity violating effect in Yb is expected to be very large, due to the near degeneracy of two states of nominal opposite parity.

Precise measurements of PNC in single isotopes of Cs² and Tl³, when combined with atomic structure calculations, have led to a determination of the weak mixing angle ($\sin^2\theta_W$), rivaling those obtained from high energy physics experiments. Measurement of PNC in a single isotope of Yb will not be competitive with Cs or Tl, because the uncertainty in the calculation of the atomic structure of Yb is large. However, Yb has seven stable isotopes. The dominant contribution to

atomic PNC comes from the electron-nucleon interaction, and one expects the effect to be roughly proportional to the neutron number, N. Comparing PNC effects in several isotopes of Yb may allow us to extract information about the weak interaction independent of the atomic structure. The PNC effect for a given isotope also depends on the distribution of neutrons within the nucleus, a nuclear property not readily accessible by other means. In addition, comparison of PNC effects in the different hyperfine components of the two odd A isotopes of Yb allows a determination of the nuclear anapole moment.

The past year has seen the publication of Yb lifetime measurements⁴ and the first observation of the forbidden transition used in the study of PNC in Yb, as shown in Fig. 1.

Footnotes and References

1. D. DeMille, Phys. Rev. Lett. **74**, 4165(1995).
2. M.S. Noecker, B.P. Masterson, and C.E. Wieman, Phys. Rev. Lett. **61**, 310 (1988).
3. P.A. Vetter *et al.*, Phys. Rev. Lett. **74**, 2658 (1995).
4. C. J. Bowers *et al.*, PRA **53**, 3103(1996).




Fig. 1. Fluorescence signal from the forbidden M1 transition in ytterbium in a 45 kV/cm electric field. The peaks correspond to individual isotopes and hyperfine components.

Experimental Study of the ^8B Neutrino Spectrum

S.J. Freedman^{*}, K. E. Rehm[†], B.K. Fujikawa[‡], G. Gwinnert[†], B. Harss[‡], C. L. Jiang[‡], M. Paul[§], R. C. Pardo[‡], J. P. Schiffer[‡], S. Q. Shang[†], and P. Vetter[†]

The principal source of high energy neutrinos from the Sun is the beta decay of ^8B produced by nucleosynthesis deep in the solar interior. The exact shape of the emitted neutrinos from ^8B is of current interest because of plans to measure the solar-neutrino energy spectrum directly in the SNO and SuperK detectors. Distortions from the primitive spectrum may provide evidence of "matter enhanced neutrino oscillations" in the solar interior.

The beta decay of ^8B is allowed but both the beta and neutrino energy spectrum deviate significantly from an ordinary allowed decay. The decay proceeds primarily to the unbound first excited state of ^8Be at 2.9 MeV which decays to two alpha particles. The distortion is due to the broad and complicated energy profile of the final state.

In the past the neutrino spectrum has been calculated from measurements of the delayed alpha spectrum and in one case from constraints imposed from measurements of the beta spectrum¹. Recently, Bahcall et. al² reviewed all the available experimental data attempting to predict the 8B neutrino spectrum and establish the uncertainty with which it is known. It is pointed out in that work that the five existing measurements of the alpha spectrum are in poor agreement. While the basic shape of the spectra are similar there are discrepancies of about 80 keV in the energy scales, making it difficult to assess the overall systematic uncertainty.

We proposed to measure the alpha spectrum directly using the novel technique of implanting ^8B in a silicon detector. In previous experiments ^8B was implanted in thin metallic foils. We suspect that the discrepancies in the energy scales of the various experiments are due to the difficulties of correcting for energy losses of the alpha particles and uncertainties in the distribution of the ^8B in the foil. Our technique

will avoid these uncertainties. The experiment makes use of the Enge Spectrograph at ATLAS and a new technique of producing secondary beams with a gas cell target. In this case we use the $^6\text{Li}(^3\text{He},n)^8\text{B}$ reaction. The experimental plan was developed this year and the proposal was recently approved by the ATLAS PAC to run this Spring at Argonne.




Fig. 1 Delayed alpha particle spectra from previous experiments.

Footnotes and References

[†]Lawrence Berkeley National Laboratory

^{*}University of California at Berkeley

[‡] Argonne National Laboratory

[§] Hebrew University, Jerusalem

1. J. Napolitano, S. J. Freedman, and J. Camp, Phys. Rev. C36, 298 (1987)
2. J. N. Bahcall, et al, Phys. Rev. C58, 411, (1996).

Search for Narrow Positron Emission Lines in Heavy Ion Collisions with APEX

Stuart Freedman, Michael Maier, as part of the Apex collaboration

Motivation

The apparent discovery of narrow positron emission lines in two separate experiments at the GSI, Darmstadt has been an object of intense investigation for nearly two decades. The signal reported in both singles and in other experiments with electrons detected in coincidence were taken as potential evidence for the decay of a new light neutral particle or other exotic phenomena. The APEX collaboration built a sensitive spectrometer at the ATLAS facility at Argonne to help discover the explanation for the surprising effect.¹

Experiment

During experimental runs in 1995 we searched for the previously reported effect in the reaction $^{238}\text{U} + ^{232}\text{Th}$ at 5.95 MeV/u and the reaction $^{238}\text{U} + ^{181}\text{Ta}$ at 5.95, 6.10 and 6.60 MeV/u. We searched the data for evidence of narrow structures in the positron singles spectrum and the positron-electron coincidence energy spectrum. Using analysis techniques motivated by the previous experiments we failed to find any effects consistent with the previous positive reports.² Figure 1 shows the electron-positron sum energy spectrum from the $^{238}\text{U} + ^{232}\text{Th}$ reaction with APEX and the resulting limits. Since the publication of this work, the EPOS experiment at GSI has reported that they have been unable to reproduce their previous findings with a more sensitive apparatus.

There are no plans to continue these searches at the present time. Other uses for the APEX spectrometer are under consideration.




Fig. 1. Sum-energy spectra for $^{238}\text{U} + ^{232}\text{Th}$ and the upper limits. The dashed peak represents the size of the effect expected from the previous experiments.

Footnotes and References

The APEX collaborating institutions consist of: Argonne National Laboratory, Florida State University, Lawrence Berkeley National Laboratory, Michigan State University, Princeton University, Rochester University, University of Washington, and Yale University.

¹I. Ahmad, *et al.* Nuclear Instruments and Methods A **370**, 539 (1996)

²I. Ahmad, *et al.* Phys. Rev. Lett. **75**, 2658 (1995)

Studying New Physics Using Ultrahigh-Energy Cosmic-Ray γ -Family Data*

Y. D. He

This paper discusses some recent developments in the study of ultrahigh-energy interactions using cosmic-ray γ -family data obtained with emulsion chambers at mountain altitudes. The apparent excess of the event rate at large transverse momenta with respect to the prediction based on perturbative QCD indicates new interaction mechanisms at $E_{\text{lab}} \simeq 10^4\text{--}10^5$ TeV, an energy regime beyond the reach of existing colliders. To reconcile the data with a compositeness model of quarks, the characteristic energy scale would have to be as low as $\Lambda_c \leq 0.1$ TeV, in conflict with the lower limit of $\Lambda_c > 1.4$ TeV or a possible value of $\Lambda_c \simeq 1.6$ TeV obtained by the CDF experiment at Tevatron. Possible new physics beyond the standard model, together with future experiments at the LHC, are also discussed.

*Abstract of an invited review paper in *Modern Physics Letter A* 11 (1996) 2013-2026.

Search for Dirac Magnetic Monopole Production in High Energy Heavy Ion Collisions*

Y. D. He and P. B. Price

Extensive searches for monopole pair production in e^+e^- , pp , and $\bar{p}p$ collisions have been performed at various high energy colliders. In each of these, an upper limit on its production cross section has been placed. In all these collisions, the monopole pairs are expected to be produced via Drell-Yan mechanism. In AA collisions, the thermal production of monopole pairs has also been predicted in addition to Drell-Yan.

We exploit a useful feature of the BP-1 track-recording glass: its sensitivity can be tuned by a suitable choice of chemical etchants. Our detector consisted of 17 sheets of BP-1 glass and a Pb target. Two of the BP-1 plates were placed in front of the target and 15 downstream. For particles with $Z/\beta > 84$, we measured their instantaneous values of Z/β along their paths. With measurements of Z/β as a function of penetrating depth, we were able to determine Z and β .

In a search for Lee-Wick matter, we found nine events with $Z/\beta > 82$. All of them were slowing particles ($\beta < 0.79$) from interactions of beam particles with pipe or air. None of the candidates has dE/dx that matches that predicted for a magnetic monopole with $n = 2$.

Based on a null result in $\sim 10^9$ interactions of 11 A GeV Au with a Pb target, we can place an upper limit on its production cross section: $2 \times 10^{-32} \text{ cm}^2$. No one has realistically calculated the cross section for monopole production. The

Drell-Yan cross section serves as a rough point of reference for production of monopole pairs via an intermediate massive virtual photon, multiple virtual photons, or gluon-gluon fusion.

At BNL AGS, we are currently analyzing a new search in $\sim 10^{11}$ Au on Pb interactions at ~ 11 A GeV. With this new experiment, we expect to achieve an improvement of ~ 2 orders of magnitude in sensitivity. We have also proposed a new search at CERN SPS using the high intensity Pb beam at 160 A GeV.




Figure - Upper limit to the production cross section for Dirac monopole pair in heavy ion collisions.

*Condensed from a paper in the Proceedings of 24th International Conference on Cosmic Rays, Rome, Italy 1 (1995) 845-848.

Measurement of Low Energy Ion Tracks in CR-39 Plastic with An Atomic Force Microscope*

Y. D. He and C. I. Hancox

We demonstrate that an atomic force microscope allows one to measure the detailed geometry of etch pits due to heavy ions with kinetic energies of 1 – 10 keV/amu at small distance scales registered in the nuclear track detector CR-39 plastic. With a typical range of a few hundred nm and an etch pit depth on the orders of a few tens of nm, these ion tracks cannot be measured using conventional methods. With the technique developed in this work one is able to study the response of CR-39 plastic to particles at low ionization rates by precise measurements of low energy ion tracks. Among other applications, of particular interest is to explore the response of CR-39 in the regime in which nuclear stopping is comparable to electronic stopping.

*Abstract of a paper in *Review of Scientific Instruments* 66 (1995) 4575-4582.

Low-background Counting Facilities

A.R. Smith, R.J. McDonald, D.L. Hurley, and E.B. Norman

The LBNL Low Background Facilities (LBF) consist of a Berkeley site and an Oroville site specially configured for low-background gamma-ray spectroscopy. The Berkeley site was established in 1963 and consists of a 3m by 7m x 3m room surrounded by 1.6m of specially-selected low-background concrete shielding. The aggregate in this concrete is from serpentine gravel which is low in U, Th, and K. This barrier was made to shield against accelerator-produced neutrons and natural gamma radiation as well as some cosmic rays. Also, the low-activity concrete emits little radon, and a HEPA-filtered air system constantly purges the room to reduce airborne radon.

Detectors at this site include a 20 cm diameter by 10 cm thick NaI crystal, two 30% p-type Ge spectrometers (one of these with an external active cosmic ray suppresser), an 80% p-type Ge spectrometer and a 55% n-type spectrometer suitable for low-energy gamma-ray and X-ray measurements. These detectors each have small local shields consisting of 10 cm of Pb. The overall shielding reduces background to the point where internal activity in the detectors and cosmic-rays are the dominant source of background.

The LBF Oroville site is located in the powerhouse of the Oroville Dam, under 180 m of rock cover. This site now has a 115% n-type and a 30% p-type Ge spectrometer and is used for our most sensitive counting. Sensitivities of 50 parts-per-trillion (PPT) for U and daughters, 200 PPT for Th and daughters, and 100 parts-per-billion for K are realized at the Oroville site.

The LBF has been involved in a wide variety of experiments supporting programs from LBNL and a variety of other institutions. There are five main types of work the facility supports: low-activity materials certification, cosmic ray activation, neutron activation, nuclear science experiments and environmental health and safety activities. The ongoing materials certification work is for two large detector projects: SNO and the UCB Dark Matter Search. A variety of stock materials and components were surveyed for these projects. Cosmic-ray

activation work, begun with the LDEF and HST, continued with a Pb-glass sample from Mir and a stainless steel sample from another Russian satellite. The latter study involved looking for excess Be-7 on the earth-facing side of the sample. Neutron Activation Analysis work continued on semiconductor-grade silicon, and verified parts-per-trillion sensitivity to 29 elements in wafer-sized samples (Ref. 1). A new initiative was begun with biological samples. Selenium-laden bacteria and sludges were studied as proof-of-principle for a program in bioremediation. Uranium uptake was measured in another bacterial sample. The facility supported research aspects of the Nuclear Astrophysics Group including looking for electron density effects on the half-life of ^{40}K , a half-life determination of ^{108}Ag , and measurements of a large sample of ^{150}Nd separated isotope proposed to be used in a double beta decay experiment. An additional program involved developing mixtures of natural La, Lu, and K as a "non-radioactive" calibration source. A substantial amount of the facility's time was involved with Environmental Health and Safety work. This included a major radiological survey of the building and site of the new waste handling facility, Building 85, measurements of sub-surface soils under the BEVALAC, characterization of concrete shielding blocks for disposal, and measurements of a variety of samples in support of the ES&H analytical lab.

During the coming year, new projects screening materials for semiconductor manufacturing are proposed, including both direct counting and neutron activation. Work in support of bioremediation is expected to increase. Cosmic-ray activated parts are expected from the second HST servicing mission in February 1997. Characterization work on LBNL radioactive and mixed waste will increase.

Footnotes and References

1. A.R. Smith, R.J. McDonald, H. Manini, D.L. Hurley, E.B. Norman, M.C. Vella, and R.W. Odom: *J. Electrochem Soc.* **143** (1996) 339-346

Low-background Gamma-ray Spectroscopy Applied to Measuring the Uptake of Metals by Bacteria

A.R. Smith, R.J. McDonald, D.L. Hurley, and E.B. Norman

Low-background gamma-ray spectroscopy offers a sensitivity to U of 10 micro-grams of depleted U and 100 nano-grams of ^{235}U by direct counting. Following neutron activation, sensitivities of 0.01 nano-grams have been observed for 29 elements in semiconductor-grade silicon [1], and should be similar for pure life-elements (H, C, N, O). In real organisms, this sensitivity will be reduced due to trace elements such as Na and Fe. However, the sensitivity to per-cent level uptakes in micro-gram sized samples or PPB sensitivities in gram-sized samples should have many applications in studying the uptake of metals by bacteria. Two proof-of-principle experiments follow:





Figure 1 shows a gamma-ray spectrum observed from a 0.055 g sample of *p. aeruginosa* bacteria which absorbed 1.55 mg (2.8%) of (depleted) U. Characteristic gamma-ray lines at 63 and 92 keV are observed from the decay of the 24.1 day half-life ^{234}Th (the first daughter of ^{238}U) and at 185 keV from ^{235}U . Observed over 30 days, the Th activity "grows in" to a level of 2.8% of the sample mass by weight. Not knowing the relative abundance of ^{235}U compared to ^{238}U in the depleted solution, there was no way to

correlate this measurement with that from ^{235}U as a check. This technique can be used, for example, to screen large numbers of bacteria and characterize their ability to take up U as a function of variables such as pH and concentrations of other elements in the growth medium.

Figure 2 shows a gamma-ray spectrum observed following neutron activation of 0.84 mg Se absorbed by 20 mg of bacteria (4.2%). Since most of the bacteria is composed of H, C, N, O, the background is favorably low. Fe, at the 0.2% level is observed, and Compton-scattered gamma rays reduce somewhat the sensitivity to Se compared to pure H, C, N, O or Si. Again, because of the accuracy and the small sample size, this technique can be used to determine uptake in large numbers of samples as functions of a number of variables, including other contaminants such as Cr, in the growth medium.



Footnotes and References

1. A.R. Smith, R.J. McDonald, H. Manini, D.L. Hurley, E.B. Norman, M.C. Vella, and R.W. Odom: J. Electrochem Soc. 143 (1996) 339-346

Low-Level Measurement of Alpha-Particle Emitters in Ceramics and Metals

A.R. Smith, R.J. McDonald, D.L. Hurley, and E.B. Norman


Nearly all natural materials contain trace quantities, typically in the PPM range, of U and Th. Even processed materials often contain these elements in the PPB range. These radioactive elements decay via complex alpha and beta decay chains, forming 11-15 daughter nuclides each, many of which emit alpha particles in their own decay. When close enough to sensitive electronic components, such as transistors in an IC chip, they can disrupt the normal operation of processors or memory.

Direct alpha counting techniques using solid state or gas-filled detectors can be used to measure activity, but this method is only sensitive to a 0.01-0.03 mm surface layer and, unless even much thinner films are used, provides only a count rate and not spectrographic information. Besides examining only a small part of the material, alpha detection rates are low and can be distorted by contamination, i.e. from radon in the air.


For the assay of U and Th in materials, at the PPB level, low-background gamma-ray spectroscopy is a very sensitive and isotope-specific method for determining the bulk concentrations of these radionuclides in essentially all solid and liquid materials, including ceramics, metals, plastics, and etchants. While some of the U- and Th-series alpha-emitters are not detected directly, the gamma-ray evidence correctly indicates the present levels of alpha-activity, and also provides accurate predictions for how the alpha-activity may change with time. 5 kg samples provide adequate counting rates at the PPB level for 1 day counting times.

For the analysis of ^{210}Pb in Pb, thinner samples are required to measure the characteristic 46 keV gamma ray, but counting rates are similar to those for alpha counters, spectrographic information is obtained, and no wait is needed for the ingrowth of ^{210}Po .

The low-background facility is presently seeking an industrial partner to work on these problems. The 115% n-type detector at the LBF underground Oroville site has the sensitivity to measure 10 Bq/kg levels in 100 g samples of Pb and 1 PPB levels of U and Th in 5 kg samples of metals or ceramics.



Relativistic Nuclear Collisions



Δ Resonance Production in $^{58}\text{Ni} + \text{Cu}$ Collisions at $E=1.97 \text{ A GeV}$

E.L. Hjort and the EOS Collaboration

In heavy-ion collisions above 1 A GeV a significant fraction of the baryonic content is in the form of resonances, primarily the Δ resonance. Using data taken with the EOS TPC we have performed invariant mass analyses of (p, π^\pm) pairs which show correlations resulting from the decays of the Δ resonance, the Λ baryon and the $N^*(1440)$ resonance. A reduction in the Δ mass which is maximized in central collisions is seen, and this feature is related to the size of the reaction volume and the production mechanisms of the Δ resonance.




Figure 1:

The Δ^{++} resonance [a]; the Δ^0 and N^* resonances and Λ peak [b].

Figures 1a and 1b show the Δ^{++} and Δ^0 resonance content of the data along with the best-fit Breit-Wigner functions. In the case of the Δ^0 a second Breit-Wigner function has been included to account for $N^*(1440)$ decays. Decays of the Λ hadron into a (p, π^-) pair produce the narrow peak in two channels at $\sqrt{s} \approx 1.116 \text{ GeV}/c^2$. The fact that the Λ mass is correct confirms the absolute momentum calibration of the TPC.

The negative(positive) values in Fig. 1a(b) at $\sqrt{s} < 1.12 \text{ GeV}/c^2$ result from the Coulomb repulsion(attraction) of the $(p, \pi^+(\pi^-))$ pair.




Figure 2: The Δ^{++} resonance for 5 multiplicity (M) bins [a]; and the mass [b], width [c], combinatoric background [d], yield [e] and the Δ^{++} to π^+ ratio [f] versus impact parameter.

The Δ^{++} has also been analyzed according to the charged particle multiplicity of each event. Fig. 2a shows the resulting fits for each of 5 multiplicity bins, and Figs. 2b-e show related quantities as a function of impact parameter. A mass reduction is observed in all bins and the reduction increases by about $50 \text{ MeV}/c^2$ from the most peripheral collisions to the most central collisions. A larger reaction volume in central collisions increases the proportion of Δ 's which are produced by pion scattering ($\pi N \rightarrow \Delta$), a process which has less available energy and populates a lower mass region of the resonance relative to initial nucleon-nucleon collisions ($NN \rightarrow \Delta N$), resulting in the observed mass shift.

Dielectron Production in A-A Reactions at 1.0 A·GeV

R. Jeff Porter and the DLS Collaboration

Measurements of dielectron production in nucleus-nucleus collisions offer a unique probe into the dynamics of heavy-ion reactions. Dielectrons are not subject to the same rescattering rates within the collision as hadronic participants and can yield direct information about internal properties of the reacting system. Important features such as baryon resonance formation, sub-threshold meson production (η , ρ , and ω), and $\pi^+\pi^-$ annihilation have been predicted to contribute to dielectron production at Bevalac energies[1]. Dielectron production measurements have yielded interesting results at both Bevalac[2] and SPS[3] energies where unresolved differences between the data from p-A and A-A collisions have been found.




Figure 1: Dielectron cross sections in A-A systems at 1.0 A·GeV.

The Dilepton Spectrometer (DLS) Collaboration has performed dielectron cross section measurements in Ca+Ca, C+C, He+Ca, and d+Ca reactions at 1.0 A·GeV. The invariant mass spectra, $d\sigma/dM$, from the four measurements are shown in Fig. 1. A common shape to the four spectra at low mass includes a large signal below the pion mass suggesting π^0 Dalitz decays and a distribution in the 0.2-0.4 GeV/c^2 mass region resembling that predicted from η Dalitz

decays[1]. The cross sections in this low mass region are found to scale in proportion to the product of the projectile and target numbers, $d\sigma/dM \sim (A_p \cdot A_t)^{1.0}$.

A direct comparison of the cross sections from Ca+Ca and C+C reactions is shown in Fig. 2 as the ratio in the measurements as a function of the pair mass. The low-mass scaling with $(A_p \cdot A_t)^{1.0}$ is illustrated by the dashed line in the figure marking the $A_p \cdot A_t$ ratio value. For $M \geq 0.5 \text{ GeV}/c^2$, the ratio increases significantly indicating that a density dependent mechanism(s) is exhibited in the high-mass cross section.




Figure 2: Cross section ratio from Ca+Ca and C+C reactions.

References

- [1] G. Wolf et al., Prog. Part. Nucl. Phys. **30**, 273 (1993); K.K. Gudima, Sov. Jour. of Nucl. Phys. **55**, 1715 (1992); E.L. Bratkovskaya et al., Phys. Lett. **B376** 12 (1996).
- [2] G. Roche et al., Phys. Lett. **B226**, 228 (1989).
- [3] G. Agakichiev et al., Phys. Rev. Lett. **75**, 1272 (1995).

The E895 experiment at the AGS

G. Rai and the E895 Collaboration

The acceleration of Au beams at the Brookhaven National Laboratory's AGS accelerator facility has made it feasible to investigate the bulk characteristics of nuclear matter and its Equation of State (EOS) at high energy and baryon density. Latest experimental data and theoretical calculations on collective phenomena at low beam energies suggest that highest compression of nuclear matter might occur in the 2-10 A GeV energy range. Moreover, the potential for interesting new physics exist in the form of resonance matter and signals of phase transitions such as QGP[2] and chiral symmetry restoration[3].

The E895 experiment has, for the first time at the AGS, carried out an excitation study of Au induced reactions in fine detail. Specifically, E895 is currently studying particle production yields and cross-sections, global characteristics and energy spectra, multiparticle correlations, directed flow in symmetric and asymmetric systems, radial flow and squeeze-out of light fragments, pion production and shadowing (anti-flow) effects, and strangeness production.

E895 has the unique ability to measure the four-momentum of light mass particles, projectile fragments from $Z=6$ to $Z=79$, and anti-particle production. All of the data was collected on an event by event basis from a Time Projection Chamber (EOS TPC). The EOS TPC provides continuous tracking, almost 4π acceptance and particle identification for the light mass particles. Projectile fragments are identified in a multiple ionization sampling device called MUSIC. In this way full event reconstruction allowed simultaneous measurement of many experimental observables.

The E895 experiment[1] was made operational at BNL and, in December 1995, had a successful first run using low energy Au beam from the AGS. High statistics data was recorded using the

2 and 4 A GeV Au beams impinging on a Au target, and with less statistics on Ag, Cu and Be targets. During the second run in 1996 data was recorded at 6 and 8 A GeV using the same combination of targets.

Preliminary online analysis showed good dE/dx particle identification in the TPC. The $p, d, ^3H, ^4He, K^+$ and pion bands were visible over a wide rigidity range. Multiplicity and rapidity distributions along with transverse momentum spectra were also extracted from the uncalibrated data. Figure 1 is representative of the quality of pion data and highlights the very low P_t acceptance of the experiment. A complete offline data analysis effort is now underway at LBNL utilizing the Parallel Distributed Scientific Farm (PDSF) at NERSC.




Figure 1: Pion P_t spectra at 6 A GeV for Au+Au collisions plotted for various rapidity intervals

References

- [1] G. Rai et al., AGS Proposal, LBL-PUB-5399, 1993
- [2] D. Rischke, Proc. HIPAGS,(1996),138
- [3] B.A. Li and C.M. Ko, Nucl. Phys. A601,(1996),447

Rare Processes in Relativistic Heavy Ion Collisions--Results from BNL E878

M.J. Bennett, J.B. Carroll, H. Crawford, M. Cronqvist, J. Engelage, I. Flores, L. Greiner, T.J. Hallman, H.H. Heckman, C. Kuo, P.J. Lindstrom

E878 is a high sensitivity search experiment, designed to investigate rare processes in relativistic heavy ion collisions, e.g. antibaryon production and the formation of new, previously undiscovered particles. The experiment was conducted at the Alternating Gradient Synchrotron (AGS) at Brookhaven National Laboratory, and is a follow-on to experiment E858. Data were recorded using Au beams on various nuclear targets during the spring of 1992 and the fall of 1993. Over the course of the last two years, analysis of this data has been completed, resulting in several publications and one Ph D thesis.

The primary goal of E878 was a search for strangelets, which are multi-quark hadrons made of roughly equal number of u, d and s quarks which have been predicted to be stable. E878 was sensitive to strangelets up to $A=30$ (90 quarks) with lifetimes of ~ 100 ns or longer. Our search yielded no strangelet candidates. Sensitivities for positively charged strangelets are shown in figure 1; similar sensitivities were reached for negatively charged strangelets.




Figure 1. The sensitivity of E878 for the detection of charge +1, +2 strangelets. The three curves are 90% sensitivity upper limits based on specific models of strangelet production. Strangelet predictions of Crawford *et al* are shown as triangles and hypernuclei predictions of Baltz *et al* are shown as squares. [1 and references therein]

The biggest improvement in E878 over its fore-runner E858 is the ability to measure the centrality of the nucleus-nucleus collision producing the detected particle. This information has been used to investigate pion and kaon production cross sections, as well as a study of the formation of light nuclei as a function of centrality. Manuscripts of these studies are in the final stages of preparation.

The most interesting use of centrality information in E878 is in the study of antiproton production. As shown in Figure 2, the E878 data differed widely from theoretical predictions for models which heretofore had been quite successful in matching particle spectra. This result has spurred new thinking about how the antiproton annihilation process proceeds in the hot, dense environment of central Au + Au collisions.

Footnotes and References

- 1 D. Beavis *et al*, Phys. Rev. Lett. 75, 3078 (1995)
- 2 D. Beavis *et al*, Phys. Rev. Lett. 75, 3633 (1995)




Figure 2. The invariant multiplicities of antiprotons measured in Au + Au collisions plotted as functions of rapidity for four non-overlapping centrality bins. The data are shown as symbols, RQMD calculations as solid lines and ARC calculations as dashed lines. [2 and references therein]

Development of a Distributed Drift Chamber for BNL E896

J. Engelage, M.J. Bennett, J.B. Carroll, H. Crawford, M. Cronqvist, I. Flores, L. Greiner, E. Judd, P.J. Lindstrom, J. Marx, I. Sakrejda, and G. Visser

Experiment 896 (E896) is a search for the H_c (a six quark, neutral charged, short-lived strange dibaryon state) in nucleus-nucleus (AA) collisions at the AGS. The primary detector in this experiment is a large volume tracking detector located in a 1.5T field. A superconducting magnet will be utilized to sweep the beam and charged secondaries away from the area occupied by neutral particles. The tracking detector has been designed to unambiguously identify the topological signature of particle decays and provide enough track information to reconstruct the rigidity of each charged particle produced. A Distributed Drift Chamber (DDC) was determined to be the optimum tracking detector for this application, capable of higher event rates than a TPC and better spatial resolution than an MWPC.

The design of the 144 plane DDC relies heavily on GEANT-based simulations¹. A 2mm wire spacing was determined to be sufficiently large to avoid electrostatic breakdown and still achieve the double track resolution required to resolve the $\Sigma+p$ decay channel of the H_c . A granularity of 0.6 cm along the beam direction allows for multiple measurements along the short lived sigma track while maintaining a reasonable total depth of the detector to increase momentum resolution. Conductive kapton foil High Voltage planes were used because the low Z material reduces the delta ray background and foils facilitate transitions between different sense wire orientations. A 3cm diameter hole was cut in the foils to reduce background from passage of beam through a non-active region of the chamber. A Helium-based gas, He:C₂H₆ (50:50), was chosen to reduce the amount of δ -rays and secondary interactions produced in the gas by the uninteracted beam and projectile fragments. It is expected that the effect of the magnetic field on the drift velocity of this "cooler" helium-based gas will be less than that experienced in the "hotter" Argon-based gases. However, the effect of the magnetic field will reduce the pulse height and distort the drift paths which has been a concern².

In June 1996 a Prototype Drift Chamber (PDC) using He:C₂H₆ was tested in a 1.65T field at the AGS. The PDC consisted of 3 full size DDC planes. The PDC resolution was measured to be 2.8ns, cor-

responding to a spatial resolution of $\sim 100 \mu\text{m}$ (the effective drift velocity being $\sim 35 \mu\text{m}/\text{ns}$). The efficiency for most of the volume of the drift cell was determined to be $\sim 99\%$. The distortion of the drift region by the magnetic field caused the efficiency at the edges of the cell to be reduced to $\sim 75\%$.

It is important for the analysis to be able to simulate these effects. Using the CERN packages GEANT and GARFIELD, along with a time to TDC interpolation code³, we are able to reproduce the data quite well, as shown below. The simulations clearly reproduce all the major features of the measured data.

The results of the testbeam show 1) that the response of the He:C₂H₆ gas in the presence of the magnetic field is more than sufficient for our application 2) the distortion of the drift lines is consistent with the GEANT/GARFIELD simulations 3) the resolution is within the tolerances set by the GEANT simulations and track reconstruction algorithms developed for this experiment.




Figure 1. TDC distributions of neighboring wires from X and X' planes for simulated and testbeam data. Testbeam data was produced by 10GeV/c, $Z=+1$ particles at normal incidence to the PDC.

Footnotes and References

1 I. Sakrejda, LBL-37384 UC-413, 125 (1995).

2 Becker, NIM A335, 439 (1993).

3 <http://centauri.lbl.gov/~mats/e896/digit.html>

Spectroscopy of Scalar Mesons with the Crystal Barrel Detector

*K.M. Crowe, T. Case, F.H. Heinsius, P. Kammel, M. Lakata
and the Crystal Barrel Collaboration*

Three new scalar mesons have been observed by the Crystal Barrel experiment at LEAR(CERN) in the analysis of high statistics/high precision data on $\bar{p}p$ annihilation into three neutral pseudoscalars¹. The Crystal Barrel detector allows the complete reconstruction of $\bar{p}p$ annihilations into charged as well as neutral final states. Its main components are a multiplicity trigger, a Jet Drift Chamber (furnished by the Berkeley group) and a CsI(Tl) calorimeter.

These new results led to a major revision of our understanding of the $J^{PC} = 0^{++}$ scalar meson sector². An alternative model for the classification of scalar states is discussed where the new scalars $f_0(1370)$, $a_0(1450)$ replace the well established states $f_0(980)$ and $a_0(980)$ as members of the $J^{PC} = 0^{++}$ ground state nonet. The $f_0(1500)$ is supernumerary in all classification schemes and difficult to interpret as a $q\bar{q}$ state.

This experimental progress is of particular relevance in the search for exotic meson resonances containing constituent gluons g (in particular gg states called glueballs) which are suggested by the strong gluon self coupling in QCD. The discovery of gluonic mesons would directly demonstrate the unique features of strong QCD. During the last years large scale lattice QCD calculations succeeded in quantitative predictions for glueball masses and even provide some guidance on their properties. They firmly predict the ground state glueball as an isoscalar, scalar object in the 1.5–1.8 GeV mass region.

Several papers and arguments appeared recently which identify the new state $f_0(1500)$ as a promising candidate for this long-sought scalar glueball. However, another contender, the

$f_J(1710)$, is hotly debated as well. More information about decay couplings and production reactions of these states are needed for definite conclusions.

Our recent work focussed on establishing the properties of the $f_0(1500)$ using both new data (higher statistics and new channels) as well as coupled channel analyses of several related data sets. We obtain a mass and width of $m = (1505 \pm 10)$ MeV and $\Gamma = (135 \pm 15)$ MeV and the following invariant couplings to the different pseudoscalar states relative to $\pi\pi$:

$\eta\eta$	$K\bar{K}$	$\eta\eta'$
0.27 ± 0.11	$0.24 \pm 0.10^{+0.13}_{-0.05}$	0.19 ± 0.08

The decay into 4π is found to be the dominant decay mode of the $f_0(1500)$, being (3.4 ± 0.8) times more frequent than 2π decays³.

In order to further clarify the quark-gluon content of these new scalar mesons, it is essential to systematically study their $K\bar{K}$ coupling with similar precision as their coupling to π^0 and η . For that purpose the Crystal Barrel detector was upgraded with a new silicon vertex detector with allows a highly selective trigger on K_S decays.

With this method we were able to increase the world statistics on K_S channels in liquid/gaseous hydrogen and in liquid deuterium by 1-2 orders of magnitude⁴. The key information for $K\bar{K}$ decays of intermediate scalar resonances is contained in the $K\bar{K}\pi$ final states, where we expect $(2 - 5) \times 10^4$ events (depending on reaction) in the final Dalitz Plots. These data are currently being analyzed in Berkeley.

Footnotes and References

¹C. Amsler et al., (CBAR-Coll.), Phys. Lett. B355 (1995) 425, and references given there.

²c.f. Review of Particle Physics, R.M. Barnett et al., Phys. Rev. D 54 (1996) 1.

Footnotes and References

³A. Abele et al. (CBAR-Coll.), Phys. Lett. B380,(1996) 453.

⁴P. Kammel et al., (CBAR-Coll.), PANIC 96, Williamsburg, 1996.

Measurement of Rare $\omega \rightarrow \eta\gamma$ Radiative Decay*

Mark Lakata, Ken Crowe, Tom Case, Peter Kammel, Fritz-Herbert Heinsius

The radiative decays of vector and pseudoscalar mesons are useful tests of the simple quark model and its extensions. In the family of the eleven vector meson to pseudoscalar meson decays, the decay of ω into $\eta\gamma$ is one of the least well measured because of its very small branching ratio into neutral final states.

The Crystal Barrel Experiment (PS197) at Cern, Geneva, Switzerland, was used to measure the annihilations of an antiproton beam on a proton target. The nearly 4π solid angle coverage of the decay allows full event reconstruction from all of the final γ rays. The annihilation channel of $\eta\omega$ has been used to produce decays of ω into the reference channel $\pi^0\gamma$ and into the rare channel $\eta\gamma$ (where $\pi^0 \rightarrow \gamma\gamma$ and $\eta \rightarrow \gamma\gamma$). Thus the intermediate states were $\eta\pi^0\gamma$ and $\eta\eta\gamma$ respectively, which end up finally as five γ states. Nearly 20 million neutral annihilations, triggered by an incoming antiproton and a veto from the tracking chamber, were used in the analysis.

The dominant source of background was feed-through from six γ final states, where a soft γ is lost in the detection or reconstruction process, resulting in a five γ final state. The respective backgrounds of $\eta\pi^0\gamma$ and $\eta\eta\gamma$ were therefore $\eta\pi^0\pi^0$ and $\eta\eta\pi^0$, where the soft γ is due to the last π^0 . The $\eta\eta\pi^0$ channel's production rate is several orders of magnitude higher than that of $\eta(\omega \rightarrow \eta\gamma)$, so even a small percentage of feed-through causes a large background.

Extensive Monte Carlo simulations of all of the signal and background event channels were produced using the GEANT package.

The γ reconstruction for each event was repeated twice. The first reconstruction used a high energy threshold to discard low energy noisy signals to enhance the desired channels. The second reconstruction used a low energy threshold to look for the soft γ present in the background channels.

The first cuts on the data and simulated data selected 5 γ states, with each γ having a minimum energy of 20 MeV, which passed a 4C fit to total momentum and energy conservation. This selected data was reprocessed from the original measured signals, but this time with a 4 MeV minimum γ

energy. The γ 's were paired to form π^0 and η ; any event with more than 1 π^0 or with having $\eta\eta\pi^0$ were discarded. The γ 's from the 20 MeV reconstruction were used in the further analysis.

The 5 γ events were kinematically fitted to $\eta\pi^0\gamma$ and $\eta\eta\gamma$ hypotheses and separated into two groups, where ambiguous or bad events were discarded. From each group, a Dalitz plot of $\eta\gamma$ vs. $\pi^0\gamma$ and $\eta\gamma$ vs. $\eta\gamma$, respectively, was made. The real data and simulated data were treated to the same analysis chain, and in the end the real data was fitted bin by bin to a sum of the appropriate simulated data. 65K events of $\omega \rightarrow \pi^0\gamma$ and 150 events of $\omega \rightarrow \eta\gamma$ were identified in the fit.

Using tabulated values for all branching ratios except the rare channel, the branching ratio for the rare channel was measured,

$$\text{BR}(\omega \rightarrow \eta\gamma) = (6.2 \pm 0.7 \pm 1.0) \times 10^{-4}$$

where the first error is statistical and the second is systematic. This improves the errors of the previous tabulated value by 20%.

Footnotes and References

*Ph.D. Thesis of Mark Lakata, to be published.

A Precision Measurement of Nuclear Muon Capture on ${}^3\text{He}$

*K.M. Crowe, T. Case, P. Kammel**

In an experiment performed at PSI Switzerland our collaboration has measured the muon capture rate in the reaction $\mu^- + {}^3\text{He} \rightarrow \nu_\mu + {}^3\text{H}$ (1.9 MeV, BR \approx 0.33%) with unprecedented accuracy. Our results allow new tests of PCAC and chiral perturbation theory^{1 2 3}.

At first glance it might seem that one could more easily compare the simpler system $\mu^- + p \rightarrow \nu_\mu + n$ to the more accurate theoretical predictions associated with it. However, the experiment is difficult to carry out with precision as both reaction products are neutral and also the initial state of the muon is uncertain due to the formation of $p\mu p$ mesonic molecules. The $\mu^3\text{He}$ system turns out to be much more accessible; the muon is quickly bound in the 1s state and there is a charged particle (triton) which can be detected with extreme efficiency.

We used a high-pressure ionization chamber as an active target to count both the tritons and the incoming muons with 100% efficiency for the time region of our measurement. The monoenergetic tritons form a peak at 1.9 MeV in figure 1. The only remaining background is from the "breakup" reactions $\mu^- + {}^3\text{He} \rightarrow \nu_\mu + d + n$ and $\mu^- + {}^3\text{He} \rightarrow \nu_\mu + p + n + n$, which occur at rates of 27% and 15% relative to the main reaction.

The theory of the A=3 system is well known

Footnotes and References

*With a Collaboration from: The Austrian Academy of Sciences Institute for Medium Energy Physics / St. Petersburg Nuclear Physics Institute / Université Catholique de Louvain / Paul Scherrer Institute / Technical University of Munich / University of California at Berkeley and Lawrence Berkeley Laboratory / Kurchatov Institute / and University of Victoria.

¹C.W. Kim and H. Primakoff, Phys. Rev. 140B (1965) 566.

²J.G. Congleton and H.W. Fearing, Nucl. Phys. A552 (1993) 534; J.G. Congleton, Nucl. Phys. A570 (1994) 511.

³H. Kameyama, M. Kamimura and Y. Fukushima, Phys. Rev. C40 (1989) 974.

from the related system ${}^3\text{H} \rightarrow {}^3\text{He} + \bar{\nu}_e + e^-$. Recent improved calculations⁴ predicted a capture rate $\lambda_{\text{stat}} = 1502 \pm 27 \text{ s}^{-1}$ (as compared with 1305 s^{-1} for no meson exchange currents). Our final result $\lambda_{\text{stat}} = 1496 \pm 3 \pm 3 \text{ s}^{-1}$ confirms this calculation and even calls for more precise predictions (stat refers to the statistical population of the muonic hyperfine levels).

Our result confirms PCAC for the nuclear pseudoscalar ${}^3\text{H}-{}^3\text{He}$ form factor $F_P(q_0^2)$ to within 15%:

$$\frac{F_P(q_0^2)}{F_P^{\text{PCAC}}(q_0^2)} = 1.005 \pm 0.145, \quad (1)$$

where most of the error now resides in the theoretical calculations (q_0^2 is the momentum relevant to the capture reaction).




Figure 1: Energy distribution of the tritons from $\mu^3\text{He}$ capture. The background is from the associated breakup reactions with energies from 0 to 50 MeV.

Footnotes and References

⁴J.G. Congleton and E. Truhlík, Phys. Rev. C53 (1996) 956.

Elliptic Event Shapes at the CERN SPS

T. Wienold, I. Huang, and the NA49 Collaboration

The azimuthal asymmetry of hadron emission and transverse energy production in non-central Pb + Pb collisions at SPS energies was studied. The transverse energy was measured by the NA49 Ring Calorimeter in a special run without magnetic field to ensure azimuthally symmetric acceptance in momentum space. This calorimeter is segmented into 240 modules, configured in 10 radial rings and 24 azimuthal sectors. To search for azimuthal correlations we construct a two dimensional tensor as suggested in [1]. We define:

$$\vec{E}_{T,k} = (E_{T,k} * \cos\phi_k, E_{T,k} * \sin\phi_k) \quad (1)$$

and the tensor

$$F_{xy} = \sum_k E_{T,k}(x) * E_{T,k}(y) \quad (2)$$

with $E_{T,k}(x), E_{T,k}(y)$ being the components of the hadronic part of the transverse energy vector $\vec{E}_{T,k}$ for a given cell k centered at ϕ_k .




Figure 1: Forward-backward angular correlation of the major transverse energy flow axes.

This tensor is then evaluated to give the oval shape of the event separately in regions forward ($2.9 < \eta < 3.8$) and backward ($2.1 < \eta < 2.9$) of mid-pseudo rapidity for each event as a function of E_{VETO} , which is directly related to the impact

parameter. Fig. 1 demonstrates a strong angular correlation of the major axes between the two hemispheres in an event sample, corresponding to an impact parameter range of approximately 7-8 fm. The orientations of the forward and backward ellipses describing the azimuthal E_T distribution are shown to be aligned. This observation cannot be explained as a detector bias since the individual angular distributions of the major axes are uniform. To quantify the correlation strength of the orientation of the shape we fit the angular distribution in Fig. 1 with the function shown in the figure where c is a normalization constant. The centrality dependence is




Figure 2: Centrality dependence of the a_2 correlation strength.

displayed in Fig. 2. We used the pseudo rapidity intervals $2.1 < \eta < 2.6$ and $3.3 < \eta < 3.8$ to reduce the influence of shower leakage to our analysis. The correlation strength a_2 exhibits a strong impact parameter dependence and is largest at roughly half overlap collisions. Filtered VENUS events fail to reproduce the data whereas RQMD (in mean field mode) agrees roughly within the statistical errors.

References

- [1] J.-Y. Ollitrault, Phys. Rev. D48 (1993) 1132

Proton and Negative Hadron Spectra from NA49

Milton Toy, Peter Jacobs, and the NA49 Collaboration

The proton and negative hadron spectra from central Pb-Pb collisions at 158 GeV/nucleon have been measured by the NA49 experiment at the CERN SPS. These two distributions show two facets of the collision process: the rapidity shift (and thus energy loss) of the beam nucleons, which are represented by the protons, and the subsequent production of particles. The data shown here were taken by the NA49 Main TPCs and are fully corrected for acceptance, tracking efficiency, and non-target vertex track backgrounds.

Figure 1 shows the proton distribution in rapidity determined by the 'plus-minus-minus' method. The transverse momentum inverse slope parameter at mid-rapidity is 291 ± 22 GeV. This technique uses the fact that charge and baryon number are conserved to form the basis of the net proton yield on the charge difference of all detected particles. Corrections are then made for the residual non-proton content composed of $K^+ - K^-$ from associated production, $\pi^+ - \pi^-$ from the isospin carried by the participating neutrons, and decay products from Λ baryons that are misidentified as coming from the target vertex. The VENUS¹ model was used to generate the particle distributions used for these corrections. Preliminary strange particle yields from NA49 agree with the predictions from VENUS.

Also shown are data from central S-S collisions at 200 GeV/nucleon by the NA35 experiment². The data are scaled for the difference in beam energy and number of participating nucleons. The Pb results show a flatter spread in rapidity which suggest a greater rapidity loss than the S data.

Because the beam projectile and target are composed of only nucleons, the negatively charged particles from the collision are a mea-

sure of the particle production. Figure 2 shows the negative hadron rapidity spectrum that is the sum of the π^- , K^- , and \bar{p} yields. The scaled NA35 S-S data shows good agreement with the Pb-Pb data and indicates that multiparticle production scales simply with the number of participating nucleons.




Figure 1: Rapidity distribution of protons




Figure 2: Rapidity distribution of h^-

Footnotes and References

¹K. Werner, Phys Rep 232 (1993) 87

²J. Baechler et. al., Phys. Rev. Lett. 72 (1994) 1419

A new method for V0 reconstruction in NA49 CERN experiment

S. Margetis

The NA49 CERN experiment uses four large Time Projection Chambers (TPC) for tracking. Two (VT1/2) are placed inside magnets, and two (MTPCs) are placed further downstream and on both sides of the beam. A set of central Pb+Pb events was taken with the target placed about 30 cm upstream of the entrance of the MTPCs. In this configuration (without magnetic field) the reconstruction of V0 -type vertices is done the conventional way (by combining track pairs), but by using straight instead of curved tracks [1]. The momentum of the parent and daughter particles can be inferred from the decay angles if one assumes their masses. This is done by solving the energy/momentum conservation equations. The advantages of this method include




Figure 1: Daughter particle decay angle distribution (relative to the parent direction) for K_S^0 (dots) and Lambdas (squares).

the easier/high-accuracy (straight line) tracking in the large MTPC volumes, the absence of ExB distortions, and the target proximity to the active volume. Also, this method provides complementary information to the standard V0 analysis

done in the two vertex TPCs [2].

The separation of K_S^0 from Lambdas is done by placing cuts in the angles between the parent and daughter particles. In Lambda decays the opening angle of the proton cannot exceed a certain value whereas the K_S^0 decay is symmetric (see Fig.1). The background was found to be combinatoric and, depending on the set of cuts, in the range 20-30%. It was estimated using simulated events (see Fig.2) and subtracted from the reconstructed signal. The reconstruction efficiency was estimated by either, using simulated events, or by embedding in raw events simulated decays.




Figure 2: Normalized distribution of the distance of two daughter particles at the decay vertex (dca). Filled symbols are data, open symbols are simulated data and the solid line is the background only in the simulated data.

References

- [1] K. Alpgard et al., Phys.Lett. 115B(82)65
G.J. Alner et al., Nucl.Phys B 258(85)505
- [2] S. Margetis, Heavy Ion Phys. 4 (96) 63

K_S^0 production in Pb+Pb collisions at CERN SPS

S. Margetis and the NA49 Collaboration

Neutral kaons were reconstructed in NA49 Time Projection Chambers (TPC) using a method described in [1], via their V0 decay topology. A sample of 20000 Pb+Pb events at 158 GeV/c was analyzed and 15000 simulated events were used for efficiency and background estimations. The interaction cross-section is 5% of σ_{inel}^{tot} which corresponds to $b_{max} = 3$ fm. Results were obtained in the rapidity region $2.0 < y < 2.8$ and $p_T > 0.4$ GeV/c.

The resulting transverse mass distribution is shown in Fig. 1. An exponential fit ($1/m_T dN/dm_T = e^{-m_T/T}$) gives an inverse slope parameter (T) of 220 ± 15 MeV.




Figure 1: Transverse mass distributions of K_S^0 in the rapidity region $2.2 < y < 2.6$.

By integrating over all p_T values one obtains the rapidity density (dN/dy) which is shown in Fig. 2. The filled symbols are the measured data whereas the open ones are the same values but reflected around mid-rapidity ($y_{mid}^{Pb+Pb} = 2.92$). This is because Pb+Pb is a symmetric system and assuming the trigger biases are negligible. The solid line is the fitted S+S distribution scaled with the ratio of number of participants in the two systems ($390/58 = 6.7$) which

is also the ratio of produced negative hadrons (mostly pions). The two distributions are compatible within errors. This leads to the conclusion that the K_S^0/π ratio is about the same in S+S and Pb+Pb collisions [2]. This ratio in S+S was found to be twice as large than in nucleon-nucleon collisions at the same energy [3]. It is therefore intriguing that in a much larger system, like Pb+Pb, there is no further enhancement of this ratio.




Figure 2: Rapidity distribution of K_S^0 in Pb+Pb collisions (symbols). See text for an explanation of the symbols.

References

- [1] S. Margetis, Elsewhere in this report
- [2] S. Margetis, Heavy Ion Phys. 4 (96) 63
- [3] T. Alber et al, NA35 Collaboration, Z.Phys.C 64(94)195

Projectile Fragmentation in Pb+Pb Collisions at 158 A·GeV

I. Huang, S. Margetis, G. Odyniec and the NA49 Collaboration

The fragmentation of the projectiles in Pb+Pb collisions at 158 A·GeV at the CERN SPS is studied in order to determine how many spectator nucleons are bound in fragments as a function of centrality. This is accomplished by measuring the forward-going energy in the NA49 zero-degree calorimeter (called Veto calorimeter) in conjunction with the adjustable iron collimator, which defines the acceptance of the calorimeter. NA49 uses two superconducting dipole magnets with a total bending power of 7.8 T·m. Since the spectator nucleons in the projectile fragmentation region have approximately the beam energy and small p_T , the deflections of nucleons and fragments in the bending plane depend mostly on their charge-to-mass ratios. (The amount of deflection of spectator protons is 30 cm at the collimator.) Thus, neutrons, protons, and fragments of the spectator matter can be disentangled and measured separately in the Veto calorimeter.

The centrality trigger is provided by the NA49 Ring calorimeter (positioned upstream of the collimator and the Veto calorimeter) which measures energy deposited near mid-rapidity in each event. By comparing the data with the prediction of VENUS, the impact parameter was deduced. Forward energy data were taken in 1995 and '96 with appropriate configurations of the collimator in four separate runs to measure 1) neutrons only, 2) protons only, 3) fragments only, and 4) all three simultaneously. To estimate the amount of background contamination, a target-out run was also performed.

The magnitude of the contamination in the Veto calorimeter signal from showers that originate in the collimator and reach the Veto calorimeter, as well as from produced particles, is estimated using GEANT simulation. A fraction of the spectator nucleons in VENUS are assigned to fragments such that the full-physics GEANT simulation for the neutron configura-

tion resembles the neutron data. This procedure was reiterated until the results of all configurations roughly fitted the respective data sets. The corrections for these effects were applied to the data.




Figure 1: Projectile spectator energy as a function of the impact parameter. The square brackets are the estimated systematic errors.

Fig. 1 shows the energy carried by spectator neutrons, protons and fragments as a function of the impact parameter. The sum of energies carried by neutrons, protons and fragments agrees with the total energy to within the systematic uncertainties. These data, however, have not been corrected for the small non-uniformity of the Veto calorimeter. This correction will slightly affect the relative energy calibration of protons and neutrons. We observe that the energy carried by fragments is small for central collisions but increases dramatically for larger values of b . The final analysis of these data is in progress.

Fragmentation of 160 A GeV Pb in Various Targets*

Y. D. He and P. B. Price

A substantial fraction of ultrarelativistic heavy ion collisions results in fragmentation of projectile nuclei in peripheral collisions involving both nuclear and electromagnetic interactions. These reactions are intrinsically of interest, as an aspect of ultrarelativistic nucleus-nucleus interactions which is not thoroughly understood. Moreover, measurements of cross sections for fragmentation are needed in studies of cosmic ray propagation. Measurements of some of these cross sections have been previously made using beams of 14.5 A GeV ^{28}Si and 11.4 A GeV ^{197}Au at BNL AGS, and 60 and 200 A GeV ^{18}O and 200 A GeV ^{32}S at CERN SPS. In this paper, we shall report new measurements using the beam of 160 A GeV ^{208}Pb at CERN SPS.

We exposed 10 stacks of BP-1 glass stacks that were sandwiched with various targets to the beam of 160 A GeV Pb in December 1994. The exposure was carried out at normal incidence at a density of $\sim 800\text{ cm}^{-2}$. The dimension of each plate of BP-1 glass was $50\text{ mm} \times 50\text{ mm} \times 1\text{ mm}$. We etched the glass in 70% $\text{CH}_3\text{SO}_3\text{H}$ at $50\text{ }^\circ\text{C}$ for 120 hours. The charge threshold is $Z_{\text{th}} \sim 68$.

We typically obtain $\sim 1.5 \times 10^4$ events in each stack. The charge resolution is ~ 0.14 charge unit. The charge resolution can even be improved by multiple measurements of etch pits in several sheets of BP-1 detectors. We present the charge distribution of beam particles and pro-

jectile fragments obtained in 5 sheets of glass in the figure. The charge resolution is found to be ~ 0.06 charge unit. This charge resolution is more than adequate to identify fragments and hence to measure cross sections for charge-changing interactions. The measurements of fragmentation cross section of 160 A GeV Pb in various targets are presented.




Figure - The distribution of averaged charges from 5 sheets of BP-1 detectors for beam particles and projectile fragments created in collisions of 160 A GeV Pb with target.

*Condensed from a paper in the Proceedings of 24th International Conference on Cosmic Rays, Rome, Italy 1 (1995) 119-122.

STAR TPC System Test

W. Betts¹, F. Bieser², R. Bossingham², M. Botlo³, M. Cherney⁴, J. Chrin⁴, P. Colarco⁴, H. Crawford⁵, H. Diaz³, K. Dao², D. Greiner², L. Greiner⁵, E. Hjort⁶, S. Jacobson², R.C. Jared², E. Judd⁵, S.R. Klein², A.N. Lebedev⁷, M.J. Levine³, V. Lindenstruth², M.A. Lisa², K. Marks², C. McParland², T.S. McShane⁴, J. Meier⁴, M.T. Nguyen³, D.L. Olson², I. Sakrejda², J. Schambach¹, R.A. Scheetz³, N.T.B. Stone², C.E. Tull², G. Visser², C. Vu², H. Wieman², E. Yee² and the STAR Collaboration




Figure 1: TPC system test cosmic-ray setup.

The STAR TPC system test assembles components at their current stage of development, testing functionality and interactions in a semi-realistic environment. Preliminary results have been reported at conferences[1],[2].

A typical setup is shown in Fig. 1. A TPC subsector is mounted in a field cage with a 10-cm drift region; 20 front-end cards and a prototype readout board instrument up to 640 pads. After a trigger, data are transmitted to "MiniDAQ" to be stored on tape and/or analyzed on line. System parameters are monitored by an EPICS-based slow controls system, while run control and a state manager coordinate the systems.

The front-end electronics gain, noise and stability have been studied, while cosmic-ray and laser tracks are used to debug and tune the analysis codes, as well as to test the hardware. A reconstructed track is shown in Fig. 2; rectangles mark the instrumented areas. A fully instru-

mented sector will soon be available for testing, leading to TPC field-cage tests in spring, 1997.




Figure 2: Reconstructed cosmic-ray track.

- ¹University of Texas at Austin
- ²Lawrence Berkeley National Laboratory
- ³Brookhaven National Laboratory
- ⁴Creighton University
- ⁵Univ. Calif. Space Sciences Laboratory
- ⁶Purdue University
- ⁷Moscow Engineering Physics Institute

References

- [1] Presented by I. Sakrejda, APS DNP Meeting, Indianapolis, IN., Oct. 2-5, 1996.
- [2] Presented by J. Chrin, IEEE Nuclear Science Symposium, Anaheim, CA., Nov. 3-9, 1996.

Front End Electronics for the STAR TPC

F. S. Bieser, J. Hunter, S. R. Klein, C. Vu, and the STAR Collaboration

The front end electronics (FEE) for the STAR TPC receives signals from the 136,600 pads on the TPC, amplifies them, shapes them, and digitizes them with a 512 time sample, 6/12 MHz, 10 bit waveform digitization system[1]. The high channel count requires a highly integrated design to minimize size, power, and costs, and to maximize reliability[2].

The analog functionality is contained in two custom 1.2 μ CMOS chips, the STAR Amplifier/Shaper (SAS), which contains a low noise preamplifier, shaper (with tail correction), and output buffer[3], and the SCA, which contains a 512 time bucket switched capacitor array, plus a 12 bit ADC. Both chips are 16 channels wide, with 32 channels (2 chip sets) packaged onto 2.9" by 7" FEE cards. The FEE cards contain all of the analog circuitry, and plug onto the TPC sectors, eliminating cabling and associated ground loops. A water cooled aluminum bar maintains FEE temperature within 0.5 ° C, necessary for accurate dE/dx measurement in the TPC.

The FEE cards are read out by readout boards, which control 36 FEE cards (1152 channels) of FEE. Data is sent from the readout boards to STAR DAQ over a fiber optic link at 1.2 Gbit/sec. A trigger bus provides trigger, abort and calibration event functionality, while a slow controls link provides for monitoring and control, such as turning groups of FEE cards on and off. The readout board sequencer, readout buffers, and control are implemented in FPGA's; the system can read out events at 200 Hz.

20 FEE cards and a prototype readout board are now in use in the STAR system test[4]. These tests have shown that the system meets it's requirements, and that the on-detector noise levels match the bench levels. Output stability with temperature, humidity and time have all been monitored, and grounding and cooling addressed.

The FEE cards went into low rate production (4% build, or 240 cards) at the end of 1996; full production is slated to begin in 1997, to be complete at STAR turn on in 1999. Readout board prototyping is almost complete, and production should follow a similar schedule.

Roughly 25,000 channels of this electronics will also be used for the STAR forward TPC's. This application takes advantage of the flexibility of the design; the SAS shaping time is adjusted to 400 nsec FWHM, and the SCA sampling clock and number of samples are reduced. Because of the reduced noise and output slew rate, SAS power consumption can be reduced to about 1/3 of that in the main TPC. The chips and circuitry will be repackaged to fit the allowable space. STAR will also provide 3840 channels of this electronics (plus spares) to the BRAHMS collaboration at RHIC, for use with their TPC's.

References

- [1] S. Klein *et al.*, "Front End Electronics for the STAR TPC", IEEE Transactions on Nuclear Science **43**, 1768 (1996).
- [2] S. Klein, *et al.*, "The STAR TPC Front End Electronics", presented at the First Workshop for LHC Electronics", Lisbon, Portugal, September 11-15, 1995, and published in the proceedings.
- [3] E. Beuville *et al.*, "A Low Noise Amplifier-Shaper with Tail Correction for the STAR Detector", IEEE Transactions on Nuclear Science **43**, 1619 (1996).
- [4] W. Betts *et al.*, Results from the STAR TPC System Test. , preprint CU (Creighton U.) -PHY-NP 96/03, Nov. 1996, submitted to IEEE Transactions on Nuclear Science.

Triggering in the STAR Experiment at RHIC

Eleanor Judd and the STAR trigger group

The STAR collaboration was formed to investigate the behavior of matter under conditions of extremely high temperature and density at RHIC. One particular goal is to search for the existence of a deconfined state of quarks and gluons, the quark-gluon plasma. The UCB contingent in STAR is part of the group responsible for triggering the experiment. The major goals of the trigger group are:

- Analyze data from every RHIC crossing in the trigger detectors.
- Issue triggers based on the total charged multiplicity, the energy deposited in the calorimeter and the interaction position.
- Abort events based on a more detailed analysis of the trigger detector data and on data from slower detectors.
- Issue triggers to fast detectors (EMC) while the slow detectors (TPC and SVT) are busy.
- Inform DAQ when an event is ready to be built and taped.
- Implement enough scalars to enable cross-sections to be calculated.

The UCB STAR collaborators have concentrated on designing and building the custom hardware for the early levels of the trigger, and the control software for the complete trigger system.

Over the past year a prototype Data Storage and Manipulation board (DSM) and Trigger Control Unit (TCU) have been built and tested. In the final system a tree of 16-channel DSM boards will be used to store the data from the trigger detectors every RHIC crossing. The tree will also calculate triggerable quantities; total multiplicity, total energy, etc.... The output from each branch of the tree will then be collected in the last DSM board, which feeds the TCU. The prototype DSM board had just two input channels, but the rest of its functionality was the

same as for the production board. A fast, high precision, TDC, used as input to one branch of the DSM tree has also been prototyped.

The prototype TCU board was very close to the final production model. The pre-scalars and trigger word look-up tables were fully implemented, and so were most of the output FIFOs. The board could also drive the trigger word on the VME backplane to be distributed to the main detector front-end electronics.

A prototype SCI-PCI (SPSB) card was designed and built for use as the internal trigger network. This should allow the trigger group to use a Scalable Coherent Interface (SCI) network to communicate between processors in many different VME crates. The prototype has been successfully used to connect the two processors that make up the trigger-daq interface.

In software, the Level 1 controller, which reads out the TCU and feeds tokens back to the TCU, and the trigger-daq interface (TDI), which informs minidaq of an event, have been written and used extensively in testing the hardware.

All the trigger pieces have now been integrated into an on-going system test at LBL, along with a TPC sector, minidaq, slow controls and experiment controls. The trigger can reliably detect a cosmic-ray induced coincidence between two scintillators placed around the TPC sector. The TCU can issue a trigger to the TPC front-end cards. Level 1 can read out the TCU FIFOs and inform minidaq that an event has occurred.

Finally, the whole STAR trigger group has just been through a successful, internal STAR review. The review committee was very impressed with the power and flexibility of the trigger system and the project can now move to the production phase.

STAR Analysis Framework*

D. L. Olson, C. E. Tull,[†] D. Prindle[§]

The analysis framework in STAR (called STAF) generally provides the interface between the physicists doing data analysis and the off-line computing facilities. STAF provides an encapsulation for data analysis algorithms permitting the integration of components provided by many physicists with those components which provide the rest of the computing environment, i.e., data access, user interface, control logic, etc.

This framework, developed in C++ and following an interface standard for component software (CORBA)[‡] was released to the collaboration during the summer and process of moving the pre-existing simulation and analysis software into the new framework is nearly complete.

There are many components to this framework as shown in figure 1 and some of the major ones are:

- DUI - unix-like user interface to the hierarchical data structures
- DIO - interface to disk, network and tape data input & output
- AMI - interface to user-written analysis code
- TBR - table browser for viewing data

A new user interface based on Tcl/Tk is being developed for STAF (and the whole STAR off-line environment) at UW, called the STAR Off-line Notebook (figure 2). This will provide a graphic interface to the available set of programs and off-line activities. This interface should permit more reliable usage of the off-line software as well as enabling non-experts to play a significant role in the simulations and data analysis activities.

Besides its current use for STAR simulations software, STAF is being used for analysis of actual cosmic-ray test data in the STAR System Test environment**.

Footnotes and References

* <http://www.rhic.bnl.gov/STAR/star.html>

† LBNL ICSD

§ UW NPL

‡ <http://www.omg.org/orb.htm>

** See separate report on STAR system test.




Fig. 1. Artistic rendition of a scientist controlling the components of the STAR analysis framework.




Fig. 2. Screen view of STAR Offline Notebook. Programs or activities are selected by clicking on the notebook tabs.

Simulations and Analysis Software for the STAR TPC

P.M. Jacobs, M.A. Lisa, I.M. Sakrejda, N.T.B. Stone and the STAR Collaboration

A set of programs to simulate and analyze data from the STAR Time Projection Chamber has been developed. This package includes the detector simulations, reconstruction of the particle tracks in the detector, and the particle identification software. The simulations and reconstruction modules are accompanied by the calibrations and geometry packages.

The first step in the simulation chain is to track particles produced in a 100GeV/nucleon Au+Au collision through the STAR detector. This task is performed by GSTAR [1], a module based on the CERN simulations package GEANT. It accounts for the hadronic interactions of the particles produced during the collision with the detector material, multiple scattering, decays in flight, and many other effects. The next step is designed to study impact of the detector performance on the ionization deposited in the volume of the TPC by charged products of the collision. Two packages were provided to perform this task. First, the TPC Slow Simulator (tss) [2] includes effects of the charge drifting in the electric and magnetic field and the signal processing by the Front-End Electronics (FEE). The Slow Simulator writes output in the raw data format. This simulated data then serves as an input to the cluster finder and hit reconstruction software [3]. The other option is to forgo detailed simulations of the detector and use a parametrization of the reconstructed position resolution and the hit finding efficiency to directly create reconstructed hits. The second option is implemented in the form of the TPC Fast Simulator, (tfs) [4]. After the hits are reconstructed or simulated, the next step in data analysis is the track reconstruction. This task is performed by the TPC tracking module - tpt [5]. High tracking efficiency (>95%) and good momentum resolution provide input for the particle identification based on the dE/dx analysis.




Figure 1: Reconstructed laser tracks in a test module. The rectangles outline parts of the detector that have been instrumented so far.

Recently parts of the TPC software chain were tested (Fig. 1) during the STAR TPC System Test. Data taken in the fall of 1996 agreed with the simulated detector parameters. The simulation and reconstruction software chain is used to develop physics analysis software so that, when the experiment starts taking data in the year 1999, a prompt and reliable analysis will be possible.

References

- [1] P.M. Jacobs GSTAR: A GEANT-based Detector Simulation Chain for STAR, STAR Note SN0235.
- [2] Wen Gong; The STAR-TPC Slow Simulator, Star Note SN0197
- [3] M.A. Lisa; The STAR TPC Cluster finder Hit finder, Star Note SN0238.
- [4] P.G. Jones; The STAR Fast TPC Simulation (A User's Guide), STAR Note SN0056
- [5] I.M. Sakrejda; Tracking for the STAR TPC, STAR Note SN0190

The PDSF Computing Facility at LBNL

R. Jeff Porter

During the past year, the computing facility known as PDSF was relocated from its original home at the SSC laboratory in Texas to LBNL. PDSF is a multi-platform workstation farm designed to support the computing needs of detector development projects at the SSC laboratory. It was moved to LBNL to take advantage of both the scientific computing environment provided by the National Energy Research Scientific Computing Center (NERSC) and the strong presence in Nuclear Science (NS) and High Energy Physics (HEP) research found at LBNL. The PDSF facility is being supported jointly by NERSC, the Nuclear Science Division, and the Physics Division. PDSF will be used to meet the computing requirements of large-scale data analysis and detector simulation projects in HEP and NS investigations.

PDSF at LBNL was initially brought on-line in a temporary form during the summer of this past year before moving to its final home in October. The Phase I hardware configuration, shown in Fig. 1, was designed using equipment obtained from the SSC laboratory. The current status of the facility can be found on the PDSF WWW pages noted in Fig. 1. At present, the PDSF systems include,

- 32 HP 9000/735(25) workstations
- 32 SUN Sparc10 workstations
- 2 80-Gbyte Data-Vault disk storage
- 2 SGI Challenge-L data servers
- 100BaseT external ethernet connection
- FDDI internal PDSF network

The nuclear science research community has been very active in making use of PDSF. A listing of NS groups currently using or preparing to use the facility is given below.

STAR is running event and detector simulation projects on PDSF.

NA49 is preparing to use PDSF for data analysis and physics simulations.

PHENIX is preparing to run event and detector simulation projects on PDSF.

E895 is preparing to use PDSF as a data analysis facility.

EOS-Bevalac is analyzing data on PDSF

SNO will use PDSF in developing data analysis systems and plans to analyze data on PDSF.

Gammasphere is preparing to extend its data analysis program to PDSF.

PDSF Configuration at Phase I
<http://www.nersc.gov/hardware/PDSF>




Figure 1: PDSF hardware configuration

Development of a Micro TPC Vertex Detector

H. Wieman, E. Beuville,[†] M. Burks,[‡] D. Fritz,[†] S. Margetis, F. Retiere, S. Trentalange,[§] and R. Wells [†]

We are developing a new Micro TPC vertex detector that will be capable of tracking in the high track density environments which will be encountered in the STAR experiment at RHIC and in the ALICE experiment at LHC. This detector can handle track densities of 10 tracks/cm², approaching the capabilities of silicon devices.[1] It has, however, the important advantage that it is essentially massless in comparison. This greatly reduces problems due to multiple scattering and secondary interactions, which is of utmost importance for vertex detectors. This technology could provide a significant improvement over silicon in these experiments particularly at low pt where exciting results have been predicted for heavy ion collisions. In STAR the combined radiation length of the beam pipe plus silicon vertex detector averages 4.8%. Replacing the silicon detector with a Micro TPC will reduce the combined radiation length to 0.85%, an improvement factor of over 5.

The Micro TPC will use micro-strip gas chambers (MSGCs) to read out the signal. The fine pitch of these devices is well matched to the low diffusion that can be achieved with a short drift distance in dimethyl-ether (DME). This combination makes it possible to achieve much better two-track resolution than has been possible with other TPCs. The main thrusts of the program have been the demonstration that electrons can be drifted in DME over the planned drift distance of 15 cm without significant attenuation and the development of a MSGC system that can be constructed with the required channel density. We have built a drift cell, shown in fig. 1, in which we measured electron attenuations of less than 0.1% loss per cm.[2] We have also produced a MSGC on a silicon amplifier chip and demonstrated suitable operation.

The MSGC was fabricated with the amplifier using a standard HP CMOS process. A

postprocess layer of partially conductive Si-Carbide was added to correctly shape the electric field at the readout anode. Integrating the detector with the amplifier on a single chip reduces noise permitting low gas gain operation. We have successfully tested the detector-amplifier chip using an Fe⁵⁵ X-ray source. The amplifier noise was 110 electrons rms which allowed excellent signal to noise operation with a gas gain of only 20.

Footnotes and References

[†] Engineering Division LBNL

[‡] Univ. of Arkansas

[§] Univ. Calif. Los Angeles

1. S. Margetis, H. Wieman, W. Gong and the STAR Collaboration, "VTX: A compact TPC with Microstrip readout for STAR", LBL-37384, NSD Ann. Rep. 1994
2. M. Burks, S. Trentalange, S. Margetis and H. Wieman, "Electron drift parameters in dimethyl ether", NIM to be published




Fig. 1. Drift cell for testing electron attenuation while drifting through DME gas

Production and Detection of Hyperfragments in High Energy Nucleus-Nucleus Collisions*

Y. D. He and P. B. Price

We discuss electromagnetic production of hyperfragments induced by the extremely intense flux of photons generated by heavy target nuclei and seen by rapidly moving projectile nuclei in high energy distant nucleus-nucleus collisions. The cross section estimated using Williams-Weizsäcker method is found to be accessible to future experiments at the Relativistic Heavy Ion Collider. We also discuss its signature and detection.




Fig. 2 - Estimated cross sections for electromagnetic production of hyperfragments in nucleus-nucleus collisions.




Fig. 1 - Hyperfragment production in high energy nucleus-nucleus collisions by nuclear and electromagnetic modes.

* Abstract of a paper in the Proceedings of 24th International Conference on Cosmic Rays, Rome, Italy 1 (1995) 64-67.

Coherent Nuclear Interactions at RHIC

Spencer Klein and Evan Scannapieco

When ultrarelativistic nuclei undergo interactions at large impact parameters, the entire nucleus can interact as a single particle, via a coherent electromagnetic (photon) or Pomeronic fields. Collisions between these fields have a broad physics interest.

Two-photon collisions result from the interactions of the electromagnetic fields of the two nuclei. This process can be modelled by the Weizsacker-Williams method as the collision of two almost-real photons; any spin 0 or spin 2 state with internal or external charge is accessible[1]. We have calculated the photon fluxes, collision rates and final state production rates for a variety of final states at RHIC[2]. For final state energies below 1.5 GeV, RHIC will have a higher $\gamma\gamma$ luminosity than e^+e^- colliders such as CESR and LEP II.

Photon-Pomeron and double-Pomeron interactions are also possible. Pomerons are a representation of colorless interactions involving the strong force, such as pp elastic scattering, and having the same quantum numbers as the vacuum. They represent the absorptive part of the interaction cross section. At RHIC, interactions such as $\gamma + P \rightarrow V$, where V is a vector meson will produce large numbers of ρ , ϕ and J/ψ . Double Pomeron interactions can lead to spin 0 or 2 final states, at higher energies than can be produced in $\gamma\gamma$ collisions. These interactions measure the photon-Pomeron and nucleon-Pomeron coupling, and shed light on the nature of the Pomeron.

We have investigated the feasibility of studying these interactions, using two-photon collisions as our model[2]. These interactions have signatures that can be distinguished from backgrounds such as grazing nuclear collisions, beam gas interactions, cosmic rays, and the like. Since the nuclei interact as a single particle, the perpendicular momentum scale p_\perp of the prod-

ucts is determined by the nuclear size R , with $p_\perp = \hbar c/R$, or about 30 MeV/c for gold. In contrast, incoherent background has a p_\perp scale given by QCD, typically 300 MeV/c. For the reactions of interest studied here, there are typically 2 or 4 charged and 0 neutrals, allowing for complete reconstruction of the event, and hence accurate p_\perp determination. Because the photons and Pomerons are both color singlets, the final state should not be accompanied by additional particles, and should be well separated in rapidity space from both beams.

We have simulated $\gamma\gamma$ collisions to a number of final states: $\mu^+\mu^-$, $\tau^+\tau^- \rightarrow l^+l^-$, $\eta_c \rightarrow K^{*0}K^+\pi^-$, η' , $f_0(975)$, $f_2(1270)$, and $\rho^0\rho^0 \rightarrow \pi^+\pi^-\pi^+\pi^-$, and found the rates and acceptances in the STAR detector. Rates are high, and, except for the η_c , all states may be seen and studied with good statistics; the η_c is marginal. We have also simulated the backgrounds due to grazing nuclear collisions and beam gas events. Except for the η_c , signal to noise ratios are good.

We have also developed a scheme for STAR to trigger on these events at level 0, 1, 2, and 3. This trigger selects events based on multiplicity and topology in levels 0 through 2, adding tracking information to find the total charge, vertex position and momentum balance at level 3. At each stage, we have demonstrated good acceptance, while using a small fraction of the available bandwidth.

References

- [1] S. Klein, "Two-Photon Physics at RHIC", in *Photon '95*, ed. D. J. Miller, S. L. Cartwright and V. Khoze, World Scientific, 1995.
- [2] Spencer Klein and Evan Scannapieco, "Two-Photon Physics with STAR, STAR Note 243, March 22, 1996.

NSD Pre-College Educational Activities

Howard S. Matis, Chairman NSD Educational Committee

The Nuclear Science Division has established an active education outreach program which has developed several strategies to introduce nuclear physics into the high school and middle school classroom. Our goals are to prepare educational literature that teachers can introduce into their curriculum and have experimental equipment that they can borrow.

To disseminate this material, we have developed a teaching center in cooperation with Oakland Public School's Chabot Science Center. Using a modest grant (the Meggers Award) from the American Institute of Physics, sufficient equipment was purchased to provide classroom hands-on activities centered on the general topic of "*The ABCs of Radioactivity*." This unit covers general properties of radioactivity and common radioactive materials found in the home and environment. Division scientists have given several workshops at Chabot Science Center for teachers. After attending the workshop, teachers have the opportunity to borrow the detectors for classroom use.

A teacher working with several members of the Nuclear Science Division created a laboratory manual that describes several experiments and activities on radioactivity. These experiments can be done with either equipment borrowed from the Chabot Science Center or from items bought from a science supply house. We have been distributing this manual to teachers. Last summer, we put these experiments on our educational web site.

To continue our work on the ABC's of Radioactivity, we have created a low cost cosmic ray detector that has been used in several schools and a 25 minute video on Cosmic Rays and Radiation. We have recently received another Meggers Foundation grant to add this equipment to the Chabot Science Center.

Another educational activity for the Division in the past few years has been participation in

the annual California Chemathon which is attended by more than 2000 high school students. During the Chemathon, NSD scientists provide several "hands-on" demonstrations of nuclear science research. More than 400 students visit this popular station; it provides students from many diverse backgrounds an opportunity to talk to "real scientists" and see what they do. In 1995, we presented many of our demonstrations at the LBL Open House.

The major activity of 1996 has been the creation of a "Nuclear Science Wall Chart." This chart will illustrate the basics of Nuclear Physics coupled with the most exciting research that is being done in the world. We intend to make this chart widely available to schools. In August of 1996, we joined the organization called Contemporary Physics Education Project (CPEP). CPEP is the creator of the popular Particle Physics Wall chart and the recently produced Fusion chart. NSD is working with scientists and teachers from throughout the nation to produce this chart.




Fig. 1. One of the graphics that can be found in the Nuclear Science Educational Web site -- http://user88.lbl.gov/NSD_docs/ed.html.

Nuclear Theory

1. The first part of the document discusses the importance of maintaining accurate records of all transactions.

2. It is essential to ensure that all entries are supported by appropriate documentation.

3. Regular audits should be conducted to verify the accuracy of the records.

4. The second part of the document outlines the procedures for handling discrepancies.

5. Any errors identified during the audit process should be promptly investigated.

6. The findings of the audit should be reported to the appropriate authorities.

7. The third part of the document provides guidelines for the management of financial risks.

8. It is crucial to identify potential risks and implement effective mitigation strategies.

9. Regular risk assessments should be performed to monitor the effectiveness of these strategies.

10. The fourth part of the document discusses the role of internal controls in ensuring compliance.

11. Strong internal controls are necessary to prevent fraud and ensure the integrity of the financial statements.

12. The fifth part of the document concludes with a summary of the key points discussed.

13. It is hoped that this document will provide valuable insights and guidance for all stakeholders.

14. The sixth part of the document provides a list of references for further reading.

15. The seventh part of the document contains a list of appendices.

16. The eighth part of the document provides a list of contact information for the relevant departments.

17. The ninth part of the document contains a list of abbreviations used throughout the document.

18. The tenth part of the document provides a list of definitions for key terms.

19. The eleventh part of the document contains a list of footnotes.

20. The twelfth part of the document provides a list of references.

21. The thirteenth part of the document contains a list of appendices.

22. The fourteenth part of the document provides a list of contact information for the relevant departments.

23. The fifteenth part of the document contains a list of abbreviations used throughout the document.

24. The sixteenth part of the document provides a list of definitions for key terms.

25. The seventeenth part of the document contains a list of footnotes.

26. The eighteenth part of the document provides a list of references.

27. The nineteenth part of the document contains a list of appendices.

28. The twentieth part of the document provides a list of contact information for the relevant departments.

29. The twenty-first part of the document contains a list of abbreviations used throughout the document.

30. The twenty-second part of the document provides a list of definitions for key terms.

Study of Medium-induced Parton Energy Loss in γ +jet Events of High-Energy Heavy-Ion Collisions *

X. N. Wang and Z. Huang[†]

Among the proposed hard probes of dense matter in high-energy heavy-ion collisions, large transverse momentum jets or partons are especially useful because they interact strongly with the medium. Jet quenching due to the medium-induced radiative energy loss of a high-energy parton propagating through a dense medium can provide important information on the properties of the medium and interaction processes that may lead to partial thermalization of the produced parton system.

In QCD, one can measure the radiative energy loss indirectly via the modification of the jet fragmentation function. In order to measure the fragmentation function one has to first determine the initial energy of the fragmenting parton. We propose to measure the particle p_T distribution in the opposite transverse direction of a tagged direct photon. Since a direct photon in the central rapidity region ($y = 0$) is always accompanied by a jet in the opposite transverse direction with roughly equal transverse energy, the p_T distribution of particles in that direction is directly related to the jet fragmentation function with known initial energy, $E_T^{\text{jet}} \approx E_T^\gamma$. In such γ + jet events, one can easily extract the fragmentation function from the experimental data. By comparing the extracted jet fragmentation function in AA to that in pp collisions, one can then measure the modification of the fragmentation function and determine the parton energy loss.

In this paper, we have studied in detail the effect of parton energy loss on the jet fragmentation function as extracted from the p_T spectrum in the opposite direction of a triggered direct photon. In particular, we have taken into account the E_T smearing of the jet due to initial state radiations associated with the γ + jet processes. We have shown that the particle spectrum from jet fragmentation at $p_T \sim E_T^\gamma$ is very sensitive to the E_T broadening from initial and final state scatterings with beam partons (see Fig. 1). One can then use our proposed measurement to determine the E_T broadening in




Figure 1: The modification factor for the inclusive fragmentation function of photon-tagged jets with (solid) and without (dashed) E_T broadening due to initial parton scatterings.

pA collisions. This small but finite effect must then be subtracted out when one determines the medium-induced parton energy loss in AA collisions.

*LBNL-39742, 1997, submitted to Phys. Rev. C.

[†]Department of Physics, University of Arizona, Tucson, AZ 85721

Jet Quenching in the Direction Opposite to a Tagged Photon in High-Energy Heavy-Ion Collisions *

X. N. Wang, Z. Huang[†] and Ina Sarcevic[†]

The study of large p_T jets can probe their energy loss due to inelastic scatterings inside dense matter or a quark-gluon plasma. Because of the enormous background in high-energy heavy-ion collisions, the conventional calorimetric study cannot measure the jet energy to the accuracy required to determine the energy loss.

In this work, we proposed the study of jet quenching in high-energy heavy-ion collisions by measuring the p_T distribution of charged hadrons in the opposite direction of a tagged direct photon. A direct photon is produced by quark-antiquark annihilation or quark(antiquark)-gluon Compton scatterings in which a gluon or quark(antiquark) jet is also produced in the opposite direction of the photon. By tagging a direct photon with a given transverse energy E_T^γ , one can avoid the uncertainties associated with the jet production cross section. One can also determine the initial transverse energy of the produced jet, $E_T \approx E_T^\gamma$, from momentum conservation, modulo calculable corrections from initial state radiations.

In such events, the p_T spectrum of charged hadrons from jet fragmentation in the opposite direction of the tagged photon is a very good approximation of the jet fragmentation function and is estimated to be well above the background which can be reliably subtracted at moderately large p_T . We demonstrate that comparison between the extracted fragmentation function in AA and pp collisions can be used to determine the jet energy loss and the interaction mean-free-path in the dense matter produced in high-energy heavy-ion collisions.




Figure 1: The differential p_T spectrum of charged particles from the fragmentation of a photon-tagged jet with $E_T^\gamma = 15, 20$ GeV and the underlying background in central $Au + Au$ collisions at $\sqrt{s} = 200$ GeV. The direct photon is restricted to $|y| \leq \Delta y/2 = 0.5$. Charged particles are limited to the same rapidity range and in the opposite direction of the photon, $|\phi - \phi_\gamma - \pi| \leq \Delta\phi/2 = 1.0$. Solid lines are perturbative calculations and points are HIJING simulations of 10K events. The dashed lines are calculations with jet energy loss, $dE_q/dx = 1$ GeV/fm and the mean-free-path $\lambda_q = 1$ fm.

*Phys. Rev. Lett. 77, 231 (1996).

[†]Department of Physics, University of Arizona, Tucson, AZ 85721

Dilepton and Photon Production from a Coherent Pion Oscillation *

Z. Huang[†] and X. N. Wang

Electromagnetic probes are known to be ideal probes of dense hadronic matter owing to the fact that they escape the strong interaction region once produced without further final state interactions and thus carry the information on the early dynamical evolution. In this work, we studied the dilepton and direct photon production from the classical pion field in the context of a disoriented chiral condensate (DCC), or most generally, a nonequilibrium pion cloud. We developed a general formalism for the dilepton and photon emissions in the presence of a classical electromagnetic current. Since the electromagnetic current coincides with the third component of the isovector current, the isospin angular oscillation of the condensate field can be a significant source of electromagnetic emission in the low mass (transverse momentum) region.

The dilepton differential distribution with respect to the lepton pair 4-momentum q can be derived as

$$\frac{dN_{\ell^+\ell^-}}{d^4q} = \frac{\alpha^2 B}{6\pi^3 q^4} [q^\mu q^\nu - q^2 g^{\mu\nu}] J_\mu^{\text{cl}}(q) J_\nu^{\text{cl}*}(q), \quad (1)$$

where $J_\mu^{\text{cl}}(q)$ is the electromagnetic current carried by the classical pion fields, $B = [1 + 2m_\ell^2/q^2][1 - 4m_\ell^2/q^2]^{1/2}$ and m_ℓ is the lepton mass.

Given an analytical solvable model where a general class of solutions for the pion fields can be obtained, we calculate the dilepton spectrum as shown in Fig. 1.

Both the dilepton and the photon spectra fall off exponentially for large transverse momentum which is characteristic of coherent production from a finite domain. The electromagnetic emission from a DCC domain is thus only important in the low momentum region where the spectra increase as some inverse power law of the momentum.

The result depends on a constant a_3 in the third component of the isospin which is conserved, $J_\mu^{(3)} = a_3 f_\pi^2 x_\mu / \tau^2$. The constant a_3 can




Figure 1: The dilepton invariant mass spectrum for different choices of initial time scale τ_0 and the coherent field domain size R_D . The initial energy density is assumed to be $\epsilon_0 = 0.1 \text{ GeV/fm}^3$. The typical thermal spectrum due to the π - π annihilation is also plotted for a comparison

be related to the initial energy density using the symmetry argument,

$$\langle a_3^2 \rangle = \frac{1}{6} \frac{\epsilon_0 \tau_0^2}{2 f_\pi^2} \quad (i = 1, 2, 3). \quad (2)$$

Most notably, there does not exist a pion mass threshold for dilepton production from a coherent field: the spectrum rises even below $M = 2m_\pi$. The finite pion mass plays no roles in the conserved isovector current whose third component directly couples to the photon. Therefore, the coherent field is most effective in producing lepton pairs in the low mass region $M < 2m_\pi$.

*Phys. Lett B383, 457 (1996).

[†]Department of Physics, University of Arizona, Tucson, AZ 85721

Thermal Equilibration in an Expanding Parton Plasma *

H. Heiselberg[†] and X. N. Wang

The approach to thermal equilibrium in relativistic heavy ion collisions is dictated by the competition between expansion and parton interactions. If the expansion is much more rapid than the typical collision time among partons, the expansion is closer to free-streaming than hydrodynamic expansion. Only at times on the order of the collision time may the parton gas reach local thermal equilibrium and expand hydrodynamically. Furthermore, the time dependence of the collision time (or the relaxation time) will determine whether the system can eventually reach local thermal equilibrium because of the competition between expansion and parton interactions. If the collision time increases rapidly with time, the parton system may never thermalize, leading only to a free-streaming limit. The collision time, therefore, is a very important quantity which in turn depends sensitively on the infrared behavior of parton interactions.

What determine the thermalization processes are the transport rates which are free of logarithmic divergences after the resummation of thermal loops. This is because thermalization is achieved to leading order mainly through momentum changes by elastic scatterings. The resultant transport times for a system near thermal equilibrium behave like

$$\frac{1}{\tau_{tr}} \sim T \alpha_s^2 \ln(1/\alpha_s) \quad (1)$$

to leading order in α_s .

For a system near local thermal equilibrium, the time dependence of the transport times is through the temperature according to Eq. (1). This dependence is in general slower than $1/\tau$ and thus can lead to local thermal equilibrium according to arguments based on the relaxation time approximation. We can solve the Boltzmann equation in the relaxation time approximation and demonstrate how the time dependence of the relaxation time will affect the approach to thermal equilibrium.

From Fig. 1, one can see that if the time dependence of the relaxation time is weaker than linear, the thermal equilibrium limit will




Figure 1: Time evolution of $G(\tau/\tau_0)(\tau/\tau_0)^{1/3} = (\epsilon/\epsilon_0)(\tau/\tau_0)^{4/3}$ according to the solution to Boltzmann equation, for different time dependence of the relaxation time $\theta = \theta_0(\tau/\tau_0)^\beta$, with $\theta_0/\tau_0 = 1$, $\beta = 0.9$ (dotted), $1/3$ (solid), $1/4$ (dot-dashed) and 0 (dashed line). $Y_0 = 1.2$ is the width of the initial rapidity distribution.

eventually be reached. For a time dependence stronger than the linear one, the system will never thermalize, only leading to a free-stream limit. For an exact linear time dependence, the system will reach an asymptotic state between free-streaming and thermal equilibrium. We find that the thermalization process also depends on the initial condition of the system. The deviation of the initial momentum distribution from an isotropic one in the longitudinal direction determines the initial approach to thermal equilibrium. This initial approach will then carry its inertia throughout the whole thermalization process. This "memory effect" can be seen from the dependence of the final total entropy production on the initial momentum distributions.

*Nucl. Phys. B462, 389 (1996).

[†]NORDITA, Blegdamsvej 17, DK-2100 Copenhagen Ø., Denmark

Domain Structure of a Disoriented Chiral Condensate from a Wavelet Perspective *

Z. Huang[†], I. Sarcevic[†], R. Thews[†] and X. N. Wang

Theoretical investigations of nonequilibrium dynamics using the classical linear σ -model have found some evidence for the formation of Disoriented Chiral Condensate (DCC) or the growth of long wavelength pion modes. Although the precise dimension of a typical domain or cluster is still under debate, it seems likely, especially in heavy-ion collisions, that many domains or clusters could be formed in the large interaction volume. If there are many uncorrelated small domains, the integrated probability distribution of the neutral pion fraction f emitted from a disoriented region, predicted to be $P(f) = 1/2\sqrt{f}$, would become Gaussian, following the Central Limit Theorem.

Normally DCC domains are localized in coordinate space. If they develop collective motion in the course of their time evolution, they should also appear localized in momentum space. In order to disentangle the DCC domain structure in high energy heavy-ion collisions, we propose a new method which emphasizes not only the behavior of the probability distribution in the full phase space region but also its fluctuation in rapidity η or azimuthal angle ϕ . It is a multiresolution analysis performed by a discrete wavelet transformation (DWT) which has been found effective in systematically detecting structures on various scales in turbulence, astrophysics, and multiparticle production. We demonstrate that the DWT proves to be very useful in identifying and measuring the DCC domain structures *simultaneously* in terms of their size (in scale) and location (in space). Since it is likely that there are other physical scales accompanying the typical DCC domain scale in a physical process, the multiresolution feature of the DWT is essential for identification of the structures of interest. It acts like a mathematical microscope which can zoom in or out to various scales at each location. Due to the completeness and orthogonality of the DWT basis, there will be no information loss.

Shown in Fig. 1 are the wavelet power spectrum in rapidity of different samples. The ran-




Figure 1: The wavelet power spectra for different dynamical scenarios.

dom noise sample features a flat power spectrum, i.e. the power of fluctuations is the same at any scale. For the DCC sample there should be a flat spectrum when the scale is small and some power build-up should show up when the scale becomes larger than the DCC scale. The crossing point in Fig. 1 is found to be at $j_d = 3.6$ which unambiguously suggests the existence of the DCC clustering with a typical size of $\Delta\eta_d = 2\eta_{\max}/2^{j_d} \simeq 0.8$ units in rapidity. Also plotted is the power spectrum from HIJING Monte Carlo data which is also flat, consistent with the random noise case.

The existence of a plateau structure in the wavelet power spectrum is important in that one may attempt to define an effective "temperature" inside a domain structure where the fluctuations are relatively "stable" against the scale change.

*Phys. Rev. D 54, 750 (1996).

[†]Department of Physics, University of Arizona, Tucson, AZ 85721

J/ψ Suppression in an Equilibrating Parton Plasma *

Xiao-Ming Xu[†], D. Kharzeev[‡], H. Satz and X. N. Wang

J/ψ suppression due to color screening has been proposed to probe deconfinement. This requires that the interactions of J/ψ with hadrons and deconfined partons are different. A parton-based calculation of J/ψ -hadron cross section via an operator product expansion gives a very small break-up cross section at low energies. Only at very high energies, this cross section will reach its asymptotic value of a few mb. Therefore, a slow J/ψ is very unlikely to be absorbed inside a hadron gas of reasonable temperature.

On the other hand, a deconfined partonic system contains much harder gluons which can easily break up a J/ψ . A study of the energy dependence of the gluon- J/ψ inelastic cross section shows a strong peak just above the break-up threshold of the gluon energy, $\epsilon_0 = 2M_D - M_{J/\psi}$, where $M_{J/\psi}$ and M_D are the J/ψ and D meson masses, respectively. In the pre-equilibrium stage, i.e., before the partons have reached equilibrium, the average parton transverse momentum is sufficiently large to break up a J/ψ , provided the partons are deconfined. The dissociation of the J/ψ will continue during the whole equilibration process until the effective temperature drops below a certain value or the beginning of hadronization, whichever takes place first. Therefore measurements of J/ψ suppression can probe the deconfinement of the early partonic system and shed light on the subsequent equilibration process, provided that possible nuclear effects on the production of $Q\bar{Q}$ pairs and on pre-resonance charmonium states are understood and taken into account.

In this paper we first calculated the thermal gluon- J/ψ dissociation cross section at different temperatures and for different J/ψ transverse momentum. We then follow the evolution of an initially produced parton gas toward equilibrium and calculate the resulting total survival probability of a J/ψ and its p_T -dependence.

Shown in Fig. 1 are the J/ψ survival probabilities in the deconfined and equilibrating parton plasma at RHIC and LHC energies with initial conditions given by HIJING Monte Carlo simulations. We find that there is stronger J/ψ sup-




Figure 1: The survival probability of J/ψ in an equilibrating parton plasma at RHIC and LHC energies with initial conditions given by HIJING.

pression at LHC than at RHIC energy, due both to the higher initial parton densities and longer lifetime of the parton plasma. The increase of the survival probabilities with the J/ψ transverse momentum is a consequence of the decrease of the thermal cross section with increasing p_T at high temperatures and the shorter time spent by a higher- p_T J/ψ inside the parton plasma.

For a parton system with a low initial temperature (below 300 MeV), the p_T dependence of the survival probability should be flatter. One can therefore use the p_T dependence to shed light on the initial temperature and the evolution of the system.

*Phys. Rev. C **53**, 3051 (1996).

[†]Theory Division, Shanghai Institute of Nuclear Research, Chinese Academy of Sciences, P.O. Box 800204, Shanghai 201800, China

[‡]Fakultät für Physik, Universität Bielefeld D-33501 Bielefeld, Germany

Screening of Initial Parton Production in Ultrarelativistic Heavy-ion Collisions *

K. J. Eskola[†], B. Müller[‡] and X. N. Wang

Because the dominant QCD parton cross sections are singular in the soft scattering limit, most model calculations of minijet production via perturbative QCD (pQCD) have introduced an infrared cut-off, p_0 , corresponding to the smallest permissible transverse momentum transfer in a $2 \rightarrow 2$ parton scattering, to which perturbative QCD can still be applied. This cut-off is used in most of the models to separate perturbative hard processes from nonperturbative soft interactions. Since there is no distinct boundary between soft and hard physics, both the hard and soft part of the interaction in this scheme are very sensitive to the cut-off p_0 .

Heavy ion collisions differ from pp collisions in that minijets are produced in large number, so that a medium of minijets is formed. In the space-time evolution of a heavy-ion collision soft particle production will be completed after semihard and hard processes. Therefore, the soft interactions are expected to be screened by interactions with the semihard quanta (minijets). We here take a step further by proposing that the perturbative semihard particle production should also be screened by the processes which have happened even earlier, i.e., by the harder processes.

We considered color screening of initial semihard parton production in a phenomenological but self-consistent manner. We first compute the static electric screening mass of the parton system by using the number distributions of produced minijets with transverse momentum larger than p_T and by taking into account the formation time of the minijets. We then use the obtained electric screening mass as a regulator in divergent t and u -channel sub-processes for the production of partons with transverse momentum smaller than p_T . We iteratively compute the lowest order minijet cross section with a feedback from the screening mass towards the region $p_T \sim \mu_D \lesssim 2$ GeV.

In Fig. 1 we show the screening mass μ_D and the screened one-jet cross section as functions of p_T . We can see that the medium of produced




Fig. 2

Figure 1: (a) Differential minijet cross section $d\sigma_{jet}/dp_T dy$ at $y = 0$ and screening mass μ_D as functions of transverse momentum p_T in a pp sub-process of a central AA collision at $\sqrt{s} = 5.5$ ATeV with $A = 200$. The dashed line is for the unscreened cross section, the solid and dotted curves for the screened case with different parameters a . Nuclear shadowing is not taken into account. (b) The same as in panel (a) but for $\sqrt{s} = 200$ AGeV.

minijets regulates the rapid growth of the jet cross section. Finally, at $\mu_D \sim p_T$, the cross section saturates. For sufficiently large nuclei and for high collision energies this happens in the perturbative region $p_T \gg \Lambda_{QCD}$.

*Phys. Lett. **B374**, 20 (1996).

[†]TH Division, CERN, CH-1211 Geneva 23, Switzerland

[‡]Department of Physics, Duke University, Durham, NC 27708-0305

Partial $U(1)_A$ Restoration and η Enhancement in High-Energy Heavy-Ion Collisions *

Z. Huang[†] and X. N. Wang

It is well known that the $U(1)_A$ symmetry in QCD is violated by the axial anomaly present at the quantum level and thus cannot give rise to the Goldstone boson which would occur when $U(N_f) \times U(N_f)$ chiral symmetry is spontaneously broken. The $U(1)_A$ particle, known as $\eta'(958)$ in the $N_f = 3$ case, acquires an additional mass through the quantum tunneling effects mediated by instantons, breaking up the mass degeneracy with pions, kaons and η 's. The $\eta(547)$ particle also acquires an additional mass through the mixing with the η' . It is believed that at high temperatures the instanton effects are suppressed due to the Debye-type screening. Then one expects a practical restoration of $U(1)_A$ at high temperatures.

One of the consequences of $U(1)_A$ restoration is the enhancement of η particle production at small and intermediate transverse momenta due to the softening of its mass at high temperatures. However, the final yield of the η particles and their p_t distributions both depend crucially on the chemical and thermal equilibrating processes involving the η .

In this paper, we examine the rates of various processes relevant for the thermal η particle production, in particular, whether or not the η can decouple early enough from the thermal system expected to be produced in relativistic heavy-ion collisions. We present a theoretical calculation of thermal cross sections for the processes $\eta\eta \leftrightarrow \eta\eta$, $\pi\eta \leftrightarrow \pi\eta$ and $\eta\eta \leftrightarrow \pi\pi$, essential to the thermal and chemical equilibration. Our calculations are based on models which explicitly incorporate the $U(1)_A$ anomaly. We also assume an exponential suppression of the $U(1)_A$ anomaly due to the Debye-type screening of the instanton effect, which leads to the temperature dependence of the η and η' masses. Our results, as shown in Fig. 1 and 2, suggest that the η particles are out of chemical equilibrium long before the thermal freeze-out.

*Phys. Rev. D **53**, 5034 (1996).

[†]Department of Physics, University of Arizona, Tucson, AZ 85721




Figure 1: The temperature dependence of m_η , $m_{\eta'}$, m_δ .




Figure 2: The characteristic time scales of the thermal and chemical equilibration for the η particle.

Study of Parton Energy Loss in High-energy Heavy-ion Collisions *

X. N. Wang

Medium-induced radiative energy loss of a high-energy parton traversing a dense QCD medium is interesting not only because it illustrates the importance of quantum interference effects in QCD, but also because it depends sensitively on the density of the medium and thus can be used as a probe of the dense matter formed in ultrarelativistic heavy-ion collisions. Unlike in the QED case, where one can measure directly the radiative energy loss of a fast electron, one cannot measure directly the energy loss of a fast leading parton in QCD. One can only measure parton energy loss indirectly via the modification of the jet fragmentation function and jet profile. Here, the effects of energy loss on single-particle distributions both in the normal central $A + A$ collisions and in events with a tagged direct photon with known transverse energy are reviewed.

The p_T distribution of particles from jet fragmentation in a normal central heavy-ion collision can be calculated via the convolution of the fragmentation functions with the jet cross sections. In AA collisions, one has to take into account the modification of the jet fragmentation functions due to parton energy loss inside the medium. Then, jet energy loss will result in the suppression of high p_T particles as compared to pp collisions. Therefore, the ratio,

$$R_{AA}(p_T) = \frac{dN_{AA}/dy/d^2p_T}{\sigma_{pp}T_{AA}(0)dN_{pp}/dy/d^2p_T}, \quad (1)$$

at large p_T in Fig. 1 is smaller than one due to the energy loss suffered by the jet partons. It, however, increases with p_T because of the constant energy loss. The ratio is normalized to the effective total number of binary pp collisions in a central AA collision.

In order to study the modification of the fragmentation function due to energy loss, one might in principle measure the inclusive p_T spectrum in the direction of a triggered jet. However, with the large background and its fluctuation due to hadrons from many other minijets and soft processes, the determination of the jet en-




Figure 1: The ratio of charged particle p_T spectrum in central $Au + Au$ collisions at $\sqrt{s} = 200$ GeV over that of pp collisions, normalized by the total binary nucleon-nucleon collisions in central $Au + Au$ collisions. The mean-free-path of a quark inside the medium is assumed to be 1 fm.

ergy is almost impossible. To overcome this difficulty, we proposed the study of the high p_T particle spectrum in the opposite direction of a tagged direct photon. Direct photons are always accompanied by a jet in the opposite transverse direction. Even taking the initial state radiation into account, the average energy of the jet is approximately that of the tagged photon. One can therefore relate the p_T distributions of hadrons in the opposite direction of a tagged photon to the fragmentation function of a jet with known initial energy and study the modification of the fragmentation function due to parton energy loss.

*LBNL-39408, in the proceedings of RHIC Summer Study 196.

A pQCD-based Approach to Parton Production and Equilibration in High-Energy Nuclear Collisions *

X. N. Wang

In this report, I presented a perturbative QCD (pQCD)-based picture of ultrarelativistic heavy-ion collisions. In this framework, a nucleus in the infinite momentum frame consists of many partons (quarks and gluons). The interactions among these partons can be divided into perturbative, which can be described by pQCD calculations, and nonperturbative, which can only be modeled phenomenologically. I demonstrate that pQCD processes dominate the underlying dynamics of heavy-ion collisions at extremely high energies. It is then reasonable to assume that the evolution of the initially produced partons can be described by pQCD processes. Using the initial conditions estimated by the HIJING Monte Carlo model, the following picture emerges:

(1) During the early stages of ultrarelativistic heavy-ion collisions, hard or semihard parton scatterings, which happen in a time scale of about $0.2 \text{ fm}/c$, produce a hot and undersaturated parton gas. This parton gas is dominated by gluons and is far from chemical equilibrium. Multiple hard scatterings suffered by a single parton during this short period of time when the beam partons pass through each other are suppressed due to the interference embedded in the Glauber formula for multiple scatterings. Interference and parton fusion also lead to the depletion of small x partons in the effective parton distributions inside a nucleus. This nuclear shadowing of parton distributions reduces the initial parton production.

(2) After the two beams of partons pass through each other, the produced parton gas in the central rapidity region starts its evolution toward (kinetic) thermalization and (chemical) equilibration through elastic scatterings and induced radiations. Further evolution of the parton gas toward a fully equilibrated parton plasma is dictated by the parton proliferation through induced radiation and gluon fusion. Though the gluon equilibration rate is reduced by the inclusion of the Landau-Pomeranchuk-Migdal effect, the gluon fugacity still increases rapidly toward

its equilibrium value. Due to the consumption of energy by the additional parton production, the effective temperature of the parton plasma cools down considerably faster than the ideal Bjorken scaling solution. Therefore, the life time of the plasma is reduced to $4 - 6 \text{ fm}/c$ before the temperature drops below the QCD phase transition temperature.

(3) The evolution of the quark distribution always lags behind that of gluons due to a smaller equilibration rate and the initial density. For heavy quarks, the equilibration rate is even smaller. Take charm quarks for example. The thermal production during the equilibration period is much smaller than the initial direct production, due to the small initial gluon fugacity and the short lifetime during which the temperature remains high enough to produce charm quarks. For the same reason, dilepton and photon production during the evolution of the parton plasma is also small because of small quark number density. Therefore, observation of large charm and dilepton enhancement would imply high initial gluon and quark density and thus a longer life time of the parton plasma.

(4) Even though the initial parton system is not in full equilibrium, a study of color screening shows that the system is already in a deconfined state with large average momentum (or effective temperature). Such a deconfined parton system, though not in equilibrium, will dissociate hadronic states such as the J/ψ . It was shown that the J/ψ can be substantially suppressed during the evolution of the parton plasma toward equilibrium. The measurements of this suppression can reveal the initial conditions and the evolution history of the parton plasma in high-energy heavy-ion collisions.

*LBNL-38145, 1997, Physics Report in press.

Phenomenology of Charm and Bottom Production*

R. Vogt

Previous measurements of the $c\bar{c}$ production cross section at $\sqrt{S} \leq 63$ GeV suggested that the Born cross section underpredicted the data by a factor of two to three, called the K factor after a similar situation in Drell-Yan production,

$$K_{\text{exp}} = \frac{\sigma_{\text{data}}(AB \rightarrow Q\bar{Q})}{\sigma_{\text{theory}}(AB \rightarrow Q\bar{Q})}, \quad (1)$$

where Q is the produced heavy quark. An analogous theoretical K factor can be defined from the ratio of the next-to-leading order (NLO) to the Born cross sections,

$$K_{\text{th}} = \frac{\sigma_{\text{NLO}}(AB \rightarrow Q\bar{Q})}{\sigma_{\text{Born}}(AB \rightarrow Q\bar{Q})}, \quad (2)$$

where σ_{NLO} is the sum of the Born and $\mathcal{O}(\alpha_s)$ corrections. The NLO cross section is strongly dependent on the choice of the renormalization and factorization scales, μ_R and μ_F , which determine both K_{exp} and K_{th} .

We discuss the scale dependence of c and b quark production and its influence on the K factors. We adjust the scales and the heavy quark mass, m_Q , to achieve $K_{\text{exp}}^{\text{NLO}} \approx 1$ [1] keeping in mind that further corrections to the cross section could also be large. Our calculations are done with a Monte Carlo program developed by Nason and collaborators [2].

The physical cross section should be independent of the scale. If the perturbative expansion is convergent, *i.e.* if further higher-order corrections are small, at some scale the $\mathcal{O}(\alpha_s^{n+1})$ contribution to the cross section should be smaller than the $\mathcal{O}(\alpha_s^n)$ contribution. If the scale dependence is strong, the perturbative expansion is untrustworthy. Since $K_{\text{th}} - 1 > 1$, further higher-order corrections are needed, particularly for charm and bottom quarks which are rather "light" when \sqrt{S} is large. Although the scales are, in principle, independent, we take $\mu_F =$

$\mu_R = \mu$ because this assumption is inherent in global analyses of parton densities.

In calculations of the total cross section, $\mu \propto m_Q$. However, for single inclusive or double differential distributions, it may be more appropriate to choose a scale proportional to the transverse momentum of the heavy quark, p_T , or its transverse mass, m_T . A constant scale would be appropriate if $m_Q \simeq p_T$, but generally $m_c \ll p_T$ and $m_b \ll p_T$ at collider energies. Therefore the p_T dependent scale absorbs (resums) large logarithmic terms such as $\ln(p_T/\mu)$ appearing when $p_T \gg m_Q$ and producing collinear divergences which are unregulated if $\mu = m_Q$.

Since the $Q\bar{Q}$ pair distributions are essential to determine their contribution to lepton pair production, it would be convenient if the nontrivial distributions could be modeled by the Born distributions to within a constant K_{th} . With $\mu \propto m_T$, K_{th} is nearly constant, even in a regime where $m_Q \ll \sqrt{S}$ although some variations occur near the boundaries of phase space. Thus event generators for heavy quark production can, with relative confidence, scale all non-trivial Born results. Thus for heavy quark and quark pair distributions calculable at the Born level, K_{th} is nearly constant provided that $\mu \propto m_T$. The actual value of K_{th} can be determined by a comparison of the NLO and Born total cross sections.

[1] P.L. McGaughey *et al.*, Int. J. Mod. Phys. **A10** (1995) 2999.

[2] M.L. Mangano, P. Nason, and G. Ridolfi, Nucl. Phys. **B373** (1992) 295; M.L. Mangano, P. Nason, and G. Ridolfi, Nucl. Phys. **B405** (1993) 507.

*LBL-37105; Z. Phys. **C71** (1996) 475.

Lepton Production from Charm Decay in Nuclear Collisions at $\sqrt{s} = 200 \text{ GeV}$ and 5.5 TeV per Nucleon*

S. Gavin[†], P. L. McGaughey[‡], P. V. Ruuskanen[§] and R. Vogt

Dilepton production provides an important tool for measuring the temperature of the high density matter produced in the early stages of a relativistic heavy-ion collision [1]. In high energy pp interactions, the continuum in the dilepton mass range above $M \sim 2 \text{ GeV}$ is dominated by the Drell-Yan process and by semileptonic decays of charm mesons. This production can be addressed using perturbative QCD. In contrast, the lower mass region arises from soft processes, for which theory offers little guidance. We therefore hope to find a signal of thermal dilepton production at masses $M \sim 2 - 3 \text{ GeV}$ where *i*) the thermal contribution can still be sizable and *ii*) the background is calculable.

We compare the predictions of dilepton production from a simple thermal model with the hard 'background' from heavy quark pair, $Q\bar{Q}$, decays and Drell-Yan production at RHIC and LHC nucleus-nucleus collision energies, $\sqrt{s} = 200 \text{ GeV}$ and 5.5 TeV in the nucleon-nucleon center of mass. This background is now calculated to next-to-leading order (NLO), shown to agree with pp and $p\bar{p}$ data [2], and is no longer dependent on arbitrary phenomenological 'K factors'. The remaining uncertainties in the NLO perturbative approach are well defined and likely rather small [2]. We also calculate the invariant mass and transverse momentum distributions of the lepton pairs and use these distributions to illustrate how thermal and hard dileptons can be distinguished in an experiment. In addition, we introduce the dilepton contribution from B meson decays, and discuss the effects of nuclear shadowing on the initial production.

We find that hard charm quark production and decay dominates the continuum below the Υ mass. In particular, the charm signal is more than an order of magnitude above the optimistic

thermal dilepton and thermal charm rates for $M > 2 \text{ GeV}$. Thus the isolation of thermal signals will not be straightforward.

To experimentally enhance the thermal signal, one can count only those lepton pairs with a small separation in rapidity. Lepton pairs from charm decays typically occur with a large rapidity gap, absent in Drell-Yan and thermal pairs. Together with like-sign subtraction, rapidity gap cuts can essentially remove the uncorrelated charm and greatly suppress the correlated charm background. The finite acceptance of a real detector can serve this purpose. Then at least one of the $D\bar{D}$ decay leptons may be outside the finite detector acceptance. In particular, relatively few high mass lepton pairs from uncorrelated $D\bar{D}$ decays will be detected, significantly reducing the uncorrelated yield even before like-sign subtraction. We show that the acceptance window of PHENIX/RHIC and ALICE/LHC can enhance the signal from thermal charm decays to the point of measurability by rejecting pairs with large gaps. However, charm production remains the dominant source of dileptons in heavy-ion collisions, even with acceptance cuts, for $M < 6 - 8 \text{ GeV}$. Since charm cannot be removed simply by the finite detector acceptance, charm measurements are crucial.

[1] R. Vogt, B.V. Jacak, P.L. McGaughey and P.V. Ruuskanen, Phys. Rev. **D49** (1994) 3345.

[2] P.L. McGaughey *et al.*, Int. J. Mod. Phys. **A10** (1995) 2999; S. Gavin *et al.*, Int. J. Mod. Phys. **A10** (1995) 2961.

*LBL-37981; Phys. Rev. **C54** (1996) 2606.

[†]Physics Department, Brookhaven National Laboratory

[‡]Los Alamos National Laboratory

[§]Department of Physics, University of Jyväskylä, Jyväskylä, Finland

Charm and Bottom Quark Production Cross Sections Near Threshold*

J. Smith[†] and R. Vogt

Next-to-leading order calculations of charm production are large compared to the Born cross section, suggesting that further higher order corrections are substantial. Near threshold large logarithms in the perturbative expansion can arise from an imperfect cancellation of the soft-plus-virtual (S+V) terms, which must be resummed. An approximation of these terms was used to resum the leading logarithms to all orders in perturbation theory [1]. The method relies on the proportionality of the higher order terms to the Born cross section. A cutoff parameter, μ_0 , is introduced to keep the result finite. A strong dependence on μ_0 , implies that the cross section requires nonperturbative contributions.




Figure 1: We show the $c\bar{c}$ cross sections, σ^{res} (solid), $\sigma^{\text{imp}} = \sigma^{\text{res}} + \sigma^{\text{NLO}}|_{\text{exact}} - \sigma^{\text{NLO}}|_{\text{app}}$ (dashed), and $\sigma^{\text{NLO}}|_{\text{exact}}$ (dot-dashed), in (a) π^-p and (b) pp interactions. Extreme values of σ^{res} are shown in the dotted lines.

Because m_c is relatively small, $1.2 \leq m_c \leq 1.8$ GeV/ c^2 , charm production must be treated with

some care. The only consistent NLO evaluation of the pion and proton parton densities is GRV HO [2], in the $\overline{\text{MS}}$ scheme. This set also has a small initial scale so that $\mu = m_c = 1.5$ GeV/ c^2 is used. We find that resummed cross section, σ^{res} , in the $q\bar{q}$ channel in the $\overline{\text{MS}}$ scheme converges for $\mu_0 \approx 0.15m_c$ while the gg channel, with its larger color factor, converges for $\mu_0 \approx 0.35m_c$. The ratios μ_0/m_c agree with the convergence ratios for bottom and top production.

Figure 1 shows that the perturbative expansion no longer converges at higher energies, since σ^{res} and σ^{imp} increases with energy faster than $\sigma^{\text{NLO}}|_{\text{exact}}$. The upper dotted curves, with $\mu = m_c = 1.3$ GeV/ c^2 , increase faster than σ^{res} , implying that the resummation breaks down at lower energies for lighter masses. The lower dotted curves are calculated with $\mu/2 = m_c = 1.8$ GeV/ c^2 and the MRS D-' proton and SMRS P2 pion distributions [3]. The larger quark mass requires a larger μ_0 for convergence.

- [1] E. Laenen, J. Smith, and W.L. van Neerven, Nucl. Phys. **B369** (1992) 543.
- [2] M. Glück, E. Reya and A. Vogt, Z. Phys. C53 (1992) 127; Z. Phys. C53 (1992) 651.
- [3] A.D. Martin, W.J. Stirling and R.G. Roberts, Phys. Lett. **B306**, 145 (1993); P.J. Sutton, A.D. Martin, R.G. Roberts and W.J. Stirling, Phys. Rev. **D45** (1992) 2349.

*LBL-38282 and ITP-SB-95-60; Z. Phys. C in press.

[†]Institute for Theoretical Physics, State University of New York at Stony Brook

Resummed Heavy Quark Production Cross Sections to Next-to-Leading Logarithm*

N. Kidonakis[†], J. Smith[‡] and R. Vogt

The first resummation of leading logarithmic, LL, terms in heavy quark production was discussed in [1]. The analysis was based on the fact that the LL terms are identical to those in the Drell-Yan process. The importance of incorporating resummation effects in threshold production of heavy quarks in QCD was apparent. The order α_s^2 corrections to the Drell-Yan process allow a check of the NLL terms in the resummation formulae. However, this information cannot be used in heavy quark resummation since the color structure is more complicated. A resummation formalism which correctly incorporates the NLL heavy quark resummation near threshold has recently been presented [2].

We apply this new NLL resummation formalism to calculate the top quark production cross section at the Fermilab Tevatron and the bottom quark production cross section at fixed target energies. We are particularly interested in the size and therefore the phenomenological importance of the NLL terms with respect to the LL terms.

Our calculations are based on the factorization of soft gluons from high-energy partons in perturbative QCD. In [2] it was shown that to NLL it is possible to pick a color basis in which moments of the short distance cross section, $\hat{\sigma}_{ab}^{(IJ)}$, exponentiate so that

$$\begin{aligned}\tilde{\sigma}_{ab}^{(IJ)} &= \int_0^1 dz z^{n-1} \hat{\sigma}_{ab}^{(IJ)}(z, \theta^*, \alpha_s(Q^2)) \\ &= h_I(\theta^*, Q^2) h_J^*(\theta^*, Q^2) e^{E_{IJ}^{(ab)}}.\end{aligned}\quad (1)$$

The hard scattering prefactor is a product of contributions from the amplitude h_I and its complex conjugate h_J^* . The functions h_I and h_J^* have no collinear or soft divergences at the partonic threshold since these terms have been factored

into the exponent E_{IJ} in eq. (1), given by

$$\begin{aligned}E_{IJ}^{(ab)} &= - \int_0^1 dz \frac{z^{n-1} - 1}{1-z} \\ &\times \left\{ (2-r) \int_0^z \frac{dy}{1-y} g_1^{(ab)}(y, z, Q^2) + g_2^{(ab)}(z, Q^2) \right. \\ &\left. + g_3^{(I)}(z, Q^2, \theta^*) + g_3^{(J)*}(z, Q^2, \theta^*) \right\},\end{aligned}\quad (2)$$

where g_1 , g_2 and g_3 are functions of the running coupling constant α_s . The scheme dependent parameter r changes the lower limit of the y -integral in the $\overline{\text{MS}}$ scheme.

The NLL functions $g_3^{(I)}$, depend on the color structure in the hard scattering so that $g_3^{(I)}$ is a function of both α_s and the angle θ^* between the incoming and outgoing partons. Although the eigenvalues are complex, the total g_3 contribution to $E_{IJ}^{(ab)}$ in eq. (2) is real.

We have investigated the numerical importance of the NLL terms in the resummation of subleading soft gluon contributions near threshold for heavy quark production cross sections. We have shown that these contributions are generally quite small for top production either because they are numerically small or due to cancellations between them. This result has only been demonstrated for the resummation method of [1] and at $\theta^* = 90^\circ$.

[1] E. Laenen, J. Smith, and W.L. van Neerven, Nucl. Phys. **B369**, 543 (1992).

[2] N. Kidonakis and G. Sterman, Phys. Lett. **B387**, 867 (1996); N. Kidonakis, SUNY at Stony Brook Ph.D. Thesis (1996), hep-ph/9606474.

*LBNL-39025, ITP-SB-96-32 and Edinburgh 96/30; submitted to Phys. Rev. D.

[†]Department of Physics and Astronomy, University of Edinburgh, Scotland

[‡]DESY, Hamburg, Germany and Institute for Theoretical Physics, State University of New York at Stony Brook

Reanalysis of the EMC Charm Production Data With Extrinsic and Intrinsic Charm at NLO*

B. W. Harris[†], J. Smith[‡] and R. Vogt

The European Muon Collaboration (EMC) [1] established that photon-gluon fusion (PGF) in QCD, the analogue of the Bethe-Heitler reaction in QED, explains most of the charm deep inelastic structure function F_2^c . However, the EMC data was not in complete agreement with PGF at all x and Q^2 . The disagreement at large x and Q^2 suggested that a higher-twist component of charm production was necessary, called intrinsic charm (IC) [2] to distinguish it from PGF, referred to as extrinsic charm (EC).

In the analysis of the EMC data [1], a relatively simple model was used for both the EC and IC components. At the time, only the LO contributions to F_2^c from both models were available. Afterwards, Hoffman and Moore [3] calculated the next-to-leading order (NLO) corrections to the IC component and discussed their effects on the EMC analysis. Based on LO photon-gluon fusion, they found evidence for an 0.3% IC component in the proton. Since the complete NLO results are now available for both EC and IC production, a more detailed QCD analysis of the EMC results is finally possible, allowing us to make a more reliable determination of the IC content of the proton.

Up to NLO, the IC component of the structure function is [3]

$$F_2^c = \frac{8}{9} \xi \left[c(\xi, \gamma) + \int_{\xi/\gamma}^1 \frac{dz}{z} c(\xi/z, \gamma) \sigma_2^{(1)}(z, \lambda) \right]. \quad (1)$$

Likewise the NLO EC structure function is

$$\begin{aligned} F_2^c = & \frac{Q^2 \alpha_s(\mu^2)}{4\pi^2 m_c^2} \int_{\xi_0}^1 \frac{d\xi}{\xi} \left[e_c^2 f_{\frac{p}{p}}(\xi, \mu^2) c_{2,g}^{(0)} \right] \\ & + \frac{Q^2 \alpha_s^2(\mu^2)}{\pi m_c^2} \int_{\xi_0}^1 \frac{d\xi}{\xi} \left\{ e_c^2 f_{\frac{p}{p}}(\xi, \mu^2) \left(c_{2,g}^{(1)} + \bar{c}_{2,g}^{(1)} \ln \frac{\mu^2}{m_c^2} \right) \right. \\ & \left. + \sum_{i=q,\bar{q}} f_{\frac{p}{p}}(\xi, \mu^2) \left[e_c^2 \left(c_{2,i}^{(1)} + \bar{c}_{2,i}^{(1)} \ln \frac{\mu^2}{m_c^2} \right) \right. \right. \end{aligned}$$

$$\left. \left. + e_i^2 d_{2,i}^{(1)} + e_c e_i o_{2,i}^{(1)} \right] \right\}. \quad (2)$$

The coefficient functions are of different origin: $c_{2,i}^{(1)}$ and $\bar{c}_{2,i}^{(1)}$ originate from the virtual photon-charmed quark coupling and appear for both charged and neutral parton-induced reactions; $d_{2,i}^{(1)}$ arise from the virtual photon-light quark coupling; $o_{2,i}^{(1)}$ come from their interference and do not contribute to F_2^c . Both the IC and EC components hold only in the DIS regime where $Q^2 > 0$.

We fit the EMC data with the sum of the EC and IC component of F_2^c . The normalization of both the IC and EC components are taken as free parameters,

$$F_2^c = \alpha F_2^{c,EC} + \beta F_2^{c,IC}, \quad (3)$$

with $\mu = \mu_0$. The shift in the normalization of the EC component may be considered as an estimate of the size of the NNLO contribution, equivalent to a shift in the scale μ . Since we have assumed a 1% normalization of the IC component, the fitted β is the fraction of this normalization. Our fitted value of β confirms the Hoffman-Moore result of an $\approx 0.3\%$ IC contribution to F_2^c .

[1] J.J. Aubert *et al.*, (EMC), Nucl. Phys. **B 213** (1983) 31; Phys. Lett. **B 94** (1980) 96; *ibid.* **B110** (1982) 73.

[2] S.J. Brodsky, P. Hoyer, C. Peterson and N. Sakai, Phys. Lett. **B93** (1980) 451; S.J. Brodsky, C. Peterson and N. Sakai, Phys. Rev. **D23** (1981) 2745.

[3] E. Hoffmann and R. Moore, Z. Phys. **C20** (1983) 71.

*LBL-37266, ITP-SB-95-15, and FSU-HEP-951030; Nucl. Phys. **B461** (1996) 181.

[†]Physics Department, Florida State University

[‡]Institute for Theoretical Physics, State University of New York at Stony Brook

Charmed Hadron Asymmetries in the Intrinsic Charm Coalescence Model*

R. Vogt and S.J. Brodsky[†]

In leading-twist charm production, there is no connection between the spectator and participant partons. However, in higher-twist processes, the interaction between spectators and participants can be strong. These higher-twist processes, such as intrinsic charm, are usually suppressed by $\alpha_s^2(M_{c\bar{c}})/M_{c\bar{c}}^2$ relative to leading-twist production. However, if the transverse distance between the partons is small, they may interact during the time they are near each other, allowing the higher-twist processes to become dominant.

The intrinsic $c\bar{c}$ production cross section, $\sigma_{ic}(hN) = P_{ic}\sigma_{hp}^{\text{in}}\mu^2/(4\hat{m}_c^2)$, extracted from 200 GeV proton- and pion-induced interactions, is $\sigma_{ic}(\pi^-N) \approx 0.5 \mu\text{b}$ and $\sigma_{ic}(pN) \approx 0.7 \mu\text{b}$ [1]. The probability of finding a $c\bar{c}$ pair in the proton wavefunction was determined from a fit to the EMC charm structure function [2]. Then the total charm production cross section is the sum of leading-twist fusion and higher-twist intrinsic charm, $d\sigma(hN)/dx_F = d\sigma_{\text{lt}}/dx_F + d\sigma_{ic}/dx_F$.

There are two ways of producing D mesons from intrinsic $c\bar{c}$ pairs. The first is through standard fragmentation processes. The c quarks can also coalesce with projectile valence spectators to produce leading charmed mesons. Coalescence introduces flavor correlations between the projectile and the final-state hadrons. A critical test of flavor correlations in charm production is the asymmetry between leading and nonleading charm. For example, in $\pi^-(\bar{u}d)$ interactions, the $D^-(\bar{c}d)$ is leading since it has a valence quark in common with the projectile while the $D^+(c\bar{d})$ with no valence quark in common, is nonleading. This observed leading behavior suggests that hadronization at large x_F involves the coalescence of the charmed quarks with projectile spectator quarks.

Here we extended this model to other charmed hadrons. As expected, the asymmetries predicted by the intrinsic charm coalescence model are a strong function of x_F . We find that Λ_c production in the proton fragmentation region ($x_F < 0$ in π^-p collisions) is dominated by the coalescence of the intrinsic charm quark with the ud valence quarks of the proton. The production of D_s/\bar{D}_s and, at $x_F > 0$, $\Lambda_c/\bar{\Lambda}_c$ by coalescence must occur within still higher Fock states such as $|n_V c\bar{c}d\bar{d}\rangle$ and $|n_V c\bar{c}s\bar{s}\rangle$. These states are normalized from a calculation of $\psi\psi$ production from $|n_V c\bar{c}c\bar{c}\rangle$ configurations which allows us to obtain the probability of additional light quark pairs in the Fock states by mass scaling. As more partons are included in the Fock state, the coalescence distributions soften and approach the standard fragmentation distributions. Thus we do not consider $\bar{\Lambda}_c$ production by coalescence at $x_F < 0$ since a minimal nine-parton Fock state is required. Therefore there is no asymmetry in the model for these cases.

[1] R. Vogt and S.J. Brodsky, Nucl. Phys. **B438** (1995) 261; R. Vogt and S.J. Brodsky, Phys. Lett. **B349** (1995) 569; R. Vogt, Nucl. Phys. **B446** (1995) 149.

[2] B.W. Harris, J. Smith, and R. Vogt, Nucl. Phys. **B461** (1996) 181.

*LBL-37666 and SLAC-PUB-95-7068; Nucl. Phys. **B478** (1996) 311.

[†]Stanford Linear Accelerator Center

Charmonium Suppression by Comover Scattering in Pb+Pb Collisions*

S. Gavin[†] and R. Vogt

Experiment NA50 has reported an abrupt decrease in ψ production in Pb+Pb collisions at 158 GeV per nucleon [1]. Specifically, the collaboration presented a striking ‘threshold effect’ in the ψ -to-continuum ratio by plotting it as a function of a calculated quantity, the mean path length of the ψ through the nuclear medium, L . This apparent threshold has sparked considerable excitement as it may signal the formation of quark-gluon plasma in the heavy system.

We study the Pb results in the context of a hadronic model of charmonium suppression [2]. We point out that the behavior as a function of L is not a threshold effect but, rather, reflects the approach to the geometrical limit of L as the collisions become increasingly central. When plotted as a function of the measured neutral transverse energy E_T , the data varies smoothly as in S+U measurements [1]. The difference between S+U and Pb+Pb data lies strictly in the relative magnitude. To assess this magnitude, we compare ψ and ψ' data to expectations based on the hadronic comover model [2].

The hadronic contribution to the suppression arises from scattering of the ψ with produced particles, comovers, and nucleons [2]. The standard nucleon absorption survival probability is

$$S_A = \exp\left\{-\int_z^\infty dz \rho_A(b, z) \sigma_{\psi N}\right\} \quad (1)$$

where ρ_A is the nuclear density, b the impact parameter and $\sigma_{\psi N}$ the absorption cross section for ψ -nucleon interactions. One can estimate $S_A \sim \exp\{-\sigma_{\psi N} \rho_0 L_A\}$, where L_A is the path length traversed by the $c\bar{c}$ pair.

Suppression can also be caused by scattering with produced particles traveling with the $c\bar{c}$ pair. This comover density scales $\propto E_T$. The

corresponding survival probability is

$$S_{co} = \exp\left\{-\sigma_{co} v n_0 \bar{\tau}_0 \ln\left(\frac{\tau_F}{\tau_0}\right)\right\}. \quad (2)$$

Thus S_{co} depends on the scattering frequency, the formation time of the comovers and the transverse size of the central region. The comover density, n_0 , scales roughly with E_T .

The path length L and transverse size R_T depend on the collision geometry. The path length grows with E_T , asymptotically approaching the geometric limit $R_A + R_B$. Nucleon absorption saturates for $b < R_A$, where R_A is the smaller of the two nuclei. On the other hand, E_T continues to grow for $b < R_A$ due, *e.g.*, to fluctuations in the number of NN collisions.

Our Pb+Pb predictions account for the NA50 data. Nucleon absorption indeed saturates for small values of b . Comover scattering accounts for the remaining suppression. To compare our predictions with the NA50 analysis [1], we calculate the continuum dimuon yield for $2.9 < M < 4.5$ GeV and adjust the E_T scale to the NA50 calorimeter, $1.1 < \eta < 2.3$. The agreement depends on these updates. The saturation with L but not E_T suggests an additional density-dependent suppression mechanism. Comover scattering explains the additional suppression. Nevertheless, it is unlikely that this explanation is unique.

[1] M. Gonin *et al.* (NA50), Proc. Quark Matter '96, Heidelberg, Germany, P. Braun-Munzinger *et al.*, eds. (1996).

[2] S. Gavin and R. Vogt, Nucl. Phys. **B345** (1990) 104; S. Gavin, H. Satz, R. L. Thews, and R. Vogt, Z. Phys. **C61** (1994) 351; S. Gavin, Nucl. Phys. **A566** (1994) 383c.

*LBL-37980; to be published in Phys. Rev. Lett.

[†]Physics Department, Brookhaven National Laboratory

Transverse Momentum of ψ and Dimuon Production in Pb+Pb Collisions*

S. Gavin[†] and R. Vogt[‡]

The NA50 collaboration at the SPS has reported a suppression of ψ production in Pb+Pb collisions relative to Drell-Yan dimuon production as the neutral transverse energy of hadrons, E_T , is increased [1]. They further presented a striking ‘threshold effect’ by comparing the data to S+U results as a function of the mean path length of the ψ through nuclear matter, L , calculated assuming a sharp-edged nucleus. We point out that the centrality dependence of the transverse momenta of Drell-Yan dimuons essentially provide an experimental determination of L . Such a determination can provide vital evidence for or against the threshold behavior.

Important information can be extracted from the nuclear dependence of the ψ 's transverse momentum, p_T . Hadronic suppression [2] does not modify the transverse momentum dependence of ψ production appreciably. To account for the nuclear modification measured in pA and S+U collisions, initial-state parton scattering was introduced [3]. This elastic parton scattering broadens the p_T distributions of charmonium and Drell-Yan production without affecting the p_T -integrated yields. Partons essentially undergo a random walk in momentum space, so that $\langle p_T^2 \rangle$ grows linearly with L .

In a hadron-nucleus collision, a parton from the projectile can suffer soft quasielastic interactions as it crosses the nuclear target [3]. The $\langle p_T^2 \rangle$ of the dimuon or ψ is increased by:

$$\Delta p_T^2 \equiv \langle p_T^2 \rangle - \langle p_T^2 \rangle_{NN} = \lambda^2(\bar{n}_A - 1), \quad (1)$$

where \bar{n}_A is the number of NN subcollisions that the projectile suffers in the target, λ^2 determines the p_T^2 increment from each subcollision and $\langle p_T^2 \rangle_{NN}$ is A -independent contribution from the hard scattering.

In a nucleus-nucleus collision, both projectile

and target partons scatter,

$$\Delta p_T^2 \equiv \langle p_T^2 \rangle - \langle p_T^2 \rangle_{NN} = \lambda^2(\bar{n}_A + \bar{n}_B - 2), \quad (2)$$

where the path length is

$$L \equiv (\bar{n}_A + \bar{n}_B)/2\sigma_{NN}\rho_0 \equiv \bar{n}/2\sigma_{NN}\rho_0. \quad (3)$$

The relation between \bar{n} and the impact parameter \bar{b} depends on the collision geometry.

We expect $\langle p_T^2 \rangle$ to increase by 12.3% for ψ as E_T increases from 50 to 150 GeV. This represents a flattening of $\langle p_T^2 \rangle(E_T)$ in comparison to the S+U $\rightarrow \psi + X$ data, which show an 18.5% increase as E_T varies from 30 to 90 GeV. However, we stress that the most direct extraction of L comes not from ψ but from Drell-Yan production since this process is unaffected by final-state interactions. To check that the NA50 extraction of L is correct, Drell-Yan data in Pb+Pb would have to establish a 2.7% increase in $\langle p_T^2 \rangle$. This requires dimuon data far more precise than that for S+U collisions.

The model parameters were revised to describe the latest E772 $pA \rightarrow \mu^+\mu^- + X$ data. Our revision implies a ratio $(\lambda_\psi/\lambda_{\mu^+\mu^-})^2 \sim 3.9$, larger than that extracted earlier, indicating that final-state scattering of the octet $c\bar{c}$ may occur. More precise $pA \rightarrow \psi + X$ measurements are needed to explore this possibility.

[1] M. Gonin *et al.* (NA50), Proc. Quark Matter '96, Heidelberg, Germany, P. Braun-Munzinger *et al.*, eds. (1996).

[2] S. Gavin and R. Vogt, LBL-37980, to be published in Phys. Rev. Lett.

[3] S. Gavin and M. Gyulassy, Phys. Lett. **B214** (1988) 241.

*CU-TP-791, DOE/ER/40561-292-INT96-21-01; submitted to Phys. Rev. C.

[†]Physics Department, Brookhaven National Laboratory and Physics Department, Columbia University

[‡]Institute for Nuclear Theory, University of Washington

Systematics of quarkonium production*

G. A. Schuler[†] and R. Vogt

Some time ago we [1] showed that existing quarkonium production data at fixed-target energies are, in fact, compatible with the assumption that the non-perturbative transition of the $Q\bar{Q}$ pair to quarkonium is more universal than expected from the velocity-scaling rules. Low-energy data are well reproduced if this infinite sum is truncated to a single term

$$\sigma [H(nJ^{PC})] = F[nJ^{PC}] \tilde{\sigma} [Q\bar{Q}] . \quad (1)$$

We demonstrate that the colour-evaporation model (CEM) of eq. (1) also accounts for quarkonium production at the Tevatron. The number of non-perturbative parameters is minimal, giving the model great predictive power.

The short-distance part of eq. (1) is the perturbative subthreshold cross section expanded in powers of $\alpha_s(\mu)$ where $\mu \propto m_Q$. Specifying to charm, the cross section is

$$\tilde{\sigma} [c\bar{c}] = \int_{2m_c}^{2m_D} dM_{c\bar{c}} \frac{d\sigma [c\bar{c}]}{M_{c\bar{c}}} \quad (2)$$

where $\sigma[c\bar{c}]$ is the *spin- and colour-averaged* open heavy-quark pair production cross section. The CEM is hence based on two ingredients. First, the quarkonium dynamics are assumed to be identical to those of low mass open $Q\bar{Q}$ pairs. All perturbative QCD corrections apply to the short-distance cross section and hence are identical for open and bound heavy-quark production. Second, although the $Q\bar{Q}$ pair is produced at short distances in different states, distinguished by colour, angular momentum, relative momentum, and their relative production rates may be different for different high-energy collisions, the average over many long-distance matrix elements, combined in the long-distance factor $F[nJ^{PC}]$, determines the probability to form a specific bound state. Necessarily, the factor F needs to be universal, *i.e.* process- and kinematics-independent.

The long-distance factors determined from the low-energy total cross sections are

$$F_{tot}[J/\psi] = 2.5\% \quad (3)$$

$$\sum_{n=1}^3 B[\Upsilon(nS) \rightarrow \mu\mu] F_{tot}[\Upsilon(nS)] = 1.6 \times 10^{-3} .$$

Here the subthreshold cross sections were calculated in next-to-leading order (NLO) using the MRS D-' parametrization [2] of the parton-distribution functions (PDF) with renormalization and factorization scales μ_R and μ_F chosen to be $\mu_R = \mu_F = 2m_c = 2.4$ GeV and $\mu_R = \mu_F = m_b = 4.75$ GeV, respectively. The results in eq. (4) are rather insensitive to variations of the parameters in the open heavy-quark cross section, if they are tuned to the open heavy-flavour total cross section data.

The transverse momentum distributions of prompt charmonium production (*i.e.* not originating from B decays) and bottomonium production at the Tevatron energy $\sqrt{s} = 1.8$ TeV, with normalizations extracted from eq. (4), are in good agreement with the data, typically better than 50%. The CEM prediction is based on the subthreshold cross section calculated to $O(\alpha_s^3)$, NLO for the p_T integrated cross section but LO only for the p_T distribution. In the absence of the NLO corrections to the p_T spectrum one might apply a K factor to account for the unknown higher-order corrections.

[1] P.L. McGaughey *et al.*, Int. J. Mod. Phys. **A10** (1995) 2999.

[2] A.D. Martin, R.G. Roberts and W.J. Stirling, Phys. Lett. **B306** (1993) 145.

*LBL-39012 and CERN-TH/96-157; Phys. Lett. **B387** (1996) 181.

[†]Theory Division, CERN

Upsilon Suppression in Pb+Pb Collisions at the LHC?*

R. Vogt

One of the proposed signatures of the QCD phase transition is the suppression of quarkonium production, particularly of the J/ψ [1]. In a quark-gluon plasma, the suppression occurs due to the shielding of the $c\bar{c}$ binding potential by color screening, leading to the breakup of the resonance. Because the Υ is much smaller than the $c\bar{c}$ and other $b\bar{b}$ resonances, a much higher initial temperature, T_i , than expected from past estimates is needed to dissociate the Υ [1]. Therefore it was previously assumed that the Υ would not be suppressed by QGP production. However, in view of the high T_i of a gluon plasma [2], $T_i \sim 1$ GeV, a reexamination of this assumption is in order. The relative suppression of the members of the Υ family should be testable at the LHC.

The potential for nonrelativistically bound quarkonium at finite temperature is [2]

$$V(r, T) = \frac{\sigma}{\mu(T)}(1 - e^{-\mu(T)r}) - \frac{\alpha}{r}e^{-\mu(T)r}, \quad (1)$$

where r is the separation between the Q and \bar{Q} and $\mu(T)$ is the screening mass. The parameters are $\sigma = 0.192$ GeV², $\alpha = 0.471$, $m_c = 1.32$ GeV and $m_b = 4.746$ GeV. Minimizing the quarkonium energy gives the radius of the bound state at each T . Where there is no longer a minimum and $\mu(T = T_D) = \mu_D$ the resonance no longer forms in the plasma.

We concentrate on the Υ states since they can be cleanly measured by CMS. It is necessary to know the dependence of the screening mass on temperature before T_D can be determined. Since the behavior of $\mu(T)$ is unknown for $T \gg T_c$, we show two rather extreme scenarios which may be expected to bracket the realistic situation. The first is a parameterization based on SU(N) lattice simulations,

$$\frac{\mu(T)}{T_c} \simeq 4 \frac{T}{T_c} \quad (2)$$

which results in the lowest values of T_D . Although $\mu(T)$ is independent of T_c , since we present our results as a function of the ratio T/T_c , for definiteness we take $T_c = 260$ MeV, consistent with SU(3) lattice calculations. For this value of T_c , the Υ breaks up at $T_D/T_c \approx 1.5$. In [2], this parameterization was used with $T_c = 150$ MeV, leading to the estimate $T_D/T_c \sim 2.6$ for the Υ . With initial temperatures of 260 MeV predicted for the LHC, Υ suppression appeared unlikely. The second is a perturbative estimate,

$$\frac{\mu(T)}{T_c} = \sqrt{1 + \frac{n_f}{6}g} \left(\frac{T}{T_c}\right) \frac{T}{T_c}, \quad (3)$$

with a temperature-dependent running coupling constant. In this case, T_D can be quite high and depends strongly on n_f and T_c . We present results use $n_f = 3$ and $T_c = 150$ MeV.

When the parameterization of eq. (3) is used, the Υ can easily be suppressed in the minijet gluon plasma. However, the perturbative estimate leads to much higher breakup temperatures, indicating that while the Υ' and χ_b resonances may break up, directly produced Υ 's will probably not. The initial energy density and temperature have been shown to be much larger at the LHC than previously predicted. One advantage of these higher densities is that Υ production may be suppressed, depending on the temperature dependence of the screening mass. The rates for bottomonium production are large enough for such effects to be observable in the dilepton spectra.

[1] T. Matsui and H. Satz, Phys. Lett. **B178** (1986) 416; F. Karsch, M.T. Mehr, and H. Satz, Z. Phys. **C37** (1988) 617.

[2] K.J. Eskola, K. Kajantie and P.V. Ruuskanen, Phys. Lett. **B332** (1994) 191; K.J. Eskola, Nucl. Phys. **A590** (1995) 383c.

*CMS TN/96-041

Determining the Existence and Nature of the Quark-Gluon Plasma by Upsilon Suppression at the LHC*

J. F. Gunion[†] and R. Vogt

Following up on the work presented in Ref. [1], we found that expectations for Υ production in Pb+Pb collisions at the LHC are very dependent upon the nature and details of the quark-gluon plasma (QGP). We demonstrated that this dependence may allow us to determine the fundamental nature of the QGP, including: the energy density, the initial temperature, the plasma radius and the screening mass. We chose the Υ family to examine in detail because while the Υ rate is high enough for statistically significant measurements to be made, particularly at the LHC, the Υ is not strongly affected by interactions with hadronic matter. Strikingly different expectations for the p_T -dependence of the Υ'/Υ ratio, are found depending upon whether or not the QGP is formed and on the QGP properties. While our calculations of the survival probability are rather schematic, the general trend is correct.

The much higher energy of the LHC could be crucial for Υ suppression by a QGP. The high minijet density at the LHC implies that the p_T spectra of the Υ resonances are likely to be highly sensitive to details of QGP formation. In contrast, at RHIC, the minijet density will be a factor of 10 to 30 smaller, and the maximum initial temperature predicted is $T_0 \sim 0.5$ GeV. Thus no suppression is expected. Thus even a very high T_0 does not guarantee plasma suppression. Models assuming a slow equilibration result in greater suppression because of the longer time the system spends in the screening region with $T > T_D$ where T_D is the resonance dissociation temperature.

Even if suppression is absent at RHIC, it is only at RHIC that pA measurements will be possible. Despite the lower energy, these pA measurements will greatly aid in constraining and checking our understanding of nuclear effects.

Thus, RHIC measurements will provide important benchmarks.

We demonstrated that statistics should be adequate to detect the differences in the Υ'/Υ ratio that would discriminate between different QGP models. Although such ratios have the advantage that systematic effects will cancel, further vital information can be extracted if the p_T spectra for the individual resonances can be measured. We have pointed to a comparison with Z production as a potentially useful benchmark. The ideal situation arises if HERA nuclear shadowing data is available for the x and Q^2 values appropriate for both Υ and Z production at the LHC so that the observed p_T spectrum for the Z could be compared to predictions using the experimentally measured nuclear parton densities. If there is agreement, then we can unfold the shadowing effects on the Υ p_T spectra.

Certain detector features will play a key role in carrying out the analysis as envisioned here. The resolution for the CMS detector is such that the Υ , Υ' and Υ'' resonances can be cleanly separated. Less certain is the extent to which the $\chi_b \rightarrow \gamma\Upsilon$ process can be separated from direct Υ production. The statistics necessary to discriminate between different QGP models is much greater if the direct 'prompt' Υ'/Υ ratio cannot be isolated. One also would lose the ability to observe the χ_b/Υ ratio. It will be important for the LHC detector groups to give further attention to both experimental issues.

[1] R. Vogt, CMS-TN/96-041.

*LBNL-39474 and UCD-96-31; submitted to Nucl. Phys. B.

[†]Davis Institute for High Energy Physics, Physics Department, University of California at Davis

Aspects of chiral symmetry*

Volker Koch

In this review the basic concepts of chiral symmetry in nuclear physics are reviewed. Effective chiral models such as the linear and nonlinear sigma model will be discussed as well as the essential ideas of chiral perturbation theory. Based on these models heuristic derivations of important current algebra relations, such as the Gell-Mann Oakes Renner relation, are provided. Emphasis is given to the applications for the physics of ultrarelativistic heavy ion collisions. In particular questions such as chiral

restoration, temperature and density dependencies of the scalar quark condensate are discussed. We also give a critical review concerning changes of vector meson masses and their relation to chiral symmetry. The basic principles behind the formation of disoriented chiral condensates are also discussed. The purpose of this review is to serve as an introduction to the chiral symmetry aspects of the physics of ultrarelativistic heavy ion collisions.

* LBNL-39463: *Jou. Mod. Phys. E*, in press.

Properties of hadrons in the nuclear medium *

C.M. Ko[†], V. Koch and G.Q. Li[§]

This review is devoted to the discussion of hadron properties in the nuclear medium and its relation to the partial restoration of chiral symmetry. Special attention is given to disentangling in-medium effects due to conventional many-body interactions from those due to the change of the chiral condensate. In particular, we medium effects on the Goldstone bosons (pion, kaon and eta), the vector mesons (rho, omega, phi),

and baryons (nucleon, delta, hyperons) are discussed. Also, for each proposed in-medium effect the experimental consequences are reviewed. These include subthreshold kaon production, kaon flow and pion spectra for the Goldstone bosons. Dilepton production is the central observable for the vector mesons and the relevance of the most recent measurements for possible in-medium modifications is thoroughly discussed.

* LBNL-39866: To appear in *Rev. Nucl. Part. Sci.*, Volume 47.

[†] Cyclotron Institute and Physics Department
Texas A&M University, College Station, Texas 77843

[§] Department of Physics State University of New York at
Stony Brook, Stony Brook, N.Y. 11794

Cold Kaons from Hot Fireballs*

Volker Koch

We have studied the effect of an attractive mean field potential on the low p_t behavior of particle spectra. Specifically, we concentrate on kaons in order to compare with preliminary data of the E-814 collaboration [1]. An attractive kaon potential would be conceivable in the framework of chiral perturbation theory if one allows for a considerable drop in the vector meson coupling above T_c , as suggested by lattice gauge calculations. We have used a relativistic transport model in order to simulate the expansion dynamics, since this approach also allow to include the effect of rescattering of the kaons. For the kaons, we take a potential of the form

$$U_K(r) = U_0 \frac{\rho_s}{\rho_0} \quad (1)$$

where the density ρ_s is the scalar density $\langle \bar{\psi}\psi \rangle$. Using a kaon potential of $U_0 \simeq -50$ MeV and a reduced vector coupling for the nuclear mean field of $g_v = 5.5$, which leads to an expansion velocity of the fireball of $V_{exp} \simeq 0.1c$ we obtain a slope parameter as low as 15 MeV for the low momentum kaons. Slow expansion is expected if the system is close to the chiral phase transition, where the expansion parameter p/ϵ is close to zero. If we, on the other hand, do not reduce the vector mean field coupling, the expansion velocity is $v_{exp} \simeq 0.3c$ and no soft component in the spectrum is seen.

A similar sensitivity is seen if one considers the coulomb interaction of the positively charge kaons (see. figure 1) with the charged fireball. If slow expansion is assumed the low p_t kaons are pushed away leading to an observable dip in the spectrum (dashed curve). For fast expansion, on the other hand, the potential has disappeared before the kaons have been shifted to




Figure 1: Initial and final kaon spectra for different expansion times τ including the coulomb interaction. The initial value for the kaon mean field has been taken to be $U_0 = -100$ MeV. All spectra are normalized at $m_t - m = 100$ MeV.

higher momenta resulting in no change of the slope (dotted curve). Similarly the low p_t spectrum of negative kaons will be enhanced. Therefore, a careful measurement of the ratio of positive to negative charge particles may reveal at low transverse momenta may reveal important information about the expansion velocity of the fireball.

[1] J. Stachel, Nucl. Phys. A566 (1994) 183c.

* LBNL-36961: Nucl. Phys. A590 (1995) 531c.

Thermal effects on dilepton production from pion-annihilation *

C. Song, V. Koch, S.H. Lee[†] and C.M. Ko[§]

Recently the CERES-collaboration has reported [1] a considerable enhancement in the dilepton spectrum over a hadronic cocktail in the invariant mass range $300 \text{ MeV} \leq M_{\text{inv}} \leq 500 \text{ MeV}$. Part of this enhancement is certainly due to pion annihilation which has not been taken into account in the CERES-cocktail. In a pion gas the pion-annihilation rate is modified by interactions with the environment in two ways. First, the pion form factor is reduced close to the mass of the ρ -meson [2]. This is a direct consequence of chiral restoration, where some of the strength of the current-current correlation function is moved to higher masses, around that of the a_1 meson. Secondly, the pion dispersion relation is modified in a pion gas due to the attractive p-wave interaction. As a result the pion annihilation cross section is enhanced for low invariant masses, just above the two pion threshold. A similar enhancement has been proposed by Gale and Kapusta in the context of BEVALAC energy heavy ion collisions, where the pion dispersion relation is modified due to the interaction with nucleons forming deltas. The combined effect of both in-medium modifications is to flatten the invariant mass spectrum due to pion annihilation in qualitative agreement with the CERES measurement (see figure 1). A quantitative comparison, however, requires to take into account the experimental acceptance cuts as well as the proper expansion dynamics of the system created in the heavy ion reaction [4].




Figure 1: Dilepton production rate from pion-annihilation at $T = 160 \text{ MeV}$. The dotted line is the result obtained without medium effects, the dashed line is that including modifications of the pion dispersion relation. The dashed-dotted line is the production rate obtained by only taking into account the in medium pion form-factor and the solid line is the result when both effects are taken into account.

- [1] G. Agakichiev et al., Phys. Rev. Lett. 75 (1995) 1272.
- [2] C. Song, S.H. Lee and C.M. Ko, Phys. Rev. C52 (1995) R476.
- [3] C. Gale and J. Kapusta, Phys. Rev. C35 (1987) 2107.
- [4] V. Koch and C. Song, Phys. Rev. C54 (1996) 1903.

* LBNL-37388: Phys. Lett. B 366 (1996) 379.

[†] Department of Physics, Yonsei University, Seoul 120-749, South Korea

[§] Cyclotron Institut, Texas A & M University, College Station, TX 77843

Dilepton production in relativistic heavy-ion collisions*

Volker Koch and Chungsik Song

Recently the CERES-collaboration has reported [1] a considerable enhancement in the dilepton spectrum over a hadronic cocktail in the invariant mass range $300 \text{ MeV} \leq M_{\text{inv}} \leq 500 \text{ MeV}$. Using a hadronic transport model we have calculated dilepton spectra using a wide range of initial conditions for the hadronic phase which are only constrained by the hadronic observables. The purpose of this exercise was twofold. First of all, we wanted to see to which extent the CERES data can be explained in a purely hadronic scenario including pion annihilation and other channels not included in the CERES cocktail. Secondly, we wanted to investigate to which extent a dilepton measurement puts additional constraints on the initial conditions of the hadronic phase. We found a very weak sensitivity of the dilepton invariant mass spectrum on the initial hadronic configurations (figure 1). As far as the CERES data are concerned we could reach the lower end of the sum of statistical and systematic error. It appears impossible, however, to explain the central points if they turn out to be correct after an improved measurement.

We also included the in-medium corrected pion annihilation cross section [2] into our calculation. While the pion-annihilation contribution is enhanced by a factor of about 2 in the low mass range, the total dilepton yield is only increased by 30 % and, thus our medium effect does not explain the CERES enhancement (figure 2).

We predicted no additional enhancement when going from the small system S+Au to the large system Pb+Pb. This is in agreement with preliminary data from the CERES collaboration [3].

* LBNL-38619: Phys. Rev. C54 (1996) 1903.




Figure 1: Dilepton invariant mass distribution for several initial hadronic configurations




Figure 2: Dilepton invariant mass spectrum with (full line) and without (dashed line) in-medium corrected pion annihilation in comparison with CERES (left) and HELIOS [4] (right) data.

[1] G. Agakichiev et al., Phys. Rev. Lett. 75 (1995) 1272.

[2] C. Song, V. Koch, S.H. Lee and C.M. Ko, Phys. Lett. B366 (1996) 379.

[3] A. Drees, Proceedings Quark Matter '96, to appear in Nucl. Phys. A.

[4] M. Masera, Nucl. Phys. A590 (1995) 93c.

Pion electromagnetic formfactor at finite temperature *

Chungsik Song and Volker Koch

In [1] we have proposed that a combined effect of an in medium modified pion dispersion relation together with a change of the pion form-factor due to chiral symmetry could provide a qualitative explanation for the enhancement of the dilepton production reported by the CERES collaboration [2]. As previous studies in the context of BEVALAC energy heavy ion collisions have shown [3,4], special care needs to be taken to ensure gauge invariance of the medium modified production amplitude. Using the soft pion limit, we explicitly could prove the gauge invariance of our result by showing that the relevant Ward-Takahashi identities are all satisfied.

An important result is that for back-to-back dilepton pairs the pion form factor in the time-like region does not have to go to one in the limit $k^2 \rightarrow 0$. Charge conservation constrains only the limit of the zero-component of the vertex-function

$$\Gamma_0(k_0 \rightarrow 0, \vec{k} = 0) = -\partial \Pi_\pi(p) / \partial p_0 \quad (1)$$

If, on the other hand, one approaches $k^2 \rightarrow 0$ from the space-like region the Ward-Takahashi identities constrain the spatial components of the vertex function

$$\Gamma_i(k_0 = 0, k_j = 0, j \neq i; k_i \rightarrow 0) = -\frac{\partial \Pi_\pi(p)}{\partial p_i}. \quad (2)$$

This of course is due to the fact that the heat bath breaks Lorentz invariance. In other words, there may very well a discontinuity in either Γ_0 or Γ_i when going from space-like to time like photons. The actual pion formfactor we obtain is shown in figure 1.

As far as a quantitative comparison with the CERES data is concerned, we found [5] that the change in the pion form-factor around the mass of the ρ -meson, which is directly related with the onset of chiral restoration, can not be extracted from present data. To achieve that one needs to have good enough a mass resolution to identify the ω -meson.




Figure 1: Pion form-factor at finite temperatures

- [1] C. Song, V. Koch, S.H. Lee and C.M. Ko, Phys. Lett. B 366 (1996) 379.
- [2] G. Agakichiev et al., Phys. Rev. Lett. 75 (1995) 1272.
- [3] C. Gale and J. Kapusta, Phys. Rev. C35 (1987) 2107.
- [4] C. Korpa and S. Pratt, Phys. Rev. Lett. 64 (1990) 1502.
- [5] V. Koch and C. Song, Phys. Rev. C54 (1996) 1903.

* LBNL-38362: Phys. Rev. C54 (1996) 3218.

Chemical relaxation time of pions in hot hadronic matter*

Chungsik Song and Volker Koch

We have studied the thermal and chemical relaxation time scales of pions in hot hadronic matter with an effective chiral Lagrangian. From the explicit calculation we show that pions in hot hadronic matter are in a phase where elastic collisions rates are very fast compared to typical expansion rates of the system. For chemical equilibration the dominant contribution comes from the inelastic collision involving a_1 mesons. Comparing with previous calculations [1] based on chiral perturbation theory, the inclusion of the resonances has reduced the chemical relaxation time by about a factor of 10. When we neglect the formation time of these resonances, the resulting chemical relaxation time of pions is 10 fm/c at $T = 150$ MeV. This value is comparable to the size of the hot system produced the collision of large nuclei.

Given a system size of $5 \sim 10$ fm we obtain a thermal freeze-out temperature which is small compared to those extracted from experiments [2,3]. This might be due to flow effects which lead to smaller effective system sizes. If we take the thermal freeze-out temperature be about 150 MeV, then the freeze-out size of the system would be $2 \sim 3$ fm. On the other hand the chemical relaxation time for a system of this size would be $T = 170$ MeV. This implies that chemical freeze-out of pions happens at considerably higher temperatures than thermal freeze-out.

We also have studied the effect of baryons on the chemical relaxation time of pions. Since the effect of baryons is suppressed by their large mass, we consider only low lying baryons, $N(938)$ and $\Delta(1236)$. To estimate the relaxation time we use the phenomenological cross section for $NN \rightleftharpoons N\Delta$. The effect of baryons is very small and can be neglected in SPS experiments.

* LBNL-38363: submitted to *Phys. Rev. C*




Figure 1: Chemical relaxation time of pions in hot hadronic matter. The reactions $\rho\rho \leftrightarrow \pi\pi$ (long dashed curve), $\pi\omega \leftrightarrow \pi\pi$ (dashed-dot curve), $\pi a_1 \leftrightarrow \pi\pi$ (dashed curve) and $\pi\pi\pi\pi \leftrightarrow \pi\pi$ (dotted curve) are considered. The solid curve represents the total relaxation time. These results are compared with the thermal relaxation time, τ_{th} .

However, it becomes important in AGS experiments where the baryon chemical potential is much larger than that in the SPS experiments.

We have extend the definition for the chemical relaxation time to a system of pions out of equilibrium with $\mu_\pi \neq 0$. In this case it is possible that the overpopulated pions will be reduced by the inelastic reactions involving vector and axial vector mesons. At $T = 150$ with $\mu_\pi = 100$ MeV the relaxation time is about 2 fm/c which is certainly comparable to the system size at freeze-out.

- [1] J. L. Goity, *Phys. Lett. B* 319 (1993) 401.
- [2] J. Stachel and P. Braun-Munzinger, *Phys. Lett. B* 216 (1989) 1.
- [3] U. Heinz, *Nucl Phys. A* 566 (1994) 205c.

Excess of pions with chiral symmetry restoration*

Chungsik Song and Volker Koch

Chiral symmetry, a symmetry of quantum chromodynamics (QCD) in the limit of massless quarks, is spontaneously broken in the ground state of QCD as indicated by the small mass of the pion. At high temperatures chiral symmetry is expected to be restored. However, some intriguing questions still remain on how chiral symmetry is actually restored in hot hadronic matter and what are the signatures of the restored phase.

One of the interesting features of the symmetry restored phase is the appearance of the scalar σ -meson which forms a chiral multiplet with the pions. At low temperatures where chiral symmetry is spontaneously broken, the σ -meson has very large width due to the strong decay channel into two pions. On the other hand, as the quark condensate drops with increasing temperature, the mass difference of the σ -meson and pion becomes small. As a result, the decay width of scalar meson decreases because the phase space available for the outgoing pions is reduced. Close to the phase transition temperature T_χ , the σ becomes an elementary excitation.

The observation of a narrow width scalar meson has been suggested as a direct signature of chiral symmetry restoration [1], but since the σ does not couple to any penetrating probes such as photons and dileptons this is difficult to observe in experiment. The purpose of this paper is to study the effect of the σ -meson on the pion production in high energy nucleus-nucleus collisions.

The pion production will depend on the thermodynamic conditions of a system during the evolution from hadronization to freeze-out. In the symmetric phase a *relative* chemical equilibrium among the particles will be established rapidly, leading to $\mu_\sigma = \mu_\pi$ and $\mu_\rho = 2\mu_\pi = \mu_{a_1}$.

The number of scalar mesons is then given by one third of the total number of pions at the given temperature. This is quite different from the situation encountered in the broken phase, where $\mu_\sigma = 2\mu_\pi$ and $\mu_{a_1} = 3\mu_\pi$. This is mainly due to the appearance of the light σ meson and the drop of the chiral condensate.

This difference in chemical equilibration conditions of pions might lead to the excess of pions at freeze-out. As temperature decreases and the symmetry is broken scalar mesons become heavier and decay into two pions. Also a_1 mesons decay into three pions. The number of observed pions will be given by the number of pions plus contributions from the resonance decay. When we include the scalar and a_1 meson contributions to observed pions, we have 1.4 ~ 1.6 times more pions compared to the case when there is no chiral phase transition. This, however, can only be observed, if the chiral transition temperature is not too high $T_\chi \leq 180$ MeV. Otherwise, pion number changing processes in the broken phase will absorb the excess obtained from the chiral phase transition.

Finally, let us conclude by pointing out that an analysis of the particle abundances measured at SPS-energy heavy ion collisions found an excess of pions by a factor of 1.6 over the expected thermal value [2]. However, a different analysis based on the same data, does not find such an excess of pions [3].

- [1] T. Hatsuda and T. Kunihiro, Prog. Theor. Phys. Suppl. 91 (1987) 284.
H. A. Weldon, Phys. Lett. B 274(1992) 133.
R. Pisarski, Phys. Rev. Lett. 76 (1996) 76.
- [2] M. Gazdzicki for the NA35 Collaboration, Nucl. Phys. A590, (1995) 215c.
- [3] P. Braun-Munzinger, J. Stachel, J. Wessels and N. Xu, Phys. Lett. B 365 (1996) 1.

* LBNL-39391: submitted to Phys. Lett. B

Effective mass of phi mesons at finite temperature*

Chungsik Song

For phi mesons, changes in their properties are interesting because they would affect the production rate in high energy nucleus-nucleus collisions, which probes the enhancement of strangeness in quark-gluon plasma phase [1]. Recently, it also has been suggested that a change of phi mass in hot hadronic matter might be a possible probe for the chiral phase transition in hot matter [2].

The effective mass of phi meson at non-zero temperature is examined with an effective chiral Lagrangian. We find that ϕ effective mass decreases with temperature and is reduced by about 20 MeV at $T = 200$ MeV. The dominant contributions come from kaon loops due to $\mathcal{L}_{\phi KK}$ and the $SU(3)_V$ symmetry breaking terms. As temperature increases effects from K^* mesons become important and increase the effective mass of phi meson.

Compared with the calculation done by K. Haglin and C. Gale [3], we do not have the large effect from kaon tadpole loops which increases phi mass. In our calculation we also have kaon tadpole loop corrections. However, these contributions come from $SU(3)_V$ symmetry breaking terms and show different effect. In the massive Yang-Mills approach which also includes vector mesons in chirally symmetric way, these tadpole loop contributions are exactly canceled by those from axial-vector-pseudoscalar loops [4]. This implies that chiral symmetry plays an important role in vector meson mass at finite temperature and shows different result. Calculations using QCD sum rules also show that the effective mass of phi mesons decreases with temperature. However, we have a small effect compared to the result obtained from in Ref. [2] and have an opposite result for K^* contributions. This difference requires more study in future.

* LBNL-38475: Phys. Lett. B 388 (1996) 141.




Figure 1: Effective mass of phi meson at finite temperature

A small change in ϕ effective mass makes it hard to observe the double phi peak in dilepton spectrum which has been suggested as a possible probes of chiral phase transition in hot hadronic matter. Since it has been estimated that the effective width of phi mesons in hot hadronic matter becomes about $20 \sim 30$ MeV, the mass shift obtained from the calculation will be within the effective width. With very accurate mass resolution, we might have a chance to see these small changes of the effective mass in dilepton spectrum. Details will also depend on the coupling of phi meson to photon which will be modified in hot hadronic matter as for ρ mesons.

- [1] Pin-Zhen Bi and J. Rafelski, Phys. Lett. B 262 (1991) 485.
- [2] M. Asakawa and C. M. Ko, Phys. Lett. B 322 (1994) 33, Nucl. Phys. A 572 (1994) 732.
- [3] K. Haglin and C. Gale, Nucl. Phys. B 421 (1994) 613.
- [4] Chungsik Song, Phys. Rev. D 53 (1996) 3962.

Dissipation and Decoherence in Mean Field Theory*

S. Habib[†], Y. Kluger, E. Mottola[†], and J.P. Paz[†]

The time evolution of a closed system of mean fields and fluctuations is Hamiltonian, with the canonical variables parameterizing the general time-dependent Gaussian density matrix of the system. Yet, the evolution exhibits both quantum decoherence and apparent irreversibility of energy flow from the coherent mean fields to fluctuating quantum modes. Using scalar QED as an example, we show how this collisionless damping and decoherence may be understood as the result of *dephasing* of the rapidly varying fluctuations and particle production in the time varying mean field.

Mean field methods have a long history in such diverse areas as atomic physics (Born-Oppenheimer), nuclear physics (Hartree-Fock), condensed matter (BCS) and statistical physics (Landau-Ginzburg), quantum optics (coherent/squeezed states), and semiclassical gravity. Because no higher than second moments of the fluctuations are incorporated, the mean field approximation is related to a Gaussian variational ansatz for the wave function of the system.

The broad applicability of the approximation, as well as the variety of different approaches to it in the literature makes it worthwhile to exhibit its general features unobscured by the particulars of specific applications. Accordingly, our first purpose in this work is to demonstrate the equivalence of the time-dependent mean field approximation to the general Gaussian ansatz for the mixed state density matrix ρ , and to underline its Hamiltonian structure.

The Hamiltonian nature of the evolution makes it clear from the outset that the mean field approximation does *not* introduce dissipation or time irreversibility at a fundamental level. Nevertheless, typical evolutions seemingly manifest an arrow of time, in the sense that energy flows from the mean field to the fluctuations without returning over times of physical interest.

Closely connected to this *effective* dissipation is the phenomenon of quantum decoherence, *i.e.* the suppression with time of the overlap between wave functions corresponding to two different mean field evolutions. This decoherence is the reason why quantum superpositions of different mean field states are difficult to observe in nature, and is crucial to understanding the quantum to classical transition in macroscopic systems.

Our second aim in this investigation is to present an explicit example of a quantum field theory (scalar QED) treated in mean field approximation where these effects are observed, and to provide a clear physical explanation of the behavior in terms of dephasing of the fluctuations, *i.e.*, the averaging to zero of their rapidly varying phases on time scales short compared to the collective motion of the mean field(s).

* LBNL-37786; Phys. Rev. Lett. 76 (1996) 4660.

[†] Theory Division, Los Alamos National Laboratory, Los Alamos, New Mexico.

Anomalous transverse distribution of pions as a signal for disoriented chiral condensates*

F. Cooper[†], Y. Kluger, and E. Mottola[†]

We give evidence that the production of DCC's during a non-equilibrium phase transition can lead to an anomalous transverse distribution of secondary pions when compared to a more conventional boost invariant hydrodynamic flow in local thermal equilibrium. Our results pertain to the linear σ model, treated in leading order in large- N , in a boost invariant approximation

In this work we see that a non-equilibrium phase transition taking place during a time evolving quark-gluon or hadronic plasma can lead to an enhancement of the low transverse momentum distribution. In particular, if a Centauro type event is not accompanied by such an enhancement one would be suspicious of ascribing this event to the production of disoriented chiral condensates as a result of a rapid quench.

Transverse expansion and direct pion-pion collisions are two competing effects that might change the degree of enhancement. The inclusion of transverse expansion might lead to amplification of the low momenta modes. On the other hand in the mean field approximation the pions can interact with the mean fields (DCC) via the auxiliary field χ but do not interact directly with each other. Direct pion-pion collisions will tend to thermalize the system, and reduce the amplification of the unstable low momentum modes. This effect is included only in the next to leading order term of the $1/N$ expansion, and we plan to incorporate it in a future work.

* LBL-38585; hep-ph/9604284; Phys. Rev. C (in press).

[†] Theory Division, LANL, Los Alamos, New Mexico.

Symmetry breaking in $\lambda\phi^4$ theory*

F. Cooper[†], S. Habib[†], Y. Kluger, and E. Mottola[†]

The time evolution of $O(N)$ symmetric lambda Φ^4 scalar field theory is studied in the large N limit. In this limit the $\langle \Phi \rangle$ mean field and two-point correlation function $\langle \Phi\Phi \rangle$ evolve together as a self-consistent closed Hamiltonian system, characterized by a Gaussian density matrix. The static part of the effective Hamiltonian defines the True Effective Potential U_{eff} for configurations far from thermal equilibrium. Numerically solving the time evolution equations for energy densities corresponding to a quench in the unstable spinodal region, we find results quite different from what might be inferred from the equilibrium free energy "effective" potential F . Typical time evolutions show effectively irreversible energy flow from the coherent mean fields to the quantum fluctuating modes, due to the creation of massless Goldstone

bosons near threshold. The plasma frequency and collisionless damping rate of the mean fields are calculated in terms of the particle number density by a linear response analysis and compared with the numerical results. Dephasing of the fluctuations leads also to the growth of an effective entropy and the transition from quantum to classical behavior of the ensemble. In addition to casting some light on fundamental issues of nonequilibrium quantum statistical mechanics, the general framework presented in this work may be applied to a study of the dynamics of second order phase transitions in a wide variety of Landau-Ginsburg systems described by a scalar order parameter.

* hep-ph/9610345; Phys. Rev. D. (in press)

[†] Theory Division, LANL, Los Alamos, New Mexico.

Statistical Properties of the Linear Sigma Model*

Jørgen Randrup

The statistical equilibrium properties of the linear sigma model are studied, with a view towards characterizing the field configurations employed as initial conditions for numerical simulations of the formation of disoriented chiral condensates in high-energy nuclear collisions.

The $O(4)$ chiral field $\phi = (\sigma, \pi)$ is subject to a non-linear interaction, $V = (\lambda/4)(\phi^2 - v^2)^2 - H\sigma$. The field can be decomposed into its spatial average, the order parameter, and the fluctuations, the quasi-particles, and enclosed in a box.

The quantized quasi-particle modes are described approximately by Klein-Gordon dispersion relations with an effective mass that depends on both the temperature and the magnitude of the order parameter:




Figure 1: The effective masses $\mu_{||}$ and μ_{\perp} as functions of ϕ_0 for a range of temperatures, calculated in the thermodynamic limit, $L \rightarrow \infty$. For temperatures above T_c , the curves start at $\phi_0 = 0$ with degenerate values, whereas below T_c they only exist if ϕ_0 is sufficiently large. The corresponding starting points for $\mu_{||}$ are connected by the dotted curve (only $T=0$ is shown). Also shown are the free masses m_{σ} and m_{π} .

* LBNL-38125 (1996); Physical Review D (in press).

The thermal fluctuations are instrumental in shaping the effective potential for the order parameter. As the system is cooled the field fluctuations subside, causing a smooth change from the hot phase having approximate chiral symmetry towards the broken phase:




Figure 2: The magnitude of the order parameter, ϕ_0 . For a box with $L=5$ fm, the bars show the full width at half maximum of the thermal distribution of ϕ_0 and the open dots show the centroids for the idealized case having $H=0$; the behavior is qualitatively similar even though the nature of the phase transition changes.

Of practical interest is the fact that the equilibrium field configurations can be sampled in a simple manner, thus providing a convenient means for specifying the initial conditions in dynamical simulations of the non-equilibrium relaxation of the chiral field.

The corresponding correlation function is briefly considered and used to calculate the spectral strength of radiated pions.

Finally, by propagating samples of initial configurations by the exact equation of motion, it has been ascertained that the treatment is sufficiently accurate to be of practical utility.

Amplification of pionic instabilities in high-energy collisions?*

Jørgen Randrup

The possibility of forming disoriented chiral condensates in high-energy collisions has generated considerable research activity in recent years. We have developed a simple and instructive framework for analyzing the conditions for the occurrence of the *DCC* phenomenon.

Enclosing the system in a box, we decompose the $O(4)$ chiral field $\phi = (\sigma, \pi)$ into its spatial average $\phi(t)$, the order parameter, and the fluctuating remainder $\delta\phi(x, t)$ representing the quasi-particle excitations. A Hartree factorization [1] then yields Klein-Gordon equations,

$$\left[\square + \mu^2 \right] \delta\phi(x, t) = 0, \quad (1)$$

The associated effective masses are given by

$$\begin{aligned} \mu_\sigma^2 &= \lambda[3\sigma_0^2 + \langle \delta\phi^2 \rangle + 2\langle \delta\sigma^2 \rangle - v^2], \\ \mu_\pi^2 &= \lambda[\sigma_0^2 + \langle \delta\phi^2 \rangle + 2\langle \delta\pi_i^2 \rangle - v^2], \end{aligned}$$

where the usual non-linear interaction has been employed, $V = (\lambda/4)(\phi^2 - v^2)^2 - H\sigma$.

Imagine that the system is formed at a high temperature. The field fluctuations are then sufficiently large to ensure $\mu^2 > 0$. The combined effect of expansion and radiation cools the system and the fluctuations thus decrease in the course of time. This reduces μ^2 which allows the order parameter to grow larger, thus counteracting the decrease of the effective masses. The resulting behavior of μ^2 is then a delicate balance: for slow cooling the induced growth of σ_0 is approximately adiabatic and the system relaxes towards the vacuum through metastable configurations. On the other hand, for a sufficiently rapid cooling a compensating growth of the order parameter cannot occur quickly enough and the effective pion mass may turn imaginary, $\mu_\pi^2 < 0$, indicating that the system has entered a regime exhibiting exponential growth of some modes.

* LBNL-38379: Physical Review Letters 77 (1996) 1226




Figure 1: The combined dynamical evolution of the order parameter and the field fluctuations. The dashed curve connects the equilibria and the shaded region is the unstable region within which $\mu_\pi^2 < 0$. The systems start in equilibrium at $T_0 = 400$ MeV. The irregular solid trajectory ($D=0$) has been obtained by solving the standard equations of motion for a spherical source with $R=5$ fm. The other three trajectories have been obtained by adding a cooling term emulating expansion in $D=1,2,3$ dimensions.

The resulting distortion of the pion spectrum can be estimated by a simple WKB method in which the integral of the imaginary frequency yields an amplification factor given by $\exp(G_k)$:

Table 1: Amplification coefficients $G_{k=0}^\pi$.

T_0 (MeV)	$D = 1$	$D = 2$	$D = 3$
200	0.00	0.02	0.11
220	0.00	0.50	0.55
240	0.01	1.20	1.19
300	0.00	1.84	2.06
400	0.00	1.67	2.49
500	0.00	1.31	2.61

[1] J. Randrup, Physical Review D (in press).

Mean-field treatment of the linear sigma model in dynamical calculations of DCC observables*

Jørgen Randrup

Approximate mean-field equations of motion for the classical chiral field are developed within the linear sigma model by means of a Hartree factorization. Both the approximate and the unapproximated equations of motion are augmented with a Rayleigh cooling term to emulate a uniform expansion, thereby allowing the extraction of observables relevant to the detection of disoriented chiral condensates. While the mean-field dynamics appears to be sufficiently accurate to be practically useful, the results also illustrate some of the difficulties associated with identifying the phenomenon experimentally.




Figure 1: Distribution of the neutral fraction $= n_0/n$ after pseudo-expansion in D dimensions, using either the exact equation of motion (left) or the proposed mean-field approximation (right).

* LBNL-39328 (1996): Nuclear Physics A (in press)




Figure 2: Pion power spectrum either in thermal equilibrium (upper-left) [1] or after a pseudo-expansion in D dimensions [2], with the exact equation of motion (solid) as well as the developed mean-field approximation (dashed).




Figure 3: Pion correlation function for the same scenarios as in fig. 2.

[1] J. Randrup, Physical Review D (in press).

[2] J. Randrup, Physical Review Letters 77 (1996) 1226

Treatment of Pionic Modes at the Nuclear Surface for Transport Descriptions*

Johan Helgesson[†] and Jørgen Randrup

Using a recently developed $\pi + NN^{-1} + \Delta N^{-1}$ model [1,2], we derive dispersion relations and amplitudes for collective pionic modes for use in transport descriptions.

In-medium properties obtained in an infinite stationary system consisting of interacting nucleons, nucleon resonances and mesons, can be incorporated into transport descriptions by a local density approximation. We have obtained density dependent dispersion relations of the pionic modes, as well as density dependent amplitudes of the components constituting the pionic mode. These quantities are conveniently parametrized in terms of a few density dependent coefficients.

While such a prescription is rather straightforward to implement in the interior regions of the nuclear system, conceptual problems exist at the nuclear surface. When the nuclear density approaches zero, collective mesonic modes formed in the medium have to be converted to real particles in vacuum. The problems arise since some collective modes (*e.g.* ΔN^{-1} -like) may exist in the infinite stationary system at arbitrary low (but non-vanishing) density, but no corresponding real particle exists in vacuum. It is discussed how pionic modes can be converted to real particles when penetrating the nuclear surface and how earlier treatments can be improved. When the surface is stationary only free pions emerge.

For the transport process it is not necessary to determine the character of the pionic modes until they penetrate the surface and emerge as free particles. This is automatically determined within our formalism from the amplitudes at zero density. The time-dependent situation has also been addressed.

[†] ECT*, European Centre for Studies in Theoretical Nuclear Physics and Related Areas, Trento, Italy.

* LBL-37623: Nucl. Phys. A597 (1996) 672.




Figure 1: The dispersion relations for the spin-isospin modes in the spin-longitudinal channel, in infinite nuclear matter at normal nuclear density and for zero temperature. The non-collective modes are shown by solid curves, while the collective modes $\tilde{\pi}_1$ and $\tilde{\pi}_2$ are represented by dot-dashed curves.

We have further shown that for a stationary density profile, the conservation of the energy of the pionic mode and the partial Δ decay width combine to guarantee that only real pions are realized as free particles when the pionic mode penetrates the surface.

A simplified one-dimensional scenario is used to investigate the reflection and transmission of pionic modes at the nuclear surface. It is found that reflection of pionic modes is rather unlikely, but the process can be incorporated into transport descriptions by the use of approximate local transmission coefficients.

[1] J. Helgesson and J. Randrup, Ann. Phys. 244 (1996) 12

[2] J. Helgesson and J. Randrup, Phys. Rev. C52 (1995) 427

Simplified Treatment of Collective Instabilities in Matter*

Jørgen Randrup

A formal analysis was made of the onset of instabilities in dilute nuclear matter in which collective modes are agitated by stochastic nucleon-nucleon collisions and then exponentially amplified by the self-consistent field. Moreover, employing approximate expressions for the transport coefficients [1], simple expressions were derived for the key quantities, so that survey calculations are facilitated.

It is convenient to discuss instabilities in uniform matter in terms of the Landau parameter $F_0 = (3\rho/2\epsilon_F)(\partial h/\partial\rho)$. When harmonic modes in matter are considered, this quantity generalizes to $F_0(k) \equiv (3\rho/2\epsilon_F)(\partial h_k/\partial\rho)$, involving the appropriate Fourier component of the self-consistent response. Further generalization is useful at finite T ,

$$F_T(k) \equiv \phi_0 \frac{\rho}{T} \frac{\partial h_k}{\partial \rho} \approx F_0(k) \left[1 - \frac{\pi^2}{12} \left(\frac{T}{\epsilon_F} \right)^2 \right], \quad (1)$$

employing the Sommerfeld expansion of the Fermi-surface moment ϕ_0 [2]. The dispersion relation for the collective growth time $t_k \equiv m/kP_F\gamma_k$ is then to a good approximation given by $1 = F_T(k)(\gamma_k \arctan(1/\gamma_k) - 1)$, which can readily be solved by iteration:




Figure 1: Characteristic energies for the collective modes in unstable matter, $E_k = \hbar/t_k$, with the generalized Seyler-Blanchard model [3].

* LBL-35847: Nucl. Phys. A583 (1995) 329

The random collisions provide a source term generating density irregularities which are then amplified by the unstable mean field h [4], leading quickly from a linear growth to an explosive development, $\sigma_k \approx \mathcal{D}_k \exp(2t/t_k)$:




Figure 2: The magnitude of the variance σ_k of density fluctuations having the wave length $\lambda = 2\pi/k = 8$ fm (near which the most rapid growth occurs), after a given time $t_0 = 10^{-22}$ s, as a function of the average density ρ and for specified temperatures T .

The derived analytical approximations facilitate the analysis of the onset of fragmentation in the spinodal zone of the phase diagram. Both the source terms for the fluctuations and the amplification times can be easily obtained. Several additional results are also useful, including the expansion of the angular quantities on complex Legendre polynomials, which is helpful for understanding the multipolarity properties.

[1] J. Randrup and S. Ayik, Nucl. Phys. A572 (1994) 489

[2] J. Randrup, *Statistical Description of Transport in Plasma, Astro, and Nuclear Physics*, Les Houches, France (1992), Nova Science, p. 353

[3] E. de Lima Medeiros and J. Randrup, Phys. Rev. C45 (1991) 372

[4] M. Colonna, Ph. Chomaz, and J. Randrup, Nucl. Phys. A567 (1994) 637

Multifragmentation with Brownian One-Body Dynamics*

A. Guarnera^{1,2}, Ph. Chomaz¹, M. Colonna^{1,3}, and Jørgen Randrup

A first application to nuclear multifragmentation has been made of Brownian One-Body Dynamics [1], a recently suggested simplified model for the dynamics of the one-body phase-space density that approximates the nuclear Boltzmann-Langevin description.

A gold nucleus is compressed to double density and then let free to evolve under the combined influence of the effective one-body field and the residual two-body collision processes, with the effects of the fluctuations included whenever local spinodal instability occurs.

The system quickly expands into a hollow and unstable configuration which transforms into several intermediate-mass fragments. The analysis of the resulting fragment pattern suggests that the model provides a physically reasonable description of nuclear multifragmentation.




Figure 1: Fragment charge distribution. The fragment charge distribution as obtained by analyzing the matter density at time $t=200$ fm/c using a density cut equal to $\rho_{\text{cut}}=0.05$ fm⁻³.

¹ GANIL, B.P. 5027, F-14021 Caen Cedex, France

² Laboratorio Nazionale del Sud, Viale Andrea Doria, I-95129 Catania, Italy

³ CEA DAPNIA, CE Saclay, F-91191 Gif-sur-Yvette Cedex, France

* LBL-39544 (1996): Physics Letters B (submitted).




Figure 2: Multipole strength distribution. The multipole strength coefficients σ_L [2] are shown at various points in time, $t=0, 60, 120, 180$ fm/c, as the initially compressed gold nucleus expands towards a fragmenting hollow shell. The results are obtained by averaging over 100 events.

[1] Ph. Chomaz, M. Colonna, A. Guarnera, and J. Randrup, Phys. Rev. Lett. 73 (1994) 3512

[2] G. Batko and J. Randrup, Nucl. Phys. A563 (1993) 97

Inclusion of Quantum Fluctuations in Wave Packet Dynamics*

Akira Ohnishi[†] and Jørgen Randrup

We have addressed the treatment of quantum fluctuations in microscopic descriptions based on wave packets, a problem encountered in a broad range of fields involving quantum physics. Since the wave packets are not energy eigenstates, the statistical operator $\exp(-\beta\hat{H})$ cannot be treated as a c -number. In order to take account of the associated spectral distribution and ensure that the statistical properties are quantal, it is necessary to introduce suitable modifications relative to the ordinary equations of motion for the wave packet parameters which are basically classical in character, having been derived from the time-dependent variational principle.

We have formulated a simple but apparently successful treatment by including the first correction term in the cumulant expansion of the statistical weight. The associated small parameter is $\sigma_E^2/T\mathcal{H}$, where $\mathcal{H} \equiv \langle Z|\hat{H}|Z\rangle$ is the mean energy of a wave packet and σ_E^2 is the corresponding energy variance. This approach is exact when the spectral distribution is of Poisson form, and the corresponding effective level spacing is $D \equiv -\partial \log \mathcal{H}_\beta / \partial \beta = \sigma_E^2/\mathcal{H}$. It is then straightforward to write down the improved expression for the statistical weight. Moreover, the associated thermal distortion of the internal structure of the wave packet can be determined.

Since our initial suggestion [1] that this treatment might be useful has led to some debate [2,3], we have discussed and illustrated the various possible approaches to determining the statistical behavior of one-body observables, such as the occupation number. The key to resolving the issue lies in the inevitable distortion of the many-body wave packet caused by the canonical operator $\exp(-\beta\hat{H})$.

The practical utility was exemplified by ^{12}C and ^{40}Ca which exhibit the desired evolution from a quantum fluid to a fragment gas, as the temperature is raised.

The quantum fluctuations can be incorporated into the dynamics by allowing stochastic transitions between the wave packets [4]. This can conveniently be done by introducing a quantum Langevin force in the equations of motion for the wave packet parameters. We derived the general form of the associated transport coefficients and verified that the proper microcanonical equilibrium distribution is indeed achieved. Simple approximate expressions for the specific values of the transport coefficients were then obtained, leading to a practically useful treatment.

The proposed extension of the standard treatment represents a formally well based approach. Moreover, it leads to the desired statistical properties in static scenarios and can be included in the dynamics in a conceptually simple and tractable manner. The method may, therefore, find useful application in the context of microscopic simulations of actual many-body processes, such as the production of nuclear fragments [5] and atomic clusters [6].

[1] A. Ohnishi and J. Randrup, LBL-33703, Nucl. Phys. A565 (1993) 474

[2] J. Schnack and H. Feldmeier, Nucl. Phys. A601 (1996) 181

[3] A. Ono and H. Horiuchi, Phys. Rev. C53 (1996) 2341

[4] A. Ohnishi and J. Randrup, LBL-36358, Phys. Rev. Lett. 75 (1995) 596

[5] A. Ohnishi and J. Randrup, LBNL-39473, Phys. Lett. B (in press).

[6] A. Ohnishi and J. Randrup, LBNL-39754, Phys. Rev. A (submitted).

* LBNL-38596 (1996); Annals of Physics 253 (1997) 279.

[†] Department of Physics, Faculty of Science, Hokkaido University, Sapporo 060, Japan.

Quantum Fluctuation Effects on Nuclear Fragment Formation*

Akira Ohnishi[†] and Jørgen Randrup

Many-body systems described by wave packets contain quantum fluctuations which may significantly affect the statistical properties [1]. The effect can be included in dynamical treatments by means of a quantal Langevin force [2,3]. We have adapted the treatment to QMD simulations of nuclear collisions where the individual nucleons are described by gaussian wave packets. This augmentation endows the system with larger fluctuations and the excitation of the emerging fragments is smaller. These two features conspire to enhance the production of intermediate-mass fragments. The effect on the mass distribution of atomic clusters has also been studied [4].

The usual QMD treatment leads to primary fragments that are typically sufficiently excited to emit nucleons and it is therefore essential to consider the statistical decay chain. This process causes a strong suppression of the IMFs, and a corresponding enhancement of lighter fragments. By contrast, the quantum Langevin treatment leads to fragments having a relatively small degree of excitation and, consequently, a larger proportion of them survive the statistical decay.

Our results for Au+Au collisions (illustrated in fig. 1) indicate that the inclusion of the quantum fluctuations in the wavepacket dynamics leads to a significant increase in the production of massive fragments with low excitation. Although the experimental data are not yet reproduced quantitatively, the improvement is significant over the results obtained with the usual treatments in which the quantum fluctuations are ignored. This general qualitative result suggests that the underlying quantum nature of the nuclear many-body system may indeed play a significant role in fragmentation reactions.

* LBNL-39473 (1996); Physics Letters B (in press).

[†] Department of Physics, Faculty of Science, Hokkaido University, Sapporo 060, Japan.




Figure 1: IMF multiplicity before and after statistical decay for central Au+Au collisions. Circles and triangles indicate QMD results at given energies with and without the quantal Langevin force, respectively. The upper and lower parts show the distributions before and after the statistical decay [5], respectively. The experimental data [6] are shown by solid diamonds.

[1] A. Ohnishi and J. Randrup, LBL-33703, Nucl. Phys. A565 (1993) 474

[2] A. Ohnishi and J. Randrup, LBL-36358, Phys. Rev. Lett. 75 (1995) 596

[3] A. Ohnishi and J. Randrup, LBL-38596, Ann. Phys. (in press).

[4] A. Ohnishi and J. Randrup, LBNL-39754, Phys. Rev. A (submitted)

[5] F. Pühlhofer, Nucl. Phys. A280 (1977) 267

[6] M.B. Tsang et al., Phys. Rev. Lett. 71 (1993) 1502

Quantum Fluctuations Affect Critical Properties of Noble Gases*

Akira Ohnishi† and Jørgen Randrup

Molecular dynamics presents a powerful tool for elucidating the features of mesoscopic systems. The present communication draws attention to the possible importance of quantum fluctuations in such treatments. To illustrate this issue, we focus on the cluster mass distribution for argon atoms in thermal equilibrium.

We have adapted a recently developed quantum Langevin treatment [1,2] to a system of argon atoms in thermal equilibrium. The method was developed in the context of nuclear dynamics and takes approximate account of the energy fluctuations that are necessarily present when wave packets are used to describe the system. The presence of these quantum fluctuations changes the character of the specific heat from classical to quantal and their inclusion by the developed method leads to a significant improvement of the statistical properties in a number of simple test cases that can be subjected to exact analysis [2,3] as well as for finite nuclei [1,2]. When incorporated into microscopic dynamical simulations of nuclear collisions, it leads to a significant improvement of the calculated fragment mass distribution [4].

Our studies suggest that quantum fluctuations inherent in wave packet dynamics may also play a role in atomic physics. As illustrated in fig. 1, the cluster mass distribution for noble gases can be affected significantly. In particular, the critical temperature for argon is reduced by around 20%, which is the value of the factor α entering into the modified Einstein relation. The quantum fluctuations may therefore also affect the formation process and might affect the outcome of dynamical simulations aimed at understanding the observed mass distributions.

* LBL-39754 (1996); Physical Review A (submitted).

† Department of Physics, Faculty of Science, Hokkaido University, Sapporo 060, Japan.




Figure 1: The mass distribution of argon clusters calculated either *with* (solid circle) or *without* (open triangle) the quantum Langevin force emulating the quantum fluctuations inherent in wave-packet dynamics. The argon atoms interact with a Lennard-Jones potential, $V(r) = \epsilon((\sigma/r)^{12} - (\sigma/r)^6)$; the temperatures are indicated in units of ϵ and the atomic density is $\rho = 0.025 \sigma^{-3}$.

[1] A. Ohnishi and J. Randrup, LBL-36358, Phys. Rev. Lett. 75 (1995) 596

[2] A. Ohnishi and J. Randrup, LBL-38596, Ann. Phys. (in press)

[3] A. Ohnishi and J. Randrup, LBNL-39473, Phys. Lett. B (in press)

[4] A. Ohnishi and J. Randrup, LBL-33703, Nucl. Phys. A565 (1993) 474

K^+ Momentum Spectrum from (K^-, K^+) Reactions in the Intranuclear Cascade Model*

Yasushi Nara^a, Akira Ohnishi^a, Toru Harada^b, Andreas Engel^c

Multi-strange systems have recently attracted much attention in nuclear, particle, and astrophysics, as they may yield information on the generalized nuclear interaction between octet baryons, may reveal the inter-quark forces through the study of “ H ” particle, and may be realized as strange matter in neutron stars. Among them, nuclear systems with $S=-2$ form the starting point of these studies.

Recently, it has become possible to measure double strangeness exchange reactions (K^-, K^+) on nuclear targets. For example, small angle (K^-, K^+) cross sections at $p_{K^-} = 1.65$ GeV/c were measured on several targets at KEK-PS [1]. The measured K^+ momentum spectrum shows a striking structure: in addition to quasifree peaks reflecting the elementary process $K^- p \rightarrow K^+ \Xi^-$, there appears a broad bump extending from $p_{K^+} = 0.35$ GeV/c to 1.0 GeV/c.

We have studied K^+ momentum spectra in (K^-, K^+) reactions and double-hyperfragment ($S = -2$) formation by using an intranuclear cascade model calculation. We have found that this bump is well explained by taking account of direct reactions $p(K^-, K^+) \Xi^{(*)}$, heavy meson subthreshold production and decay [2], and various two-step processes (Fig. 1); in the first step, the strange quark in the K^- particle is transferred to other baryons, and $\bar{s}s$ pair creation occurs in the second step. These two-step processes are effective in producing K^+ mesons in this energy region for the following two reasons:

* nucl-th/9608017 (1996): Nuclear Physics A (in press).

^a Department of Physics, Faculty of Science, Hokkaido University, Sapporo 060, Japan.

^b Department of Social Information, Sapporo Gakuin University, Ebetsu 069, Japan.

^c Department of Physics, Kyoto University, Kyoto 606-01, Japan.

(a) The incident energy corresponds to baryon resonance region, where the cross section becomes maximum. (b) When the intermediate mesons are heavy ($\rho, \eta, \omega, \dots$), the second step reaction becomes exoergic ($Q > 0$), then the strangeness production cross sections with these mesons are much larger than those with pions.

This two-step mechanism not only explains the K^+ spectra for various nuclear targets, but also suggests that more double-hyperfragments would be formed at this momentum region. More detailed study of double-hyperfragment formation in (K^-, K^+) reaction and Ξ^- absorption at rest, which is the other clean reaction to make double-hyperfragments, is in progress.




Figure 1: K^+ momentum spectrum from the $^{107}\text{Ag}(K^-, K^+)$ reaction. The thin solid, dot-dashed, and dotted lines show the contribution from direct processes, meson decays, and two-step processes, respectively. The thick solid line represents the calculated total spectrum. The experimental data are taken from [1].

- [1] T. Iijima *et al.*, Nuc. Phys. **A546** (1992) 588.
[2] C. Gobbi, C. B. Dover and A. Gal, Phys. Rev. **C50** (1994) 1594.

Four-Alpha Linear-Chain States in $^{16}\text{O}^*$

Naoyuki Itagaki[†], Akira Ohnishi[†], and Kiyoshi Kato[†]

Nuclei with large deformations are at the frontier in nuclear spectroscopy. It is expected that deformations above 1:3 may be possible in light nuclei due to the α -cluster structure. For example, the possibility of multi- α linear-chain configuration in light nuclei, such as the 4α linear-chain band starting around the 4α threshold energy region in ^{16}O , has been suggested experimentally [1].

Here we study 4α linear-chain states in ^{16}O in comparison with 3α states in ^{12}C by using the Generator Coordinate Method within a microscopic $N\alpha$ -cluster model. In contrast to the previous theoretical works, we discuss the stability of the $N\alpha$ linear-chain structure by solving dynamics of $N\alpha$ systems. Also it is shown to be very important to take into account the orthogonality between the linear-chain states and other low-lying states including the ground state. This is achieved by diagonalizing the Hamiltonian matrix in a wide space which also covers low-lying levels including the ground state. The framework used here is based on the combination of the Generator Coordinate Method (GCM) and the Constraint Cooling Method [2] proposed in the framework of AMD in order to generate GCM basis which describes low-lying levels.

The linear-chain state of ^{12}C is hardly considered to be a stable state as we increase the number of the GCM basis states. Their components fragment to the levels over broad range of excitation energy, especially to the 0_2^+ state, and these couplings make a pure linear-chain state unstable.

* nucl-th/9606056.

[†] Department of Physics, Faculty of Science, Hokkaido University, Sapporo 060, Japan.




Figure 1: The rotational band of ^{16}O linear-chain state. The numbers show the order of excited state.

On the other hand, the 4α chain state in ^{16}O is hardly affected by low-lying states and persists to remain above the 4α threshold. The calculated moment of inertia of the 4α linear-chain rotational band (88 keV) reproduces the experimentally suggested value qualitatively. These conclusions are consistent with the previous work by Ikeda [3] where the stability against small vibrations around the equilibrium configuration is considered. Moreover, we have shown that the linear-chain state of ^{16}O may survive even after the couplings to the lower states are taken into account.

[1] P. Chevallier and F. Scheibling, Phys. Rev. **160** (1967) 160.

[2] Y. Kanada-En'yo and H. Horiuchi, Prog. Theor. Phys. **93** (1995) 115.

[3] K. Ikeda, N. Takigawa and H. Horiuchi, Prog. Theor. Phys. Suppl. Extra Number (1968) 464.

Detectability of Strange Matter in Heavy Ion Experiments*

J. Schaffner-Bielich^{†,‡}, C. Greiner[§], A. Diener[†] and H. Stöcker[†]


Strangeness and antistrangeness is abundantly produced in heavy ion collisions. Baryonic objects with a high strangeness fraction may be formed, like small droplets of strange quark matter (strangelets) or metastable exotic multihypernuclear objects (MEMOs) consisting of nucleons and multiple hyperons [1]. Both are expected to possess properties quite different from ordinary nuclei, like a negative charge while carrying a positive baryon number. We examined the properties of both forms of strange matter for low masses, its decay properties and its detectability for heavy ion experiments.

The MEMOs were treated within the framework of an extended relativistic mean-field theory. We extended the calculation of [1] to small mass numbers which are most interesting for heavy ion physics. We found that the two smallest bound systems for $A = 4$ are ${}^4\text{He}$ and the corresponding Ξ -system, i.e. two Ξ^- and two Ξ^0 . The next heavier ones ($A = 6$) are the combinations ${}_{\Lambda\Lambda}^6\text{He}$, $\{2n, 2\Lambda, 2\Xi^-\}$, $\{2p, 2\Lambda, 2\Xi^0\}$, and $\{2\Lambda, 2\Xi^0, 2\Xi^-\}$. Note that the double Λ hypernucleus ${}_{\Lambda\Lambda}^6\text{He}$ has already been seen experimentally. These objects live, if formed, on the time scale of the weak hyperon decay, i.e. $\tau \approx 10^{-10}$ s. They can not be seen with the present experimental setups, as they are only sensitive to much larger lifetimes.

We calculated the binding energy of strangelets for an arbitrary number of up, down, and strange quarks using the MIT bag model. Afterwards we look for possible strong decays, i.e. nucleon, hyperon and pion emission. We checked also for fission of a strangelet into another strangelet and an arbitrary number of hadrons. This allows for example for a decay where the a strangelet emits a neutron and a pion. A strangelet stable against weak hadronic decays can then only decay via weak leptonic de-

cay or via weak radiative decays and lives on the time scale of $\tau_l = 10^{-4} - 10^{-5}$ s which is well in reach of present heavy ion experiments.

The long-lived strangelets found are mainly lying on a chain which starts from the triple magic strangelet ($6u6d6s$). The 'valley of stability' continues then towards negative charges by adding one unit of negative charge when going to a higher mass number. The reason for this stability line is a pronounced shell effect as e.g. the first candidate is also triple magic ($6u6d18s$ or $6u18d6s$). Note that these candidates are all highly negative charged contrary to common belief, while most experiments are, however, designed to detect only particles with small charge-to-mass ratio.



[†] Niels Bohr Institute, Copenhagen, Denmark

[‡] Institut für Theoretische Physik, University of Frankfurt, Germany

[§] Institut für Theoretische Physik, University of Giessen, Germany

* LBL-39652; Physical Review C (submitted)

[1] J. Schaffner, C.B. Dover, A. Gal, C. Greiner, H. Stöcker, Phys. Rev. Lett. 71, 1328 (1993)

Quark Phase Transition & Time-structure of Pulsar Spin-down*

N. K. Glendenning, S. Pei[†] and F. Weber^{††}

Pulsars—highly magnetized rotating neutron stars—emit magnetic dipole radiation and a wind of electron-positron pairs. Through the energy and angular momentum loss the angular velocity decreases. As a pulsar spins down it becomes less deformed and the central density rises. For some pulsars the mass and initial angular velocity Ω may be such that the central density rises from below to above the critical density for dissolution of baryons into their quark constituents. Because the compressibility of quark matter is greater than that of the confined phase, the phase change will be mirrored in structural changes in the star such as its size and moment of inertia: the star has entered an era in which it shrinks anomalously as it spins down over time because an increasing proportion of the stellar mass is converted to the more compressible deconfined phase. The star's mass becomes ever more concentrated near its center—more so than would be the case for a star composed of a simple fluid on which a weakening centrifugal force was acting. The concentration arising from the greater compressibility of quark matter is *amplified* by its greater gravitational attraction on the outer parts of the star.

At the stage described, the tendency of the star to shrink as the region occupied by quark matter grows in radius, counteracts (by angular momentum conservation) the spin-down rate ($\dot{\Omega}$) caused by radiation. The development of a growing central region of deconfined quark matter acts, so to speak, as a governor. Therefore the rates at which the mass becomes concentrated near the center and the star shrinks are *large* as functions of decreasing angular velocity but *small* as functions of time. A *strong* anomalous time-structure, which will endure for a *long time*, is introduced into the spin-down of a pulsar by conversion of the core to quark matter.

The anomaly in time-structure will appear in

the value and behavior of the so-called braking index, a dimensionless measurable quantity,

$$n(\Omega) \equiv \frac{\Omega \ddot{\Omega}}{\dot{\Omega}^2} = n - \frac{3I'\Omega + I''\Omega^2}{2I + I'\Omega}, \quad (1)$$

where $I' \equiv dI/d\Omega$ reflects the response of the moment of inertia to centrifugal and structural changes and $n = 3$ for magnetic dipole radiation. The behavior of $n(\Omega)$ for a model star is shown in Fig. 1 where the anomaly is clearly visible in the departure from the smooth curve.




Figure 1: Braking index anomaly.

We estimate the plausibility of observing the phase transitions in the pulsar population. The duration over which the observable index is anomalous is $\Delta T = -\Delta\Omega/\dot{\Omega}$ where $\Delta\Omega$ is the frequency interval of the anomaly. For a typical period derivative, $\dot{P} \sim 10^{-16}$, we find $\Delta T \sim 10^5$ years. During a typical pulsar's active lifetime, about 10^7 yr, the signal (negative index) would endure for 1/100 of the lifetime. Given that $\sim 10^3$ pulsars are known about 10 of them may be signaling the phase transition.

* LBL-39746.

[†] Beijing Normal University.

^{††} Ludwig-Maximilians University of Munich.

Response of Pulsar Braking to Rotation and Internal Structure*

N. K. Glendenning, S. Pei[†] and F. Weber^{††}

Pulsar spin-down occurs because of energy and angular momentum loss due to radiative processes. The energy loss equation representing processes of multipolarity n is of the form

$$\frac{dE}{dt} = \frac{d}{dt} \left(\frac{1}{2} I \Omega^2 \right) = -C \Omega^{n+1} \quad (1)$$

where, for magnetic dipole radiation, $C = \frac{2}{3} m^2 \sin^2 \alpha$, $n = 3$, m is the magnetic dipole moment and α is the angle of inclination between magnetic moment and rotation axis. Other multipoles may participate or be important over certain eras of a pulsar's lifetime (for example gravitational radiation in an early era before pulsations are damped). For all such processes the response of the moment of inertia I to the changing angular velocity Ω will produce its effect upon the behavior of $\dot{\Omega}$. While such other processes may be uncertain or speculative, the response of the internal constitution and moment of inertia of a neutron star to changing rotational frequency are not. Taking account of the response, the rate of change of frequency is governed by

$$\dot{\Omega} = -\frac{C}{I(\Omega)} \left[1 + \frac{I'(\Omega) \Omega}{2I(\Omega)} \right]^{-1} \Omega^n \quad (2)$$

where $I' \equiv dI/d\Omega$. This reduces to the usual form quoted in the literature [1] for low frequency or if changes in I are ignored, namely

$$\dot{\Omega} = -K \Omega^n \quad (K = C/I). \quad (3)$$

The usual expression for the moment of inertia in General Relativity [2] is not adequate for our purpose. It ignores the alteration of the metric of spacetime by rotation and the dragging of local inertial frames, and even the centrifugal flattening and changes in internal constitution resulting from the changing density profile of the star with changing rotational frequency. Instead we must use an expression that incorporates these effects as derived by Glendenning and Weber [3].

The dimensionless quantity $\Omega \dot{\Omega} / \Omega^2$ would be equal to the intrinsic index n if the frequency were small or if the moment of inertia were a constant, as can be obtained from (3). However these conditions are not usually fulfilled and the measurable quantity is not the constant index of the energy-loss mechanism (1) but a variable 'braking' index as can be calculated from (2). The measurable quantity is

$$n(\Omega) \equiv \frac{\Omega \dot{\Omega}}{\dot{\Omega}^2} = n - \frac{3I'\Omega + I''\Omega^2}{2I + I'\Omega}. \quad (4)$$

It approaches the index n that characterizes the energy loss mechanism only in the limits $\Omega \rightarrow 0$ or $I \rightarrow \text{constant}$.




Figure 1: Braking index for two stellar models of different mass showing the strong departure from $n = 3$ for higher frequencies.

* LBL-37592.

[†] Beijing Normal University.

^{††} Ludwig-Maximilians University of Munich.

[1] R. N. Manchester and J. H. Taylor, *Pulsars*, (W. H. Freeman and Co., San Francisco, 1977).

[2] J. B. Hartle, *Astrophys. J.* **150** (1967) 1005.

[3] N. K. Glendenning and F. Weber, *Astrophys. J.* **400** (1992) 647; *Phys. Rev. D* **50** (1994) 3836.

Crystalline Structure Size in Neutron Stars*

N. K. Glendenning and S. Pei †

We investigate the size of the objects forming a crystal lattice in the mixed phase of confined and deconfined matter in neutron stars whose presence was predicted in [1]. The objects take various forms according to the pressure and therefore the location in the star. We idealize the geometry of the objects as droplets, rods and slabs. As the spacing between droplets decreases, they merge to form rods, and the rods to form slabs.




Figure 1: Crystalline mixed region in a neutron star showing the diameter D (lower curves) and spacing S (upper curves) of indicated geometric structures as a function of radial Schwarzschild coordinate. Region internal to 4.6 km is pure quark matter. Notation 'h drops' denotes hadronic drops immersed in quark matter, and so on. Stellar radius is 10.7 km. Dashed line is continuous dimensionality interpolation

In Fig. 1 we show the diameter of the geometrical objects as a function of radial location in a star, identify their forms and plot the spacing between centers of the rare phase objects immersed in the other phase. The pressure at the center and extending to 4.6 km is sufficiently high that this region is occupied by pure quark mat-

ter. The region between 4.6 and 7.8 km is in the crystalline confined-deconfined phase. Since the phase transition is completed before the center of the star is reached, the geometrical structures span the full range of forms. At the outer edge of the mixed phase region, quark drops of finite diameter are spaced, in the limit of no quark matter, at infinite distance. At greater depth and therefore proportion of quark matter the drops are more closely spaced and slightly larger in size. Deeper in the star, drops are no longer the favored configuration and merge to form rods of varying diameter

It is almost certain that solid regions in a pulsar will play a role in the period glitch phenomenon, whether associated with cracking of the solid as in star quakes, or with unpinning of superfluid vortices from solid regions. Glitch behavior is highly individualistic from one pulsar to another. We tentatively suggest that this may be due to the extreme sensitivity on stellar mass of the radial extent of the solid crystal region and the forms that occupy it as well as the moments of inertia associated with different gaseous (quark), liquid and solid regions. The interior solid region of the mixed phase and the crustal solid, separated by a nuclear liquid, offer interesting possibilities for interaction or stimulated response at the time of a glitch originating in one of them and in post-glitch recovery.

* N. K. Glendenning and S. Pei, Phys. Rev. C **52** (1995) 2250.

† Beijing Normal University.

[1] N. K. Glendenning, Phys. Rev. D, **46** (1992) 1274.

Crystalline Cores of Neutron Stars*

N. K. Glendenning

First order phase transitions have been much studied in nuclear physics and cosmology. A remarkable aspect of the coexistence phase in substances having more than one independent component (or conserved charge) has been overlooked until recently [1]. If the substance is allowed to reach equilibrium and one of the conserved charges is the electric charge, then the rarer phase in the coexistence regime will form a crystalline lattice immersed in the dominant phase. The form and spacing of the rare phase objects will vary as its proportion of the mixed phase varies. This is true in general.

In particular, the quark phase transition has been discussed for many years. In the original and succeeding discussions between 1976 and 1990, the transition was treated in analogy to the liquid-vapor transition in water—a single-component substance. However neutron stars are characterized by two independent conserved charges, the baryon and electric charges. A first order phase transition in multi-component substances is profoundly different from that in a single-component one. There are four main aspects that impinge on the structure of neutron stars: (1) The two phases in coexistence adjust their internal structure at each proportion of the phases so as to minimize the total energy—a degree of freedom unavailable to a single-component substance. (2) One consequence of the readjustment—actually a rearrangement in the concentrations of the conserved charges—is that the pressure varies as a function of the proportion. For this reason the coexistence region of the two phases can extend over a non-zero radial range in the monotonically varying pressure environment of a star (unlike the coexistence of the two phases of a single-component substance for which the pressure is constant, causing the mixed phase to be squeezed out by the gravitational field of a star). (3) The readjustment

of the two phases in each others presence lowers the value of the critical pressure (and density). (4) The degree of freedom afforded by the possibility of reappportioning the conserved charges is exploited by the isospin symmetry energy of nuclear matter with the twin consequence that (a) the charge densities of the two equilibrium phases are unequal and non-zero so that neutrality is achieved not by vanishing charge density but by cancelling charges (neutrality of stars is a global, not a local constraint on their constitution); (b) the spatial arrangement of the two phases in equilibrium that minimizes the Coulomb and surface energies is a crystal lattice (of typically nuclear dimensions).




Figure 1: Radial boundaries of the various phases, pure quark, mixed (and the geometrical phases, for which 'q drops' means quark drops immersed in nuclear matter) and pure hadronic fluid for stars of various masses and stellar radius R for stars.

* LBL-39808

[1] N. K. Glendenning, *Phys. Rev. D*, **46** (1992) 1274.

Internal Constitution of Neutron and Strange Stars*

N. K. Glendenning

The weakest force—gravity—binds a nucleon in a neutron star 10 times more strongly than the strong force binds a nucleon in a nucleus. In doing so it works against the strong short-range repulsion of the nuclear force and against the Fermi pressure. Gravity therefore brings the Pauli principle into play in distributing the conserved baryon number of the star over many baryon species so as to reach the ground state of charge neutral matter. The name “neutron star” therefore has to be understood as a generic name for a star populated by many baryon species, also by quarks and also a mixed phase of confined and deconfined matter, that as I will discuss, arranges itself in a very intricate pattern in the deep interior of the star.

I will discuss several consequences of the rich constitution of compact stars: (1) a mechanism for the formation of low-mass black holes ($M \sim 1.5 - 2M_{\odot}$), (2) a multi-layered crystalline structure of confined and deconfined quark phases and (3) the effect of a quark core on the braking index of pulsars as well as the general effect of rotational distortion on the inferred magnetic fields and spin-down times of millisecond pulsars.

In this paper we explore possibilities—not certainties. The properties of matter at densities higher than nuclear are essentially unknown, although they are the subjects of investigation at several ultra high energy accelerators. Essentially all we can be fairly confident of are: (1) the equation of state of dense matter obeys the condition of causality, (2) the equation of state also obeys the condition of microscopic stability ($dp/d\rho \geq 0$) known as Le Chatelier’s principle and (3) at sufficiently high density, asymptotic freedom of quarks is achieved. Beyond this, a theory of dense matter ought to be firmly anchored to what is known at nuclear density. Within these constraints we explore what is allowed by the laws of physics, in the belief that the

laws of nature are likely to be realized in many if not all possible ways in the universe. The vehicle for the exploration is a covariant nuclear field theory that embraces the above constraints [1].




Figure 1: Pie section of a hybrid star (nuclear matter outer region enclosing a solid mixed phase and pure phase of quark matter) showing regions of quantum liquid (white areas) and solid regions of various geometric phases [2]. Notation ‘q drops’ means quark droplets immersed in nuclear matter, etc.

* Abstract of two lectures delivered at “The Many Faces of Neutron Stars”, Lipari, Sicily, October 1996, (Organizers: M. A. Alpar, R. Buccheri, H. Ogelman and J. van Paradijs), LBL-39638

[1] N. K. Glendenning, *Astrophys. J.* **293** (1985) 470.

[2] N. K. Glendenning, *COMPACT STARS, Nuclear Physics, Particle Physics, and General Relativity* (Springer-Verlag New York, 1997).

Thermal Evolution of Compact Stars*

Christoph Schaab [†], Fridolin Weber [†], Manfred K. Weigel [†] and Norman K. Glendenning

A broad collection of modern, field-theoretical equations of state (EOSs) is applied to studying the cooling behavior of both neutron stars and strange matter stars. The collection was derived under numerous assumptions about the behavior of superdense stellar matter. To mention several are: (1) the many-body technique used to determine the equation of state; (2) the model for the nucleon-nucleon interaction; (3) description of electrically charge neutral neutron star matter in terms of either only neutrons, (4) neutrons and protons in generalized chemical equilibrium (β equilibrium) with electrons and muons, or (5) nucleons, hyperons and more massive baryon states in β equilibrium with leptons; (6) behavior of the hyperon coupling strengths in matter, (7) inclusion of meson (π , K) condensation; (8) treatment of the transition of confined hadronic matter into quark matter; and (9) assumptions about the true ground state of strongly interacting matter (i.e., absolute stability of strange quark matter relative to baryon matter).

We find that *standard* cooling gives agreement between the theoretical cooling curves and the observed data for some but not all pulsars (cf. upper band in Fig. 1). On the other hand, the *enhanced* cooling mechanisms, which are connected to higher neutrino-emission rates coming from the direct Urca process, π - and K -meson condensates, or up, down and strange quarks in the cores of neutron stars, lead to too rapid a cooling. Therefore one is left to examine processes which somewhat delay enhanced cooling. A plausible candidate is superfluidity, of which there occur probably two different types in the cores of neutron stars, namely 1S_0 and 3P_2 . We find that already small changes in the theoretical value for the 1S_0 gap shift the cooling curves into the region of the observed data, giving an overall good agreement (band labeled "intermediate" in Fig. 1). An accurate determination of

the superfluid gaps in neutron star matter therefore attains its particular interest.

With respect to the cooling behavior of strange stars, whose luminosities lie in the lower part of the band labeled "enhanced", we find that pulsars like Geminga, Monogem, and PSR 1055-52 can probably ruled out to be strange pulsar candidates. There is however one pulsar, PSR 1929+10, which could be interpreted as a strange star. Of course, the QCD related uncertainties in the properties of strange matter as well as observational uncertainties do not permit us to draw stringent conclusions yet.




Figure 1: Comparison of the luminosity of observed pulsars with theoretical model calculations. The bands represent uncertainties inherent in the EOS (see text).

* Ch.Schaab, F. Weber, M. K. Weigel and N. K. Glendenning, Nucl. Phys. **A605** (1996) 531.

[†] Institut für Theoretische Physik, Ludwig-Maximilians Universität München, Theresienstr. 37, D-80333 München.

The Nuclear Thomas-Fermi Model*

W.D. Myers and W.J. Swiatecki

The statistical Thomas Fermi model is applied to a comprehensive survey of macroscopic nuclear properties. The adjustable parameters of the effective nucleon-nucleon interaction were fitted to shell-corrected masses of 1654 nuclei, to the diffuseness of the nuclear surface and to the measured depths of the optical model potential. With these parameters nuclear sizes are well reproduced, and only relatively minor deviations between measured and calculated fission barriers of 36 nuclei are found. The model determines the principal bulk and surface properties of nuclear matter and provides estimates for the more

subtle, Droplet Model, properties. The predicted energy vs. density relation for neutron matter is in striking correspondence with the 1981 theoretical estimate of Friedman and Phandaripande [1]. Other extreme situations to which the model is applied are a study of Sn isotopes from ^{82}Sn to ^{170}Sn , and the rupture into a bubble configuration of a nucleus (constrained to spherical symmetry) which takes place when Z^2/A exceeds about 100.

*Condensed from Acta Physica Polonica B26 (1995) 111
[1] B. Friedman and V.R. Pandharipande, Nucl. Phys. A361 (1981) 502

The Rotating Nuclear Thomas-Fermi Model*

W.D. Myers and W.J. Swiatecki

The Thomas Fermi model of Ref. [1] is generalized by the addition of a rotational energy. For heavy elements the calculated fission barriers of rotating nuclei agree with those of Ref. [2]. For lighter elements the barriers are lowered appreciably by the inclusion of the shape dependence of the congruence energy, but even then they exceed those of Ref. [2] by up to a few MeV. The shapes,

density distributions, deformation energies and saddle-point properties of the superdeformed nuclei ^{152}Dy and ^{83}Sr are calculated.

*Condensed from Acta Physica Plonica B27 (1996) 99
[1] W.D. Myers and W.J. Swiatecki, Nucl. Phys. A601 (1996) 141
[2] A. J. Sierk, Phys. Rev. C33 (1986) 2039

The Nuclear Thomas-Fermi Model with Angular Momentum: Fission Barriers, Superdeformations, Moments of Inertia*

W.D. Myers and W.J. Swiatecki

When rotational energy is added to the Thomas-Fermi nuclear model of Ref. [1] a number of new predictions are possible. In this paper we present a survey of fission barriers, deformation energies, gamma-ray rotational cascades and moments of inertia. We also explore a hypothesis according to which the moment of inertia of a deformed nucleus can be estimated by

subtracting from the rigid body value the moment of inertia of an inscribed sphere.

*Condensed from LBNL-39224
[1] W.D. Myers and W.J. Swiatecki, Nucl. Phys. A601 (1996) 141

The Congruence Energy: A Contribution to Nuclear Masses, Deformation Energies and Fission Barriers*

W.D. Myers and W.J. Swiatecki

It has been known for a long time that nuclear binding energies, when plotted along isobaric sequences that cross the $N = Z$ locus, exhibit (after correction for even-odd effects) a slope discontinuity roughly proportional to $|I|$, where $I = (N - Z)/A$.

Our interpretation of a negative contribution with a kink at $N = Z$ is related to the quantal granularity of nucleonic densities. Thus the density distribution of a quantized particle in a potential well consists of cushion-like bumps boxed in by a latticework of the wave function nodal surfaces. A pair of nucleons with congruent nodal surfaces, say a neutron and a proton, will interact more strongly (in the case of short range forces) than a pair with uncorrelated density modulations. Since the number of neutron-proton pairs is the lesser of N and Z , i.e., $\frac{1}{2}(N + Z) - \frac{1}{2}|N - Z|$, and since each pair interacts with a strength proportional to the reciprocal of the nuclear volume, i.e., to A^{-1} , the congruence energy should contain a negative term independent of A , modified by a positive term proportional to $|N - Z|/A$. A correction of this type should thus be added to a Thomas-Fermi model, whose smooth, structureless density distributions ignore this rather obvious consequence of quantization in a finite potential well.

A remarkable feature of the congruence energy, in addition to its telltale dependence on $|I|$, is that, being independent of A , it has the same value for a fissioning nucleus as for each of the resulting fission fragments. Hence the total congruence energy must somehow double as the fissioning nucleus deforms into a necked-in scission shape. There is empirical evidence for such doubling.

Figure 2 in Ref. [3] shows the fission barriers of 36 nuclei as a function of a fissility parameter. Two curves in this figure connect points calculated using the above-mentioned Thomas-Fermi model. The upper one assumed that the congruence energy is the same at the saddle point as in the ground state, the lower that it has doubled. There is a fascinating hint in the fact that the almost perfect agreement with the upper curve for Radium and heavier elements, gives place to an approach to the lower curve for lighter nuclei. The Radium region is precisely where saddle-point shapes develop (rather suddenly) a pronounced neck!

We have developed a model for the shape dependence of the congruence energy according to which the congruence energy is linear in the neck radius, and doubles its original value as the neck tends to zero. We have incorporated this shape dependence into our Thomas-Fermi calculations of nuclear deformabilities and fission barriers. The method we use is to solve the Thomas-Fermi equations first for a spherical nucleus and then for a sequence of elongating configurations for which the separation between the centers of mass of the two reflection symmetric halves is constrained to increase by a distance $2D$, where $D = 0.2, 0.4, 0.6 \dots$ fm. The resulting fission barriers are in good agreement with measurements.

*Extracted from Ref. [3]

[1] J.M. Blatt and V.F. Weisskopf, *Theoretical Nuclear Physics*, John Wiley & Sons, New York, 1952.

[2] W.D. Myers and W.J. Swiatecki, *Nucl. Phys.* 81 (1966) 1.

[3] W.D. Myers and W.J. Swiatecki, LBL-39224, November, 1995.

The Excitation of an Independent-particle Gas—Classical or Quantal—by a Time-dependent Potential Well*

J. Blocki[†], J. Skalski[‡] and W.J. Swiatecki

A systematic numerical investigation of the excitation of a classical or quantal gas of non-interacting particles in a time-dependent potential well is described. The energy was followed in time for one oscillation around the sphere for six types of deformation: spheroidal shapes and Legendre polynomial ripples P_2 , P_3 , P_4 , P_5 , P_6 with relative rms amplitudes of 0.2. Ten different speeds of deformation and eleven different values of the diffuseness of the potential well were studied. In the upper range of deformation speeds the quantal results for the

non-integrable shapes P_3 - P_6 agree approximately with the wall formula for dissipation, the deviations being largely accounted for by the wave-mechanical suppression factor of Koonin et al. For low deformation speeds the dissipation becomes dominated by one or two avoided level crossings.

*Condensed from Nucl. Phys. A594 (1995) 137

[†]Inst. for Nucl. Studies, 05-400 Swierk, Poland

[‡]Inst. for Nucl. Studies, 00-681 Warsaw, Poland

The Excitation of an Independent-particle Gas by a Time-dependent Potential Well. Part II*

J. Blocki[†], J. Skalski[‡] and W.J. Swiatecki

A systematic comparison is carried out between quantal and classical computer simulations of the excitation of independent particles in a time-dependent, diffuse potential well undergoing one cycle of oscillation. Eleven values of the diffuseness, up to 25 values of the oscillation frequency, and five Legendre polynomial deformations P_2 , P_3 , P_4 , P_5 , P_6 were examined. Oscillations around the spherical shape as well as around a P_3 deformed shape were considered. The results are compared with the one-body dissipation theory in the form of

the wall formula, including corrections for the heating up of the gas, the diffuseness of the surface, the wave-mechanical suppression of dissipation and the reduction in the effective volume available to a quantal gas in a container whose diffuseness is small compared to the particle wavelengths.

*Condensed from LBNL-39225, August, 1996, submitted to Nucl. Phys.

[†]Inst. for Nucl. Studies, 05-400 Swierk, Poland

[‡]Inst. for Nucl. Studies, 00-681 Warsaw, Poland

The Effect of Dynamical Correlations in a Slowly Pumped Knudsen Gas*

J. Blocki[†], C. Jarzynski[‡] and W.J. Swiatecki

In this paper we consider the effect of dynamical correlations on the absorption of energy by a gas of mutually noninteracting particles inside a container whose shape changes slowly (and periodically) with time. In principle, such correlations can significantly alter the rate at which energy is absorbed by the gas. We present the results of numerical


simulations in which this effect is clearly seen, and compare the results with theoretical estimates.

*Condensed from Nucl. Phys. A599 (1996) 486

[†]Inst. for Nucl. Studies, 05-400 Swierk, Poland

[‡]Inst. for Nucl. Theory, Univ. of Washington, Seattle, WA 98195

Seminars



Seminars

1995-1996

Special Seminars

Bikash Sinha, Saha Institute of Nuclear Physics, India	Electromagnetic Signals of Quark Gluon Plasma	10-02-96
Jay Marx, LBNL	Searching for the Quark-Gluon Plasma	11-26-96
Michael Turner, Fermilab and U of Chicago	Appraising Inflation and Cold Dark Matter	12-03-96
Heinz Gaeggeler, U of Bern and Paul Scherrer Institute, Switzerland	Chemistry Gains A New Element: Z=106 (Seaborgium)	12-05-96
David Radford, Chalk River, Canada	Coulomb Excitation Studies with the 8-pi array	12-09-96

Heavy Ion Tea

Rolf Scharenberg, Purdue U	Critical Characteristics	09-28-95
Tamas Csorgo, Budapest	Bose-Einstein Correlations	10-05-95
Jørgen Randrup, LBNL	Extracting Thermodynamic Variables	10-12-95
Shin Nan Yang, National Taiwan U	Pion Production	10-19-95
Volker Koch, LBNL	Chiral Symmetry	10-24-95 10-25-95 10-26-95
Iwona M. Sakrejda, LBNL	Physics with STAR, Part I	10-26-95
	Physics with STAR, Part II	11-02-95
Emil Mottola, LANL	Disoriented Chiral Condensates	11-09-95
Rob Pisarski, BNL	Baked Anomalies: Where Does the Omega Go?	11-16-95
Ramona Vogt, LBNL	Parton Densities in Perturbative QCD	11-30-95
Jim Carroll, UCLA @ LBNL	Spin Physics with STAR at RHIC	12-07-95
Nicolo de Groot, NIKHEF/SMC	The Spin of the Nucleon	12-14-95
Volker Koch, LBNL	Electromagnetic Heavy Ion Physics	01-04-96
Jeff Porter, LBNL	DLS Dielectron Measurements at the Bevalac	01-16-96
Kevin Haglin, MSU	Dileptons from Dense Matter	01-23-96
Sean Gavin, BNL	Return of the J/ψ	01-30-96
Ramona Vogt and Xin-nian Wang, LBNL	J/ψ Progress	02-06-96
Dieter Best, GSI	K^+ Production in the 1.93 AGeV Ni+Ni Reaction	02-13-96
Detlef Irscher, LBNL	CERES/NA45 Measurements of Electromagnetic Probes	02-22-96
Che-ming Ko, TAMU	Low-Mass Dileptons from Heavy-Ion Collisions	02-27-96

Klaus Kinder-Geiger, BNL	Parton Dynamics	03-05-96 03-06-96 03-07-96
Xin-nian Wang, LBNL	Anatomy of Parton Cascades: Problems and Cures HIT Forum on Parton Dynamics HIT Forum on Event-by-Event Physics	03-12-96 03-19-96 03-26-96
Richard Seto, UC Riverside	The PHENIX Experiment at RHIC: Measuring Electrons and Muons	04-02-96
Raju Venugopalan, INT Seattle	High Parton Densities in Perturbative QCD	04-16-96
Thomas Wienold, LBNL	Recent Results from NA49 on Stopping and Flow	04-23-96
Spiros Margetis, LBNL	Aspects of Strangeness Production at CERN Energies	04-30-96
John Harris, LBNL	Scaling of Nuclear Stopping in Central Nucleus-Nucleus Collisions from $E(\text{Lab}) = 0.2 - 200 \text{ A-GeV}$	05-07-96
Tim Hallman, BNL	Measuring the Spin-Averaged and Spin-Dependent Gluon Structure Function of the Proton with STAR	06-18-96
Fuqiang Wang, Columbia	Kaon Production and K/π Ratio in Au+Au at 11.1 A GeV/C at the AGS	06-25-96
Ulrich Heinz, Regensburg	Hadron Abundancies and Spectra in Relativistic Nuclear Collisions Lifetimes and Sizes from Two-Particle Correlations in Relativistic Nuclear Collisions	07-01-96 07-02-96
Willibrod Reisdorf, GSI	Heavy Ion Collisions at 0.1 to 2 A GeV: New Results and Plans from the FOPI Collaboration	07-09-96
Peter Filip, Bratislava	Azimuthally Sensitive HBT Analysis	07-16-96
Craig Ogilvie, MIT	Searching for the Quark-Gluon Plasma at the AGS	07-23-96
Steffen Bass, U of Frankfurt	Ultradense Nuclear Matter, Stopping, and Flow Excitation Functions with URQMD	07-30-96
Miklos Gyulassy, Columbia	Turbulent Glue Scenario at RHIC	07-31-96
Sergei Panitkin, Stony Brook	Two Particle Correlations: E877 Results	09-10-96
Xin-nian Wang, LBNL	Parton Energy Loss and Jet Quenching	09-17-96
Volker Koch, LBNL	Low-Mass Dilepton Production in Ultrarelativistic Heavy Ion Collisions	09-24-96
Klaus Geiger, BNL	Parton Cascades and QCD?	10-01-96
Spencer Klein, LBNL	Peripheral Collision Physics at RHIC	10-02-96
Nu Xu, LANL	Hadronic Freeze-Out Conditions in Ultra-Relativistic Heavy-Ion Collisions	10-03-96
Yuri Sinyukov, ITP Kiev	Boson Interferometry at High Multiplicities	10-08-96
Ziwei Lin, LBNL	Nuclear Shadowing from Dileptons at RHIC	10-15-96
Daniel Ferenc, Zagreb	Bose-Einstein Correlations in Relativistic Nuclear Collisions: Current Status and Outlook	10-16-96

Mark Baker, MIT	What Can We Learn from Two-Particle Correlations in Heavy Ion Collisions?	10-23-96
Ron Soltz, LLNL	Calibrating Hadronic Probes of the Quark-Gluon Plasma	10-28-96
Jørgen Randrup, LBNL	Summary of the DCC Workshop at ECT in Trento	10-29-96
Huan Huang, UCLA	What Can Be Learned from Lambda Polarization?	11-07-96
Larry McLerran, Minneapolis	Initial Conditions for Ultra-Relativistic Nuclear Collisions	11-12-96
Jay Marx, LBNL	Search for the Quark-Gluon Plasma with STAR	11-26-96
Carlos Lourenco, CERN	Dimuon Production in Heavy Ion Collisions: Recent Results and Future Perspectives	12-03-96
Vesa Ruuskanen, Jyväskylä	Hydrodynamic Study of Heavy Ion Collisions at the CERN SPS: Any Sensitivity to the Equation of State?	12-10-96
Joseph Kapusta, Minneapolis	Coulomb Effects on Charged Kaon Distributions from Vlasov Dynamics	12-19-96
INPA Journal Club		
D. Moltz, LBNL	A Proposed Measurement of the ${}^7\text{Be}(p, \gamma)$ Reaction Cross Section	01-06-95
M. Isaac, LBNL	First Results from the ${}^{51}\text{Cr}$ Neutrino Source Experiment with the GALLEX Detector	01-13-95
S. Deustua, LBNL	Some Highlights from the Recent American Astronomical Society Meeting	01-20-95
E. Bloom, SLAC	Gamma-Ray Telescopes	01-27-95
K. Lesko, LBNL	Update on the Sudbury Neutrino Observatory	02-10-95
K. Hurley, UCB	Cosmic Gamma-Ray Bursts and Soft Gamma Repeaters	02-17-95
L. Rosenberg, MIT	A Search for Dark Matter Axions	02-24-95
M. Rees, Cambridge	Theories of Gamma-Ray Bursts Origin	03-01-95
Max Tegmark, Max-Planck Institute	Extracting Power Spectra	03-03-95
D. Branch, Univ. of Oklahoma	Type Ia Supernovae and the Hubble Constant	03-10-95
P.J.E. Peebles, Princeton U.	Numerical Applications of the Action Principle	03-17-95
D. Welch, McMaster U.	New Light on Cepheid Variables from MACHO Project Results	03-31-95
B. Fujikawa, LBNL	The Search for the Origin of VHE Cosmic Rays	04-07-95
G. Mamon, Institut d'Astrophysique de Paris	A Near-IR Imaging Survey + the Galaxy Groups/Cosmology Connections	04-14-95
D. Snowden-Ifft, UCB	Limits on Dark Matter Using Ancient Mica	04-21-95
S. Perlmutter, LBNL	On New Supernova Model	04-28-95
T. Banks, Rutgers U.	Modular Cosmology	05-05-95

C. Kuo, LBNL	Free Oscillations in the Earth	05-12-95
M. Moorhead, LBNL	Neutral Current Detection in the Sudbury Neutrino Observatory	05-19-95
S. Deustua, LBNL	Low Luminosity Active Galactic Nuclei - Do They Exist?	05-26-95
L. Cayon, LBNL	Topology of Anisotropies in the COBE CMBR Data	06-02-95
E. Wasserman, LBNL	Search for CP/T Violations	06-09-95
B. Tripp, LBNL	Using Type Ia Supernovae to Measure the Cosmological Expansion Parameters	06-17-95
D. Lowder, UCB and LBNL	The HEAT (High Energy Antimatter Telescope) Experiment and First Flight Results	06-23-95
R. Taillet, LAPP (Annecy, France)	Dark Matter in the Form of Low Mass Stars in Globular Clusters	07-07-95
D. Weiss, UCB	Observation of Bose-Einstein Condensate in Dilute Atomic Gas	07-21-95
P. Salati, ENSLAPP (Annecy, France)	The Gas Deficiency in the Galactic Halo	07-28-95
S. Bludman, U. Pennsylvania	Big Bang Nucleosynthesis in Crisis	08-04-95
L. Krauss, Case Western Reserve U.	Big Bad Nucleosynthesis; the TRUE Story	08-11-95
S. Perlmutter, LBNL	An Informal Report on the SN 1a June '95 Conference in Spain	08-18-95
L. Tenorio, LBNL	Comments on CMB Parameter Estimation	08-25-95
E. Gawiser, LBNL	Microwave Anisotropy from Infrared Galaxies	09-01-95
R. Pain, LBNL	Supernova at $z=0.4$	09-08-95
C. Baker, UCB	Detecting Neutrino-Induced Radio Signals in the Antarctic Ice	09-15-95
G. Savard, Chalk River Lab.	A New Penning Trap Mass Spectrometer	10-13-95
M. Frank, LLNL	X- and Gamma-Ray Detectors with Superconducting Absorber	10-20-95
W. Stoeffl, LLNL	Anomalous Shape in the Tritium Beta	10-27-95
M. Bennett, LBNL	H^0 Search in BNL Experiment 896	11-03-95
L. Krauss, Case Western Reserve U.	The Case for a Cosmological Constant	11-10-95
F. Boehm, Caltech	The S. Onofre Neutrino Oscillation Experiment	11-17-95
O. Saavedra, CERN	Correlation of GRBs with Underground Detectors	12-01-95
R. Muller, LBNL	Fresh News from the Ice Ages	12-15-95
A. Westphal, UC Berkeley	Composition of Heavy Isotopes and Ultra-Heavy Elements in Cosmic Rays Using Detectors on the MIR Space Station	01-19-96


Supernova Group Tag Team	Journal Club Update on Last Week's American Astronomical Society Meeting	01-26-96
Yuen Dat Chan, LBNL	Getting Ready to Analyze a SNO Event	02-02-96
J. Jochum, UCB	The Solar Neutrino Problem in the ^7Be Energy Range	02-09-96
R. Hoffman, UC Santa Cruz	Heavy Element Synthesis in Supernovae	02-16-96
B. Grossan, LBNL	Physics in Mountaineering	02-23-96
G. Marcy, SFSU and UCB	Discovery of Planets Orbiting Normal Stars	03-01-96
A. Olinto, U of Chicago	Forming Primordial Black Holes in Phase Transitions	03-08-96
J. Frieman, Fermilab and U of Chicago	Weak Lensing and the Measurement of Q^0 from Type Ia Supernovae	03-15-96
C. Alcock, LLNL	Cosmic Dark Matter: Recent News from Gravitational Microlensing	03-21-96
B. Price, UCB	High Energy Neutrino Astrophysics: Ice and Oceans	03-29-96
M. Isaac, LBNL	Strange Matter and How To Detect It	04-05-96
B. Fujikawa, LBNL	Determination of the U-D CKM Matrix Element from Superallowed Fermi Decays	04-12-96
P. Vetter, LBNL	What the $\%*\&!#\$\$$ Is an Anapole Moment?	04-19-96
E. Daw, MIT	A Search for Halo Axions	04-26-96
P. Mantsch, FNAL	The Pierre Auger Project: A Large Cosmic Ray Observatory.	05-10-96
D. Nygren et al., LBNL	Report on: "U.S. Meeting on Future Prospects for km-scale Neutrino Detectors—Arcadia, Apr. 18-19"	05-17-96
M. Kim, LBNL	The Latest Hubble Constant	05-24-96
Dave Nygren et al., LBNL	Part II of the Report on: "U.S. Meeting on Future Prospects for km-scale Neutrino Detectors—Arcadia, Apr. 18-19"	05-31-96
B. Remington, LLNL	Experimental Astrophysics Using Intense Lasers	06-14-96
B. Fujikawa, LBNL	LSND - Unauthorized	06-21-96
S. Elliott, U of Washington	Recent Results from SAGE	07-12-96
G. Chew, LBNL	Experimental Predictions from Cosmology, with Emphasis on Supernovae Measurements	07-19-96
J. Marx, LBNL	The Quark-Gluon Plasma and You	07-26-96
J. Ellis, CERN	Outlook on Neutrino Physics 1996	08-02-96
M. Smith, Oak Ridge Natl. Lab.	Nuclear Astrophysics at ORNL	08-16-96
G. Jernigan, UCB	Recent Results from X-ray Timing Explorer	08-23-96
B. Cabrera, Stanford U.	Cryogenic Detection of Dark Matter	08-30-96
E. Gawiser, LBNL	Microwave Anisotropy from IR Galaxies	09-01-96
R. Pain, LBNL	Supernova Rate at $Z=0.4$	09-02-96

G. Gwinner, LBNL	Quantum Computing	09-13-96
T. Culler, LBNL	Measurement of Cratering Rate with Lunar Spherules	09-27-96
R. Norman, LBNL	You Can See a Lot Just by Looking	09-29-96
E. Gawiser, LBNL	Microwave Anisotropy from Infrared Galaxies	10-04-96
C. Quigg, Fermilab	Neutrinos	10-06-96
N. Glendenning, LBNL	Strange Matter Stars	10-18-96
H. Crawford, LBNL	Status of Experimental Searches for Strange Matter	10-25-96
S. Gordon, LBNL	The Radio Properties of an Optically Selected Sample of Supernova Remnants in M33	11-01-96
S. Perlmutter, LBNL	Latest News from the Supernova Search	11-15-96
S. Freedman, LBNL	The Bloodsucking Vector: A Quest of New Physics in Heavy Ion Collisions	11-22-96
R. Puetter, UC San Diego	Information, Language and Pixon-Based Image Reconstruction	11-26-96
G. Fisher, Space Sciences Lab, UCB	The Solar Cycle: the Role of Magnetic Flux Tube Dynamics	12-06-96
G. Marcy, SFSU	Detection of a New Planet Around a Nearby Star	12-08-96
P. Nugent, LBNL	Synthetic Spectra of Hydrodynamic Models of Type 1a Supernovae	12-13-96
C. Okada, Boston U	A Search for Oscillations of Atmospheric Neutrinos with the MACRO Experiment	12-20-96
Nuclear Physics Forum		
T. L. Khoo, ANL	Decay of Superdeformed Bands	02-01-96
L. W. Phair, LBNL	Reducible and Statistical Nature of Multifragmentation	02-22-96
R. N. Cahn, LBNL	Testing C Invariance in Positronium Decay	02-29-96
Luciano Moretto, LBNL	The Unclear Physics of Phase Transitions	03-14-96
Albert Young, Princeton U	Probing for Physics beyond the Standard Model with Nuclear Beta Decay	03-21-96
D. Sarantites, Washington U	Hyperdeformed Nuclei and How to Make Them	03-28-96
G. Greene, LANL	Beer Cans, Neutron Bottles, and the Boeing 777: Neutron Science at LANL	04-04-96
C. J. Lister, ANL	AYE-Ball: A Peep into the Future of Nuclear Structure	04-11-96
Bill McCurdy, LBNL	The National Energy Research Scientific Computing Center at LBNL: New Opportunities for Computing Sciences	04-18-96
Jorolf Alstad, Oslo U, Norway	SISAK III: Single-Atom Chemical Separations on a One-Second Timescale	04-25-96
S. Yates, U of Kentucky	The Search for Two-Phonon Excitations in Nuclei	05-16-96
Vic Viola, Indiana U	Delta Resonance-Enhanced Multifragmentation	06-03-96


G. Young, ORNL	Electromagnetic Studies of Quark-Gluon Plasma Using the PHENIX Detector at RHIC	06-05-96
V. Flambaum, U of New South Wales, Australia	Experiments with Heavy Nuclei: Anapole Moment	06-20-96
Wladek Swiatecki, LBNL	Overview of the Nuclear Thomas-Fermi Model	06-27-96
Stefan Frauendorf, Institute of Nuclear and Hadronic Physics, Rossendorf, Germany	Persistent Currents: Nuclear Rotation and Cluster Magnetism	07-11-96
R. Donangelo, U of Rio de Janeiro, Brazil	Post-Acceleration Effects in the Direct Break-up of Halo Nuclei	07-16-96
Stefan Frauendorf, Institute of Nuclear and Hadronic Physics, Rossendorf, Germany	Magnetic Rotation	07-18-96
P. Reiter, ANL	Gamma-Ray Spectroscopy of Neutron-Rich Nuclei Using Radioactive Beams at 2.2 MeV/u and 230 MeV/u	10-10-96
John Hardy, AECL, Chalk River, Canada	Superallowed Beta Decay: A Nuclear Probe of Electroweak Standard Model	11-11-96
Wladek Swiatecki, LBNL	Nuclear Dynamics and the Order-to-Chaos Transition	11-21-96
Brian Fujikawa, LBNL	Determination of CKM Matrix Elements with Superallowed Fermi Decays	11-24-96
K. Grotowski, Jagellonian U, Poland	Study of Reaction Mechanisms and of Exotic Events in Heavy-Ion Collisions	11-27-96
John Rasmussen, LBNL	Spontaneous Fission Studies in Gammasphere: What We Have Learned	12-05-96
Igor Pavlichenkov, Kurchatov Institute, Moscow	Non-Adiabatic Mean Field Effects in the Delta I=2 Staggering of Superdeformed Bands	12-12-96
Theory Seminars		
Thomas Schäfer, Stony Brook, NY	Instantons and Chiral Phase Transition	01-17-95
David Blaschke, Rostock, Germany	Thermodynamics of the Quark Hadron Transition In a Nonlocal Chiral Quark Model	01-19-95
József Zimanyi, Budapest, Hungary	ALCOR: A Dynamic Model For Hadronization	01-19-95
Biswarup Banerjee, Bombay, India	Phase Transitions In Early Universe	02-02-95
G. Z. Obrant, St. Petersburg, Russia	Coherent Pion Effect At Large Rapidities In Nucleus-Nucleus Collisions	02-06-95
Vesteinn Thorsson, INT, Seattle, WA	Kaon Condensation In Neutron Star Matter	02-15-95
Jim Huang, Tucson, AZ	Disoriented Chiral Condensate	02-23-95
Caio Lewenkopf, INT, Seattle, WA	Electronic Transport In Microstructures and Compound Nucleus Reactions: Similarities and Differences	02-28-95

Chungsik Song	Photon and Dilepton Production From Hot Hadronic Matter In High Energy Nucleus-Nucleus Collisions	03-03-95
Carsten Greiner	Non-Markovian Effects In High-Energy Collisions	03-09-95
Igor Dremin, Moscow, Russia	Correlation and Statistical Analogies In Multiparticle Production	03-30-95
Chris Jarzynski, INT, Seattle, WA	Can One Do Statistical Mechanics with Only a Few Degrees of Freedom—Case of a Brownian Particle Coupled to Deterministic Chaos	04-24-95
Alex Kovner, Minneapolis, MN	Variation Approach to the Yang-Mills Vacuum	05-18-95
Paul Fallon, NSD/LBNL	Recent Results in High-Spin Physics	05-23-95
Paul Bonche, Saclay, France	Skyrme Forces Revisited	07-18-95
Judah Eisenberg, Tel Aviv, Israel	Proton Spin Content from Skyrmions	07-25-95
Robert Vinh Mau, Paris, France	Quark Stars and Quark-Hadron Phase Transition	08-01-95
Sid Bludman, Philadelphia, PA	Big Bang Nucleosynthesis in Crisis	08-04-95
Cheuk-Yin Wong, ORNL, TN	Suppression of Ψ' and J/ψ in High-Energy Heavy-Ion Collisions	08-14-95
Berndt Müller, Duke, NC	Interface Tension and Entropy: A Simple Model	08-17-95
Xiao-Ming Xu, Shanghai, China	J/ψ Suppression in an Equilibrating Parton Plasma	09-19-95
Chungsik Song, NSD/LBNL	Medium Effects on Dilepton Production from Hot Hadronic Matter	09-26-95
Shin-Nan Yang, Teipei, Taiwan	Electroproduction of f -Meson and Strangeness Content of the Proton	10-03-95
Emil Mottola, LANL, NM	Non-Equilibrium QCD: The Chiral Phase Transition in Heavy-Ion Collisions	10-31-95
Dirk Rischke, Columbia, NY	Hot Spots and Turbulent Initial Conditions in AA-Collisions at $E_{cm} = 200$ AGeV	11-14-95
Krishna Kumar, Tenn Tech U, TN	The Nuclear Equation of State in a Semi-Classical Field Theory	11-16-95
Engelbert Quack, SLAC, CA	Soft Proton Production from a Quark-Gluon Plasma	11-21-95
Valeri Emel'yanov, Moscow, Russia	Peripheral Heavy Ion Collisions	11-30-95
Patrick Talou and Nicolae Carjan, Bordeaux, France	Time-Dependent Decay Rates	12-12-95
Fridolin Weber, Munich, Germany	Braking of Pulsars	12-14-95
Pawel Danielewicz, MSU, MI	Delays in Elementary Processes	12-19-95
Su Huong Lee, Yonsei U, Korea	Hadron Properties in Nuclear Medium from QCD Sum Rules	01-09-96
Cheuk-Yin Wong	Effect of Initial and Final State Interactions on Cross Sections	01-30-96

Burkhard Kämpfer, Rossendorf, Germany	Electromagnetic Signals of Parton Matter	02-15-96
Ramona Vogt, NSD/LBNL	Colorful Quarkonium Production	03-14-96
Ziwei Lin, Columbia U, NY	Charm in RHIC	03-21-96
Xiaofeng Guo, Iowa State U, IA	Nuclear Dependence in Direct Photon Production	03-25-96
Fred Cooper, LANL, NM	Time Dependent Variational Methods; From Solitons to Quantum Chaos	03-27-96
Akira Ohnishi, Sapporo, Japan	Multistep Effects in (K^- , K^+) Reactions: How Are $S=-2$ Hyperfragments Formed?	04-03-96
Peter Valerio, Tucson, AZ	Charm and Bottom Production and Decay in Ultra- Relativistic Heavy-Ion Collisions	04-25-96
Jürgen Schnack, GSI, Germany	Short Range Correlations in Fermionic Molecular Dynamics	07-02-96
Robert Vinh Mau, Paris, France	Nuclear Forces and Quark Degrees of Freedom	08-15-96
J. Zimanyi, KFKI, Budapest, Hungary	Relativistic Mean Fields, Multipion Correlation, and Hadronization	09-05-96
Michael Christiansen, U of Århus, Denmark	The Cosmological Quark-Hadron Phase Transition	11-05-96
Yasushi Nara, Sapporo, Japan	Study of (K^- , K^+) Reaction within the Quantum Molecular Dynamics Approach	11-14-96
Dimitri Kharzeev, U of Bielefeld, Germany	J/ψ Suppression in Heavy-Ion Collisions Novel Mechanism in Baryon Stopping	12-11-96 12-12-96
Fridolin Weber, Munich, Germany	Neutron Stars as Probes of Superdense Matter	12-12-96



Author Index



Author Index

A

Ackermann 85–86
Adams 61, 62–63
Ahmad 85, 145, 148
APEX Collaboration 153
Archer 87
Asztalos 80, 83–86, 88–92, 94, 144
Austin 148

B

Baglin 97
Baldsiefen 89
Bauer 87
Becker 80–81, 83, 87–89, 91, 137
Bennett 166–167
Bernstein 80, 83, 87, 89, 137
Betts 177
Beuville 183
Bieser 177–178
Bilewicz 64
Blocki 240
Blumenthal 85
Bossingham 177
Botlo 177
Bowers 144, 147, 151
Bowman 103, 107
Brinkman 81
Brodsky 204
Browne 136, 140–141
Budker 151
Burks 183
Busse 84–85, 88

C

Canto 94–96
Carlin 103, 107
Carpenter 85
Carroll 166–167
Case 168–170
Cederwall 80–81, 91
Cerny 57–60, 114
Chalmers Collaboration 65
Chan 123–134, 136–139
Cherney 177
Chinowsky 135
Chomaz 225
Chrin 177
Chu 93–95, 97–100
Chung 61–63, 71, 76
Cizewski 87
Clark 80–81, 83–90, 92, 113, 117, 144
Colarco 177
Cole 94
Colonna 107, 111, 225
Commins 151
Cooper 219
Crawford 135, 166–167, 177
Cronqvist 166–167
Crowe 168–170
Crystal Barrel Collaboration 168

D

da Cruz 141
Dairiki 35, 142
Dao 177

Dardenne 94
Davis 150
de Souza 103, 107
Deleplanque 80-92
Deleplanque-Stephens 144
DeMille 151
Dewald 88
Diamond 80-81, 83-92
Diaz 177
Diener 231
DiGregorio 138
Ding 87
Dionisio 82
DLS Collaboration 164
Donangelo 94, 95
Dragowsky 123-134, 138
Draper 81
Duyar 81

E

E878 Collaboration 166
E895 Collaboration 165
E896 Collaboration 167
Ekstrom 98
emiT Collaboration 149
Engel 229
Engelage 166-167
EOS Collaboration 163
Eskola 195

F

Fallon 80-81, 83-92, 144
Farhan 96
Farris 80-81, 83
Ferris 137
Firestone 97-100, 142

Fischer 85
Flores 166-167
Frauendorf 81, 91
Freedman 143-153
Fritz 183
Fujikawa 143-147, 149, 152
Fusezy 135

G

Gall 82
Gammasphere Collaboration 147
Gatti 108
Gavin 200, 205
Gavin 206
Gelbke 103, 107
Ghetti 101-102, 105
Glendenning 232-237
Goldman 136, 141
Gong 103, 107
Greene 144-145
Gregorich 61-69, 71-78
Greiner 166-167, 177, 231
Guarnera 225
Gueorguieva 82
Gunion 209
Gwinner 143, 151-152

H

Habib 218-219
Hackman 86
Hallman 166
Hamilton 79, 94
Hancox 156
Hannachi 82, 85
Hanold 111
Harada 229

Harris 203
Harss 152
Hauschild 80, 87-88
Haustein 114
He 135, 154-156, 176, 184
Heckman 166
Heinsius 168-169
Heiselberg 192
Helsgesson 223
Hendricks 61-63, 66-67, 69, 72-77
Henry 81, 83, 91
Herskind 86
Hibbert 89
Hindi 138
Hjort 163, 177
Hoffman 61-67, 69-79
Hsu 78
Hua 91
Huang 171, 175, 189-191, 193, 196
Hübel 81-82, 89
Hughes 81
Hunter 178
Hurley 130, 131, 139, 157-159

I

Isaac 123-134, 137-140
Itagaki 230

J

Jackson 135
Jacobs 172, 181
Jacobson 177
Janssens 85-86
Jared 177
Jarzynski 240
Jiang 152

Jing 108-111
Joss 80
Judd 167, 177, 179

K

Kacher 64, 66, 78
Kaci 82
Kadkhodayan 64, 66, 78
Kammel 168-170
Kate 230
Kelly 80, 82-83, 87
Kharraja 82
Kharzeev 194
Khoo 85-86
Kidonakis 202
Kim 103, 107
Klein 177-178, 185
Kluger 219
Kluger, 218
Ko 210, 212
Koch 210-216
Korichi 82, 85
Korten 81
Krane 137-138
Kreek 64
Krücken 84-90, 92
Kuo 166

L

Lakata 168-169
Lane 61-64, 66-67, 69, 72-79
Larimer 124, 136-138, 140
Laue 61, 62-63
Lauritsen 85-86
LBNL, GSI, Mainz, Dresden, Krakow,
JAERI, PSI, Bern, Rossendorf, JINR, Oslo,
Chalmers, Collaboration 65

Lebedev 177
Lee, D.M. 61-67, 69, 71-78
Lee, I.Y. 80-81, 83-92, 141, 144
Lee, S.H. 212
Lesko 123-137, 148
Levine 177
Lhenry 111
Li 210
Lindenstruth 177
Lindstrom 166-167
Ling 135
Lisa 103, 107, 177, 181
Lising 144, 149
Lister 85
Lopez-Martens 82, 85
Lowder 135
Lynch 103, 107
Lyneis 41, 113, 115-116

M

Macchiavelli 80-81, 83-92, 137-138, 141, 144
MacGarth 69
MacLeod 84-90, 92, 137-138, 144
Maier 153
Margetis 173-175, 183
Marks 177
Marx 167
Matis 186
McDonald 130-131, 139-140, 157-159
McGaughey 200
McGrath 61-63, 67, 75-77
McMahan 118-119
McNabb 87
McParland 177
McShane 177
Meier 177

Mohar 64, 78
Moltz 57-60, 114
Moore 85
Moorhead 123-128, 130-132, 135, 137, 140
Moretto 101-112
Mortara 145-146, 148, 150
Mottola 218-219
Müller 195
Myers 238-239

N

NA49 Collaboration 171-172, 174-175
Nakatsukasa 84
Nara 229
Nelson 136
Neu 64, 78
Nguyen 177
Nisius 85
Nolan 80
Nordberg 98
Norman 114, 123-134, 136-141, 157-159
Nygren 135

O

O'Brien 80
Odyniec 175
Ognibene 57, 60
Ohnishi 226-230
Olson 177, 180

P-Q

Pardo 152
Paul 152
Paz 218
Peaslee 103, 107
Pei 232, 233-234
Perillo-Isaac 123-134, 137-140

Peusquens 88
Phair 91, 101–107, 109–110, 112
Pohler 82
Porter 164, 182
Powell 57–60, 114
Price 135, 155, 176, 184
Prindle 180
Przybylski 135

R

Rai 165
Randrup 31, 220–228
Rasmussen 93–96
Rehm 152
Reich 144, 147
Retiere 183
Richards 135
Ring 95–96
Ritter 20
Robinson 138
Ross 146
Rowe 57–60, 114, 143–144
Rubehn 104, 107, 109, 110–112
Rubel 81
Ruuskanen 200

S

Sakrejda 167, 177, 181
Saladin 91
Sarantites 91
Sarcevic 190, 193
Satz 194
Scannapieco 185
Schaab 237
Schaffner-Bielich 231
Schambach 177

Scheetz 177
Schiffer 145, 152
Schmid 84–90, 92
Schmitt 108
Schroeder 1, 7
Schück 82
Schuelke 123–134
Schuler 207
Schulze 82
Semple 80
Seweryniak 85
Shang 143–144, 147, 151–152
Shapiro 135
Shaughnessy 61–63, 66–67, 69, 72–77
Shirley 97
Singh 100
Skalski 240
Skulski 111
Smith 130–131, 139–140, 157–159, 201–203
Smoot 135
Song 212–217
Stalnaker 151
STAR Collaboration 177–178, 181
STAR Trigger Group 179
Stephens 80–92, 144
Stevenson 135
Stöcker 231
Stokstad 14, 123–135, 142
Stone 177, 181
Stoyer 64, 66, 78, 81, 93–95
Strellis 61–63, 67, 69, 72–77, 94
Sui 111
Swiatecki 238–240
Sylwester 61–67, 69, 72–78

T-U

Teixeira 141
Thews 193
Toy 172
Trentalange 183
Tripp 135
Tsang 103
Tso 101-102, 105-106, 109-111
Tull 177, 180

V

van Severen 82
Veeck 66, 111
Vetter 84-86, 88, 90, 92, 143, 147, 152
Vieu 82
Visser 167, 177
Vogt 199-209
von Brentano 88
Vu 177-178

W

Wadsworth 80, 82, 89
Wallsgrove 72
Wang 189-198
Wasserman 143, 144, 147, 149
Watanabe 64
Weber 232-233, 237

Weigel 237
Wells 183
Wieman 177, 183
Wienold 171
Wierczinski 64, 66, 77
Wietfeldt 136
Wilk 61-63, 67, 69-70, 72-76
Williams 107
Willsau 81
Woosley 142
Wozniak 91, 101-112
Wu 99, 142
Wuosmaa 148
Wutte 146

X-Z

Xi 113
Xie 115-116
Xu 194
Yang 78
Yee 177
Younes 87
Yu 91, 112
Zaerpoor 137-138
Zeuli 145
Zhu 103
Zipkin 97
Zlimen 136