

ANCR-1270

Distributed Under Category:  
NRC-3  
Water Reactor Safety Research  
Fuel Behavior  
TID-4500, R63

USNRC-OECD HALDEN PROJECT FUEL BEHAVIOR TEST PROGRAM --  
EXPERIMENT DATA REPORT FOR TEST ASSEMBLIES

IFA-226 AND IFA-239

**NOTICE**  
This report was prepared as an account of work sponsored by the United States Government. Neither the United States nor the United States Energy Research and Development Administration, nor any of their employees, nor any of their contractors, subcontractors, or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness or usefulness of any information, apparatus, product or process disclosed, or represents that its use would not infringe privately owned rights.

by

E. T. Laats  
P. E. MacDonald  
W. J. Quapp

AEROJET NUCLEAR COMPANY

Date Published -- December 1975

PREPARED FOR THE  
U.S. ENERGY RESEARCH AND DEVELOPMENT ADMINISTRATION  
IDAHO OPERATIONS OFFICE  
UNDER CONTRACT NO. E(10-1)-1375

## ACKNOWLEDGMENTS

Grateful acknowledgment is given to D. R. Coleman and W. F. Domenico for their numerous contributions which led to the final formulation of this report.

## **DISCLAIMER**

**This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency Thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.**

## **DISCLAIMER**

**Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.**

## ABSTRACT

This report presents the experimental data which were obtained from the IFA-226 and IFA-239 test assemblies during operation in the Halden Boiling Water Reactor. Included are cladding elongation, fuel centerline temperature, internal gas pressure, and power history data from IFA-226 which were obtained from November 1971 through April 1974, and cladding elongation, diametral profile, and power history data from IFA-239 covering the period from March 1973 through April 1974.

The data, presented in the form of composite graphs, have been analyzed only to the extent necessary to assure that they are reasonable and correct. The intent of this report is to make available the uninterpreted data from these two tests for use in development and verification of analytical models which evaluate fuel rod behavior.

A description of these mixed oxide fuel test assemblies and their instrumentation is presented in the early chapters of the text. Test pin fabrication history, instrument calibration data, assembly power calibration methods, and the neutron detector data reduction technique are included as appendices.

## SUMMARY

The instrumented test assemblies IFA-226 and IFA-239 began operation in the Halden Boiling Water Reactor on November 24, 1971 and March 12, 1973, respectively. The use and management of these assemblies is being directed by Aerojet Nuclear Company for the United States Nuclear Regulatory Commission, who is a member of the OECD<sup>[a]</sup> Halden Reactor Project.

Test assembly IFA-226 consists of a vertically stacked train of two clusters of six fuel rods each. Each cluster is about 3.1 feet in length and 2.8 inches in diameter. The rods within each cluster are arranged in a hexagonal lattice. The assembly rods are cooled by natural circulation of heavy water at 240°C and  $3.45 \times 10^6$  N/cm<sup>2</sup>. Each fuel rod is composed of recycled plutonium-uranium oxide fuel material which is clad in zircaloy-4. The density of the fuel varies from 92 to 96% of theoretical. The rod dimensions, except for length, are typical of those of pressurized water reactor reload fuel. IFA-226 is equipped with four primary in-pile instruments: elongation sensors, pressure transducers, fuel centerline thermocouples, self-powered neutron detectors.

IFA-239 is a single-rod test assembly which is used to determine fuel rod axial and diametral strains during transient and steady state reactor operation. The fuel rod is similar to those used in IFA-226. The coolant conditions are also similar.

The experimental data which are presented in this document cover the period from beginning-of-life through April 16, 1974. Data from the elongation sensors, neutron detectors, and fuel centerline thermocouples were collected at regular intervals using an IBM-1800 data collection system. During steady state fuel power operation, data were automatically collected every six hours. During transient operation, data were collected as often as every 15 minutes. The pressure transducer data from IFA-226 and the diametral profile data from IFA-239 were obtained on a demand basis. The frequency of data collection varied from a few minutes to several months.

---

[a] OECD – Organization for Economic Cooperation and Development.

# CONTENTS

ACKNOWLEDGMENTS . . . . .	ii
ABSTRACT . . . . .	iii
SUMMARY . . . . .	iv
I. INTRODUCTION . . . . .	1
II. HALDEN BOILING WATER REACTOR . . . . .	3
III. IFA-226 DESIGN . . . . .	5
1. GENERAL DESCRIPTION . . . . .	5
2. INSTRUMENTATION . . . . .	5
2.1 Elongation Sensors . . . . .	9
2.2 Pressure Transducers . . . . .	9
2.3 Fuel Centerline Thermocouples . . . . .	9
2.4 Self-Powered Neutron Detectors . . . . .	9
2.5 Additional Instrumentation . . . . .	12
IV. IFA-239 DESIGN . . . . .	13
1. INSTRUMENTATION . . . . .	13
1.1 Diametral Profile Sensor . . . . .	13
1.2 Elongation Sensor . . . . .	18
1.3 Self-Powered Neutron Detectors . . . . .	18
1.4 Additional Instrumentation . . . . .	18
V. DATA PRESENTATION . . . . .	19
1. PRESENTATION OF DATA FROM IFA-226 . . . . .	19
2. PRESENTATION OF DATA FROM IFA-239 . . . . .	142
3. OPERATIONAL STATUS OF THE INSTRUMENTATION . . . . .	174
APPENDIX A – FABRICATION REPORT . . . . .	175
1. PELLET FABRICATION . . . . .	177
1.1 Pellet Starting Materials . . . . .	177
1.2 Final Pellet Fabrication . . . . .	177
1.3 Chemical Analysis . . . . .	178
1.4 Pellet Autoradiography and Metallography . . . . .	181

2.	CLADDING MATERIALS . . . . .	182
3.	ROD FABRICATION . . . . .	195
4.	INSTRUMENTATION INSERTION . . . . .	205
APPENDIX B – CALIBRATION RESULTS . . . . .		207
1.	CLADDING ELONGATION SENSOR CALIBRATION . . . . .	209
2.	FUEL CENTERLINE THERMOCOUPLE CALIBRATION . . . . .	209
3.	TURBINE FLOWMETER CALIBRATION . . . . .	217
4.	FISSION GAS PRESSURE TRANSDUCER CALIBRATION . . . . .	219
5.	NEUTRON DETECTOR CHARACTERISTICS . . . . .	225
6.	DIAMETRAL PROFILE CALIBRATION (IFA-239) . . . . .	227
APPENDIX C – DATA REDUCTION TECHNIQUES . . . . .		231
1.	IFA-226 NEUTRON DETECTOR DATA . . . . .	233
2.	IFA-239 NEUTRON DETECTOR DATA . . . . .	235

## FIGURES

1.	HBWR Core Loading 14 (March 1974) . . . . .	4
2.	Diagram of Instrumented Fuel Assembly 226. . . . .	6
3.	Schematic diagram of four types of IFA-226 test rods . . . . .	7
4.	Schematic diagram of a cladding elongation sensor . . . . .	10
5.	Schematic diagram of an IFA-226 pressure sensor . . . . .	11
6.	Diagram of Instrumented Fuel Assembly 239. . . . .	14
7.	Schematic diagram of the IFA-239 diametral profile sensor . . . . .	15
8.	Schematic diagram of the IFA-239 diameter gauge . . . . .	16
9.	Schematic diagram of the IFA-239 long range linear transformer . . . . .	17
10.	Elongation history of IFA-226 test rods from November 1971 through January 1972 . . . . .	23



11.	Elongation history of IFA-226 test rods from March 1972 through May 1972 . . . . .	24
12.	Elongation history of IFA-226 test rods from May 1972 through July 1972 . . . . .	25
13.	Elongation history of IFA-226 test rods from July 1972 through August 1972 . . . . .	26
14.	Elongation history of IFA-226 test rods from October 1972 through January 1973 . . . . .	27
15.	Elongation history of IFA-226 test rods from March 1973 through May 1973 . . . . .	28
16.	Elongation history of IFA-226 test rods from June 1973 through July 1973 . . . . .	29
17.	Elongation history of IFA-226 test rods from August 1973 through September 1973 . . . . .	30
18.	Elongation history of IFA-226 test rods from December 1973 through January 1974 . . . . .	31
19.	Elongation history of IFA-226 test rods from February 1974 through April 1974 . . . . .	32
20.	Fuel centerline temperature history of IFA-226 test rods from November 1971 through January 1972 . . . . .	33
21.	Fuel centerline temperature history of IFA-226 test rods from March 1972 through April 1972 . . . . .	34
22.	Fuel centerline temperature history of IFA-226 test rods from May 1972 through June 1972 . . . . .	35
23.	Fuel centerline temperature history of IFA-226 test rods from July 1972 through August 1972 . . . . .	36
24.	Fuel centerline temperature history of IFA-226 test rods from October 1972 through November 1972 . . . . .	37
25.	Fuel centerline temperature history of IFA-226 test rods from December 1972 through January 1973 . . . . .	38
26.	Fuel centerline temperature history of IFA-226 test rods from March 1973 through May 1973 . . . . .	39
27.	Fuel centerline temperature history of IFA-226 test rods from June 1973 through August 1973 . . . . .	40

28.	Fuel centerline temperature history of IFA-226 test rods from August 1973 through September 1973 . . . . .	41
29.	Peak power history of IFA-226 test rods from November 1971 through December 1971 . . . . .	42
30.	Peak power history of IFA-226 test rods for January 1972 . . . . .	43
31.	Peak power history of IFA-226 test rods from March 1972 through April 1972 . . . . .	44
32.	Peak power history of IFA-226 test rods from May 1972 through June 1972 . . . . .	45
33.	Peak power history if IFA-226 test rods from July 1972 through August 1972 . . . . .	46
34.	Peak power history of IFA-226 test rods from October 1972 through November 1972 . . . . .	47
35.	Peak power history of IFA-226 test rods from December 1972 through January 1973 . . . . .	48
36.	Peak power history of IFA-226 test rods from March 1973 through May 1973 . . . . .	49
37.	Peak power history of IFA-226 test rods from June 1973 through July 1973 . . . . .	50
38.	Peak power history of IFA-226 test rods from August 1973 through September 1973 . . . . .	51
39.	Peak power history of IFA-226 test rods from December 1973 through January 1974 . . . . .	52
40.	Peak power history of IFA-226 test rods from February 1974 through April 1974 . . . . .	53
41.	Local power history at thermocouple location of IFA-226 test rods from November 1971 through January 1972 . . . . .	54
42.	Average power history of IFA-226 test rods from November 1971 through December 1971 . . . . .	55
43.	Average power history of IFA-226 test rods from January 1972 through March 1972 . . . . .	56
44.	Average power history of IFA-226 test rods from April 1972 through June 1972 . . . . .	57

45.	Average power history of IFA-226 test rods from June 1972 through July 1972 . . . . .	58
46.	Average power history of IFA-226 test rods from August 1972 through October 1972 . . . . .	59
47.	Average power history of IFA-226 test rods from November 1972 through December 1972 . . . . .	60
48.	Average power history of IFA-226 test rods from January 1973 through March 1973 . . . . .	61
49.	Average power history of IFA-226 test rods from April 1973 through May 1973 . . . . .	62
50.	Average power history of IFA-226 test rods from June 1973 through July 1973 . . . . .	63
51.	Average power history of IFA-226 test rods from August 1973 through September 1973 . . . . .	64
52.	Average power history of IFA-226 test rods from December 1973 through January 1974 . . . . .	65
53.	Average power history of IFA-226 test rods from February 1974 through March 1974 . . . . .	66
54.	Average power history of IFA-226 test rods for April 1974 . . . . .	67
55.	Fission gas pressure history of IFA-226 test rods at high power levels . . . . .	68
56.	Fission gas pressure history of IFA-226 test rods from November 1971 through January 1972 . . . . .	69
57.	Fission gas pressure history of IFA-226 test rods from March 1972 through April 1972 . . . . .	70
58.	Fission gas pressure history of IFA-226 test rods from May 1972 through June 1972 . . . . .	71
59.	Fission gas pressure history of IFA-226 test rods from July 1972 through August 1972 . . . . .	72
60.	IFA-226 test rod elongation versus peak rod power from November 24, 1971 at 1000 hours through November 24, 1971 at 2300 hours . . . . .	73
61.	IFA-226 test rod elongation versus peak rod power from November 25, 1971 at 0000 hours through November 26, 1971 at 0200 hours . . . . .	74
62.	IFA-226 test rod elongation versus peak rod power from November 26, 1971 at 0300 hours through November 16, 1971 at 2200 hours . . . . .	75

63.	IFA-226 test rod elongation versus peak rod power from November 27, 1971 at 0000 hours through November 27, 1971 at 1300 hours . . . . .	76
64.	IFA-226 test rod elongation versus peak rod power from December 21, 1971 at 1700 hours through December 22, 1971 at 1000 hours . . . . .	77
65.	IFA-226 test rod elongation versus peak rod power from January 16, 1972 at 1200 hours through January 18, 1972 at 0200 hours . . . . .	78
66.	IFA-226 test rod elongation versus peak rod power from March 19, 1972 at 1600 hours through March 21, 1972 at 1000 hours . . . . .	79
67.	IFA-226 test rod elongation versus peak rod power from March 21, 1972 at 1500 hours through March 23, 1972 at 0000 hours . . . . .	80
68.	IFA-226 test rod elongation versus peak rod power from May 20, 1972 at 1800 hours through May 22, 1972 at 2200 hours . . . . .	81
69.	IFA-226 test rod elongation versus peak rod power from August 7, 1972 at 0000 hours through August 8, 1972 at 1000 hours . . . . .	82
70.	IFA-226 test rod elongation versus peak rod power from December 14, 1972 at 0000 hours through December 15, 1972 at 1100 hours . . . . .	83
71.	IFA-226 test rod elongation versus peak rod power from March 14, 1973 at 1300 hours through March 16, 1973 at 0500 hours . . . . .	84
72.	IFA-226 test rod elongation versus peak rod power from August 2, 1973 at 0900 hours through August 2, 1973 at 2000 hours . . . . .	85
73.	IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from November 24, 1971 at 1000 hours through November 24, 1971 at 2300 hours . . . . .	86
74.	IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from November 25, 1971 at 0000 hours through November 26, 1971 at 0200 hours . . . . .	87
75.	IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from November 26, 1971 at 0300 hours through November 26, 1971 at 2200 hours . . . . .	88
76.	IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from November 27, 1971 at 0000 hours through November 27, 1971 at 1300 hours . . . . .	89
77.	IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from December 21, 1971 at 1700 hours through December 22, 1971 at 1000 hours . . . . .	90

78.	IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from January 16, 1972 at 1200 hours through January 18, 1972 at 0200 hours . . . . .	91
79.	IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from March 19, 1972 at 1600 hours through March 21, 1972 at 1000 hours . . . . .	92
80.	IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from March 21, 1972 at 1500 hours through March 23, 1972 at 0000 hours . . . . .	93
81.	IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from May 20, 1972 at 1800 hours through May 22, 1972 at 2000 hours . . . . .	94
82.	IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from June 5, 1972 at 0600 hours through June 7, 1972 at 1800 hours . . . . .	95
83.	IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from August 7, 1972 at 0000 hours through August 8, 1972 at 1000 hours . . . . .	96
84.	IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from October 26, 1972 at 1500 hours through October 27, 1972 at 2250 hours . . . . .	97
85.	IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from October 27, 1972 at 2350 hours through October 29, 1972 at 1400 hours . . . . .	98
86.	IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from December 14, 1972 at 0000 hours through December 15, 1972 at 1100 hours . . . . .	99
87.	IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from January 15, 1972 at 2000 hours through January 19, 1973 at 0800 hours . . . . .	100
88.	IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from March 14, 1973 at 1300 hours through March 16, 1973 at 0500 hours . . . . .	101
89.	IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from July 7, 1973 at 0000 hours through July 8, 1973 at 0600 hours . . . . .	102

90.	IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from July 12, 1973 at 0000 hours through July 13, 1973 at 0800 hours . . . . .	103
91.	IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from August 2, 1973 at 0900 hours through August 2, 1973 at 2000 hours . . . . .	104
92.	IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from September 24, 1973 at 0000 hours through September 24, 1973 at 1900 hours . . . . .	105
93.	IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from September 25, 1973 at 1600 hours through September 26, 1973 at 1300 hours . . . . .	106
94.	IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from October 26, 1973 at 2000 hours through October 27, 1973 at 2000 hours . . . . .	107
95.	IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from December 6, 1973 at 1200 hours through December 8, 1973 at 1600 hours . . . . .	108
96.	IFA-226 assembly axial flux profile at 1200 hours on November 24, 1971 . . . . .	109
97.	IFA-226 assembly axial flux profile at 0000 hours on November 25, 1971 . . . . .	110
98.	IFA-226 assembly axial flux profile at 2100 hours on November 25, 1971 . . . . .	111
99.	IFA-226 assembly axial flux profile at 0400 hours on November 27, 1971 . . . . .	112
100.	IFA-226 assembly axial flux profile at 1800 hours on November 28, 1971 . . . . .	113
101.	IFA-226 assembly axial flux profile at 1800 hours on December 2, 1971 . . . . .	114
102.	IFA-226 assembly axial flux profile at 1800 hours on December 8, 1971 . . . . .	115
103.	IFA-226 assembly axial flux profile at 1800 hours on December 12, 1971 . . . . .	116
104.	IFA-226 assembly axial flux profile at 0000 hours on December 23, 1971 . . . . .	117
105.	IFA-226 assembly axial flux profile at 1200 hours on March 20, 1972 . . . . .	118
106.	IFA-226 assembly axial flux profile at 0000 hours on March 31, 1972 . . . . .	119
107.	IFA-226 assembly axial flux profile at 0000 hours on April 12, 1972 . . . . .	120
108.	IFA-226 assembly axial flux profile at 0000 hours on April 23, 1972 . . . . .	121

109.	IFA-226 assembly axial flux profile at 0000 hours on June 2, 1972 . . . . .	122
110.	IFA-226 assembly axial flux profile at 0000 hours on July 1, 1972 . . . . .	123
111.	IFA-226 assembly axial flux profile at 0000 hours on July 30, 1972 . . . . .	124
112.	IFA-226 assembly axial flux profile at 0000 hours on August 26, 1972 . . . . .	125
113.	IFA-226 assembly axial flux profile at 1800 hours on October 31, 1972 . . . . .	126
114.	IFA-226 assembly axial flux profile at 0000 hours on December 23, 1972 . . . . .	127
115.	IFA-226 assembly axial flux profile at 0000 hours on January 17, 1973 . . . . .	128
116.	IFA-226 assembly axial flux profile at 0000 hours on March 28, 1973 . . . . .	129
117.	IFA-226 assembly axial flux profile at 0000 hours on April 3, 1973 . . . . .	130
118.	IFA-226 assembly axial flux profile at 0000 hours on May 4, 1973 . . . . .	131
119.	IFA-226 assembly axial flux profile at 0000 hours on June 25, 1973 . . . . .	132
120.	IFA-226 assembly axial flux profile at 1800 hours on June 30, 1973 . . . . .	133
121.	IFA-226 assembly axial flux profile at 0000 hours on July 16, 1973 . . . . .	134
122.	IFA-226 assembly axial flux profile at 0000 hours on August 23, 1973 . . . . .	135
123.	IFA-226 assembly axial flux profile at 0000 hours on December 26, 1973 . . . . .	136
124.	IFA-226 assembly axial flux profile at 0000 hours on January 28, 1974 . . . . .	137
125.	IFA-226 assembly axial flux profile at 0000 hours on February 28, 1974 . . . . .	138
126.	IFA-226 assembly axial flux profile at 1200 hours on March 1, 1974 . . . . .	139
127.	IFA-226 assembly axial flux profile at 0600 hours on March 25, 1974 . . . . .	140
128.	IFA-226 assembly axial flux profile at 0000 hours on April 15, 1974 . . . . .	141
129.	Axial distance traveled by diameter gauge . . . . .	144
130.	Diametral profile of IFA-239 calibration rod – Run 1 . . . . .	145
131.	Diametral profile of IFA-239 calibration rod -- Run 2 . . . . .	146
132.	IFA-239 diametral profile at 1631 hours on March 12, 1973 . . . . .	147
133.	IFA-239 diametral profile at 1645 hours on March 12, 1973 . . . . .	148

134. IFA-239 diametral and axial flux profiles at 2124 hours on March 12, 1973 . . . . .	149
135. IFA-239 diametral and axial flux profiles at 0042 hours on March 13, 1973 . . . . .	151
136. IFA-239 diametral and axial flux profiles at 0054 hours on March 13, 1973 . . . . .	151
137. IFA-239 diametral and axial flux profiles at 0907 hours on March 13, 1973 . . . . .	152
138. IFA-239 diametral and axial flux profiles at 0923 hours on March 13, 1973 . . . . .	153
139. IFA-239 diametral and axial flux profiles at 1609 hours on March 13, 1973 . . . . .	154
140. IFA-239 diametral and axial flux profiles at 1625 hours on March 13, 1973 . . . . .	155
141. IFA-239 diametral and axial flux profiles at 1721 hours on March 14, 1973 . . . . .	156
142. IFA-239 diametral and axial flux profiles at 1734 hours on March 14, 1973 . . . . .	157
143. IFA-239 diametral and axial flux profiles at 2212 hours on March 14, 1973 . . . . .	158
144. IFA-239 diametral and axial flux profiles at 2220 hours on March 14, 1973 . . . . .	159
145. IFA-239 diametral and axial flux profiles at 0001 hours on March 15, 1973 . . . . .	160
146. IFA-239 diametral and axial flux profiles at 0009 hours on March 15, 1973 . . . . .	161
147. IFA-239 diametral and axial flux profiles at 0108 hours on March 15, 1973 . . . . .	162
148. IFA-239 diametral and axial flux profiles at 0121 hours on March 15, 1973 . . . . .	163
149. IFA-239 diametral and axial flux profiles at 1258 hours on March 15, 1973 . . . . .	164
150. IFA-239 diametral and axial flux profiles at 1312 hours on March 15, 1973 . . . . .	165



151. IFA-239 diametral profile at 0930 hours on March 16, 1973 . . . . .	166
152. IFA-239 diametral profile at 0942 hours on March 16, 1973 . . . . .	167
153. IFA-239 elongation history from March 1973 through April 1973 . . . . .	168
154. IFA-239 elongation history from May 1973 through June 1973 . . . . .	169
155. IFA-239 elongation history from July 1973 through August 1973 . . . . .	170
156. IFA-239 elongation history from September 1973 through December 1973 . . .	171
157. IFA-239 elongation history from January 1974 through February 1974 . . . . .	172
158. IFA-239 elongation history from March 1974 through April 1974 . . . . .	173
A-1. Fuel pellet autoradiography. . . . .	183
A-2. Fuel pellet metallography – radial section . . . . .	184
A-3. Fuel pellet metallography – axial section . . . . .	185
A-4. Lot 84003 hydride orientation . . . . .	190
A-5. Lot 74001 hydride orientation . . . . .	191
A-6. Typical weld metallography of cladding . . . . .	196
A-7. Dimensional profile of Rod AG . . . . .	199
A-8. Dimensional profile of Rod AH . . . . .	200
A-9. Dimensional profile of Rod AJ . . . . .	201
A-10. Dimensional profile of Rod AK . . . . .	202
A-11. Dimensional profile of Rod AM . . . . .	203
A-12. Dimensional profile of Rod AO . . . . .	204
B-1. Calibration curve at 240 <sup>0</sup> C for the elongation sensor on IFA-226 Test Rod AG . . . . .	210
B-2. Calibration curve at 240 <sup>0</sup> C for the elongation sensor on IFA-226 Test Rod AH . . . . .	211
B-3. Calibration curve at 240 <sup>0</sup> C for the elongation sensor on IFA-226 Test Rod AJ . . . . .	212

B-4.	Calibration curve at 240°C for the elongation sensor on IFA-226 Test Rod AK . . . . .	213
B-5.	Calibration curve at 240°C for the elongation sensor on IFA-226 Test Rod AM . . . . .	214
B-6.	Calibration curve at 240°C for the elongation sensor on IFA-226 Test Rod AO . . . . .	215
B-7.	Calibration curve at 240°C for the elongation sensor on IFA-226 Test Rod B-6 . . . . .	216
B-8.	Wiring diagram of a fuel centerline thermocouple . . . . .	217
B-9.	Calibration curves for the IFA-226 inlet and outlet flowmeters . . . . .	218
B-10.	Switch point consistency of the pressure transducer in Rod AA . . . . .	220
B-11.	Switch point consistency of the pressure transducer in Rod AB . . . . .	221
B-12.	Switch point consistency of the pressure transducer in Rod AC . . . . .	222
B-13.	Switch point consistency of the pressure transducer in Rod AD . . . . .	223
B-14.	Switch point consistency of the pressure transducer in Rod AE . . . . .	224
B-15.	Calibration curve for the diameter gauge transformer . . . . .	228
B-16.	Calibration curve for the long range linear transformer . . . . .	229

**TABLES**

I.	Fuel Rod Data for IFA-226 . . . . .	8
II.	Fuel Rod Data for IFA-239 . . . . .	13
III.	Internal Rod Pressure for IFA-226 from November 20, 1971 through August 28, 1972 . . . . .	21
IV.	Times When In-Pile Diametral Profile Data were Obtained . . . . .	143
V.	Operational Status of IFA-226 and IFA-239 Instrumentation as of April 16, 1974 . . . . .	174
A-I.	Pu Isotopic Content and Associated Burnup . . . . .	178
A-II.	Plutonium Nitrate Impurities . . . . .	179

A-III.	Depleted UO <sub>2</sub> Powder Impurities . . . . .	180
A-IV.	Isotope Content of Fuel Pellets . . . . .	181
A-V.	Plutonium Content . . . . .	181
A-VI.	Fuel Pellet Impurities . . . . .	182
A-VII.	Description, Properties, and Test Results for Sandvik Cladding -- First Lot . . . . .	186
A-VIII.	Description, Properties, and Test Results for Sandvik Cladding -- Second Lot . . . . .	188
A-IX.	Results of Physical and Chemical Analysis of Plain End Plug Bar Stock . . . . .	192
A-X.	Results of Chemical Analysis of Halden Instrumentation Bar Stock . . . . .	193
A-XI.	Results of Physical and Chemical Analysis of Grooved End Plug Bar Stock . . . . .	194
A-XII.	Fuel Pellet Data . . . . .	197
A-XIII.	Tube and Plenum Data . . . . .	198
A-XIV.	Finished Assembly Data . . . . .	205
B-I.	IFA-226 Neutron Detector Characteristics . . . . .	226

**USNRC-OECD HALDEN PROJECT FUEL BEHAVIOR TEST PROGRAM --  
EXPERIMENT DATA REPORT FOR TEST ASSEMBLIES  
IFA-226 AND IFA-239**

**I. INTRODUCTION**

Understanding the performance of light-water reactor fuel under normal and accident conditions is a major objective of the United States Nuclear Regulatory Commission's (USNRC) reactor safety research program. An extensive program has been defined -- centered on out-of-pile and in-pile experiments and their analyses -- with the goal of verifying analytical codes. These codes are intended for use in predicting transient fuel performance during a wide range of accident types and conditions, at any time during the normal useful life of a fuel rod.

Analysis of fuel behavior during an accident depends critically upon knowledge of fuel rod conditions during normal (steady state) operation. Especially important are the temperature distributions of the fuel pellets, the internal gas pressure and composition, the amount of restructuring and cracking of the pellets, and the mechanical strains and irradiation damage in the cladding. All of these variables are affected by the rod design variables at beginning-of-life and, subsequently, by the degree of burnup and the power history.

This document presents the data which were obtained during the steady state irradiation of two test assemblies in the Halden Boiling Water Reactor (HBWR) located in Halden, Norway. Cladding elongation, fuel centerline temperature, rod internal pressure, and fuel rod diameter data are presented as functions of power and time for rods with various initial pellet-to-cladding gap sizes and fuel densities. These data will facilitate development of analytical models describing:

- (1) Fuel pellet-cladding mechanical interactions as a function of power, burnup, fuel density, and initial pellet-cladding diametral gap
- (2) Fuel density, pellet-cladding gap, and temperature effects on fission gas release and rod internal pressure
- (3) Pellet-to-cladding gap, fuel density, and irradiation effects on the temperature of mixed oxide fuels
- (4) Fuel rod axial and diametral strains as functions of power and burnup.

The instrumented fuel assemblies IFA-226 and IFA-239 were designed, fabricated, and initially irradiated in the HBWR by Nuclear Fuel Services, Incorporated (NFS) of Rockville, Maryland. In 1974, these two assemblies and all of their existing data were

acquired from NFS by the USNRC. The continued use and management of these assemblies is being directed by Aerojet Nuclear Company under the USNRC's participation in the OECD<sup>[a]</sup> Halden reactor project.

Test assembly IFA-226 contains 12 mixed plutonium-uranium oxide fuel rods about 33 inches long arranged in two clusters. Irradiation of this assembly began November 24, 1971. The assembly contains six cladding extensometers (LVDTs)<sup>[b]</sup>, four fuel centerline thermocouples, five fuel rod internal pressure sensors, eight self-powered neutron detectors, and various thermal-hydraulic power calibration equipment. IFA-239 contains one mixed oxide test rod, one fuel rod diameter gauge (LVDT), one cladding extensometer, and various power sensors. Irradiation of IFA-239 began March 12, 1973.

Data which were obtained from beginning-of-life through April 16, 1974 (or until instrument failure) are presented in this report. During this time, IFA-226 and IFA-239 attained a burnup of about 20,000 MWd/tU and 12,300 MWd/tU (assembly average values), respectively.

Section II of this report describes the HBWR. Sections III and IV describe the designs of IFA-226 and IFA-239, respectively. Section V presents the data obtained from these assemblies. Appendix A describes the test rod fabrication processes, Appendix B describes the assembly and test rod instrumentation calibration procedures, and Appendix C describes the data reduction techniques.

---

[a] OECD – Organization for Economic Cooperation and Development.

[b] Linear Variable Differential Transformer.

## II. HALDEN BOILING WATER REACTOR

Operation of the Halden Boiling Water Reactor is sponsored through an international agreement among the appropriate government agencies of Norway, Denmark, Finland, Italy, Japan, Germany, the Netherlands, Sweden, and the USA. The Electric Power Research Institute, USA, is also a member. Combustion Engineering, Inc., General Electric Company, United States Nuclear Regulatory Commission, and Companhia Brasileira de Tecnologia Nuclear, Brazil, participate as associated parties.


The reactor is operated with a water temperature of 240°C and a pressure of  $3.45 \times 10^6 \text{ N/m}^2$ . The core consists of about 60 assemblies. Of these assemblies, 15 to 20 are either driver assemblies or nonfueled instrumented assemblies. The remaining are test assemblies fabricated by either the Halden project or the various members.

The majority of the test assemblies are cooled by natural circulation of nearly saturated heavy water. The specific hydraulic conditions depend upon assembly design and amount of inlet throttling (most of the test assemblies are cooled by fluid which acquires a significant void fraction while progressing up the flow channel). A limited number of high power Halden test assemblies are operated with forced circulation of heavy water subcooled 10 to 15°C. The region between test assemblies serves as the return flow path for the coolant. Typical reactor steady state operating conditions are:

Core Power	12 MW
Coolant Pressure	$3.45 \times 10^6 \text{ N/m}^2$
Coolant Inlet Temperature	237°C
Coolant Saturation Temperature	240°C
Natural Circulation Flow Rate	0.5 to 2 l/sec
Forced Circulation Flow Rate	2 to 4 l/sec
Axial Power Peaking Factor	1.2 to 1.7
Thermal Flux	$3 \text{ to } 3.6 \times 10^{13} \text{ n/cm}^2\text{-sec}$
Fast Flux (>1 MeV)	$5 \times 10^{11} \text{ n/cm}^2\text{-sec}$
Core Active Length	1.7 m
Maximum Test Assembly Outside Diameter	73 mm
Core Configuration	open hexagonal lattice.

IFA-226 and IFA-239 were cooled by natural circulation of the heavy water except during power calibration (the first few days of operation) when forced circulation of subcooled coolant was used. Figure 1 shows the core locations of IFA-226 and IFA-239.

The HBWR normally operates on a four-month schedule having three months of irradiation followed by one month of shutdown for repair and exchange of test assemblies. However, special tests and emergency repairs often require brief shutdowns of the reactor during the three-month irradiation periods.



HBWR IV CORE LOADING No 14		Date March-74
19	Control rod (CS19)	total 29
202	Instrumented fuel assembly (IFA-202)	.. 43
S	Standard third charge assembly	.. 11
31	Neutron detector rig (PEI-303)	.. 7

Fig. 1 HBWR Core Loading 14 (March 1974).

### III. IFA-226 DESIGN

This section presents a general description of the IFA-226 test rod geometry, the steady state full power coolant conditions, and the basic in-pile assembly instrumentation.

#### 1. GENERAL DESCRIPTION

The instrumented fuel assembly IFA-226 consists of a vertically stacked train of two clusters of six fuel rods each. Each cluster is about 3.1 feet in length and 2.8 inches in diameter. The rods within each cluster are arranged in a hexagonal lattice. A diagram of IFA-226 is presented in Figure 2 and a schematic diagram of each of the four types of test rods within the assembly is shown in Figure 3.

As mentioned, the test assembly is generally cooled by natural circulation of heavy water. When the assembly is operating at high, steady state power levels, the nominal inlet flow rate of the coolant is about 2 l/sec, and the coolant inlet temperature is about 237°C. The nominal coolant pressure and the saturation temperature are  $3.45 \times 10^6$  N/m<sup>2</sup> and 240°C, respectively.

The test rod fuel is fabricated from recycled plutonium oxide powder which is blended with depleted (0.20 wt% U<sup>235</sup>) uranium oxide powder. This mixed oxide material (9.5 wt% PuO<sub>2</sub>) is pressed and sintered into pellet form and clad with zircaloy-4. A complete fabrication history is presented in Appendix A and the final pellet and rod dimensions are listed in Table I. The dimensions, except for length, are typical of those of pressurized water reactor reload fuel.

#### 2. INSTRUMENTATION

The experimental data are obtained from the following in-pile sensors:

- (1) elongation sensors
- (2) pressure transducers
- (3) fuel centerline thermocouples
- (4) self-powered neutron detectors.

The pressure transducers and elongation sensors were manufactured, attached to the fuel pins, and calibrated at the Halden Project. The fuel centerline thermocouples were manufactured by Continental Sensing, Inc., of Melrose Park, Illinois, and were installed in the test pins by the Halden Project. The self-powered neutron detectors were obtained from AB Atomenergi of Sweden and are located among the test rods at selected axial and radial positions. Results of the instrument calibration test are reported in Appendix B.






Fig. 2 Diagram of Instrumented Fuel Assembly 226.




Fig. 3 Schematic diagram of four types of IFA-226 test rods.

TABLE I

## FUEL ROD DATA FOR IFA-226

Upper Cluster	Rod	Cladding <sup>[a]</sup>		Fuel <sup>[b]</sup>			Gap <sup>[d]</sup> (mm)	Instrumentation		
		OD (mm)	ID (mm)	Density <sup>[c]</sup> (% theoretical)	Diameter (mm)	Stack Length (mm)		Fuel Centerline <sup>[e]</sup> Thermocouple	Pressure Transducer	Elongation Sensor
	AA	10.69	9.51	92.06	9.30	653	0.21	X	X	
	AB	10.64	9.52	91.50	9.30	650	0.21		X	
	AC	10.66	9.51	90.58	9.30	650	0.21		X	
	AD	10.65	9.52	95.10	9.30	663	0.21		X	
	AE	10.68	9.51	91.64	9.26	655	0.25	X	X	
	AG	10.68	9.50	94.33	9.40	663	0.10			X
Lower Cluster										
	AH	10.69	9.49	94.46	9.40	607	0.09			X
	AJ	10.67	9.50	94.43	9.35	610	0.14			X
	AK	10.66	9.51	95.94	9.31	607	0.20	X		X
	At Thermo- couple Location	10.66	9.51	96.10	9.30		0.21			
	AM	10.68	9.50	94.52	9.30	607	0.20			X
	AO	10.66	9.52	92.11	9.30	615	0.21	X		X
	At Thermo- couple Location	10.66	9.51	92.04	9.30		0.21			
	B-5	10.67	9.51	94.18	9.26	612	0.25			

[a] All cladding made of zircaloy-4.

[b] Fuel pellet length = 15.0 mm  
Dish depth = 0.33 mm  
Dish shoulder = 1.70 mm  
Dish spherical radius = 6.79 mm.

[c] The values listed here are measured geometric densities (that is, weight divided by volume). The density of a limited number of fuel samples was also measured by immersion techniques. The immersion (true) densities were found to be about 3/4% higher at all density levels.

[d] Backfill helium pressure =  $1.01 \times 10^4$  N/m<sup>2</sup>.

[e] Centerline thermocouple hole diameter = 1.73 mm.

## 2.1 Elongation Sensors

Linear variable differential transformers are used to measure the cladding elongation of six of the IFA-226 test rods. Each differential transformer (elongation sensor) consists of coaxial primary and secondary coils with a movable ferritic core in the center. The core is spring-loaded against the end of the fuel rod. Displacement of the core due to cladding axial movement influences the voltage induced in the secondary coils and provides a readable signal. A drawing of the elongation sensor used in IFA-226 is shown in Figure 4.

Five of the elongation sensors are placed on the lower cluster rods and one sensor is placed on an upper cluster rod. The elongation sensors are concentrated in the bottom cluster because the neutron flux in IFA-226 is skewed toward the bottom of the core and, therefore, the highest power and the hottest pellets are located in the lower cluster near the top of the fuel stack. As a result, the transition from free thermal expansion of the cladding-to-fuel-induced thermal expansion is more abrupt. In the top cluster, the hottest pellet in each rod is at the bottom of the fuel stack, and the transition is more gradual.

## 2.2 Pressure Transducers

Five fuel rods in the upper cluster of IFA-226 are instrumented with Halden Project internal pressure transducers. The sensing mechanism in the transducer is a thin platinum membrane which is exposed on one side to internal rod gas of unknown pressure, whereas the other side is exposed to externally-controlled helium gas pressure. The pressure balance across the membrane is indicated by the opening of an electrical circuit between the membrane and a contact normally resting against the membrane. Figure 5 presents a schematic diagram of a pressure transducer.


## 2.3 Fuel Centerline Thermocouples

Two of the IFA-226 lower cluster test rods which are instrumented with elongation sensors, and two of the upper cluster test rods which are instrumented with fission gas pressure sensors, also contain fuel centerline thermocouples. These thermocouples are composed of W/3wt% Re-W/25wt% Re with BeO insulation and molybdenum sheathing. The ends of the thermocouples in the upper cluster are located approximately 0.068 m above the bottom of the respective fuel stacks. The ends of the two thermocouples in the lower cluster are located approximately 0.246 m below the top of the respective plenums at essentially the rod axial peak power position.

## 2.4 Self-Powered Neutron Detectors

The assembly power is monitored by eight beta-current, self-powered neutron detectors. Each detector utilizes vanadium as the emitter.

Of the eight detectors, four are axially distributed within the two clusters in order to measure the axial flux distribution. Two additional detectors are mounted within each cluster to facilitate measurement of the radial flux distribution. The locations of the eight neutron detectors are shown in Figure 2.



ANC-B-4198

Fig. 4 Schematic diagram of a cladding elongation sensor.




Fig. 5 Schematic diagram of an IFA-226 pressure sensor.

ANC-B-4199

## 2.5 Additional Instrumentation

In addition to the sensors mentioned, two turbine flowmeters and four coolant thermocouples are built into the assembly. A flowmeter and two thermocouples are located at the inlet and the outlet of the coolant flow channel. These instruments are required in order to calibrate the neutron detectors using thermal-hydraulic techniques (Appendix C).

## IV. IFA-239 DESIGN

IFA-239 is a single-rod test assembly which has been used to determine the axial and diametral strains of spare IFA-226 Rod B6. A diagram of IFA-239 is presented in Figure 6. The dimensions of Test Rod B6 are listed in Table II and in Appendix A.

TABLE II  
FUEL ROD DATA FOR IFA-239

<u>Cladding [a]</u>		<u>Fuel [b]</u>			<u>Gap [d]</u>
<u>OD</u> <u>(mm)</u>	<u>ID</u> <u>(mm)</u>	<u>Density [c]</u> <u>(% theoretical)</u>	<u>Diameter</u> <u>(mm)</u>	<u>Stack Length</u> <u>(mm)</u>	<u>(mil)</u>
10.69	9.51	95.30	9.40	607	0.11

[a] Cladding made of zircaloy-4.

[b] Fuel pellet length = 15.0 mm  
Dish depth = 0.33 mm  
Dish shoulder = 1.70 mm  
Dish spherical radius = 6.79 mm.

[c] Value listed is measured geometric density (that is, weight divided by volume).

[d] Backfill helium pressure =  $1.01 \times 10^4$  N/m<sup>2</sup>.

IFA-239 is cooled by natural circulation of heavy water. When the assembly is operating at high, steady state power levels, the nominal inlet flow rate of the coolant is approximately 0.5 l/sec. The coolant pressure and saturation temperature are  $3.45 \times 10^6$  N/m<sup>2</sup> and 240°C, respectively.


### 1. INSTRUMENTATION

Experimental data have been obtained from three principal types of in-pile instrumentation: a diametral profile sensor, a cladding axial elongation sensor, and self-powered neutron detectors.

#### 1.1 Diametral Profile Sensor

The diametral profile of the B6 test rod is determined from data generated by two instruments: a diameter gauge (linear variable differential transformer) and an axial position indicator (long range linear transformer) which is attached to the diameter gauge. A schematic diagram of the diametral profile sensor is shown in Figure 7. Diagrams of the diameter gauge and the long range linear transformer are presented in Figures 8 and 9, respectively.





ANC-A-4441

Fig. 6 Diagram of Instrumented Fuel Assembly 239.





Fig. 7 Schematic diagram of the IFA-239 diametral profile sensor.



ANC-A-4576

Fig. 8 Schematic diagram of the IFA-239 diameter gauge.




Fig. 9 Schematic diagram of the IFA-239 long range linear transformer.

Diametral profile data were not obtained on a regularly scheduled basis, but rather, the data were obtained upon demand and primarily during the startup period. When data were desired, the diameter gauge was moved slowly and continuously along the length of the test rod and the measured rod diameter and the corresponding axial elevation were simultaneously recorded. The diameter gauge traveled the entire length of the test rod in about four to six minutes. This time period was small relative to changes of the assembly power level.

Whenever the diameter gauge made a full length sweep of the test rod, the diameter of three calibrated bands was also measured. The bands had been machined during assembly fabrication, onto the structure supporting the lower end of the test rod. Measurement of these bands during the experiment serves as an additional source of calibration data to assure the correct conversion of the diametral profile data to usable units.

### 1.2 Elongation Sensor

The axial elongation sensor used in IFA-239 is identical to the sensors which are used in IFA-226 and are described in Section III.

### 1.3 Self-Powered Neutron Detectors

Six self-powered neutron detectors are distributed axially and radially about the test rod. Of the six detectors, five are vanadium self-powered detectors which are identical to those used in IFA-226. The remaining neutron detector uses cobalt as the emitter. The cobalt detector did not provide reliable data after beginning-of-life operation.

### 1.4 Additional Instrumentation

An inlet turbine flowmeter and thermocouples located at the inlet and the outlet of the flow channel were used to calibrate the neutron detectors using thermal-hydraulic techniques. A description of the calibration and data reduction procedures is presented in Appendix C.

## V. DATA PRESENTATION

The experimental data that were obtained from IFA-226 and IFA-239 are presented in the following figures. These data cover the period from beginning-of-life (November 24, 1971 and March 12, 1973, respectively) through April 16, 1974.

Data from the elongation sensors, neutron detectors, and fuel centerline thermocouples were collected at regular intervals using an IBM-1800 data collection system. During steady state full power operation, these data were automatically collected every six hours. When a change of power was occurring, the data were collected as often as every 15 minutes. The pressure data from IFA-226 and the diametral profile data from IFA-239 were obtained on a demand basis. The frequency of data collection varied from a few minutes to several months.

The data points that are shown on all figures have been connected by a curve or a series of curves in order to more clearly indicate the trend of the data. When data were not available during operating periods, a curve or set of curves were drawn to represent the best estimate of the missing data.

Prior to the loading of IFA-226 and IFA-239 into the HBWR, the instrumentation in these assemblies was calibrated in order to ensure that accurate, reproducible data could be obtained. The results of the instrument calibration are presented in Appendix B.

### 1. PRESENTATION OF DATA FROM IFA-226

The data obtained from the IFA-226 instrumentation are presented in Figures 10 through 128. Processing and analysis of the elongation sensor data, fuel centerline thermocouple data, and fission gas pressure data were performed to the extent necessary to assure that the data are understandable, reasonable, and correct. However, no effort was made to correct the thermocouple readings for the effects of neutron irradiation. The neutron detector data have been interpreted and analyzed in order to provide assembly and individual rod power history and flux profile data. The method which was used to analyze the neutron detector data is presented in Appendix C.

The elongation histories of Test Rods AG, AH, AJ, AK, AM, and AO are presented in Figures 10 through 19. The fuel centerline temperature histories of Rods AA, AE, AO, and AK are shown in Figures 20 through 28. Also included in these figures is the assembly power history as determined from the neutron detector data. Since all thermocouples had failed by December 1973, no temperature data are shown for the operating period from December 1973 through April 1974.

The neutron detector data were used to determine the test pin power history. The peak power histories of the rods which are equipped with elongation sensors are presented

in Figures 29 through 40. The local power histories of Rods AA, AE, AO, and AK at the thermocouple location are given in Figure 41, which covers the period from beginning-of-life through January 1972. The average power histories of the rods equipped with pressure sensors are presented in Figures 42 through 54.

The fission gas pressure data for Rods AA, AB, AC, AD, and AE are presented in Figures 55 through 59, and also in Table III. As can be seen, additional data which were obtained after April 16, 1974, have been added to Figure 55 for completeness. In order to present the fission gas pressure history in a more meaningful manner, only the data which were obtained at high assembly power levels (between 250 and 300 kW) are shown in Figure 55. The data obtained at lower power levels have been omitted. The use of a range of assembly power values rather than a single value was necessary because fission gas pressure data were not frequently obtained at any single high power level throughout the lifetime of the assembly.

In order to increase the usefulness of the elongation sensor and fuel centerline temperature data, Figures 60 through 72 present rod elongation versus peak rod power during various time intervals. Also, Figures 73 through 95 present fuel centerline temperature versus rod power at the thermocouple location during various time intervals. The elongation sensor and fuel centerline temperature data which are shown on these graphs were obtained from the elongation and temperature history graphs (Figures 10 through 28).

The last group of graphs which have been included for IFA-226 show the axial flux profile of the assembly at various times throughout the lifetime. These profiles are presented in Figures 96 through 128. In order to determine the cluster axial flux profiles from these figures, note should be taken of the fact that the top and bottom of the lower cluster fuel are located at elevations of 42.6 and 18.6 inches, respectively. The top and bottom of the upper cluster fuel are located at elevations of 80.6 and 54.7 inches, respectively.

TABLE III

INTERNAL ROD PRESSURE FOR IFA-226  
FROM NOVEMBER 20, 1971 THROUGH AUGUST 28, 1972

	Date	Time (hr)	Moderator Temperature (°C)	Assembly Power (kW)	Internal Rod Pressure (atm-gauge)				
					AA	AB	AC	AD	AE
1971	November 20	1730	115	0	0.40	0.39	0.30	Valve Closed	0.31
	November 21	0200	150	0	0.50	0.43	0.38	Valve Closed	0.37
	November 21	1030	192	0	0.87	0.78	0.78	Valve Closed	0.75
	November 23	1300	209	0	0.92		0.81	Valve Closed	0.89
	November 23	2355	240	5	1.20	1.10	1.02	Valve Closed	1.05
	November 24	1220	240	47	1.12	1.02	0.97	Valve Closed	0.90
	November 24	1430	240	75	1.38	1.29	1.23	Valve Closed	1.03
	November 24	1715	240	115	1.22	1.14	1.04	Valve Closed	0.83
	November 24	1920	240	197	1.21	1.15	1.04	Valve Closed	0.89
	November 24	2130	240	246	1.40	1.32	1.23	Valve Closed	1.03
	November 24	2350	240	262	1.34	1.31	1.23	Valve Closed	1.10
	November 25	0250	240	256	1.47	1.43	1.32	Valve Closed	1.13
	November 25	0400	240	251	1.37	1.32	1.23	Valve Closed	1.04
	November 25	1030	240	249	1.44	1.32	1.22	Valve Closed	1.12
	November 25	1540	240	203	1.31	1.24	1.14	Valve Closed	0.97
	November 25	1715	240	181	1.37	1.35	1.33	Valve Closed	1.10
	November 25	1940	240	160	1.16	1.13	1.00	Valve Closed	0.83
	November 25	2230	240	133	1.10	1.07	0.96	Valve Closed	0.76
	November 25	2310	240	111	1.11	1.10	0.97	Valve Closed	0.76
	November 26	0330	240	85	0.93	0.92	0.76	Valve Closed	0.61
	November 26	0402	240	96	0.89	0.87	0.78	Valve Closed	0.65
	November 26	1300	240	168	0.99	0.97	0.87	Valve Closed	0.72
	November 26	2025	240	254	1.08	1.02	0.92	Valve Closed	0.81
	November 27	1140	240	76	0.84	0.82	0.71	Valve Closed	0.57
	December 1	1030	240	268	1.18	1.13	1.02	Valve Closed	0.89
	December 2	1830	240	258	1.15	1.03	0.94	Valve Closed	0.82
	December 3	1320	240	256	0.99	0.98	0.98	Valve Closed	0.73
	December 6	0015	240	168	0.92	0.87	0.71	Valve Closed	0.57
	December 6	2300	227	172	0.62	0.56	0.50	Valve Closed	0.32
	December 8	0900	240	177	0.81	0.73	0.67	Valve Closed	0.48
	December 13	1200	240	265	1.06	0.99	0.90	Valve Closed	0.70
	December 18	1300	240	258	1.21	1.03	0.99	Valve Closed	0.76
	December 20	1320	240	239	0.96	0.92	0.85	Valve Closed	0.63
	December 21	1630	222	31	0.61	0.55	0.48	Valve Closed	0.24
	December 28	2210	240	249	0.99	0.94	0.87	Valve Closed	0.62



TABLE III (contd.)

	Date	Time (hr)	Moderator Temperature (°C)	Assembly Power (kW)	Internal Rod Pressure (atm-gauge)				
					AA	AB	AC	AD	AE
1972	January 3	1240	240	246	1.00	0.98	0.89	Valve Closed	0.63
	January 8	1220	236	47	0.60	0.58	0.53	Valve Closed	0.21
	January 16	1530	240	43	0.71	0.63	0.58	Valve Closed	0.29
	January 17	1210	240	184	0.82	0.76	0.69	Valve Closed	0.42
	January 18	2130	240	262	0.99	0.95	0.87	Valve Closed	0.65
	March 19	0800	240	10	0.58	0.61	0.51	0.72	0.21
	March 19	1340	226	21	0.57	0.60	0.54	0.69	0.26
	March 19	2110	240	77	0.70	0.76	0.67	0.80	0.30
	March 20	0240	240	144	0.78	0.81	0.75	0.88	0.33
	March 20	0700	240	175	0.84	0.86	0.81	0.92	0.38
	March 21	1500	225	4	0.54	0.57	0.53	0.68	0.26
	March 22	0300	240	136	0.76	0.78	0.73	0.86	0.35
	March 22	0920	240	198	0.85	0.87	0.82	0.92	0.30
	March 22	1400	240	158	0.89	0.84	0.80	0.90	0.30
	March 22	2340	240	62	0.67	0.69	0.65	0.80	0.25
	March 23	1220	240	183	0.82	0.84	0.80	0.91	0.28
	April 15	1310	240	248	0.84	0.87	0.80	0.91	0.34
	April 24	1720	223	72	0.48	0.55	0.50	0.63	0.04
	April 25	1200	240	269	0.95	0.99	0.98	1.03	0.40
	May 2	1020	240	271	0.93	1.02	1.01	1.05	0.40
	May 11	1940	240	274	0.99	1.10	1.10	1.11	0.50
	May 19	1310	240	275	0.97	1.13	1.17	1.11	0.55
	May 21	1730	185	20	0.48	0.63	0.63	0.64	0.07
	May 22	1630	240	267	0.99	1.18	1.21	1.15	0.59
	May 28	2330	226	266	0.61	0.75	0.76	0.76	0.20
	May 30	1530	240	260	1.07	1.29	1.35	1.24	0.59
	June 25	2220	240	268	1.12	1.40	1.51	1.29	0.78
	July 8	1330	236	268	1.27	1.48	1.60	1.31	0.79
	August 7	1530	232	4	0.90	1.30	1.28	1.03	0.67
	August 16	1110	236	265	1.34	--	1.98	1.48	1.33
	August 25	1130	236	261	1.38	--	2.04	1.32	1.40
	August 26	1210	228	20	0.88	--	1.40	0.78	0.81
	August 28	0745	80	0	0.50	--	0.75	0.19	0.08







Fig. 10 Elongation history of IFA-226 test rods from November 1971 through January 1972.

ANC-D-4369







Fig. 11 Elongation history of IFA-226 test rods from March 1972 through May 1972.












Fig. 12 Elongation history of IFA-226 test rods from May 1972 through July 1972.

ANC-D-4476







ANC-D-4475

Fig. 13 Elongation history of IFA-226 test rods from July 1972 through August 1972.



ANC D 4315

Fig. 14 Elongation history of IFA-226 test rods from October 1972 through January 1973.



ANC-D-4365

Fig. 15 Elongation history of IFA-226 test rods from March 1973 through May 1973.







Fig. 16 Elongation history of IFA-226 test rods from June 1973 through July 1973.



ANC-D-4432





ANC-D-4394

Fig. 17 Elongation history of IFA-226 test rods from August 1973 through September 1973.



ANC-D-4260

Fig. 18 Elongation history of IFA-226 test rods from December 1973 through January 1974.





Fig. 19 Elongation history of IFA-226 test rods from February 1974 through April 1974.







Fig. 20 Fuel centerline temperature history of IFA-226 test rods from November 1971 through January 1972.






Fig. 21 Fuel centerline temperature history of IFA-226 test rods from March 1972 through April 1972.



ANC-D-4370

Fig. 22 Fuel centerline temperature history of IFA-226 test rods from May 1972 through June 1972.





Fig. 23 Fuel centerline temperature history of IFA-226 test rods from July 1972 through August 1972.







Fig. 24 Fuel centerline temperature history of IFA-226 test rods from October 1972 through November 1972.





ANC-D-4300

Fig. 25 Fuel centerline temperature history of IFA-226 test rods from December 1972 through January 1973.




Fig. 26 Fuel centerline temperature history of IFA-226 test rods from March 1973 through May 1973.







Fig. 27 Fuel centerline temperature history of IFA-226 test rods from June 1973 through August 1973.




Fig. 28 Fuel centerline temperature history of IFA-226 test rods from August 1973 through September 1973.





Fig. 29 Peak power history of IFA-226 test rods from November 1971 through December 1971.






Fig. 30 Peak power history of IFA-226 test rods for January 1972.



ANC-D-4326

Fig. 31 Peak power history of IFA-226 test rods from March 1972 through April 1972.





Fig. 32 Peak power history of IFA-226 test rods from May 1972 through June 1972.







Fig. 33 Peak power history of IFA-226 test rods from July 1972 through August 1972.





Fig. 34 Peak power history of IFA-226 test rods from October 1972 through November 1972.





Fig. 35 Peak power history of IFA-226 test rods from December 1972 through January 1973.











Fig. 36 Peak power history of IFA-226 test rods from March 1973 through May 1973.

ANC-D 4395



ANC D 4299

Fig. 37 Peak power history of IFA-226 test rods from June 1973 through July 1973.



ANC-D-4357

Fig. 38 Peak power history of IFA-226 test rods from August 1973 through September 1973.





Fig. 39 Peak power history of IFA-226 test rods from December 1973 through January 1974.




Fig. 40 Peak power history of IFA-226 test rods from February 1974 through April 1974.









Fig. 41 Local power history at thermocouple location of IFA-226 test rods from November 1971 through January 1972.





Fig. 42 Average power history of IFA-226 test rods from November 1971 through December 1971.





Fig. 43 Average power history of IFA-226 test rods from January 1972 through March 1972.









Fig. 44 Average power history of IFA-226 test rods from April 1972 through June 1972.

ANC-E-5584





ANC-E-5583

Fig. 45 Average power history of IFA-226 test rods from June 1972 through July 1972.





ANC-E-5586

Fig. 46 Average power history of IFA-226 test rods from August 1972 through October 1972.





ANC-E-5582  
 Fig. 47 Average power history of IFA-226 test rods from November 1972 through December 1972.





ANC-E-5585  
 Fig. 48 Average power history of IFA-226 test rods from January 1973 through March 1973.







ANC-E-5576

Fig. 49 Average power history of IFA-226 test rods from April 1973 through May 1973.



ANC-E-5578

Fig. 50 Average power history of IFA-226 test rods from June 1973 through July 1973.



ANC-E-5579

Fig. 51 Average power history of IFA-226 test rods from August 1973 through September 1973.








Fig. 52 Average power history of IFA-226 test rods from December 1973 through January 1974.

ANC-E-5588



ANC-E-5577

Fig. 53 Average power history of IFA-226 test rods from February 1974 through March 1974.



ANC-E-5580

Fig. 54 Average power history of IFA-226 test rods for April 1974.





Fig. 55 Fission gas pressure history of IFA-226 test rods at high power levels.



ANC-C-4603

Fig. 56 Fission gas pressure history of IFA-226 test rods from November 1971 through January 1972.







Fig. 57 Fission gas pressure history of IFA-226 test rods from March 1972 through April 1972.





Fig. 58 Fission gas pressure history of IFA-226 test rods from May 1972 through June 1972.





Fig. 59 Fission gas pressure history of IFA-226 test rods from July 1972 through August 1972.

73




Fig. 60 IFA-226 test rod elongation versus peak rod power from November 24, 1971 at 1000 hours through November 24, 1971 at 2300 hours.




Fig. 61 IFA-226 test rod elongation versus peak rod power from November 25, 1971 at 0000 hours through November 26, 1971 at 0200 hours.




Fig. 62 IFA-226 test rod elongation versus peak rod power from November 26, 1971 at 0300 hours through November 26, 1971 at 2200 hours.




Fig. 63 IFA-226 test rod elongation versus peak rod power from November 27, 1971 at 0000 hours through November 27, 1971 at 1300 hours.






Fig. 64 IFA-226 test rod elongation versus peak rod power from December 21, 1971 at 1700 hours through December 22, 1971 at 1000 hours.






ANC-C-4206

Fig. 65 IFA-226 test rod elongation versus peak rod power from January 16, 1972 at 1200 hours through January 18, 1972 at 0200 hours.



ANC-C-4205

Fig. 66 IFA-226 test rod elongation versus peak rod power from March 19, 1972 at 1600 hours through March 21, 1972 at 1000 hours.



ANC-C-4257

Fig. 67 IFA-226 test rod elongation versus peak rod power from March 21, 1972 at 1500 hours through March 23, 1972 at 0000 hours.





Fig. 68 IFA-226 test rod elongation versus peak rod power from May 20, 1972 at 1800 hours through May 22, 1972 at 2200 hours.



ANC C 4195

Fig. 69 IFA-226 test rod elongation versus peak rod power from August 7, 1972 at 0000 hours through August 8, 1972 at 1000 hours.




Fig. 70 IFA-226 test rod elongation versus peak rod power from December 14, 1972 at 0000 hours through December 15, 1972 at 1100 hours.





Fig. 71 IFA-226 test rod elongation versus peak rod power from March 14, 1973 at 1300 hours through March 16, 1973 at 0500 hours.



ANC-C-4193

Fig. 72 IFA-226 test rod elongation versus peak rod power from August 2, 1973 at 0900 hours through August 2, 1973 at 2000 hours.






Fig. 73 IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from November 24, 1971 at 1000 hours through November 24, 1971 at 2300 hours.




Fig. 74 IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from November 25, 1971 at 0000 hours through November 26, 1971 at 0200 hours.





Fig. 75 IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from November 26, 1971 at 0300 hours through November 26, 1971 at 2200 hours.



ANC-C-4212

Fig. 76 IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from November 27, 1971 at 0000 hours through November 27, 1971 at 1300 hours.




Fig. 77 IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from December 21, 1971 at 1700 hours through December 22, 1971 at 1000 hours.




Fig. 78 IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from January 16, 1972 at 1200 hours through January 18, 1972 at 0200 hours.





Fig. 79 IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from March 19, 1972 at 1600 hours through March 21, 1971 at 1000 hours.



ANC-C-4208

Fig. 80 IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from March 21, 1972 at 1500 hours through March 23, 1972 at 0000 hours.






Fig. 81 IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from May 20, 1972 at 1800 hours through May 22, 1972 at 2000 hours.




Fig. 82 IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from June 5, 1972 at 0600 hours through June 7, 1972 at 1800 hours.




Fig. 83 IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from August 7, 1972 at 0000 hours through August 8, 1972 at 1000 hours.




Fig. 84 IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from October 26, 1972 at 1500 hours through October 27, 1972 at 2250 hours.




Fig. 85 IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from October 27, 1972 at 2350 hours through October 29, 1972 at 1400 hours.




Fig. 86 IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from December 14, 1972 at 0000 hours through December 15, 1972 at 1100 hours.




Fig. 87 IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from January 15, 1972 at 2000 hours through January 19, 1973 at 0800 hours.

ANC-C-4221




Fig. 88 IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from March 14, 1973 at 1300 hours through March 16, 1973 at 0500 hours.






Fig. 89 IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from July 7, 1973 at 0000 hours through July 8, 1973 at 0600 hours.





Fig. 90 IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from July 12, 1973 at 0000 hours through July 13, 1973 at 0800 hours.



ANC-C-4220

Fig. 91 IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from August 2, 1973 at 0900 hours through August 2, 1973 at 2000 hours.




Fig. 92 IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from September 24, 1973 at 0000 hours through September 24, 1973 at 1900 hours.




Fig. 93 IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from September 25, 1973 at 1600 hours through September 26, 1973 at 1300 hours.




Fig. 94 IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from October 26, 1973 at 2000 hours through October 27, 1973 at 2000 hours.




Fig. 95 IFA-226 test rod fuel centerline temperature versus local rod power at thermocouple location from December 6, 1973 at 1200 hours through December 8, 1973 at 1600 hours.




Fig. 96 IFA-226 assembly axial flux profile at 1200 hours on November 24, 1971.

ANC-B-4398






Fig. 97 IFA-226 assembly axial flux profile at 0000 hours on November 25, 1971.

ANC-B-4399




Fig. 98 IFA-226 assembly axial flux profile at 2100 hours on November 25, 1971.




Fig. 99 IFA-226 assembly axial flux profile at 0400 hours on November 27, 1971.




Fig. 100 IFA-226 assembly axial flux profile at 1800 hours on November 28, 1971.




Fig. 101 IFA-226 assembly axial flux profile at 1800 hours on December 2, 1971.




Fig. 102 IFA-226 assembly axial flux profile at 1800 hours on December 8, 1971.

ANC-B-4404




Fig. 103 IFA-226 assembly axial flux profile at 1800 hours on December 12, 1971.




Fig. 104 IFA-226 assembly axial flux profile at 0000 hours on December 23, 1971.






Fig. 105 IFA-226 assembly axial flux profile at 1200 hours on March 20, 1972.




Fig. 106 IFA-226 assembly axial flux profile at 0000 hours on March 31, 1972.

ANC-B-4408




Fig. 107 IFA-226 assembly axial flux profile at 0000 hours on April 12, 1972.




Fig. 108 IFA-226 assembly axial flux profile at 0000 hours on April 23, 1972.

ANC-8-4409




Fig. 109 IFA-226 assembly axial flux profile at 0000 hours on June 2, 1972.




Fig. 110 IFA-226 assembly axial flux profile at 0000 hours on July 1, 1972.

ANC-B-4411




Fig. 111 IFA-226 assembly axial flux profile at 0000 hours on July 30, 1972.




Fig. 112 IFA-226 assembly axial flux profile at 0000 hours on August 26, 1972.






Fig. 113 IFA-226 assembly axial flux profile at 1800 hours on October 31, 1972.




Fig. 114 IFA-226 assembly axial flux profile at 0000 hours on December 23, 1972.

ANC-B-4416




Fig. 115 IFA-226 assembly axial flux profile at 0000 hours on January 17, 1973.




Fig. 116 IFA-226 assembly axial flux profile at 0000 hours on March 28, 1973.

ANC-B-4418




Fig. 117 IFA-226 assembly axial flux profile at 0000 hours on April 3, 1973.




Fig. 118 IFA-226 assembly axial flux profile at 0000 hours on May 4, 1973.




Fig. 119 IFA-226 assembly axial flux profile at 0000 hours on June 25, 1973.




Fig. 120 IFA-226 assembly axial flux profile at 1800 hours on June 30, 1973.






Fig. 121 IFA-226 assembly axial flux profile at 0000 hours on July 16, 1973.




Fig. 122 IFA-226 assembly axial flux profile at 0000 hours on August 23, 1973.

ANC-B-4424




Fig. 123 IFA-226 assembly axial flux profile at 0000 hours on December 26, 1973.




Fig. 124 IFA-226 assembly axial flux profile at 0000 hours on January 28, 1974.

ANC-B-4426




Fig. 125 IFA-226 assembly axial flux profile at 0000 hours on February 28, 1974.




Fig. 126 IFA-226 assembly axial flux profile at 1200 hours on March 1, 1974.




Fig. 127 IFA-226 assembly axial flux profile at 0600 hours on March 25, 1974.

ANC-B-4429




Fig. 128 IFA-226 assembly axial flux profile at 0000 hours on April 15, 1974.



## 2. PRESENTATION OF DATA FROM IFA-239

Data for IFA-239 are shown in Table IV and Figures 129 through 158. Figure 129 shows the distance traveled by the diameter gauge. The results of the diametral profile measurements are shown in Figures 130 through 152. A sample of the results from the autoclave calibration measurements is presented in Figures 130 and 131; the results from the in-pile measurements are given in Figures 132 through 152. Also shown in Figures 134 through 150 is the axial flux profile present at essentially the same time as when the diametral profile data were obtained. Table IV summarizes the times when the in-pile measurements were made and gives their corresponding power level.

As can be seen from Table IV, a limited quantity of diametral profile data is currently available. The data which are available were obtained during the first few days of assembly operation. The elongation and assembly power histories, however, are available for the entire period from beginning-of-life through April 16, 1974. These data are presented in Figures 153 through 158.

The assembly power histories, which are shown in Figures 153 through 158, should be used with caution. During the first month of operation, all neutron detectors were operative. Thus, the power histories which were derived from these data are considered to be quite accurate. Shortly after this time, however, several neutron detectors failed, thus resulting in a less accurate and less reliable value for the assembly power. (The method that was used to reduce neutron detector data is described in Appendix C.)

The results from the diameter gauge used in IFA-239 must be interpreted with caution. During the out-of-pile autoclave testing, the data from the zircaloy calibration rod were significantly less noisy than the data from the in-pile experiments, as shown in Figures 130 and 131, respectively. Since the cladding of the calibration rod and the fuel rod were manufactured by the same vendor, the two rods are expected to have similar surface roughness characteristics. The only observed difference between the two rods was the degree of surface oxidation. The calibration rod became heavily oxidized (that is, it became shiny blue-black) during the autoclave testing due to relatively high oxygen levels in the autoclave. In comparison, the fuel rod was operated only in the environment of the reactor coolant where the oxygen content is much less. The only observed change of the surface finish after one year of operation was a slight dulling of the previously bright zircaloy surface. As a result, the two different oxidation states resulted in a different surface sliding coefficient between the fuel rod surface and the inconel pads of the diameter head.


The data shown in Figures 132 and 133 exhibit a sawtooth pattern in the direction of travel of the diameter gauge. The sawtooth shape points toward the top of the rod in Figure 132 and toward the bottom of the rod in Figure 133 as the diameter gauge was moved up and down the rod, respectively. Due to the design of the diameter gauge, excessive friction on the fuel rod restrained the movement of the LVDT core up to the point where the spring forces allowed abrupt release and thus produced the sawtooth pattern.

TABLE IV

TIMES WHEN IN-PILE DIAMETRAL PROFILE DATA WERE OBTAINED

<u>Run</u>	<u>Date (1973)</u>	<u>Logging Start Time</u>	<u>Diameter Gauge Movement</u>	<u>Assembly Power (kW)</u>
9	March 12	1631	UP	~2
10	March 12	1645	DOWN	~2
11	March 12	2124	UP	8.6
13	March 13	0042	UP	16.8
14	March 13	0054	DOWN	17.1
15	March 13	0907	UP	16.5
16	March 13	0923	DOWN	16.4
17	March 13	1609	UP	15.7
18	March 13	1625	DOWN	15.7
19	March 14	1721	UP	~17
20	March 14	1734	DOWN	~17
21	March 14	2212	UP	22.3
22	March 14	2220	DOWN	22.1
23	March 15	0001	UP	25.8
24	March 15	0009	DOWN	25.7
25	March 15	0108	UP	25.5
26	March 15	0121	DOWN	25.4
27	March 15	1258	UP	25.5
28	March 15	1312	DOWN	25.5
29	March 16	0930	UP	~0
30	March 16	0942	DOWN	~0

This sawtooth pattern was most pronounced at low power levels early in the rod irradiation period. At high power levels of about 400 W/cm, the same pattern was not present, and the few discrete ridges probably resulted from strong pellet-cladding contact.



ANC - A - 4391

Fig. 129 Axial distance traveled by diameter gauge.




Fig. 130 Diametral profile of IFA-239 calibration rod -- Run 1.




Fig. 131 Diametral profile of IFA-239 calibration rod -- Run 2.




Fig. 132 IFA-239 diametral profile at 1631 hours on March 12, 1973.




Fig. 133 IFA-239 diametral profile at 1645 hours on March 12, 1973.




Fig. 134 IFA-239 diametral and axial flux profiles at 2124 hours on March 12, 1973.






Fig. 135 IFA-239 diametral and axial flux profile at 0042 hours on March 13, 1973.




Fig. 136 IFA-239 diametral and axial flux profiles at 0054 hours on March 13, 1973.




Fig. 137 IFA-239 diametral and axial flux profiles at 0907 hours on March 13, 1973.




Fig. 138 IFA-239 diametral and axial flux profiles at 0923 hours on March 13, 1973.




Fig. 139 IFA-239 diametral and axial flux profiles at 1609 hours on March 13, 1973.




Fig. 140 IFA-239 diametral and axial flux profiles at 1625 hours on March 13, 1973.




Fig. 141 IFA-239 diametral and axial flux profiles at 1721 hours on March 14, 1973.




Fig. 142 IFA-239 diametral and axial flux profiles at 1734 hours on March 14, 1973.






Fig. 143 IFA-239 diametral and axial flux profiles at 2212 hours on March 14, 1973.




Fig. 144 IFA-239 diametral and axial flux profiles at 2220 hours on March 14, 1973.




Fig. 145 IFA-239 diametral and axial flux profiles at 0001 hours on March 15, 1973.




Fig. 146 IFA-239 diametral and axial flux profiles at 0009 hours on March 15, 1973.




Fig. 147 IFA-239 diametral and axial flux profiles at 0108 hours on March 15, 1973.




Fig. 148 IFA-239 diametral and axial flux profiles at 0121 hours on March 15, 1973.




Fig. 149 IFA-239 diametral and axial flux profiles at 1258 hours on March 15, 1973.




Fig. 150 IFA-239 diametral and axial flux profiles at 1312 hours on March 15, 1973.






Fig. 151 IFA-239 diametral profile at 0930 hours on March 16, 1973.




Fig. 152 IFA-239 diametral profile at 0942 hours on March 16, 1973.





Fig. 153 IFA-239 elongation history from March 1973 through April 1973.





Fig. 154 IFA-239 elongation history from May 1973 through June 1973.





Fig. 155 IFA-239 elongation history from July 1973 through August 1973.





Fig. 156 IFA-239 elongation history from September 1973 through December 1973.

ANC-D-4549





Fig. 157 IFA-239 elongation history from January 1974 through February 1974.





Fig. 158 IFA-239 elongation history from March 1974 through April 1974.



### 3. OPERATIONAL STATUS OF THE INSTRUMENTATION

The operational status of the IFA-226 and IFA-239 instrumentation is summarized in Table V.

TABLE V  
OPERATIONAL STATUS OF IFA-226 AND IFA-239 INSTRUMENTATION  
AS OF APRIL 16, 1974

<u>Assembly</u>	<u>Instrument</u>	<u>Number</u>	<u>Status</u>
IFA-226	Neutron Detectors	ND-1	} Operational
		ND-2	
		ND-3	
		ND-4	
		ND-5	
		ND-6	
		ND-7	Failed March 21, 1974
		ND-8	Operational
	Fuel Center Thermocouples	TF-1	Failed December 2, 1972
		TF-2	Failed March 17, 1972
		TF-3	Failed January 16, 1972
		TF-4	Failed December 6, 1973
	Elongation Sensors	EC-1	Failed March 17, 1972
		EC-2	Failed May 4, 1972
		EC-3	} Operational
		EC-4	
		EC-5	
		EC-6	
	Fission Gas Sensors	PF-1	} Operational
PF-2			
PF-3			
PF-4			
PF-5			
IFA-239	Neutron Detectors	ND-1	Operational
		ND-2	Failed April 4, 1973
		ND-3	Failed April 11, 1973
		ND-4	} Operational
		ND-5	
		ND-6	Failed March 27, 1973
	Diametral Profile Sensor		Failed Fall 1973
Elongation Sensor	EC-1	Operational	

**APPENDIX A**

**FABRICATION REPORT**



## APPENDIX A

### FABRICATION REPORT

This appendix describes the materials and the fabrication process used for the test rods in the Halden Boiling Water Reactor assemblies IFA-226 and IFA-239.

#### 1. PELLET FABRICATION

The IFA-226 and IFA-239 fuel pellets contain approximately 90.5% depleted uranium dioxide with an initial enrichment of 0.2%  $U^{235}$  and 9.5% recycled plutonium dioxide. The recycled plutonium dioxide powder contained approximately 84.3% fissile material.

##### 1.1 Pellet Starting Materials

A description of the nuclear fuel materials used for fabricating the test rod fuel pellets is presented.

1.1.1 Plutonium Dioxide. The plutonium dioxide powder was obtained from two lots of plutonium nitrate solution: one 11.60-gram lot was generated in the New Plutonium Reactor (NPR) at Hanford, and the second 18.92-gram lot was generated in the Consumer's Power Company (CPC) Big Rock Point Reactor in Michigan. The isotopic content of each lot is shown in Table A-I. The burnup of the reprocessed fuel was estimated to be 9,000 and 7,000 MWd/tU for the CPC and NPR materials, respectively. The calculated isotopic contents associated with the estimated burnup are shown in Table A-I. The impurities which were present in each plutonium nitrate solution are listed in Table A-II.

The plutonium nitrate was chemically converted to plutonium oxide by utilizing a precipitation process. This process was applied to each lot of plutonium nitrate separately. Upon completion, the two lots were mechanically blended together.

1.1.2 Uranium Dioxide. The  $UO_2$  powder was prepared from depleted  $UF_6$  material using an ammonium diuranate process. (Basically, the uranyl fluoride was mixed with ammonium hydroxide, precipitated, and then heated in the presence of steam.) The chemical impurities which were found in the  $UO_2$  powder are listed in Table A-III. The powder particle size was about 0.55  $\mu m$  and the oxygen-to-metal ratio was 2.01.

##### 1.2 Final Pellet Fabrication

After the oxide powders were screened and mechanically mixed in the desired proportion and then ball-milled, the fuel pellets were fabricated by using a pressing and

TABLE A-I

## Pu ISOTOPIIC CONTENT AND ASSOCIATED BURNUP

CPC PLUTONIUM LOT:

<u>Isotope</u>	<u>Weight Percent Measured</u>	<u>Weight Percent Estimated for 9,000 MWd/tU</u>
Pu 238	0.43	
239 <sup>[a]</sup>	76.24	76
240	16.34	17.7
241 <sup>[a]</sup>	5.82	5.2
242	1.18	0.5

NPR PLUTONIUM LOT:

<u>Isotope</u>	<u>Weight Percent Measured</u>	<u>Weight Percent Estimated for 7,000 MWd/tU</u>
Pu 238	1.08	
239 <sup>[b]</sup>	85.83	86
240	11.53	11
241 <sup>[b]</sup>	2.31	2.6
242	0.25	~0.2

[a] Total fissile content -- 82.06 wt%.

[b] Total fissile content -- 88.14 wt%.

sintering technique. Rather high press pressure was used, based upon results which were obtained from prefabrication tests. Specifically, the pellets were pressed at about 100,000 psi and sintered for four hours at 2,800°F, six hours at 3,050°F, or sixteen hours at 3,070°F, depending on desired pellet density. The pellets were then ground to the desired dimensions and outgassed using a 10 to 20  $\mu$  vacuum at 1,000°F for one hour.

### 1.3 Chemical Analysis

The finished fuel pellets were subjected to chemical analyses in order to determine the isotopic content, the enrichment, and the chemical impurities. These results are presented in Tables A-IV, A-V, and A-VI, respectively.

TABLE A-II

## PLUTONIUM NITRATE IMPURITIES

Impurity	NPR Pu(NO <sub>3</sub> )		CPC Pu(NO <sub>3</sub> )	
	Sample 1 (ppm)	Sample 2 (ppm)	Sample 1 (ppm)	Sample 2 (ppm)
Ag	0.1	0.1	0.9	0.7
Al	10	10	25.9	22.5
As	10	10	10	10
B	0.5	0.5	1.1	0.7
Ba	10	10	5	5
Be	2	2	6	6
Bi	2	2	2	2
Ca	10	10	125	150
Cd	0.5	0.5	5	5
Co	1	1	1	1
Cr	1,667	1,667	763.7	764.6
Cu	7.2	7.2	4.9	6.1
Fe	4,900	4,900	1,778.2	1,234.8
Ge	2	2	10	10
K	4	4	10	8
Ll	5	5	5	10
Mg	28	31	14	15
Mn	140	140	58.3	73.4
Mo	5.8	6	4.1	3.7
Na	120	120	99.8	94.1
Ni	1,034	1,034	935.6	1,026.1
P	450	550	358.2	472.8
Pb	2	2	15	12.4
Sc	31	35	31	31
Sn	2	2	17.8	19.9
St	50	50	50	50
Te	10	10	10	10
Ti	5	5		
Tl	10	10	10	10
V	5	5	5	5
Sb			3	3
Zn	10	10		
C	0.2	0.2		
S	200		1,000	
Halide	200		150	
Dy			2	2
Eu			1	1
Gd			2	2
Sm			5	5
Total	9,115 ppm		4,341 ppm	

TABLE A-III

DEPLETED UO<sub>2</sub> POWDER IMPURITIES

---

<u>Impurity</u>	<u>Sample (ppm)</u>
Ag	0.1
Al	14
As	10
Au	
B	0.2
Ba	5
Be	0.1
Bi	1
Ca	25
Cd	0.85
Co	5
Cr	15
Cu	3
Fe	115
Ge	1
Hg	10
Li	50
Mg	12
Mn	5
Mo	1
Na	40
Ni	36
P	10
Pb	1
Sb	1
Si	135
Sn	1
Sr	100
Te	1
Th	100
Ti	1
Tl	1
V	2.5
W	50
Zn	3
C	123
N	23
F	12
Cl	15
Dy	0.02
Eu	0.02
Gd	0.01
Sm	0.2

---

TABLE A-IV

ISOTOPE CONTENT OF FUEL PELLETS

<u>Plutonium Isotope</u>	<u>Content (wt%)</u>	<u>Uranium Isotope</u>	<u>Content (wt%)</u>
Pu <sup>238</sup>	0.31	U <sup>234</sup>	~0.00
Pu <sup>239</sup>	79.98	U <sup>235</sup>	0.20
Pu <sup>240</sup>	14.52	U <sup>236</sup>	~0.00
Pu <sup>241</sup>	4.36	U <sup>238</sup>	99.79
Pu <sup>242</sup>	0.83		

TABLE A-V

PLUTONIUM CONTENT

<u>Blend</u>	<u>Enrichment</u>	<u>Oxygen-to-Metal Ratio</u>	<u>Test Rods</u>
1	9.27	1.970 to 1.974	AA, AB, AC, AD, AE, AG, AJ[a], AM[a], AO, B5[a]
4	9.21	1.972 to 1.987	AK, AM[a], B6
5	9.45	1.972 to 1.981	AH, AJ[a], AM[a], B5[a]

[a] Rods which contain pellets from more than one blend.

A fuel oxygen-to-metal ratio ranging from 1.970 to 1.987 was also measured (8 samples, 2 measurements each).

#### 1.4 Pellet Autoradiography and Metallography

Fuel pellet samples from each of three enrichment blends were autoradiographed using Kodak NTA film plates. Figure A-1 illustrates the plutonium particle size (actually particle agglomerate size) and dispersion for samples from Blends 1 and 4. The largest plutonium particle is noted on each autoradiograph. (Table A-V lists which test rods contain which enrichment blend.) All three blends were screened and then ball-milled for 16 hours; however, the delay time between screening and ball-milling varied somewhat from blend to blend and is noted on Figure A-1. Increased particle reagglomeration seemed to be associated with increased screening to ball-milling delay time.



TABLE A-VI

## FUEL PELLETT IMPURITIES

<u>Element</u>	<u>Impurities (ppm)</u>	<u>Element</u>	<u>Impurities (ppm)</u>
Al	170	Mg	30
B	>1	Mn	2
Bi	2	Mo	19
C	104	N	12
Ca	5	Ni	114
Cd	>1	Pb	2
Co	2	Si	208
Cr	38	Sn	12
Cu	22	Ti	250
F	5	V	5
Fe	60	Zn	102
H	2.2 <sup>[a]</sup>	Total gas	0.025 g/cm <sup>3</sup> <sup>[a]</sup>
H <sub>2</sub> O	1.6 <sup>[a]</sup>		
In	5		


[a] Measured after hot vacuum outgassing of the pellets.

Photomicrographs were also obtained from samples from each blend. Figures A-2 and A-3 illustrate the pore size and distribution at the pellet center and near the surface of Blend 5 radial and axial sections, respectively. The large porosity average diameter and the average number of large pores per square inch are noted on the figures.


## 2. CLADDING MATERIALS

The IFA-226 and IFA-239 test rod tubing was supplied by Sandvik Special Metals, Inc. Two lots of tubing were purchased. The chemical and physical data supplied by Sandvik with the first batch of material (Lot 84001) are presented in Table A-VII. The data for the second batch (Lot 74001) are presented in Table A-VIII. Photomicrographs showing the zirconium hydride orientations of Lot 84003 are shown in Figure A-4. Figure A-5 presents the photomicrographs for Lot 74001.


To check the Sandvik strength and ductility measurements, random samples from each batch were sent to Battelle Memorial Institute (BMI), Columbus, Ohio, for elevated temperature testing. The BMI tensile test results were consistently several thousand psi lower, and the elongation was several percent higher, than those reported by Sandvik Special Metals, Inc., for this same material. These results suggest a variation between the BMI and the Sandvik tubing material or in their testing temperatures. The test temperatures which were used by BMI were checked and found to be correct.



RADIAL




RADIAL



AXIAL

Blend 1 (9.5wt%)

$\Delta t$  - 7 days




AXIAL


Blend 4 (9.5wt%)

$\Delta t$  - 10 days

Fig. A-1 Fuel pellet autoradiography.



Edge




Center

Large Porosity

3.48 mils average diameter  
446 average pores per 0.1 in.<sup>2</sup>

9.5 wt% Fuel (Blend 5)

Fig. A-2 Fuel pellet metallography -- radial section.



Large Porosity

3.08 mils average diameter  
 396 average pores per 0.1 in.<sup>2</sup>

9.5 wt% Fuel (Blend 5)

Fig. A-3 Fuel pellet metallography -- axial section.

The end plug bar stock was supplied by Wah Chang Corporation and was machined in the NFS Rockville Model Shop. The chemical and physical data for the material used for the smooth end plugs and for the Halden instrument fabrication are presented in Tables A-IX and A-X, respectively. The data for the grooved end plugs are presented in Table A-XI.

TABLE A-VII

DESCRIPTION, PROPERTIES, AND TEST RESULTS  
FOR SANDVIK CLADDING -- FIRST LOT

MATERIAL

Sandvik zircaloy-4 tubing, Lot 84003 (Rods AG, AH, AJ, AM, B5, B6)

Inside Diameter =  $9.487 \pm 0.038$  mm  
 Final Annealing Temperature =  $488^{\circ}\text{C}$  for 4 hr  
 Length =  $838 \pm 1.5$  mm Diameter  
 Outside Diameter =  $10.74 \pm 0.05$  mm  
 Wall Thickness = 0.533 mm minimum

FINISHED TUBE ANALYSIS (ppm)

<u>Element</u>	<u>Sample 1</u>	<u>Sample 2</u>
H	12	11
N	34	29
O	1,100	1,140

TENSILE PROPERTIES (test temperature of  $380^{\circ}\text{C}$ )

	<u>Sample 1</u>	<u>Sample 2</u>
Ultimate Tensile Strength ( $\text{N/m}^2$ )	$4.68 \times 10^8$	$4.66 \times 10^8$
0.2% Yield Strength ( $\text{N/m}^2$ )	$3.54 \times 10^8$	$3.47 \times 10^8$
Elongation for 51 mm specimen (%)	23.4	23.4

CORROSION TEST

	<u>Sample 1</u>	<u>Sample 2</u>	<u>Sample 3</u>
Weight Gain after Three Days ( $\text{mg}/\text{dm}^2$ )	17.6	16.2	16.6
Color:	Slightly Gray		

GRAIN SIZE (recrystallization data -  $667^{\circ}\text{C}$  for 45 minutes)

	<u>Sample 1</u>	<u>Sample 2</u>
Longitudinal, ASTM Number	Not Applicable	
Transverse, ASTM Number	11.5	11.5

HYDRIDE ORIENTATION (exposed to 1 molar LiOH at  $316^{\circ}\text{C}$  for 18 hours)

	<u>Sample 1</u>	<u>Sample 2</u>
F <sub>n</sub> Number	0.03	0.04

SURFACE ROUGHNESS

	<u>Sample 1</u>	<u>Sample 2</u>
OD (mm)	0.25	0.25
ID (mm)	0.36	0.41

TABLE A-VII (contd.)

DIMENSIONS, STRAIGHTNESS, ULTRASONIC FLAW AND FREE PATH TEST

All Tubes Approved

INGOT ANALYSIS  
COMPOSITION (wt%)

	<u>Top</u>	<u>Center</u>	<u>Bottom</u>
Sn	1.54	1.48	1.37
Fe	0.22	0.22	0.20
Cr	0.11	0.12	0.11

Impurities (ppm)

Al	<25	31	33
B	0.2	<0.2	<0.2
C	120	180	170
Ca	<10	<10	<10
Cd	<0.2	<0.2	<0.2
Cl	<15	<15	<15
Co	<5	<5	<5
Cu	16	<10	17
H	5	4.8	6
Hf	55	51	51
Hg	<5	<5	<5
Mn	<10	<10	<10
N	27	26	26
Ni	24	19	16
O	1,050	1,120	1,140
Pb	<20	<20	<20
Si	47	41	43
Ti	<20	<20	<20
U	<0.5	<0.5	<0.5
W	<25	<25	<25

FORGING ULTRASONIC TEST RESULTS

Acceptable

CORROSION TEST RESULTS, RUNS 301-10 (14 days at 399°C,  $1.03 \times 10^7$  N/m<sup>2</sup>)

<u>Sample</u>	<u>Weight Gain</u> (mg/dm <sup>2</sup> )	<u>Appearance</u>
1	26	Acceptable, No Visible
2	25	Corrosion Defects

PRODUCT CHEMISTRY (ppm)

	<u>Sample 1</u>	<u>Sample 2</u>
N	42	47
H	15	18

HARDNESS (BHN)

Range	163 to 170
Average	167

TABLE A-VIII

DESCRIPTION, PROPERTIES, AND TEST RESULTS  
FOR SANDVIK CLADDING -- SECOND LOT

MATERIAL

Sandvik zircaloy-4 tubing, Lot 74001 (Rods AA, AB, AC, AD, AE, AK, AO)

Inside Diameter =  $9.49 \pm 0.038$  mm  
 Final Annealing Temperature =  $496^{\circ}\text{C}$  for 4 hr  
 Length =  $368.1 + 3.0 - 0.0$  mm  
 Outside Diameter =  $10.72 \pm 0.05$  mm  
 Wall Thickness = 0.533 minimum

FINISHED TUBE ANALYSIS (ppm)

<u>Element</u>	<u>Sample 1</u>	<u>Sample 2</u>
H	14	14
N	34	36
O	1,060	1,050

TENSILE PROPERTIES (test temperature  $371^{\circ}\text{C}$ )

	<u>Sample 1</u>	<u>Sample 2</u>
Ultimate Tensile Strength ( $\text{N/m}^2$ )	$4.29 \times 10^8$	$4.34 \times 10^8$
0.2% Yield Strength ( $\text{N/m}^2$ )	$3.20 \times 10^8$	$3.28 \times 10^8$
Elongation for 51 mm Specimen (%)	23.4	21.9

CORROSION TEST

	<u>Sample 1</u>	<u>Sample 2</u>	<u>Sample 3</u>
Weight Gain after Three Days ( $\text{mg/dm}^2$ )	14.9	13.1	15.0
Color:		Lustrous Black	

GRAIN SIZE (recrystallization data -  $677^{\circ}\text{C}$  for 45 minutes)

	<u>Sample 1</u>	<u>Sample 2</u>
Longitudinal, ASTM Number	Not Applicable	
Transverse, ASTM Number	11.5	11.5

HYDRIDE ORIENTATION (exposed to 1 molar LiOH at  $316^{\circ}\text{C}$  for 18 hours)

	<u>Sample 1</u>	<u>Sample 2</u>	<u>Sample 3</u>
$F_n$ Number	0.04	0.03	0.04

SURFACE ROUGHNESS

	<u>Range of Values</u>
OD (mm)	0.46 to 0.51
ID (mm)	0.43 to 0.46

TABLE A-VIII (contd.)

DIMENSIONS, STRAIGHTNESS, ULTRASONIC FLAW AND FREE PATH TEST

All Tubes Approved

INGOT ANALYSIS COMPOSITION (wt%)			
	<u>Top</u>	<u>Center</u>	<u>Bottom</u>
Sn	1.44	1.41	1.37
Fe	0.21	0.21	0.21
Cr	0.11	0.11	0.11
Fe+Cr	0.32	0.32	0.32
Impurities (ppm)			
Al	27	32	33
B	0.3	0.4	0.5
C	180	150	110
Cd	<0.2	<0.2	<0.2
Co	<5	<5	<5
Cu	19	22	33
Ca	<10	<10	<10
Cl	<15	<15	<15
H	3.5	3.7	6
Hf	41	41	40
Mn	18	18	16
Mg	<5	<5	<5
N	31	31	39
Ni	25	25	23
O	1,170	1,170	1,220
Pb	<20	<20	<20
Si	55	55	77
Ti	<30	<20	<20
W	<25	<25	<25
U	<0.5	<0.5	<0.5

BILLET ULTRASONIC RESULTS

Acceptable

PRODUCT CHEMISTRY (ppm)

	<u>Sample 1</u>	<u>Sample 2</u>
H	13	10
N	39	43
O	1,080	1,120


CORROSION TEST RESULTS, RUNS 353-4 (14 days at 399°C,  $1.03 \times 10^7$  N/m<sup>2</sup>)

<u>Sample</u>	<u>Weight Gain (mg/dm<sup>2</sup>)</u>	<u>Appearance</u>
1	26	Acceptable, No Visible Corrosion Defects
2	25	

HARDNESS (BHN)

Range	170 to 183
Average	178





—  
0.1 mm

Fig. A-4 Lot 84003 hydride orientation.

161




Fig. A-5 Lot 74001 hydride orientation.

TABLE A-IX

RESULTS OF PHYSICAL AND CHEMICAL  
ANALYSIS OF PLAIN END PLUG BAR STOCK

---

<u>INGOT ANALYSIS COMPOSITION (wt%)</u>		
	<u>Top</u>	<u>Bottom</u>
Sn	1.49	1.46
Fe	0.23	0.22
Cr	0.11	0.11
Fe+Cr	0.34	0.33
<u>Impurities (ppm)</u>		
Al	29	27
B	0.4	0.4
Cd	<0.2	<0.2
C	180	130
Co	<5	<5
Cu	13	13
H	1.8	7
Hf	58	60
Mn	<10	<10
Ni	54	51
N	30	31
Si	57	59
Ti	26	27
U	0.7	0.9
W	<25	<25

HEAT NUMBER 377536Q, ZIRCALOY-4

INGOT HARDNESS (BHN)

Range        163 to 174  
Average      169

INGOT ULTRASONIC TEST RESULTS

Acceptable

---

TABLE A-X

RESULTS OF CHEMICAL ANALYSIS OF  
HALDEN INSTRUMENTATION BAR STOCK

---

ZIRCONIUM INGOT  
HEAT NUMBER 360265, ZIRCALOY-4  
COMPOSITION (wt%)

---

	<u>Top</u>	<u>Bottom</u>
Sn	1.39	1.45
Fe	0.22	0.20
Cr	0.12	0.10
Zr	Balance	

Impurities (ppm)

---

Al	28	<25
B	0.2	0.2
C	130	120
Cd	<0.2	<0.2
Co	<5	<5
Cu	20	14
H	4.8	4.4
Hf	47	47
Mn	<10	<10
Ni	14	12
N	44	38
O	1,020	1,160
Si	64	48
Ti	<20	<20
U	<0.5	<0.5
W	<25	<25

PRODUCT ULTRASONICS TEST RESULTS

Acceptable

---

TABLE A-XI

RESULTS OF PHYSICAL AND CHEMICAL  
ANALYSIS OF GROOVED END PLUG BAR STOCK

---

INGOT ANALYSIS  
COMPOSITION (wt%)

	<u>Top</u>	<u>Bottom</u>
Sn	1.34	1.28
Fe	0.19	0.18
Cr	0.09	0.10
Fe+Cr	0.28	0.28

Impurities (ppm)

Al	<25	<25
B	<0.2	<0.2
Cd	<0.2	<0.2
C	90	120
Co	<5	<5
Cu	12	13
H	3.1	4.1
Hf	41	44
Mn	<10	<10
Ni	13	14
N	35	33
Si	40	44
Ti	<20	<20
U	<0.5	<0.5
W	<25	<25

HARDNESS (BHN)

Range	170 to 181
Average	176

HEAT NUMBER 379632Q, ZIRCALOY-4

INGOT ULTRASONIC TEST RESULTS

Acceptable

---

### 3. ROD FABRICATION

After the necessary cleaning of the tubing and end plugs had been completed, the test pins were assembled as follows:

- (1) The bottom end plug was welded to the tubing (tungsten inert gas welding was used)
- (2) The tube was loaded with fuel pellets
- (3) The plenum spring was inserted
- (4) The loaded tube was placed in the weld chamber and backfilled with helium at one atmosphere
- (5) The top end plug was welded into place (with the exception of Rods AB, AC, AD, AK, and AO, which had mechanical end plugs on one end and Rods AA and AE which had mechanical end plugs at both ends. These rods were later sealed and welded shut at the Halden project.)

At the start and finish of each welding cycle, a small weld sample was prepared for each type of end plug design. Each sample was X-rayed, cut lengthwise, examined metallographically, and corrosion tested. The results of the metallographic examinations showed that no cracks or porosity were present in the region of the end plug welds. The highest measured local wall reduction was 14%, but the average value was only 4%. Figure A-6 presents two typical photomicrographs of the sample weld region.

Welded and cleaned samples from Lots 1 and 2 were corrosion tested at Battelle Memorial Institute, Columbus, Ohio. The weight gain after 3 days in 750°F, 1,500-psi steam varied from 13.2 to 17.2 mg/dm<sup>2</sup> and fell within the range often reported for good quality zircaloy-4. The tubing appeared slightly grey, the end caps were lustrous black and an intermittent white oxide band was observed at the weld-tubing fusion line after the corrosion test. The intermittent oxide band was found to be the result of superficial contamination on the surface.

The end plug welds were also examined radiographically. Several defective welds appeared, most of which were due to an undercut of the inside diameter. Those welds which exhibited full wall thickness with no evidence of porosity as shown on the radiograph were considered to be satisfactory. Only one rod showed porosity (Rod AM), and was subsequently repaired by welding. All the rods were pickled just before shipment to Halden (approximately 0.003 in. of material was removed).

During the fabrication process, several diameter and density measurements were made of the finished pellets and zircaloy tubing. The results of these measurements are presented in Tables A-XII and A-XIII. The axial profiles of the pellet diameter and the cladding inside diameter were determined for selected rods and are presented in Figures A-6 through A-12.





Fig. A-6 Typical weld metallography of cladding.

Assembly	Rod	DENSITY (% Theoretical) <sup>[a]</sup>			DIAMETER (mm)			Stack Length (mm)	Stack Weight <sup>[d]</sup> (g)	Total Fissile Plutonium Content (g)	Fuel Centerline Thermocouple Length (mm) <sup>[e]</sup>
		Mean Value	Maximum Observed Deviation (% of mean value)	95% of Loaded Population <sup>[b]</sup>	Mean Value	Maximum Observed Deviation from Mean Value	95% of Loaded Population <sup>[c]</sup>				
IFA-226	AA	92.06	+ 1.42	91.22 to 93.10	9.304	+ 0.018	9.291 to 9.322	653.0	437	29.75	68
	AB	91.50	+ 0.85	91.04 to 92.20	9.301	+ 0.014	9.294 to 9.317	650.6	434	29.56	--
	AC	90.58	+ 1.33	89.41 to 91.28	9.300	+ 0.033	9.268 to 9.317	650.7	430	29.28	--
	AD	95.10	+ 0.87	94.04 to 95.63	9.304	+ 0.033	9.294 to 9.314	662.9	463	31.53	--
	AE	91.64	+ 1.55	90.79 to 92.83	9.258	+ 0.020	9.233 to 9.266	656.1	439	29.88	68
	AG	94.33	+ 0.90	93.69 to 94.90	9.400	+ 0.010	9.355 to 9.411	662.7	465	31.51	--
	AH	94.46	+ 0.72	93.93 to 94.87	9.400	+ 0.010	9.393 to 9.406	606.6	434	29.39	--
	AJ	94.43	+ 0.86	93.98 to 94.88	9.355	+ 0.014	9.345 to 9.365	608.3	428	29.55	--
	AK	95.99	+ 0.40	95.85 to 96.18	9.312	+ 0.009	9.307 to 9.319	607.1	429	29.01	68
	AM	94.52	+ 1.05	93.88 to 95.17	9.304	+ 0.015	9.294 to 9.312	606.0	422	29.12	--
	A0	92.11	+ 1.31	91.28 to 92.80	9.304	+ 0.019	9.294 to 9.314	613.9	418	28.29	68
IFA-239	B-5	94.18	+ 1.11	93.16 to 94.91	9.258	+ 0.019	9.248 to 9.268	612.1	418	28.84	--
	B-6	95.30	+ 0.74	94.1 to 95.62	9.400	+ 0.028	9.385 to 9.416	606.6	441	29.04	--

[a] Geometric pellet density measurements are as follows: Immersion pellet density measurements were also performed on the following samples: 18 equals 92% dense pellets, 21 equals 94% dense pellets, and 34 equals 96% dense pellets. A statistical evaluation of the difference between the two methods showed immersion density to be  $0.75 \pm 0.17\%$  higher regardless of the nominal density.

[b] 95% of the pellets loaded into the rod had a density value within the given range.

[c] 95% of the pellets loaded into the rod had a diameter within the given range.

[d] The dish depth and diameter of 20 pellets were measured. The results indicated a void correction of  $1.46 \pm 0.06\%$  of the cylindrical pellet volume (or weight).

[e] Length of the thermocouple within the fuel stack. In Rods AK and A0 the total thermocouple length is about 252 mm and the length of the thermocouple in the stack and plenum is 246 mm.



TABLE A-XIII

TUBE AND PLENUM DATA

Assembly	Rod	TUBE DATA <sup>[a]</sup> (mm)					Ovality	Maximum Observed Deviation from Ovality Value	Plenum <sup>[b]</sup> Length (mm)	Tubing Lot No.
		Mean OD	Maximum Observed Deviation from Mean OD	Mean ID	Maximum Observed Deviation from Mean ID					
IFA-226	AA	10.69	+ 0.002	9.510	+ 0.0046	0.0020	+ 0.0046	135	74001	
	AB	10.65	+ 0.025	9.515	+ 0.0070	0.0020	+ 0.0089	131	74001	
	AC	10.66	+ 0.016	9.507	+ 0.0069	0.0018	+ 0.0064	134	74001	
	AD	10.64	+ 0.037	9.515	+ 0.0060	0.0008	+ 0.0046	121	74001	
	AE	10.68	+ 0.025	9.515	+ 0.0076	0.0010	+ 0.0041	126	74001	
	AG	10.68	+ 0.016	9.500	+ 0.0058	0.0025	+ 0.0041	125	84003	
	AH	10.69	+ 0.008	9.492	+ 0.0050	0.0025	+ 0.0051	177	84003	
	AJ	10.67	+ 0.000	9.495	+ 0.0050	0.0025	+ 0.0051	177	84003	
	AK	10.67	+ 0.041	9.512	+ 0.0038	0.0025	+ 0.0051	178	74001	
	AM	10.68	+ 0.073	9.502	+ 0.0043	0.0025	+ 0.0051	180	84003	
	AO	10.66	+ 0.008	9.515	+ 0.0036	0.0012	+ 0.0036	172	74001	
	B-5	10.67	+ 0.081	9.510	+ 0.0076	0.0012	+ 0.0102	174	84003	
IFA-239	B-6	10.69	+ 0.010	9.507	+ 0.0046	0.0008	+ 0.0076	183	84003	

[a] All tubing was made of zircaloy-4.

[b] Plenum spring OD = 9.35 mm  
 Plenum spring wire diameter = 1.30 mm  
 Each plenum spring had 20 turns.




Fig. A-7 Dimensional profile of Rod AG.





Fig. A-8 Dimensional profile of Rod AH.



ANC-A-6025

Fig. A-9 Dimensional profile of Rod AJ.




Fig. A-10 Dimensional profile of Rod AK.





Fig. A-11 Dimensional profile of Rod AM.



ANC-A-6021

Fig. A-12 Dimensional profile of Rod A0.

#### 4. INSTRUMENTATION INSERTION

After the test rods had been successfully fabricated and tested, the rods were shipped to the Halden reactor project. The fuel centerline thermocouple and pressure sensor instrumentation were then added to the appropriate rods by the OECD Halden reactor project staff. The end plugs were welded into place, examined radiographically and metallographically, and subjected to a steam corrosion test. Upon successful completion of these tests, the test rods were deemed acceptable and were subsequently mounted in the test assembly. Table A-XIV presents pertinent data describing the finished assembly.

TABLE A-XIV  
FINISHED ASSEMBLY DATA

	<u>IFA-226</u>	<u>IFA-239</u>
Number of Clusters	2	1
Number of Rods per Cluster	6	1
Pitch Distance (mm)	46	--
Shroud Material	Aluminum	Stainless Steel
Shroud ID (mm)	71	71





**APPENDIX B**

**CALIBRATION RESULTS**



## APPENDIX B

### CALIBRATION RESULTS

This appendix briefly describes the calibration procedure for the various instruments in the IFA-226 and IFA-239 test assemblies and presents the calibration constants for those instruments.

#### 1. CLADDING ELONGATION SENSOR CALIBRATION

The elongation sensors (differential transformers) were calibrated prior to installation in the test assembly. These preinstallation tests were conducted in order to determine the sensitivity characteristics (mV output versus elongation in mm) of each sensor. The measured values were obtained at room temperature and at 240°C in air. The values at 240°C are used for signal conversion when the cladding elongation is reported in millimeters.

The results of the preinstallation tests of the IFA-226 sensors at 240°C are shown in Figures B-1 through B-6. The results at 240°C for the IFA-239 sensor were not available for this report. However, some data which were obtained at room temperature are presented in Figure B-7.

#### 2. FUEL CENTERLINE THERMOCOUPLE CALIBRATION

No direct calibration of fuel centerline thermocouples was made. But an indication of the accuracy can be determined from the data at very low reactor power where the temperature difference between the fuel center and the moderator is small. At these powers and temperatures, the output from all thermocouples is nearly identical at beginning-of-life, about 25°C above moderator temperature, and no major discrepancies are observed. The difference between the measured temperature and the moderator temperature reduces to about 20°C at about 160°C moderator temperature. Also, the fuel centerline temperature versus power curves extrapolate to about the coolant saturation temperature (240°C). This is true not only at beginning-of-life, but also throughout the lifetime of the thermocouples.

After the reactor had been shut down for 1.5 hours following a period of high power operation (at beginning-of-life), and thermal equilibrium had been reached between the fuel and the moderator, the thermocouples indicated nearly identical temperatures with respect to each other and to the moderator temperature. The conclusion can, therefore, be reached from these results that the fuel centerline thermocouples were performing reasonably well.




Fig. B-1 Calibration curve at 240°C for the elongation sensor on IFA-226 Test Rod AG.




Fig. B-2 Calibration curve at 240°C for the elongation sensor on IFA-226 Test Rod AH.




Fig. B-3 Calibration curve at 240°C for the elongation sensor on IFA-226 Test Rod AJ.




Fig. B-4 Calibration curve at 240°C for the elongation sensor on IFA-226 Test Rod AK.






Fig. B-5 Calibration curve at 240°C for the elongation sensor on IFA-226 Test Rod AM.




Fig. B-6 Calibration curve at 240°C for the elongation sensor on IFA-226 Test Rod A0.




Fig. B-7 Calibration curve at 240°C for the elongation sensor on IFA-226 Test Rod B-6.

A wiring diagram of the fuel centerline thermocouple configuration is presented in Figure B-8.




Fig. B-8 Wiring diagram of a fuel centerline thermocouple.

### 3. TURBINE FLOWMETER CALIBRATION

The inlet and outlet turbine flowmeters for IFA-226 and the inlet turbine flowmeter for IFA-239 were calibrated prior to installation into their respective assemblies. This calibration was accomplished by utilizing the output from a digital clock and a pulse counter connected to each flowmeter. When a prescribed quantity of water had flowed through the assembly equal to the tare weight on the scale holding the collection tank, the counter and clock were stopped and the turbine flowmeter pulse rate was determined.

At least two measurements were made at each water quantity with the calibration valve in the natural circulation position, and at least two measurements with the valve in the forced circulation position. The repeatability of the pulse count versus water quantity was very good, less than 1% difference between all measurements of a particular water quantity. In Figure B-9, the individual flowmeter signals converted to pulses/l are plotted versus l/sec for IFA-226.

The data shown in Figure B-9 for the outlet turbine flowmeter indicated no major performance difference between the natural and forced circulation operations. This lack of difference in performance is to be expected because any entrance effects caused by the position of the calibration valve should not be detectable at the location of the outlet turbine flowmeter. The data for the inlet turbine do indicate a difference between natural and forced circulation operations. The spread in the data at high flow rates ( $> 1.5$  l/sec) is less than 1%. Since the typical inlet velocity of IFA-226 is about 2 l/sec, the spread in the calibration data at this velocity was about 0.5%, which was assumed negligible.

The calibration data for the turbine flowmeter in IFA-239 also indicated the same degree of repeatability of the pulse count versus water quantity. This repeatability was observed when operation was in either the natural or forced circulation mode.




Fig. B-9 Calibration curves for the IFA-226 inlet and outlet flowmeters.

During the startup period, an intercalibration of the inlet and outlet turbine flowmeters in IFA-226 was performed while the assembly was operating in the forced circulation mode. This intercalibration suggested that an entrance length effect occurred during operation of the inlet turbine flowmeter in forced circulation. Due to these entrance effects, the inlet turbine flowmeter indicated a 2% higher flow than the outlet turbine flowmeter.

#### 4. FISSION GAS PRESSURE TRANSDUCER CALIBRATION

The Halden pressure transducers used in the IFA-226 assembly were calibrated individually out-of-pile prior to installation (welding) onto the test rods. As stated in Section III, the basic sensing mechanism in the transducer is a thin membrane which is, on one side, exposed to fission and fill gas of unknown pressure, and the other side is exposed to externally controlled helium gas pressure. The pressure balance across the membrane is indicated by the opening and closing of a circuit which is formed between the membrane and a contact normally resting against the membrane.

The switch point sensitivity of each transducer was measured as a function of temperature and pressure. These data are presented in Figures B-10 through B-14. The transducers exhibited very good switch point constancy over wide ranges of pressures and temperatures. The single exception was Transducer PF5 (Rod AE). The calibration performance by Transducer PF5 was not good, but the in-pile performance appears to be acceptable.





Fig. B-10 Switch point consistency of the pressure transducer in Rod AA.





Fig. B-11 Switch point consistency of the pressure transducer in Rod AB.







Fig. B-12 Switch point consistency of the pressure transducer in Rod AC.





Fig. B-13 Switch point consistency of the pressure transducer in Rod AD.





Fig. B-14 Switch point consistency of the pressure transducer in Rod AE.

## 5. NEUTRON DETECTOR CHARACTERISTICS

The vanadium neutron detectors in IFA-226 and IFA-239 are 10 cm in length by 2 mm in diameter. They were purchased from AB Atomenergi of Sweden.

The characteristics of the neutron detectors are presented in Table B-I. These results indicate a small difference in detector sensitivities to presumably the same neutron flux, although the absolute flux value was known only to within  $\pm 2\%$ . (The measurements were obtained in the R2 reactor at Studsvik.) The range of emitter current about the average is  $-1.7\%$  to  $2.9\%$ , based on corrections for the different gamma compensation-current value of each detector.

The normalization factors in the last column of Table B-I were used in the calibration computer code to modify the signals from the neutron detectors so that all signals were relative to the same detector sensitivity.

The calibration data for the neutron detectors in IFA-239 are not available. Since the in-pile performance of these detectors was very predictable and consistent, no reason exists to believe that these detectors were not operating as desired.

TABLE B-I

## IFA-226 NEUTRON DETECTOR CHARACTERISTICS

Detector	Emitter Weight (g)	$\frac{W_e}{W_{e\text{ avg}}}$ [a]	Emitter Current (nA)	$\frac{I_e}{I_{e\text{ avg}}}$	Gamma Compensation Current (pA)	$I_e - I_c$ (nA)	$\frac{I_e - I_c}{(I_e - I_c)_{\text{avg}}}$
ND 1	1.8468	0.9923	53.0	1.025	6.2	52.38	1.021
ND 2	1.8970	1.0094	50.9	0.985	4.5	50.45	0.983
ND 3	1.8705	0.9953	52.2	1.010	3.9	51.81	1.010
ND 4	1.8790	0.9998	50.9	0.985	4.5	50.45	0.983
ND 5	1.8985	1.0102	50.9	0.985	4.3	50.47	0.984
ND 6	1.8741	0.9972	53.0	1.025	2.2	52.78	1.029
ND 7	1.8562	0.9881	51.0	0.986	3.5	50.65	0.987
ND 8	1.8940	1.0078	51.8	1.002	3.4	51.46	1.003
Average	1.8792	--	51.7	--	4.06	51.31	--

Note: Thermal neutron flux  $1.1 \times 10^{11}$  n/cm<sup>2</sup>-sec (+2%)

[a]  $W_e$  = emitter weight

$I_e$  = emitter electrical current

$I_c$  = compensation for gamma-induced electrical current.

## 6. DIAMETRAL PROFILE CALIBRATION (IFA-239)

Two components which were used to determine the diametral profiles required pretest calibration: the diameter gauge transformer (which was used to measure test pin diameter) and the long range transformer [which was used to indicate the axial position (elevation) of the diameter gauge].

The results of the diameter gauge calibration are shown in Figure B-15. The setpoint of the diameter gauge was adjusted in order to use the portion of the curve between 0.375 and 0.720 mm, which appeared to be nearly linear. This assumption of curve linearity is accurate to within  $\pm 3 \mu\text{m}$ .

The results of the long range transformer calibration are presented in Figure B-16. Except for a short distance near both ends of the coil, the output is linear with respect to transformer core position.




Fig. B-15 Calibration curve for the diameter gauge transformer.




Fig. B-16 Calibration curve for the long range linear transformer.





**APPENDIX C**

**DATA REDUCTION TECHNIQUES**



4

5

6

7

8



## APPENDIX C

### DATA REDUCTION TECHNIQUES

The neutron detector data which were obtained from both assemblies were interpreted and analyzed in order to obtain more meaningful power history information. A different procedure was used for each assembly.

#### 1. IFA-226 NEUTRON DETECTOR DATA

A FORTRAN computer program was developed and used to determine the power of the IFA-226 test assembly and the individual test rods within that assembly. The assembly power was determined by utilizing the signals from the neutron detectors which were axially and radially positioned throughout the assembly. First, an axial flux profile was fit to the detector signals. Since only four axial locations are occupied by the neutron detectors, a single value was used for each of the four locations. At the two axial locations where more than one detector was located, an average value of all signals at that location was used to represent the local value. The axial flux profile was then represented by a Fourier sine series expressed as

$$\phi(x) = \sum_{n=1}^4 B_n \sin\left(\frac{n\pi x}{L}\right)$$

where

L = effective length of core; that is, length at which the flux extrapolates to zero

x = location for evaluation of the flux

B<sub>n</sub> = Fourier coefficients.

The Fourier coefficients were solved by the simultaneous solution of

$$\begin{array}{l} \text{ND}(x_1) = \sum_{n=1}^4 B_n \sin\left(\frac{n\pi x_1}{L}\right) \\ \vdots \\ \text{ND}(x_4) = \sum_{n=1}^4 B_n \sin\left(\frac{n\pi x_4}{L}\right) \end{array}$$

where  $ND(x_1)$  and  $ND(x_4)$  were the detector signals at the  $x_1$  and  $x_4$  axial locations, respectively. Since all of the unknown parameters (the Fourier coefficients) have been obtained,  $\phi(x)$  can be evaluated at any  $x$ .

Through use of the axial flux profile determined, the code then calculated the power of the test assembly. This power was determined by first integrating the total area above each cluster and then by multiplying this integrated area by a constant of proportionality, or:

$$\text{Power} = k \int_{x_1}^{x_2} \phi(x) dx + k \int_{x_3}^{x_4} \phi(x) dx$$

where

- $x_1$  to  $x_2$  = active length of fuel in one cluster
- $x_3$  to  $x_4$  = active length of fuel in other cluster
- $k$  = constant of proportionality. The value of  $k$  was determined by integrating the area under the axial flux profile curve determined from the neutron detectors' signals and comparing this area with the assembly power as determined from the thermal-hydraulic (flow rate and differential temperature) measurements. The  $k$  value was equal to 4.40 kW/nA.

The peak and the average powers of an individual rod within a cluster were determined in a similar manner. First, the average cluster power was calculated by the equation,

$$\bar{P}_{\text{cluster}} = k \frac{\int_{x_1}^{x_2} \phi(x) dx}{x_2 - x_1} .$$

A radial peaking factor was then determined for each rod, one cluster of rods at a time. A plane was determined first for the lower cluster from the output of the three radially distributed neutron flux detectors within the cluster. The flux value at each rod position was normalized to the midpoint of the plane. The same procedure was repeated to determine the radial peaking factors for the upper cluster rods.

The average rod power was then calculated by the expression

$$P_{\text{avg rod}} = \frac{\bar{P}_{\text{cluster}} f_{\text{rp}}}{N}$$

where

- $P_{\text{avg rod}}$  = average rod power
- $f_{\text{rp}}$  = radial peaking factor of that rod
- $N$  = number of rods within the cluster.

The peak rod power was determined by multiplying the average rod power by the cluster axial peaking factor which was obtained from the previously determined axial flux profile.

## 2. IFA-239 NEUTRON DETECTOR DATA

The power of the IFA-239 test assembly was determined by averaging the signals from the neutron detectors which were positioned at three different axial locations. This average value was multiplied by a calibration constant to convert the neutron detector signal directly to assembly power in kW. The calibration constant was determined by comparing the average of the neutron detector signals with the assembly power as calculated from the thermal-hydraulic (flow rate and differential temperature) measurements. A value of 0.201 kW/nA was determined from the data which were obtained during the first two weeks of assembly operation at beginning-of-life operation.

When a detector failure occurred, the power was thereafter determined from the data of the remaining operative detectors. The value of the calibration constant was recalculated from the beginning-of-life data, excluding the data from the detector which failed. The integrity of the assembly power value obviously decreases as more detectors become inoperative.