The University of
Nottingham

UNITED KINGDOM · CHINA · MALAYSIA

Jadoon, Khalid A. and Ratcliffe, Stuart H. and Barrett, David A. and Thomas, E. Louise and Stott, Colin and Bell, Jimmy D. and O'Sullivan, Saoirse and Tan, Garry D. (2016) Efficacy and safety of Cannabidiol and Tetrahydrocannabivarin on glycemic and lipid parameters in patients with Type 2 diabetes: a randomized, double-blind, placebo-controlled, parallel group pilot study. Diabetes Care, 39 (10). pp. 1777-1786. ISSN 1935-5548

Access from the University of Nottingham repository:
http://eprints.nottingham.ac.uk/37816/1/submitted%2013%207%202016%20%28002%29.pdf

Efficacy and safety of Cannabidiol and Tetrahydrocannabivarin on glycaemic and lipid parameters in patients with Type 2 diabetes: a randomised, double blind, placebo-controlled, parallel group pilot study

SCHOLARONE™
Manuscripts

Efficacy and safety of Cannabidiol and Tetrahydrocannabivarin on glycaemic and lipid parameters in patients with Type 2 diabetes: a randomised, double-blind, placebo-controlled, parallel group pilot study

KA Jadoon[1], SH Ratcliffe[2], DA Barrett[3], EL Thomas[4], C Stott[6], JD Bell[4],

SE O'Sullivan[1*] and GD Tan[5*]

[1] Division of Medical Sciences & Graduate Entry Medicine, School of Medicine, University of Nottingham, Royal Derby Hospital Centre, Uttoxeter Road, Derby DE22 3DT, 01332724701.
[2] CogMaze Ltd, London SW5 9SX
[3] Centre for Analytical Bioscience, School of Pharmacy, University of Nottingham, Nottingham NG7 2RD
[4] Research Centre for Optimal Health, Department of Life Sciences, University of Westminster, London, W1W 6UW.
[5] The NIHR Oxford Biomedical Research Centre, Oxford Centre for Diabetes, Endocrinology & Metabolism, Churchill Hospital, Oxford University Hospitals NHS Trust, Oxford OX3 7LE
[6] GW Pharmaceuticals, Sovereign House, Vision Park, Histon, Cambridge CB24 9BZ

*These authors contributed equally to this paper

Corresponding author: saoirse.osullivan@nottingham.ac.uk

Trial Registration (ClinicalTrials.gov): NCT01217112

Keywords: Cannabinoid, cannabidiol, delta-9-tetrahydrocannabivarin, type 2 diabetes, dyslipidaemia, phytocannabinoid, adipokine, oral glucose tolerance

Short title: CBD and THCV in humans with type 2 diabetes

1

Abstract

Objective   Cannabidiol (CBD) and delta-9-tetrahydrocannabivarin (THCV) are non-psychoactive phytocannabinoids affecting lipid and glucose metabolism in animal models. This study set out to examine the effects of these compounds in patients with type 2 diabetes.

Research Design and Methods In this randomised, double-blind, placebo-controlled study, 62 subjects with non-insulin treated type 2 diabetes were randomised to five treatment arms; CBD (100 mg twice daily), THCV (5 mg twice daily), 1:1 ratio of CBD and THCV (5 mg:5 mg, twice daily), 20:1 ratio of CBD and THCV (100 mg:5 mg, twice daily), or matched placebo, for 13 weeks. The primary endpoint was a change in HDL-cholesterol concentrations from baseline. Secondary/tertiary endpoints included changes in glycaemic control, lipid profile, insulin sensitivity, body weight, liver triglyceride content, adipose tissue distribution, appetite, markers of inflammation, markers of vascular function, gut hormones, circulating endocannabinoids and adipokine concentrations. Safety and tolerability endpoints were also evaluated.

Results   Compared with placebo, THCV significantly decreased fasting plasma glucose (estimated treatment difference (ETD)=-1.2mmol/L, $P<0.05$) and improved pancreatic β-cell function (homeostasis model assessment (HOMA2 B) (ETD=-44.51 points, $P<0.01$), adiponectin (ETD=-5.9 x 10^6pg/mL, $P<0.01$) and apolipoprotein A (apoA) (ETD=-6.02μmol/L, $P<0.05$), although plasma HDL was unaffected. Compared to baseline (but not placebo), CBD decreased resistin (-898 pg/ml, $P<0.05$) and increased glucose-dependent insulinotropic peptide (21.9 pg/ml, $P<0.05$). None of the combination treatments had a significant impact on endpoints. CBD and THCV were well tolerated.

2

Conclusions   THCV could represent a new therapeutic agent in glycaemic

control in subjects with type 2 diabetes.

3

The endocannabinoid system (ECS) modulates food intake and energy homeostasis (1, 2) and chronic over-activation of the ECS has been identified in obesity and type 2 diabetes (3). The ECS exerts some of its actions by various components activating cannabinoid receptors 1 (CB_1) and 2 (CB_2). Modulation of CB_1 receptors with rimonabant (a synthetic cannabinoid) led to a significant reduction in body weight, waist circumference and triglyceride (TG) concentrations, and an increase in HDL-cholesterol and adiponectin concentrations (4), as well as a reduction in HbA1c in subjects with type 2 diabetes (- 0.8% to – 1.25%, $P<0.001$). However, marketing authorisation for rimonabant was withdrawn in 2008 because of an increased incidence of psychiatric adverse events (AEs) (5). Rimonabant is thought to be a CB_1 receptor antagonist/inverse agonist, but it is unclear whether modulation of other cannabinoid receptor activity could have beneficial metabolic effects without significant psychiatric effects.

Cannabidiol (CBD) is one of the major phytocannabinoids obtained from the *Cannabis sativa L.* plant. In rodent studies, CBD has multiple desirable effects in the context of hyperglycaemia, mainly through its anti-inflammatory and anti-oxidant properties (6-10). In animal models of obesity (*ob/ob* genetically obese mice), four weeks treatment with CBD 3mg/kg, produced a 55% increase in HDL-C concentration and reduced total cholesterol (total-C) by more than 25% (GW Pharma data on file). In addition, the same dose reduced liver triglycerides and increased both liver glycogen and adiponectin concentration. There is also evidence from animal studies showing that CBD modulates cardiovascular response to stress (11).

Unlike the related molecule Δ^9-tetrahydrocannabinol (THC), CBD does not activate CB_1 receptors in the brain and therefore lacks the psychotropic actions of THC. Indeed, CBD may reduce psychosis (12) and mitigate the psychoses associated with

cannabis misuse (13). Other receptor sites implicated in the actions of CBD include the orphan G-protein coupled receptor-55 (GPR55), the putative endothelial cannabinoid receptor (CB_e), the transient receptor potential vanilloid 1 (TRPV1) receptor, α1-adrenoceptors, μ opioid receptors, the adenosine transporter and serotonin-1A ($5\text{-}HT_{1A}$) receptors (14). CBD also activates and has physiological responses mediated by peroxisome proliferator activated receptor γ (PPARγ) (15,16, 17). A CBD/THC combination (Sativex®/Nabiximols) is currently licensed in most EU countries and in Canada, New Zealand, Australia, Malaysia, the United Arab Emirates and Kuwait, for the symptomatic treatment of spasticity in moderate to severe multiple sclerosis, and CBD alone (Epidiolex®) was granted orphan drug designation by the FDA in February 2014 in Dravet and Lennox-Gastaut syndromes in children, with Phase 3 clinical trials ongoing in those conditions.

Δ^9-tetrahydrocannabivarin (THCV) is a naturally occurring analogue of THC, but with different pharmacological effects. It is has been reported to behave as both a CB_1/CB_2 agonist and/or a CB_1/CB_2 neutral antagonist (20, 21, 22, 23,24), probably dose-dependent, with agonism observed at high doses and antagonism at low doses (21). However, there is little evidence of CB_1 agonsim *in vivo* compared with the observed *in vivo* effects of THC at similar doses. Other target sites of action include GPR55 (25) and transient receptor potential channels (26, 27).

Acute intraperitoneal administration of THCV in rodents at 3, 10 and 30 mg/kg body weight, caused hypophagia and weight loss, with food intake and body weight returning to normal on day 2 (18). The effect was similar to that of a CB_1 antagonist AM251, also used in the same study. In another study, involving diet-induced obese (DIO) mice, oral THCV (2.5 to 12.5 mg/kg) reduced body fat content, increased energy expenditure, and reduced fasting insulin and 30 min insulin response to oral

glucose tolerance test (OGTT) (19). In the same study, in genetically obese *(ob/ob)* mice, a similar increase in 24-hour energy expenditure was observed with 3mg/kg THCV, while 12.5 mg/kg THCV caused a significant reduction in liver triglycerides (19). In genetically obese mice (*ob/ob*), a 1:1 ratio of a combination of THCV and CBD (3 mg/kg:3 mg/kg) reduced total cholesterol levels by 19% and increased HDL-C by 50%. The same combination reduced liver TG, increased liver glycogen levels, reduced fasting insulin and increased energy expenditure (GW Pharma data on file).

The findings from these preclinical studies demonstrate a potential beneficial effect of both CBD and THCV, alone or in combination, in diabetes and lipid metabolism, with very distinct pharmacological profiles, and therefore different side effects, to rimonabant. This prompted the first ever investigation of the effects of CBD and THCV on dyslipidaemia and glycaemic control in subjects with type 2 diabetes.

Research Design and Methods

Subjects and study design

This randomised, double-blind, placebo-controlled, parallel-group, phase 2a proof-of-concept study was conducted at four United Kingdom centres. The protocol was reviewed and approved by the East Midlands - Leicester Multi Centre Research Ethics Committee (10/H0406/42) and local R&D departments as required, and was conducted in accordance with the Declaration of Helsinki. All subjects provided written informed consent.

Subjects aged 18 years or above with type 2 diabetes and HbA1c ≤10% (86 mmol/mol), HDL-C ≤1.3mmol/L in females and ≤1.2mmol/L in males, and plasma triglycerides ≤10mmol/L, were eligible. Subjects needed to either receive no oral hypoglycaemic agents or take stable doses of pre-specified non-insulin glucose lowering therapies (metformin, sulfonylurea, dipeptidyl peptidase-4 (DPP-4) inhibitor or glucagon-like peptide-1 (GLP-1) therapy) for three months prior to screening. Subjects not on statin therapy or on a stable dose of a statin, for at least four weeks prior to randomisation, were eligible for inclusion. Subjects were also required not to make any changes to their diet or exercise for four weeks prior to randomisation and during the course of the study.

Main exclusion criteria (see supplemental data for full details) included use of prohibited medications (insulin, fibrates, thiazolidinediones, therapeutic omega-3 fatty acids, alpha-glucosidase inhibitors), recent or current use of cannabis, history of significant depression, planned travel outside the UK during the course of study, genetic dyslipidaemia or significant cardiac, renal or hepatic impairment.

There was a one to five week period between screening (visit 1) and treatment randomisation (visit 2). Visit 1 could be split into two separate visits (1A and B) to allow a 21-day washout period of the prohibited medications prior to blood sampling for eligibility. Remaining visits occurred 4, 8 and 13 weeks after initiation of treatment (visits 3, 4 and 5, respectively), or earlier if patients withdrew. A safety follow up visit occurred 7 days after study completion or withdrawal (visit 6). Visits 4 and 6 were telephone assessments.

Patients were required to take study medication in the fasted state, twice daily, 30 minutes before breakfast and 30 minutes before evening meal, typically 12 hours apart for 13 weeks.

Study endpoints and assessments

The primary endpoint was change in mean serum HDL-C from baseline, in CBD and THCV groups, compared with the change in placebo group, at week 13. Secondary endpoints included changes in lipid profile, glycaemic control, insulin sensitivity, body weight, visceral adiposity, appetite and cardiovascular function. Tertiary endpoints were changes in markers of inflammation, vascular function, adipokines, endocannabinoids and gut hormone concentrations.

Serum lipid concentrations were analysed with the Roche modular system using enzymatic calorimetric assays. Non-esterified fatty acid (NEFA) concentrations were quantified on the Roche COBAS 311 system, using an acyl-CoA synthetase/acyl-CoA oxidase (ACS-ACOD) method. Apolipoprotein markers were analysed on the Roche COBAS 311 system, using immunoturbidimetric assays, based on the principle of immunological agglutination. Plasma VLDL-C concentrations were determined by ultracentrifugation.

A standard 75 g OGTT was performed and plasma glucose and serum insulin were analysed using the Roche modular system and Advia Centaur immunoassay analyser respectively. HOMA-insulin resistance (IR), insulin sensitivity and β-cell function were calculated using the HOMA2 Calculator v2.2© (Diabetes Trials Unit, University of Oxford).

Plasma endocannabinoids, N-arachidonoylethanolamine (AEA), 2-arachidonoylglycerol (2-AG), oleoylethanolamine (OEA) and palmitoylethanolamine

(PEA), were analysed using liquid chromatography-tandem mass spectrometry, based on a previously published method (28). Ketones, orexin A and retinol binding protein (RBP) 4 were analysed using immunoassay, while all other tertiary endpoints including adiponectin, resistin, leptin, E-Selectin, vascular cell adhesion molecule (VCAM), Von Willebrand factor (vWF), C-reactive protein (CRP), interleukin (IL) 6, tumour necrosis factor (TNF) α, glucose-dependent insulinotropic peptide (GIP), ghrelin and GLP-1 were analysed by multiplex analysis, using commercially available kits (Milliplex™, HMHMAG-34K, HCVD1-67AK, HADK-1-61K-A, HCVD2-67BK, BPHCVD05-6, Merck Millipore[®]).

Resting blood pressure was measured using digital blood pressure monitor while cardiovascular parameters including systolic, diastolic and mean arterial pressure, heart rate, stroke volume, cardiac output, inter beat interval, ejection time and total peripheral resistance were measured using a Finometer[®] (Finapres Medical Systems), which uses a finger-clamp method to detect beat-to-beat changes in digital arterial diameter with an infrared photoplethysmograph.

Adipose tissue distribution was assessed using whole body magnetic resonance imaging (MRI); images were analysed by a blinded investigator using SliceOmatic™. Body weight and 7-point skin fold measures were also recorded. Hepatic TG concentration was assessed using magnetic resonance spectroscopy (MRS) and analysed using JMRUI software

Subject's Global Impression of Change (SGIC) and Clinician's Global Impression of Change (CGIC) was assessed using an ordinal 7-point Likert scale (1=very much improved to 7=very much worse). Changes in appetite were established using patients' scores of their appetites that they recorded on daily basis using an appetite

0-10 numerical rating scale (NRS), where 0=no appetite (don't feel hungry) and

10=maximum appetite (completely hungry all the time) (29). The change from mean

baseline score (mean of seven days before start of treatment) was compared to the

mean score from the last seven days on treatment (end of 13 weeks).

Safety assessments included reporting for adverse events (AEs) and serious

adverse events (SAEs), recording vital signs, pre- and post-treatment laboratory

sampling and electrocardiograms (ECG) and change from baseline in Beck

Depression Inventory-II (BDI-II) scores.

The BDI-II questionnaire, an assessment for anxiety and depression, is a multiple

choice, self-reported inventory, and is one of the most widely used and validated

instruments for measuring severity of depression (30).

Statistical methods

An independent statistician produced a schedule for random treatment allocation

which was held centrally and not divulged to any other person involved in the study

until the database had been locked. Patients were randomly allocated to treatment

groups in a 1:1:1 ratio, stratified by centre, according to the randomisation schedule.

Study site staff identified the pack number to be dispensed to the subject at each of

Visits 2 and 3 according to the randomisation schedule.

Analysis was performed using the intention-to-treat (ITT) population; all subjects who

were randomised, received at least one dose of study medication and had on-

treatment efficacy data. All statistical tests were two-sided at the 5% significance

level. Between group differences and 95% confidence intervals (CI) were also

calculated. The primary endpoint and the majority of secondary endpoints were

analysed using analysis of covariance (ANCOVA) of the changes from baseline to

the end of treatment in the associated parameter, with the exception of the SGIC and

CGIC, which were analysed with ordinal logistic regression using the cumulative

proportional odds model. The parameter's baseline values were included as a

covariate, and treatment was included as a factor. The tertiary variables were

analysed using ANCOVA with baseline value as covariate and treatment group and

gender as factors, or using pairwise Fisher's Exact test, as appropriate. The null

hypothesis was one of no difference in the effects of any of the active treatments

compared individually with placebo. As this study was a phase 2a proof of concept

study, no formal sample size calculation was performed.

Changes from baseline in all the plasma markers were analysed *post hoc* using a

paired t-test, and the glucose response to OGTT was analysed using repeated

measures 2-way ANOVA.

Results

One hundred and twenty-five patients were screened and 62 randomised to the five

treatment arms. . The disposition of subjects enrolled is presented in Figure 1.

Subjects were similar between treatment groups (Table 1) in terms of baseline

characteristics.

Lipids

THCV had no effect on HDL-C concentrations (Table 2), but it increased Apo A

concentrations compared with placebo from baseline to the end of treatment (from

48.5 to 49.1 µmol/L in the THCV vs. 47.3 to 43.9 µmol/L in the placebo group;

P<0.05, Fig. 2A). THCV had no effect on LDL-C concentrations. CBD alone and in combination with THCV, did not affect any of the lipid parameters (Table 2).

Glycaemic Control

THCV reduced fasting plasma glucose concentration compared with placebo from baseline to the end of treatment (from 7.4 to 6.7 mmol/L in the THCV vs. 7.6 to 8.0 mmol/L in the placebo group, ETD = -1.24 ± 0.6 (SEM), *P*<0.05, Fig. 3A). In line with this, there was a significant increase in HOMA2 B in the THCV treatment group compared with placebo from baseline to the end of treatment (from 105.1 to 144.4 in the THCV group vs. 96.4 to 94.7 in the placebo group, ETD = 44.6 ± 16.1 (SEM), *P*<0.01, Table 2, Fig 3B). There was no significant difference in glucose response to OGTT at 2 hours. However, when compared with baseline, THCV significantly improved 3-hour blood glucose response (*P*<0.05, Fig 3C). CBD alone or in combination with THCV had no effect on glycaemic parameters (Table 2).

Vascular Function

Compared to placebo, CBD and THCV, alone and in combination, had no effect on cardiovascular parameters (Table 2), or plasma markers of vascular function (Supplementary data Table 1).

Adipokines

There was an increase from baseline in adiponectin concentration in the THCV group and a reduction in placebo group; the treatment difference was statistically significant in favour of THCV treatment (ETD -5.9 x 10^6 pg/mL, *P*<0.01, Fig. 3B). Plasma concentrations of leptin and resistin remained unchanged with THCV treatment. Compared with baseline rather than placebo, CBD caused a significant

reduction in the concentration of resistin (-898 pg/mL, *P*<0.05, Fig. 3C), but had no

effect on leptin or adiponectin. Subjects taking a combination of CBD and THCV had

no change in adipokine levels (Supplementary data Table 1).

Markers of Inflammation

Both THCV and CBD, or their combination, had no significant effect on plasma

markers of inflammation (CRP, TNF α and IL-6; supplementary data Table 1).

Gut Hormones

THCV, on its own and in combination with CBD, had no effect on the concentrations

of gut signalling hormones including GLP-1, GIP and ghrelin (supplementary data

Table 1). However, in a post-hoc analysis, for which post-treatment concentrations

were compared with baseline (rather than placebo), CBD caused a significant

increase in the concentration of GIP (21.2 pg/mL, *P*<0.05, Fig. 3D), without any

effect on GLP-1 or ghrelin concentrations.

Body weight

Baseline mean body weight (kg ± SD) in the CBD, THCV, 1:1 CBD:THCV, 20:1

CBD:THCV and placebo groups were 97.1 ± 13.8, 98.3 ± 17.5, 100.7 ± 14.5, 100.5 ±

17.9 and 94.2 ± 19.1 respectively. There were no statistically significant changes in

anthropometric parameters including weight, waist circumference, waist to hip ratio

and skin fold thickness in any of the treatment groups (Table 2).

Visceral adiposity and liver triglycerides

There were no changes in visceral adiposity or liver TG (Table 2) as assessed by

MRI/MRS in any of the treatment groups.

Appetite

None of the treatments had any significant impact on appetite as assessed by 0-10 NRS scores (Table 2).

PGIC and CGIC

A full summary of the PGIC and CGIC assessment responses is presented in Supplemental Figures 1 and 2. Analysis of these responses showed a treatment difference in favour of all the active treatments, to varying degrees, but most notably between the 1:1 CBD:THCV and placebo treatment groups on CGIC. There were reported improvements in seven out of 11 (63.6%) patients in the CGIC on 1:1 CBD:THCV treatment, compared with only two of the 14 (14.3%) placebo patients, with a recorded improvement on CGIG. This translated to a statistically significant treatment effect of 1:1 CBD:THCV treatment compared with placebo, with an odds ratio of 9.529 ($P<0.05$) in the CGIC. No other statistically significant effects were calculated for any other active treatment in either assessment.

Endocannabinoids

There was no significant change in the levels of circulating AEA, 2-AG, OEA and PEA after 13 weeks of any treatment (Table 2).

Post hoc analysis in THCV group analysing glucose response t

o OGTT and changes in HbA1c

An improvement in glucose response to OGTT was noted in the THCV group at 3 h (see Fig 3C). When subjects on any form of diabetes treatment other than diet/metformin were excluded from analysis, this effect became more pronounced

(*P*<0.05 at 1 h and *P*<0.01 at 3 h; n=6, Fig 3D). In the same group of diet/metformin only patients, compared with placebo, a significant improvement in HbA1c was also observed (*P*<0.05, Fig 3E).

Safety

The study medication was well tolerated, with the majority of subjects experiencing AEs that were mild or moderate in severity. Treatment-emergent (all causality) AEs were reported by 11 of 13 (84.6%) subjects in the CBD group, 11 of 12 (91.7%) in the THCV group, 7 of 11 (63.6%) in the 1:1 CBD:THCV group, 8 of 11 (66.7%) in the 20:1 CBD:THCV group, compared with 13 of 14 subjects (92.9%) receiving placebo.

The more common treatment-related AE reported by subjects in all the groups, except for 20:1 CBD:THCV, was decreased appetite (two subjects (15.4%) receiving CBD, four subjects (33.3%) receiving THCV, one subject (9.1%) receiving 1:1 CBD:THCV and two subjects (14.3%) receiving placebo). None of the subjects in 20:1 CBD:THCV group experienced an AE of decreased appetite. Two subjects reported diarrhoea with THCV, compared to no subjects in the placebo group. Two subjects (14.3%) on placebo also reported dizziness. All other treatment-related AEs were reported in individual subjects.

No deaths occurred during the study. There were two SAEs in this study. One patient (8.3%) taking 20:1 CBD:THCV treatment experienced an SAE of myocardial infarction that was considered moderate in severity, had recovered by the end of study, and was not considered to be treatment related. One placebo patient experienced an SAE of myocardial ischaemia that was not considered to be treatment-related, was mild in severity and occurred on Day 92 of the study; the SAE was still ongoing at the end of the study.

Mean changes from screening to the end of treatment in BDI-II scores for the CBD, THCV and 1:1 CBD:THCV treatment groups were 0.85, 0.58 and 0.27 points, respectively, which were not statistically significant from placebo (change from baseline of -0.08 points), and remained within the 'minimal depression' range for all treatments. The largest change from baseline to the end of treatment in BDI-II score was in the 20:1 CBD:THCV treatment group (4.91 points). While this remained in the 'minimal depression' bracket, it was statistically significant compared to placebo (ETD = 4.77, $P<0.01$).

Conclusions

The aim of this pilot study was to investigate the clinical effect and tolerability of two phytocannabinoids, THCV and CBD, alone and in combination, in subjects with type 2 diabetes and dyslipidaemia. THCV significantly decreased fasting plasma glucose, and increased β-cell function, adiponectin and Apo A concentrations, and was well tolerated in patients. These findings suggest that THCV may represent a new therapeutic agent for glycaemic control in subjects with type 2 diabetes.

The ECS plays an important role in modulating energy intake and expenditure (for reviews, see 1, 2), and a chronically over active ECS may have a role in diabetes and its various complications (2). A recent cross-sectional study showed that marijuana use was associated with lower concentrations of fasting insulin, insulin resistance and waist circumference (31). Some of the favourable metabolic effects seen with smoking cannabis may be due to partial CB_1 agonists like THC, which may act as a functional antagonist in conditions of increased endocannabinoid tone like obesity, because of its lower CB_1 binding affinity and efficiacy in comparison to 2-AG, whose levels are elevated in visceral obesity (32). Rimonabant, a CB_1 receptor

antagonist, was the first in its class to be used as anti-obesity drug, but led to significant psychiatric adverse events (5). Pre-clinical studies with the plant-derived compound THCV have shown that it produces hypophagia and weight reduction in lean mice (18) and improves glucose tolerance and insulin sensitivity in DIO mice (19). Similar results have been seen with CBD in *ob/ob* mice (GW Pharma data on file) and CBD has been reported to lower the incidence of diabetes in non-obese diabetic mice (33), and arrest the onset of autoimmune diabetes in non-obese diabetic mice (34). Given the positive metabolic effects of both THCV and CBD in preclinical studies and their potent anti-inflammatory and antioxidant properties (22,35,36), we decided to investigate, for the first time, their efficacy and tolerability in subjects with type 2 diabetes.

THCV Alone

THCV treatment alone had no effect on HDL-C concentration. It did, however, produce a significant rise in serum Apo A, when compared with placebo. Apo A makes 90% of HDL protein and constitutes an important structural component of the HDL particle. Apo A I, which accounts for 70% of the Apo A (the remaining 20% accounted for by Apo A II), plays an important role in reverse cholesterol transport (37). The significance of this result remains unclear.

THCV significantly reduced fasting blood glucose concentrations, improved HOMA2 B and improved the 3-hour blood glucose response to OGTT, without any significant difference in insulin response. These findings are in keeping with the recent animal data, where THCV improved fasting glucose and 30 min glucose response to OGTT, and also improved insulin sensitivity by reducing fasting and post glucose insulin concentrations (19). In the same study, THCV treatment improved insulin-induced

phosphorylation of Akt (also known as protein kinase B) in insulin-resistant human hepatocytes and mice myotubes, suggesting improved insulin signalling as one of the possible mechanisms of action.

Although there was an improvement in fasting and 3-hour post OGTT blood glucose, there were no changes in body weight and gut hormone concentrations. In fact, a rise in the concentration of retinol binding protein 4 (RBP-4) was observed with THCV, an adipokine that has been associated with obesity and insulin resistance (38). Therefore the mechanism by which THCV improves glycaemic control remains unclear.

THCV significantly increased adiponectin concentrations. Adiponectin enhances hepatic insulin sensitivity, increases fatty acid oxidation and has important anti-atherogenic properties. Its concentrations are reduced in obesity and type 2 diabetes (39).

Positive metabolic effects of THCV on glycaemic control and adiponectin concentrations were also seen with rimonabant, the first CB_1 antagonist to be licenced as anti-obesity medication that was later withdrawn from market due to increased incidence of psychiatric adverse events (5). It is, however, important to emphasize that while rimonabant consistently reduced body weight in all the reported randomised clinical trials, no such change was seen with THCV, suggesting clear differences in the mechanisms of action of these compounds. Recent animal data with THCV similarly showed no effect on body weight (19). Moreover, rimonabant improved the lipid profile (increased HDL-C and reduced TG levels), while THCV had no effect on lipid parameters in our study (40). There is also a clear difference in chemical structure between THCV and rimonabant. It is therefore reasonable to believe that THCV and rimonabant have different pharmacological and

safety profiles. At micromolar concentrations, THCV inhibits the activity of both fatty

acid amide hydrolase (FAAH) and monoacyl glycerol lipase (MAGL), thereby

inhibiting the hydrolysis of AEA and 2-AG respectively (41). THCV, therefore, can act

as an indirect agonist at the cannabinoid receptors, by enhancing the activity of the

endocannabinoid system. Since such a change was not seen in our study, it is

reasonable to believe that, at the dose tested, THCV was unable to modulate the

endocannabinoid system. Recent animal data from Wargent and colleagues (19)

showed that most of the positive metabolic effects of THCV were seen with 5 and

12.5 mg/kg doses given orally in rodents. In comparison to this, the dose used on

our study (10 mg/day, approx. 0.1 mg/kg in humans) was much lower.

CBD Alone

Although CBD did not produce any effects on the primary and secondary efficacy

outcomes compared with placebo, it reduced circulating resistin concentrations from

baseline, while increasing the concentration of circulating GIP. Increased

concentrations of resistin are associated with obesity and insulin resistance (42). GIP

is one of the incretin hormones, produced by K cells in the proximal duodenum,

which is known to have insulinotropic and pancreatic β-cell preserving properties

(43). Despite having positive effects on resistin and GIP, CBD did not produce any

improvement in glycaemic control.

CBD is known for its indirect agonism at the CB_1 receptors, by either increasing CB_1

constitutional activity or the endocannabinoid tone. CBD has been reported to inhibit

hydrolysis of AEA by FAAH (but only at high micromolar levels) and also increases

2-AG levels (39). In a recent clinical study, in subjects with schizophrenia, 800 mg

per day of CBD treatment significantly increased serum AEA levels and was

associated with an improvement in clinical profile of these subjects (12). In our study, CBD (albeit at a much lower dose), alone or in combination with THCV, had no effect on the plasma levels of endocannabinoids, suggesting that it had minimal interaction with the endocannabinoid system at the doses investigated.

Studies in rodents have used intraperitoneal CBD in a dose ranging from 1 mg/kg/day to 20 mg/kg/day, with positive effects on the metabolism seen only with higher dose ranges (7, 8, 9). In a 70 kg individual, a 20 mg/kg/day dose equates to 1400 mg/day. Similarly, human studies have used CBD in higher doses (12, 44). The dose used in our study was 200 mg/day, which could possibly explain lack of therapeutic effects seen with CBD.

Combination of CBD and THCV

Except for an improvement in CGIC assessments with 1:1 CBD:THCV treatment, none of the efficacy parameters were affected by 1:1 or 20:1 combination of CBD and THCV. There was a trend towards an improvement in most lipid parameters and the overall incidence of all-causality treatment related AEs was lowest in the 1:1 CBD:THCV treatment group; these factors could have led to an impression of improvement in subjects' overall condition with this treatment. While the combination of CBD and THCV did not produce any favourable effects on any of the parameters, the favourable effects of THCV were also lost in the combination treatment. Similarly, the positive effects of CBD on GIP and resistin were not seen in any of the combination treatments. This suggests that CBD and THCV in combination may counteract their individual therapeutic effects at least in the ratios and doses tested in this study. This may be at the level of receptors or due to interference with each other's metabolism or therapeutic half-life, and requires further investigation.

Safety

Both CBD and THCV were well tolerated, with the majority of patients experiencing AEs that were mild in severity. The most common AE was reduced appetite with similar incidence across all the treatment groups. There were no reports of depression and no clinically significant abnormalities on ECG and laboratory results including blood count, liver and renal biochemistry in any treatment groups. There was one SAE of myocardial ischaemia in the placebo group, and one SAE of myocardial infarction in the 20:1 CBD:THCV group; both were considered unrelated to study medication. With regards to the BDI-II scale, though the change in 20:1 CBD:THCV treatment group was statistically significant, all mean active treatments and placebo scores remained in the 'minimal depression' range.

Conclusion

In this clinical study, the first to study the effects of CBD and THCV in subjects with type 2 diabetes and dyslipidaemia, THCV improved glycaemic control, and therefore warrants further investigation in this therapeutic area. CBD failed to show any detectable metabolic effects despite producing desirable changes in some adipokines and gut hormone concentrations. The incidence of AEs was similar between treatment groups, and both CBD and THCV were well tolerated. No new safety concerns were identified in the study.

Conflicts of interest and source of funding

SHR has been a member of GW's Speaker's Board and has received funding for clinical studies. GT is supported by the National Institute for Health Research (NIHR) Oxford Biomedical Research Centre Programme. The views expressed are those of

GT and not necessarily those of the NHS, the NIHR or the Department of Health.
The study was investigator led and initiated, and was supported by GW Research
Ltd.

Figure legends

Figure 1. Summary of breakdown of patients enrolled in the study. 125 subjects were screened and 62 randomised to this study.

Figure 2. Compared with placebo, THCV alone caused a significant improvement in the concentration of Apo A (*P*<0.05; A) and adiponectin (*P*<0.01; B). Data was analysed by analysis of covariance and presented as mean ± SEM. CBD caused a significant reduction in resistin (*P*<0.05; C) and an increase in GIP concentration (*P*<0.05; D), when compared with pre-treatment values. Data were analysed *post hoc* using paired t-test and presented as mean ± SEM.

Figure 3. Compared with placebo, THCV alone caused significant improvement in fasting glucose (*P*<0.05; A) and in keeping with this, there was a highly significant improvement in β cell function measured by HOMA2 (*P*<0.01; B). THCV caused significant improvement in 3 hour glucose response during OGTT (*P*<0.05; C), when compared with pre-treatment values.

Data were analysed using 2-way ANOVA and presented as mean ± SEM. (D) Compared with pre-treatment values, there was a highly significant improvement in 3 hour glucose response to OGTT with THCV, when subjects on any oral hypoglycaemic therapy other than diet and/or metformin were excluded from analysis (*P*<0.01, n=6). In the same subgroup (analysed post hoc), compared with placebo, there was a statistically significant improvement in HbA1c (*P*<0.05, E). Data were analysed *post hoc* using repeated measures 2 way ANOVA and paired t-test respectively and presented as mean ± SEM.

References

1. Silvestri C, Ligresti A, Di Marzo V. Peripheral effects of the endocannabinoid system in energy homeostasis: adipose tissue, liver and skeletal muscle. Rev Endocr Metab Disord 2011;12:153-162.

2. Horvath B, Mukhopadhyay P, Hasko G, Pacher P. The endocannabinoid system and plant-derived cannabinoids in diabetes and diabetic complications. Am J Pathol 2012;180:432-442.

3. Di Marzo V. The endocannabinoid system in obesity and type 2 diabetes. Diabetologia 2008;51:1356-1367.

4. Christopoulou FD, Kiortsis DN. An overview of the metabolic effects of rimonabant in randomized controlled trials: potential for other cannabinoid 1 receptor blockers in obesity. J Clin Pharm Ther 2011;36:10-18.

5. Le Foll B, Gorelick DA, Goldberg SR. The future of endocannabinoid-oriented clinical research after CB1 antagonists. Psychopharmacology (Berl) 2009;205:171-174.

6. Rajesh M, Mukhopadhyay P, Batkai S, Hasko G, Liaudet L, Drel VR, Obrosova IG, Pacher P. Cannabidiol attenuates high glucose-induced endothelial cell inflammatory response and barrier disruption. Am J Physiol Heart Circ Physiol 2007;293:H610-H619.

7. El-Remessy AB, Al-Shabrawey M, Khalifa Y, Tsai NT, Caldwell RB, Liou GI. Neuroprotective and blood-retinal barrier-preserving effects of cannabidiol in experimental diabetes. Am J Pathol 2006;168:235-244.

8. Toth CC, Jedrzejewski NM, Ellis CL, Frey WH. Cannabinoid-mediated modulation of neuropathic pain and microglial accumulation in a model of murine type I diabetic peripheral neuropathic pain. Mol Pain 2010;6:16.

9. Rajesh M, Mukhopadhyay P, Batkai S, Patel V, Saito K, Matsumoto S, Kashiwaya Y, Horvath B, Mukhopadhyay B, Becker L, Hasko G, Liaudet L, Wink DA, Veves A, Mechoulam R, Pacher P. Cannabidiol attenuates cardiac dysfunction, oxidative stress, fibrosis, and inflammatory and cell death signaling pathways in diabetic cardiomyopathy. J Am Coll Cardiol 2010;56:2115-2125.

10. Stanley CP, Wheal AJ, Randall MD, O'Sullivan SE. Cannabinoids alter endothelial function in the Zucker rat model of type 2 diabetes. Eur J Pharmacol 2013;720:376-382.

11. Resstel LB, Tavares RF, Lisboa SF, Joca SR, Correa FM, Guimaraes FS. 5-HT1A receptors are involved in the cannabidiol-induced attenuation of behavioural and cardiovascular responses to acute restraint stress in rats. Br J Pharmacol. 2009;156:181-8.

12. Leweke FM, Piomelli D, Pahlisch F, Muhl D, Gerth CW, Hoyer C, Klosterkotter J, Hellmich M, Koethe D. Cannabidiol enhances anandamide signaling and alleviates psychotic symptoms of schizophrenia. Transl Psychiatry. 2012;2:e94

13. Schubart CD, Sommer IE, van Gastel WA, Goetgebuer RL, Kahn RS, Boks MP. Cannabis with high cannabidiol content is associated with fewer psychotic experiences. Schizophr Res 2011;130:216-221.

14. Pertwee RG. The diverse CB1 and CB2 receptor pharmacology of three plant cannabinoids: delta9-tetrahydrocannabinol, cannabidiol and delta9-tetrahydrocannabivarin. Br J Pharmacol 2008;153:199-215.

15. O'Sullivan SE, Sun Y, Bennett AJ, Randall MD, Kendall DA. Time-dependent vascular actions of cannabidiol in the rat aorta. Eur J Pharmacol 2009;612:61-8.

16. Esposito G, Scuderi C, Valenza M, Togna GI, Latina V, De Filippis D, Cipriano M, Carratu MR, Iuvone T, Steardo L. Cannabidiol reduces Aβ-induced neuroinflammation and promotes hippocampal neurogenesis through PPARγ involvement. PLoS One 2011;6:e28668.

17. De Filippis D, Esposito G, Cirillo C, Cipriano M, De Winter BY, Scuderi C, Sarnelli G, Cuomo R, Steardo L, De Man JG, Iuvone T. Cannabidiol reduces intestinal inflammation through the control of neuroimmune axis. PLoS One 2011;6:e28159.

18. Riedel G, Fadda P, McKillop-Smith S, Pertwee RG, Platt B, Robinson L. Synthetic and plant-derived cannabinoid receptor antagonists show hypophagic properties in fasted and non-fasted mice. Br J Pharmacol 2009;156:1154-1166.

19. Wargent ET, Zaibi MS, Silvestri C, Hislop DC, Stocker CG, Stott CG, Guy GW, Duncan M, Di Marzo V, Cawthorne MA. The cannabinoid Delta(9)-tetrahydrocannabivarin (THCV) ameliorates insulin sensitivity in two mouse models of obesity. Nutr Diabetes 2013;3:e68

20. Thomas A, Stevenson LA, Wease KN, Price MR, Baillie G, Ross RA, Pertwee RG. Evidence that the plant cannabinoid delta 9-tetrahydrocannabivarin is a cannabinoid CB1 and CB2 receptor antagonist. Br J Pharmacol 2005;146:917-926.

21. Pertwee RG, Thomas A, Stevenson LA, Ross RA, Varvel SA, Litchman AH, Martin BR, Razdan RK. The psychoactive plant cannabinoid, delta 9-

tetrahydrocannabinol, is antagonized by delta 8- and delta 9-

tetrahydrocannabivarin in mice in vivo. Br J Pharmacol 2007;150:586-594.

22. Bolognini D, Costa B, Maione S, Comelli F, Marini P, Di Marzo V, Parolaro D,

    Ross RA, Gauson LA, Cascio MG, Pertwee RG. The plant cannabinoid Delta

    9-tetrahydrocannabivarin can decrease signs of inflammation and

    inflammatory pain in mice. Br J Pharmacol 2010;160:677-687.

23. Hill AJ, Weston SE, Jones NA, Smith I, Bevan SA, Williamson EM, Stephens

    GJ, Williams CM, Whalley BJ. Delta 9-tetrahydrocannabivarin suppresses in

    vitro epileptiform and in vivo seizure activity in adult rats. Epilepsia

    2010;51:1522-1532.

24. Batkai S, Mukhopadhyay P, Horvath B, Rajesh M, Gao RY, Mahadevan A,

    Amere M, Battista N, Litchman AH, Gauson LA, Maccarrone M, Pertwee RG,

    Pacher P. Delta 8-tetrahydrocannabivarin prevents hepatic

    ischaemia/reperfusion injury by decreasing oxidative stress and inflammatory

    responses through cannabinoid CB2 receptors. Br J Pharmacol

    2012;165:2450-2461.

25. Anavi-Goffer S, Baillie G, Irving AJ, Gertsch J, Greig IR, Pertwee RG, Ross

    RA. Modulation of L-alpha-lysophosphatidylinositol/GPR55 mitogen-activated

    protein kinase (MAPK) signaling by cannabinoids. J biol chem 2012;287:91-

    104.

26. De Petrocellis L, Ligresti A, Moriello AS, Allara M, Bisogno T, Petrosino S,

    Stott CG, Di Marzo V. Effects of cannabinoids and cannabinoid-enriched

    Cannabis extracts on TRP channels and endocannabinoid metabolic

    enzymes. Br J Pharmacol 2011;163:1479-1494.

27. De Petrocellis L, Orlando P, Moriello AS, Aviello G, Stott C, Izzo AA, Di Marzo V. Cannabinoid actions at TRPV channels: effects on TRPV3 and TRPV4 and their potential relevance to gastrointestinal inflammation. Acta Physiol (Oxf) 2012;204:255-266.

28. Richardson D, Ortori CA, Chapman C, Kendall DA, Barrett DA. Quantitative profiling of endocannabinoids and related compounds in rat brain using liquid chromatography-tandem electroscopy ionisation mass spectrometry. Anal Biochem 2007;360:216-226

29. Flint A, Raben A, Blundell JE, Astrup A. Reproducibility, power and validity of visual analogue scales in assessment of appetite sensations in single test meat studies. Int J Obes Relat Metab Disord. 2000;24:38-48

30. Endler NS, Rutherford A, Denisoff E. Beck depression inventory: exploring its dimensionality in a nonclinical population. J Clin Psychol. 1999;55:1307-1312.

31. Penner EA, Buettner H, Mittleman MA. The impact of marijuana use on glucose, insulin, and insulin resistance among us adults. Am J Med 2013;126:583-589

32. Le Foll B, Trigo JM, Sharkey KA, Le Strat Y. Cannabis and delta9-tetrahydrocannabinol (THC) for weight loss? Med Hypotheses 2013;80:564-567.

33. Weiss L, Zeira M, Reich S, Har-Noy M, Mechoulam R, Slavin S, Gallily R. Cannabidiol lowers incidence of diabetes in non-obese diabetic mice. Autoimmunity 2006;39:143-151

34. Weiss L, Zeira M, Reich S, Slavin S, Raz I, Mechoulam R, Gallily R.
Cannabidiol arrests onset of autoimmune diabetes in NOD mice.
Neuropharmacology 2008;54:244-249

35. Costa B, Colleoni M, Conti S, Parolaro D, Franke C, Trovato AE, Giagnoni G.
Oral anti-inflammatory activity of cannabidiol, a non-psychoactive constituent
of cannabis, in acute carrageenan-induced inflammation in the rat paw.
Naunyn Schmiedebergs Arch Pharmacol 2004;369:294-299.

36. Lastres-Becker I, Molina-Holgado F, Ramos JA, Mechoulam R, Fernandez-
Ruiz J.Cannabinoids provide neuroprotection against 6-hydroxydopamine
toxicity in vivo and in vitro: relevance to Parkinson's disease. Neurobiol
Dis 2005;19:96-107

37. Barter PJ. Hugh sinclair lecture: the regulation and remodelling of HDL by
plasma factors. Atheroscler Suppl. 2002;3:39-47.

38. Christou GA, Tselepis AD, Kiortsis DN. The metabolic role of retinol binding
protein 4: an update. Horm Metab Res 2012;44:6-14.

39. Whitehead JP, Richards AA, Hickman IJ, Macdonald GA, Prins JB.
Adiponectin--a key adipokine in the metabolic syndrome. Diabetes Obes
Metab. 2006;8:264-280.

40. Christopoulou FD, Kiortsis DN. An overview of the metabolic effects of
rimonabant in randomized controlled trials: potential for other cannabinoid 1
receptor blockers in obesity. J Clin Pharm Ther 2011;36:10-18.

41. McPartland JM, Duncan M, Di Marzo V, Pertwee RG. Are cannabidiol and
Δ(9)- tetrahydrocannabivarin negative modulators of the endocannabinoid
system? A systematic review. Br J Pharmacol. 2015;172:737-753

42. Steppan CM, Bailey ST, Bhat S, Brown EJ, Banerjee RR, Wright CM, Patel HR, Ahima RS, Lazar MA. The hormone resistin links obesity to diabetes. Nature 2001;409:307-312.

43. Irwin N, Flatt PR. Evidence for beneficial effects of compromised gastric inhibitory polypeptide action in obesity-related diabetes and possible therapeutic implications. Diabetologia. 2009;52:1724-1731

44. Bergamaschi MM, Queiroz RH, Chagas MH, de Oliveira DC, De Martinis BS, Kapczinski F, Quevedo J, Roesler R, Schroder N, Nardi AE, Martin-Santos R, Hallak JE, Zuardi AW, Crippa JA. Cannabidiol reduces the anxiety induced by simulated public speaking in treatment-naïve social phobia patients. Neuropsychopharmacology 2011;36:1219-1226

Participating Centres

1. Division of Medical Sciences & Graduate Entry Medicine, School of Medicine, University of Nottingham, Royal Derby Hospital Centre, Uttoxeter Road, Derby DE22 3DT

2. MAC Clinical Research. Manchester M32 0UT

3. Woolpit Health Centre, Heath Road, Woolpit, Bury St Edmunds, Suffolk, IP30 9QU

4. Mount Farm Surgery, Lawson Place, Bury St Edmunds, Suffolk, IP32 7EW

Figure 1

Table 1. Summary of patient demographics and concomitant therapy.

	CBD (n=13)	THCV (n=12)	1:1 CBD:THCV (n=11)	20:1 CBD:THCV (n=12)	Placebo (n=14)	Total (n=62)
Male (number of subjects and (%))	10 (77)	10 (83)	6 (55)	9 (75)	7 (50)	42 (68)
Female (number of subjects and (%))	3 (23)	2 (17)	5 (45)	3 (25)	7 (50)	20 (32)
Age (years, **Mean (SD)**)	56.8 (9.9)	62.5 (12.6)	59.3 (8.8)	58.0 (8.1)	58.6 (7.7)	59.0 (9.4)
Weight (kg, **Mean (SD)**)	97.2 (13.8)	98.3 (17.5)	100.7 (14.5)	100.5 (17.9)	94.2 (19.1)	98.0 (16.4)
BMI (kg/m^2 **Mean (SD)**)	33.2 (5.4)	34.0 (6.5)	36.4 (5.6)	35.4 (4.6)	33.4 (7.0)	34.4(5.8)
Duration since diagnosis of diabetes (years, **Mean (SD)**)	2.8 (3.3)	4.8 (3.6)	4.4 (2.7)	5.1 (3.3)	3.8 (3.5)	4.2 (3.3)
Number (%) of patients on anti-diabetic and lipid lowering therapy						
Metformin	9 (69)	9 (75)	10 (91)	11 (92)	12 (86)	51 (82)
DPP-4 Inhibitors	1 (8)	1 (8)	1 (9)	1 (8)	1 (7)	5 (8)
Sulfonylureas	3 (23)	5 (42)	4 (36)	3 (25)	4 (29)	19 (31)
Statins	9 (69)	11 (92)	10 (91)	8 (67)	13 (93)	51 (82)

Table 2. Clinical data before (baseline) and after (treatment) 13 weeks of

randomised treatment

Variable	CBD (n=13)		THCV (n=12)		1:1 CBD : THCV (n=11)		20:1 CBD : THCV (n=12)		Placebo (n=14)	
	Baseline	Treatment	Baseline	Treatment	Baseline	Treatment	Baseline	Treatment	Baseline	Treatment
HDL-C (mmol/l)	1.0 ± 0.3	1.0 ± 0.3	1.1 ± 0.1	1.1 ± 0.2	1.0 ± 0.2	1.0 ± 0.3	1.0 ± 0.1	1.0 ± 0.1	1.0 ± 0.3	1.0 ± 0.2
Total-C (mmol/l)	4.5 ± 0.9	4.3 ± 0.7	3.8 ± 0.9	3.7 ± 1.0	4.2 ± 1.1	3.8 ± 0.7	4.6 ± 0.9	4.2 ± 0.6	4.0± 0.7	3.9 ± 0.9
LDL-C (mmol/l)	2.5 ± 0.7	2.4 ± 0.6	2.0 ± 0.6	2.0 ± 0.8	2.2 ± 0.8	2.0 ± 0.5	2.8 ± 0.6	2.5 ± 0.5	2.2 ± 0.6	2.2 ± 0.7
HDL:LDL-C ratio	0.5 ± 0.2	0.4 ± 0.2	0.6 ± 0.3	0.6 ± 0.3	0.5 ± 0.2	0.6 ± 0.2	0.4 ± 0.1	0.4 ± 0.1	0.5 ± 0.1	0.5 ± 0.1
UC VLDL-C (mmol/l)	0.8 ± 0.4	1.0 ± 0.5	1.0 ± 0.7	0.9 ± 0.7	1.0 ± 0.5	1.0 ± 0.4	1.1 ± 0.4	1.0 ± 0.3	1.0± 0.5	0.9 ± 0.4
Triglycerides (mmol/l)	2.2 ± 1.4	2.3 ± 1.3	1.7 ± 1.1	1.8 ± 1.5	2.4 ± 1.6	2.2 ± 1.2	1.9 ± 0.7	1.9 ± 0.7	2.1 ± 1.4	2.0 ± 1.1
Apo A (µmol/l)	48.6 ± 9.7	43.6 ± 6.6	48.5 ± 7.0	**49.1 ± 6.4**[b]	48.7 ± 11.1	46.8 ± 7.4	48.7 ± 10.0	45.7 ± 6.3	47.3 ± 8.8	43.9 ± 7.2
Apo B (µmol/l)	3.1 ± 0.8	3.3 ± 0.7	2.6 ± 0.6	2.7 ± 1.0	3.0 ± 0.9	2.9 ± 0.7	3.4 ± 0.7	3.4 ± 0.6	2.9 ± 0.7	3.0 ± 0.6
Apo B:Apo A ratio	0.6 ± 0.2	0.7 ± 0.2	0.5 ± 0.1	**0.5 ± 0.2**[a]	0.6 ± 0.2	0.6 ± 0.2	0.7 ± 0.2	0.7 ± 0.1	0.6 ± 0.2	0.7 ± 0.1
NEFA (mmol/l)	0.6 ± 0.2	0.5 ± 0.3	0.6 ± 0.1	0.6 ± 0.2	0.7 ± 0.3	0.6 ± 0.2	0.7 ± 0.2	0.6 ± 0.2	0.6 ± 0.2	0.6 ± 0.2

Liver TG (%)	26.9 ± 16.9	22.2 ± 17.1	11.9 ± 8.0	11.5 ± 13.5	33.3 ± 18.3	32.2 ± 26.2	23.2 ± 14.3	25.4 ± 17.4	20.5 ± 15.1	18.5 ± 15.4
Fasting glucose (mmol/l)	8.0 ± 2.3	8.4 ± 2.8	7.4 ± 2.3	**6.7 ± 1.9[b]**	8.5 ± 2.5	8.7 ± 2.0	8.4 ± 2.8	8.8 ± 3.1	7.6 ± 1.4	8.0 ± 1.6
Fructosa mine (μmol/l)	259.5 ± 34.4	256.8 ± 44.6	238.2 ± 25.0	239.3 ± 28.7	254.4 ± 35.7	256.0 ± 55.2	253.3 ± 34.8	268.8 ± 58.2	241.4 ± 19.3	253.7 ± 32.0
HbA1c (%)	6.9 ± 0.9	7.0 ± 1.1	6.6 ± 0.6	6.5 ± 0.7	7.2 ± 1.1	7.4 ± 1.5	7.2 ± 0.9	7.3 ± 1.3	7.0 ± 0.7	7.3 ± 1.0
Glucose - 2 h OGTT (mmol/l)	7.4 ± 2.4	6.6 ± 2.7	5.7 ± 3.1	6.2 ± 2.7	8.7 ± 3.8	8.8 ± 2.5	5.6 ± 3.4	6.6 ± 2.3	7.9 ± 2.6	8.4 ± 2.2
Insulin - 2 h OGTT (pmol/l)	604.1 ± 605.2	454.8 ± 387.5	661.0 ± 381.2	724.9 ± 589.6	789.5 ± 677.2	900.2 ± 875.8	659.3 ± 570.4	651.6 ± 730.0	653.6 ± 381.5	619.7 ± 455.3
Fasting insulin (pmol/l)	110.3 ± 42.8	123.8 ± 60.8	152.9 ± 94.2	203.5 ± 197.7	175.3 ± 86.1	185.7 ± 67.6	197.6 ± 107.9	192.2 ± 69.1	171.7 ± 105.0	179.7 ± 75.7
C-peptide (nmol/l)	0.9 ± 0.2	0.9 ± 0.2	1.0 ± 0.3	1.1 ± 0.5	1.2 ± 0.2	1.2 ± 0.3	1.1 ± 0.3	1.2 ± 0.3	1.0 ± 0.4	1.1 ± 0.4
HOMA2-IR	2.3 ± 0.9	2.6 ± 1.5	3.0 ± 1.9	3.8 ± 3.3	3.5 ± 1.6	3.7 ± 1.3	4.2 ± 2.9	4.0 ± 1.5	3.4 ± 2.1	3.6 ± 1.5
HOMA2 insulin sensitivity	51.3 ± 20.1	53.0 ± 36.2	47.3 ± 32.4	53.5 ± 44.3	34.9 ± 17.1	30.4 ± 12.9	30.2 ± 11.4	28.9 ± 11.5	42.4 ± 29.2	37.8 ± 32.2
HOMA2 B cell function	70.9 ± 27.2	69.6 ± 31.5	105.1 ± 64.7	**144.4 ± 110.3[c]**	95.7 ± 50.7	93.8 ± 47.5	103.7 ± 60.6	97.9 ± 50.5	96.4 ± 41.4	94.7 ± 39.2
BMI (kg/m^2)	33.2 ± 5.4	33.0 ± 4.9	34.0 ± 6.5	33.8 ± 6.7	36.4 ± 5.6	36.1 ± 5.7	35.4 ± 4.6	35.4 ± 4.4	33.4 ± 7.0	32.9 ± 7.7
Waist circumfer ence (cm)	107.7 ± 10.8	108.0 ± 10.6	115.3 ± 13.1	114.9 ± 13.8	115.4 ± 9.5	116.2 ± 11.8	113.7 ± 13.1	113.5 ± 12.1	109.2 ± 13.0	108.4 ± 13.1
Waist-to-hip ratio	1.0 ± 0.05	1.0 ± 0.1	1.0 ± 0.05	1.0 ± 0.06	1.0 ± 0.1	1.0 ± 0.05	1.0 ± 0.1	1.0 ± 0.1	1.0 ± 0.1	1.0 ± 0.1

Neck circumference (cm)	42.4 ± 3.3	42.1 ± 3.7	42.8 ± 3.8	42.8 ± 3.6	42.7 ± 3.3	42.2 ± 3.8	42.8 ± 3.6	42.5 ± 4.0	41.7 ± 4.8	41.1 ± 4.8
Visceral abdominal fat (l)	8.1 ± 1.9	8.5 ± 2.2	9.1 ± 3.5	9.0 ± 3.5	8.5 ± 3.0	8.6 ± 2.7	9.1 ± 2.5	10.2 ± 2.2	7.2 ± 2.4	7.5 ± 3.4
Appetite 0-10 NRS score	5.6 ± 1.0	4.9 ± 1.0	5.4 ± 1.7	5.0 ± 1.5	4.7 ± 1.2	3.6 ± 1.6	5.0 ± 2.2	4.1 ± 1.9	5.1 ± 1.3	4.5 ± 1.3
Systolic BP (mmHg)	133.4 ± 16.4	132.2 ± 13.0	135.9 ± 13.4	132.8 ± 17.1	126.4 ± 11.6	134.3 ± 12.8	132.7 ± 11.0	134.2 ± 14.8	137.2 ± 11.9	140.4 ± 11.2
Diastolic BP (mmHg)	70.1 ± 8.8	70.6 ± 8.8	70.6 ± 12.2	71.0 ± 9.4	73.2 ± 6.8	77.5 ± 7.7	73.5 ± 10.4	72.2 ± 10.5	73.0 ± 9.5	72.3 ± 10.6
Pulse rate (bpm)	71.5 ± 17.7	70.5 ± 15.7	74.5 ± 12.3	74.1 ± 12.4	80.1 ± 12.2	76.6 ± 8.0	77.1 ± 12.1	82.0 ± 15.8	72.1 ± 10.8	75.5 ± 7.3
BDI-II score	3.8 ± 3.5	4.6 ± 3.7	2.8 ± 3.8	3.3 ± 3.3	4.5 ± 5.2	4.7 ± 5.0	2.8 ± 2.7	7.9 ± 7.6	3.5 ± 3.9	3.5 ± 3.2
AEA	0.2 ± 0.1	0.2 ± 0.05	0.2 ± 0.1	0.2 ± 0.1	0.2 ± 0.1	0.2 ± 0.1	0.2 ± 0.04	0.2 ± 0.1	0.2 ± 0.1	0.2 ± 0.1
2-AG	5.0 ± 2.9	4.7 ± 2.9	4.3 ± 1.7	13.6 ± 28.6	6.2 ± 3.1	5.0 ± 1.5	3.8 ± 1.5	3.7 ± 1.7	5.0 ± 3.3	5.3 ± 3.4
OEA	2.4 ± 1.1	1.8 ± 0.7	2.4 ± 1.0	2.3 ± 0.6	2.5 ± 0.8	2.2 ± 0.7	2.2 ± 0.5	2.2 ± 0.8	2.4 ± 0.5	2.1 ± 0.5
PEA	2.7 ± 1.9	1.8 ± 0.7	2.7 ± 1.1	2.5 ± 0.7	2.5 ± 0.7	2.4 ± 0.6	2.5 ± 1.2	2.6 ± 1.7	2.9 ± 1.3	2.0 ± 0.4

Data are mean ± SD; [a]$P<0.05$, [b]$P<0.01$ compared with placebo; Abbreviations: AEA, N-arachidonoylethanolamine; Apo, Apolipoprotein; BDI-II, Beck Depression Inventory-II; BMI, Body mass index; BP, blood pressure; HbA1c, glycosylated haemoglobin A1c; HDL, high density lipoprotein; HOMA2-IR, homeostatic assessment model 2 - insulin resistance; LDL-C, low density lipoprotein cholesterol; NEFA, non-esterified fatty acid; OEA, oleoylethanolamine; OGTT, oral glucose tolerance test; PEA, palmitoylethanolamine; TG; triglyceride, UC, ultracentrifugation; VLDL, very low density lipoprotein; 2-AG, 2-arachidonoylglycerol

Figure 2

A — Fasting Glucose
B — HOMA 2 Insulin B cell function
C — All patients
D — Diet/metformin patients
E — HbA1c (Diet/metformin patients only)

Figure 3

Variable	CBD		THCV		1:1 CBD:THCV		20:1 CBD:THCV		Placebo	
	Baseline	Treatment	Baseline	Treatment	Baseline	Treatment	Baseline	Treatment	Baseline	Treatment
CRP (ng/mL)	7073 ± 8345	7301 ± 7578	13915 ± 22142	6026 ± 5488	12369 ± 10425	18958 ± 19162	21166 ± 43390	8224 ± 6330	6369 ± 6217	10512 ± 10718
TNFα (pg/mL)	7.0 ± 1.6	7.0 ± 1.9	7.3 ± 1.4	7.1 ± 2.2	6.8 ± 2.5	7.2 ± 2.3	6.6 ± 2.4	6.9 ± 2.5	7.2 ± 2.6	7.0 ± 2.5
IL-6 (pg/mL)	3.9 ± 6.8	6.2 ± 8.0	12.5 ± 13.2	9.2 ± 9.5	4.3 ± 4.1	4.4 ± 4.8	6.9 ± 13.5	12.0 ± 20.5	4.0 ± 4.4	7.2 ± 11.8
GLP-1 (pg/mL)	16.7 ± 34.5	20.2 ± 25.3	22.1 ± 30.6	35.7 ± 51.9	18.5 ± 26.1	20.4 ± 25.9	20.2 ± 30.4	32.5 ± 33.7	24.0 ± 29.0	27.6 ± 33.0
GIP (pg/mL)	32.4 ± 15.0	54.0 ± 35.0	40.5 ± 18.6	36.1 ± 21.8	53.6 ± 27.6	49.5 ± 21.2	45.8 ± 27.2	53.3 ± 29.9	48.8 ± 21.4	45.7 ± 27.2
Ghrelin (pg/mL)	15.0 ± 22.5	15.4 ± 17.1	18.1 ± 17.0	14.7 ± 18.3	9.8 ± 15.8	8.0 ± 11.3	4.7 ± 10.6	7.0 ± 14.0	15.7 ± 21.3	12.9 ± 7.9
Leptin (pg/mL)	12010.6 ± 9319.0	13002.3 ± 10492.0	16075.9 ± 8760.4	16563.9 ± 14015.3	22477.5 ± 10035.1	22844.6 ± 12955.1	16608.9 ± 6863.7	17119.7 ± 7919.1	17095.4 ± 9477.2	21216.2 ± 16743.1
Adiponectin (pg/mL)	18682707.9 ± 14433872.3	17256334.9 ± 9657725.5	20057340.7 ± 8556371.9	23065791.7 ± 11645915.9	17726284.0 ± 11350339.9	15171832.9 ± 8668602.0	14291816.0 ± 4955302.0	16090325.8 ± 5955671.9	18579597 ± 10527661.9	15959291.4 ± 9591038.9
Resistin (pg/mL)	12466.8 ± 4380.0	11568.9 ± 4444.7	13635.9 ± 5074.5	13444.2 ± 4279.7	17249.7 ± 7303.0	16857.6 ± 4139.0	13202.9 ± 6962.1	11715.0 ± 3480.2	14801.8 ± 6873.7	14761.6 ± 6082.8
RBP-4 (ng/mL)	8874 ± 1186	9158 ± 1317	8692 ± 2186	9355 ± 1949	8653 ± 1311	8939 ± 1676	9177 ± 1732	8742 ± 1282	9436 ± 2108	8738 ± 1328
Orexin (ng/mL)	0.6 ± 0.3	0.7 ± 0.6	1.0 ± 0.6	1.0 ± 0.6	1.0 ± 0.5	0.8 ± 0.4	0.6 ± 0.5	0.8 ± 1.2	0.8 ± 0.4	0.8 ± 0.5
Ketones (mM)	0.1 ± 0.1	0.1 ± 0.1	0.1 ± 0.1	0.1 ± 0.1	0.2 ± 0.1	0.1 ± 0.0	0.1 ± 0.1	0.1 ± 0.0	0.1 ± 0.1	0.1 ± 0.1

Supplemental Table 1. Tertiary endpoint before (baseline) and after (treatment) 13 weeks of randomised treatment.

Supplemental Figure 1. Summary of Subject Global Impression of Change (SGIC) assessment responses. There was no significant effect of any treatment compared to placebo.

Supplemental Figure 2. Summary of Clinician Global Impression of Change (CGIC) (or Physician Global Impression of Change (PGIC) assessment responses. There was no significant effect of any treatment compared to placebo.

Efficacy and safety of Cannabidiol and Tetrahydrocannabivarin on glycaemic

and lipid parameters in patients with Type 2 diabetes: a randomised,

double-blind, placebo-controlled, parallel group pilot study

KA Jadoon[1], SH Ratcliffe[2], DA Barrett[3], EL Thomas[4], C Stott[6], JD Bell[4],

SE O'Sullivan[1*] and GD Tan[5*]

[1] Division of Medical Sciences & Graduate Entry Medicine, School of Medicine, University of Nottingham, Royal Derby Hospital Centre, Uttoxeter Road, Derby DE22 3DT, 01332724701.
[2] CogMaze Ltd, London SW5 9SX
[3] Centre for Analytical Bioscience, School of Pharmacy, University of Nottingham, Nottingham NG7 2RD
[4] Research Centre for Optimal Health, Department of Life Sciences, University of Westminster, London, W1W 6UW.
[5] The NIHR Oxford Biomedical Research Centre, Oxford Centre for Diabetes, Endocrinology & Metabolism, Churchill Hospital, Oxford University Hospitals NHS Trust, Oxford OX3 7LE
[6] GW Pharmaceuticals, Sovereign House, Vision Park, Histon, Cambridge CB24 9BZ

*These authors contributed equally to this paper

Corresponding author: saoirse.osullivan@nottingham.ac.uk

Short title: CBD and THCV in humans with type 2 diabetes

1

Abstract

Objective   Cannabidiol (CBD) and delta-9-tetrahydrocannabivarin (THCV) are non-psychoactive phytocannabinoids that affect lipid and glucose metabolism in animal models of metabolic function. This study set out to examine the effects of these compounds in patients with type 2 diabetes.

Research Design and Methods In this randomised, double-blind, placebo-controlled study, 62 subjects with non-insulin treated type 2 diabetes were enrolled and 39 were randomised to five treatment arms. These were CBD (100 mg twice daily), THCV (5 mg twice daily), 1:1 ratio of CBD and THCV (5 mg : 5 mg, twice daily), 20:1 ratio of CBD and THCV (100 mg : 5 mg, twice daily), or matched placebo, for 13 weeks. The remaining subjects were randomised to two other treatment arms not presented here. The primary endpoint was a change in HDL-cholesterol concentrations from baseline. Secondary/tertiary endpoints included changes in glycaemic control, lipid profile, insulin sensitivity, body weight, liver triglyceride content, adipose tissue distribution, appetite, markers of inflammation, markers of vascular function, gut hormones, circulating endocannabinoids and adipokine concentrations. Safety and tolerability endpoints were also evaluated.

Results   Compared with placebo, THCV significantly decreased fasting plasma glucose (estimated treatment difference (ETD)=-1.2mmol/L, $P<0.05$) and improved pancreatic β-cell function (homeostasis model assessment (HOMA2 B) (ETD = -44.51 points, $P<0.01$), adiponectin (ETD = -5.9 x 10^6 pg/mL, $P<0.01$) and apolipoprotein A (apoA) (ETD = -6.02μmol/L, $P<0.05$), although plasma HDL was unaffected. Compared to baseline (but not placebo), CBD decreased resistin (-898 pg/ml, $P<0.05$) and increased glucose-dependent insulinotropic peptide (21.9 pg/ml, $P<0.05$). None of

the combination treatments had a significant impact on endpoints. CBD and THCV were well tolerated.

Conclusions   THCV could represent a new therapeutic agent in glycaemic control in subjects with type 2 diabetes.

3

The endocannabinoid system (ECS) modulates food intake and energy homeostasis (1, 2) and chronic over-activation of the ECS has been identified in obesity and type 2 diabetes (3). The ECS exerts some of its actions by various components activating cannabinoid receptors 1 (CB_1) and 2 (CB_2). Modulation of CB_1 receptors with rimonabant (a synthetic cannabinoid) led to a significant reduction in body weight, waist circumference and triglyceride (TG) concentrations, and an increase in HDL-cholesterol and adiponectin concentrations (4), as well as a reduction in HbA1c in subjects with type 2 diabetes (- 0.8% to – 1.25%, $P<0.001$). However, marketing authorisation for rimonabant was withdrawn in 2008 because of an increased incidence of psychiatric adverse events (AEs) (5). Rimonabant is thought to be a CB_1 receptor antagonist/inverse agonist, but it is unclear whether modulation of other cannabinoid receptor activity could have beneficial metabolic effects without significant psychiatric effects.

Cannabidiol (CBD) is one of the major phytocannabinoids obtained from the *Cannabis sativa L.* plant. In rodent studies, CBD has multiple desirable effects in the context of hyperglycaemia, mainly through its anti-inflammatory and anti-oxidant properties (6-10). In animal models of obesity (*ob/ob* genetically obese mice), four weeks treatment with CBD 3mg/kg, produced a 55% increase in HDL-C concentration and reduced total cholesterol (total-C) by more than 25% (GW Pharma data on file). In addition, the same dose reduced liver triglycerides and increased both liver glycogen and adiponectin concentration. There is also evidence from animal studies showing that CBD modulates cardiovascular response to stress (11).

Unlike the related molecule Δ^9-tetrahydrocannabinol (THC), CBD does not activate CB_1 receptors in the brain and therefore lacks the psychotropic actions of THC. Indeed, CBD may reduce psychosis (12) and mitigate the psychoses associated with

cannabis misuse (13). Other receptor sites implicated in the actions of CBD include the orphan G-protein coupled receptor-55 (GPR55), the putative endothelial cannabinoid receptor (CB_e), the transient receptor potential vanilloid 1 (TRPV1) receptor, α1-adrenoceptors, μ opioid receptors, the adenosine transporter and serotonin-1A ($5-HT_{1A}$) receptors (14). CBD also activates and has physiological responses mediated by peroxisome proliferator activated receptor γ (PPARγ) (15,16, 17). A CBD/THC combination (Sativex®/Nabiximols) is currently licensed in most EU countries and in Canada, New Zealand, Australia, Malaysia, the United Arab Emirates and Kuwait, for the symptomatic treatment of spasticity in moderate to severe multiple sclerosis, and CBD alone (Epidiolex®) was granted orphan drug designation by the FDA in February 2014 in Dravet and Lennox-Gastaut syndromes in children, with Phase 3 clinical trials ongoing in those conditions.

Δ^9-tetrahydrocannabivarin (THCV) is a naturally occurring analogue of THC, but with different pharmacological effects. It is has been reported to behave as both a CB_1/CB_2 agonist and/or a CB_1/CB_2 neutral antagonist (20, 21, 22, 23,24), probably dose-dependent, with agonism observed at high doses and antagonism at low doses (21). However, there is little evidence of CB_1 agonsim *in vivo* compared with the observed *in vivo* effects of THC at similar doses. Other target sites of action include GPR55 (25) and transient receptor potential channels (26, 27).

Acute intraperitoneal administration of THCV in rodents at 3, 10 and 30 mg/kg body weight, caused hypophagia and weight loss, with food intake and body weight returning to normal on day 2 (18). The effect was similar to that of a CB_1 antagonist AM251, also used in the same study. In another study, involving diet-induced obese (DIO) mice, oral THCV (2.5 to 12.5 mg/kg) reduced body fat content, increased energy expenditure, and reduced fasting insulin and 30 min insulin response to oral

glucose tolerance test (OGTT) (19). In the same study, in genetically obese *(ob/ob)* mice, a similar increase in 24-hour energy expenditure was observed with 3mg/kg THCV, while 12.5 mg/kg THCV caused a significant reduction in liver triglycerides (19). In genetically obese mice (*ob/ob*), a 1:1 ratio of a combination of THCV and CBD (3 mg/kg : 3 mg/kg), while reducinged total cholesterol levels by 19% and, increased HDL-C by 50%. The same combination reduced liver TG, increased liver glycogen levels, reduced fasting insulin and increased energy expenditure (GW Pharma data on file).

The findings from these preclinical studies demonstrate a potential beneficial effect of both CBD and THCV, alone or in combination, in diabetes and lipid metabolism, with very distinct pharmacological profiles, and therefore different side effects, to rimonabant. This prompted the first ever investigation of the effects of CBD and THCV on dyslipidaemia and glycaemic control in subjects with type 2 diabetes.

Research Design and Methods

Subjects and study design

This randomised, double-blind, placebo-controlled, parallel-group, phase 2a proof-of-concept study was conducted at four United Kingdom centres. The protocol was reviewed and approved by the East Midlands - Leicester Multi Centre Research Ethics Committee (10/H0406/42) and local R&D departments as required, and was conducted in accordance with the Declaration of Helsinki. All subjects provided written informed consent.

Subjects aged 18 years or above with type 2 diabetes and HbA1c ≤10%

(86 mmol/mol), HDL-C ≤1.3mmol/L in females and ≤1.2mmol/L in males, and plasma

triglycerides ≤10mmol/L, were eligible. Subjects needed to either receive no oral

hypoglycaemic agents or take stable doses of pre-specified non-insulin glucose

lowering therapies (metformin, sulfonylurea, dipeptidyl peptidase-4 (DPP-4) inhibitor

or glucagon-like peptide-1 (GLP-1) therapy) for three months prior to screening.

Subjects not on statin therapy or on a stable dose of a statin, for at least four weeks

prior to randomisation, were eligible for inclusion. Subjects were also required not to

make any changes to their diet or exercise for four weeks prior to randomisation and

during the course of the study.

Main exclusion criteria (see supplemental data for full details) included use of

prohibited medications (insulin, fibrates, thiazolidinediones, therapeutic omega-3

fatty acids, alpha-glucosidase inhibitors), recent or current use of cannabis, history of

significant depression, planned travel outside the UK during the course of study,

genetic dyslipidaemia or significant cardiac, renal or hepatic impairment.

There was a one to five week period between screening (visit 1) and treatment

randomisation (visit 2). Visit 1 could be split into two separate visits (1A and B) to

allow a 21-day washout period of the prohibited medications prior to blood sampling

for eligibility. Remaining visits occurred 4, 8 and 13 weeks after initiation of treatment

(visits 3, 4 and 5, respectively), or earlier if patients withdrew. A safety follow up visit

occurred 7 days after study completion or withdrawal (visit 6). Visits 4 and 6 were

telephone assessments.

Patients were required to take study medication in the fasted state, twice daily, 30 minutes before breakfast and 30 minutes before evening meal, typically 12 hours apart for 13 weeks.

Study endpoints and assessments

The primary endpoint was change in mean serum HDL-C from baseline, in CBD and THCV groups, compared with the change in placebo group, at week 13. Secondary endpoints included changes in lipid profile, glycaemic control, insulin sensitivity, body weight, visceral adiposity, appetite and cardiovascular function. Tertiary endpoints were changes in markers of inflammation, vascular function, adipokines, endocannabinoids and gut hormone concentrations.

Serum lipid concentrations were analysed with the Roche modular system using enzymatic calorimetric assays. Non-esteriomatic fatty acid (NEFA) concentrations were quantified on the Roche COBAS 311 system, using an acyl-CoA synthetase/acyl-CoA oxidase (ACS-ACOD) method. Apolipoprotein markers were analysed on the Roche COBAS 311 system, using immunoturbidimetric assays, based on the principle of immunological agglutination. Plasma VLDL-C concentrations were determined by ultracentrifugation.

A standard 75 g OGTT was performed and plasma glucose and serum insulin were analysed using the Roche modular system and Advia Centaur immunoassay analyser respectively. HOMA-insulin resistance (IR), insulin sensitivity and β-cell function were calculated using the HOMA2 Calculator v2.2[©] (Diabetes Trials Unit, University of Oxford).

Plasma endocannabinoids, N-arachidonoylethanolamine (AEA), 2-arachidonoylglycerol (2-AG), oleoylethanolamine (OEA) and palmitoylethanolamine

(PEA), were analysed using liquid chromatography-tandem mass spectrometry, based on a previously published method (28). Ketones, orexin A and retinol binding protein (RBP) 4 were analysed using immunoassay, while all other tertiary endpoints including adiponectin, resistin, leptin, E-Selectin, vascular cell adhesion molecule (VCAM), Von Willebrand factor (vWF), C-reactive protein (CRP), interleukin (IL) 6, tumour necrosis factor (TNF) α, glucose-dependent insulinotropic peptide (GIP), ghrelin and GLP-1 were analysed by multiplex analysis, using commercially available kits (Milliplex™, HMHMAG-34K, HCVD1-67AK, HADK-1-61K-A, HCVD2-67BK, BPHCVD05-6, Merck Millipore®).

Resting blood pressure was measured using digital blood pressure monitor while cardiovascular parameters including systolic, diastolic and mean arterial pressure, heart rate, stroke volume, cardiac output, inter beat interval, ejection time and total peripheral resistance were measured using a Finometer® (Finapres Medical Systems), which uses a finger-clamp method to detect beat-to-beat changes in digital arterial diameter with an infrared photoplethysmograph.

Adipose tissue distribution was assessed using whole body magnetic resonance imaging (MRI); images were analysed by a blinded investigator using SliceOmatic™. Body weight and 7-point skin fold measures were also recorded. Hepatic TG concentration was assessed using magnetic resonance spectroscopy (MRS) and analysed using JMRUI software

Subject's Global Impression of Change (SGIC) and Clinician's Global Impression of Change (CGIC) was assessed using an ordinal 7-point Likert scale (1=very much improved to 7=very much worse). Changes in appetite were established using patients' scores of their appetites that they recorded on daily basis using an appetite

0-10 numerical rating scale (NRS), where 0=no appetite (don't feel hungry) and 10=maximum appetite (completely hungry all the time) (29). The change from mean baseline score (mean of seven days before start of treatment) was compared to the mean score from the last seven days on treatment (end of 13 weeks).

Safety assessments included reporting for adverse events (AEs) and serious adverse events (SAEs), recording vital signs, pre- and post-treatment laboratory sampling and electrocardiograms (ECG) and change from baseline in Beck Depression Inventory-II (BDI-II) scores.

The BDI-II questionnaire, an assessment for anxiety and depression, is a multiple choice, self-reported inventory, and is one of the most widely used and validated instruments for measuring severity of depression (30).

Statistical methods

An independent statistician produced a schedule for random treatment allocation which was held centrally and not divulged to any other person involved in the study until the database had been locked. Patients were randomly allocated to treatment groups in a 1:1:1 ratio, stratified by centre, according to the randomisation schedule. Study site staff identified the pack number to be dispensed to the subject at each of Visits 2 and 3 according to the randomisation schedule.

Analysis was performed using the intention-to-treat (ITT) population; all subjects who were randomised, received at least one dose of study medication and had on-treatment efficacy data. All statistical tests were two-sided at the 5% significance level. Between group differences and 95% confidence intervals (CI) were also calculated. The primary endpoint and the majority of secondary endpoints were analysed using analysis of covariance (ANCOVA) of the changes from baseline to

the end of treatment in the associated parameter, with the exception of the SGIC and CGIC, which were analysed with ordinal logistic regression using the cumulative proportional odds model. The parameter's baseline values were included as a covariate, and treatment was included as a factor. The tertiary variables were analysed using ANCOVA with baseline value as covariate and treatment group and gender as factors, or using pairwise Fisher's Exact test, as appropriate. The null hypothesis was one of no difference in the effects of any of the active treatments compared individually with placebo. As this study was a phase 2a proof of concept study, no formal sample size calculation was performed.

Changes from baseline in all the plasma markers were analysed *post hoc* using a paired t-test, and the glucose response to OGTT was analysed using repeated measures 2-way ANOVA.

Results

One hundred and twenty-five patients were screened and 62~~39~~ randomised to the three ~~five~~ treatment arms. ~~presented in this report. The remainder of the randomised subjects were randomised to two other treatment arms, 1:1 and 20:1 ratio combination of CBD and THCV, which will not be reported here.~~ The disposition of subjects enrolled is presented in Figure 1. Subjects were similar between treatment groups (Table 1) in terms of baseline characteristics.

Lipids

THCV had no effect on HDL-C concentrations (Table 2), but it increased Apo A concentrations compared with placebo from baseline to the end of treatment (from

48.5 to 49.1 µmol/L in the THCV vs. 47.3 to 43.9 µmol/L in the placebo group; $P<0.05$, Fig. 2A). THCV had no effect on LDL-C concentrations. CBD~~, on its own~~ alone and in combination with THCV, did not affect any of the lipid parameters~~CBD did not affect any of the lipid parameters~~ (Table 2).

Glycaemic Control

THCV reduced fasting plasma glucose concentration compared with placebo from baseline to the end of treatment (from 7.4 to 6.7 mmol/L in the THCV vs. 7.6 to 8.0 mmol/L in the placebo group, ETD = –1.24 ± 0.6 (SEM), $P<0.05$, Fig. 3A). In line with this, there was a significant increase in HOMA2 B in the THCV treatment group compared with placebo from baseline to the end of treatment (from 105.1 to 144.4 in the THCV group vs. 96.4 to 94.7 in the placebo group, ETD = 44.6 ± 16.1 (SEM), $P<0.01$, Table 2, Fig 3B). There was no significant difference in glucose response to OGTT at 2 hours. However, when compared with baseline, THCV significantly improved 3-hour blood glucose response ($P<0.05$, Fig 3C). CBD ~~on its own~~alone or in combination with THCV had no effect on glycaemic parameters (Table 2).

Vascular Function

Compared to placebo, CBD and THCV, alone~~on their own~~ and in combination, had no effect on cardiovascular parameters (Table 2), or plasma markers of vascular function ~~Neither THCV nor CBD treatment significantly affected any cardiovascular parameter or plasma markers of vascular function compared to placebo~~ (~~see~~ Supplementary data tTable 1~~Table 2~~).

Adipokines

There was an increase from baseline in adiponectin concentration in the THCV group and a reduction in placebo group; the treatment difference was statistically significant in favour of THCV treatment (ETD = -5.9 x 10^6 pg/mL, $P<0.01$, Fig. 3B). Plasma concentrations of leptin and resistin remained unchanged with THCV treatment. Compared with baseline rather than placebo, CBD caused a significant reduction in the concentration of resistin (-898 pg/mL, $P<0.05$, Fig. 3C), but had no effect on leptin or adiponectin. Subjects taking a combination of CBD and THCV had no change in adipokine levels (Supplementary data Table 1).

Markers of Inflammation

Both THCV and CBD, or their combination, had no significant effect on plasma markers of inflammation (CRP, TNF α and IL-6; supplementary data Table 1).

Gut Hormones

THCV, on its own and in combination with CBD, had no effect on the concentrations of gut signalling hormones including GLP-1, GIP and ghrelin (supplementary data Table 1).THCV had no effect on the concentrations of gut signalling hormones including GLP-1, GIP and ghrelin (supplementary data table 1). However, in a post-hoc analysis, for which post-treatment concentrations were compared with baseline (rather than placebo), CBD caused a significant increase in the concentration of GIP (21.2 pg/mL, $P<0.05$, Fig. 3D), without any effect on GLP-1 or ghrelin concentrations.

Body weight

Baseline mean body weight (kg ± SD) in the CBD, THCV, 1:1 CBD:THCV, 20:1 CBD:THCV and placebo groups were 97.1 ± 13.8, 98.3 ± 17.5, 100.7 ± 14.5, 100.5 ± 17.9 and 94.2 ± 19.1 respectively. There were no statistically significant

changeswere no statistically significant changes in anthropometric parameters including weight, waist circumference, waist to hip ratio and skin fold thickness in either any of the treatment groups (Table 2).

Visceral adiposity and liver triglycerides

There were no changes in visceral adiposity (Table 2) or liver TG (Table 2) as assessed by MRI/MRS in any of the treatment groups.

Appetite

There were no statistically significant differences in appetite, assessed by 0-10 NRS scores in both CBD and THCV groupsNone of the treatments had any significant impact on appetite as assessed by 0-10 NRS scores (Table 2).

PGIC and CGIC

A full summary of the PGIC and CGIC assessment responses is presented in Supplemental Figures 1 and 2. Analysis of these responses showed a treatment difference in favour of all the active treatments, to varying degrees, but most notably between the 1:1 CBD:THCV and placebo treatment groups on CGIC. There were reported improvements in seven out of 11 (63.6%) patients in the CGIC on 1:1 CBD:THCV treatment, compared withto only two of the 14 (14.3%) placebo patients, with a recorded improvement on CGIG. This translated to a statistically significant treatment effect of 1:1 CBD:THCV treatment compared withto placebo, with an odds ratio of 9.5429 (*P*<0.05) in the CGIC. No other statistically significant effects were calculated for any other active treatment in either assessment.

No statistically significant effects were noted in either assessment with both CBD and THCV (Supplemental Figures 1 and 2).

Endocannabinoids

There was no significant change in the levels of circulating AEA, 2-AG, OEA and PEA after 13 weeks of any treatment (Table 2).

Post hoc analysis in THCV group analysing glucose response t

o OGTT and changes in HbA1c

An improvement in glucose response to OGTT was noted in the THCV group at 3 h (see Fig 3C).~~.~~ ~~W~~when subjects on any form of diabetes treatment other than diet/metformin were excluded from analysis, this effect became more pronounced (*P*~~P~~<0.05 at 1 h and *P*<0.01 at 3 h; n=6, Fig 3D). In the same group of diet/metformin only patients, compared with placebo, a significant improvement in HbA1c was also ~~recorded~~ observed (*P*<0.05, Fig 3E~~. 4~~).

Safety

The study medication was well tolerated, with the majority of subjects experiencing AEs that were mild or moderate in severity. Treatment-emergent (all causality) AEs were reported by 11 of 13 (84.6%) subjects in the CBD group,~~ and~~ 11 of 12 (91.7%) in the THCV group, 7 of 11 (63.6%) in the 1:1 CBD:THCV group, 8 of 11 (66.7%) in the 20:1 CBD:THCV group, compared with 13 of 14 subjects (92.9%) receiving placebo.

The ~~most~~ more common treatment-related AE reported by subjects in all the ~~three~~ groups, except for 20:1 CBD:THCV, was decreased appetite (two subjects (15.4%) receiving CBD, four subjects (33.3%) receiving THCV, one subject (9.1%) receiving 1:1 CBD:THCV and two subjects (14.3%) receiving placebo). None of the subjects in 20:1 CBD:THCV group ~~reported reduction in their~~experienced an AE of decreased

appetite. ~~In addition, two~~ Two subjects reported diarrhoea with THCV, compared to no subjects in the placebo group. Two subjects (14.3%) on placebo also reported dizziness. All other treatment-related AEs were reported in individual subjects.

No deaths occurred during the study. There were two ~~serious adverse events~~SAEs in this study. One patient (8.3%) taking 20:1 CBD:THCV treatment experienced an SAE of myocardial infarction that was considered moderate in severity, had recovered by the end of study, and was not considered to be treatment related. One placebo patient experienced an SAE of myocardial ischaemia that was not considered to be treatment-related, was mild in severity and occurred on Day 92 of the study; the SAE was still ongoing at the end of the study.

~~In terms of measures of depression,~~ ~~Mm~~ean changes from screening to the end of treatment in BDI-II scores for the CBD, ~~and~~THCV and 1:1 CBD:THCV treatment groups were 0.85, ~~and~~0.58 and 0.27 points, respectively, which were not statistically significant from placebo (change from baseline of -0.08 points), and remained within the 'minimal depression' range for all treatments. The largest change from baseline to the end of treatment in BDI-II score was in the 20:1 CBD:THCV treatment group (4.91 points). While this remained in the 'minimal depression' bracket, it was statistically significant compared to placebo (ETD = +4.77, P<0.01).

Conclusions

The aim of this pilot study was to ~~establish~~ investigate the ~~efficacy~~ clinical effect and tolerability of two phytocannabinoids, THCV and CBD, alone~~on their own~~ and in combination, in subjects with type 2 diabetes and dyslipidaemia. THCV significantly decreased fasting plasma glucose, and increased β-cell function, adiponectin and

Apo A concentrations, and was well tolerated in patients. These findings suggest that THCV may represent a new therapeutic agent for glycaemic control in subjects with type 2 diabetes.

The ECS plays an important role in modulating energy intake and expenditure (for reviews, see 1, 2), and a chronically over active ECS may have a role in diabetes and its various complications (2). A recent cross-sectional study showed that marijuana use was associated with lower concentrations of fasting insulin, insulin resistance and waist circumference (31). Some of the favourable metabolic effects seen with smoking cannabis may be due to partial CB_1 agonists like THC, which may act as a functional antagonist in conditions of increased endocannabinoid tone like obesity, because of its lower CB_1 binding affinity and efficiacy in comparison to 2-AG, whose levels are elevated in visceral obesity (32). Rimonabant, a CB_1 receptor antagonist, was the first in its class to be used as anti-obesity drug, but led to significant psychiatric adverse events (5). Pre-clinical studies with the plant-derived compound THCV have shown that it produces hypophagia and weight reduction in lean mice (18) and improves glucose tolerance and insulin sensitivity in DIO mice (19). Similar results have been seen with CBD in *ob/ob* mice (GW Pharma data on file) and CBD has been reported to lower the incidence of diabetes in non-obese diabetic mice (33), and arrest the onset of autoimmune diabetes in non-obese diabetic mice (34). Given the positive metabolic effects of both THCV and CBD in preclinical studies and their potent anti-inflammatory and antioxidant properties (22,35,36), we decided to investigate, for the first time, their efficacy and tolerability in subjects with type 2 diabetes.

THCV Alone

THCV treatment alone had no effect on HDL-C concentration. It did, however, produce a significant rise in serum Apo A, when compared with placebo. Apo A makes 90% of HDL protein and constitutes an important structural component of the HDL particle. Apo A I, which accounts for 70% of the Apo A (the remaining 20% accounted for by Apo A II), plays an important role in reverse cholesterol transport (37). The significance of this result remains unclear.

THCV significantly reduced fasting blood glucose concentrations, improved HOMA2 B and improved the 3-hour blood glucose response to OGTT, without any significant difference in insulin response. These findings are in keeping with the recent animal data, where THCV improved fasting glucose and 30 min glucose response to OGTT, and also improved insulin sensitivity by reducing fasting and post glucose insulin concentrations (19). In the same study, THCV treatment improved insulin-induced phosphorylation of Akt (also known as protein kinase B) in insulin-resistant human hepatocytes and mice myotubes, suggesting improved insulin signalling as one of the possible mechanisms of action.

Although there was an improvement in fasting and 3-hour post OGTT blood glucose, there were no changes in body weight and gut hormone concentrations. In fact, a rise in the concentration of retinol binding protein 4 (RBP-4) was observed with THCV, an adipokine that has been associated with obesity and insulin resistance (38). Therefore the mechanism by which THCV improves glycaemic control remains unclear.

THCV significantly increased adiponectin concentrations. Adiponectin enhances hepatic insulin sensitivity, increases fatty acid oxidation and has important anti-

atherogenic properties. Its concentrations are reduced in obesity and type 2 diabetes (39).

Positive metabolic effects of THCV on glycaemic control and adiponectin concentrations were also seen with rimonabant, the first CB_1 antagonist to be licenced as anti-obesity medication that was later withdrawn from market due to increased incidence of psychiatric adverse events (5). It is, however, important to emphasize that while rimonabant consistently reduced body weight in all the reported randomised clinical trials, no such change was seen with THCV, suggesting clear differences in the mechanisms of action of these compounds. Recent animal data with THCV similarly showed no effect on body weight (19). Moreover, rimonabant improved the lipid profile (increased HDL-C and reduced TG levels), while THCV had no effect on lipid parameters in our study (40). There is also a clear difference in chemical structure between THCV and rimonabant. It is therefore reasonable to believe that THCV and rimonabant have different pharmacological and safety profiles. At micromolar concentrations, THCV inhibits the activity of both fatty acid amide hydrolase (FAAH) and monoacyl glycerol lipase (MAGL), thereby inhibiting the hydrolysis of AEA and 2-AG respectively (41). THCV, therefore, can act as an indirect agonist at the cannabinoid receptors, by enhancing the activity of the endocannabinoid system. Since such a change was not seen in our study, it is reasonable to believe that, at the dose tested, THCV was unable to modulate the endocannabinoid system. Recent animal data from Wargent and colleagues (19) showed that most of the positive metabolic effects of THCV were seen with 5 and 12.5 mg/kg doses given orally in rodents. In comparison to this, the dose used on our study (10 mg/day, approx. 0.1 mg/kg in humans) was much lower.

CBD Alone

Although CBD did not produce any effects on the primary and secondary efficacy outcomes compared with placebo, it reduced circulating resistin concentrations from baseline, while increasing the concentration of circulating GIP. Increased concentrations of resistin are associated with obesity and insulin resistance (42). GIP is one of the incretin hormones, produced by K cells in the proximal duodenum, which is known to have insulinotropic and pancreatic β-cell preserving properties (43). Despite having positive effects on resistin and GIP, CBD did not produce any improvement in glycaemic control.

CBD is known for its indirect agonism at the CB_1 receptors, by either increasing CB_1 constitutional activity or the endocannabinoid tone. CBD has been reported to inhibits hydrolysis of AEA by FAAH (but only at high micromolar levels) and also increases 2-AG levels (39). In a recent clinical study, in subjects with schizophrenia, 800 mg per day of CBD treatment significantly increased serum AEA levels and was associated with an improvement in clinical profile of these subjects (12). In our study, CBD (albeit at a much lower dose), alone or in combination with THCV, had no effect on the plasma levels of endocannabinoids, suggesting that it had minimal interaction with the endocannabinoid system at the doses investigated.

Studies in rodents have used intraperitoneal CBD in a dose ranging from 1 mg/kg/day to 20 mg/kg/day, with positive effects on the metabolism seen only with higher dose ranges (7, 8, 9). In a 70 kg individual, a 20 mg/kg/day dose equates to 1400 mg/day. Similarly, human studies have used CBD in higher doses (12, 44). The dose used in our study was 200 mg/day, which could possibly explain lack of therapeutic effects seen with CBD.

Combination of CBD and THCV

Except for an improvement in CGIC assessments with 1:1 CBD:THCV treatment, none of the efficacy parameters were affected by 1:1 or 20:1 combination of CBD and THCV. There was a trend towards an improvement in most lipid parameters and the overall incidence of all-causality treatment related AEs was lowest ~~with~~in the 1:1 CBD:THCV treatment group~~, and~~; these factors could have led to an impression of improvement in subjects' overall condition with this treatment. While the combination of CBD and THCV did not produce any favourable effects on any of the parameters, the favourable effects of THCV were also lost in the combination treatment. Similarly, the positive effects of CBD on GIP and resistin were not seen in any of the combination treatments. This suggests that CBD and THCV in combination may counteract their individual therapeutic effects at least in the ratios and doses tested in this study. This~~It~~ may be at the level of receptors or due to interference with each other's metabolism or therapeutic half-life, and requires further investigation.

Safety

Both CBD and THCV were well tolerated, with the majority of patients experiencing AEs that were mild in severity. The most common AE was reduced appetite with similar incidence across all the treatment groups. There were no reports of depression and no clinically significant abnormalities on ECG and laboratory results including blood count, liver and renal biochemistry in any treatment groups. There was ~~only~~ one SAE of myocardial ischaemia in the placebo group, and one SAE of myocardial infarction in the 20:1 CBD:THCV group~~;~~ both were considered unrelated to study medication. ~~which was considered to be unrelated to study medication but was ongoing at the end of the study, having occurred on the day of the last dose of study medication (Day 92).~~ With regards to the BDI-II scale, though the change in 20:1 CBD:THCV treatment group was statistically significant, all mean active

treatments and placebo scores remained in the 'minimal depression' range~~, which is a reassuring finding~~.

Conclusion

In this clinical study, the first to study the effects of CBD and THCV in subjects with type 2 diabetes and dyslipidaemia, THCV improved glycaemic control, and therefore warrants further investigation in this therapeutic area. CBD failed to show any detectable metabolic effects despite producing desirable changes in some adipokines and gut hormone concentrations. The incidence of AEs was similar between treatment groups ~~(no difference to placebo)~~, and both CBD and THCV were well tolerated. No new safety concerns were identified in the study.

Conflicts of interest and source of funding

Acknowledgements

Author Contributions:

Figure legends

Figure 1. Summary of breakdown of patients enrolled in the study. 125 subjects were screened and ~~39~~ 62 randomi~~z~~sed to this study. ~~The remaining subjects were randomized to two other treatment arms, the data for which is not presented here.~~

Figure 2. Compared with placebo, THCV alone caused a significant improvement in the concentration of Apo A ($P<0.05$; A) and adiponectin ($P<0.01$; B). ~~CBD had no effect on Apo A (A) or adiponectin (B).~~ Data was analysed by analysis of covariance and presented as mean ± SEM. CBD caused a significant reduction in resistin ($P<0.05$; C) and an increase in GIP concentration ($P<0.05$; D), when compared with pre-treatment values. Data were analysed *post hoc* using paired t-test and presented as mean ± SEM.

Figure 3. ~~THCV caused significant improvement in 3 hour glucose response during OGTT (P<0.05; A), when compared with pre-treatment values, while CBD had no effect on glucose tolerance (B). No significant change was observed in insulin response to OGTT with THCV (C) or CBD (D).~~ Compared with placebo, THCV alone caused significant improvement in fasting glucose ($P<0.05$; A~~E~~) and in keeping with this, there was a highly significant improvement in β cell function measured by HOMA2 ($P<0.01$; B~~F)~~). THCV caused significant improvement in 3 hour glucose response during OGTT ($P<0.05$; C~~A~~), when compared with pre-treatment values.~~,~~ ~~while CBD had no effect on glucose tolerance (B). No significant change was observed in insulin response to OGTT with THCV (C) or CBD (D).~~

~~CBD had no effect on fasting glucose (E) or β cell function (F).~~ Data were analysed using 2-~~-~~way ANOVA and presented as mean ± SEM. (D) Compared with pre-treatment values, there was a highly significant improvement in 3 hour glucose response to OGTT with THCV, when subjects on any oral hypoglycaemic therapy

other than diet and/or metformin were excluded from analysis ($P<0.01$, A, n=6). In the same subgroup (analysed post hoc), compared with placebo, there was a statistically significant improvement in HbA1c ($P<0.05$, EB). Data were analysed *post hoc* using repeated measures 2 way ANOVA and paired t-test respectively and presented as mean ± SEM.

Figure 4. Compared with pre-treatment values, there was a highly significant improvement in 3 hour glucose response to OGTT with THCV, when subjects on any oral hypoglycaemic therapy other than diet and/or metformin were excluded from analysis ($P<0.01$, A, n=6). In the same subgroup (analysed post hoc), compared with placebo, there was a statistically significant improvement in HbA1c ($P<0.05$, B). By contrast, CBD had no effect on glucose tolerance (C) or HbA1c (D) in this subgroup of patients (n=9). Data were analysed *post hoc* using repeated measures 2 way ANOVA and paired t-test respectively and presented as mean ± SEM.

References

1. Silvestri C, Ligresti A, Di Marzo V. Peripheral effects of the endocannabinoid system in energy homeostasis: adipose tissue, liver and skeletal muscle. Rev Endocr Metab Disord 2011;12:153-162.

2. Horvath B, Mukhopadhyay P, Hasko G, Pacher P. The endocannabinoid system and plant-derived cannabinoids in diabetes and diabetic complications. Am J Pathol 2012;180:432-442.

3. Di Marzo V. The endocannabinoid system in obesity and type 2 diabetes. Diabetologia 2008;51:1356-1367.

4. Christopoulou FD, Kiortsis DN. An overview of the metabolic effects of rimonabant in randomized controlled trials: potential for other cannabinoid 1 receptor blockers in obesity. J Clin Pharm Ther 2011;36:10-18.

5. Le Foll B, Gorelick DA, Goldberg SR. The future of endocannabinoid-oriented clinical research after CB1 antagonists. Psychopharmacology (Berl) 2009;205:171-174.

6. Rajesh M, Mukhopadhyay P, Batkai S, Hasko G, Liaudet L, Drel VR, Obrosova IG, Pacher P. Cannabidiol attenuates high glucose-induced endothelial cell inflammatory response and barrier disruption. Am J Physiol Heart Circ Physiol 2007;293:H610-H619.

7. El-Remessy AB, Al-Shabrawey M, Khalifa Y, Tsai NT, Caldwell RB, Liou GI. Neuroprotective and blood-retinal barrier-preserving effects of cannabidiol in experimental diabetes. Am J Pathol 2006;168:235-244.

8. Toth CC, Jedrzejewski NM, Ellis CL, Frey WH. Cannabinoid-mediated modulation of neuropathic pain and microglial accumulation in a model of murine type I diabetic peripheral neuropathic pain. Mol Pain 2010;6:16.

9. Rajesh M, Mukhopadhyay P, Batkai S, Patel V, Saito K, Matsumoto S, Kashiwaya Y, Horvath B, Mukhopadhyay B, Becker L, Hasko G, Liaudet L, Wink DA, Veves A, Mechoulam R, Pacher P. Cannabidiol attenuates cardiac dysfunction, oxidative stress, fibrosis, and inflammatory and cell death signaling pathways in diabetic cardiomyopathy. J Am Coll Cardiol 2010;56:2115-2125.

10. Stanley CP, Wheal AJ, Randall MD, O'Sullivan SE. Cannabinoids alter endothelial function in the Zucker rat model of type 2 diabetes. Eur J Pharmacol 2013;720:376-382.

11. Resstel LB, Tavares RF, Lisboa SF, Joca SR, Correa FM, Guimaraes FS. 5-HT1A receptors are involved in the cannabidiol-induced attenuation of behavioural and cardiovascular responses to acute restraint stress in rats. Br J Pharmacol. 2009;156:181-8.

12. Leweke FM, Piomelli D, Pahlisch F, Muhl D, Gerth CW, Hoyer C, Klosterkotter J, Hellmich M, Koethe D. Cannabidiol enhances anandamide signaling and alleviates psychotic symptoms of schizophrenia. Transl Psychiatry. 2012;2:e94

13. Schubart CD, Sommer IE, van Gastel WA, Goetgebuer RL, Kahn RS, Boks MP. Cannabis with high cannabidiol content is associated with fewer psychotic experiences. Schizophr Res 2011;130:216-221.

14. Pertwee RG. The diverse CB1 and CB2 receptor pharmacology of three plant cannabinoids: delta9-tetrahydrocannabinol, cannabidiol and delta9-tetrahydrocannabivarin. Br J Pharmacol 2008;153:199-215.

15. O'Sullivan SE, Sun Y, Bennett AJ, Randall MD, Kendall DA. Time-dependent vascular actions of cannabidiol in the rat aorta. Eur J Pharmacol 2009;612:61-8.

16. Esposito G, Scuderi C, Valenza M, Togna GI, Latina V, De Filippis D, Cipriano M, Carratu MR, Iuvone T, Steardo L. Cannabidiol reduces Aβ-induced neuroinflammation and promotes hippocampal neurogenesis through PPARγ involvement. PLoS One 2011;6:e28668.

17. De Filippis D, Esposito G, Cirillo C, Cipriano M, De Winter BY, Scuderi C, Sarnelli G, Cuomo R, Steardo L, De Man JG, Iuvone T. Cannabidiol reduces intestinal inflammation through the control of neuroimmune axis. PLoS One 2011;6:e28159.

18. Riedel G, Fadda P, McKillop-Smith S, Pertwee RG, Platt B, Robinson L. Synthetic and plant-derived cannabinoid receptor antagonists show hypophagic properties in fasted and non-fasted mice. Br J Pharmacol 2009;156:1154-1166.

19. Wargent ET, Zaibi MS, Silvestri C, Hislop DC, Stocker CG, Stott CG, Guy GW, Duncan M, Di Marzo V, Cawthorne MA. The cannabinoid Delta(9)-tetrahydrocannabivarin (THCV) ameliorates insulin sensitivity in two mouse models of obesity. Nutr Diabetes 2013;3:e68

20. Thomas A, Stevenson LA, Wease KN, Price MR, Baillie G, Ross RA, Pertwee RG. Evidence that the plant cannabinoid delta 9-tetrahydrocannabivarin is a cannabinoid CB1 and CB2 receptor antagonist. Br J Pharmacol 2005;146:917-926.

21. Pertwee RG, Thomas A, Stevenson LA, Ross RA, Varvel SA, Litchman AH, Martin BR, Razdan RK. The psychoactive plant cannabinoid, delta 9-

tetrahydrocannabinol, is antagonized by delta 8- and delta 9-

tetrahydrocannabivarin in mice in vivo. Br J Pharmacol 2007;150:586-594.

22. Bolognini D, Costa B, Maione S, Comelli F, Marini P, Di Marzo V, Parolaro D,

    Ross RA, Gauson LA, Cascio MG, Pertwee RG. The plant cannabinoid Delta

    9-tetrahydrocannabivarin can decrease signs of inflammation and

    inflammatory pain in mice. Br J Pharmacol 2010;160:677-687.

23. Hill AJ, Weston SE, Jones NA, Smith I, Bevan SA, Williamson EM, Stephens

    GJ, Williams CM, Whalley BJ. Delta 9-tetrahydrocannabivarin suppresses in

    vitro epileptiform and in vivo seizure activity in adult rats. Epilepsia

    2010;51:1522-1532.

24. Batkai S, Mukhopadhyay P, Horvath B, Rajesh M, Gao RY, Mahadevan A,

    Amere M, Battista N, Litchman AH, Gauson LA, Maccarrone M, Pertwee RG,

    Pacher P. Delta 8-tetrahydrocannabivarin prevents hepatic

    ischaemia/reperfusion injury by decreasing oxidative stress and inflammatory

    responses through cannabinoid CB2 receptors. Br J Pharmacol

    2012;165:2450-2461.

25. Anavi-Goffer S, Baillie G, Irving AJ, Gertsch J, Greig IR, Pertwee RG, Ross

    RA. Modulation of L-alpha-lysophosphatidylinositol/GPR55 mitogen-activated

    protein kinase (MAPK) signaling by cannabinoids. J biol chem 2012;287:91-

    104.

26. De Petrocellis L, Ligresti A, Moriello AS, Allara M, Bisogno T, Petrosino S,

    Stott CG, Di Marzo V. Effects of cannabinoids and cannabinoid-enriched

    Cannabis extracts on TRP channels and endocannabinoid metabolic

    enzymes. Br J Pharmacol 2011;163:1479-1494.

27. De Petrocellis L, Orlando P, Moriello AS, Aviello G, Stott C, Izzo AA, Di Marzo V. Cannabinoid actions at TRPV channels: effects on TRPV3 and TRPV4 and their potential relevance to gastrointestinal inflammation. Acta Physiol (Oxf) 2012;204:255-266.

28. Richardson D, Ortori CA, Chapman C, Kendall DA, Barrett DA. Quantitative profiling of endocannabinoids and related compounds in rat brain using liquid chromatography-tandem electroscopy ionisation mass spectrometry. Anal Biochem 2007;360:216-226

29. Flint A, Raben A, Blundell JE, Astrup A. Reproducibility, power and validity of visual analogue scales in assessment of appetite sensations in single test meat studies. Int J Obes Relat Metab Disord. 2000;24:38-48

30. Endler NS, Rutherford A, Denisoff E. Beck depression inventory: exploring its dimensionality in a nonclinical population. J Clin Psychol. 1999;55:1307-1312.

31. Penner EA, Buettner H, Mittleman MA. The impact of marijuana use on glucose, insulin, and insulin resistance among us adults. Am J Med 2013;126:583-589

32. Le Foll B, Trigo JM, Sharkey KA, Le Strat Y. Cannabis and delta9-tetrahydrocannabinol (THC) for weight loss? Med Hypotheses 2013;80:564-567.

33. Weiss L, Zeira M, Reich S, Har-Noy M, Mechoulam R, Slavin S, Gallily R. Cannabidiol lowers incidence of diabetes in non-obese diabetic mice. Autoimmunity 2006;39:143-151

34. Weiss L, Zeira M, Reich S, Slavin S, Raz I, Mechoulam R, Gallily R.
Cannabidiol arrests onset of autoimmune diabetes in NOD mice.
Neuropharmacology 2008;54:244-249

35. Costa B, Colleoni M, Conti S, Parolaro D, Franke C, Trovato AE, Giagnoni G.
Oral anti-inflammatory activity of cannabidiol, a non-psychoactive constituent
of cannabis, in acute carrageenan-induced inflammation in the rat paw.
Naunyn Schmiedebergs Arch Pharmacol 2004;369:294-299.

36. Lastres-Becker I, Molina-Holgado F, Ramos JA, Mechoulam R, Fernandez-
Ruiz J.Cannabinoids provide neuroprotection against 6-hydroxydopamine
toxicity in vivo and in vitro: relevance to Parkinson's disease. Neurobiol
Dis 2005;19:96-107

37. Barter PJ. Hugh sinclair lecture: the regulation and remodelling of HDL by
plasma factors. Atheroscler Suppl. 2002;3:39-47.

38. Christou GA, Tselepis AD, Kiortsis DN. The metabolic role of retinol binding
protein 4: an update. Horm Metab Res 2012;44:6-14.

39. Whitehead JP, Richards AA, Hickman IJ, Macdonald GA, Prins JB.
Adiponectin--a key adipokine in the metabolic syndrome. Diabetes Obes
Metab. 2006;8:264-280.

40. Christopoulou FD, Kiortsis DN. An overview of the metabolic effects of
rimonabant in randomized controlled trials: potential for other cannabinoid 1
receptor blockers in obesity. J Clin Pharm Ther 2011;36:10-18.

41. McPartland JM, Duncan M, Di Marzo V, Pertwee RG. Are cannabidiol and
Δ(9)- tetrahydrocannabivarin negative modulators of the endocannabinoid
system? A systematic review. Br J Pharmacol. 2015;172:737-753

42. Steppan CM, Bailey ST, Bhat S, Brown EJ, Banerjee RR, Wright CM, Patel HR, Ahima RS, Lazar MA. The hormone resistin links obesity to diabetes. Nature 2001;409:307-312.

43. Irwin N, Flatt PR. Evidence for beneficial effects of compromised gastric inhibitory polypeptide action in obesity-related diabetes and possible therapeutic implications. Diabetologia. 2009;52:1724-1731

44. Bergamaschi MM, Queiroz RH, Chagas MH, de Oliveira DC, De Martinis BS, Kapczinski F, Quevedo J, Roesler R, Schroder N, Nardi AE, Martin-Santos R, Hallak JE, Zuardi AW, Crippa JA. Cannabidiol reduces the anxiety induced by simulated public speaking in treatment-naïve social phobia patients. Neuropsychopharmacology 2011;36:1219-1226

Participating Centres

1. Division of Medical Sciences & Graduate Entry Medicine, School of Medicine, University of Nottingham, Royal Derby Hospital Centre, Uttoxeter Road, Derby DE22 3DT

2. MAC Clinical Research. Manchester M32 0UT

3. Woolpit Health Centre, Heath Road, Woolpit, Bury St Edmunds, Suffolk, IP30 9QU

4. Mount Farm Surgery, Lawson Place, Bury St Edmunds, Suffolk, IP32 7EW

Screened (n=125)
Randomised (n=62)

CBD (n=13)	THCV (n=12)	1:1 CBD:THCV (n=11)	20:1 CBD:THCV (n=12)	Placebo (n=14)
Withdrew (n=1) Met withdrawal criteria (n=1)	Withdrew (n=2) Adverse event (n=2)	Withdrew (n=0)	Withdrew (n=2) Adverse event (n=2)	Withdrew (n=1) Withdrawn by investigator (n=1)
Completed (n=12)	Completed (n=10)	Completed (n=11)	Completed (n=10)	Completed (n=1)
Analysis (n=13)	Analysis (n=10)	Analysis (n=11)	Analysis (n=12)	Analysis (n=14)

Screened (n=125)
Randomised (n=62)

CBD (n=13)	THCV (n=12)	1:1 CBD:THCV (n=11)	20:1 CBD:THCV (n=12)	Placebo (n=14)
Withdrew (n=1) Met withdrawal criteria (n=1)	Withdrew (n=2) Adverse event (n=2)	Withdrew (n=0)	Withdrew (n=2) Adverse event (n=2)	Withdrew (n=1) Withdrawn by investigator (n=1)
Completed (n=12)	Completed (n=10)	Completed (n=11)	Completed (n=10)	Completed (n=13)
Analysis (n=13)	Analysis (n=10)	Analysis (n=11)	Analysis (n=12)	Analysis (n=14)

Formatted: citation, Font: 12 pt, Bold, English (U.K.), Check spelling and grammar

Figure 1

Table 1. Summary of patient demographics and concomitant therapy.

	CBD (n=13)	THCV (n=12)	1:1 CBD:THCV (n=11)	20:1 CBD:THCV (n=12)	Placebo (n=14)	Total (n=62)
Male (number of subjects and (%))	10 (77)	10 (83)	6 (55)	9 (75)	7 (50)	42 (68)
Female (number of subjects and (%))	3 (23)	2 (17)	5 (45)	3 (25)	7 (50)	20 (32)
Age- (years, **Mean (SD)**)	56.8 (9.9)	62.5 (12.6)	59.3 (8.8)	58.0 (8.1)	58.6 (7.7)	59.0 (9.4)
Weight (kg, **Mean (SD)**)	97.2 (13.8)	98.3 (17.5)	100.7 (14.5)	100.5 (17.9)	94.2 (19.1)	98.0 (16.4)
BMI (kg/m^2 **Mean (SD)**)	33.2~~3~~ (5.4)	34.0 (6.5)	36.4 (5.6)	35.4 (4.6)	33.4 (7.0)	34.4(5.~~9~~8)
Duration since diagnosis of diabetes (years, **Mean (SD)**)	2.8 (3.3)	4.8 (3.6)	4.4 (2.7)	5.1 (3.3)	3.8 (3.5)	4.2 (3.3)
Number~~.~~ (~~percentage~~%) of patients on anti-diabetic and lipid lowering therapy						
Metformin	9 (69)	9 (75)	10 (91)	11 (92)	12 (86)	51 (82)
DPP-4 Inhibitors	1 (8)	1 (8)	1 (9)	1 (8)	1 (7)	5 (8)
Sulfonylureas	3 (23)	5 (42)	4 (36)	3 (25)	4 (29)	19 (31)
Statins	9 (69)	11 (92)	10 (91)	8 (67)	13 (93)	51 (82)

Table 2. Clinical data before (baseline) and after (treatment) 13 weeks of randomised treatment

Variable	CBD (n=13)		THCV (n=12)		1:1 CBD : THCV (n=11)		20:1 CBD : THCV (n=12)		Placebo (n=14)	
	Baseline	Treatment	Baseline	Treatment	Baseline	Treatment	Baseline	Treatment	Baseline	Treatment
HDL-C (mmol/l)	1.0 ± 0.3	1.0 ± 0.3	1.1 ± 0.1	1.1 ± 0.2	1.0 ± 0.2	1.0 ± 0.3	1.0 ± 0.1	1.0 ± 0.1	1.0 ± 0.3	1.0 ± 0.2
Total-C (mmol/l)	4.5 ± 1.00.9	4.3 ± 0.7	3.8 ± 0.9	3.7 ± 0.11.0	4.2 ± 1.12	3.84 ± 0.71.0	4.6 ± 0.9	4.2 ± 0.6	4.0 ± 0.78	3.9 ± 0.9
LDL-C (mmol/l)	2.5 ± 0.78	2.4 ± 0.6	2.0 ± 0.6	2.0 ± 0.8	2.2 ± 1.00.8	2.0 ± 0.5	2.8 ± 0.6	2.5 ± 0.5	2.2 ± 0.6	2.2 ± 0.7
HDL:LDL-C ratio	0.5 ± 0.2	0.4 ± 0.2	0.6 ± 0.3	0.6 ± 0.3	0.5 ± 0.2	0.6 ± 0.2	0.4 ± 0.1	0.4 ± 0.1	0.5 ± 0.1	0.5 ± 0.1
UC VLDL-C (mmol/l)	0.8 ± 0.4	1.04 ± 0.5	1.0 ± 0.7	0.9 ± 0.7	1.0 ± 0.5	1.0 ± 0.4	1.1 ± 0.4	1.0 ± 0.3	1.0 ± 0.5	0.9 ± 0.4
Triglycerides (mmol/l)	2.23 ± 1.4	2.3 ± 1.3	1.7 ± 1.1	1.8 ± 1.5	2.45 ± 1.6	2.2 ± 1.2	1.9 ± 0.78	1.9 ± 0.7	2.1 ± 1.4	2.0 ± 1.1
Apo A (µmol/l)	48.6 ± 9.7	43.6 ± 6.6	48.5 ± 7.0	**49.1 ± 6.4[b]**	48.7 ± 11.1	46.8 ± 7.45	48.7 ± 10.0	45.7 ± 6.3	47.3 ± 8.8	43.9 ± 7.2
Apo B (µmol/l)	3.1 ± 0.8	3.3 ± 0.7	2.6 ± 0.6	2.7 ± 1.0	3.0 ± 0.9	2.9 ± 0.7	3.4 ± 0.7	3.4 ± 0.6	2.9 ± 0.7	3.0 ± 0.6
Apo B:Apo A ratio	0.6 ± 0.2	0.7 ± 0.2	0.5 ± 0.1	**0.5 ± 0.2[a]**	0.6 ± 0.2	0.6 ± 0.2	0.7 ± 0.2	0.7 ± 0.12	0.6 ± 0.2	0.7 ± 0.1
NEFA (mmol/l)	0.6 ± 0.23	0.5 ± 0.3	0.6 ± 0.1	0.6 ± 0.2	0.7 ± 0.3	0.67 ± 0.2	0.7 ± 0.2	0.6 ± 0.2	0.6 ± 0.2	0.6 ± 0.2

|										
Liver TG (%)	26.97 ± 176.19	22.2 ± 17.1	11.97 ± 8.20	14.01.5 ± 135.5	33.3 ± 18.3	32.2 ± 26.23	23.2 ± 14.3	25.4 ± 17.4	20.5 ± 15.1	18.5 ± 15.4
Fasting glucose (mmol/l)	8.0 ± 2.3	8.4 ± 2.8	7.4 ± 2.3	**6.7 ± 1.9**[b]	8.5 ± 2.5	8.97 ± 2.0	8.4 ± 2.8	8.8 ± 3.1	7.6 ± 1.4	8.0 ± 1.6
Fructosamine (µmol/l)	259.5 ± 34.4	256.8 ± 44.6	238.2 ± 25.0	239.3 ± 28.7	254.4 ± 35.7	256.0 ± 55.2	253.3 ± 34.8	268.8 ± 58.2	241.4 ± 19.3	253.7 ± 32.0
HbA1c (%)	6.9 ± 0.9	7.0 ± 1.1	6.6 ± 0.6	6.5 ± 0.7	7.21 ± 1.21	7.4 ± 1.5	7.2 ± 1.00.9	7.3 ± 1.3	7.0 ± 0.7	7.3 ± 1.0
Glucose - 2 h OGTT (mmol/l)	7.4 ± 2.43	6.6 ± 2.7	5.7 ± 3.10	6.21 ± 2.7	8.7 ± 3.8	8.8 ± 2.5	5.6 ± 3.4	6.6 ± 2.3	7.9 ± 2.6	8.4 ± 2.2
Insulin - 2 h OGTT (pmol/l)	604.1 ± 605.2	454.8 ± 387.5	661.0 ± 381.2	724.9 ± 589.6	53178 9.5 ± 551.56 77.2	602.39 00.2 ± 578.88 75.8	604.86 59.3 ± 638.05 70.4	491.86 51.6 ± 502.37 30.0	653.6 ± 381.5	619.7 ± 455.3
Fasting insulin (pmol/l)	110.3 ± 42.8	123.8 ± 60.8	152.9 ± 94.2	203.5 ± 197.7	175.3 ± 86.1	185.7 ± 67.6	197.6 ± 107.9	192.2 ± 69.1	171.7 ± 105.0	179.7 ± 75.7
C-peptide (nmol/l)	0.9 ± 0.2	0.9 ± 0.2	1.0 ± 0.3	1.1 ± 0.5	1.2 ± 0.2	1.2 ± 0.3	1.1 ± 0.3	1.2 ± 0.3	1.0 ± 0.4	1.1 ± 0.4
HOMA2-IR	2.3 ± 1.00.9	2.6 ± 1.5	3.0 ± 1.9	3.8 ± 3.3	3.5 ± 1.6	3.7 ± 1.3	4.2 ± 12.9	4.0 ± 1.5	3.4 ± 2.1	3.6 ± 1.5
HOMA2 insulin sensitivity	51.3 ± 20.1	53.0 ± 36.2	47.3 ± 32.4	53.5 ± 44.3	34.9 ± 17.1	31.20.4 ± 13.512.9	30.2 ± 11.4	28.9 ± 11.5	42.4 ± 29.2	37.8 ± 32.2
HOMA2 B cell function	70.9 ± 27.2	69.6 ± 31.5	105.1 ± 64.7	**144.4 ± 110.3**[c]	95.7 ± 50.7	87.593.8 ± 467.5	103.7 ± 60.67	97.9 ± 50.5	96.4 ± 41.4	94.7 ± 39.2
BMI (kg/m²)	33.2 ± 5.4	33.0 ± 4.9	34.0 ± 6.5	33.8 ± 6.7	36.4 ± 5.6	36.1 ± 5.7	35.4 ± 4.6	35.4 ± 4.4	33.4 ± 7.0	32.9 ± 7.7

Waist circumference (cm)	107.7 ± 10.8	108.0 ± 10.6	115.3 ± 13.~~2~~1	114.9 ± 13.8	115.4 ± 9.5	116.2 ± 11.8	113.7 ± 13.1	113.5 ± 12.1	109.2 ± 13.0~~1~~	108.4 ± 13.1
Waist-to-hip ratio	1.0 ± 0.05~~1~~	1.0 ± 0.1	1.0 ± 0.05~~1~~	1.0 ± 0.06~~1~~	1.0 ± 0.1	1.0 ± 0.05~~1~~	1.0 ± 0.1	1.0 ± 0.1	1.0 ± 0.1	1.0 ± 0.1
Neck circumference (cm)	42.4 ± 3.3	42.1 ± 3.7	42.8 ± 3.8	42.8 ± 3.6	42.7 ± 3.3	42.2 ± 3.8	42.8 ± 3.6	42.5 ± 4.0	41.7 ± 4.8	41.1 ± 4.8
Visceral abdominal fat (l)	8.1 ± 1.9	8.5 ± 2.2	9.1 ± 3.5~~6~~	9.0 ± 3.5	~~7.7~~8.5 ± ~~3.0~~2.3	~~7.8~~8.6 ± 2.7~~0~~	9.1~~8.6~~ ± 2.5	~~9.6~~10.2 ± 2.2~~7~~	7.2 ± 2.4	7.5 ± 3.4
Appetite 0-10 NRS score	5.8~~6~~ ± 1.0~~4~~	4.9 ± 1.0	5.1~~4~~ ± 1.7	~~4.9~~5.0 ± 1.7~~5~~	~~3.9~~4.7 ± 1.2~~0~~	3.7~~6~~ ± 1.6	~~4.8~~5.0 ± 2.2~~1~~	4.1~~3.9~~ ± 2.1~~1.9~~	4.7~~1~~5.1 ± 1.3~~1~~	4.5~~4~~ ± 1.5~~3~~
Systolic BP (mmHg)	133.4 ± 16.4	132.2 ± 13.0	135.9 ± 13.4	132.8 ± 17.1	126.4 ± 11.6	134.3 ± 12.8	132.7 ± 11.0	134.2 ± 14.8	137.2 ± 11.9	140.4 ± 11.2
Diastolic BP (mmHg)	70.1 ± 8.8	70.6 ± 8.8	70.6 ± 12.2	71.0 ± 9.4	73.2 ± 6.8	77.5 ± 7.7	73.5 ± 10.4	72.2~~1~~ ± 10.6~~5~~	73.0 ± 9.5	72.3 ± 10.6
Pulse rate (bpm)	71.5 ± 17.7	70.5 ± 15.7	74.5 ± 12.3	74.1 ± 12.4	80.1 ± 12.2	76.6 ± 8.0	77.1 ± 12.1	82.0 ± 15.8	72.1 ± 10.8	75.5 ± 7.3~~4~~
BDI-II score	3.8 ± 3.5	4.6 ± 3.7	2.8 ± 3.8	3.3 ± 3.3	4.5 ± 5.2	4.7 ± 5.0	2.8 ± 2.7	7.9 ± 7.6~~7~~	3.5 ± 3.9	3.5 ± 3.2
AEA	0.2 ± 0.1	0.2 ± 0.05~~1~~	0.2 ± 0.1	0.2 ± 0.1	0.2 ± 0.1	0.2 ± 0.1	0.2 ± 0.04	0.2 ± 0.1	0.2 ± 0.1	0.2 ± 0.1
2-AG	5.0 ± 2.9	4.7 ± 2.9	4.3 ± 1.7	4.1~~13.6~~ ± 1.4~~28.6~~	6.2 ± 3.1	5.0 ± 1.5	3.8 ± 1.5	3.7~~8~~ ± 1.7	5.0 ± 3.3	5.3~~4~~ ± 3.4
OEA	2.4 ± 1.1	1.8 ± 0.7	2.4 ± 1.0	2.3 ± 0.6	2.5 ± 0.8	2.2 ± 0.7	2.2 ± 0.5	2.2 ± 0.8	2.4 ± 0.5	2.1 ± 0.5
PEA	2.7 ± ~~2.01~~.9	1.8~~9~~ ± 0.7	2.7 ± 1.1	2.5 ± 0.7	2.6~~5~~ ± 0.7	2.4 ± 0.6	2.5 ± 1.2	2.6 ± 1.7	2.9 ± 1.3	2.0 ± 0.4~~5~~

Data are mean ± SD; [a]P<0.05, [b]P<0.01 compared with placebo; Abbreviations: AEA, N-arachidonoylethanolamine; Apo, Apolipoprotein; BDI-II, Beck Depression

Inventory-II; BMI, Body mass index; BP, blood pressure; HbA1c, glycosylated haemoglobin A1c; HDL, high density lipoprotein; HOMA2-IR, homeostatic assessment model 2 - insulin resistance; LDL-C, low density lipoprotein cholesterol; NEFA, non-esterified fatty acid; OEA, oleoylethanolamine; OGTT, oral glucose tolerance test; PEA, palmitoylethanolamine; TG; triglyceride, UC, ultracentrifugation; VLDL, very low density lipoprotein; 2-AG, 2-arachidonoylglycerol

Figure 2

Figure 3