

Project Overview

- Re-Align & Widen 4 Miles of I-70 Mainline + New CD System
- Construct New Six Points Interchange
- Construct New Airport Interchange
- Construct 10 New Bridge Structures
- Install 2 Miles of 96" Pipe
- Relocate 10,000 Ft. of Creek Channels
- Project Design Started in April 2002
- Open to Traffic Date December 2004



Project Overview

- Fast Track Process Accelerated Design & Construction Schedule
- Project Broken into 7 Contracts Let
 as Design Phases Completed
- 2.9 Million Cys Excavation & Embankment Required
- Grading & Embankment Contract Completion Key to Project Success
- Grading Contract Let October 2002; Work Started in November 2002

70 -----


Grading Contract


- Major Embankments to be Complete
 by May 2003
- All Excavation Complete by July 2003
- Winter Embankment Construction
 Critical to Schedule
- Soil Modification Selected to Allow Uninterrupted Construction During Winter
- Analysis Indicated Use of KLD
- Winter '02-'03 Produced Extreme Weather Conditions







Eco	onomic H	aul 🦷	Valsh Con
GENERAL HA	UL DISTANCES FOR		6
Dozer			
Wheel Loader			
Scraper			
Articulated Truck			
Rear Dump Truck			
Wagon			-
10 m	100 m 1000 m 328 8 3290 F	10 000 m	
32 R	HAUL DISTANCE	32,800 h	
Co	ourtesy Caterpillar Ir	c	














of Temporary Shoring










Placement of Fill


 After Scraper Bucket has dumped, a CAT D6 Dozer will knock down any small piles to create an even 8" lift.

• The lift is either compacted with a CAT 815 Sheepsfoot Compactor to


achieve the required density or Soil Modified.

All Dozers were equipped with GPS.















Construction Issues Continuous shifts during sub-freezing temps. to maintain 35 degree soil Proctor required for each lift due to time sensitivity of modified soil properties Reduced durability of nuke gauges in freezing temps.

Construction Issues

- Excess material > planned due to reduced shrinkage of treated soil
- Post modified soil is an "engineered" material - may be < 100 pcf
- JTRP Studying lime modification & developing new guidelines for use by INDOT

70 HAST



- Final quantity measurements?
 - Use of GPS for original & final surfaces
 - Use of DTM to provide quantities
 - Additional CE for sectioning
 - When is modification warranted?
 - MC taken daily compared to optimum
 - Drying time vs. Schedule
 - Sub on-site vs. Additional mobilizations

Construction Facts

- 2.97 Million Cys Moved from Nov. 2002 thru August 2003 at a Cost of \$11.2 Million
- 118,000 Tons of KLD Incorporated into Embankments at a Cost of \$7.1 Million
- Total Unit Cost = \$6.87 per Cy in Embankment
- Avg. Pct. KLD = 5.4%
- Critical Embankments Completed on Schedule

70 PAST

