

Needs Driven Design Solutions in Railroad Projects

Purdue Road School
March 8, 2016



Indiana Gateway & White River Bridge Projects

Tom Rueschhoff
Project Manager, Rail Office - INDOT



American Recovery & Reinvestment Act of 2009

- **ARRA had a portion of Funds focused on High Speed Rail Projects**
- **INDOT with the assistance of NS and Amtrak applied for a Grant for the Indiana Gateway Project and was selected in 2010**
- **INDOT was awarded a \$71.4M Grant that included 100% federal funds**
- **Agreements were finally reached in September 2012 between FRA, NS, Amtrak and INDOT**



Indiana Gateway Project

- **The Indiana Gateway consists of eight subprojects.**
- **Seven of the subprojects are on the Norfolk Southern Chicago Line and consist of five locations where universal crossovers will be added and three locations where a third mainline track will be constructed. The seven subprojects have an estimated cost of \$66.9 million.**
- **One subproject is on the Amtrak Michigan line, located just north of the Porter Interlocking, will construct a new passing siding to enable meeting trains to pass each other. This subproject has an estimated cost of \$ 4.5 million.**



White River Bridge (1899-2015)



Grant and Funding Sources

Total Project Cost \$13,845,220

- Federal Railroad Administration TIGER Grant
 - **\$8,245,220**
- Industrial Rail Service Grants (2013 & 2014)
 - **\$600,000**
- The Indiana Rail Road Responsibility
 - **\$5,000,000**



Project Schedule

Contactor : OCCI, Fulton, MO. May 30, 2014

Construction Began: June 2014

Bridge Change Out: May 2015

Main Project Completion: August 2015

FRA Contractual Completion: February 2016




Indiana GATEWAY PROJECT




March 2016

**Derek Tichy, P.E.
Norfolk Southern Corp.
Engineering – Design & Construction**


Trains Per Day on Major Corridors




Amtrak Trains Per Day




Chicago Line Traffic – West of Porter




Turnouts and Crossovers




Turnouts and Crossovers




Turnouts and Crossovers




New Main Line Track and Turnouts to be Installed




No. 20 Universal Crossovers



No. 20 Universal Crossovers



Project #1 - Burdick



CP 479 Turnout Installation

September 1 and 15, 2014


Two work windows on Mondays.



Project #2 – Porter - Amtrak Siding



Project #3 – Burns Harbor East



Project #3
Burns Harbor E
CP 485
In Service

Burns Harbor - East




Amtrak



Installing a No. 20 Turnout

Project #4 – Burns Harbor West



Project #4
Burns Harbor W
CP 487
In Service

Burns Harbor - West





Assembling a new No. 20 Turnout



Preparing New Signals

Project #5 – Millers



Project #5
Millers Siding
CP 490/492
Construction

Millers



Fill Section – 4" Minus Stone



Cut Section – Natural Sand

Millers



Delivering Subballast Stone



Compacting and Shaping Subballast

Millers



Third Track Construction



Project #6 – Bridge Demolition




NS NORFOLK
SOUTHERN
One line, infinite possibilities.


Project #6 – Bridge Demolition



Project #7 – Pine



Project #7
Pine Siding
CP 497/498/500/501
Construction



Pine



Before



After

Pine



Distributing Stone Fill



New Roadbed

Pine




New Roadbed



Dune and Swale Topography
on Railroad Right-of-way

Project #8 – Hammond



Project #8
Hammond
CP 506/507
In Service

Hammond



Track Construction



Temp. Position Light Signal

Hammond



Hammond



CP 507 Turnout Installations

Hammond



Setting the 4-track Signal Bridge




Track Construction on a Very Active Railroad

Hammond




Completed CP 506 and CP 507

Target Completion: End of 2016



Project Challenges



Keys to Success



Keys to Success

Define
Projects

Talk Between
Departments

Plan/Schedule



NS NORFOLK
SOUTHERN
One line, infinite possibilities.



The White River Bridge

Justin Cronin, P.E.

The Indiana Rail Road Co.

OWNER:
THE INDIANA RAIL ROAD COMPANY
INDIANAPOLIS, IN


TIGER FUND GRANTEE:
STATE OF INDIANA
INDIANA DEPT. OF TRANSPORTATION

DESIGN CONSULTANT:
DESIGN NINE INC.
ST. LOUIS, MO

CONTRACTOR:
OCCI ENGINEERING CONTRACTORS, INC.
FULTON, MO

BRIDGE LOCATION


AT MP 221.79 ON INRD'S CHICAGO SUBDIVISION
NORTH WEST OF ELNORA IN GREENE/DAVIESS COUNTY



EXISTING BRIDGE CONDITION



- Open-deck rail bridge constructed in 1899 (115 year service life)
- Composed of three 150-foot Pratt medium steel truss spans supported by stone pilings
- Speed restrictions to 10 MPH
- Maximum gross railcar weight limit restricted to 131.5 tons
- Clearance height limit to equipment meeting AAR Plate F (17'-0")



- North approach composed of 43 timber spans
- South Approach composed of 8 timber spans
- Each span consists of timber stringers with open deck ties resting on 5-pile timber bents with diagonal bracing

HISTORICAL SIGNIFICANCE



Pratt style pin-connected truss was popular because of ease of design (no moment force), ease of construction (parts fabricated off site), economical (light weight/high capacity), and was ideal for the long spans over Indiana's Rivers

EXISTING ON-GOING BRIDGE REPAIRS



Steel shims installed below bearings – Pier Settlement



Replaced steel rivets with H.S. bolts - Deterioration



Installed steel channel walers – Erosion and Undermining



Replaced expansion bearing & pedestal



Replaced displaced masonry units with concrete facing



Maintain track alignment Settlement & Deterioration


PROJECT NEEDS

- TO UPGRADE THE OBSOLETE, DETERIORATED STRUCTURE TO IMPROVE SAFETY AND EFFICIENCY.
- THE STRUCTURE IS OBSOLETE BECAUSE CURRENT TRAFFIC LOADS ARE MUCH HIGHER THAN ORIGINAL DESIGN
- RUST AND SECTION LOSS OF THE STEEL GREATLY REDUCES THE STRUCTURAL INTEGRITY OF THE BRIDGE.
- GREATER TRAFFIC LOADS AND FAST MOVING FLOOD EVENTS ARE CAUSE OF PIER SETTLEMENT AND UNDERMINING
- LOWER TRAIN SPEEDS AND LOWER CAR LOADS EFFECT THE EFFICENCY IN TRAIN CREW HOURS AND COST OF TRANSPORTATION
- PROJECT ALSO NEEDED TO BE COST EFFECTIVE



SCOPE OF WORK

- PIER RETROFIT
- CONSTRUCTION OF TEMPORARY BRIDGE
- INSTALLATION OF H-PILES AND PIER CAPS
- FABRICATION AND DELIVERY OF CONCRETE GIRDERS
- FABRICATION AND DELIVERY OF STEEL GIRDERS AND COMPONENTS
- 6 DAY OUTAGE TO COMPLETE CHANGE-OUT

ORIGINAL PIER RETROFIT



**Drill 10" dia. micro-piles
around perimeter between
masonry & sheet-pile**



**Assemble rebar mat, anchors &
thru-bolts around masonry &
encase in concrete**



PIER 1 COMPLETED MICRO-PILE

PIER 4 COMPLETED REBAR





FIRST POUR AT PIER 1

SECOND POUR AT PIER 1
NOTE: REUSABLE FORMS FOR COST SAVINGS





COMPLETED PIER RETRO-FIT

CONSTRUCT TEMPORARY BRIDGE



PIPE PILE DRIVEN WITH
VIBRATORY HAMMER
REUSABLE PIER CAP ATTACHED
TO PILE

STRUCTURE COMPONENTS
ARE RECOVERED FOR COST
SAVINGS



DRIVE BRIDGE PILING & INSTALL CAPS



New piers installed under existing bridge keeps track in service

BRIDGE DESIGN

AREMA COOPER E-80 FIGURE





Figure 15-1-2. Cooper E 80 Load



PROP. SECTION THRU RIVER SPANS
SCALE: 1/2"=1'-0"
(LOOKING SOUTH)

Except as otherwise stated, the dimensions shown on this diagram apply to the design dimensions of new empty cars on level tangent track.

The 2 3/4" above top of rails is absolute minimum under any and all conditions of lading, operation, and maintenance.




Fig 1.1 Maximum clearance requirements for double-stack container cars

PLATE H DIAGRAM

FROM "THE OFFICIAL RAILWAY EQUIPMENT REGISTER"

DELIVERY AND FABRICATION OF STEEL GIRDERS



CRANE PERFORMS A PICK OF 250 KIPS THEN DOES A 180 DEGREE TURN AND LOWERS ONTO ROLLERS

GIRDERS FABRICATED ON SITE UNDER RIGOROUS GUIDELINES AND SPECIFICATIONS



All is Ready for the Outage

NOTE: CONCRETE GIRDERS AND
INDOT 53 STONE STAGED ON SIDE
OF BRIDGE



Outage Began At 00:45 May 13th, 2015

First Night All South Approach Spans Removed, New Abutment & Wingwalls installed

North Approach Spans 13 to 22 Removed, New Abutment & Wingwalls installed

All Rail Cuts Made on North Approach Track Panel, South Panel Removed



NORTH APPROACH TRACK RAISE

UP TO 4' RAISE IN SOME AREAS TO ACHIEVE

MAX GRADE OF .44%

NOTE: TRACK PANELS MOVED TO SIDE OF
EMBANKMENT TO FACILITATE GRADING

REMOVAL OF PRATT TRUSS

ALL MAIN SPAN CRANE WORK DONE

IN DAYLIGHT HOURS FOR SAFETY



INSTALLATION OF CONCRETE GIRDERS

Second Night: Removed Remainder of North Approach Spans; Set New North and South Approach Spans



North bridge approach was replaced with twenty-two (22) precast concrete girder spans
South bridge approach was replaced with four (4) precast concrete girder spans

May 14th, 2015 - Main Spans installed



Main Span in transit. Note: 2" Depth tread marks from 500 kip load

Remainder of the Outage - May 15th to May 19th, 2015

Finish North Approach Track Raise
Dump Ballast on Approaches and Spans
Install Rail and other Miscellaneous Work



Track Back in Service at 16:55 on May 19th, 2015

BEFORE AND AFTER

SOUTH APPROACH



APPROACH SPANS



MAIN SPAN



NOTE: HORIZONTAL AND VERTICAL
RESTRICTIONS ON PREVIOUS
STRUCTURE



MAIN SPAN - ELEVATION



PROJECT CHALLENGES

Wet Roads Necessitated
Delivery of Material by Rail



Supplier issues could have
Delayed the Outage



Environmental Restrictions

The Indiana Gray Bat restricted tree clearing
White River fish spawn restricted river work

WEATHER AND FLOODING



EXTREME COLD
A.K.A. POLAR VORTEX

HISTORIC FLOOD OF 2008



HAD TO CLOSELY MONITOR RIVER GAUGES TO
MOVE EQUIPMENT AND MATERIAL BEFORE A
FLOOD EVENT

PROJECT BENEFITS

- **IMPROVED EFFICIENCY**
 - INCREASED TRACK SPEED FROM A PERMANENT SLOW ORDER OF 10 MPH TO 40 MPH RESULTS IN LESS CREW HOURS AND LESS ENGINE EXHAUST
 - INCREASED CAR LOAD WEIGHT RESULTS IN REDUCTION OF TRANSPORTATION COSTS
- **IMPROVED SAFETY**
 - STRUCTURE DESIGNED FOR COOPER E-80 AND CAN HANDLE INCREASED LOADS
 - STRUCTURE DESIGNED FOR PLATE H AND CAN HANDLE OVERDIMENSIONED CARS AVOIDING ANY BRIDGE STRIKES
- **RELIABLE INFRASTRUCTURE**
 - ENSURING KEY CROSSING OF STRACNET RAIL FREIGHT CORRIDOR SERVING CRANE NAVAL BASE

KEYS TO SUCCESS

- **RIGOROUS CONTRACTOR SELECTION PROCESS**
 - SENT REQUEST FOR PROPOSAL TO LIST OF QUALIFIED CONTRACTORS
 - MEETING WITH 2 LOWEST BIDDERS TO DISCUSS EXPERIENCE WITH RAIL PROJECTS AND POTENTIAL COST SAVINGS
- **OPEN COMMUNICATION BETWEEN ALL PARTIES**
 - WEEKLY MEETINGS WITH CONTRACTOR, INDOT REPRESENTATIVES, CONSULTANTS AND RAILROAD WAS ABLE TO IDENTIFY AND SOLVE PROBLEMS
 - REVIEW OF CONTRACTOR'S WRITTEN WORKPLAN ENSURED QUALITY AND ADHERANCE TO SCHEDULE
 - CLOSE COORDINATION AND COMMON GOALS BETWEEN RAILROAD MANAGEMENT AND CONTRACTOR LED TO GREATER PRODUCTIVITY
- **PROJECT WAS ABLE TO STAY ON BUDGET AND FINISH AHEAD OF SCHEDULE AND DELIVER A SUPERIOR PRODUCT**



Entrepreneurial RailroadingSM



THANK YOU!

STAY TUNED FOR EXCITING TIME LAPSE VIDEO OF SPAN CHANGE OUT



Needs Driven Design Solutions in Railroad Projects

Matt Spiel, AICP


Purdue Road School

March 8, 2016

INDOT's Rationale for Subcontracting

- Limited staff
- Scope of project
- Logistics
 - Multiple ongoing multi-million dollar sub-projects
 - Location of project site
- Plan review
- Invoice review
- Maintaining project records
- Maintaining communication among all stakeholders

Key Tasks



Keys to Success

- Dedicated professionals from all parties
 - INDOT
 - FRA
 - Railroads
 - HNTB
- Open and continuous communication