Greenhouse Gases (GHG) Performance of Refurbishment Projects – Lessons from UK Higher Education Student

Accommodation Case Studies

1. Introduction

There is growing scientific and political consensus that climate change represents the greatest environmental threat and challenge of modern times. The key driver of climate change is the robust link between the generation of greenhouse gases (GHG) and rising global temperatures (CCC, 2016). GHG emissions from UK buildings have been reported to contribute up to 37% of the UK's total GHG emissions (TSB, 2014). Notwithstanding GHG emissions generated during the design, material manufacture, distribution and on-site construction of both the UK buildings - reflecting up to 18% of a building's whole lifecycle carbon footprint (BIS, 2010). A clear link has been identified between the whole lifecycle environmental and GHG performance of a building and the focus and investment during the construction phase. For example lower levels of initial capital investment spent on insulation or plant may result in increased operation or maintenance expenditure and reduced environmental performance over the buildings whole lifecycle (Bribián *et al.*, 2009). Therefore if the UK is to meet its climate change targets whilst maintaining a vibrant construction sector, the industry needs to also reduce the impact of buildings through improved construction practices.

The UK Department for Environment, Food and Rural Affairs (DEFRA) confirms that improvements driven by construction industry players will be crucial for reducing emissions (DEFRA, 2013). Considering that 87% of existing buildings in the UK will likely be standing in 2050 (UK GBC, 2016), a large focus of construction projects in the future will be retrofitting and/ or refurbishment of existing buildings. The Chartered Institute of Building reported that the UK has about 30 million domestic and non-domestic buildings, 28 million of which will be required to be retrofitted or refurbished for the UK Government to meet it's carbon targets (CIOB, 2011).

The importance of low carbon construction practices, refurbishment and maintenance works to reduce energy demands and GHG emissions is well reported (Ferreira *et al.*, 2013; de Larriva, 2014; Gaspar and Santos, 2015; Killip, 2013; Pombo *et al.*, 2016). Simple retrofitting projects such as adding thermal insulation to external walls, can provide higher energy efficiency and lower energy costs (Bojic *et al.*, 2012), whilst major refurbishment can provide an opportunity to significantly improve poor energy performing buildings by replacing old items with new energy efficient materials and technologies (Carroon, 2010). Research such as that by Tang *et al.* (2013) have also identified strong relationships between a project's

GHG performance and the management focus and applied practices – different construction management strategies having significant influence on the overall GHG emissions generated over a project's lifecycle.

The UK has multiple guidelines, regulatory frameworks and incentive schemes that are designed to improve the standard of refurbishment and retrofit projects. Within the housing sector, initiatives such as Decent Homes, Warm Front and Green Deal have each provided guidance and funding avenues for construction work on retrofitting (DCLG, 2006). In the private sector, greater autonomy is given to allow stakeholders to determine the best options of individual projects. The BREEAM Refurbishment (BRE, 2015), Considerate Constructors Scheme (CCS, 2015) and SKA rating (RICS, 2013) schemes are examples of benchmarking methods that aim to improve environmental performance of construction and the resulting buildings. However in the UK the success of regulation and guidance for refurbishment has been widely criticised (CIOB, 2011; Killip, 2013; Rawlinson and Wilkes, 2014) and the uncertainties, risks and bespoke nature of refurbishment projects makes them inherently unsuitable for generic assessment schemes (Juan, 2009).

The student accommodation sectorindustry has emerged as a top performing asset in both the UK and US property markets (Hammond, 2013) - , with £1.85 billion invested in the UK in 2013 alone (CBRE, 2013) as the demand for student accommodation has continued to accelerate. Deloitte (2013) reported in 2013 that 1.72 million fulltime students are hunting for 457,000 purpose-built student accommodation spaces in the UK. In response to demand nondomestic buildings are being increasingly refurbished and converted into student accommodation, alongside an increasing number of projects upgrading existing accommodation. The UK student accommodation industry is considered a 'niche market', in which supply is adapted to meet the needs from students (considered as a specialised tenant group) (Rugg et al., 2013), as demonstrated in Manchester (Carver and Martin, 1987) and Edinburgh (Nicholson and Wasoff, 1989). With high anticipated growth within the niche student accommodation market (Savills, 2014), the construction sector is set to play a central role in determining the carbon footprint of these developments, where experience and good practices lessons will likely be key to increasing performance across the sector. -As there is limited research into the carbon emissions of student accommodation refurbishment projects; this project aims to rectify this by:

- Evaluating a series of representative comparative case study student accommodation refurbishment projects.
- Analysing emission profiles of the comparative case study projects' refurbishment works, focusing on how the characteristics of the projects may provide an indication of the GHG performance.
- Developing conclusions for how GHG emissions may be best measured in student accommodation refurbishment projects.

In summary, this paper aims to provide an analysis of the key performance indicators and GHG emission benchmarks for higher education student accommodation refurbishment projects, specifically for projects using Joints Contracts Tribunal Design and Build Contract (JCT), whereby the contractors are responsible for the building design in addition to the construction works (JCT, 2014).

A myriad of methodologies have been developed aimed at quantifying the levels of GHG emissions from construction activities. These vary in terms of the method of calculation, and the choice of metric applied to estimate emissions (eg. transport distances, construction costs, material types, etc.). Methods include (1) quantitative approaches (Suzuki and Oka, 1998) for analyses that define set emission contributors; (2) analysis of interactions between direct and indirect energy uses and emission factors for each subsection of work within a project (Acquaye and Duffy, 2010); (3) carbon emissions analysis by particle swarm optimisation (PSO) to evaluate optimal construction pathways with reduced environmental impact (Liu et al., 2013). The metric of kgCO2^{evqv_L} is currently being drafted as the 'common carbon metric' by the United Nations Environment Programmes' Sustainable Building and Climate Initiative (UNEP, 2016) to be tested against organisation's benchmark key performance indicators (KPIs) of distance (kgCO2^{eqv_vq} per km), duration (kgCO2^{eqv_vq} per week), gross internal floor area (kgCO2^{eqv_vq} per m²), rooms (kgCO2^{eqv_vq} per room) and project value (kgCO2^{eqv_vq} per £100,000).

Constructing Excellence (2014) has its own methodology to be applied when evaluating the GHG performance of _UK construction activities using (KPIs). _industry's key performance indicators (KPI) - . KPI's are a systematic measure of an activities performance that allows the benchmarking comparison against both internal and competitive targets (Constructing Excellence, 2016). To undertake KPI analysis, data must be obtained during and/ or upon completion of the project that reflects: (i) the amount of energy used on site (electricity (kWh), diesel fuel (litres), petrol fuel (litres)); and, (ii) the project value. Second, GHG emissions per energy usage will be determined using standard fuel emission factors as determined by the National Atmospheric Emission Inventory database (NAEI, 2016). Third, results are normalised with respect to the value, duration and context of each project so that they can be directly benchmarked against each other. The Constructing Excellence (2014) methodology is becoming the industry standard in the UK and as such this research analyses the respective data for the comparative case study projects. However, the Constructing Excellence methodology is largely based on overall project cost, and given its recent adage of 'cheapest is not always best', cost alone cannot be applied to decipher specific emission savings or issues. Therefore, this research builds upon the case study's Constructing Excellence data by also benchmarking emissions based on overall GHG Scopes, and the organisation's internal KPIs.

Evaluating the different scopes of GHG emissions data was found to be a useful tool for organisations to potentially monitor emissions from different contributors during the whole lifecycle of the project. The organisation has complete control of Scope 1 emissions (direct emission). The Scope 1 GHG data allow organisations to measure manage and prioritise internal resources for the project, such as internal staffing numbers, business travel and accommodation provision. Scope 2 data (indirect emissions) is the direct representation of the generation of purchased energy used on-site, with lower Scope 2 data implying to less consumption and lower costs. Scope 3 emissions are those that the organisation will have the least control over as they reflect the emissions from outsourced activities not owned or controlled by the organisation. Analysing Scope 3 data can provide the organisation with the opportunity to improve supply chains, exclusively appoint only certified sub-contractors who share the same environmental concerns, enhance wider corporate responsibility and potentially reduce costs through requiring minimum environmental performance levels by all sub-contractors and suppliers.

3. Methodology - Introducing the Student Accommodation Case Studies

This research engaged with a privately owned construction management company based in the North-West of England with projects across the country, specifically in student accommodation, hotels, social housing and schools. The company has a strong environmental focus that is integrated throughout their management systems, including a carbon management action plan developed in line with the principles of ISO26000 (ISO, 2010). A key element of company's core business is the management of projects including all contractors, sub-contractors and suppliers. Therefore this company is well placed to provide benchmarking data of overall environmental impact of refurbishment projects and to illustrate an evaluation of GHG emissions generated both on and off-site during the refurbishment process. Four comparative cases were offered by the organisation as projects representing typical UK student accommodation refurbishment works. Two of the case studies were longterm projects (more than 4 months duration) and the other two case studies were short-term projects. The clients for each of the case studies varied with each having differing requirements and project needs. A summary of the characteristics of the four student accommodation case studies is presented in Table 1. The projects were all developed under the JCT Design and Build Contract.

[insert Table 1 here]

Comparative GHG performance datasets for each of the case study projects were collected on-site through: organisational daily signing-in sheets (internal staff); sub-contractor daily signing-in sheet; delivery information; operational information for all machinery and equipment

consuming fuels (for instance, petrol, diesel, gas, etc.); as well as data reflecting all other GHG emitting activities and processes related to the projects. Material delivery data is assumed to be a full load with previous and future destination distance recorded. Only generic vehicle data is recorded (eg. car-petrol, van-diesel, etc.). All accounted GHG's emissions are calculated in carbon dioxide equivalent (CO2eqv.) values reflecting the values and methodology of the National Atmospheric Emission Inventory database (NAEI, 2016). Each projects' emission data was collected on site and analysed on a periodic monthly basis where the data is reported by the organisation's Environmental Manager. An example of a project's emission data sheet is demonstrated in Figure 2. The GHG emission data for each of the comparative case study projects was guided by the Greenhouse Gas Protocol for Project Accounting (WBCSD & WRI, 2003); the 3 tier Scope GHG classification framework; and organisational KPIs reflecting 5 themes (distance, duration, gross internal floor area, room numbers and value) as summarised in Table 2 - these 5 KPls provide the basis of this research analysis. The KPI's are reflective of those typically used by the UK construction sector (BIS, 2015) for , and reflect those used by the organisations to measure and benchmark their construction performance.

[insert Table 2 here]

The comparative case study project datasets are presented in Table 3. These reflect performance data for each scope category of GHG emissions and for each of the organisational KPI's. Emission data is omitted for the first four weeks and final two weeks of the long duration projects (CS-1 and CS-2), and data from the first week and final weeks of the shorter duration projects (CS-3 and CS-4). This is to provide a more indicative and accurate picture of the emissions profile of the core activities associated with each project, and to allow better comparisons between the different datasets.

[insert Table 3 here]

4. Results analysis

Comparative analysis of the GHG emission scope datasets in Table 3 demonstratesed the differences in emissions profiles across each of theall case study projects._-The breakdown of emissions within each GHG classification scope can be associated with the characteristics of each individual case study. For example although CS-3 and CS-4 are in the same city, there is great contrast in their emission profiles - the Scope 3 emissions for CS-3 are shown to be over 30% higher than those for CS-4, where a greater proportion of overall emissions are Scope 1. This reflects the higher proportion of sub-contracted work associated with CS-4 and

therefore the out-sourcing of emissions. The proportional breakdown of Scope 1 and 2 emissions generated by projects CS-1, CS-2 and CS-3 are similar reflecting their comparative use of sub-contractors.

The indirect Scope 2 emissions reflect the use of purchased energy across all the projects this data shows much greater consistency. Projects CS-3 and CS-4 demonstrate the least Scope 2 emissions, reflecting the short periods of onsite works associated with these projects and therefore less energy purchased. Differences in the proportion of Scope 2 emissions associated with CS-1 and CS-2 (both have long on-site refurbishment durations) may be attributed to the implementation of a new carbon action plan before CS-2, which increased the organisational focus on on-site energy saving practices/ technologies.

The refurbishment phase data (RP) presented in Table 3 demonstrates congruence between the datasets. These datasets provide more accurate representations of the GHG impact of the actual refurbishment works, as estimated emissions associated with the projects' start-up and move-out works are excluded.

4.1 Comparative Case Study Projects' KPI Data

The case study projects could be categorised in two distinct groups based on their project characteristics, as shown in Table 2. CS-1 and CS-2 reflect projects with comparatively longer work duration, larger project value, larger internal floor areas and higher number of rooms-compared to CS-3 and CS-4; compared to projects whereas CS-3 and CS-4 that are both are-located further away from the organisational head office, are smaller in size, with lesser value and with less time onsite. The KPI emissions data documented in Table 3 can be analysed to evaluate relationships between the projects' characteristics and their emissions profiles.

Table 3 shows that the distance KPI data demonstrates that more emissions are generated by projects CS-1 and CS-2 despite CS-3 and CS-4 being at greater distances from the organisational head office. This indicates that distance from the organisational head office may not be the strongest KPI to provide an indication of a project's GHG emissions. Analysis of both the duration KPI data and the value KPI data highlights the trend that greater emissions are generated by projects CS-3 and CS-4, despite projects CS-1 and CS-2 reflecting much longer duration of onsite refurbishment works and greater project value. Greater understanding of the influence of these KPI's may be gained through accepting that short term projects require the same number/ amount of start-up and move-out equipment, transport and support as any other project. In addition, short-term projects often require a higher number of operatives on-site to complete the project within the allocated timescale. This is confirmed through comparing the whole life cycle (WLC) emission data with the refurbishment phase (RP) data for these KPI's in Table 3. When estimated emissions associated with the set-up of a project are not considered (comparing RP data instead of

WLC), the disparity between the datasets is much reduced and therefore the duration and value KPI provide a fairer reflection of the projects emissions. Although the shorter duration projects are still shown to document proportionally greater emissions compared to the longer duration projects. Therefore, working to tighter schedules and involving larger teams to achieve this may result in proportionally higher project GHG emissions.

Evaluation of the emission data for the GIFA and rooms KPI's highlight further trends. The room KPI data clearly demonstrates that projects CS-1 and CS-2 each with a large number of rooms reflect proportionally higher GHG emissions than CS-3 and CS-4 each with lower numbers of rooms under refurbishment. The room KPI could therefore be construed as a close indicator of potential scope category of GHG emissions, and in this research where the analysed projects are student accommodation (typically highly cellular with a large number of rooms), this KPI provides a good indication of each projects' scale. In reality, rooms can be highly variable in size and therefore a GIFA KPI may represent a more accurate reflection of the characteristics of a project, and thus an indication of GHG emissions. The GIFA emission data in Table 3 highlights that there are only marginal differences in GHG emissions generated across the case study projects. This difference is reduced further when comparing just the case study RP data.

It has to be assumed that an organisation working on multiple projects and implementing the same work practices on each, should generate comparatively similar emissions from projectto-project / site-to-site, driven largely by the extent of work undertaken, not changes in work approach. Other potential attributes to why longer duration projects perform better include economies of scale (e.g. less transportation involved, improved learning curve for staff, and minimised fixed environmental costs for instance). The least variation in emissions profile across the case study projects is demonstrated by the GIFA KPI datasets. GIFA may represent the most accurate indicator of therefore projects' **GHG** performancecharacteristics.

4.2 Performance of KPI's to Reflect Project GHG Performance

A further analysis stage that may be undertaken using the case study projects' emission data is to entails evaluate investigating the ability of each KPI to reflect the different projects' GHG performance impact. Independently each of the KPI's provides an indication of the projects' GHG performance, and allows the projects to be benchmarked against each other.

Figure 2 has been designed to allow comparison of the GHG performance of each case study project according to the different KPIs. The values presented for each KPI have been normalised so that the different datasets may be presented on the same scale. The stacked column charts provide a breakdown of the whole lifecycle (WLC) and refurbishment phase (RP) GHG emissions for each project and allow the performance of each to be benchmarked against that of the other projects. The value labels across Figure 1 highlight the rank of each

project in terms of GHG performance for each KPI. Projects ranked first for each KPI are those with the greatest GHG impact, and likewise projects ranked fourth reflect the project with the least GHG impact according to the KPI.

[insert Figure 1 here]

As Table 4 highlights there is much variability in the comparable GHG performance of the different case study projects according to the different KPIs. CS-1 is identified as the project with the greatest whole life cycle GHG impact according to three of the KPIs (distance, GIFA and rooms), the other KPIs highlight CS-4 as the project with the greatest impact. There are fewer consensuses reflected by the refurbishment phase data, the GIFA KPI identifying CS-2 as the project with the greatest GHG impact. Contrasting trends are also showndemonstrated across the KPIs when identifying determining which the project achieves the s with the best GHG performance - projects CS-2, CS-3 and CS-4 all being identified as the best performing projects according to different KPIs.

[insert Table 4 here]

In summary, the analysis highlights that there is significant variability in the ability of the different KPIs to reflect the GHG performance of projects. This confirms the importance of consistently using the same KPI when comparing the performance of multiple projects, and also that some KPIs may reflect greater representation of GHG performance than others based on the specific characteristics of the project. Statistical correlation analysis was undertaken to directly evaluate the relationship between the KPI characteristics of the research's projects and the resulting WLC and RP emissions generated. As Table 5 demonstrates high correlation is shown between all of the KPIs and GHG performance, highlighting that each KPI may be used in their own right to provide an accurate indication of GHG performance. Negative correlation is shown between the distance KPI and GHG performance, reflecting reduced proportional GHG performance with shorter distance for the comparative case studies analysed. In contrast the other KPIs for the comparative case studies analysed show positive correlation with GHG performance — as the proportional GHG performance per KPI improves as project duration, GIFA, room number or project value increase.

The correlation analysis in Table 5 highlights that the duration, GIFA and project value KPIs were identified as the most accurate indicators of a project's overall WLC emissions, and the duration and GIFA KPIs are the best indicators of a projects refurbishment phase emissions. The value KPI ranked <u>is shown to be</u> joint-first in WLC emissions (0.990) and third in RP emissions (0.943). This came as a surprise considering that initial start-up and site removal costs are compulsory in all projects regardless of its size - demonstrating the value KPI as a

<u>potentially</u> misleading emissions indicator. The duration and GIFA KPIs were the better indicator for refurbishment emissions, compared to value.

[insert Table 5 here]

5. Discussion

This research analysed refurbishment GHG emission data from an environmentally conscious organisation undertaking refurbishment works on four student accommodation projects—each of which was used as a case study in our research. The aim of the research was to identify potential lessons that could be drawn from these projects for the wider construction industry, and to evaluate the methods in which the GHG performance of refurbishment projects arewere analysed. Although the research's case study sample size is relatively small, the projects analysed reflect a broad range of characteristics and are a typical sample of UK student accommodation refurbishment projects. T. (as the organisation has 8 years experience in operating within this field)—here are currently no readily available emissions benchmarks for the UK refurbishment construction sector, let alone for the student accommodation projects—this research and therefore providese a valuable contribution to this e-wider research theme. As the UK construction sector is currently undertaking widespread refurbishment of building stock such as social housing projects, there is clear scope for the analysis within this research to be adapted and extended to further categories of refurbishment and for different organisation and construction practices.

This research adds to the many existing studies that have focuses on the various elements influencing

As it stands most organisations only undertake internal comparisons and benchmarks of the GHG performance of their refurbishment works, in order to highlight potential improvements. A potential major issue faced by organisations can be the non-availability of common KPIs for comparison of GHG emissions. As this research demonstrates the ability of different KPIs to reflect potential GHG performance can be highly variable. Therefore, if organisations are determined to benchmark the GHG performance of their work with that of other competitors or partners, default industry/sectorial KPIs need to be applied.

Data collection for GHG emission Scope 1, 2 and 3 for construction/refurbishment projects is highly commended; however, this can be further improved and refined. One of the weaknesses of the project emission data collection was identified as being too vague in transport emissions for both organisational and sub-contracting staff. Data is collected based on the generic vehicle type (eg. car-petrol, van-petrol, LGV-diesel, etc.). More accurate data could be collected (daily signing-in sheets) from their vehicle types, daily travel distances and vehicle share. Emissions from specific vehicles are widely available. Another potential area

Formatted: Font color: Auto

Formatted: Tab stops: Not at 0.25 cm

Formatted: Font color: Auto

Formatted: Tab stops: Not at 0.25 cm

Formatted: Space After: 6 pt

for improvement is the emission calculation for materials transportation (delivery) - stating the percentage of space/load used for each materials delivery can refine data. Current practice assumes 100% loading for the vehicle, which is incorrect for most deliveries. All case studies analysed in this research were situated in central urban areas with readily available electric and/or gas connections, although benchmarks for GHG Scope 2 emissions could be considerably higher for rural projects with the use of high emission carbon-based generators (eg. diesel, petrol, gas) on-site.

In theory the GIFA, value and the number of rooms of a project should provide the best emission benchmark as they reflect the scale of work to be undertaken; but this research the research's data analysis has demonstrated otherwise. Due to the nature of student accommodation having a large number of rooms (eg. variable student rooms, kitchens, foyers and landing area combinations), using the number of rooms KPI can be a misleading indicator of GHG performance. The research found that GIFA KPI provided a more accurate reflection of potential GHG emissions for student refurbishment projects.

As it stands most organisations only undertake internal comparisons and benchmarks of the GHG performance of their refurbishment works, in order to highlight potential improvements. A potential major issue faced by organisations can be the non-availability of common KPIs for comparison of GHG emissions. As this research demonstrates the ability of different KPIs to reflect potential GHG performance can be highly variable. Therefore, if organisations are determined to benchmark the GHG performance of their work with that of other competitors or partners, default industry/sectorial KPIs need to be applied.

The student accommodation sector in the UK and US is a top performing asset for the construction sector and is expected to grow further. The quickest method to satisfy demand is to refurbish current stock or change building use, however little is known of its environmental impacts. Being able to compare and scrutinise the performances of different construction organisations, strategies and techniques is essential in order to improve the impact of the industry. The GHG emission data from projects provides an opportunity for this analysis, to measure performance, set targets and a benchmark for refurbishment This research refurbishment projects based on their varying construction characteristics.

The projects to evaluate their practices and learn lessons that may ultimately reduce the GHG impact of wider refurbishment. key thread running through all research focused on the environmental and emission performance of construction is the ways in which GHG performance is measured and reported. This research evaluates the consistency and accuracy of using different key performance indicators to predict GHG performance - This research analysed GHG emission Project key performance indicator (KPI) data for four case study student accommodation refurbishment projects — distance of the project to the construction te-organization's HQ KPI (kgCO₂^{eqv.} per km); duration of project KPI (kgCO₂^{eqv.}

per week); gross internal floor area KPI (kgCO₂eqv. per m²); number of rooms KPI (kgCO₂eqv. per room); and project value KPI (kgCO₂eqv. per £100,000). The keyThe key conclusions were:

- KPIs were predetermined by the researched organisation distance, duration, GIFA, rooms and project value <u>D</u>different KPIs were found to have varying ability that best reflect the GHG performance of refurbishment projects.
- Postive correlation is found between a project's GHG performance and its duration, value, gross internal floor area (GIFA) and number of rooms. Whilst negative correlation is found between a project's GHG performance and the distance of the project to the construction organization's HQ.

Negative correlation is shown between the distance KPI and GHG performance, reflecting reduced proportional GHG performance with shorter distance for the comparative case studies analysed.

In contrast the other KPIs for the comparative case studies analysed show positive correlation with GHG performance—as the proportional GHG performance per KPI improves as project duration, GIFA, room number or project value increase.

Formatted: Font: (Default) Arial, 10 pt, Font color:

Formatted: List Paragraph, Indent: Left: 0.63 cm, Hanging: 0.63 cm, Bulleted + Level: 1 + Aligned at: 0.63 cm + Indent at: 1.27 cm

Formatted: Font: (Default) Arial, 10 pt

Formatted: Font color: Text 1

Formatted: Font: (Default) Arial, 10 pt, Font color:

Text 1, Not Highlight

Formatted: Font color: Text 1

Formatted: Font color: Text 1, Not Highlight

Formatted: Font color: Text 1

Formatted: Indent: Left: 0.63 cm, Hanging: 0.63

cm, No bullets or numbering

Formatted: Font color: Text 1

Formatted: Indent: Left: 1.27 cm, No bullets or

numbering

Formatted: List Paragraph, Left, Space After: 0 pt, Line spacing: single, No bullets or numbering, Tab stops: Not at 0.25 cm

Based on the analysis and data from this research's case study projects, the gross internal floor area (GIFA) was identified as the KPI that best reflect the GHG impact of student accommodation refurbishment projects using ICT Design and Build contracts in the LIK.

References

Acquaye, A.A. and Duffy, A.P., 2010, Input-Output Analysis of Irish Construction Sector Greenhouse Gas Emissions. *Build Environ.* 45(3), 784-791.

BIS, 2010. Estimating the amount of CO2 emissions that the construction industry can influence, Department of Business, Innovation and Skills (BIS), London, UK.

BIS, 2015. UK Industry Performance Report: Based on the UK Construction Industry Key Performance Indicators, Department for Business Innovation and Skills (BIS), London, UK.

Bojic, M., Djordjevic, A., Stefanovic, M., Miletic, M. and Cvetkovic, D., 2012. Decreasing Energy Consumption in Thermally Non-Insulated Old House via Refurbishment. *Energ Build.* 54, 503-510.

Formatted: Highlight

- Bribián, I Z., Usón, A A., Scarpellini, S., 2009. Life Cycle Assessment in Buildings: State-of-the-art and Simplified LCA Methodology as a Complement for Building Certification. *Building and Environment*. 44(12), 2510-2520.
- BRE, 2015. BREEAM International Refurbishment and Fit-out Technical Standard, Building Research Establishment (BRE), Watford, UK.
- Carroon, J., 2010. Sustainable Preservation. Greening Existing Buildings, John Wiley & Sons, New Jersey, USA.
- Carver, K. and Martin, G., 1987. Taken for Granted: the Student Rented Sector and Related Finances in South Manchester, UMIST Students' Union, Manchester, UK.
- CBRE, 2013. Student Housing Valuation and Advisory Services, CBRE. http://www.cbre.co.uk/uk-en/services/valuation_advisory/student_accommodation Date accessed 1 July 2015.
- CCC, 2016. Greenhouse Gas Emissions 2016, Committee on Climate Change (CCC). https://www.theccc.org.uk/tackling-climate-change/the-science-of-climate-change/climate-variations-natural-and-human-factors/greenhouse-gas-emissions/ Date accessed 11 July 2016.
- CCS, 2015. Code of Practice 2015, Considerate Constructors and Scheme (CCS), London, UK.
- CIOB, 2011. Carbon Action 2050: Buildings Under Refurbishment and Retrofit, Charted Institute of Building (CIOB), Englemere, UK.
- Constructing Excellence, 2016. KPIs and Benchmarking, Constructing Excellence. http://constructingexcellence.org.uk/kpis-and-benchmarking/ Date accessed 21 July 2016.
- Constructing Excellence, 2014. *Methodology for Calculating Carbon Emissions on Site*, Constructing Excellence, London, UK.
- DCLG, 2006. Existing Housing and Climate Change: Seventh Report of Session 2007–08, Department for Communities and Local Government (DCLG), London, UK.
- de Larriva, R., Rodríguez, G., López, J., Raugei, M. and Palmer, P., 2014. A Decision-Making LCA for Energy Refurbishment of Buildings: Conditions of Comfort. *Energ Build.* 70, 333-342.
- Deloitte, 2013. Student Housing 2013. The evolving market. Deloitte Real Estate, London, UK. Ferreira, J., Pinheiro, M. and de Brito, J., 2013. Energy and Life Cycle as Key Aspects to Sustainable Refurbishment Projects. Energ. 62, 1453-1460.
- Gaspar, P.L. and Santos, A.L. 2015. Embodied energy on refurbishment vs. demolition: A southern Europe case study, *Energy and Buildings*, 87, 386-394.
- Hakkinen, T., Ala-Juusela, M. and Shemeikka, J. 2016. Usability of energy performance assessment tools for different use purposes with the focus on refurbishment projects, *Energy and Buildings*, 127, 217-228.
- ISO, 2010. Guidance on Social Responsibility. ISO26000. International Standards Organisation (ISO), Geneva, Switzerland.
- JCT, 2014. Design and Build, Joint Contracts Tribunal (JCT), http://www.jctltd.co.uk/category/design-and-build-contract Date accessed 2 March 2016.
- Juan, Y., 2009. A Hybrid Approach using Data Envelopment Analysis and Case-Based Reasoning for Housing Refurbishment Contractors Selection and Performance Improvement. Expert Syst. Appl. 36, 5702-5710.
- Killip, G., 2013. Products, Practices and Processes: Exploring the Innovation Potential for Low-Carbon Housing Refurbishment among Small and Medium-Sized Enterprises (SMEs) in the UK Construction Industry. *Energ Policy*. 62, 522-530.
- Liu, S., Tao, R. and Tam, C.M., 2013. Optimizing Cost and CO2 Emission for Construction Projects using Particle Swarm Optimization. *Habitat Int.* 37, 155-162.
- NAEI, 2016. Emissions Factors Database. National Atmospheric Emissions Inventory (NAEI). http://naei.defra.gov.uk/data/ef-all Date accessed 2 March 2016.
- Nicholson, L. and Wasoff, F., 1989. Students' Experience of Private Rented Housing in Edinburgh, Student Accommodation Service, University of Edinburgh, Edinburgh, UK.
- Pombo, O., Rivela, B. and Neila, J. 2016. The challenge of sustainable building renovation: assessment of current criteria and future outlook, *Journal of Cleaner Production*, 123, 88-100.
- Rawlinson, S. and Wilkes, M., 2014. Cost Model Office Refurbishment, Building.

 http://www.building.co.uk/data/cost-model-office-refurbishment/3116045.article Date accessed 12 January 2016.
- RICS, 2013. SKA Rating, Royal Institute of Chartered Surveyors (RICS), London, UK.
- Rugg, J., Rhodes, D. and Jones, A., 2013. Studying a Niche Market: UK Students and the Private Rented Sector. *Housing Stud.* 17(2), 289-303.
- Savills, 2014. Spotlight. World Student Housing, Savills World Research, London, UK.

- Suzuki, M. and Oka, T., 1998. Estimation of Life Cycle Energy Consumption and CO2 Emission of Office Buildings in Japan. *Energ Buildings*. 28(1), 33-41.
- Tang, P., Cass, D. and Mukherjee, A., 2013. Investigating the Effect of Construction Management Strategies on Project Greenhouse Gas Emissions using Interactive Simulation. *Journal of Cleaner Production*. 54, 78-88.
- TSB, 2014. Built Environment, Technology Strategy Board (TSB). https://www.innovateuk.org/contact-us/-/asset_publisher/b61wJfKPbeu8/content/built-environment#action Date accessed 3 May 2016.
- UK GBC, 2016. Climate Change Adaption, UK Green Building Council (UK GBC).

 http://www.ukgbc.org/resources/key-topics/energy-climate-change/climate-change-adaptation Date accessed 28 June 2016.
- UNEP, 2016. Common Carbon Metric: Draft for Pilot Testing. United Nations Environment Programmes' Sustainable Building and Climate Iniative. http://www.unep.org/sbci/pdfs/Common-Carbon-Metric-for-Pilot Testing 220410.pdf Date accessed 15 July 2016.
- WBCSD & WRI, 2003. The GHG Protocol for Project Accounting. Greenhouse Gas Protocol (GHG), World Business Council for Sustainable Development (WBCSD) and World Resource Institute (WRI), Geneva, Switzerland.