National Aeronautics and Space Administration

Bruce K. Tiller

Ares First Stage Deputy Manager


September 16, 2009

Ares First Stage Element Status



Ares I First Stage Overview








Ares I First Stage








Ares First Stage Upgrades







The Avionics System



New State-of-the-art Electronics

- 3-channel single fault avionics system
- Six Line Replaceable Units (LRUs)
 - BCPDU Booster Controller and Power Distribution
 - DARU Data Acquisition and Recording Unit
 - ISC Ignition Separation Controller
 - RCU Recovery Control Unit
 - HPUC Hydraulic Power Unit Controller
 - ACU Actuator Control Unit
- All use the same chassis
- The connector cover plates will each be unique
- The LRUs all meet the 45-pound human factor requirement
- Subassemblies are removable and testable



Built Up Data Acquisition System (DAS) Module Used within all Units


Built Up Initiator Firing Circuit (IFC) Module PWB - ISC/RCU

ISC/RCU Interface Module (IRIM) – ISC/RCU

Built Up Excitation Output Module (EOM) PWB - DARU

Avionics Box Mock-up LRU 1st Generation Engineering Boards

First Stage Thrust Oscillation





- June Program Review was completed with decision to baseline and implement Dual Plane (DP) Isolation
- **Technical Solutions exist for multiple options**
- Designs are in testing

Four basic ways to attack problem:

- Reduce forcing function
- Detune system response away from forcing function frequency
- Actively create an opposing forcing function

Baseline Design

Passively absorb forcing function

Mitigation Options







First Stage Testing Accomplishments






Parachute Drop Testing Yuma Proving Ground, AZ



DM-1 Igniter Test Promontory, UT



Ares I-X Forward Skirt Extension Separation Test Promontory, UT



Thrust Oscillation Component Testing



DM-1 Test Conducted on Sept 10, 2009









Ares I-X First Stage Accomplishments





Ares I-X Motor En Route to KSC Corinne, UT



Ares I-X Forward Assembly Transfer to VAB Kennedy Space Center, FL



Ares I-X Kennedy Space Center, FL





Ares I first stage design is robust and progressing rapidly

- Avionics
- Major structures
- Motor
- Deceleration system

Major test program milestones achieved:

- Recovery system testing
 - 7 of 14 parachute drop tests completed to date (Drogue, Main, Cluster)
- Avionics systems have begun testing
- First of 4 development motors (DM-1) has been fired
 - Preliminary data looks good and well within expectations
 - DM-2 manufacture underway
- Ares I-X hardware delivered and assembled at KSC
 - Completed all Hardware Acceptance Reviews
 - Motor segments were completed and shipped to KSC in March 2009
 - Launch scheduled for no earlier than October 31, 2009







