


# James Webb Space Telescope (JWST) Integrated Science Instruments Module (ISIM) Cryo-Vacuum (CV) Testing at GSFC

Calinda Yew  
28<sup>th</sup> Space Simulation Conference  
NASA Goddard Space Flight Center  
(GSFC)



# Topics

- JWST Mission Overview
- ISIM CV Test Campaign at GSFC
- Test Configuration
- CV1 Test Summary
- CV1 Chamber Performance
- Improvements in Path Forward to CV2 & CV3
- Summary



# JWST Mission Overview

## Mission Objective

- Study the origin and evolution of galaxies, stars & planetary systems: *Optimized for infrared observations (0.6 – 28  $\mu\text{m}$ )*

## Organization

- Mission Lead: Goddard Space Flight Center
- International collaboration with ESA & CSA
- Prime Contractor: Northrop Grumman Space Technology
- Instruments:



– Near Infrared Camera (NIRCam) – Univ. of AZ





– Near Infrared Spectrograph (NIRSpec) – ESA



– Mid-Infrared Instrument (MIRI) – JPL/ESA



– Fine Guidance Sensor (FGS) – CSA





## Description

- Deployable telescope w/ 6.5m dia segmented adjustable primary mirror
- Cryogenic temperature telescope and instruments for infrared performance
- Launch Oct 2018 on ESA-supplied Ariane 5 ECA rocket to Sun-Earth L2
- 5-year science mission + 2 years of data analysis



# ISIM CV Test Campaign at GSFC





# ISIM CV Overall Test Configuration



**Chamber specifications**  
 Volume: 27' dia x 40' high  
 Pumping speed

- 7 cryopumps:  $2.1 \times 10^5$  l/s
- Turbomolecular pump: 6,000 l/s

Payload support: 40,000 lbs

*Nitrogen shroud*

*Helium shroud*

*ISIM hardware & support frames*


*JWST OTE Simulator (OSIM)*

*Vibration isolators*

*Upper and Lower Supports Assembly*



# Nitrogen Volume Test Configuration



## N<sub>2</sub> Volume Support Hardware Components

GSFC Equipment Support Hardware Assembly (GESHA): triangular Al structure to alleviate motion between two aligned systems

- Upper GESHA held at around 90K (-183°C)
- Lower GESHA: held at ambient temperatures to alleviate CTE induced strains

Vibration Isolators System (VIS): pneumatic system isolates test articles from chamber induced jitter sources

- Chamber vibration measured amplitudes of 1 milli-G in all axes at 20 Hz – VIS provides minimum attenuation of 40 dB to these levels
- VIS vertical natural frequency is 1.0-1.3 Hz
- VIS horizontal natural frequency is 0.4-0.6 Hz






# Helium Volume Test Configuration



*SIF & STMS  
Frame*

*HR Shroud  
(HR)*

*IEC Shroud  
(IEC LN<sub>2</sub> Panel)*



*SIF = SES Integration Frame  
STMS = Surrogate Thermal Management System  
IEC = Instruments Electronics Module*



*HR = Harness Radiator  
DSR = Deep Space Radiator*

## He Shroud Specifications

- Dimensions 26' dia x 15' tall
- Provide 1000 W cooling capacity
- Cooling between 80K (-193°C) and 20K (-253°C)
- Five independently controlled shroud zones
- The other five helium zones are allocated to various parts of ISIM structure



## ISIM CV1 Test Summary



- Pump-down: 08/29/2013 ~21:00
- Warm-up: 10/29/2013
- Open chamber: 11/11/13
- Total days under vacuum = 73 days
- Total consumables
  - LN<sub>2</sub> = 520K gallons
  - Helium = 20 bottles






# Shrouds Temperature Performance

At steady state: Helium shroud achieved  $24\text{K} \pm 1\text{K}$

LN2 shroud maintained  $182\text{K} \pm 3\text{K}$  (switched LN2 to GN2 Day 11: 9/10/13)



## Chamber Vacuum Performance


- High vacuum was achieved using:
  - (qty 6) 65000 liter/sec cryopumps
  - (qty 1) 5000 liter/sec turbopump
- 1 (of 6) cryopumps left in reserve at all times

Pressure (Torr)	Time since start
$5.0 \times 10^{-5}$	29 hrs (1.2 days)
$1.0 \times 10^{-5}$	35 hrs (1.5 days)
$5.0 \times 10^{-6}$	46 hrs (1.9 days)
$1.0 \times 10^{-6}$	108 hrs (4.5 days)
$5.0 \times 10^{-7}$	128 hrs (5.3 days)



# Chamber Vacuum Performance


Chamber pressure from pump-down to back-fill





# Chamber Vacuum Performance

With cool-down, warm-up, & He skid shut-down pressure spikes omitted, normally  $3 \times 10^{-7}$  Torr



## Improvements for CV2 & CV3

- Helium skid reliability needed to be improved in order to reduce risk to flight hardware and to schedule
- Detection of helium leaks needed to be more stringent in order to verify MIRI head loads



## Helium Skid Reliability: Summary of Helium Skid Shutdowns

Total of six (6) helium skid shutdowns:

- Cause #1: low turbine bearing gas temperature alarm
- Cause #2: compressor oil level/temp alarm

#	Date	Cause	Action (back online)	Pressure Spike	Duration*	He Temp (Temp rise)	Duration**
1	09/10/13	#1	Re-start skid (<1 hr)	$4.1 \times 10^{-6}$ Torr	4.0 hrs	52K (+16K)	11.2 hrs
2	10/05/13	#1	Re-start skid (<1 hr)	$2.8 \times 10^{-4}$ Torr	5.3 hrs	42K (+15K)	8.5 hrs
3	10/15/13	#2	Re-start skid (<0.5 hr)	$1.1 \times 10^{-4}$ Torr	1.1 hrs	33K (+9K)	14.0 hrs
4	10/19/13	#2	5-sec interlock to delay shutdown command	$9.3 \times 10^{-5}$ Torr	1.1 hrs	32K (+8K)	6.5 hrs
5	10/22/13	#2	Override compressor load/unload status	$9.2 \times 10^{-5}$ Torr	6.1 hrs	37K (+13K)	N/A
6	11/05/13	#2	Re-start skid (~1 hr)	$6.8 \times 10^{-6}$ Torr	2.1 hrs	N/A (warm-up)	N/A (warm-up)

\*Duration for pressure to return to  $5 \times 10^{-7}$  Torr

\*\*Duration for helium shroud average temperature to return to temp before shut-down





Replace Dunham Busch Compressor  
6 to 10 week delivery  
Successfully installed & checked out May 2014

Old




New




## Helium Leak Detection Improvement

- MIRI requirement: 6.2 K (-266.8°C) at the instrument
  - 2-stage cooler system
  - Accurate heat map required during environmental testing
- Issues encountered during CV1
  - Measured heat loads to cooler from MIRI higher than expected
  - Presumed cause is higher levels of helium in chamber
- Actions
  - Add RGA in STMS volume a
  - Implement more stringent leak checking requirements




# JWST ISIM CV1 RGA Data

The chamber RGA detected helium levels of  $5.0 \times 10^{-7}$  Torr






# JWST ISIM CV2 RGA Data Preview



Helium levels consistently detectable to levels of  $1.0 \times 10^{-9}$  Torr (as opposed to  $5.0 \times 10^{-7}$  in CV1)




Helium levels in ISIM volume slightly higher than in the N<sub>2</sub> chamber volume: consistently  $<1.0 \times 10^{-8}$  Torr

The MIRI predicted thermal loads matched the measured within the prediction and measurement uncertainties



## JWST ISIM RGA Data Reliability

- The need for a calibrated RGA is being investigated for CV3 testing as the total RGA pressure does not match the chamber ion gauge pressure readings: chamber RGA was  $\sim 2.5 \times 10^{-7}$  Torr higher
- Currently, qualitative statements can only be made using the RGA data



## Summary

- Successful CV1 test
  - Dry run of test procedures and processes
  - Achieved thermal requirements
  - Identified facility performance improvements necessary
- Two notable facility improvements
  - New helium skid compressor
  - Additional helium shroud RGA
- Future investigation into improving confidence in RGA readings






Questions?



# Back-Up Slides




## Helium Skid Shutdown Cause #1: Low & high oil temperature interlocks (false readings)






# Helium Skid Shutdown Cause #2: Low turbine bearing return temperatures






# Helium Skid Issues #3: Unable to achieve 20K on refrigerator due to compressor loading mechanism malfunction



# Helium Skid Issues #4: In-house air pressure fluctuations House air pressure drops cause helium skid to warm up



## Power Supply Operation

- **All heater racks functioned as required for entire test duration**
  - 9 heater racks
  - 14 LS-336s
- **Only issue: heater circuit 8-2**
  - Control sensors failed
  - Placed in local mode during the test
  - Resolution: Fix broken wire




## Power outages: Generators & UPS

- # of power outages: 1
- Operated seamlessly. B10 generator & Helium skid UPS
- Short commercial power outage experienced on 09/21/2013 (approx. 21:43).
  - Several heater racks needed to be manually reset, but no significant impacts to test hardware.
  - He skid operation not impacted.
  - After coming back online, CQCM heaters came on full power and CQCMs achieved >350K.






# MIRI Air Leak



Helium Skid Issues #5: LN<sub>2</sub> purifier needed to be cleaned  
Warm up heater begins to leak when cold  
Causes differential pressure to increase



# Updated Predict

## Steady State Predict Versus Measured

Thermal Load	Thermal Model Predict *	ISIM CV2 Measured (7/15/14 12:00PM UTC)	ISIM CV2 Measured (7/21/14 8:46AM UTC)	ISIM CV2 Measured (7/28/14 1:02PM UTC)	ISIM CV2 Measured (7/29/14 5:30PM UTC) **
MIRI Thermal Shield	9.5 mW ± 2 mW	8.1 mW ± 7.5 mW	7.2 mW ± 7.5 mW	6.14 mW ± 7.5 mW	5.26 mW ± 7.5 mW
MIRI OM	17.6 mW ± 6 mW	25.9 mW ± 2.8 mW	30.6 mW ± 2.8 mW	23.12 mW ± 2.8 mW	19.27 mW ± 2.8 mW
Boundary Conditions	Assumed Thermal Model (7/15/14 at 12:00PM UTC)	ISIM CV2 Measured	ISIM CV2 Measured	ISIM CV2 Measured	ISIM CV2 Measured
ISIM Conductive Temp at HSA feet (ISIM HKT-14)	35.91 K	35.91 K			34.74 K
ISIM Conductive Temp at MIRI feet (ISIM HKT-35/36/37)	32.79 K	32.79 K	Delta between 7/15 & 7/21 = 4.7 mW accounting for detector dissipation		Delta between 7/28 & 7/29 = 3.85 mW accounting for MIRI CQCM dissipation
ISIM Radiative Temp (STMS T <sup>4</sup> * Area Weighted Avg)	Used actual measured STMS panel temps and includes other actual instrument temperatures	34.65 K			
MIRI Shield Temp (Avg of Rails)	29.53 K	29.53 K			30.5 K
MIRI OM Temp	6.31 K	6.31 K		6.2 K	6.27 K
MIRI Detectors	OFF	OFF	ON	OFF	OFF
MIRI CQCM	OFF	ON	ON	ON	OFF

\* See presentation note field for details on changes in predicted loads.

\*\* At equilibrium on MIRI OM load however this is not the officially declared steady state data point.

