General Disclaimer

One or more of the Following Statements may affect this Document

- This document has been reproduced from the best copy furnished by the organizational source. It is being released in the interest of making available as much information as possible.
- This document may contain data, which exceeds the sheet parameters. It was furnished in this condition by the organizational source and is the best copy available.
- This document may contain tone-on-tone or color graphs, charts and/or pictures, which have been reproduced in black and white.
- This document is paginated as submitted by the original source.
- Portions of this document are not fully legible due to the historical nature of some
 of the material. However, it is the best reproduction available from the original
 submission.

Produced by the NASA Center for Aerospace Information (CASI)

DOE/NASA CONTRACTOR REPORT

DOE/NASA CR-150590

DESIGN REVIEW PACKAGE FOR THE ON-SITE MONITOR FOR SOLAR HEATING AND COOLING SYSTEMS

Prepared by


IBM Federal Systems Division 150 Sparkman Drive Huntsville, Alabama 35805

Under Contract NASS-32036 with

National Aeronautics and Space Administration George C. Marshall Space Flight Center, Alabama Co812

For the U. S. Department of Energy





(NASA-CR-150590) DESIGN REVIEW PACKAGE FOR THE ON-SITE MONITOR FOR SCIAR HEATING AND COOLING SYSTEMS (IBM Federal Systems Div.) 10 p HC AD2/MF A01 CSCL 10A

N78-20611

Unclas 11845

G3/44

U.S. Department of Energy



| | | | L REPORT STANDARD TITLE PAGE |
|--|--|---------------------------------------|---|
| 1. REPORT NO. DOE/NASA CR-150590 | 2, GOVERNMENT AC | | 3. RECIPIENT'S CATALOG NO. |
| 4, TITLE AND SUBTITLE | | | 5. REPORT DATE January 1977 |
| Design Review Package for the | On-Site Monitor | ' for Solar Heating | |
| and Cooling Systems | | | 6. PERFORMING ORGANIZATION CUDE |
| 7. AUTHOR(S) | | | B. PERFORMING ORGANIZATION REPORT # |
| 9. PERFORMING ORGANIZATION NAME AND AD | ORESS | : | 10. WORK UNIT, NO. |
| IBM Federal Systems Division | | | |
| 150 Sparkman Drive | | | 11. CONTRACT OR GRANT NO. NAS8-32036 |
| Huntsville, Alabama 35805 | | • | 13, TYPE OF REPORT & PERIOD COVERED |
| 12. SPONSORING AGENCY NAME AND ADDRESS | | | |
| National Aeronauties and Space | Administration | | Contractor Report |
| Washington, D. C. 20546 | | | |
| • | | | IA, JEUNSORING AGENCY CODE |
| 15. SUPPLEMENTARY NOTES | | | |
| | | management of Mi | . Cecil W. Messer, George |
| C. Marshall Space Flight Center | r, Alabama. | | |
| 16. ABSTRACT | | | |
| | | | • |
| This design review packa | ge consists of t | he Performance Sp | ecification and Verification |
| Matrix for the On-Site Monitor | (OSM). The O | SM is a portable de | evice which, when connected |
| to the Site Data Acquisition subs | system,allows r | endout of data on s | olar heating and cooling |
| operational test sites. | • | | |
| | | | |
| | | 1977. The MSFC 1 | review and critique of these |
| documents are not included in the | ris package. | | • |
| | | | |
| | | | |
| | | | · · · · · · · · · · · · · · · · · · · |
| | | | |
| | | | |
| | | | |
| | en e | | |
| | | | |
| | | | |
| 17. KEY WORDS | | 18. DISTRIBUTION STAT | EMENT |
| 17, 1164 1101160 | | Unclassified-U | |
| | | | 1 |
| | | Williams | Smeller 7 |
| | | WILLIAM A. BK | |
| | en e | Mgr, Solar Heati | ng and Cooling Project Office |
| 19. SECURITY CLASSIF, (of this report) | 20. SECURITY CLAS | SIF, (of this page) | 21. NO. OF PAGES 22. PRICE |
| | , | · · · · · · · · · · · · · · · · · · · | ··· · |

INTRODUCTION

This package reflects the design review material submitted by IBM on their effort to develop, design and build On-Site Monitors under NASA/MSFC Contract NAS8-32036.

The On-Site Monitor is a portable device which can be easily connected to a Site Data Acquisition Subsystem to allow readouts of clock and sensor data in voltage or engineering units at instrumented solar heating and cooling sites.

| | | | | EVISIONS | | |
|----|-----|--------------|------------|-------------|---------|----------|
| LJ | CHK | ENGRG NOTICE | ↓TR | DESCRIPTION | DATE | APPROVED |
| | | | | ORIGINAL | 1/18/77 | |

INTERNATIONAL BUSINESS MACHINES CORP.
FEDERAL SYSTEMS DIVISION
HUNTSVILLE, ALA. 35807 CONTR NO. PREPARATION TITLE ON-SITE MONITOR DSCN CHK DESIGN AND PERFORMANCE SPECIFICATION DWG CHK SIZE DSGN APPROVAL CODE IDENT NO. DWG NO. 7934047 SHEET SCALE WT 1 of 7

12:70

1. INTRODUCTION

1.1 This specification establishes the design and performance requirements for the On-Site Monitor (OSM). The OSM shall be designed to interface with the Site Cata Acquisition Subsystem (SDAS) to allow local readout of sensor data in engineering units stored in the SDAS at instrumented solar heating and cooling sites.

2. APPLICABLE DOCUMENTS

2.1 The following document forms a part of this specification to the extent specified herein. In case of conflict between this document and this specification, this specification shall govern.

SPECIFICATIONS

International Business Machines Corporation

7932905

Site Data Acquisition Subsystem Performance Specification

3. REQUIREMENTS

- 3.1 <u>General</u>. The OSM shall be designed to allow manual selection and display of up to three simultaneous SDAS sensor outputs. Operation of the SDAS shall be in accordance with IBM Document 7932905.
- 3.1.1 OSM/SDAS Isolation. The OSM shall be designed such that an OSM failure shall not degrade the operation of an OSM as defined in Ital Document 7932905.
- 3.1.2 Operation. The OSM shall be designed such that the OSM operator may select the parameter to be displayed from a predefined, site-personalized table which defines the SDAS channel, type of measurement, and range (scale factor) in engineering units. Upon manual selection of these parameters, the OSM shall obtain raw sensor data in digital format from the SDAS and perform the required calculations to display this data digitally in engineering units.

- 3.2 <u>Data Scan.</u> The OSM shall present an interrupt to the SDAS as a request for data. The software in the SDAS is structured such that this request for a special OSM data scan may not be honored when the SDAS is in its normal data scan mode or is in the communications mode with the Central Data Processing System (CDPS). Therefore, operator requests for the OSM to display data may be delayed until the SDAS software accepts the OSM interrupt request during the OSM operating modes described in paragraph 3.3.
- 3.3 OSM Modes and Scan Switch. The OSM shall have two operating modes that are manually selectable by a scan select switch on the OSM display panel. These modes are Manual and Auto. Operation of the scan switch shall be as follows:

Auto Mode. - When the OSM scan switch is placed in the stationary auto position, the OSM shall present the request for data interrupt to the SDAS approximately every two seconds to obtain a complete data set and update the selected data displays at that rate.

Off/Manual. - The OSM scan switch shall also have stationary off/momentary-on positions. When the scan switch is momentarily placed in the manual position, the OSM shall present a request for data interrupt once each time this switch is depressed. A complete SDAS sensor data scan shall be requested and retained by the OSM memory for continuous display of the selected parameters. Upon release, the scan switch shall return to the off position and the displayed parameters shall reflect the data obtained at the time of momentary closure. New parameters for display shall be selectable from the data set obtained by this action without re-selecting the manual mode.

3.4 <u>Displays</u>. - The OSM display panel shall have three 5-1/2 digit Light Emitting Diode displays for presentation of SDAS sensor outputs. Associated with each display shall be four ten-position lever wheel switches. Two of the switches shall be used to select the channel to be displayed. One switch shall select the measurement type and one shall select the measurement range (scale factor).

If a channel is selected which is designated a space at a particular site, the displayed value shall be the value of the corresponding channel digital data words that are stored in the SDAS, normally zero. If the channel selected exceeds the number of installed channels in the SDAS or if there is no combination of the measurement

OWB

type and scale factor stored in the OSM memory, the selected display shall present -1.999.

- 3.5 Power Switch. The OSM shall have a two-position on/off power switch.
- 3.6 Memory. The OSM shall contain the 2K byte of Programmable Read Only Memory (PROM) minimum and 1K byte minimum of Random Access Hemory (RAM) to perform the functions defined in this specification. The PROM shall be contained in a pluggable subassembly to facilitate bench replacement of the stored measurement and scale factor table and the operational program.
- 3.7 <u>Microprocessor</u>. The OSM shall be controlled by a microprocessor similar to that provided in the SDAS.

3.8 Interfaces.

3.8.1 <u>Power</u>. - Power to the OSM shall be standard 110-125 V, 60 Hertz, 1 Phase, 2.0 amp service. A standard 3-wire power cord (sales ground, power, and return) shall be required. The power cable shall be capable of being stored in the OSM case.

The OSM shall contain a primary power supply with outputs of ± 5 Vdc and ± 12 Vdc...

3.8.2 OSM/SDAS Interface Cable. - The OSM/SDAS interface shall be via 10-ft. maximum cable terminating in a 37-pin pluggable connector. The OSM/SDAS connector shall be designed to interface with the J106 connector on the SDAS. Pin functions shall be as defined in Table 3-1. The OSM/SDAS interface cable shall be capable of being stored in the OSM case.

3.9 Packaging. -

3.9.1 Design Environment. - The OSM shall be designed to operate in an indoor environment suitable for operation by electronic tradesmen.

Table 3-1. OSM/SDAS Pin Functions

| PIN NO. | SIGNAL NAME | COMMENT |
|---------|------------------------|---------------------------------------|
| 1 | OSM TO SDAS DBI BIT 0 | Currently not used |
| 2 | 1 | |
|) · 3 | · 2 | |
| . 4 | 3 | |
| 5 | 4 | |
| 6 | . 5 | |
| 7 | 6 | |
| 8 | 7 | <u> </u> |
| 9 | -CARD SELECT 2 | |
| 10 | -INTERRUPT POLL | , , , , , , , , , , , , , , , , , , , |
| 11. | -OSM INTERRUPT REQUEST | • |
| 12 | -OSM SELECT ACK. | |
| 13 | -AI STROBE | , |
| 14 | FUNCTION BIT 0 | |
| •15 | 1 | |
| 16 | 2 | Currently not used |
| 17 | 3 | |
| 18 | SUBADDRESS BIT 0 | |
| 19 | 1 | |
| 20 | 2 | |
| 21 | ·~ 3 | |
| 22 | SDAS TO OSM DBO BIT O | |
| 23 | 1 . | |
| 24 | 2 | |
| 25 | 3 | |
| 26 | 4 | |
| 27 | 5 | |
| 28 | 6 | |
| 29 | 7 | |

Table 3-1. OSM/SDAS Pin Functions (Continued)

| PIN'NO. | SIGNAL NAME | COMMENT |
|---------|----------------|--------------------|
| - 30 | -system reset | Currently not used |
| 31 | -CLOCK | Currently not used |
| 32 | -osn connected | |
| 33 | UNUSED | |
| 34 | UNUSED | |
| 35 | UNUSED | |
| 36 | UNUSED | |
| 37 | UNUSED | |

12:102

- 3.9.2 <u>Case</u>. The OSM shall be contained in a portable case whose dimensions shall be approximately $17" \times 17" \times 7"$. The case shall have a carrying handle and a tilt stand.
- 3.9.3 <u>Weight</u>. The weight of the OSM, including cables, shall not exceed 40 pounds.
 - 4. DESIGN AND CONSTRUCTION
- 4.1 <u>Workmanship</u>. Workmanship in fabrication and assembly of the OSM shall be consistent with good commercial practices.
 - 4.2 Materials and Components. The OSM shall use commercial grade components.
 - 4.3 Certification. The OSM shall be UL-certified.

IBM SPECIFICATION 7934047-05M VERIFICATION CROSS MATRIX

VERIFICATION METHOD

S = SIMILARITY A = ANAI VSIS

| = INSPECTION | = TEST

| * | • | | VERIFIC | VERIFICATION PHASE | 띩 |
|-------|--------|---------------------------|---------------------------------------|--------------------|----------------|
| | PERFOR | PERFORMANCE REQUIREMENT | DEVELOPMENT TEST | TEST | ACCEPTANCE TES |
| | 3.0 | REQUIREMENTS | · - | | |
| | 3.1 | GENERAL | ¥ | | |
| | 3.1.1 | OSM/SDAS ISOLATION | 4 | | • |
| • | 3.1.2 | OPERATION ; | \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ | | |
| | 3.2 | DATA SCAN | · | • | |
| | 3.3 | OSM MODES AND SCAN SWITCH | * | | |
| ٠ | 3.4 | DISPLAYS | - | | J |
| : | 3.5 | POWER SWITCH | | | |
| | 3.6 | MEMORY | V | • | |
| ٠ | 3.7 | MICROPROCESSOR | | | • |
| | 3.8 | INTERFACES | } | | |
| | 3.8.1 | POWER | | | } |
| 4 | 3.8.2 | OSM/SDAS INTERFACE CABLE | , | | , |
| | 3.9 | PACKAGING | - | | |
| | 3.9.1 | DESIGN ENVIRONMENT | — | | |
| | 3.9.2 | CASE | . A,1 | | |
| | 3.9.3 | WEIGHT | - | | |
| . · . | 4.0 | DESIGN AND CONSTRUCTION | V | | |
| | 4.1 | WORKMANSHIP | | | Pi-SP4 |
| • | 4.2 | MATERIALS AND COMPONENTS | A | | |
| | 4.3 | UL CERTIFICATION | A, I, T | | HEI |
| | | | | | |